

BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK:- Repair & Maintenance of existing nonfunctional
Toilets & Electt: Works of Differents Primary Schools of
District Shikarpur. (1) GBPS Habib Sanghro.2.GBPS Dakhan 3. GBPS Arain
4. GBPS Mirzapur-I 5. GBPS Sehwan Sukapul 6. GGPS Sanjrani Muhalla 7. GBPS
Lakhi Gate 8. GBPS Khanchand Abad 9.GBPS Railway Coloney 10. GBPS Urdu
Sadar 11. GBPS Wariyal Jatt@ Alam Khan Lashari 12. GBPS Qila Kafila 13. GBPS
Jagan 14. GBPS Chak 15. GBPS Rustam Sindhi-I 16. GBPS Rustam Sindhi-II 17.
GBPS Wazir Abad 18. GGPS Chak 19. GGPS Lakhi 20. GBPS Khanpur Urdu 21.
GBPS Khanpur Sindhi 22. GBPS Rahim Abad

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART-A SCHEDULE ITEM					
1	116	Wiring for light or fan point with (3/029) PVC insulated wire in 20 mm(3/4") Chennal pati on surface as required (S.I.NO. 129 .P.NO.15)	910.00	P.Point	105,560
2	22	Wiring for plug with (3/0.29(PVC insulated wire in 20mm (3/4") Chennal pati on surface as required (S.I.NO. 130 .P.NO.15)	742.00	P.Point	16,324
3	116	Providing and Fixing One Way S.P.5 amps switch flush type (S.I.NO.219.P.NO.33)	54.00	P.No:	6,264
4	22	Providing and Fixing Two Pin S.P.5 amps Plug & Socket (S.I.NO.225.P.NO.33)	83.00	P.No:	1,826
5	22	Providing and Fixing Three Pin 10/15 amps Plug & Socket Flush type (S.I.NO.226.P.NO.33)	151.00	P.No:	3,322
6	61	Providing and Fixing Brass Button holder (S.I.NO.232.P.NO.33)	70.00	P.No:	4,270
7	660	Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-Core coper conductor 300 to 500 volt 2.5 mm (S.I.NO.60.P.NO.8)	118.00	P.Mtr:	77,880
				Total -A	215,446

PART-B NON SCHEDULE ITEMS 2004					
1	55	Providing and Fixing wall brakate light fancy type superior quality i/c necessary connection and fixing on wall or ceiling ect complete (S.I.NO.5.P.NO.33)	497.00	P.No:	27,335
2	61	Providing and Fixing energy sawer superior quality i/c fixing on existing holder etc complete (S.I.NO.6.P.NO.33)	497.00	P.No:	30,317
3	22	Providing & fixing S.W board to accommodate mains or submains complete	105.88	P.Sft	2,329
				Total -B	59,981

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR

Amount Total (CSR)

Part "A" % Above / Below _____

Total Amount _____

Part "B" % Above / Below _____

Total Amount _____

Total "A+B" _____

CONTRACTOR

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR