


REPAIR OF 300 RFT PRE-STRESSED BRIDGE OVER DRAIN NALA THARIRI JADO SHAHEED
REPLACING ELASTOMERIC BEARING PADS INCLUDING LIFTING OF GIRDERS OF CHISELING /
LOSING OF CONCRETE

REHABILITATION OF EXISTING BRIDGE WORKS

ENGINEER'S ESTIMATE

SUMMARY

| BILL NO. | DESCRIPTION | AMOUNT (RS.) |
|------------|--|-----------------|
| 4A | SUBSTRUCTURE | 9,346,250 |
| 4B | SUPERSTRUCTURE | 491,480 |
| | Engineers inspection and skilled labour including boarding and lodging etc | 1,000,000 |
| TOTAL BILL | | 10,837,730 |



EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION
DADU

REPAIR OF 300 RFT PRE-STRESSED BRIDGE OVER DRAIN NALA THARIRI JADO SHAHEED
REPLACING ELASTOMERIC BEARING PADS INCLUDING LIFTING OF GIRDERS OF CHISELING /

LOSING OF CONCRETE
REHABILITATION OF EXISTING BRIDGE WORKS
ENGINEER'S ESTIMATE

SUBSTRUCTURE


| Sr. No. | Pay Item No. | Item Description | Unit | Quantity | Rate (Rs.) | Amount (Rs.) |
|--|--------------|--|------|----------|------------|---------------------|
| 4A-401 | 406e | Elastomeric bearing pads as shown in the drawings | C.Cm | 381,150 | 3.00 | 1,143,450.00 |
| 4A-402 | SP-2 | Repalce the Bearing pads including lifting of girders removal of existing bearing pads placement of girders complete in all respects as per specification and as directed by the Engineer. | P.S | | | 8,000,000.00 |
| 4A-402 | 401a | Concrete Class A2 for Repair of concrete | CM | 13.00 | 15,600.00 | 202,800.00 |
| Total of Bill 4A Carried to Summary | | | | | | 9,346,250.00 |


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION
DADU

REPAIR OF 300 RFT PRE-STRESSED BRIDGE OVER DRAIN NALA THARIRI JADO SHAHEED
REPLACING ELASTOMERIC BEARING PADS INCLUDING LIFTING OF GIRDERS OF CHISELING /
LOSING OF CONCRETE
REHABILITATION OF EXISTING BRIDGE WORKS
ENGINEER'S ESTIMATE

SUPERSTRUCTURE

| Sr. No. | Pay Item No. | Item Description | Unit | Quantity | Rate (Rs.) | Amount (Rs.) |
|--|--------------|---|------|----------|------------|-------------------|
| 4B-401 | SP-3 | Wire Mesh use in concrete repairing works | KG | 2352.00 | 170.00 | 399,840.00 |
| 4B-402 | SP-4 | Plaster work | SM | 79.00 | 850.00 | 67,150.00 |
| 4B-403 | SP-5 | Chiping / chiseling of loose concrete and after removal of loose concrete steel claeaning due to rusting.Rusting material claning with wire brush and other chemical material.Cutting and chiesling with small tools. | SM | 79.00 | 310.00 | 24,490.00 |
| Total of Bill 4B Carried to Summary | | | | | | 491,480.00 |


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION
DADU