

OFFICE OF THE  
EXECUTIVE ENGINEER PROVINCIAL BUILDINGS DIVISION SUKKUR PH: 071-9310103

Fax # 071-9310101.

Email:- XonProvBuildingsSukkur@gmail.com

No. TC/G-55/ 530 of 2017 Sukkur dated: 27-04-2017

The Sealed Tender's are invited from interested bidders/contractors/firms and companies as well as suppliers on standard bidding documents forms for the procurement of the following works under SPPRA Rules 2010 (Amended 2013-14).

S. NO.	NAME OF WORK	ESTIMATED COST IN MILLION	EARNEST MONEY.	BIDDING DOCUMENTS FEE.	COMPLETION PERIOD
1	2	3	4	5	6
2	Construction of Courts (02 Nos) Building (1 ADJ & 1 JM) @ Ghotki ( Construction of Main Building, Ground Floor, External Development, Plinth Protection, O.H.Tank, Septic Tank, External Drainage & External V/S & S/F).	40.000	2.000	3000	24 Month
3	Construction office of Assistant Commissioner/ Mukhtiarkar Office @ Salehpat.	35.000	1.750	3000	24 Month
4	Construction of Residences of Assistant Commissioner and Mukhtiarkar @ Salehpat.	7.256	0.363	3000	24 Month
5	Construction of Director of Agriculture Extension Sukkur (Construction of Ground Floor, First Floor, 2nd: Floor, & 3rd: Floor).	41.700	2.085	3000	24 Month
6	Construction of Car parking/ Conference Hall/ Office in Deperssion Portion at District Court Sukkur (Basement, Ground Floor ).	45.500	2.275	3000	24 Month

1st: date of Issue and Opening.

First Date.

1st: Date of Issue Tenders will be issued after publication/ SPPRA Website.	
The tender will be received back (1:00 PM) & the Tender will be opened on same date (2:00 PM).	19-05-2017.

2nd: Date of Issue and Opening.

2nd: Date.

Date of Issue	22-05-2017.
The tender will be received back (1:00 PM) & opened on same date (2:00 PM)	5-06-2017.

Terms & conditions of the tenders

- Registration with Pakistan Engineering Council in the relevant field of specialization of work & to the extent of tender amount each work. Pakistan Engineering Council (PEC Certificate 2017) is not required for works below 4.00 (M).
- Bio-data of Engineers and Technical staff working with the firm.
- Documentary evidence of works executed / works in progress and certificate of satisfactory completion of works by the employers.
- List of work in progress, indicating cost of each work and copy of letter of award of work.
- List of machinery and equipment available with documentary evidence of its ownership certificate of Bank showing credit worthiness along with Bank statement.
- Registration with Income Tax Department (NTN Certificate) and copy of C.N.I.C.
- All the contractors/ firms should be registered with Sindh Revenue Board in terms of Rule 46-1(ii) of SPPRA rule (Amended 2013).
- Undertaking on stamp paper that the firm/contractor is not involved in any kind of litigation, department rift, abandoned or un-necessary delay in completion of any work in the government as well as in private organizations.
- Conditional or incomplete tenders will not be entertained.

SPPRA INWARD DIARY  
NO. 3007  
DATED: 02-05-17

x) The bids shall be evaluated on single envelope method of SPPRA rules 2010.

xi) The approved bids will be subject to stamp duty levied by the government.

xii) In case of Holiday and unforeseen circumstances on opening date the bids shall be submitted and opened on the next working day.

xiii) In case the undersigned or any member of the committee happens to be out of the Headquarter the bids shall be submitted and opened as per the given schedule on the next working day.

xiv) The bidders should submit prescribed amount of earnest money as shown against each work in shape of Call Deposit prepared from the scheduled bank in favour of the undersigned.

xv) The Procurement Agency shall not Accept in Bank instrument/ Pay order therein no any Contractor/ Firms reflects.

xvi) Affidavit to the effect that the firm / contractor have not been black listed previously by any executing agency.

xvii) Affidavit to the effect that all documents / particulars / information furnished are true and correct.

xviii) In case of firm, list of partners / Partnership Deed, giving full particulars of directors/ proprietors or others connected along with power of attorney. In case of being sole proprietors, such undertaking on affidavit be furnished.


xix) The undersigned and other competent authority reserve the right to reject any one or all the Bids as per provision of SPPRA Rules, 2010.

/

EXECUTIVE ENGINEER  
PROVINCIAL BUILDINGS DIVISION  
SUKKUR


Copy forwarded with compliments to:-

- 1/- The P.S to Minister Works & Services Department Government of Sindh Karachi.
- 2/- The Secretary, Information Technology Government of Sindh, Secretariat No.6 @ Karachi along with copies of NIT's for favour of information and placing them on the Web site of Sindh Government Karachi.
- 3/- The Director (A&F) SPPRS/3-15 Government of Sindh Public Procurement Regulatory Authority Planning and Development Department Barrack No:08 Sindh Secretariat Court Road Karachi, alongwith soft & hard copy of N.I.T. for favour of information and placing the same on the Web site.
- 4/- The Director Information Public Relation Department (Advertisement) Block-96 Sindh Secretariat Karachi, for publication in News Paper Specially in leading newspaper (English, Sindhi & Urdu)
- 5/- The Chief Engineer, (Buildings) Works & Services Department Sukkur, for favour of kind information.
- 6/- The Superintending Engineer, Provincial Buildings Circle Sukkur, for favour of kind information.
- 7/- The Executive Engineer, Provincial Buildings Division Larkana/ Shaheed Benazir Abad (Nawabshah), for information and publicity.
- 8/- The Assistant Engineer, Provincial Buildings Sub-Division Sukkur/Ghotki, Shikarpur, Khairpur and Electrical Sub-Division Sukkur, for information and publicity.
- 9/- The Divisional Accounts Officer/ Drawing Branch & Head Clerk.
- 10/- Copy to Notice Board.

  
EXECUTIVE ENGINEER  
PROVINCIAL BUILDINGS DIVISION  
SUKKUR

ANNUAL PROCUREMENT PLAN (FINANCIAL YEAR 2016-17) OF M&R WORKS  
PROVINCIAL BUILDINGS DIVISION SUKKUR.

Sl. No.	Quantities where Applicable	Estimated Unit Cost - Applicable	Contract - Estimated Cost	Total - Estimated Cost	Source of Funds (ADP, Non ADP)	Proposed Procurement Method	Timing of Procurement				Remarks
							1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	
2-	Construction of Courts (02 Nos) Building (1 ADJ & 1 JM) @ Ghotki ( Construction of Main Building, Ground Floor, External Development, Plinth Protection, O.H Tank, Septic Tank, External Drainage & External W/S & S/F)	40 000	40 000	40 000	Provincial ADP	Open Commutative Bidding	25%	25%	25%	25%	100%
3-	Construction office of Assistant Commissioner/ Mukhtiarkar Office @ Salehpat	35 000	35 000	35 000	Provincial ADP	Open Commutative Bidding	25%	25%	25%	25%	100%
	Construction of Residences of Assistant Commissioner and Mukhtiarkar @ Salehpat	7 256	7 256	7 256	Provincial ADP	Open Commutative Bidding	25%	25%	25%	25%	100%
	Construction of Director of Agriculture Extension Sukkur (Construction of Ground Floor, First Floor, 2nd Floor, & 3rd Floor)	41 700	41 700	41 700	Provincial ADP	Open Commutative Bidding	25%	25%	25%	25%	100%
	Construction of Car parking/ Conference Hall/ Office in Deperssion Portion at District Court Sukkur (Basement, Ground Floor )	45 500	45 500	45 500	Provincial ADP	Open Commutative Bidding	25%	25%	25%	25%	100%

  
 EXECUTIVE ENGINEER  
 PROVINCIAL BUILDINGS DIVISION  
 SUKKUR

IN

**CHIEF ENGINEER (BUILDINGS) GOVERNMENT OF SINDH  
WORKS & SERVICES DEPARTMENT SUKKUR**

NO. CT (B) E. B. 2013-14/201  
Phone No. 9310101.

Dated 5/11/2013

**SUBJECT:- Complaint Redressal Committee.**

**ORDER.**

In pursuance of rule 31 of Sindh Public Procurements Regulatory Authority 2010 the following Committee is hereby constituted for redressal of the grievances (if any) took place in procurement process, pertaining to Provincial Buildings Division Sukkur.

1.	Superintending Engineer Provincial Buildings Circle Sukkur	Chairman.
2.	District Accounts Officer Sukkur.	Member.
3.	Executive Engineer Provincial Buildings Division Sukkur	Member.
4.	Executive Engineer (Education) Works Division Sukkur	Member (Outsider).

The Complaints redressal committee upon receiving a complaint from an aggrieved bidder must be satisfied.

- Prohibit the procurement committee from acting or deciding in a manner, inconsistent with the rules and regulation.
- Annul in whole or in part, any unauthorized act or decision of the procurement committee; and
- Reverse any decision of the procurement committee or substitute its own decision for such a decision.
- The committee shall announce its decision within seven days. The decision shall be intimated to the bidder and the Authority within three working days by procuring agency. In case of failure of the committee to decide the complaint, the Procuring Agency shall not award the contract.

(MUSTAFA ALI MEMON)  
CHIEF ENGINEER  
BUILDINGS SUKKUR.

**Copy forwarded for information and necessary action:-**

- o The Superintending Engineer Provincial Buildings Circle Sukkur.
- o The Deputy Director (ENF-I) Sindh Public Procurement regulatory Authority Government of Sindh, Karachi.
- o The Executive Engineer Provincial Buildings Division Sukkur/Education Works Division Sukkur.
- o The District Accounts Officer Sukkur.

CHIEF ENGINEER  
BUILDINGS SUKKUR.



No. E&A (W&S) 3-9/91-2013  
**GOVERNMENT OF SINDH**  
**WORKS & SERVICES DEPARTMENT**

Karachi dated the 18<sup>th</sup> September, 2015

**NOTIFICATION**

**NO. E&A (W&S)3-9/91-2013:** With the approval of competent authority, Procurement Committees in terms of Rule-7 of Sindh Public Procurement Rules-2010, is hereby constituted for procurement of "Goods / Works" in the office of the Executive Engineer, Provincial Buildings Division, Sukkur, excluding procuring involving foreign exchange with the following composition:-

- |      |   |          |
|------|---|----------|
| i)   | Executive Engineer<br>Provincial Buildings Division<br>Sukkur           | Chairman |
| ii)  | Divisional Accounts Officer<br>Provincial Buildings Division,<br>Sukkur | Member   |
| iii) | Assistant Engineer,<br>Public Health Engineering Sub-Division,<br>Rohri | Member   |

2. The Functions & Responsibilities of the Committee in terms of Rule-7 & 8 of SPPR-2010- shall be as under:

- Preparing of bidding documents.
- Carrying out Technical as well as Financial Evaluation of the bids.
- Preparing Evaluation report as provided in Rule-45
- Making recommendation for the award of contract to the competent authority, and
- Perform any other function ancillary and identical to the above.


**AIJAZ AHMED MEMON**  
**SECRETARY TO GOVT. OF SINDH**

No. E&A(W&S) 3-9/91-2013

Karachi dated the 18<sup>th</sup> September, 2015

A copy is forwarded for information and necessary action to:-

- The Accountant General, Sindh, Karachi.
- The Secretary to Govt. of Sindh Public Health Engineering Karachi
- The Managing Director, SPPRA Karachi
- The Chief Engineer (Buildings) Sukkur
- The Deputy Director, PM&E Cell, W&SD
- The Chairman / Members of the Committee
- Notification file.

  
**SECTION OFFICER (GENERAL)**  
**FOR SECRETARY TO GOVT. OF SINDH**



**BILL OF QUANTITIES/ SCHEDULE "B"**

Description & Rate of items based on Schedule/ Market (offered Rates).

**CONSTRUCTION OF COURTS (02 NOS) BUILDING (1 ADJ & 1 JM) @ GHOTKI.  
(CONSTRUCTION OF MAIN BUILDING GROUND FLOOR, EXTERNAL DEVELOPMENT, PLINTH PROTECTION, O.H.TANK, SEPTIC TANK, EXTERNAL DRAINAGE, & EXTERNAL W/S & S/F).**

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(i)" FOUNDATION &amp; PLINTH BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Excavation in foundation of Building Bridges and other structures including dag belling dressing, refilling around structure with excavated earth Watering and ramming lead upto 5 ft. In ordinary soil. (S.I.No.18 (b) P-05).	45089	3176/25	%OCFT	143214/-
2/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:4:8). (S.I.No:4(b) P-14).	8825	9416/28	%CFT	830987/-
3/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	456.811	5001/70	P.CWT	2284832/-
4/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	18164	337/00	P.CFT	6121268/-
5/-	Coursed Ruble masonry including hammer dressing in cement sand mortar 1:6. (S.I.No:2 (iv) P-26).	6662	25321/00	%CFT	1686885/-
6/-	Filling watering ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5'feet. (S.I.No:21 P-5). Same Quantity As per Item No.1.	28800	1512/50	%OCFT	43553/-
7/-	Supplying and filling sand under floor plugging into walls. (S.I.No:29 P-26).	44200	1141/25	%CFT	504433/-
8/-	Extra for earth 6 Miles.	44200	195/36	%CFT	8634/-
9/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio (1:6:12). )S.I.No:4(d) P-15).	TOTAL:- 3271	8122/95	%CFT	265702/-
10/-	Cement concrete plain including placing compacting finishing and curing complete i/c screening and washing of stone aggregate Ratio (1:3:6). (S.I.No:5(h) P-16).	TOTAL:- 2467	12595/00	%CFT	310719/-
11/-	Erection and Removal of Centering for R.C.C. or plain C.C. work of Partal wood.(S.I.No:19(b+ii) P-18)	TOTAL:- 906	3127/41	%SFT	28334/-
12/-	Cement pointing on stone work (Raised) in cement sand mortar Ratio (1:6). (S.I.No:20(c+ii) P- 530).	1934	1758/08	%SFT	34001/-
<b>PART "A" FOUNDATION BUILDINGS SCH: ITEMS TOTAL</b>					<b>RS: 1,23,40,277/-</b>

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(ii)" GROUND FLOOR BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	788.864	CWT	5001/70	P.CWT 3945661/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	13085	CFT	337/00	P.CFT 4409645/-
3/-	Pacca brick work in Ground floor in cement sand mortar 1.6. (S.I.no:5(f) P-20).	12559	CFT	12674/36	%CFT 1591773/-
4/-	First class deodar wood wrought joinery in doors and windows fixed to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters) 1-3/4" thick (S.I.No:7(b)P-58).	2651	SFT	1273/76	P.SFT 3376738/-
5/-	Cement plaster (1:6) upto 20' height 1/2" thick. (S.I.No:13 (b) P-52).	45492	SFT	2206/60	%SFT 1003826/-
6/-	Cement plaster (1:4) upto 20' height 3/8" thick. (S.I.No:11 (a) P-52).	45492	SFT	2197/52	%SFT 999696/-
7/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	3623	SFT	14429/25	%CFT 522772/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	9801	SFT	567/48	P.SFT 5561871/-
9/-	Providing and laying 3/8" thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado striking and facing removal/ striking of existing plaster surface etc over 1-1/2" thick base of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	12811	SFT	186/04	P.SFT 2383358/-
10/-	Laying floors of approved colored glazed tiles 1/4" thick laid in white cement sand pigment on a bed of 1/4" thick cement mortar (1:2). (S.I.No:25 P-43).	454	SFT	27747/06	%SFT 125973/-
11/-	Glazed tile dado 1/4" thick laid in pigment over (1:2) cement sand mortar 1/4" thick including finishing. (S.I.No:38 P-45).	1976	SFT	28299/30	%SFT 559194/-
12/-	Supplying and fixing in position Steel grill of 1/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	1359	SFT	180/50	P.SFT 245300/-



S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
13/-	Galvanized wire gauze fixed to chowkats ¼" thick deodar strips. (S.I.No:14(d) P-59).	1359	SFT 190/72	P.SFT	259188/-
14/-	P/F colour create to wall surface of provide durable crust and aesthetic having thickness up to 3/4" specified colour having water fire & termite resistance. (S.I.No:44 P-56).	8706	SFT 6319/50	%SFT	550176/-
15/-	Distemping 3 coats. (S.I.No:24© P-54).	9617	SFT 1079/65	%SFT	103830/-
16/-	Preparing the surface and painting with mat finish paint of approved make to matt finish surface paris and then painting with weather coat of approved make (3 coats) (Old surface) (S.I.No:37(a+b) P-55).	33290	SFT 2499/56	%SFT	832104/-
17/-	French polishing complete (a) on new work. (S.I.No:7(a) P-71).	5304	SFT 3841/75	%SFT	203766/-
18/-	Providing and placing in position clip board ¼" thick for filling space b/w expansion joints of building. (S.I.No:93 P-109).	720	SFT 43/26	P.SFT	31147/-
19/-	Filling expansion joints with bitumen etc.	68	SFT 21/78	P.SFT	1481/-
20/-	P/F Ist: Class shisham wood stair case railing top rail size 3"x4" & pillar 2-1/2" x 2 ½" x 39' i/c 3" embedded in rails 1 feet a past C.C. and pillar size 6"x6"x 5 Nos @ curvier i/c simple casing and fixing in floor with nuts, bolts, in proper way (Based on New Schedule item).	210	SFT 586/-	P.SFT	123060/-
PART "A(ii)" GROUND FLOOR BUILDINGS SCH: ITEMS TOTAL					RS:- 2,77,30,558/-
PART "A(i)" FOUNDATION BUILDING SCHE: ITEM TOTAL					RS:- 1,23,40,277/-
FOUNDATION & G.FLOOR BLDG: SCH: (A+B) TOTAL					RS:- 4,00,70,835/-
<b><u>PART "B" EXTERNAL DEVELOPMENT.</u></b>					
1/-	Cement concrete stone of brick ballast 1 ½" x 2" gauge Ratio (1:6:12). (S.I.No:4(b) P-17).	3037	CFT 8122/95	%CFT	235972/-
2/-	Cement concrete stone of brick ballast 1 ½" x 2" gauge Ratio (1:6:12). (S.I.No:4(b) P-17).	5825	CFT 248/17	P.SFT	1445590/-
3/-	Providing and laying 1" thick cement concrete topping (1:2:4) including surface finishing and dividing into panel 3"thick. (S.I.No:16(d) P-42).	3000	SFT 4411/82	%SFT	132355/-
4/-	Pacca brick work in foundation/Plinth in cement sand mortar Ratio (1:6) (S.I.No:16(d) P-42).	900	SFT 11948/36	%SFT	107535/-
5/-	Cement plaster (1:6) upto 20' ft height ½" thick. (S.I.No:4(i) P-52).	2400	SFT 2206/60	%SFT	52958/-
6/-	Cement plaster (1:4) upto 20' ft height ¾" thick. (S.I.No:11(a) P-52).	2400	SFT 2197/52	%SFT	52740/-
PART "B" EXT: DEVELOPMENT BUILDINGS SCH: TOTAL					RS: 20,27,150/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b><u>PART "C" (PLINTH PROTECTION) BUILDING SCH:ITEM.</u></b>					
1/-	Excavation in foundation of Building Bridges and other structures including dag belling dressing, refilling around structure with excavated earth Watering and ramming lead upto 5 ft. In ordinary soil. (S.I.No.18 (b) P-05).	1500	3176/25	%0CFT	4764/-
2/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:5:10). (S.I.No:4(b) P-15).	500	8694/95	%CFT	43475/-
3/-	Pacca brick work in foundation/Plinth in cement sand mortar Ratio (1:6) (S.I.No:16(d) P-42).	1500	11948/36	%SFT	179225/-
4/-	Filling watering ramming earth under floor with surplus earth excavated from foundation etc complete. (S.I.No:21 P-4).	1000	1512/50	%0CFT	1513/-
5/-	Supplying and fixing sand under floor and plugging into walls. (S.I.No:29 P-26).	3004	1913/21	%SFT	57473/-
6/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:6:12). (S.I.No:4(d) P-15).	1371	8122/95	%SFT	30136/-
7/-	Providing and laying 1" thick cement concrete topping (1:2:4) including surface finishing and dividing into panel 2"thick. (S.I.No:16(c) P-42).	1500	3275/50	%SFT	49133/-
8/-	Cement plaster (1:6) upto 20' ft height 1/2" thick. (S.I.No:4(i) P-52).	1500	2206/60	%SFT	33099/-
9/-	Cement plaster (1:4) upto 20' ft height 3/4" thick. (S.I.No:11(a) P-52).	1500	2197/52	%SFT	32963/-
<b>PART "C" PLINTH PROTECTION BUILDINGS SCH: TOTAL</b>					<b>RS: 4,31,781/-</b>
<b><u>PART "D" O.H.TANK BUILDINGS SCHEDULE ITEMS.</u></b>					
1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.8 (B) P-17)	27.549	5001/70	P.CWT	137747/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	344	337/00	P.CFT	115928/-
3/-	Pacca brick work in Ground floor in cement sand mortar Ratio (1:6) (S.I.No:5(e) P-21).	176	12674/36	%CFT	22307/-
4/-	Cement plaster (1:6) upto 20' ft height 1/2" thick. (S.I.No:4(i) P-52).	472	2206/60	%SFT	10415/-
5/-	Cement plaster (1:4) upto 20' ft height 3/4" thick. (S.I.No:11(a) P-52).	248	2197/52	%SFT	5450/-

S.NO.	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
6/-	Damp proof course with cement sand ratio (1:2) mixed with dampo ¾" thick. (S.I.No:68(b) P-107).	224	SFT	2401/58	%SFT 5380/-
7/-	Cement concrete plain including placing compacting finishing curing etc complete Ratio (1:2:4).(S.I.No:5(f) P-16).	45	SFT	14429/25	%SFT 6493/-
8/-	P/F ornamental C.C. jalli 2" thick without steel etc complete. (S.I.No.11 P-18).	496	SFT	226/02	P.SFT 112106/-
<b>PART "D" O.H. TANK BUILDINGS SCH: TOTAL</b>					<b>RS: 4,15,826/-</b>
<b><u>PART "E" SEPTIC TANK BUILDINGS SCHEDULE ITEMS.</u></b>					
1/-	Excavation in foundation of Building Bridges and other structures including dag belling dressing, refilling around structure with excavated earth Watering and ramming lead upto 5 ft. In ordinary soil. (S.I.No.18 (b) P-05).	1056	CFT	3176/25	%0CFT 3354/-
2/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:5:10). (S.I.No:4(b) P-15).	198	CFT	8694/95	%CFT 17216/-
3/-	Pacca brick work in foundation/Plinth in cement sand mortar Ratio (1:6) (S.I.No:16(d) P-42).	220	CFT	11948/36	%CFT 26286/-
4/-	Perforated pacca brick walling 4 ½" thick etc complete (S.I.No:15(e) P-24).	95	SFT	3935/75	%SFT 373/-
5/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	4.91	CWT	5001/70	P.CWT 24558/-
6/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	132	CFT	337/00	P.CFT 44484/-
7/-	Cement plaster (1:6) upto 20' ft height ½" thick. (S.I.No:4(i) P-52).	442	SFT	2206/60	%SFT 9753/-
8/-	Cement plaster (1:4) upto 20' ft height ¾" thick. (S.I.No:11(a) P-52).	442	SFT	2197/52	%SFT 9713/-
9/-	Cement concrete plain including placing compacting finishing curing etc complete Ratio (1:2:4). (S.I.No:5(f) P-167).	54	SFT	14429/25	%SFT 7792/-
<b>PART "E" SEPTIC TANK BUILDINGS SCH: TOTAL</b>					<b>RS: 1,43,529/-</b>

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "F" EXTERNAL DRAINAGE/ WATER SUPPLY P.H.ENGR:SCHEDULE ITEMS.</b>					
1/-	Excavation for pipe line in trenches and pits in soft soil i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within a one chain as directed by Engineer incharge.	2600 CFT	3600/00	%OCFT	9360/-
2/-	Providing R.C.C. pipe with collers class "B" and digging the trench to required depth and fixing in position in cutting fitting jointing with maxphalt composition and cement mortar (1:1) and testing with water pressure to a head 4' feet above top of highest pipe and refilling the excavated stuff. (S.I.No:2(c+d+e) P- 24 ) W/S & S/F Schedule.				
	a)6" dia.	100 RFT	199/25	P.RFT	19925/-
	b)9" dia.	250 RFT	250/60	P.RFT	62650/-
	c)12"dia.	300 RFT	401/97	P.RFT	120591/-
3/-	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete. (S.I.No:24 P-77) P.H.E.Sch:	1733 CFT	2760/00	%OCFT	4783/-
4/-	Construction of man hole or inspection chamber for the required dia of circular sewer and 3'-6" (1067mm) depth with walls of B.B. in cement mortar(1:3) cement plaster 1:3: ½" thick inside of wall s and 1" (25mm) thick over benching manhole and chanel i/c fixing C.I. manhole cover with frame of clear opening (1- ½' x 1- ½'(457x457mm) or 1.75 Cwt (88.9 Kg) embedded in plain C.C.(1:2:4) and fixing 1" (25 mm) dia M/S. steps 6" (15mm) wide projection 4" (102mm) from the face of wall at 12" (305mm) C.C. duly painted etc complete as per specification and drawing No.D.P/1 of public health circle southern zone (S.I.No:1 P-39) P.H.Engr: Schedule ) (S.I.No:1(a) P-46)..	20 Nos.	14748/00	EACH	294960/-
5/-	Boring for tube well in all water bearing soils from depth 100' to 200' below ground level i/c sinking and with drawing of casing pipe (3" dia) P.H. Engr: Schedule(S.I.No:1(a) P-41).	100 RFT	160/00	P.RFT	16000/-
<b>PART "F" EXTERNAL DRAINAGE/ WATER SUPPLY P.H.ENGR:SCHEDULE ITEMS TOTAL</b>					<b>RS: 5,28,269/-</b>

**PART "G(i)" WATER SUPPLY AND & SANITARY FITTING SCH: ITEMS.**

1/-	Providing and fixing squatting type white glazed of flushing cistern with internal fitting and flush pipe with band and making requisite Nos. of holes in wall plinth and floor for pipe connections and making good in cement concrete (1:2:4) A) W.C. pan orf not less than 23" clear opening between flashing rims and 3 gallons flushing tank with 4" dia C.I. trap. (S.I.No:1(A)P-1).	10 Nos.	5088/20	EACH	50882/-
2/-	P/F European type white glazed earthen ware wash down W.C. pan complete with and i/c the cost of white/black plastic seat (Best Quality ) and lid with C.P. brass hinges and buffers. 3 Gallons white glazed earthen low level flushing cistern with siphon fitting 1-1/2" dia white porcelain enameled flush bend ¾" dia and cutting and making requisite number of holes in walls plinth and floor for pipe connection and making good in cement concrete (1:2:4) (Foreign Quality). (S.I.No:5 P-2).	02 Nos.	11477/40	EACH	22955/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.	
3/-	Providing & fixing 24"x18" lavatory basin in white glazed earthenware complete with & i/c the cost of W.I. or C.I. cantilever brackets 6" built into wall painted white in two coats after a primary coat of red lead paint a pair of ½" dia chrome plate pillar traps 1- ½" dia rubber plug and chrome plated brass chain 1- ¼" dia malleable iron or C.P. brass traps malleable iron or brass union and making requisite number of holes in walls plinth and floor for pipe connection and making good in cement concrete (1:2:4) (Standard pattern). Add extra for labour for providing and fixing of earthen ware pedestal white or coloured glazed (Standard pattern) (S.I.No:8 P-3).	06	Nos.	4253/70	EACH	25522/-
4/-	Add extra for labour for providing and fixing earthenware pedestal white or coloured glazed (Standard pattern) (S.I.No:9 P-3).	06	Nos.	938/47	EACH	5631/-
5/-	P/F 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with a C.I. screwed down gritting with or without a vent arm complete with and i/c making requisite number or holes in walls plinth and floor for pipe connections and making good in Cement concrete (1:2;4). (S.I.No:20 P-5).	16	Nos.	2042/13	EACH	32674/-
6/-	P/F in position nylon connection complete with ½" dia brass stop cock with pair of brass nuts and lining jointing to nylon connection.. (S.I.No:23 P-6).	26	Nos.	447/15	EACH	11626/-
7/-	Providing & fixing 24"x18" beveled edge mirror of Belgium glass complete with 1/8" thick hard board and C.P. screws fixed to wooden plate (a) standard pattern.(S.I.No:3(a) P-7).	06	Nos.	1711/60	EACH	10270/-
8/-	Supplying and fixing in position C.P. stop cock (b) ½" dia C.P. stop cock standard pattern. (S.I.No:4(b) P-13).	26	Nos.	843/92	EACH	21942/-
9/-	Supplying and fixing long bib cocks of superior quality with C.P. head ½" dia (S.I.No:1b-b P-19).	10	Nos.	1109/46	EACH	11095/-
10/-	Supplying and fixing Jet whower with rod of superior quality with C.P. head ½" dia (S.I.No:17 P-15).	10	Nos.	1142/24	EACH	11422/-
11/-	Supplying and fixing wash basin mixture of superior quality with C.P. head ½" dia. (S.I.No:14(a) P-19).	06	Nos.	2882/00	EACH	17292/-
12/-	Supplying and fixing bath room accessories set (7 piece) i/c towel rod, brush holder soap tray, shelf of approved quality and design etc complete (S.I.No:22 P-19).	02	Nos.	8122/40	EACH	16245/-
13/-	Providing and fixing C.C. gully trap etc complete.	12	Nos.	1429/67	EACH	17156/-

S.NO.	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
14/-	Providing and fixing steel stainless local make complete with cast iron or wrought iron brackets 6" built in wall 1 1/2" rubber plug chrome brass chain 1 1/2" C.P. brass waste with 1 1/2" plate P.V.C. waste pipe and making requisite number of holes in walls and plinth and floor for pipe connection and making good in cement concrete (1:2;4) © Steel sink stainless sized 33"x18" local make (Standard pattern). (S.I.No:9© P-05).	02 Nos.	5052/30	EACH	10105/-
15/-	Providing and fixing 4" dia C.I. soil and vent pipe i/c cutting and fitting and extra painting to match the colour of the building. (S.I.No:1 P-9). 4" dia.	30 RFT	333/29	P.RFT	9999/-
16/-	Providing G.I. pipes and special etc clamps etc i/c fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc with white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (S.I.No: 1 P-11).				
	a)1/2" dia.	30 RFT	73/21	P.RFT	2196/-
	b)3/4" dia.	50 RFT	95/79	P.RFT	4790/-
	c)1" dia.	100 RFT	128/55	P.RFT	12855/-
	d)1-1/4" dia.	100 RFT	153/19	P.RFT	15319/-
	e)1-1/2" dia.	100 RFT	188/97	P.RFT	18897/-
17/-	Providing and fixing handle valves (China). (S.I.No:5(i+ii+iii+iv+v) P-17).				
	a)1/2" dia.	05 Nos.	200/42	EACH	1002/-
	b)3/4" dia.	10 Nos.	271/92	EACH	2719/-
	c)1" dia.	10 Nos.	365/42	EACH	3654/-
	d)1-1/4" dia.	10 Nos.	475/42	EACH	4754/-
	e)1-1/2" dia.	10 Nos.	640/42	EACH	6404/-
18/-	Supplying and fixing fiber glass tank of approved quality and design and wall thickness and specified i/c cost of nuts, bolts and fixing in plate form of cement concrete (1:3:6) and making connection for in-let and out-let and over flow pipes etc complete.(a) 250 Gallons wall thickness 3.5mm (S.I.No:3(a) P-21).	01 No.	21989/61	EACH	21990/-
19/-	Providing R.C.C. pipe with collar class "B" digging the trenches to required depth & fixing in position including cutting, fitting & jointing with maxphalt composition & cement mortar (1:1) and testing with water pressure to a head of 4' feet above the top of the highest pipe & refilling with excavated staff. (S.I.No:2 P-24). a) 6" dia	103 RFT	199/25	P.RFT	20523/-

PART "G(i)" W/S & S/F SCHEDULE ITEMS TOTAL RS:- 4,02,700/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
-------	---------------	-----------	-------	-------	---------

**PART "H" ELECTRICAL SCHEDULE ITEMS.**

1/-	Providing and fixing pumping set 1 H.P. Electric Motor boxed on Cement Concrete foundation (1:2:4).	01	No.	18500/-	EACH	18500/-
-----	---	----	-----	---------	------	---------

PART "H" ELECTRICAL SCHEDULE ITEMS TOTAL RS:- 18,500/-

PART "G" W/S & S/F SCHEDULE ITEMS TOTAL RS:- 4,02,700/-

**PART "H" ELECTRICAL SCHEDULE ITEMS.**

1/-	Providing and fixing pumping set 1 H.P. Electric Motor boxed on Cement Concrete foundation (1:2:4).	01	No.		EACH	
-----	---	----	-----	--	------	--

PART "H" ELECTRICAL SCHEDULE ITEMS TOTAL RS:-

**GENERAL ABSTRACT.**

1/-	PART "A(i) FOUNDATION AND PLINTH BLDG:SCH: TOTAL	RS:-	1,23,40,277/-
2/-	PART "A(ii) GROUND FLOOR BUILDINGS SCH:ITEM TOTAL	RS:-	2,77,30,558/-
3/-	PART "B" EXTERNAL DEVELOPEMNT BULD: SCH: TOTAL	RS:-	20,27,150/-
4/-	PART "C" PLINTH PROTECTION BLDG: SCHEDULE TOTAL	RS:-	4,31,781/-
5/-	PART "D" OVER HEAD TANK BUILDINGS SCH: TOTAL	RS:-	4,15,826/-
6/-	PART "E" SEPTIC TANK BUILDINGS SCHEDULE TOTAL	RS:-	1,43,529/-
7/-	PART "F" EXT: DRAINAGE/WATER SUPPLY PHE SCH:TOTAL	RS:-	5,28,269/-
8/-	PART "G" EXT:W/S & S/F SCHEDULE ITEM TOTAL	RS:-	4,02,700/-
9/-	PART "G(i)" & "H" NON SCHEDULE ITEM TOTAL	RS:-	
	G.TOTAL	RS:-	

PART "A"	_____ %Above/Below Buildings Schedule Items	Total Rs:-
PART "B"	_____ %Above/Below W/S & S/F Schedule Items	Total Rs:-
PART "C"	_____ %Above/Below P.H.Engr: Schedule Items	Total Rs:-
PART "D"	_____ %Above/Below Non Schedule Items	Total Rs:-

G. Total Rs:-

CONTRACTOR


  
EXECUTIVE ENGINEER  
PROVINCIAL BUILDINGS DIVISION  
SUKKUR

**THIS SECTION SHOULD BE FILLED BY THE EXECUTIVE  
ENGINEER, PROVINCIAL BUILDINGS DIVISION SUKKUR, BEFORE  
ISSUANCE OF THE BIDDING DOCUMENTS**

- |  |   |
|--|---|
| a) Name of Procuring Agency                                    | EXECUTIVE ENGINEER, PROVINCIAL<br>BUILDINGS DIVISION SUKKUR   |
| b) Brief Description of Works                                  | :- 3-. Construction of Office of Assistant<br>Commissioner/ Mukhtiarkar Office<br>Salehpat.                             |
| c) NIT No: & Date  | :- No:TC/G-55/-530 Dated 27-04-2017.  |
| d) Procuring Agency Address                                    | :- EXECUTIVE ENGINEER, PROVINCIAL<br>BUILDINGS DIVISION SUKKUR  |
| e) Estimated Cost  | :- <b>Rs:- 35.000 (M)</b>   |
| f) Amount of Bid Security                                      | :- 5%   |
| g) Period of Bid Validity (Days)                               | :- 60 Days  |
| h) Security Deposit (i/c bid Security)                         | :- 6%   |
| i) Percentage, if any, to be deducted<br>from Bills            | :- 1150%  |
| j) Deadlines for submission of bids<br>along with times        | :- <b><u>Ist: Date On _____ of publication<br/>time 1.00 p.m.</u><br/><u>2nd: Date :- 19-05-2017 time 1.00 p.m.</u></b> |
| k) Venue, Time & Date of Bid<br>Opening                        | :- <b><u>Ist: Date :- 18-05-2017 time 2.00 p.m.</u><br/><u>2nd: Date :- 02-06-2017 time 2.00 p.m.</u></b>               |
| l) Time for completion from written<br>order of commences      | :- <b>Twenty Four ( 24 ) Months</b>   |
| m) Liquidity Damages   | :- 0.05% of amount of Bid/Estimated cost  |
| n) Deposits Receipt No: date &<br>amount with the Name of Bank | :- No: _____ Dated _____<br>For Rs: _____<br>_____<br>_____   |
| o) DRNo: Date & Amount   | :- <b>DRNo: _____ Dated _____</b><br><b>For Rs:- 3000/- (Documentation Fee)</b>   |
| p) Tender Issued to Mr, M/S                                    | :- _____  |

CONTRACTOR

Government Contractor

  
 EXECUTIVE ENGINEER  
 PROVINCIAL BUILDINGS DIVISION  
 SUKKUR



**BILL OF QUANTITIES/ SCHEDULE "B"**

Description & Rate of items based on Schedule/ Market (offered Rates).

**CONSTRUCTION OF ASSISTANT COMMISSIONER/MUKHTIARKAR OFFICE @ SALEH PAT**

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(i)" FOUNDATION &amp; PLINTH BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Excavation in foundation of Building Bridges and other structures including dag belling dressing, refilling around structure with excavated earth Watering and ramming lead upto 5 ft. In ordinary soil. (S.I.No.18 (b) P-05).	<u>35372</u>	3176/25	%OCFT	112350/-
2/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:4:8). (S.I.No:4(b) P-14).	<u>6632</u>	9416/28	%CFT	624488/-
3/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	252.052	5001/70	P.CWT	1262528/-
4/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	<u>5822</u>	337/00	P.CFT	1962014/-
5/-	Coursed Ruble masonry including hammer dressing in cement sand mortar 1:6. (S.I.No:2 (iv) P-26).	4363	25321/00	%CFT	1104755/-
6/-	Pacca brick work in foundation/Plinth in cement sand mortar Ratio (1:6) (S.I.No:16(d) P-42).	187	11948/36	%SFT	22343/-
7/-	Filling watering ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5'feet. (S.I.No:21 P-5).	<u>23581</u>	1512/50	%OCFT	35666/-
8/-	Supplying and fixing sand under floor and plugging into walls. (S.I.No:29 P-26).	<u>20344</u>	1913/21	%SFT	389223/-
9/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:5:10). (S.I.No:4(b) P-15).	<u>1957</u>	8694/95	%CFT	170160/-
10/-	Cement pointing on stone work (Raised) in cement sand mortar Ratio (1:6). (S.I.No:20(c+ii) P- 53),	996	1758/08	%SFT	17510/-
<b>PART "A" FOUNDATION BUILDINGS SCH: ITEMS TOTAL</b>					<b>RS: 56,99,037/-</b>

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(ii)" GROUND FLOOR BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	551.55 CWT	5001/70	P.CWT	2758688/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	7320 CFT	337/00	P.CFT	2466840/-
3/-	Pacca brick work in Ground floor in cement sand mortar 1.6. (S.I.no:5(f) P-20).	4129 CFT	12674/36	%CFT	523324/-
4/-	Providing and fixing G.I. frames/chowkats 7"x2" or 4-1/2" x3" for door using 20 guage G.I. Sheet i/c welded hinges and fixing. (S.I.No:29 P-94).				
	a) Doors.	477 RFT	228/90	P.RFT	109185/-
	b) Window.	875 RFT	240/850	P.RFT	210438/-
5/-	Cement plaster (1:6) upto 20' height 1/2"thick. (S.I.No:13 (b) P-52).	24082 SFT	2206/60	%SFT	531393/-
6/-	Cement plaster (1:4) upto 20' height 3/8"thick. (S.I.No:11 (a) P-52).	6256 SFT	2197/52	%SFT	495914/-
7/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	1019 SFT	14429/25	%CFT	147034/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	5993 SFT	567/48	P.SFT	3400908/-
9/-	Providing and laying 3/8"thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado striking and facing removal/ striking of existing plaster surface etc over 1-1/2"thick base of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	823 SFT	186/04	P.SFT	153111/-
10/-	Providing and laying tiles glazed 6"x6" x1/4" on floor on wall facing in required clour and patern of stile specification. (S.I.No:60 P-46).	1208 SFT	30509/77	%SFT	368558/-
11/-	First class deodar wood wrought joinery in doors and windows fixe to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters)( 1-1/3" thick (S.I.No:7(b)P-58).	1347 SFT	902/93	P.SFT	1216247/-
12/-	Supplying and fixing in position Steel grill of 3/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	440 SFT	180/50	P.SFT	79420/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.	
13/-	Galvanized wire gauze fixed to chowkats ¾" thick deodar strips. (S.I.No:14(d) P-59).	660	SFT	190/72	P.SFT	125875/-
14/-	Providing and fixing into sunkirn screws wooden archiraver. (S.I.No. P- ).	885	SFT	49/97	P.SFT	44223/-
15/-	Supplying and fixing false Ceiling of plaster of paris. (S.I.No: P- ).	900	SFT	25293/42	%SFT	227641/-
16/-	Providing and fixing of Paris Ceiling Border of 8"x12" with specification. (S.I.No: P- ).	210	SFT	104/22	P.SFT	21886/-
17/-	Distemping three coats over one coat of white wash. (S.I.No: P- ).	5829	SFT	1496/28	%SFT	87218/-
18/-	Preparing surface Painting with matt finish. (S.I.No: P- ).	14964	SFT	3444/38	%SFT	515417/-
19/-	Preparing surface Painting with weather coat. (S.I.No: P- ).	6256	SFT	2567/95	%SFT	160651/-
20/-	Preparing surface and painting of doors and windows any type including edges three coats. (S.I.No:5 (c+i+ii+iii) P-97).	2694	SFT	2116/41	%SFT	57016/-
21/-	Painting new surface:- Painting guard bars gates iron bars grating i/c standard. (S.I.No:5(d)(i+ii+iii)	660	SFT	1270/83	%SFT	8387/-

**PART "A(ii)" G. FLOOR BUILDINGS SCH: ITEMS TOTAL**      RS:      1,37,09,374/-

**PART "A(iii)" FIRST FLOOR BUILDINGS SCHEDULE ITEMS.**

1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	551.55	CWT	5001/70	P.CWT	2758688/-
2/-	Add extra labour for lifting of steel. (S.I.No: P- ).	551.55	CFT	151/25	P.CFT	83422/-
3/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	7320	CFT	349/10	P.CFT	2555412/-
4/-	Pacca brick work in First floor in cement sand mortar 1.6. (S.I.no:5( ) P-20).	3117	CFT	13112/99	%CFT	624309/-

S.NO.	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
5/-	Providing and fixing G.I. frames/chowkats 7"x2" or 4-1/2" x3" for door using 20 guage G.I. Sheet i/c welded hinges and fixing. (S.I.No:29 P-94). a)Doors.	499	RFT	228/90	P.RFT 114221/-
	a) Window.	875	RFT	240/850	P.RFT 210438/-
6/-	Cement plaster (1:6) upto 20' height 1/2"thick. (S.I.No:13 (b) P-52).	26657	SFT	2347/57	%SFT 625792/-
7/-	Cement plaster (1:4) upto 20' height 3/8"thick. (S.I.No:11 (a) P-52).	25142	SFT	2338/49	%SFT 587943/-
8/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	1019	SFT	14429/25	%CFT 147034/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	5993	SFT	567/48	P.SFT 3400908/-
9/-	Providing and laying 3/8"thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado strucking and facing removal/ strucking of existing plaster surface etc over 1-1/2"thick bace of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	823	SFT	186/04	P.SFT 15311/-
10/-	Providing and laying tiles glazed 6"x6" x1/4" on floor on wall facing in required clour and patern of stile specification. (S.I.No:60 P-46).	1208	SFT	30509/77	%SFT 368558/-
11/-	First class deodar wood wrought joinery in doors and windows fixe to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters)( 1-1/3" thick (S.I.No:7(b)P-58).	1372	SFT	902/93	P.SFT 1238820/-
12/-	Supplying and fixing in position Steel grill of 3/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	440	SFT	180/50	P.SFT 79420/-
13/-	Galvanized wire gauze fixed to chowkats 3/4" thick deodar strips. (S.I.No:14(d) P-59).	660	SFT	190/72	P.SFT 125875/-
14/-	Providing and fixing into sunkirn screws wooden archiraver. (S.I.No. P- ).	905	SFT	49/97	P.SFT 45223/-
15/-	Supplying and fixing false Ceiling of plaster of paris. (S.I.No: P- ).	900	SFT	25293/42	%SFT 227641/-
16/-	Providing and fixing of Paris Ceiling Border of 8"x12" with specification. (S.I.No: P- ).	210	SFT	104/22	P.SFT 21886/-
17/-	Distemping three coats over one coat of white wash. (S.I.No: P- ).	5829	SFT	1724/37	%SFT 100514/-
18/-	Preparing surface Painting with matt finish three coats. (S.I.No: P- ).	16920	SFT	3673/28	%SFT 621519/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
19/-	Preparing surface Painting with weather three coats. (S.I.No: P- ).	6256	SFT	2796/85	%SFT 174971/-
20/-	Preparing surface and painting of doors and windows any type including edges three coats. (S.I.No:5 (c+i+ii+iii) P-97).	2744	SFT	2116/41	%SFT 58074/-
21/-	Painting new surface:- Painting guard bars gates iron bars grating i/c standard. (S.I.No:5(d)(i+ii+iii)	660	SFT	1270/83	%SFT 8387/-
22/-	Providing and laying 1" thick cement concrete topping (1:2:4) including surface finishing and dividing into panel 2"thick. (S.I.No:16(c) P-42).	7156	SFT	3502/28	%SFT 250630/-
23/-	Two coat of bitumen laid hot using 34 lbs for % Sft over roof and binding with sand at one Cft per % Sft. (S.I.No:13 P-41).	7156	SFT	1887/40	%SFT 135062/-
24/-	Providing and fixing R.C.C. Spouts/Parnala. (S.I.No: P- ).	10	Nos.	261/25	EACH 2613/-

PART "A(iii)" F. FLOOR BUILDINGS SCH: ITEMS TOTAL RS: 1,45,82,671/-

### GENERAL ABSTRACT.

1/-	PART "A(i) FOUNDATION AND PLINTH BLDG: SCH: TOTAL	RS:-	65,57,082/-
2/-	PART "A(ii) GROUND FLOOR BUILDINGS SCH: ITEM TOTAL	RS:-	1,43,93,134/-
3/-	PART "A(iii) FIRST FLOOR BUILDING SCHEDULE TOTAL	RS:-	1,53,62,301/-
	<b>G.TOTAL</b>	RS:-	2,63,12,517/-

PART "A" \_\_\_\_\_ %Above/Below Buildings Schedule Items Total Rs:-

CONTRACTOR


  
 EXECUTIVE ENGINEER  
 PROVINCIAL BUILDINGS DIVISION  
 SUKKUR

**THIS SECTION SHOULD BE FILLED BY THE EXECUTIVE  
ENGINEER, PROVINCIAL BUILDINGS DIVISION SUKKUR, BEFORE  
ISSUANCE OF THE BIDDING DOCUMENTS**

- a) Name of Procuring Agency :- EXECUTIVE ENGINEER, PROVINCIAL BUILDINGS DIVISION SUKKUR
- b) Brief Description of Works :- 4- Construction of Residences of Assistant Commissioner and Mukhtiarkar @ Salehpat.
- c) NIT No: & Date :- No:TC/G-55/-530 Dated 27-04-2017.
- d) Procuring Agency Address :- EXECUTIVE ENGINEER, PROVINCIAL BUILDINGS DIVISION SUKKUR
- e) Estimated Cost :- **Rs:- 7.256 (M)**
- f) Amount of Bid Security :- 5%
- g) Period of Bid Validity (Days) :- 60 Days
- h) Security Deposit (i/c bid Security) :- 6%
- i) Percentage, if any, to be deducted from Bills :- 1150%
- j) Deadlines for submission of bids along with times :- Ist: Date On \_\_\_\_\_ of publication time 1.00 p.m.  
2nd: Date :- 19-05-2017 time 1.00 p.m.
- k) Venue, Time & Date of Bid Opening :- Ist: Date :- ~~19~~-05-2017 time 2.00 p.m.  
2nd: Date :- 05-06-2017 time 2.00 p.m.
- l) Time for completion from written order of commences :- **Twenty Four ( 24 ) Months**
- m) Liquidity Damages :- 0.05% of amount of Bid/Estimated cost
- n) Deposits Receipt No: date & amount with the Name of Bank :- No: \_\_\_\_\_ Dated \_\_\_\_\_  
For Rs: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
- o) DRNo: Date & Amount :- **DRNo: \_\_\_\_\_ Dated \_\_\_\_\_**  
**For Rs:- 3000/- (Documentation Fee)**
- p) Tender Issued to Mr, M/S :- \_\_\_\_\_

CONTRACTOR

Government Contractor

  
EXECUTIVE ENGINEER  
PROVINCIAL BUILDINGS DIVISION  
SUUKUR

**BILL OF QUANTITIES/ SCHEDULE "B"**

Description & Rate of Items based on Schedule/ Market (offered Rates).  
**CONSTRUCTION OF RESIDENCES OF ASSISTANT COMMISSIONER AND MUKHTIARKAR**  
**RESIDENCE @ SALEH PAT**

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(i)" FOUNDATION &amp; PLINTH BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Excavation in foundation of Building Bridges and other structures including dag belling dressing, refilling around structure with excavated earth Watering and ramming lead upto 5 ft. In ordinary soil. (S.I.No.18 (b) P-05).	17686	3176/25	%0CFT	56175/-
2/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:4:8). (S.I.No:4(b) P-14).	3316	9416/28	%CFT	312244/-
3/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	126.03	5001/70	P.CWT	630364/-
4/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	2911	337/00	P.CFT	981007/-
5/-	Coursed Ruble masonry including hammer dressing in cement sand mortar 1:6. (S.I.No:2 (iv) P-26).	2182	25321/00	%CFT	552504/-
6/-	Pacca brick work in foundation/Plinth in cement sand mortar Ratio (1:6) (S.I.No:16(d) P-42).	94	11948/36	%SFT	11231/-
7/-	Filling watering ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5' feet. (S.I.No:21 P-5).	11791	1512/50	%OCFT	17834/-
8/-	Supplying and fixing sand under floor and plugging into walls. (S.I.No:29 P-26).	10172	1913/21	%SFT	194612/-
9/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:5:10). (S.I.No:4(b) P-15).	979	8694/95	%CFT	85124/-
10/-	Cement pointing on stone work (Raised) in cement sand mortar Ratio (1:6). (S.I.No:20(c+ii) P- 53),	498	1758/08	%SFT	8755/-
<b>PART "A" FOUNDATION BUILDINGS SCH: ITEMS TOTAL</b>					<b>RS: 22,49,850/-</b>

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(ii)" GROUND FLOOR BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	275.78	CWT	5001/70	P.CWT 1379369/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	3660	CFT	337/00	P.CFT 1233420/-
3/-	Pacca brick work in Ground floor in cement sand mortar 1.6. (S.I.no:5(f) P-20).	4129	CFT	12674/36	%CFT 261726/-
4/-	Providing and fixing G.I. frames/chowkats 7"x2" or 4-1/2" x3" for door using 20 guage G.I. Sheet i/c welded hinges and fixing. (S.I.No:29 P-94).	239	RFT	228/90	P.RFT 54707/-
	a)Doors.	239	RFT	228/90	P.RFT 54707/-
	b) Window.	438	RFT	240/50	P.RFT 105339/-
5/-	Cement plaster (1:6) upto 20' height 1/2"thick. (S.I.No:13 (b) P-52).	12041	SFT	2206/60	%SFT 265697/-
6/-	Cement plaster (1:4) upto 20' height 3/8"thick. (S.I.No:11 (a) P-52).	3128	SFT	2197/52	%SFT 68738/-
7/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	510	SFT	14429/25	%CFT 73589/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	5993	SFT	567/48	P.SFT 1700738/-
9/-	Providing and laying 3/8"thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado strucking and facing removal/ strucking of existing plaster surface etc over 1-1/2"thick bace of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	412	SFT	186/04	P.SFT 76797/-
10/-	Providing and laying tiles glazed 6"x6" x1/4" on floor on wall facing in required clour and patern of stile specification. (S.I.No:60 P-46).	1208	SFT	30509/77	%SFT 184279/-
11/-	First class deodar wood wrought joinery in doors and windows fixe to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters)( 1-1/3" thick (S.I.No:7(b)P-58).	674	SFT	902/93	P.SFT 608575/-
12/-	Supplying and fixing in position Steel grill of 3/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	220	SFT	180/50	P.SFT 39710/-



S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
13/-	Galvanized wire gauze fixed to chowkats ¾" thick deodar strips. (S.I.No:14(d) P-59).	330	SFT 190/72	P.SFT	62938/-
14/-	Providing and fixing into sunkirn screws wooden archiraver. (S.I.No. P- ).	443	SFT 49/97	P.SFT	22137/-
15/-	Supplying and fixing false Ceiling of plaster of paris. (S.I.No: P- ).	450	SFT 25293/42	%SFT	113820/-
16/-	Providing and fixing of Paris Ceiling Border of 8"x12" with specification. (S.I.No: P- ).	105	SFT 104/22	P.SFT	10943/-
17/-	Distempering three coats over one coat of white wash. (S.I.No: P- ).	2915	SFT 1496/28	%SFT	43617/-
18/-	Preparing surface Painting with matt finish. (S.I.No: P- ).	7482	SFT 3444/38	%SFT	257709/-
19/-	Preparing surface Painting with weather coat. (S.I.No: P- ).	6256	SFT 2567/95	%SFT	160651/-
20/-	Preparing surface and painting of doors and windows any type including edges three coats. (S.I.No:5 (c+i+ii+iii) P-97).	2694	SFT 2116/41	%SFT	57016/-
21/-	Painting new surface:- Painting guard bars gates iron bars grating i/c standard. (S.I.No:5(d)(i+ii+iii)	660	SFT 1270/83	%SFT	8387/-

PART "A(ii)" G. FLOOR BUILDINGS SCH: ITEMS TOTAL RS: 40,54,730


### GENERAL ABSTRACT.

1/-	PART "A(i) FOUNDATION AND PLINTH BLDG: SCH: TOTAL	RS:-	22,49,850/-
2/-	PART "A(ii) GROUND FLOOR BUILDINGS SCH: ITEM TOTAL	RS:-	40,54,730/-
	<b>G.TOTAL</b>	RS:-	63,04,580/-

PART "A" \_\_\_\_\_ %Above/Below Buildings Schedule Items

Total Rs:-

CONTRACTOR


  
EXECUTIVE ENGINEER  
PROVINCIAL BUILDINGS DIVISION  
SUKKUR

**THIS SECTION SHOULD BE FILLED BY THE EXECUTIVE  
ENGINEER, PROVINCIAL BUILDINGS DIVISION SUKKUR, BEFORE  
ISSUANCE OF THE BIDDING DOCUMENTS**

- a) Name of Procuring Agency EXECUTIVE ENGINEER, PROVINCIAL BUILDINGS DIVISION SUKKUR
- b) Brief Description of Works :- 6-. Construction of Director Extension Sukkur (Construction of Ground Floor, First Floor, 2<sup>nd</sup>: Floor and 3<sup>rd</sup>: Floor).
- c) NIT No: & Date :- No:TC/G-55/-530 Dated 27-04-2017.
- d) Procuring Agency Address :- EXECUTIVE ENGINEER, PROVINCIAL BUILDINGS DIVISION SUKKUR
- e) Estimated Cost :- **Rs:- 41.700 (M)**
- f) Amount of Bid Security :- 5%
- g) Period of Bid Validity (Days) :- 60 Days
- h) Security Deposit (i/c bid Security) :- 6%
- i) Percentage, if any, to be deducted from Bills :- 1150%
- j) Deadlines for submission of bids along with times :- Ist: Date On \_\_\_\_\_ of publication time 1.00 p.m.  
2nd: Date :- 19-05-2017 time 1.00 p.m.
- k) Venue, Time & Date of Bid Opening :- Ist: Date :- ~~12~~05-2017 time 2.00 p.m.  
2nd: Date :- ~~05~~06-2017 time 2.00 p.m.
- l) Time for completion from written order of commences :- **Twenty Four ( 24 ) Months**
- m) Liquidity Damages :- 0.05% of amount of Bid/Estimated cost
- n) Deposits Receipt No: date & amount with the Name of Bank :- No: \_\_\_\_\_ Dated \_\_\_\_\_  
For Rs: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
- o) DRNo: Date & Amount :- **DRNo: \_\_\_\_\_ Dated \_\_\_\_\_**  
**For Rs:- 3000/- (Documentation Fee)**
- p) Tender Issued to Mr, M/S :- \_\_\_\_\_

CONTRACTOR

Government Contractor

  
EXECUTIVE ENGINEER  
PROVINCIAL BUILDINGS DIVISION  
SUUKUR

**BILL OF QUANTITIES/ SCHEDULE "B"**

Description &amp; Rate of items based on Schedule/ Market (offered Rates).

**CONSTRUCTION OF DIRECTOR OF AGRICULTURE EXTENSION SUKKUR ( CONSTRUCTION OF GROUND FLOOR, FIRST FLOOR, 2<sup>ND</sup>: FLOOR & 3<sup>RD</sup>: FLOOR).**

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(i)" FOUNDATION &amp; PLINTH BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Excavation in foundation of Building Bridges and other structures including dag belling dressing, refilling around structure with excavated earth Watering and ramming lead upto 5 ft. In ordinary soil. (S.I.No.18 (b) P-05).	45089	3176/25	%0CFT	143214/-
2/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:4:8). (S.I.No:4(b) P-14).	8825	9416/28	%CFT	830987/-
3/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	456.811	5001/70	P.CWT	2284832/-
4/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	18164	337/00	P.CFT	6121268/-
5/-	Coursed Ruble masonry including hammer dressing in cement sand mortar 1:6. (S.I.No:2 (iv) P-26).	6662	25321/00	%CFT	1686885/-
6/-	Filling watering ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5'feet. (S.I.No:21 P-5). Same Quantity As per Item No.1.	28800	1512/50	%OCFT	43553/-
7/-	Supplying and filling sand under floor plugging into walls. (S.I.No:29 P-26).	44200	1141/25	%CFT	504433/-
8/-	Extra for earth 6 Miles.	44200	195/36	%CFT	8634/-
9/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio (1:6:12). )S.I.No:4(d) P-15).	TOTAL:- 3271	8122/95	%CFT	265702/-
10/-	Cement concrete plain including placing compacting finishing and curing complete i/c screening and washing of stone aggregate Ratio (1:3:6). (S.I.No:5(h) P-16).	TOTAL:- 2467	12595/00	%CFT	310719/-
11/-	Erection and Removal of Centering for R.C.C. or plain C.C. work of Partal wood.(S.I.No:19(b+ii) P-18)	TOTAL:- 906	3127/41	%SFT	28334/-
12/-	Cement pointing on stone work (Raised) in cement sand mortar Ratio (1:6). (S.I.No:20(c+ii) P- 530.	1934	1758/08	%SFT	34001/-
<b>PART "A" FOUNDATION BUILDINGS SCH: ITEMS TOTAL</b>					<b>RS: 58,40,312/-</b>

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(ii)" GROUND FLOOR BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	788.864	CWT	5001/70	P.CWT 3945661/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	13085	CFT	337/00	P.CFT 4409645/-
3/-	Pacca brick work in Ground floor in cement sand mortar 1.6. (S.I.no:5(f) P-20).	12559	CFT	12674/36	%CFT 1591773/-
4/-	First class deodar wood wrought joinery in doors and windows fixed to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters) 1-3/4" thick (S.I.No:7(b)P-58).	2651	SFT	1273/76	P.SFT 3376738/-
5/-	Cement plaster (1:6) upto 20' height 1/2"thick. (S.I.No:13 (b) P-52).	45492	SFT	2206/60	%SFT 1003826/-
6/-	Cement plaster (1:4) upto 20' height 3/8"thick. (S.I.No:11 (a) P-52).	45492	SFT	2197/52	%SFT 999696/-
7/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	3623	SFT	14429/25	%CFT 522772/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	9801	SFT	567/48	P.SFT 5561871/-
9/-	Providing and laying 3/8"thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado strucking and facing removal/ strucking of existing plaster surface etc over 1-1/2"thick base of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	12811	SFT	186/04	P.SFT 2383358/-
10/-	Laying floors of approved colored glazed tiles 1/4" thick laid in white cement sand pigment on a bed of 3/4" thick cement mortar (1:2). (S.I.No:25 P-43).	454	SFT	27747/06	%SFT 125973/-
11/-	Glazed tile dado 1/4" thick laid in pigment over (1:2) cement sand mortar 3/4" thick including finishing. (S.I.No:38 P-45).	1976	SFT	28299/30	%SFT 559194/-
12/-	Supplying and fixing in position Steel grill of 3/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	1359	SFT	180/50	P.SFT 245300/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
13/-	Galvanized wire gauze fixed to chowkats ¾" thick deodar strips. (S.I.No:14(d) P-59).	1359	SFT	190/72	P.SFT 259188/-
14/-	P/F colour create to wall surface of provide durable crust and aesthetic having thickness up to ¾" specified colour having water fire & termite resistance. (S.I.No:44 P-56).	8706	SFT	6319/50	%SFT 550176/-
15/-	Distempering 3 coats. (S.I.No:24© P-54).	9617	SFT	1079/65	%SFT 103830/-
16/-	Preparing the surface and painting with mat finish paint of approved make to matt finish surface paris and then painting with weather coat of approved make (3 coats) (Old surface) (S.I.No:37(a+b) P-55).	33290	SFT	2499/56	%SFT 832104/-
17/-	French polishing complete (a) on new work. (S.I.No:7(a) P-71).	5304	SFT	3841/75	%SFT 203766/-
18/-	Providing and placing in position clip board ¾" thick for filling space b/w expansion joints of building. (S.I.No:93 P-109).	720	SFT	43/26	P.SFT 31147/-
19/-	Filling expansion joints with bitumen etc.	68	SFT	21/78	P.SFT 1481/-
20/-	P/F Ist: Class shisham wood stair case railing top rail size 3"x4" & pillar 2-1/2" 2 ½" x39' i/c 3" embedded in rails 1 feet a past C.C. and pillar size 6"x6"x 5 Nos @ curvier i/c simple casing and fixing in floor with nuts, bolts, in proper way (Based on New Schedule item).	210	SFT	586/-	P.SFT 123060/-
<b>PART "A(ii)" GROUND FLOOR BUILDINGS SCH: ITEMS TOTAL</b>					<b>RS:- 85,88,915/-</b>

**PART "A(iii)" FIRST FLOOR BUILDINGS SCHEDULE ITEMS.**

1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	788.864	CWT	5001/70	P.CWT 3945661/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	13085	CFT	337/00	P.CFT 4409645/-
3/-	Pacca brick work in Ground floor in cement sand mortar 1.6. (S.I.no:5(f) P-20).	12559	CFT	12674/36	%CFT 1591773/-
4/-	First class deodar wood wrought joinery in doors and windows fixed to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters) 1-¾" thick (S.I.No:7(b)P-58).	2651	SFT	1273/76	P.SFT 3376738/-
5/-	Cement plaster (1:6) upto 20' height ½"thick. (S.I.No:13 (b) P-52).	45492	SFT	2206/60	%SFT 1003826/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
6/-	Cement plaster (1:4) upto 20' height 3/8" thick. (S.I.No:11 (a) P-52).	45492 SFT	2197/52	%SFT	999696/-
7/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	3623 SFT	14429/25	%CFT	522772/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	9801 SFT	567/48	P.SFT	5561871/-
9/-	Providing and laying 3/8" thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado striking and facing removal/ striking of existing plaster surface etc over 1-1/2" thick base of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	12811 SFT	186/04	P.SFT	2383358/-
10/-	Laying floors of approved colored glazed tiles 1/4" thick laid in white cement sand pigment on a bed of 3/4" thick cement mortar (1:2). (S.I.No:25 P-43).	454 SFT	27747/06	%SFT	125973/-
11/-	Glazed tile dado 1/4" thick laid in pigment over (1:2) cement sand mortar 3/4" thick including finishing. (S.I.No:38 P-45).	1976 SFT	28299/30	%SFT	559194/-
12/-	Supplying and fixing in position Steel grill of 3/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	1359 SFT	180/50	P.SFT	245300/-
13/-	Galvanized wire gauze fixed to chowkats 3/4" thick deodar strips. (S.I.No:14(d) P-59).	1359 SFT	190/72	P.SFT	259188/-
14/-	P/F colour create to wall surface of provide durable crust and aesthetic having thickness up to 3/4" specified colour having water fire & termite resistance. (S.I.No:44 P-56).	8706 SFT	6319/50	%SFT	550176/-
15/-	Distempering 3 coats. (S.I.No:24© P-54).	9617 SFT	1079/65	%SFT	103830/-
16/-	Preparing the surface and painting with matt finish paint of approved make to matt finish surface paris and then painting with weather coat of approved make (3 coats) (Old surface) (S.I.No:37(a+b) P-55).	33290 SFT	2499/56	%SFT	832104/-
17/-	French polishing complete (a) on new work. (S.I.No:7(a) P-71).	5304 SFT	3841/75	%SFT	203766/-
18/-	Providing and placing in position clip board 3/4" thick for filling space b/w expansion joints of building. (S.I.No:93 P-109).	720 SFT	43/26	P.SFT	31147/-
19/-	Filling expansion joints with bitumen etc.	68 SFT	21/78	P.SFT	1481/-
20/-	P/F Ist: Class shisham wood stair case railing top rail size 3"x4" & pillar 2-1/2" 2 1/2" x39' i/c 3" embedded in rails 1 feet a past C.C. and pillar size 6"x6"x 5 Nos @ curvier i/c simple casing and fixing in floor with nuts, bolts, in proper way (Based on New Schedule item).	210 SFT	586/-	P.SFT	123060/-
<b>PART "A(iii)" FIRST FLOOR BUILDINGS SCH: ITEMS TOTAL</b>				<b>RS:-</b>	<b>85,95,613/-</b>

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b><u>PART "A(iv)" 2<sup>ND</sup>: FLOOR BUILDINGS SCHEDULE ITEMS.</u></b>					
1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	788.864	CWT	5001/70	P.CWT 3945661/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	13085	CFT	337/00	P.CFT 4409645/-
3/-	Pacca brick work in Ground floor in cement sand mortar 1.6. (S.I.no:5(f) P-20).	12559	CFT	12674/36	%CFT 1591773/-
4/-	First class deodar wood wrought joinery in doors and windows fixed to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters) 1-3/4" thick (S.I.No:7(b)P-58).	2651	SFT	1273/76	P.SFT 3376738/-
5/-	Cement plaster (1:6) upto 20' height 1/2"thick. (S.I.No:13 (b) P-52).	45492	SFT	2206/60	%SFT 1003826/-
6/-	Cement plaster (1:4) upto 20' height 3/8"thick. (S.I.No:11 (a) P-52).	45492	SFT	2197/52	%SFT 999696/-
7/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	3623	SFT	14429/25	%CFT 522772/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	9801	SFT	567/48	P.SFT 5561871/-
9/-	Providing and laying 3/8"thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado striking and facing removal/ striking of existing plaster surface etc over 1-1/2"thick base of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	12811	SFT	186/04	P.SFT 2383358/-
10/-	Laying floors of approved colored glazed tiles 1/4" thick laid in white cement sand pigment on a bed of 3/4" thick cement mortar (1:2). (S.I.No:25 P-43).	454	SFT	27747/06	%SFT 125973/-
11/-	Glazed tile dado 1/4" thick laid in pigment over (1:2) cement sand mortar 3/4" thick including finishing. (S.I.No:38 P-45).	1976	SFT	28299/30	%SFT 559194/-
12/-	Supplying and fixing in position Steel grill of 3/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	1359	SFT	180/50	P.SFT 245300/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
13/-	Galvanized wire gauze fixed to chowkats ¾" thick deodar strips. (S.I.No:14(d) P-59).	1359	SFT 190/72	P.SFT	259188/-
14/-	P/F colour create to wall surface of provide durable crust and aesthetic having thickness up to 3/4" specified colour having water fire & termite resistance. (S.I.No:44 P-56).	8706	SFT 6319/50	%SFT	550176/-
15/-	Distempering 3 coats. (S.I.No:24© P-54).	9617	SFT 1079/65	%SFT	103830/-
16/-	Preparing the surface and painting with mat finish paint of approved make to matt finish surface paris and then painting with weather coat of approved make (3 coats) (Old surface) (S.I.No:37(a+b) P-55).	33290	SFT 2499/56	%SFT	832104/-
17/-	French polishing complete (a) on new work. (S.I.No:7(a) P-71).	5304	SFT 3841/75	%SFT	203766/-
18/-	Providing and placing in position clip board ¾" thick for filling space b/w expansion joints of building. (S.I.No:93 P-109).	720	SFT 43/26	P.SFT	31147/-
19/-	Filling expansion joints with bitumen etc.	68	SFT 21/78	P.SFT	1481/-
20/-	P/F 1st: Class shisham wood stair case railing top rail size 3"x4" & pillar 2-1/2" 2 ½" x39' i/c 3" embedded in rails 1 feet a past C.C. and pillar size 6"x6"x 5 Nos @ curvier i/c simple casing and fixing in floor with nuts, bolts, in proper way (Based on New Schedule item).	210	SFT 586/-	P.SFT	123060/-
<b>PART "A(iv)" 2<sup>ND</sup>: FLOOR BUILDINGS SCH: ITEMS TOTAL</b>				<b>RS:-</b>	<b>85,95,831/-</b>

**PART "A(v)" 3<sup>RD</sup>: FLOOR BUILDINGS SCHEDULE ITEMS.**

1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	788.864	CWT 5001/70	P.CWT	3945661/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	13085	CFT 337/00	P.CFT	4409645/-
3/-	Pacca brick work in Ground floor in cement sand mortar 1.6. (S.I.no:5(f) P-20).	12559	CFT 12674/36	%CFT	1591773/-
4/-	First class deodar wood wrought joinery in doors and windows fixed to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters) 1-3/4" thick (S.I.No:7(b)P-58).	2651	SFT 1273/76	P.SFT	3376738/-
5/-	Cement plaster (1:6) upto 20' height ½" thick. (S.I.No:13 (b) P-52).	45492	SFT 2206/60	%SFT	1003826/-



S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
6/-	Cement plaster (1:4) upto 20' height 3/8" thick. (S.I.No:11 (a) P-52).	45492 SFT	2197/52	%SFT	999696/-
7/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	3623 SFT	14429/25	%CFT	522772/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	9801 SFT	567/48	P.SFT	5561871/-
9/-	Providing and laying 3/8" thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado strucking and facing removal/ strucking of existing plaster surface etc over 1-1/2" thick base of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	12811 SFT	186/04	P.SFT	2383358/-
10/-	Laying floors of approved colored glazed tiles 1/4" thick laid in white cement sand pigment on a bed of 3/4" thick cement mortar (1:2). (S.I.No:25 P-43).	454 SFT	27747/06	%SFT	125973/-
11/-	Glazed tile dado 1/4" thick laid in pigment over (1:2) cement sand mortar 3/4" thick including finishing. (S.I.No:38 P-45).	1976 SFT	28299/30	%SFT	559194/-
12/-	Supplying and fixing in position Steel grill of 3/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	1359 SFT	180/50	P.SFT	245300/-
13/-	Galvanized wire gauze fixed to chowkats 3/4" thick deodar strips. (S.I.No:14(d) P-59).	1359 SFT	190/72	P.SFT	259188/-
14/-	P/F colour create to wall surface of provide durable crust and aesthetic having thickness up to 3/4" specified colour having water fire & termite resistance. (S.I.No:44 P-56).	8706 SFT	6319/50	%SFT	550176/-
15/-	Distempering 3 coats. (S.I.No:24© P-54).	9617 SFT	1079/65	%SFT	103830/-
16/-	Preparing the surface and painting with mat finish paint of approved make to matt finish surface paris and then painting with weather coat of approved make (3 coats) (Old surface) (S.I.No:37(a+b) P-55).	33290 SFT	2499/56	%SFT	832104/-
17/-	French polishing complete (a) on new work. (S.I.No:7(a) P-71).	5304 SFT	3841/75	%SFT	203766/-
18/-	Providing and placing in position clip board 3/4" thick for filling space b/w expansion joints of building. (S.I.No:93 P-109).	720 SFT	43/26	P.SFT	31147/-
19/-	Filling expansion joints with bitumen etc.	68 SFT	21/78	P.SFT	1481/-
20/-	P/F Ist: Class shisham wood stair case railing top rail size 3"x4" & pillar 2-1/2" 2 1/2" x39' i/c 3" embedded in rails 1 feet a past C.C. and pillar size 6"x6"x 5 Nos @ curvier i/c simple casing and fixing in floor with nuts, bolts, in proper way (Based on New Schedule item).	210 SFT	586/-	P.SFT	123060/-
<b>PART "A(v)" 3<sup>RD</sup>: FLOOR BUILDINGS SCH: ITEMS TOTAL</b>				<b>RS:-</b>	<b>90,84,646/-</b>

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
-------	---------------	-----------	-------	-------	---------

## GENERAL ABSTRACT.

1/-	PART "A(i) FOUNDATION AND PLINTH BLDG:SCH: TOTAL	RS:-	58,40,312/-
2/-	PART"A(ii) GROUND FLOOR BUILDINGS SCH:ITEM TOTAL	RS:-	85,88,915/-
2/-	PART"A(iii) FIRST FLOOR BUILDINGS SCH:ITEM TOTAL	RS:-	85,95,613/-
2/-	PART"A(iv) 2 <sup>ND</sup> : FLOOR BUILDINGS SCH:ITEM TOTAL	RS:-	85,95,831/-
2/-	PART"A(v) 3 <sup>RD</sup> : FLOOR BUILDINGS SCH:ITEM TOTAL	RS:-	90,84,646/-
	<b>G.TOTAL</b>	<b>RS:-</b>	<b>4,07,05,099/-</b>

PART "A" \_\_\_\_\_ %Above/Below Buildings Schedule Items **Total Rs:-**


PART "B" \_\_\_\_\_ %Above/Below W/S & S/F Schedule Items **Total Rs:-**

PART "C" \_\_\_\_\_ %Above/Below P.H.Engr: Schedule Items **Total Rs:-**

PART "D" \_\_\_\_\_ %Above/Below Non Schedule Items **Total Rs:-**

G. Total Rs:-

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 PROVINCIAL BUILDINGS DIVISION  
 SUKKUR



**BILL OF QUANTITIES/ SCHEDULE "B"**

Description & Rate of items based on Schedule/ Market (offered Rates).

**CONSTRUCTION OF CAR PARKING/ CONFERENCE HALL/ OFFICE IN DEPRESSION PORTION AT DISTRICT COURT SUKKUR (CONSTRUCTION OF BASEMENT, GROUND FLOOR).**

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART "A(i)" FOUNDATION &amp; PLINTH BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Excavation in foundation of Building Bridges and other structures including dag belling dressing, refilling around structure with excavated earth Watering and ramming lead upto 5 ft. In ordinary soil. (S.I.No.18 (b) P-05).	45089	3176/25	%0CFT	143214/-
		CFT			
2/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio(1:4:8). (S.I.No:4(b) P-14).	8825	9416/28	%CFT	830987/-
		CFT			
3/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	456.811	5001/70	P.CWT	2284832/-
		CWT			
4/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	18164	337/00	P.CFT	6121268/-
		CFT			
5/-	Coursed Ruble masonry including hammer dressing in cement sand mortar 1:6. (S.I.No:2 (iv) P-26).	6662	25321/00	%CFT	1686885/-
		CFT			
6/-	Filling watering ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5'feet. (S.I.No:21 P-5). Same Quantity As per Item No.1.	28800	1512/50	%OCFT	43553/-
		CFT			
7/-	Supplying and filling sand under floor plugging into walls. (S.I.No:29 P-26).	44200	1141/25	%CFT	504433/-
		CFT			
8/-	Extra for earth 6 Miles.	44200	195/36	%CFT	8634/-
		CFT			
9/-	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio (1:6:12). )S.I.No:4(d) P-15).	TOTAL:- 3271	8122/95	%CFT	265702/-
		CFT			
10/-	Cement concrete plain including placing compacting finishing and curing complete i/c screening and washing of stone aggregate Ratio (1:3:6). (S.I.No:5(h) P-16).	TOTAL:- 2467	12595/00	%CFT	310719/-
		CFT			
11/-	Erection and Removal of Centering for R.C.C. or plain C.C. work of Partal wood.(S.I.No:19(b+ii) P-18)	TOTAL:- 906	3127/41	%SFT	28334/-
		SFT			
12/-	Cement pointing on stone work (Raised) in cement sand mortar Ratio (1:6). (S.I.No:20(c+ii) P- 530.	1934	1758/08	%SFT	34001/-
		SFT			
<b>PART "A" FOUNDATION BUILDINGS SCH: ITEMS TOTAL</b>					<b>RS: 1,23,40,277/-</b>

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
<b>PART**A(ii)" GROUND FLOOR BUILDINGS SCHEDULE ITEMS.</b>					
1/-	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (S.I.No.7 (ii) P/20)	788.864	CWT	5001/70	P.CWT 3945661/-
2/-	RCC work including all labour and material except the cost of steel reinforcement and its labour for bending and binding, which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle)a) R.C. work in roof slab, beams columns rafts, lintels and other structural members laid in situ or pre cast laid in position complete in all respect. i) Ratio (1:2:4). (S.I.No:6(a)(i) P-19).	13085	CFT	337/00	P.CFT 4409645/-
3/-	Pacca brick work in Ground floor in cement sand mortar 1.6. (S.I.no:5(f) P-20).	12559	CFT	12674/36	%CFT 1591773/-
4/-	First class deodar wood wrought joinery in doors and windows fixed to position including chowkats, hold fasts, hinges, iron tower bolts cleats deodar paneled or paneled and glazed or fully glazed (Only shutters) 1-3/4" thick (S.I.No:7(b)P-58).	2651	SFT	1273/76	P.SFT 3376738/-
5/-	Cement plaster (1:6) upto 20' height 1/2"thick. (S.I.No:13 (b) P-52).	45492	SFT	2206/60	%SFT 1003826/-
6/-	Cement plaster (1:4) upto 20' height 3/8"thick. (S.I.No:11 (a) P-52).	45492	SFT	2197/52	%SFT 999696/-
7/-	Cement concrete plain i/c placing compacting finishing curring complete (1:2:4). (S.I.No:5 P-15).	3623	SFT	14429/25	%CFT 522772/-
8/-	Laying white marble flooring fine dresses on the surface without winding set in lime mortar (1:2) i/c rubbing and polishing of joints (3/4" thick). (S.I.No:28(a) P-43).	9801	SFT	567/48	P.SFT 5561871/-
9/-	Providing and laying 3/8"thick marble tiles of approved quality and color shade size 8"x4/6"x4" in dado strucking and facing removal/ strucking of existing plaster surface etc over 1-1/2"thick base of cement mortar (1:3) setting mortar base i/c filling the joints and washing the tiles with white cement slurry, curring, finishing cleaning and polishing etc complete. (S.I.No:68(i) P-49).	12811	SFT	186/04	P.SFT 2383358/-
10/-	Laying floors of approved colored glazed tiles 1/4" thick laid in white cement sand pigment on a bed of 3/4" thick cement mortar (1:2). (S.I.No:25 P-43).	454	SFT	27747/06	%SFT 125973/-
11/-	Glazed tile dado 1/4" thick laid in pigment over (1:2) cement sand mortar 3/4" thick including finishing. (S.I.No:38 P-45).	1976	SFT	28299/30	%SFT 559194/-
12/-	Supplying and fixing in position Steel grill of 3/4"x1/4" size flat iron of approved design i/c painting 3 coats. (S.I.No:26 P-94)	1359	SFT	180/50	P.SFT 245300/-

S.NO:	NAME OF ITEM.	QUANTITY.	RATE.	UNIT.	AMOUNT.
13/-	Galvanized wire gauze fixed to chowkats ¼" thick deodar strips. (S.I.No:14(d) P-59).	1359	SFT 190/72	P.SFT	259188/-
14/-	P/F colour create to wall surface of provide durable crust and aesthetic having thickness up to 3/4" specified colour having water fire & termite resistance. (S.I.No:44 P-56).	8706	SFT 6319/50	%SFT	550176/-
15/-	Distempering 3 coats. (S.I.No:24© P-54).	9617	SFT 1079/65	%SFT	103830/-
16/-	Preparing the surface and painting with mat finish paint of approved make to matt finish surface paris and then painting with weather coat of approved make (3 coats) (Old surface) (S.I.No:37(a+b) P-55).	33290	SFT 2499/56	%SFT	832104/-
17/-	French polishing complete (a) on new work. (S.I.No:7(a) P-71).	5304	SFT 3841/75	%SFT	203766/-
18/-	Providing and placing in position clip board ¾" thick for filling space b/w expansion joints of building. (S.I.No:93 P-109).	720	SFT 43/26	P.SFT	31147/-
19/-	Filling expansion joints with bitumen etc.	68	SFT 21/78	P.SFT	1481/-
20/-	P/F Ist: Class shisham wood stair case railing top rail size 3"x4" & pillar 2-1/2" 2 ½" x39" i/c 3" embedded in rails 1 feet a past C.C. and pillar size 6"x6"x 5 Nos @ curvier i/c simple casing and fixing in floor with nuts, bolts, in proper way (Based on New Schedule item).	210	SFT 586/-	P.SFT	123060/-

PART "A(ii)" GROUND FLOOR BUILDINGS SCH: ITEMS TOTAL RS:- 2,77,30,558/-

PART "A(i)" FOUNDATION BUILDING SCHE: ITEM TOTAL RS:- 1,23,40,277/-

FOUNDATION & G.FLOOR BLDG: SCH: (A+B) TOTAL RS:- 4,00,70,835/-

### GENERAL ABSTRACT.


1/-	PART "A(i) FOUNDATION AND PLINTH BLDG: SCH: TOTAL	RS:-	1,23,40,277/-
2/-	PART "A(ii) GROUND FLOOR BUILDINGS SCH: ITEM TOTAL	RS:-	2,77,30,558/-
	<b>G.TOTAL</b>	<b>RS:-</b>	<b>4,00,70,835/-</b>

PART "A" \_\_\_\_\_ %Above/Below Buildings Schedule Items

Total Rs:-

G. Total Rs:-

CONTRACTOR

  
EXECUTIVE ENGINEER  
PROVINCIAL BUILDINGS DIVISION  
SUKKUR