

Name of work: M/R TO D.S FLAT 13 TO 18 GOR I BATH IS LAND KARACHI (ELECTRIC WORK)


Schedule					
S.No.	Description	Qty	Rate	Unit	Amount
1	P/F of flood light 400 watts (SON) having classification with 400 w lamp choke, ignator, & internal wiring complete in all respect at the height upto 40ft with the help hydraulic crane and manual labour as per site requirement and instruction of	2-Nos	17585/-	Each	35170
	TOTAL				35170
	PART B N.S.I				
	Part B NSI				
1	P/F Fancy LED Tube Light 2-40 watt fancy shade i/c chock & starter i/c necessary electric connection etc complete.	20-Nos		□	
2	P/F Ceiling Fan 56" sweep make GFC imported or equalent quality i/c necessary electric connection as req.	10-Nos		"	
3	P/F Wall Bracket Fan" sweep make GFC imported or equalent quality i/c necessary electric connection as req.	5-Nos		"	
4	S/F Fancy Switch socket with board as approved quality by the Engineer Incharge etc complete.	120-Nos		Each	
5	S/F Fancy Fan Dimmer as approved quality etc complete.	20-Nos		□	
6	P/F Universal light Plug 10-amp imported quality i/c necessary electric connection etc complete.	25-Nos		□	
7	P/F Power Plug 15-amps imported quality i/c necessary electric connection etc complete.	25-Nos			
8	P/F Energy Sever 25 watt i/c holder imported quality i/c necessary electric connection etc complete.	45-Nos		Each	
9	P/F Distribution board double shutter size (1-1/2"x1-1/4") to accommodate heavy duty for Circuit Brackers i/c painting enameled paint for other similar job on prepared board on surface.	13.50 Sft		Sft	
10	P/F LED Pannel Light (Energy Saving Effect)(24□x24□)(Model 6500 k) for using false ceiling imported quality i/c making	5-Nos		Each	

	connection as per requirement of site etc complete.			
11	P/F Exhaust Fan Plastic Body equalent quality i/c necessary electric connection as per approved quality etc complete.	15-Nos		
12	P/F Exhaust Fan Metal Body equalent quality i/c necessary electric connection as per approved quality etc complete.	6-Nos		
13	P/F fancy wall bracket light i/c fancy glass lamp holder i/c electric connection as directed by the Engineer Incharge etc complete.	25-Nos		Each
14	P/F fancy Ceiling Light i/c fancy glass lamp holder i/c electric connection as directed by the Engineer Incharge etc complete.	20-Nos		
15	P/F Pilot Lamp(Main Indicator Lamp) Bulb i/c matching Three colours (Red,Blue,&yellow) i/c fixing for DB i/c necessary electric connection as approved quality etc complete.	15-Nos		P.Set
16	P/F Amper Meter 0-600Amp for DB i/c fixing necessary electric connection as approved quality etc complete.	5-Nos		Each
17	P/F Volt Meter 0-500 Amp for DB i/c fixing necessary electric connection as approved quality etc complete.	5-Nos		
	Total B			
	G Total			
	Say Rs			

TERMS & CONDITION

- Any typographical errors in the schedule B are subject to the correct condition with Reference to the schedule of rate General 2012 enforced from 12-07-2012 as approved by the SRC Sindh.
- Arbitration clause stands deleted from the agreement.
- No Premium shall be paid on Non Schedule Items
- 100% well Graded crushed bajri shall be used in items of work without any extra payment.
- No any items of exveceed then the quantity provided in the schedule B without prior of the Executive Engineer.
- All sample of items should be got approved by the Executive Engineer

Contractor


Assistant Engineer
Provincial Electrical sub Division-XII
Karachi

Executive Engineer,
Provincial Buildings Division No. I,
Karachi.