

# OFFICE OF THE EXECUTIVE ENGINEER (B&R) SITE ZONE DMC (WEST) KARACHI

Email Address: Sitezone\_dmc@yahoo.com  
Phone No.021-32550457

NO.XEN/S.Z/DMC/W/261/2017

DATED.03/05/2017

## TENDER NOTICE

(Through Website of SPPRA & SITE Zone DMC (West))

Tender in sealed covers are invited for the following work (s) under SPP Rules 2010 from the firms having adequate experience in the relevant field. The tentative cost of work is under Rs. 1.0 Million.

S. No	Name of Work	E/Cost Rs.	Bids Security 2%	Cost of Tender
1.	Const / Imp of CC Flooring at Agha Khan Flat Kareem Nagar in Sector IV Metrovill in UC-04 SITE Zone DMC (West)	9,98,920/-	20,000/-	1000/-
2.	Const / Imp of Sewerage Line i/c CC Flooring from Rustom Khan at Sector 5 Metrovill in UC-04 SITE Zone DMC (West)	9,49,810/-	20,000/-	1000/-
3.	Const / Imp of CC Flooring from H. No E-107 to E-78 and professor khurram at Sector 2 in UC-04 SITE Zone DMC (West)	9,97,000/-	20,000/-	1000/-
4.	Const of CC Flooring from Haji Jandad House to Metrovill Hospital at Sector IV Metrovill in UC-04 SITE Zone DMC (West)	9,98,000/-	20,000/-	1000/-
5.	Const / Imp of Sewerage Line i/c CC Flooring from Tilawat House and Zaheer House at Sector III in UC-04 Metrovill SITE Zone DMC (West)	9,61,940/-	20,000/-	1000/-
6.	Repair / Maintenance & Engine Overhauling of Sanitation Vehicle No. CH-11402 & CH-21288 in SITE Zone DMC (West)	9,72,000/-	20,000/-	1000/-
7.	Repair / Maintenance of Vehicle No. CH-16643 Hino Lifter SITE Zone DMC (West)	9,75,800/-	20,000/-	1000/-

### Terms & Conditions: -

1. Tender Schedule Shall be as follows.

SCHEDULE	DATE & TIME	VENUE
Receiving of Application & Issuance of Tenders	03/05/2017 to 18/05/2017 During Office Hours	DMC (West) SITE Zone Office D-1 SITE Main Manghopir Road Karachi
Dropping of Tenders	19/05/2017 2:00 P.M	Executive Engineer SITE Zone DMC (West) Office
Opening of Tenders	19/05/2017 2:30 P.M	Executive Engineer SITE Zone DMC (West) Office

2. The tender documents will be issued to contractor on submission of written request on letter head and on payment of non-refundable cost of tender price through pay order from Sindh Bank in favour of SITE Zone DMC (West).
3. The Bid Security as mentioned above in shape of pay order in favour of SITE Zone DMC (West) shall must be enclosed with tender documents without which the tender will be treated as cancelled.
4. In case the date of opening is declared as a public holiday by the Government, the next official working day shall be deemed to be the date for submission and opening of tenders at the same time as mentioned.
5. The total bid amount as well as the rates of items must be filled both in figures and words and in case any correction is made by the contractor himself then each correction must be initialed by the contractor; otherwise the tenders are liable to be summarily rejected.
6. The bidder are required to submit the above information along with their bid.
7. If any fake documents are found then the tender is liable to be rejected / cancelled without any compensation but with penalty as per rules.
8. Canvassing in connection with tenders is strictly prohibited and tenders submitted by the contractors who are reported to be involved in canvassing will be liable for rejection.
9. Bid Security of the unsuccessful bidder shall be released once the contractor has been signed with the successful bidder or the validity period has expired.
10. The Procuring agency may reject all or any bid subject to the relevant provisions of SPPRA Rules 2010.
11. Eligibility
  - i. NTN Certificate
  - ii. Valid Professional Tax
  - iii. S.R.B Certificate
  - iv. Bank Statement
  - v. Relevant Experience
  - vi. Turn Over of at least three years

  
**EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC (WEST)**

**Not to be published**

**Director (CB) SPPRA**

With a request to upload on SPPRA (Authority) website and issue ID Number

**Incharge (I.T), SITE Zone DMC (West)**


With a request to upload on SITE Zone DMC (West) Website

**Copy to: -**

1. Administrator DMC (West)
2. P.S to Managing Director SPPRA
3. Office File

**ANNUAL PROCUREMENT PLAN**  
**(DISTRICT MUNICIPAL CORPORATION WEST)**  
**FINANCIAL YEAR 2016-2017**

S.No:	Name of Scheme	Allocated Funds	Cost of ongoing works (Expenditure already incurred)	Funds earmarked for ongoing works	Cost of New Work (components)	Funds for new works (c-e)	Nature of Procurement	Method of Procurement	Anticipated/ Actual Date of Advertisement	Anticipated/ Actual Date of Start	Anticipated/ Actual Date of completion
A	b	c	d	e	f	g	h	i	j	k	l
1.	Const / Imp of CC Flooring at Agha Khan Flat Kareem Nagar in Sector IV Metrovill in UC-04 SITE Zone DMC (West)	100000000	9,07,91,732	-----	9,98,920/-	9,98,920/-	Works and Services	SPPRA Rule 15(b) & 16	03.05.2017	In due course	In due course
2.	Const / Imp of Sewerage Line i/c CC Flooring from Rustom Khan at Sector 5 Metrovill in UC-04 SITE Zone DMC (West)	100000000	8,98,41,922	-----	9,49,810/-	9,49,810/-	Works and Services	SPPRA Rule 15(b) & 16	03.05.2017	In due course	In due course
3.	Const / Imp of CC Flooring from H. No E-107 to E-78 and proffesar khurram at Sector 2 in UC-04 SITE Zone DMC (West)	100000000	8,88,44,922	-----	9,97,000/-	9,97,000/-	Works and Services	SPPRA Rule 15(b) & 16	03.05.2017	In due course	In due course
4.	Const of CC Flooring from Haji Jandad House to Metrovill Hospital at Sector IV Metrovill in UC-04 SITE Zone DMC (West)	100000000	8,78,46,922	-----	9,98,000/-	9,98,000/-	Works and Services	SPPRA Rule 15(b) & 16	03.05.2017	In due course	In due course
5.	Const / Imp of Sewerage Line i/c CC Flooring from Tilawat House and Zaheer House at Sector III in UC-04 Metrovill SITE Zone DMC (West)	100000000	8,68,84,982	-----	9,61,940/-	9,61,940/-	Works and Services	SPPRA Rule 15(b) & 16	03.05.2017	In due course	In due course



6.	Repair / Maintenance & Engine Overhauling of Sanitation Vehicle No. CH-11402 & CH-21288 in SITE Zone DMC (West)	100000000	8,59,12,982	-----	9,72,000/-	9,72,000/-	Works and Services	SPPRA Rule 15(b) & 16	03.05.2017	In due course	In due course
7.	Repair / Maintenance of Vehicle No. CH-16643 Hino Lifter SITE Zone DMC (West)	100000000	8,49,37,182	-----	9,75,800/-	9,75,800/-	Works and Services	SPPRA Rule 15(b) & 16	03.05.2017	In due course	In due course



# OFFICE OF THE EXECUTIVE ENGINEER (B&R)

## SITE ZONE DMC WEST KARACHI

**SUBJECT: - CONST / IMP OF CC FLOORING AT AGHA KHAN FLAT KAREEM**

**NAGAR IN SECTOR IV METROVILL IN UC-04 SITE ZONE DMC (WEST)**

**E/Cost: 9,98,920/- E/Money 20,000/- T/Limit 45 Days Penalty 500/- PD.**

S.No	Description of Work	Quantity	Rate Per%
1.	Dismantling of CC Work 1:2:4	6525/Cft	3327.50%Cft
2.	Cartage of 100 Cft 5 tons all materials like stone aggregate spwals lime surkhi BG rail fasting points crossing bridge guders pipe sheet M/S Brass sheets 1000 trenches 10×5×3" 1000 tiles 12×6×2" 150 cft timber 100 mould fuel wood by trenches owned by the contractor withing 10 miles etc comp:	5220/Cft	902.20%Cft
3.	CC plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering ratio 1:4:8	3263/Cft	9416.28%Cft
4.	P/L 2" thick toping cement concrete 1:2:4 i/c surface finishing and dividing into panels eto completed.	13050/Sft	3275.50%Sft

  
**EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC (WEST)**

I / we hereby quoted \_\_\_\_\_ Above / Below the SR.

Signature \_\_\_\_\_ Address \_\_\_\_\_

# OFFICE OF THE EXECUTIVE ENGINEER (B&R)

## SITE ZONE DMC WEST KARACHI

**SUBJECT: - CONST / IMP OF SEWERAGE LINE I/C CC FLOORING FROM RUSTOM KHAN AT SECTOR 5 METROVILL IN UC-04 SITE ZONE DMC (WEST)**

**E/Cost: 9,49,810/- E/Money 20,000/- T/Limit 45 Days Penalty 500/- PD.**

S.No	Description of Work	Quantity	Rate Per%
1.	Dismantling of CC Work 1:2:4	2805/Cft	3327.50%Cft
2.	Excavation of pipe line trenches pipe all kind of soil murum i/c trimming dressing leveling beds trenches correct level and graded cutting joints holes disposal of surplus earth with in 1 chains as directed by the Engg: Inch: P. fence guard lights flags temporary crossing non vehicler traffic where ever req: a lift up to 5 ft & lead up to 1 chain.	4500/Cft	4650 %0 Cft
3.	P. Rcc pipe ASTM class class 'C' 76-62 T/C 76-70 class II wall 'B' and fixing in trenches i/c cutting fitting jointing with rubber ring i/c testing with water to specified pressure 9" & 12" dia pipe.	400/Rft	412/P.Rft
4.	Const of Main Holes 4 inside with Rcc covers 21" dia 3×¾ with flat iron frame 5ft depth 1:2:4 in laying CC cost in situ 9" thick wall and disposal of surplus stuff etc comp:	16/Nos.	13028 / Each
5.	Add or deduct for depth of man holes above or beyond 5 ft (RA).	16/Rft	2245.55/P.Rft
6.	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc comp:	4050/Cft	2760.0/%0Cft
7.	Cartage of 100 Cft 5 tons all materials like stone aggregate spwals lime surkhi BG rail fasting points crossing bridge guders pipe sheet M/S Brass sheets 1000 trenches 10×5×3" 1000 tiles 12×6×2" 150 cft timber 100 mould fuel wood by trenches owned by the contractor withing 10 miles etc comp:	2244/Cft	902.20%Cft
8.	CC plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering ratio 1:4:8	2125/Cft	9416.28%Cft
9.	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and dividing into panels eto completed.	8140/Sft	3275.50%Sft



**EXECUTIVE ENGINEER (B&R)  
SITE ZONE DMC (WEST)**

**II / we hereby quoted \_\_\_\_\_ Above / Below the SR.**

**Signature \_\_\_\_\_ Address \_\_\_\_\_**

# OFFICE OF THE EXECUTIVE ENGINEER (B&R)

## SITE ZONE DMC WEST KARACHI

**SUBJECT: - CONST / IMP OF CC FLOORING FROM H. NO E-107 TO E-78 AND**  
**PROFFESAR KHURRAM AT SECTOR 2 IN UC-04 SITE ZONE DMC**  
**(WEST)**

**E/Cost: 9,97,000/- E/Money 20,000/- T/Limit 45 Days Penalty 500/- PD.**

S.No	Description of Work	Quantity	Rate Per%
1.	Dismantling of CC Work 1:2:4	4998/Cft	3327.50%Cft
2.	Cartage of 100 Cft 5 tons all materials like stone aggregate spwals lime surkhi BG rail fasting points crossing bridge guders pipe sheet M/S Brass sheets 1000 trenches 10×5×3" 1000 tiles 12×6×2" 150 cft timber 100 mould fuel wood by trenches owned by the contractor withing 10 miles etc comp:	3998/Cft	902.20%Cft
3.	CC plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering ratio 1:4:8	3900/Cft	9416.28%Cft
4.	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and dividing into panels eto completed.	13600/Sft	3275.50%Sft

  
**EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC (WEST)**

I / we hereby quoted \_\_\_\_\_ Above / Below the SR.

Signature \_\_\_\_\_ Address \_\_\_\_\_

# OFFICE OF THE EXECUTIVE ENGINEER (B&R)

## SITE ZONE DMC WEST KARACHI

**SUBJECT: - CONST OF CC FLOORING FROM HAJI JANDAD HOUSE TO**  
**METROVILL HOSPITAL AT SECTOR IV METROVILL IN UC-04**  
**SITE ZONE DMC (WEST)**

E/Cost: 9,98,000/- E/Money 20,000/- T/Limit 45 Days Penalty 500/- PD.

S.No	Description of Work	Quantity	Rate Per%
1.	Dismantling of CC Work 1:2:4	2079/Cft	3327.50%Cft
2.	Excavation of pipe line trenches pipe all kind of soil murum i/c trimming dressing leveling beds trenches correct level and graded cutting joints holes disposal of surplus earth with in 1 chains as directed by the Engg: Inch: P. fence guard lights flags temporary crossing non vehicler traffic where ever req: a lift up to 5 ft & lead up to 1 chain.	7875/Cft	4650 %0 Cft
3.	P. Rcc pipe ASTM class class 'C' 76-62 T/C 76-70 class II wall 'B' and fixing in trenches i/c cutting fitting jointing with rubber ring i/c testing with water to specified pressure 9" & 12" dia pipe.	700/Rft	412/P.Rft
4.	Const of Main Holes 4 inside with Rcc covers 21" dia 3×¾ with flat iron frame 5ft depth 1:2:4 in laying CC cost in situ 9" thick wall and disposal of surplus stuff etc comp:	28/Nos.	13028 / Each
5.	Add or deduct for depth of man holes above or beyond 5 ft (RA).	28/Rft	2245.55/P.Rft
6.	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc comp:	7085/Cft	2760.0/%0Cft
7.	Cartage of 100 Cft 5 tons all materials like stone aggregate spwals lime surkhi BG rail fasting points crossing bridge guders pipe sheet M/S Brass sheets 1000 trenches 10×5×3" 1000 tiles 12×6×2" 150 cft timber 100 mould fuel wood by trenches owned by the contractor withing 10 miles etc comp:	1663/Cft	902.20%Cft
8.	CC plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering ratio 1:4:8	1238/Cft	9416.28%Cft
9.	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and dividing into panels eto completed.	4950/Sft	3275.50%Sft

  
**EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC (WEST)**

II / we hereby quoted \_\_\_\_\_ Above / Below the SR.

Signature \_\_\_\_\_ Address \_\_\_\_\_



# OFFICE OF THE EXECUTIVE ENGINEER (B&R)

## SITE ZONE DMC WEST KARACHI

**SUBJECT: - CONST / IMP OF SEWERAGE LINE I/C CC FLOORING FROM TILAWAT**  
**HOUSE AND ZAHEER HOUSE AT SECTOR III IN UC-04 METROVILL**  
**SITE ZONE DMC (WEST)**

**E/Cost: 9,61,940/- E/Money 20,000/- T/Limit 45 Days Penalty 500/- PD.**

S.No	Description of Work	Quantity	Rate Per%
1.	Dismantling of CC Work 1:2:4	4998/Cft	3327.50%Cft
2.	Cartage of 100 Cft 5 tons all materials like stone aggregate spwals lime surkhi BG rail fasting points crossing bridge guders pipe sheet M/S Brass sheets 1000 trenches 10×5×3" 1000 tiles 12×6×2" 150 cft timber 100 mould fuel wood by trenches owned by the contractor withing 10 miles etc comp:	3998/Cft	902.20%Cft
3.	CC plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering ratio 1:4:8	3927/Cft	9416.28%Cft
4.	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and dividing into panels eto completed.	11900/Sft	3275.50%Sft

  
**EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC (WEST)**

I / we hereby quoted \_\_\_\_\_ Above / Below the SR.

Signature \_\_\_\_\_ Address \_\_\_\_\_

# OFFICE OF THE EXECUTIVE ENGINEER (M&E)

## SITE ZONE DMC WEST KARACHI

**SUBJECT: - REPAIR / MAINTENANCE & ENGINE OVERHAULING OF SANITATION**  
**VEHICLE NO. CH-11402 & CH-21288 IN SITE ZONE DMC (WEST)**

E/Cost: 9,72,000/- E/Money 20,000/- T/Limit 45 Days Penalty 500/- PD.

S.No	Description of Work	Quantity	Rate Per%
1.	<b><u>MACHINING / GRINDING WORK.</u></b>		
	a) Crank Shaft Grinding Polish.		
	b) Cam Bush Fitting.		
	c) Connecting Rod Bush Fitting Boring.		
	d) Cylinder Boring / Sleeve Removing.		
	e) Sleeve Fitting.		
	f) Head Tikli Fitting.		
	g) Main & Big end Bearing.		
	h) Valve Seat Cutting & Facing.		
	i) Head Facing.		
	j) Main Tikli Fitting.		
	k) Crank Shaft Alignment.		
	l) Engine Block and Head Checking with Lines Chemical Treatment of Cleaning all Engine Complete.	01 Job	35,500/-
2.	<b><u>ENGINE.</u></b>		
	a) Liner kit.		
	b) Main & Big end Bearing. 01 Set.		
	c) Engine Overhauling Kit. 01 Set.		
	d) Valve Intel / Exhaust set. 01 Set.		
	e) Valve Guide Set. 01 Set.		
	f) Came Bush Set. 01 Set.		
	g) Connecting Rod Bush Set. 01 Set.		
	h) Tappid Bush. 01 Set.		
	i) Valve Catcher. 01 Set.		
	j) Oil Pump Assembly. 01 Set.		
	k) Hose Pipe / Fan belt. 01 Set.		
	l) Water Jacket. 01 Set.		
	m) Complete Gas Kit. 01 Set. Complete in all Respect	01 Job	1.45,000/-
3.	<b><u>FUEL INJECTION PUMP.</u></b>		
	a) Providing / fixing Rear / Head Disk. 01 No		
	b) Providing / fixing Diesel Plate. 01 No		
	c) Providing / fixing Packing Kit. 01 No		
	d) Providing / fixing Spring with washers. 01 No		
	e) Providing / fixing Plunger Nozzles. 01 No		
	f) Providing / fixing Injection Nozzles. 01 No	01 Job	31,700/-
4.	Providing /Fixing the air compressor by means complete replacement of piston, sleeve & connecting rod & gray in all respect.	01 Job	80,900/-
5.	Clutch system over hauling work I/C the cost of replacement of following parts:		

a) Clutch Plate.		
b) Pressure Plate.		
c) Clutch Cylinder(upper & Lower) kit. 02 Kit		
d) Fly wheel twining & polishing. 01 Job	01 Job	35,500/-
6. Brake System: over hauling work I/C the cost of replacement of following parts:		
a) Brake Washers. 12 Nos		
b) Brake Shoes. 16 Nos		
c) Wheel Oil Seal. 04 Nos		
d) Brake Booster control valves. 03 Nos		
e) Brake Booster diaphragms. 04 Nos		
f) Liner kit of compressor. 01 Set		
g) Wheel Cylinder complete in all respect. 04 Job	01 Job	30,500/-
7. Electric System Providing / Fixing complete wiring kit work i/c the cost of the replacement of following Genuine / imported accessories.		
a) P/Fixing head light complete with housing. 04 Nos		
b) Back light assembly. 02 Nos		
c) P/Fixing Parking light. 02 Nos		
d) P/Fixing indicator assembly. 04 Nos		
e) P/Fixing Choke Cable. 02 Nos		
f) Complete wiring.		
g) P/Fixing oil gauge. 02 Nos		
h) P/Fixing batteries 100AMP. 02 Nos		
i) Wiring of Batteries. 01 Set	01 Job	40,700/-
8. P/Fixing the water body complete in all respect		
9. Repair of rear spring leaf by means of opening leaf repairing & refitting the same the work i/c P/F broken spring leaf, change of U-Clamp, centre bolt bush & tensioning the all leafs etc as required as per instruction of E/L.	01 Job	13,500/-
10. Repair of front spring leaf by means of opening leaf repairing & refitting the same the work i/c P/F broken spring leaf, change of U-Clamp, centre bolt bush & tensioning the all leafs etc as required as per instruction of E/L.	01 Job	14,500/-
11. P/Fixing the radiator opening the radiator from top & bottom side & soldering top & bottom cover damage fixing the nut bolt & bracket fitting & complete as required.	01 Job	15,900/-
12. P/Fixing the self complete in all respect as required.	01 Job	12,900/-
13. Providing / Fixing Alternator Complete	01 Job	11,500/-
14. P/Fixing the tie rod & steering knuckle repairing of spindle, P/Fixing the ball joint, & all rubber accessories bearings complete in all respect.	01 Job	10000/-

#### **CH-21288**

#### **15. MACHINING / GRINDING WORK.**

- Crank Shaft Grinding Polish.
- Cam Bush Fitting.
- Connecting Rod Bush Fitting Boring.
- Cylinder Boring / Sleeve Removing.

e) Sleeve Fitting.		
f) Head Tikli Fitting.		
g) Main & Big end Bearing.		
h) Valve Seat Cutting & Facing.		
i) Head Facing.		
j) Main Tikli Fitting.		
k) Crank Shaft Alignment.		
l) Engine Block and Head Checking with Lines Chemical Treatment of Cleaning all Engine Complete.	01 Job	35,500/-

#### 16. **ENGINE.**

a) Liner kit.		
b) Main & Big end Bearing. 01 Set.		
c) Engine Overhauling Kit. 01 Set.		
d) Valve Intel / Exhaust set. 01 Set.		
e) Valve Guide Set. 01 Set.		
f) Came Bush Set. 01 Set.		
g) Connecting Rod Bush Set. 01 Set.		
h) Tappid Bush. 01 Set.		
i) Valve Catcher. 01 Set.		
j) Oil Pump Assembly. 01 Set.		
k) Hose Pipe / Fan belt. 01 Set.		
l) Water Jacket. 01 Set.		
m) Complete Gas Kit. 01 Set. Complete in all Respect	01 Job	1.45,000/-

#### 17. **FUEL INJECTION PUMP.**

g) Providing / fixing Rear / Head Disk. 01 No		
h) Providing / fixing Diesel Plate. 01 No		
i) Providing / fixing Packing Kit. 01 No		
j) Providing / fixing Spring with washers. 01 No		
k) Providing / fixing Plunger Nozzles. 01 No		
l) Providing / fixing Injection Nozzles. 01 No	01 Job	31,700/-

18. Providing /Fixing the air compressor by means complete replacement of piston, sleeve & connecting rod & gray in all respect.	01 Job	80,900/-
--	--------	----------

19. Clutch system over hauling work I/C the cost of replacement of following parts:		
a) Clutch Plate.		
b) Pressure Plate.		
c) Clutch Cylinder(upper & Lower) kit. 02 Kit		
d) Fly wheel twining & polishing. 01 Job	01 Job	35,500/-

20. Brake System: over hauling work I/C the cost of replacement of following parts:		
a) Brake Washers. 12 Nos		
b) Brake Shoes. 16 Nos		
c) Wheel Oil Seal. 04 Nos		
d) Brake Booster control valves. 03 Nos		
e) Brake Booster diaphragms. 04 Nos		
f) Liner kit of compressor. 01 Set		
g) Wheel Cylinder complete in all respect. 04 Job	01 Job	30,500/-

21. Electric System Providing / Fixing complete wiring kit work i/c the cost of the replacement of following Genuine / imported accessories.		
a) P/Fixing head light complete with housing. 04 Nos		
b) Back light assembly. 02 Nos		
c) P/Fixing Parking light. 02 Nos		

d) P/Fixing indicator assembly. 04 Nos		
e) P/Fixing Choke Cable. 02 Nos		
f) Complete wiring.		
g) P/Fixing oil gauge. 02 Nos		
h) P/Fixing batteries 100AMP. 02 Nos		
i) Wiring of Batteries. 01 Set	01 Job	40,700/-
22. P/Fixing the water body complete in all respect		
23. Repair of rear spring leaf by means of opening leaf repairing & refitting the same the work i/c P/F broken spring leaf, change of U-Clamp, centre bolt bush & tensioning the all leafs etc as required as per instruction of E/I.		
	01 Job	13,500/-
24. Repair of front spring leaf by means of opening leaf repairing & refitting the same the work i/c P/F broken spring leaf, change of U-Clamp, centre bolt bush & tensioning the all leafs etc as required as per instruction of E/I.		
	01 Job	14,500/-
25. P/Fixing the radiator opening the radiator from top & bottom side & soldering top & bottom cover damage fixing the nut bolt & bracket fitting & complete as required.		
	01 Job	15,900/-
26. P/Fixing the self complete in all respect as required.		
	01 Job	12,900/-
27. Providing / Fixing Alternator Complete		
	01 Job	11,500/-
28. P/Fixing the tie rod & steering knuckle repairing of spindle, P/Fixing the ball joint, & all rubber accessories bearings complete in all respect.		
	01 Job	10000/-

  
 EXECUTIVE ENGINEER (M&E)  
 SITE ZONE DMC (WEST)

I / we hereby quoted \_\_\_\_\_ Above / Below the SR.

Signature \_\_\_\_\_ Address \_\_\_\_\_

# OFFICE OF THE EXECUTIVE ENGINEER (M&E)

## SITE ZONE DMC WEST KARACHI

**SUBJECT: - REPAIR / MAINTENANCE OF VEHICLE NO. CH-16643 HINO**

**LIFTER SITE ZONE DMC (WEST)**

**E/Cost: 9,75,800/- E/Money 20,000/- T/Limit 45 Days Penalty 500/- PD.**

S.No	Description of Work	Quantity	Rate Per%
1.	Re-fabrication of driver cabin Hino-KR-by means of Manufacturing and fixing of roof complete as per Genuine shape and design. P/F of inner roof regizin And form repairing of seats by means of full cautioning with seat cover best quality manufacturing and fixing of mudguard left and right side rear and front denting of front show denting L/R side door denting of rear side denting and repairing front bumper repairing of cooly seat, P/F of valve 3"dia with electric welding complete cabin painted with under coat and protein etc. P/F of following accessories door lock. P/F of glass channel and side glass with handle cabin back glass with rubber. P/F of front indicator set.	01 Job	2,50,000/-
2.	P/F Tyres, Tubes & Flap Size 7-50-16 General Make as required.	06 Nos	1,50,000/-
3.	Clutch system over hauling work I/C the cost of replacement of following parts: a) Clutch Plate. b) Pressure Plate. c) Clutch Cylinder(upper & Lower) kit. 02 Kit d) Fly wheel twining & polishing. 01 Job	01 Job	35,500/-
4.	Brake System: over hauling work I/C the cost of replacement of following parts: a) Brake Washers. 12 Nos b) Brake Shoes. 16 Nos c) Wheel Oil Seal. 04 Nos d) Brake Booster control valves. 03 Nos e) Brake Booster diaphragms. 04 Nos f) Liner kit of compressor. 01 Set g) Wheel Cylinder complete in all respect. 04 Job	01 Job	30,500/-
5.	Fuel Injection Pump. a) Providing / fixing Rear / Head Disk. 01 No b) Providing / fixing Diesel Plate. 01 No c) Providing / fixing Packing Kit. 01 No d) Providing / fixing Spring with washers. 01 No e) Providing / fixing Plunger Nozzles. 01 No f) Providing / fixing Injection Nozzles. 01 No	01 Job	50,500/-
6.	P/F of Hydraulic Jack shaft with piston, Oil Seal Kit & both sides pin with lock.	01 Job	65,700/-
7.	Manufacturing and fixing of all pin with lock rear & front side Booms.	01 Job	45,900/-

8.	P/F of Control Valve Assembly.	01 Set	25,000/-
9.	P/F of Hydraulic Pipe with tee both side as per req.	10 Nos	35,700/-
10.	Manufacturing, Cutting, Bending of M.S Sheet for floor with electric welding as par required.	01 Job	45,500/-
11.	Repair of rear hydraulic jacks both side with hydraulic pipe both side.	01 Job	75,900/-
12.	P/Fixing self & generator complete as required.	01 Job	60,900/-
13.	Repair of Fiber Basket as per required.	01 Job	45,000/-
14.	Complete Vehicle of Hydrulic Boom Painted as per required.	01 Job	35,000/-
15.	P/Fixing batteries 100AMP Exide with Terminals.	02 Nos	24,700/-

  
**EXECUTIVE ENGINEER (M&E)**  
**SITE ZONE DMC (WEST)**

I / we hereby quoted \_\_\_\_\_ Above / Below the SR.

Signature \_\_\_\_\_ Address \_\_\_\_\_