



OFFICE OF THE ADMINISTRATOR LYARI GENERAL HOSPITAL,

NOTICE INVITING TENDER

1. The Administrator (MS) Lyari General Hospital, Health Department, Government of Sindh invites sealed tenders on Composite Schedule of Rates (CSR)/ Item Rate basis or on *both* from interested contractors/firms.

List of Works

S No	Name of Work	Estimated Cost (In Rs. in Million)	Bid Security	Tender Fee	Time for completion
1.	M/R, Repair & Rehabilitation works at Main Building	45.00	2% of Estimated cost/offered rate	Rs. 2000/-	30 days
2.	M/R, Repair & Rehabilitation works at Main Building (Electrical Works)	10.00	2% of Estimated cost/offered rate	Rs. 2000/-	30 days
3.	M/R, Repair & Rehabilitation works of Cardiology & OPD Blocks	10.00	2% of Estimated cost/offered rate	Rs. 2000/-	30 days
4.	M/R, External Development & Sewerage System up gradation	15.00	2% of Estimated cost/offered rate	Rs. 2000/-	30 days

2. **Eligibility:** Valid Registration with tax authorities (FBR, Sindh Revenue Board) & Pakistan Engineering Council in relevant category **C-5 & above** and discipline civil works; For Electrical Works valid license is required from Inspectorate of Electrical Sindh of the similar region with respect to works shown at s.r.no. 02

3. **Method of Procurement.** *Single Stage Single Envelop.*

4. **Bidding/Tender Documents:**

(i) **Issuance:** Documents will be issued from date of publication to **16-05-2017**, on payment of tender fee Rs. 2000/= (non-refundable) in the shape of pay order to the name Administrator (M.S) Lyari General Hospital.

(ii) **Submission:** Last date will be **17-05-2017 at 1:00 pm.**

(iii) **Opening:** Tenders will be opened on same day i.e. **17-05-2017 at 2:00 pm**

(iv) **Place** of issuance, submission, inquiries and opening will be:-

Address (Postal) : M.S office, Lyari General Hospital

Telephone Number(s) :

Fax Number :

E-mail Address (If available) :

(v) **Schedule of Un-responded tenders** will be again issued/submitted/opened on following dates:-

2 nd Attempt: Date of Issuance of Tenders (a) 18-05-2017 up to 05-06-2017	(b) Submission and Opening Received on 06-06-2017 upto 2:00 pm and open at the same day at 3:00 pm
---	---

5. **Terms & Conditions.**

- (a) Under following conditions bid will be rejected:-
(i) Conditional and telegraphic bids/tenders;
(ii) Bids not accompanied by bid security of required amount and form;
(iii) Bids received after specified date and time.
(iv) Black listed firms.
- (b) **Bid validity Period: - (90) days**
- (c) **Performance Security:** 4% of the accepted bid price in the shape of pay order, demand draft or Bank Guarantee from any schedule bank with in the period of 14 days after receipt of Letter of acceptance.
- (d) Procuring Agency reserves the right to reject all or any bids subject to the relevant provisions of Sindh Public Procurement Rules 2010.
- (e) **Responsive Bidder is required to submit following documents with bid:**
(i) List of similar assignments with cost (*atleast 02 similar projects with their cost*) undertaken over the past (02) years with completion certificate; (List of projects to be provided with bid)
(ii) *Details of equipments, machineries and transport owned by firm/contractor;*
(iii) Financial Statement (summary)/ Bank Statement and income tax return for the last 02 years;
(iv) Affidavit that the firm has never been black listed;
- (f) In case of public holiday or any holiday announced by the Sindh Government the bid will be submitted/ opened on the next working day, as per usual schedule in accordance with Rule 41 (3) of SPP Rules 2010.

MEDICAL SUPERINTENDENT
SINDH GOVT LYARI GENERAL HOSPITAL
KARACHI



دفتر ایڈمنسٹریٹر لیاری جنرل ہاسپٹل

نمبر: L.GHK/2016-17/1211 مورخہ 28.04.2017

نوٹس طلبی ٹینڈر

1۔ ایڈمنسٹریٹر (ایم ایس) لیاری جنرل ہاسپٹل، حکومت سندھ کو طبی رکٹوں کے لئے کثیر الترقی اور مزید کمپوزٹ ٹیڈول آف رٹس (CSR) / آئی ٹیم پر مبنی ٹینڈرز مطلوب ہیں:

نمبر	کام کا نام	تینڈر کی قیمت (ملین روپے)	ڈیڈ لائن	ٹینڈر فرس	مدت
1	M/R مرمت و بحالی کا کام بمقام مین بلڈنگ	45.00	تینڈر کی پیشکش کی تاریخ کی 2% آگے	2000-	30 دن
2	M/R مرمت و بحالی کا کام بمقام مین بلڈنگ (الیکٹریکل ورکس)	10.00	تینڈر کی پیشکش کی تاریخ کی 2% آگے	2000-	30 دن
3	M/R مرمت و بحالی کا کام بمقام کارڈیالوجی اور OPD پلاس	10.00	تینڈر کی پیشکش کی تاریخ کی 2% آگے	2000-	30 دن
4	M/R بیرونی ترقی اور سرسبز سسٹم اپ گریڈیشن	15.00	تینڈر کی پیشکش کی تاریخ کی 2% آگے	2000-	30 دن

2۔ **اہلیت:** ٹیکس حکام (FBR) سندھ رجسٹرڈ بورڈ (C-S اور C-S) اور باڈر ٹیکسٹری میں برائے سول ورکس پاکستان انجینئرنگ کونسل میں رجسٹرڈ ممبر ہونا، نمبر شمار 100 سے زائد اور انجینئرنگ کے کاموں کیلئے انجینئر آف الیکٹریکل سندھ سے گرانٹس، لیکن کاروباری کردار ہو کر رجسٹرڈ ہونا۔

3۔ **پرو کوریور منٹ کا طریق کار:** سٹیل آئیٹم ایک خاص طریق کار

4۔ **بڈنگ/ٹینڈر دستاویزات:**

(i) **اجراء:** دستاویزات تاریخ اجراء سے 16.05.2017 تک تینڈر-2000 روپے (تین ہزار روپے) بشمل پی آر آر، ایڈمنسٹریٹر (ایم ایس) لیاری جنرل ہاسپٹل اور گرانٹس پر جاری کی جائیں گی۔

(ii) **جمع کرنا:** آخری تاریخ ہونی 17.05.2017 سے پہلے 1:00 بجے تک۔

(iii) **کھولنا:** ٹینڈر کی تاریخ 17.05.2017 سے پہلے 2:00 بجے تک ہونی چاہئے۔

(iv) **مقام اجراء:** جمع کرنا اور کھولنا ہوگا۔

پتہ (ڈاک ٹا): ایم ایس آفیس، لیاری جنرل ہاسپٹل

5۔ **بدم جواب:** والے ٹینڈرز کا ٹیڈول، درج ذیل تاریخوں میں دوبارہ جاری کرنے کے لئے مانگوئے جائیں گے۔

دوسری کوشش: ٹینڈرز کی تاریخ اجراء 18.05.2017 تا 06.06.2017 صبح 10:00 بجے تک اور ای تاریخ پر صبح 3:00 بجے تک ہونی چاہئے۔

شرائط و ضوابط:

(a) درج ذیل صورتوں میں پیشکش مسترد کر دی جائیگی:

- مشروطہ/ٹینڈر گرانٹس سے منسلک پیشکشیں ٹینڈرز۔
- مقررہ وقت میں مطلوبہ رقم کی ڈیڈ لائن کے بعد پیشکشیں۔
- مقررہ تاریخ اور وقت کے بعد وصول پیشکشیں۔
- بیک اپڈ فرمز۔

(b) پیشکش ٹینڈر کرنے کی مدت: (90) دن۔

(c) پرفارمنس کی گرانٹ: قبول کردہ ورک کی کل لاگت کی 4% پیشکش ہے آرڈر ڈیمانڈ ڈرافٹ یا بینک گرانٹی اسٹیٹمنٹ والے بینک مراسلہ قبولیت کی وصولی کے اندر 14 دن تک کرنائی ہوگی۔

(d) پرو کوریور منٹ کا نام سندھ پبلک ورکس ڈیپارٹمنٹ، 2010 کے متعلقہ مندرجات سے مشروط تمام یا کوئی پیشکش مسترد کرنے کا حق محفوظ رکھی ہے۔

(e) جواب دینے والے پیشکش دہندہ سے پیشکش کے معاوضہ اور جیل و سٹاپ و سٹاپ کی طلب کی جائیگی:

- گزارش 02 برسوں کے دوران کی گئی مہاش اسٹینٹس (کم از کم 02 مہاش پر پیشکش مع لاگت) کی فراہمیت معاہدہ عملی مہاش کے لئے (پرو کوریور منٹ کے معاوضہ فراہم کی جائے گی)۔
- فرم کونٹریکٹ کی ملکیت میں موجود ایک پیشکش، پیشکش اور فراہمیت کی تفصیلات۔
- گزارش 02 برسوں کی ڈیڈ لائن اسٹینٹس (سٹیٹ) ایکٹ 1973 کے تحت فراہم کی جائے گی۔
- ایسی ڈیڈ لائن فراہم کی جائے گی جس سے اسٹینٹس کا انمان کے تحت کی صورت میں پیشکشیں SPP ہزار 2010 کے ردول (3) 41 کی مطابقت سے عمومی ٹیڈول پر لاگے ایم کار پر پیش کرانی کی گئی ہوگی۔

... و ...

میڈیکل سپرنٹنڈنٹ

حکومت سندھ، لیاری جنرل ہاسپٹل، کراچی

(INF-KRY-2341/17) ہم روشت گروہی کے ساتھ ساتھ ہیں

SAY NO TO CORRUPTION

8398

روبرو جناب کامران عطاء سومرو چیف صاحب

ادارت لائبریری، ڈسٹرکٹ اینڈ سیشن جج کراچی ایسٹ

سیشن کیس نمبر 474 سال 2017

ایس آئی آر نمبر 42 سال 2017

زیرو دفتر 147/149/302/34 PPC

قانون لائبریری، کراچی، سرکار، **مخلاف**

گورنمنٹ لائبریری، سیشن لائبریری، سید اسمان سمن ولد محمد حسین (حقنی) قانونی رہائش گاہ، کورٹ سیشن و لائبریری سیشن (پب) اور ڈیپارٹمنٹ آف جج کورٹ سیشن (پب) (پب)

ایکٹایز برضاہ (2) 345 (2) مجموعی ضابطہ ہداری اور (6) 345 (6) مجموعی ضابطہ ہداری

برگورنٹ بلاٹروم خزانہ کے مکمل کے لئے ضابطہ (2) 345 (2) اور (6) 345 (6) مجموعی ضابطہ ہداری کے تحت ایک درخواست مہاش کیلئے دائر کی ہے اور مورخہ 8 مئی 2017 کو درخواست برائے مہاش کی سماعت مقرر کی گئی ہے۔ آپ کو مکمل کیا جاتا ہے کہ عدالت میں 8 مئی 2017 کو 30-30 بجے بذات خود حاضر ہوں یا وکیل کو مہاش کے لئے درخواست کے خلاف اظہار و بیان کریں۔ حاضر میں قانونی کی سماعت میں مذکورہ درخواست کی سماعت کے لئے نظر نہ قبول کیا جائے گا۔ برائے مہاش اور ہدایت کے ساتھ آج 28-04-2017 مہاش کی ہدایت ہوگی۔

محکمہ... سرسبز

محکمہ عدالت

محکمہ عدالت سندھ، لاہور سیشن ڈسٹرکٹ جج کراچی ایسٹ

کے لئے لکھا گیا ہے۔

- مشروطہ/ٹینڈر گرانٹس سے
- پرو کوریور منٹ کی پیشکشیں
- ٹینڈرز/پیشکشیں مسترد کر دیں
- اس ضمن میں مزید تفصیلات
- جاسکتی ہیں۔
- ٹینڈر پر SPPRA اور
- سائٹ w.sindh.gov.pk

KRY-2328/17

پروجیکٹ

پروجیکٹ

سندھ ایگریکلچر گروٹھ

مکان نمبر F-50/3 بلاک 8، کراچی، ٹیلی فون: 99332724-121

انتہاس برائے اظہار

(کنسلٹنگ سروسز - میڈیا مانیٹرنگ)

اسلامی جمہوریہ پاکستان

سندھ ایگریکلچر گروٹھ پر پروجیکٹ (P128307)

اسائنمنٹ کا عنوان: ٹیلی وژن الاٹن (BTL) سروسز کیلئے میڈیا فرم کی خدمات کا حصول

حوالہ نمبر: PK-SAGP-9547-CS-QQS

حکومت سندھ کو ایگریکلچر ڈیپارٹمنٹ، ایگریکلچر گروٹھ پر پروجیکٹ (قرض نمبر: K-دو ایف) کے تحت کنسلٹنگ سروسز پر فرج کرنے کی خواہاں ہے۔

کنسلٹنگ سروسز ("سروسز") میں ماس میڈیا کوئی سیشن شامل ہے۔ سندھ ایگریکلچر گروٹھ پر پروجیکٹ کا شکار ہے، ایسے اداروں کو ذریعہ آلات فراہم کر رہا ہے۔ ماس میڈیا کی سیشن کی فراہمی سے ایک چاہیہ ایسٹیمیاٹنگ ٹیم (ٹی وی، ڈی وی، سٹیٹو، پرنٹ اور انٹرنیٹ) ہوگا۔

ماس میڈیا یا این سروسز کی توہین کیلئے تقریباً پانچ میڈیا مانیٹرنگ کی خدمات حاصل کرنے کا ارادہ اور سوشل میڈیا استعمال کرتے ہوئے تمام ماس میڈیا سروسزوں کی مانیٹرنگ اور توثیق کرنے کی ذمہ داریات فراہم کرے گی۔

- ATL اور BTL فرمز کی جانب سے فراہم کی جائے گی، ایسے سروسزوں کی میڈیا گورننگ کی ٹیم
- مسلحہ میڈیا مانیٹرنگ فراہم کرنا اور ایسے سروسزوں کی میڈیا گورننگ اور پرنٹ انٹرویوز اور کے ساتھ ساتھ سوشل میڈیا یا مانیٹرنگ سمیت مہاش پر پیش تیار کرنا۔
- میڈیا سروسزوں کی رسائی اور ڈیٹا انگریزی اور اردو ذرائع عاقلوں میں مہاش پڑھ کر ماس سے نسبت پر مبنی مہاش پر سندھ ایگریکلچر گروٹھ پر پروجیکٹ اہل کنسلٹنٹس کو ہدایت دینا ہے کہ وہ مذکورہ خدمات کی فراہمی کیلئے اختیار کرنے والی معلومات فراہم کریں کہ وہ مطلوبہ خدمات کی فراہمی کیلئے مطلوبہ قابلیت اور متعلقہ تجربے کے برسوں کا تجربہ (ii) گزارش پانچ برسوں کے دوران کم از کم تین (3) مہاش اسٹینٹس فراہم دی ہوں (iii) اسٹینٹس، MNC، ماس میڈیا براڈ کاسٹنگ فراہم کی ہوں (iv) متعلقہ شعبے کے ٹیکنیکل اور ایگزیکٹو پروفیشنلس کی فراہمیت (CQS) پر مبنی پروپوزل اور کارٹیلڈ اسٹینٹس: اسٹینٹس اینڈ اسٹینٹ آف کنسلٹنٹس
- اپریل 2017 سے جنوری 2011 تک فراہمی شدہ ہدایتی 2014 میں مقرر کردہ ہدایت کے تحت کنسلٹنٹ منتخب کیا جائے
- تعمیراتی اور فرج اور سروسز فراہمیت SAGP ویب سائٹ w.sagp.org.pk پر مہاش ہیں۔ مزید معلومات
- شام 5:00 بجے بروز جمعہ فراہم حاصل کی جاسکتی ہیں۔

پتہ: کراچی، آخری تاریخ 15 مئی 2017 ہے۔ اظہار و بیان کی مہاش ہاؤس کا پتہ اور تاریخ ذیل پتہ پر فراہم کیا جائے گا۔

پروجیکٹ

SAGP-A

مکان نمبر F-50/3 بلاک

انور@yaho.com

(INF-KRY-2322/17)

ہم روشت گروہی کے خلاف متحد ہیں

8398

ENGINEER (BUILDINGS)

DIVISION, DISTRICT JAMSHORO
 Add: Opposite Irrigation Work Shop Near NADRA Office Kotri,
 Taluka Kotri District Jamshoro
 Email: m_aslam_tanloy@yahoo.com Phone: 022-3874164
 No.XEN/(B)/TC/G-55/424 Jamshoro Dated: 26-04-2017

NOTICE INVITING TENDERS

Sealed Tenders on Standard Bidding Documents are invited from the Interested Firms / Agencies / Contractors Under SPP Rules - 2010 for the following works.

Sr. No.	Name of Schemes / Sectors	Estimated Cost (In Million)	Earnest Money	Cost of Printing & Providing Documents	Time of Completion
ADP Schemes.					
1.	ADP 19, Rehabilitation of Govt. Buildings of (Assistant Commissioner Residence Bungalow) at Sehwan, Taluka Sehwan, (Compound Wall & Guard Room).	5.000	5%	3000	12 Months
2.	ADP 20, Rehabilitation of Government Building of Lal Shahbaz Qalandar DCO Camp Office at Sehwan, Taluka Sehwan (Remaining Work).	5.000	5%	3000	12 Months
3.	ADP 416, Renovation / Rehabilitation of BHU / RHC i/c Boundary Wall of RHC U.C. Dhan, Taluka Sehwan, District Jamshoro.	1.000	5%	1500	06 Months
4.	Construction of Boundary Wall i/c Improvement of Graveyard Gahir, Taluka Sehwan, District Jamshoro (New ADP).	2.000	5%	2500	12 Months
5.	ADP 4, Repair / Renovation of Dak Bungalow at T.B. Khan, Taluka T.B. Khan (Supplying / Providing Furniture & Equipment).	1.000	5%	2500	06 Months
6.	ADP 410, Rehabilitation of Dispensary 4 Rooms i/c Verandha @ Village Jumoon Shoro Wapda Colony Jamshoro (Supplying / Providing Furniture & Equipment).	1.000	5%	2500	06 Months
7.	Provision of Furniture - Maintenance of Existing Union Council Offices at Bubak, Jhangara, Araz, Wahur & Talti, Taluka Sehwan District Jamshoro New ADP.	5.000	5%	3000	12 Months

Date of Issue of Blank Tender upto	15-05-2017	Receive Tender 01:00 PM
Date of Receive Back & Opening of Tenders	16-05-2017	Open Tender 02:00 PM

Tenders will be issued to the contractors on payment of cost of printing and providing documents shown above (Non Refundable) from the date of publication upto 16-05-2017, in the office of undersigned. Tender will be received back on 16-05-2017, at 01:00 PM and will be opened on 16-05-2017, at 02:00 PM in presence of contractor or their representative who wish to remain present before committee, comprising the Superintending Engineer (Works & Services) Department Jamshoro & Executive Engineer Buildings (Division) Works & Services Jamshoro & Executive Engineer Public Health Engineering Division, District Jamshoro. The bid security at the rate of 3% of bid amount offered be submitted with the bid documents.

Blank Tender forms / description of work / scheme can be had from the office of the undersigned on any working day. Conditional tender will not be entertained. The applicant must be registered with Federal Board of Revenue (FBR) and Sindh Board of Revenue, whose certificate should be attached along with tender form at the time of submission of bid.

[In case of holiday or if any member of the procurement committee is un-available, the opening of tender will be issued / opened on the next working day].

Pakistan Engineering Council Certificate for the year 2017 is required for the works above Rs. 4.000 (Million).

"The Procuring Agency may reject all or any bids subject to the relevant provision of SPP Rules" 2010.

[The place of tenders for issue & opening is the office of Executive Engineer Buildings Division (W&S) Jamshoro at Kotri Opposite Irrigation Work Shop, Taluka Kotri].


In case of no response the issue and opening date of tender will be as under. Second Attempt Tender will be issued upto 30-05-2017 at 12:00 PM received and Opened on 30-05-2017 (01:00 PM).

Note: This NIT can be seen on Sindh Govt Website at www.sindh.gov.pk.

Note: This NIT can be seen on SPPRA Website at www.pprasinhd.gov.pk.

**EXECUTIVE ENGINEER
(BUILDINGS) DIVISION
JAMSHORO**

INF-KRY:No.2325/17



OFFICE OF THE ADMINISTRATOR

LYARI GENERAL HOSPITAL

No.LGHK/2016-17/1211 Dated: 28-04-2017

NOTICE INVITING TENDER

1. The Administrator (MS) Lyari General Hospital, Health Department, Government of Sindh invites sealed tenders on Composite Schedule of Rates (CSR)/ Item Rate basis or on both from interested contractors/firms.

List of Works

S. No.	Name of Work	Estimated Cost (In Rs. in Million)	Bid Security	Tender Fee	Time for Completion
1.	M/R, Repair & Rehabilitation works at Main Building	45.00	2% of Estimated Cost/ Offered Rate	Rs.2000/-	30 days
2.	M/R, Repair & Rehabilitation works at Main Building (Electrical Works)	10.00	2% of Estimated Cost/ Offered Rate	Rs.2000/-	30 days
3.	M/R, Repair & Rehabilitation works of Cardiology & OPD Blocks	10.00	2% of Estimated Cost/ Offered Rate	Rs.2000/-	30 days
4.	M/R, External Development & Sewerage System up Gradation	15.00	2% of Estimated Cost/ Offered Rate	Rs.2000/-	30 days

2. Eligibility: Valid Registration with tax authorities (FBR, Sindh Revenue Board) & Pakistan Engineering Council in relevant category C-5 & above and discipline civil works; For Electrical Works valid license is required from Inspectorate of Electrical Sindh of the similar region with respect to works shown at Sr.No.02

3. Method of Procurement: Single Stage Single Envelope.

4. Bidding/Tender Documents:

- Issuance: Documents will be issued from date of publication to 16-05-2017, on payment of tender fee Rs. 2000/= (non-refundable) in the shape of pay order to the name Administrator (M.S) Lyari General Hospital.
- Submission: Last date will be 17-05-2017 at 1:00 pm.
- Opening: Tenders will be opened on same day i.e. 17-05-2017 at 2:00 pm.
- Place of issuance, submission, inquiries and opening will be: Address (Postal) - M.S office, Lyari General Hospital Telephone Number(s): Fax Number: E-mail Address (If available):
- Schedule of Un-responded tenders will be again issued/submitted/opened on following dates:-


2 nd Attempt	(a) Date of Issuance of tenders	(b) Submission and Opening
	18-05-2017 upto 05-06-2017	Received on 06-06-2017 upto 02:00 pm and Opened on same day at 03:00 pm

5. Terms & Conditions.

- Under following conditions bid will be rejected:
 - Conditional and telegraphic bids/tenders;
 - Bids not accompanied by bid security of required amount and form;
 - Bids received after specified date and time.
 - Black listed firms.
- Bid validity Period: (90) days
- Performance Security: 4% of the accepted bid price in the shape of pay order, demand draft or Bank Guarantee from any schedule bank with in the period of 14 days after receipt of Letter of acceptance.
- Procuring Agency reserves the right to reject all or any bids subject to the relevant provisions of Sindh Public Procurement Rules 2010.
- Response Bidder is required to submit following documents with bid:
 - List of similar assignments with cost (atleast 02 similar projects with their cost) under-taken over the past (02) years with completion certificate, (List of projects to be provided with bid)
 - Details of equipments, machineries and transport owned by firm/contractor.
 - Financial Statement (summary)/ Bank Statement and Income Tax Return for the last 02 years;
 - Affidavit that the firm has never been black listed;
- In case of public holiday or any holiday announced by the Sindh Government the bid will be submitted/ opened on the next working day as per usual schedule in accordance with Rule 41 (3) of SPP Rules 2010.

**MEDICAL SUPERINTENDENT
Sindh Government,
Lyari General Hospital
Karachi**

INF-KRY:No.2341/17



Expressed to Lyari General Hospital - 28/4/17



NOTIFICATION

No SO (PM&I) Health./LGHK/Procurement/2017: In pursuance of Rule-07 of the Sindh Public Procurement Rules, 2010 (Amended 2013), Procurement Committee comprising of following Officers for Repair & Maintenance (M&R) of SINDH GOVERNMENT LYARI GENERAL HOSPITAL KARACHI" for the year 2016-17 & 2017-18, is constituted as under;-

- | | |
|--|-------------------|
| 1- Deputy Medical Superintendent,
Sindh Govt. Lyari General Hospital, Karachi | Chairman |
| 2- Sr. RMO General
Sindh Govt. Lyari General Hospital, Karachi | Member/ Secretary |
| 3- Executive Engineer,
Education Works - Karachi | Member |

Function & Responsibilities of the Committee

- Preparing bidding documents;
- Carrying out technical as well as financial evaluation of the bids;
- Preparing evaluation reports as provided in Rule-45;
- Making recommendations for the award of contract to the competent authority; and
- Performing any function ancillary and incidental to the above.

- DR. FAZLULLAH PECHUHO-
SECRETARY
TO GOVT. OF SINDH

No.SO (PM&I) Health. LGHK Procurement 2017

dated 25th - April - 2017

Copy forwarded for information & necessary action to:

1. All Members of Committee.
2. The P.S. to Senior Minister, Health Department, Govt. of Sindh, Karachi.
3. The Additional Secretary (Dev.), Health Department, Government of Sindh, Karachi
4. The P.S to Secretary, Health Department, Govt. of Sindh, Karachi
5. Office Order File


SECTION OFFICER (PM&I)



NO.HD(P&E) 3-2 (427)/2014
GOVERNMENT OF SINDH
HEALTH DEPARTMENT
(Procurement, Monitoring and Inspection Cell)
Karachi dated the 10th APRIL, 2017.

NOTIFICATION

No.HD(P&E)3-2(427)/2014. In supersession to this department's notification of even number dated 9-03-2017 and in pursuance of Rule 31 of the Sindh Public Procurement Rules, 2010, a Departmental Complaint Redressal Committee, comprising of following officers is hereby re-constituted as under to resolve complaints of aggrieved bidders:

- | | |
|---|------------------|
| 1. Special Secretary,
Health Department. | Chairman |
| 2. Representative from Accountant General Sindh, | Member |
| 3. Independent expert from relevant field concerning
(to be nominated by the Head of Procuring Agency) | Member |
| 4. Deputy Secretary (PM&I) | Member |
| 5. Deputy*Secretary (General) | Member/Secretary |

ToRs.

- To perform according to Rule 31 of SPPRA, 2010.
- To Perform any other function ancillary and incidental to the above.

- DR. FAZLULLAH PECHUHO -
SECRETARY TO GOVERNMENT OF Sindh

No.HD(P&E)3-2(427)/2014.

Karachi dated the 10th APRIL, 2017

1. The D.G.Health Services, Sindh, Hyderabad.
2. The District Health Officers (All)
3. Medical Superintendents (All)
4. All the Member of the Committee.
5. The PS to Secretary Health Department, Govt. of Sindh, Karachi.
6. Office order file.


SECTION OFFICER (PM&I)



OFFICE OF THE MEDICAL SUPERINTENDENT
SINDH GOVT. LYARI GENERAL HOSPITAL, KARACHI
(Email: lyarigeneralhospital@gmail.com)



ANNUAL PROCUREMENT PLAN FOR THE FINANCIAL YEAR 2016-17

S.No.	Description of Procurement	Quantity (Where applicable)	Estimated Unit Cost (where applicable)	Estimated Total Cost	Funds Allocated (Rs.) Million	Source of Funds (ADP/Non ADP)	Proposed Procurement Method	Timing of Procurement				Remarks
								1 st Qtr.	2 nd Qtr.	3 rd Qtr.	4 th Qtr.	
01	REPAIR & MAINTENANCE WORKS(M&R) – CIVIL & ELECTRICAL	On need basis	Nil	Nil	83 M	Regular Budget	Competitive Bidding amongst Contractors			To be procured	To be procured	
02	RENOVATION WORKS AT SINDH GOVERNMENT LYARI GENERAL HOSPITAL KARACHI	On need basis	Nil	Nil	76.502M	Regular Budget	Competitive Bidding amongst Contractors			To be procured	To be procured	
03	CONSULTANCY SERVICES FOR CONSTRUCTION SUPERVISION	On need basis	Nil	Nil	3M	Regular Budget	Least Cost Method			To be procured	To be procured	



GOVERNMENT OF SINDH

BILL OF QUANTITIES

**Renovation Works of Sindh Government Lari General
Hospital at Lyari Karachi
Main Building**

BID COST RS.



GOVERNMENT OF SINDH

BILL OF QUANTITIES

**Renovation Works of Sindh Government Lari General
Hospital at Lyari Karachi
Main Building**

BID COST RS.

SUMMARY OF COST

Renovation Works of Sindh Government Lari General Hospital at Lyari Karachi Main Building

S. No.	As per Detail Estimate	Amount
	M/R, Repair & Rehabilitation works at Main Building	
1	Renovation of Dental Department	
2	Renovation of Blood Bank	
3	Renovation of Ojha (TB OPD)	
4	Renovation of X-Ray Department	
5		
6	Renovation of General Store	
7	Renovation of Laundry	
8	Renovation of Sterilization	
9	Renovation of Admin Department	
10	Renovation of Cooridor Dental Deptt:	
11	Renovation of Cooridor Admin Deptt:	
12	Post Operative Recovery Area 2nd Floor	
13	Face Uplifting of Main Building	
14	Psychiatry Department	
	TOTAL MAIN BUILDING	

**RENOVATION OF DENTAL DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
PART-A (CIVIL WORKS)					
1	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	956.75	1043.90	9,988
2	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	378.00	2116.41	8,000
3	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	189.00	902.93	170,654
PART-B					
1	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	117.50	1647.69	193,604
2	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	396.75	30509.77	121,048
PART-C					
1	Supplying & fixing Bath room accessories set (7 pieces i/c. towel rod brush holder soap tray shelf of approved quality and design etc. complete. (S.I-22/19)	Each	2.00	8122.40	16,245
TOTAL					519,539
ADD PREMIUM(BELOW OR ABOVE) _____%					
TOTAL					
(NON-SCH. ITEMS)					

RENOVATION OF DENTAL DEPARTMENT
ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
1	Providing and laying fancy type Porcelain floor and dado tiles 24" x 24" & 1/4" thick as approved size specified approved quality / make / design and colour including laying with bond solution sand mortar including jointing in white cement including washing of tiles and filling of joints with slurry of white cement in desired shape with finishing including cutting of tiles to proper profile i/c. all respect labour and necessary required material as directed by the Engineer Incharge etc. complete.	Sft	845.00		
2	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	3182.50		
3	S/F Fancy door locks as approved quality imported etc. complete.	Each	8.00		
4	P/F false ceiling of gypsum board in panels of required design & size i/c. frame work of aluminum T section hanged with nails, wire to ceiling etc. complete as per directed by the Engineer Incharge. Rates also i/c. all cost of material / labour etc. complete.	St	2938.50		
5	Providing and fixing English commode imported set couple set as approved quality make and design including with matching colour with existing tiles colour including three gallon flushing tank with p Trap and waste pipe including finishing curing etc. complete.	Each	2.00		
6	P/F wash basin approved quality etc. complete in all respect. (Imported).	Each	2.00		
7	S/F Muslim Shower with double bib cock approved quality etc. complete. (Imported make)	Each	2.00		
8	S/F CP brass concealed T-stop cock of superior quality with crystal head 1/2" dia (Master make)	Each	6.00		
9	P/F floor trap jali 6"x6" size double sheeted as approved colour, make & design matching with Existing Ties & fixing with fine finishing and proper slope etc. complete.	Each	4.00		

**RENOVATION OF DENTAL DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
10	S/F Wash Basin Mixture of superior quality with CP head 3/4" dia (Imported make)	Each	2.00		
11	Providing and fixing uPVC pipe including cutting making and jointing with switch pest with special approved quality including all cost of labour as directed by the Engineer Incharge etc. complete.				
	uPVC Pipe 4" dia	Rft	40.00		
	uPVC Pipe 3/4" dia	Rft	60.00		
	uPVC Pipe 1/2" dia	Rft	60.00		
12	Providing and fixing uPVC pipe fiffing imported quality including all cost of labour as directed by the Engineer Incharge etc. complete.				
	4" dia plug tee	Each	2.00		
	4" dia plain bend	Each	2.00		
	4" dia cowel	Each	2.00		
	4" dia y-tee	Each	2.00		
	3/4" dia valve	Each	2.00		
	1/2" dia valve	Each	2.00		
TOTAL OF NON-SCHEDULE					
GRAND TOTAL					

**RENOVATION OF BLOOD BANK
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	1,187.94	1,043.90	12,401
2	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	299.00	2,116.41	6,328
3	Providing and fixing with sunk iron screw wooden Architrave approved design / shape saving with not less than 2-1/2 inches as Directed by Engineer Incharges. (S.I. 60/66)	Rft	259.00	49.97	12,942
4	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	149.50	902.93	134,988
<u>PART-B</u>					
1	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	236.68	30,509.77	72,211
2	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	136.50	1,647.69	224,910
<u>PART-C</u>					

**RENOVATION OF BLOOD BANK
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
1	Supplying & fixing G.I. frames / Chowkats of size 7" x 2" or 4-1/2" x 3" for windows using 20 gauge G.I. Sheet i/c. welded hinges and fixing at site with necessary holds fasts, filing with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c. all carriage, tools and plants used in making and fixing. (S.I-28/93)	Rft	129.50	240.50	31,145
	TOTAL				494,925
	ADD PREMIUM(BELOW OR ABOVE) _____%				
	TOTAL				
	(NON-SCH. ITEMS)				
1	Providing and laying fancy type Porcelain floor and dado tiles 24" x 24" & 1/4" thick as approved size specified approved quality / make / design and colour including laying with bond solution sand mortar including jointing in white cement including washing of tiles and filling of joints with slurry of white cement in desired shape with finishing including cutting of tiles to proper profile i/c. all respect labour and necessary required material as directed by the Engineer Incharge etc. complete.	Sft	1,187.94		
2	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	2,634.00		
3	S/F Fancy door locks as approved quality imported etc. complete.	Each	6.00		
4	Providing and fixing English commode imported set couple set as approved quality make and design including with matching colour with existing tiles colour including three gallon flushing tank with p Trap and waste pipe including finishing curing etc. complete.	Each	1.00		
5	P/F wash basin approved quality etc. complete in all respect. (Imported).	Each	1.00		
6	S/F Muslim Shower with double bib cock approved quality etc. complete. (Imported make)	Each	1.00		

RENOVATION OF OJHA (TB OPD)
ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Distemp'ring. (b) Two Coat. (S.I-24(b)/54)	%Sft	2,254.20	1,043.90	23,532
3	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	201.00	2,116.41	4,254
4	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	100.50	902.93	90,744
5	Providing and fixing with sunk iron screw wooden Architrave approved design / shape saving with not less than 2-1/2 inches as Directed by Engineer Incharges. (S.I. 60/66)	Rft	411.00	49.97	20,538
<u>PART-B</u>					
1	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	46.00	1,647.69	75,794
2	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I. 60/47)	%Sft	248.50	30,509.77	75,817
<u>PART-C</u>					

RENOVATION OF OJHA (TB OPD)
ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
1	Supplying & fixing G.I. frames / Chowkats of size 7" x 2" or 4-1/2" x 3" for windows using 20 gauge G.I. Sheet i/c. welded hinges and fixing at site with necessary holds fasts, filing with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c. all carriage, tools and plants used in making and fixing. (S.I-28/93)	Rft	205.50	240.50	49,423
	TOTAL				340,102
	ADD PREMIUM(BELOW OR ABOVE) _____%				
	TOTAL				
<u>(NON-SCH. ITEMS)</u>					
1	Providing and laying fancy type Porcelain floor and dado tiles 24" x 24" & 1/4" thick as approved size specified approved quality / make / design and colour including laying with bond solution sand mortar including jointing in white cement including washing of tiles and filling of joints with slurry of white cement in desired shape with finishing including cutting of tiles to proper profile i/c. all respect labour and necessary required material as directed by the Engineer Incharge etc. complete.	Sft	2,254.20		
2	S/F Fancy door locks as approved quality imported etc. complete.	Each	12.00		
3	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	6,132.74		
				TOTAL OF NON-SCHEDULE	
				GRAND TOTAL	

RENOVATION OF X-RAY DEPARTMENT

ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	2429.75	1043.90	25,364
2	Nicking concrete surface. (a) Cement concrete surface. (S.I-17(a)/18)	%Sft	840.50	272.25	2,288
3	Applying floating coat of Hi Bond (Universal) as a bond coat or as an adhesive link between old & fresh concrete or plaster as directed by Engineer Incharge. (S.I-13(i)/52)	%Sft	840.50	1029.05	8,649
4	Cement plaster 1:6 upto 12' height. (b) 1/2" thick (S.I-13(b)/52)	%Sft	840.50	2206.60	18,546
5	Cement Plaster 1:4 upto 12' height. (c) 3/8" thick. (S.I-11(c)/52)	%Sft	840.50	3015.76	25,347
6	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	215.00	902.93	194,130
7	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	430.00	2116.41	9,101
7	Providing and fixing with sunk iron screw wooden Architrave approved design / shape saving with not less than 2-1/2 inches as Directed by Engineer Incharges. (S.I. 60/66)	Rft	370.00	49.97	18,489
8	Providing and fixing deodar wooden wardrobe including boxing with back shelves shutters drawers and brass fitting such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2' x 1' complete as per approved design. (S.I-24/61)	Sft	280.00	2364.63	662,096
<u>PART-B</u>					
1	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	268.00	30509.77	81,766
<u>PART-C</u>					

RENOVATION OF X-RAY DEPARTMENT

ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
1	Supplying & fixing G.I. frames / Chowkats of size 7" x 2" or 4-1/2" x 3" for windows using 20 gauge G.I. Sheet i/c. welded hinges and fixing at site with necessary holds fasts, filing with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c. all carriage, tools and plants used in making and fixing. (S.I-28/93)	Rft	185.00	240.50	44,493
	TOTAL				1,090,269
	ADD PREMIUM(BELOW OR ABOVE) _____%				
	TOTAL				
<u>(NON-SCH. ITEMS)</u>					
1	Providing and laying fancy type Porcelain floor and dado tiles 24" x 24" & 1/4" thick as approved size specified approved quality / make / design and colour including laying with bond solution sand mortar including jointing in white cement including washing of tiles and filling of joints with slurry of white cement in desired shape with finishing including cutting of tiles to proper profile i/c. all respect labour and necessary required material as directed by the Engineer Incharge etc. complete.	Sft	3971.75		
2	S/F Fancy type false of gypsum board size 24" x 24" i/c. making & fixing aluminum T sanction channel patti imported make with fine finishing approved make & design i/c. all cost of labour material & tools and wastage as directed by the Engineer Incharge.	Sft	174.00		
3	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	6209.00		
4	S/F Fancy door locks as approved quality imported etc. complete.	Each	9.00		
5	Providing and fixing English commode imported set couple set as approved quality make and design including with matching colour with existing tiles colour including three gallon flushing tank with p Trap and waste pipe including finishing curing etc. complete.	Each	2.00		
6	P/F wash basin approved quality etc. complete in all respect. (Imported).	Each	2.00		

RENOVATION OF X-RAY DEPARTMENT

ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
7	S/F Muslim Shower with double bib cock approved quality etc. complete. (Imported make)	Each	2.00		
8	S/F CP brass concealed T-stop cock of superior quality with crystal head 1/2" dia (Master make)	Each	6.00		
9	P/F floor trap jali 6"x6" size double sheeted as approved colour, make & design matching with Existing Ties & fixing with fine finishing and proper slope etc.complete.	Each	4.00		
10	S/F Wash Basin Mixture of superior quality with CP head 3/4" dia (Imported make)	Each	2.00		
11	Providing and fixing uPVC pipe including cutting making and jointing with switch pest with special approved quality including all cost of labour as directed by the Engineer Incharge etc. complete.				
	uPVC Pipe 4" dia	Each	40.00		
	uPVC Pipe 3/4" dia	Each	60.00		
	uPVC Pipe 1/2" dia	Each	60.00		
12	Providing and fixing uPVC pipe fiffing imported quality including all cost of labour as directed by the Engineer Incharge etc. complete.				
	4" dia plug tee	Each	2.00		
	4" dia plain bend	Each	2.00		
	4" dia cowel	Each	2.00		
	4" dia y-tee	Each	2.00		
	3/4" dia valve	Each	2.00		
	1/2" dia valve	Each	2.00		
TOTAL OF NON-SCHEDULE					
GRAND TOTAL					

**RENOVATION OF GENERAL STORE
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Dismantling of glazed or encaustic tiles. (S.I-55/13)	%Sft	1764.00	786.50	13,874
2	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	1764.00	1043.90	18,414
3	Nicking concrete surface. (a) Cement concrete surface. (S.I-17(a)/18)	%Sft	882.00	272.25	2,401
4	Applying floating coat of Hi Bond (Universal) as a bond coat or as an adhesive link between old & fresh concrete or plaster as directed by Engineer Incharge. (S.I-13(i)/52)	%Sft	882.00	1029.05	9,076
5	Cement plaster 1:6 upto 12' height. (b) 1/2" thick (S.I-13(b)/52)	%Sft	882.00	2206.60	19,462
6	Cement Plaster 1:4 upto 12' height. (c) 3/8" thick. (S.I-11(c)/52)	%Sft	882.00	3015.76	26,599
7	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	116.43	2116.41	2,464
8	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	116.43	902.93	105,132
9	Providing and fixing with sunk iron screw wooden Architrave approved deisgn / shape saving with not less than 2-1/2 inches as Directed by Engineer Incharges. (S.I. 60/66)	Rft	154.00	49.97	7,695
10	Providing and fixing deodar wooden wardrobe including boxing with back shelves shutters drawers and brass fitting such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2' x 1' complete as per approved design. (S.I-24/61)	Sft	280.00	2364.63	662,096
<u>PART-B</u>					

**RENOVATION OF GENERAL STORE
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
1	Laying white marble flooring fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (a) 3/4" thick flooring. (S.I-28(a)/43)	Sft	1764.00	567.48	1,001,035
2	Providing and fixing 3/8" thick marble tiles of approved quality and colour and shade size 8" x 4" x / 6" x 4" in dado skirting and facing removal / tucking of existing plaster surface etc. Over 1/2" thick base of cement mortar 1:3 setting of tiles in slurry of white cement over mortar base including filling the joints and washing the tiles with white cement slurry, current finishing, cleaning and polishing etc. complete. (i) For New Works (S.I-68(i)/49)	Sft	2304.00	186.04	428,636
3	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	213.68	1647.69	352,078
<u>PART-C</u>					
1	Supplying & fixing G.I. frames / Chowkats of size 7" x 2" or 4-1/2" x 3" for windows using 20 gauge G.I. Sheet i/c. welded hinges and fixing at site with necessary holds fasts, filing with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c. all carriage, tools and plants used in making and fixing. (S.I-28/93)	Rft	77.00	240.50	18,519
TOTAL					2,667,481
ADD PREMIUM(BELOW OR ABOVE) _____%					
TOTAL					
<u>(NON-SCH. ITEMS)</u>					
1	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	915.32		
2	P/F false ceiling of gypsum board in panels of required design & size i/c. frame work of aluminum T section hanged with nails, wire to ceiling etc. complete as per directed by the Engineer Incharge. Rates also i/c. all cost of material / labour etc. complete.	Sft	1764.00		
TOTAL OF NON-SCHEDULE					

**RENOVATION OF GENERAL STORE
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
			GRAND TOTAL		

**RENOVATION OF LAUNDRY
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
PART-A (CIVIL WORKS)					
1	Dismantling of glazed or encaustic tiles. (S.I-55/13)	%Sft	1,265.00	786.50	9,949
2	Dismantling Cement Concrete Plain 1:2:4.(S.I-19(c)/10)	%Cft	229.50	3,327.50	7,637
3	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	1,265.00	1,043.90	13,205
4	Nicking concrete surface. (a) Cement concrete surface. (S.I-17(a)/18)	%Sft	792.00	272.25	2,156
5	Applying floating coat of Hi Bond (Universal) as a bond coat or as an adhesive link between old & fresh concrete or plaster as directed by Engineer Incharge. (S.I-13(i)/52)	%Sft	792.00	1,029.05	8,150
6	Cement plaster 1:6 upto 12' height. (b) 1/2" thick (S.I-13(b)/52)	%Sft	792.00	2,206.60	17,476
7	Cement Plaster 1:4 upto 12' height. (c) 3/8" thick. (S.I-11(c)/52)	%Sft	792.00	3,015.76	23,885
8	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	196.00	2,116.41	4,148
9	Providing & Laying 3" thick topping cement concrete (1:2:4) including Surface finishing and dividing into panels. (d) 3" thick. (S.I-16(d)/42)	%Sft	1,350.00	4,411.82	59,560
10	Providing and fixing bitumen felt paper of 60 Lbs over roof i/c. cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per %Sft as premix inter coats and then laying felt paper with 10% over laps, then applying and spreading hill sand at the rate of 1 Cft for 100 Sft. The cost also i/c. necessary fire material, kerosene oil, wood etc. (S.I-41/38)	Sft	1,350.00	54.70	73,845
11	Providing and fixing with sunk iron screw wooden Architrave approved deisgn / shape saving with not less than 2-1/2 inches as Directed by Engineer Incharges. (S.I. 60/66)	Rft	84.00	49.97	4,197

**RENOVATION OF LAUNDRY
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
12	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	91.11	902.93	82,268
PART-B					
1	Laying white marble flooring fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (a) 3/4" thick flooring. (S.I-28(a)/43)	Sft	1,265.00	567.48	717,862
2	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	394.50	30,509.77	120,361
3	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	120.00	1,647.69	197,723
PART-C					
1	Supplying & fixing G.I. frames / Chowkats of size 7" x 2" or 4-1/2" x 3" for windows using 20 gauge G.I. Sheet i/c. welded hinges and fixing at site with necessary holds fasts, filing with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c. all carriage, tools and plants used in making and fixing. (S.I-28/93)	Rft	42.00	240.50	10,101
TOTAL					1,352,523
ADD PREMIUM(BELOW OR ABOVE) _____%					
TOTAL					
(NON-SCH. ITEMS)					

**RENOVATION OF LAUNDRY
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
1	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	1,237.00		
2	Preparing surface & Painting with weather shield coat approved quality the rate i/c. cost of material labour & cartage etc. complete.	Sft	1,657.00		
TOTAL OF NON-SCHEDULE					
GRAND TOTAL					

**RENOVATION OF STERILIZATION
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Dismantling of glazed or encaustic tiles. (S.I-55/13)	%Sft	1235.25	786.50	9,715
2	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	1235.25	1043.90	12,895
3	Nicking concrete surface. (a) Cement concrete surface. (S.I-17(a)/18)	%Sft	415.13	272.25	1,130
4	Applying floating coat of Hi Bond (Universal) as a bond coat or as an adhesive link between old & fresh concrete or plaster as directed by Engineer Incharge. (S.I-13(i)/52)	%Sft	415.13	1029.05	4,272
5	Cement plaster 1:6 upto 12' height. (b) 1/2" thick (S.I-13(b)/52)	%Sft	415.13	2206.60	9,160
6	Cement Plaster 1:4 upto 12' height. (c) 3/8" thick. (S.I-11(c)/52)	%Sft	415.13	3015.76	12,519
7	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	248.85	2116.41	5,267
8	Providing and fixing with sunk iron screw wooden Architrave approved deisgn / shape saving with not less than 2-1/2 inches as Directed by Engineer Incharges. (S.I. 60/66)	Rft	193.00	49.97	9,644
9	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	124.43	902.93	112,348
<u>PART-B</u>					
1	Laying white marble flooring fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (a) 3/4" thick flooring. (S.I-28(a)/43)	Sft	1235.25	567.48	700,980

**RENOVATION OF STERILIZATION
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
2	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	2127.00	30509.77	648,943
3	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	68.00	1647.69	112,043
<u>PART-C</u>					
1	Supplying & fixing G.I. frames / Chowkats of size 7" x 2" or 4-1/2" x 3" for windows using 20 gauge G.I. Sheet i/c. welded hinges and fixing at site with necessary holds fasts, filing with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c. all carriage, tools and plants used in making and fixing. (S.I-28/93)	Rft	96.50	240.50	23,208
TOTAL					1,662,124
ADD PREMIUM(BELOW OR ABOVE) _____%					
TOTAL					
<u>(NON-SCH. ITEMS)</u>					
1	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	2119.50		
TOTAL OF NON-SCHEDULE					
GRAND TOTAL					

**RENOVATION OF ADMIN DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	5,041.13	1,043.90	52,624
1	Preparing the surface & painting with matt finish paint of approved make to old matt finish surface. 2nd & subsequent coat. (S.I-37(a)(b)/55)	%Sft	14,644.01	1,772.38	259,548
2	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	854.00	2,116.41	18,074
3	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	427.00	902.93	385,551
4	Providing and fixing with sunk iron screw wooden Architrave approved design / shape saving with not less than 2-1/2 inches as Directed by Engineer Incharges. (S.I. 60/66)	Rft	369.00	49.97	18,439
<u>PART-B</u>					
1	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	244.00	1,647.69	402,036
2	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	581.00	30,509.77	177,262
<u>PART-C</u>					

**RENOVATION OF ADMIN DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
1	Supplying & fixing G.I. frames / Chowkats of size 7" x 2" or 4-1/2" x 3" for windows using 20 gauge G.I. Sheet i/c. welded hinges and fixing at site with necessary holds fasts, filing with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c. all carriage, tools and plants used in making and fixing. (S.I-28/93)	Rft	369.00	240.50	88,745
PART-D					
1	Supplying & fixing Bath room accessories set (7 pieces i/c. towel rod brush holder soap tray shelf of approved quality and design etc. complete. (S.I-22/19)	Each	6.00	8,122.40	48,734
TOTAL					1,451,013
ADD PREMIUM(BELOW OR ABOVE) _____%					
TOTAL					
(NON-SCH. ITEMS)					
1	Preparing the surface & painting with matt finish paint of approved make to old matt finish surface. 2nd & subsequent coat.	Sft	14,644.01		
2	Providing and laying fancy type Porcelain floor and dado tiles 24" x 24" & 1/4" thick as approved size specified approved quality / make / design and colour including laying with bond solution sand mortar including jointing in white cement including washing of tiles and filling of joints with slurry of white cement in desired shape with finishing including cutting of tiles to proper profile i/c. all respect labour and necessary required material as directed by the Engineer Incharge etc. complete.	Sft	4,885.63		
3	S/F Fancy door locks as approved quality imported etc. complete.	Each	22.00		
4	P/F false ceiling of gypsum board in panels of required design & size i/c. frame work of aluminum T section hanged with nails, wire to ceiling etc. complete as per directed by the Engineer Incharge. Rates also i/c. all cost of material / labour etc. complete.	Sft	5,041.13		
5	Providing and fixing English commode imported set couple set as approved quality make and design including with matching colour with existing tiles colour including three gallon flushing tank with p Trap and waste pipe including finishing curing etc. complete.	Each	6.00		

CORRIDOR DENTAL DEPARTMENT
ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Dismantling of glazed or encaustic tiles. (S.I-55/13)	%Sft	1,800.00	786.50	14,157
2	Nicking concrete surface. (a) Cement concrete surface. (S.I-17(a)/18)	%Sft	500.00	272.25	1,361
3	Applying floating coat of Hi Bond (Universal) as a bond coat or as an adhesive link between old & fresh concrete or plaster as directed by Engineer Incharge. (S.I-13(i)/52)	%Sft	500.00	1,029.05	5,145
4	Cement plaster 1:6 upto 12' height. (b) 1/2" thick (S.I-13(b)/52)	%Sft	500.00	2,206.60	11,033
5	Cement Plaster 1:4 upto 12' height. (c) 3/8" thick. (S.I-11(c)/52)	%Sft	500.00	3,015.76	15,079
6	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	162.00	902.93	146,275
7	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	783.63	2,116.41	16,585
<u>PART-B</u>					
1	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	859.50	30,509.77	262,231

**CORRIDOR DENTAL DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
2	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	70.00	1,647.69	115,338
	TOTAL				587,204
	ADD PREMIUM(BELOW OR ABOVE) _____%				
	TOTAL				
(NON-SCH. ITEMS)					
1	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	4,468.19		
2	Providing and laying fancy type Porcelain floor and dado tiles 24" x 24" & 1/4" thick as approved size specified approved quality / make / design and colour including laying with bond solution sand mortar including jointing in white cement including washing of tiles and filling of joints with slurry of white cement in desired shape with finishing including cutting of tiles to proper profile i/c. all respect labour and necessary required material as directed by the Engineer Incharge etc. complete.	Sft	1,800.00		
3	P/F false ceiling of gypsum board in panels of required design & size i/c. frame work of aluminum T section hanged with nails, wire to ceiling etc. complete as per directed by the Engineer Incharge. Rates also i/c. all cost of material / labour etc. complete.	Sft	1,800.00		
4	Repairing Collapsible gate by replacing new iron patties, removing, repairing and refinishing the same size (12' x 12') i/c. painting enamel paint two coats of required colour etc. complete.	Each	1.00		
	TOTAL OF NON-SCHEDULE				
	GRAND TOTAL				

**CORRIDOR ADMIN DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Dismantling of glazed or encaustic tiles. (S.I-55/13)	%Sft	1,050.00	786.50	8,258
2	Nicking concrete surface. (a) Cement concrete surface. (S.I-17(a)/18)	%Sft	400.00	272.25	1,089
3	Applying floating coat of Hi Bond (Universal) as a bond coat or as an adhesive link between old & fresh concrete or plaster as directed by Engineer Incharge. (S.I-13(i)/52)	%Sft	400.00	1,029.05	4,116
4	Cement plaster 1:6 upto 12' height. (b) 1/2" thick (S.I-13(b)/52)	%Sft	400.00	2,206.60	8,826
5	Cement Plaster 1:4 upto 12' height. (c) 3/8" thick. (S.I-11(c)/52)	%Sft	400.00	3,015.76	12,063
6	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	240.30	902.93	216,977
7	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	480.61	2,116.41	10,172
<u>PART-B</u>					
1	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	630.00	30,509.77	192,212

**CORRIDOR ADMIN DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
2	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	60.50	1,647.69	99,685
	TOTAL				553,398
	ADD PREMIUM(BELOW OR ABOVE) _____%				
	TOTAL				
(NON-SCH. ITEMS)					
1	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	2,835.00		
2	Providing and laying fancy type Porcelain floor and dado tiles 24" x 24" & 1/4" thick as approved size specified approved quality / make / design and colour including laying with bond solution sand mortar including jointing in white cement including washing of tiles and filling of joints with slurry of white cement in desired shape with finishing including cutting of tiles to proper profile i/c. all respect labour and necessary required material as directed by the Engineer Incharge etc. complete.	Sft	1,050.00		
3	P/F false ceiling of gypsum board in panels of required design & size i/c. frame work of aluminum T section hanged with nails, wire to ceiling etc. complete as per directed by the Engineer Incharge. Rates also i/c. all cost of material / labour etc. complete.	Sft	1,050.00		
4	S/F Fancy door locks as approved quality imported etc. complete.	Each	9.00		
5	Repairing Collapsible gate by replacing new iron patties, removing, repairing and refinishing the same size (12' x 12') i/c. painting enamel paint two coats of required colour etc. complete.	Each	2.00		
	TOTAL OF NON-SCHEDULE				
	GRAND TOTAL				

POST RECOVERY AREA (2ND FLOOR)
ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Dismantling of glazed or encaustic tiles. (S.I-55/13)	%Sft	726.00	786.50	5,710
2	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	240.00	1,043.90	2,505
3	Painting old surfaces. (c) Painting doors and windows any type (i) First Coat. (S.I-4(c)(i)/68)	%Sft	84.00	657.91	553
<u>PART-B</u>					
1	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	726.00	30,509.77	221,501
TOTAL					230,269
ADD PREMIUM(BELOW OR ABOVE) _____%					
TOTAL					
<u>(NON-SCH. ITEMS)</u>					
1	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	484.00		
TOTAL OF NON-SCHEDULE					
GRAND TOTAL					

**FACE UPLIFTING OF MAIN BUILDING
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
	<u>(NON-SCH. ITEMS)</u>				
1	Supply of Prime Aluminum / Chawla Aluminum / Lucky Aluminum / Krudsons Aluminum Sliver anodized curtain wall section, size 75mm x 50mm in 2mm thickness with Fischer / Rawlplug bolts anchoring, Silicon sealant Dow Corning USA gasket rubber including necessary hardware, accessories, transportation and complete in all respect. Labour include fabrication, installation of curtain wall.	Sft	14292.00		
	TOTAL OF NON-SCHEDULE				

**PSYCHIATRY DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Distempering. (b) Two Coat. (S.I-24(b)/54)	%Sft	4,330.43	1,043.90	45,205
2	Painting New Surfaces. (c) Preparing surface and painting of doors and windows any types. (including edges). (i) Priming Coat (ii) Each subsequent coat of paint. (Three Coat) (S.I-5(c)(i,ii)/70)	%Sft	674.00	2,116.41	14,265
3	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	337.00	902.93	304,287
4	Providing and fixing with sunk iron screw wooden Architrave approved deisgn / shape saving with not less than 2-1/2 inches as Directed by Engineer Incharges. (S.I. 60/66)	Rft	496.00	49.97	24,785
<u>PART-B</u>					
1	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c. handles stoppers & locking arrangement etc. complete. (a) Deluxe Model (Bronze). (S.I-84(b)/108)	Sft	244.00	1,647.69	402,036
2	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of Stile specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (S.I-60/47)	%Sft	665.50	30,509.77	203,043
<u>PART-C</u>					

**PSYCIATRY DEPARTMENT
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
1	Supplying & fixing G.I. frames / Chowkats of size 7" x 2" or 4-1/2" x 3" for windows using 20 gauge G.I. Sheet i/c. welded hinges and fixing at site with necessary holds fasts, filing with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c. all carriage, tools and plants used in making and fixing. (S.I-28/93)	Rft	248.00	240.50	59,644
	TOTAL				1,053,265
	ADD PREMIUM(BELOW OR ABOVE) _____%				
	TOTAL				
(NON-SCH. ITEMS)					
1	Repairing old surface & painting with Matt Finish i/c. filling of joints and cracks with fine finishing including all respect labour, as directed by the Engineer Incharge etc. complete.	Sft	7,406.76		
2	Providing and laying fancy type Porcelain floor and dado tiles 24" x 24" & 1/4" thick as approved size specified approved quality / make / design and colour including laying with bond solution sand mortar including jointing in white cement including washing of tiles and filling of joints with slurry of white cement in desired shape with finishing including cutting of tiles to proper profile i/c. all respect labour and necessary required material as directed by the Engineer Incharge etc. complete.	Sft	4,074.43		
3	S/F Fancy door locks as approved quality imported etc. complete.	Each	14.00		
4	P/F false ceiling of gypsum board in panels of required design & size i/c. frame work of aluminum T section hanged with nails, wire to ceiling etc. complete as per directed by the Engineer Incharge. Rates also i/c. all cost of material / labour etc. complete.	St	4,330.43		
					TOTAL OF NON-SCHEDULE
					GRAND TOTAL



GOVERNMENT OF SINDH

BILL OF QUANTITIES

**Renovation Works of Sindh Government Lari General
Hospital at Lyari Karachi
OPD AND CARDIOLOGY DEPT**

BID COST RS.

SUMMARY OF COST

Renovation Works of Sindh Government Lari General Hospital at Lyari Karachi OPD AND CARDIOLOGY DEPT

S. No.	As per Detail Estimate	Amount
	<p>M/R, Repair & Rehabilitation works of Cardiology & OPD Blocks</p> <p>Cardiology & OPD Department</p> <p style="text-align: right;">GRAND TOTAL</p>	

#REF!
ABSTRACT OF COST

S.No	Description	Unit	Quantity	Rate	Amount
SCHEDULE ITEMS					
1	Nicking concrete surface. (a) Cement concrete surface. (S.I-17(a)/18)	%Sft	8,479.74	272.25	23,086
2	Providing & Laying 2" thick topping cement concrete (1:2:4) including Surface finishing and dividing into panels. (S.I-16(c)/42)	%Sft	16,959.49	3,275.50	555,508
TOTAL					578,594
ADD PREMIUM(BELOW OR ABOVE) _____%					
TOTAL					
NON- SCHEDULE ITEMS					
1	Providing and laying rubber lining 2mm thick in flooring. Self adhesive type lining to be installed as per fixing drawing details.	Sft	16,959.49		
2	P/Making graphic auto paint top wall surface to provide durable & asethic surface having thickness between 1.6 x 2.0mm in specified colour / shape & working at height of 50" using scaffolding as directed by Engineer Incharge.	Sft	3,265.60		
TOTAL					
GRAND TOTAL					



GOVERNMENT OF SINDH

BILL OF QUANTITIES

**Renovation Works of Sindh Government Lari General
Hospital at Lyari Karachi
ELECTRICAL WORKS**

BID COST RS.

SUMMARY OF COST

Renovation Works of Sindh Government Lari General Hospital at Lyari

S. No.	As per Detail Estimate	Amount
	M/R, Repair & Rehabilitation works at Main Building (Electrical Works)	
1	Electrical Work of Different Department	
	GRAND TOTAL	

Electrical Work of Different Department

ABSTRACT OF COST

S.#	Description	Unit	Qty	Rate	Amount
1	<u>Point/Circuit Wiring</u>				
1)a	Point Wiring for Fan / Light or bell complete with 3x2.5mm ² PVC / PVC cable in 3/4" PVC pipe / conduit to be recessed in wall/column and ceiling with specials complete as required.	No.	20.00		
1)b	Rewiring for Fan / Light or bell complete with 3x2.5mm ² PVC / PVC cable in 3/4" PVC pipe / conduit to be recessed in wall/column and ceiling with specials complete as required.	No.	413.00		
2	Same as Item No.1 but point to point.	No.	100.00		
3	Circuit wiring with 2x4mm ² PVC/PVC cable with 1x2.5mm ² PVC/PVC cable (ECC) in PVC conduit 3/4" dia PVC pipe Conduit to be recessed in the wall/column with special complete as required (from sub DB to switch board)	No.	100.00		
4)a	Point wiring for light plug or power plugs with 2x4mm ² PVC/PVC cable to energise set of light or power plugs (03 no in a row) in 18 mm ² PVC conduit with specials complete as required. (from switch board to bed)	No.	20.00		
4)b	Re wiring for light plug or power plugs with 2x4mm ² PVC/PVC cable to energise set of light or power plugs (03 no in a row) in 18 mm ² PVC conduit with specials complete as required. (from switch board to bed)	No.	100.00		
5	Wiring for AC/Split unit with 2x10mm ² + 1x2.5 (ECC) PVC/PVC cable in 2.5mm ² pvc conduit and special complete in required.	No.	20.00		
6	Switches/sockets/lights or power plugs P/F of following accessories for different purposes to be used in hospital wards as per following specification				
	i) switch one gauge	No.	40.00		
	ii) switch two gauge	No.	40.00		
	iii)switch three gauge	No.	40.00		

S.#	Description	Unit	Qty	Rate	Amount
	iv)switch four gauge	No.	40.00		
	v)switch five gauge	No.	40.00		
	vi)switch six gauge with two fans dimers	No.	200.00		
	vii) fan dimers	No.	400.00		
	viii) five pin/ multiple pins plugs 15 ampere with ms back box	No.	400.00		
	ix) three pin plugs 20 ampere with ms back box	No.	100.00		
7	<u>LAPS / FITTING FIXTURES / FAN / HOLDERS:</u>				
	P/F of Electrical accessories as per following need requirement and specification.				
	A) MS back box suitable for				
	a) 01 Light Plug	No.	40.00		
	b) 02 Light Plug	No.	40.00		
	c) 03 Light Plug	No.	40.00		
	d) 01 power plug	No.	40.00		
	e) 02 power plug	No.	41.00		
	f) 03 power plug	No.	41.00		
	g) Backlite holder thread type	No.	400.00		
	h) Fan 56" with rod and clamps	No.	120.00		
	i) Exhaust Fan 18" (Plastic) with starter	No.	20.00		
	j) Exhaust Fan 18" (Metal)	No.	20.00		
	k) Fan hook in MS back box	No.	20.00		
	l) Ceiling rose with cover plate	No.	400.00		
	m) PVC back box with cover plate to be used as cable pull box.	No.	40.00		
	n) Energy saver lamps 9W thread type	No.	200.00		
	o) Energy saver lamps 24W thread type	No.	200.00		
	p) Energy saver lamps 35W thread type	No.	200.00		
	q) Steel chain with clamp to be fixed on roof with down lighter shed poly carbonate.	No.	20.00		
	r) Call bell multi tone best quality	No.	10.00		
	s) Flood security light 250 W	No.	6.00		
	t) Flood security light 400 W	No.	6.00		
8	<u>DISTRIBUTION BOARDS/SUB D.B / DISTRIBUTION PANEL / MAIN D.B</u>				
	i) P/F of MS powder coated ward or room DB as first protection				
	provision as per following need, requiriment and components				
	.- MCB 20 Amp 01				
	.- MCB, 3-10 Amp (one spare) 05				
	.- MCB 6-10 Amp (one spare) 05				
	.- Internal wiring with 6mm2 S/C cable				
	.- PVC cable extension joint 18/25mm2				

S.#	Description	Unit	Qty	Rate	Amount
	.- Wall mounted type with door and locking arrangements complete as required.	No.	40.00		
ii)	P/F of MS powder coated board for corridor / floor wise as per following need, requirement and components. .- MCB TP 100 Amp 1 KA-- 01 .- MCCB TP 50 Amp 8 KA -- 06 .- MCCB TP 30 Amp 8 KA -- 06 .- MCB 3-10 Amp 6 KA -- 04 .- Internal wiring with S/C 10mm cable .- PVC cable extension joint 18/25mm2 .- Wall mounted type with door and locking arrangements complete as required.	No.	3.00		
iii)	Same as Item No.8(ii) but as per following need, requirement and components .- MCC TP 150 Amp 10 KA-- 01 .- MCCB TP 100 Amp (one spare)-- 04 .- Copper bus bar 150 Amp -- 04 .- Earth / Neutral Terminal .- Internal wiring with S/C 16mm2 cable .- PVC cable extension joint 18/25mm2 .- Wall mounted type with door and locking arrangements complete as required.	No.	3.00		
iv)	P/F of Main Distribution frame for Building and Main feeder complete as per following components and specifications. .- MCC TP 600 Amp 25 KA --01 .- MCCB TP 150 Amp 18 KA-- 01 .- Copper bus bar 250 Amp -- 04 .- Earth / Neutral Terminal .- Internal wiring with S/C 95mm2 cable .- PVC cable extension joint 18/25mm2 .- Wall mounted type with door and locking arrangements complete as required.	No.	2.00		
9	<u>CABLE / TRENCHES / EXCAVATION / MAIN HOLE:</u>				
i)	P/L LT cable to be used as feeders as per following specification: a) 4/C cable 50mm2 PVC/PVC b) 4/C cable 25mm2 PVC/PVC c) 4/C cable 16mm2 PVC/PVC d) 4/C cable 10mm2 PVC/PVC	Mtr	225.00		
		Mtr	225.00		
		Mtr	400.00		
		Mtr	400.00		
ii)	Construction of Main hole with MS Cover plate as per following specification. .- 12"x12"x24" .- Block Messery duly plastered .- Provision of IN and OUT going.	No.	4.00		

S.#	Description	Unit	Qty	Rate	Amount
10	Excavation and backfilling 1x1x3	Cft	3,000.00		
11	<u>SPLIT UNITS:</u> P/F of Split Unit 24000 BTU complete with piping Kit, frame wiring 3x10mm2 with power circuit breaker complete as required.	No.	20.00		
12	<u>PVC/ G1 / RCC PIPE</u> P/L PVC / G1 / RCC pipe to cross cable underground / floor to floor with bend sockets etc as specials as per following specifications.				
	i)PVC pipe 1"	Mtr.	80.00		
	ii) PVC pipe 2"	Mtr.	80.00		
	iii)PVC pipe 4"	Mtr.	100.00		
	iv)G.I pipe 2"	Mtr.	50.00		
	v) G.I pipe 4"	Mtr.	50.00		
			TOTAL		



GOVERNMENT OF SINDH

BILL OF QUANTITIES

**Renovation Works of Sindh Government Lari General
Hospital at Lyari Karachi
External Development & Sewerage System up
gradation**

BID COST RS.

-

SUMMARY OF OST

Renovation Works of Sindh Government Lari General Hospital at Lyari Karachi External Development & Sewerage System up gradation

S. No.	Description	Amount
	M/R, External Development & Sewerage System up gradation	
1	Hard Land Scaping & Sewerage Work	
2	Repair / Construction of Boundary Wall	
	GRAND TOTAL	

**HARD LAND SCAPING
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
(NON-SCH. ITEMS)					
1	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape with natural colours, having strength b/w. 5000 psi to 8500 psi i/c. filling the joints with hill sand and laying in specified manner / pattern and design etc. complete. (S.I-71/49)	Sft	37,338.00		
2	Making & fixing cement concrete benches with music, approved colour & design i/c. making foundation etc. complete.	Each	20.00		
3	Removing Earth upto 6" with i/c. disposal of debries from site of work to out side KMC / Cantonment area etc. complete.	Sft	5,568.00		
4	Providing and spreading sweet earth from approved quarry & spreading in layers etc. complete. (6" inch thick)	Sft	5,568.00		
5	Providing and spreading garden manure from approved place or Kda / KMC & spreading over sweet earth in layers etc. complete.	Sft	5,568.00		
6	Providing and planting Dacca grass from approved nursery & watering upto 1st grow etc. complete.	Sft	5,568.00		
7	Supply of Prime Aluminum / Chawla Aluminum / Lucky Aluminum / Krudsons Aluminum Sliver anodized curtain wall section, size 75mm x 50mm in 2mm thickness with Fischer / Rawlplug bolts anchoring, Silicon sealant Dow Corning USA gasket rubber including necessary hardware, accessories, transportation and complete in all respect. Labour include fabrication, installation of curtain wall.	Sft	12,928.00		
TOTAL OF NON-SCH. ITEM					

**REPAIR / CONSTRUCTION OF BOUNDARY WALL
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
<u>PART-A (CIVIL WORKS)</u>					
1	Excavation in foundation of buildings bridges and other structure including dagbelling dressing refilling around structure with excavated earth watering and ramming lead upto 5'ft (b) in Ordinary Soil. (S.I. No. 4(b)/18)	%Cft	593.00	3,176.25	1,884
2	Cement Concrete brick or stone ballast 1-1/2" to 2" guage. Ratio 1:4:8 (S.I-4(b)/15)	%Cft	186.00	9,416.28	17,514
3	Reinforced Cement Concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle.(a) R.C. work in roof slab beams columns rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects.i) Ratio (1:2:4) 90 Lbs cement 2 Cft Sand 4 Cft Shingle 1/8" to 1/4" gauge. (S.I-6(a)(i)/16-17)	Cft	269.16	337.00	90,707
4	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust.) Using Tor Bars. (S.I-8(a)(b)/17)	Cwt	10.40	5,001.70	52,016
5	Providing and laying 1:3:6 Cement concrete solid Block Masonry wall above 6" and below in thickness set in 1:6 cement mortar in ground floor Super Structure including raking out joints & curring etc. complete. (S.I-24/19)	%Cft	343.00	15,771.01	54,095
6	Cement Plaster 1:4 upto 12' height. (d) 3/4" thick (only for block masonry). (S.I-11(d)/52)	%Sft	1,372.00	3,191.76	43,791
7	Distempering. (c) Three Coat. (S.I-24(c)/54)	%Sft	1,603.00	1,079.65	17,307
TOTAL OF PART-A					277,314
<u>PART-B (CIVIL WORKS)</u>					
<u>OLD WALL (FRONT)</u>					

**REPAIR / CONSTRUCTION OF BOUNDARY WALL
ABSTRACT OF COST**

S.No	Description	Unit	Quantity	Rate	Amount
1	Applying floating coat of Hi Bond (Universal) as a bond coat or as an adhesive link between old & fresh concrete or plaster as directed by Engineer Incharge. (S.I-13(i)/52)	%Sft	10,804.00	1,029.05	111,179
2	Cement Plaster 1:4 upto 12' height. (d) 3/4" thick (only for block masonry). (S.I-11(d)/52)	%Sft	10,804.00	3,191.76	344,838
3	P/Making graphic auto paint top wall surface to provide durable & asethic surface having thickness between 1.6 x 2.0mm in specified colour / shape & working at height of 50" using scaffolding as directed by Engineer Incharge.	Sft	18,907.00	45.00	850,815
4	Providing and fixing angle iron 1-1/2 x 1-1/2" by 1/4" thick including making cuts, for fixing bar bid wire and painting enamel paint three coats fixed in existing wall with cement mortar 1:2 curing and finishing etc. complete (length 4').	Each	135.00	2,500.00	337,500
5	Providing and fixing bar bid wire in angle iron post horizontal and vertical approved quality etc. complete.	Rft	4,624.00	45.00	208,080
6	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering. Ratio 1:3:6 (S.I-5(h)/16)	%Cft	4,624.00	12,595.00	582,393
7	Erection and removal of centering for RCC or plain cement concrete works of Deodar Wood (2nd Class). For Partal Wood. (b)(i) Horizontal Floor. (S.I-19b(i)/18)	%Sft	4,624.00	3,588.48	165,931
TOTAL OF PART-B					2,600,736
GRAND TOTAL					2,878,050
ADD PREMIUM(BELOW OR ABOVE) _____%					
TOTAL					