

OFFICE OF THE EXECUTIVE ENGINEER  
KARACHI DIVISION CIVIL-I, KW&SB

B.O.Q.


SUBJECT: EMERGENT REPAIR OF LEAKAGES ON 48" PRCC PIPE TRUNK MAIN  
PIPE AT AMIR KHUSRO ROAD OR INFRONT OF PIPE PAGARA HOUSE  
NEAR H.S.R. STAFF COLONY MAIN KARSANZ ROAD.

| ITEM NO.            | DESCRIPTION OF ITEMS  | QTY   | RATE |        | PER   | AMOUNT |
|---------------------|---|-------|------|--------|-------|--------|
|                     |   |       | Word | Figure |       |        |
| Item No. 1          | Leakages on 48" dia PRCC Pipe Trunk Main line (External Vatta) i/c Excavation, de-watering, sealing material, labour back filling etc.  | 08    |      |        | Each  |        |
| Item No. 2          | Deduction of refilling the excavated stuff in trench 6" layers i/c watering, ramming to full compaction etc complete.   | -5292 |      |        | 0%Cft |        |
| Item No. 3          | Preparing sub base by supplying and spreading well graded pits or bed run gravel having a liquid limit of greater than 25 and plasticity index not greater than 6" proper chamber and grade i/c watering, rolling and compacting in layers thickness of each compacted layer not exceeding 6" compaction upto 98-100% density as per modified AASHO density / rate i/c all cost of material T&P and carriage upto 3 chain. Quantity as per item No.2 to 8 | 5292  |      |        | %Cft  |        |
| Item No.4           | Internal repair of leaking joint on 48" dia PRCC Water Trunk Main Pipe  | 25    |      |        | Each  |        |
| Total Rs.           |   |       |      |        |       |        |
| Amount in words ( ) |   |       |      |        |       |        |

I / We hereby quoted the cost of Rs. \_\_\_\_\_  
for execution of the above work and I / We hereby undertaking  
to accept all clauses of SPPR, 2010.

Signature of Contractor  
with Name of Firm & Seal

Address : \_\_\_\_\_  
\_\_\_\_\_

  
Executive Engineer,  
(KDC-I), KWSB.

Contact # \_\_\_\_\_