

OFFICE OF THE EXECUTIVE ENGINEER
KARACHI DIVISION CIVIL-I, KW&SB

B.O.Q.

SUBJECT: REPAIR & MAINTENANCE OF 24" DIA VERTICAL SLUICE VALVE AT
COD FILTER PLANT AND INTERNAL LEAKAGES ON 54" DIA PRCC
WATER TRUNK MAIN PIPE AT COD FILTER PLANT...

ITEM NO.	<u>DESCRIPTION OF ITEMS</u>	QTY	RATE		PER	AMOUNT
			Word	Figure		
Item 1	Dismantling of RCC Slab	60			%Cft	
Item 2	Dismantling of CC Walls	512			%Cft	
Item 3	Dismantling of CC floor	128			%Cft	
Item 4	Dismantling of CC 1:4:8	121			%Cft	
Item 5	M.Supply of following mechanical parts as per sample.					
a)	Brass metal main spindle from 4.5" dia i/c cutting threads 60 Nos. i/c making color complete.	02			Each	
b)	Brass Metal Gutka nut	02			Each	
c)	M.S. Crown Wheel 54 teeth	02			Each	
d)	Pinion 14 teeth	02			Each	
e)	Brass metal spindle 14" long	02			Each	
f)	Nuts & bolts 1.5" x 8" long	60			Each	
	Nuts & bolts 1.5" to 6" long	30			Each	
g)	Rubber packing	112			P/Sft	
Item 6	Supply of labours for opening of valves head removing of seat, spindle & other parts etc.					
a)	Machine Fitter	08			Each	
b)	Helper	08			Each	