

OFFICE OF THE EXECUTIVE ENGINEER
KARACHI DIVISION CIVIL-I, KW&SB

B.O.Q.

SUBJECT: **EMERGENT REPAIR OF LEAKAGES ON 36" DIA M.S. PIPE INTERCONNECTION OF K-III RISING MAIN AT N.E.K. & 48" DIA / LEAKAGES ON PRCC PIPE.**

ITEM NO.	DESCRIPTION OF ITEMS	QTY	RATE		PER	AMOUNT
			Word	Figure		
Item No.1	Excavation for pipe line in trenches & pits in wet soil of murum i/c trimming & dressing sides to true alignment & shape, leveling of bed of trenches to concrete level and grade, cutting joints holes & disposal of surplus earth within one chain as directed by Engineer Incharge. Providing fence guard, light, flags & temporary crossing for non-vehicular traffic where ever required lift upto 5 ft (1.52m) & lead upto one chain (30.5 m)	1200			%0Cft	
Item No.2	Add for additional lift of every three 3 feet (5-8)	559.35			%0Cft	
Item No.3	Add for additional lift of every three feet (8-11)	308.70			%0Cft	
Item No.4	Full hire charges of pumping set per day inclusive of wages of driver and assistant fuel and electric energy plate form required for placing pumps etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges of pumping sets of upto 10 HP pumping out water from 10 ft deep trench.	40			P/Day	
Item No.5	Gas cutter for removing of rusted / corroded M.S. Pipe.	06			P/Day	
Item No.6	Welding plant	48			P/ Hour	
Item No.7	Welder 1 st Class	06			P/Day	
Item No.8	Fabricator	06			P/Day	
Item No.9	Beldar	18			P/Day	
Item No.10	Welding Rod	500			Each	
Item No.11	M.S. Plate	61.57			P/Kg.	