

# ABSTRACT OF COST

NAME OF WORK: Replacement of New Water Supply Line Double story 9<sup>th</sup> Mile  
Karsang.

Item No	Description	Quantity	Rate	Unit	Amount
1-	Excavation for Pipe line in trenches & pits all kind of material i.e. trimming & dressing sides to true alignment & shape leveling of bed of trenches to correct level & grade, cutting joint holes & disposal of surplus earths within in a one chain as directed by Engineer in charge Providing fence guards, lights, flags & Temporary Crossing for non-vehicular traffic where ever required lift upto 5ft (1-5.2m) & lead upto one chain (30-5m)	8000-00	4650-00	% off.	37200-00
2-	Excavation for Pipe line in trenches & pits in hard rock by hammering & chiselling i.e. trimming & dressing side to true alignment & shape leveling of beds of trenches to correct level & grade, cutting joint holes & disposal of surplus earths within in a one chain as directed by Engineer in charge Providing fence guards, light, flags & Temporary Crossing for non-vehicular traffic where ever required lift upto 5ft (1-5.2m) & lead upto one chain (30-5m)	5600-00	24150-00	% off.	135240-00
3-	Pipe & fitting in trenches i.e. fitting, joining & testing etc. complete in all respect the high density Polyethylene PE Pipes (HDPE-100) for water Confining ISO 4427 / Din 8075 / 8075 BS 3580 & PSI 3051 PN-10 (10mm) dia.	1700-00	268-00	% off.	455600-00

628040

455600