



OFFICE OF THE DISTRICT COUNCIL KARACHI, BIN QASIM ZONE.

Near Police Training Center, Main National Highway Razzakabad³

Tel:0213-4100461/0213-4127551

No.DCK/DE/BQ.Z/ 26 /2017/

Dated: 27 / 07 /2017.

TENDER NOTICE

The Tender is sealed covers are invited for the following work under SPPRA Rules-2010 from the firms having adequate experience in the relevant field. The tentative cost of work is under Rs: 1.00 Million

S#	Name of Work	Amount	Earnest Money	Time Allowed	Tender Fee Non Refundable
1.	POVIDING AND LAYING WATER SUPPLY LINE AT DARYA KHAN JOKHIO GOTH UC- GHAGGAR DISTRICT COUNCIL KARACHI	998000	20000	03 Month	1000
2.	PROVIDING AND LAYING WATER SUPPLY LINE AT PEER SARHANDI GOTH & UNDERGROUND TANSK AT RAMZAN MUHALLAH UC- KOTIARO DCK	903435	18100	03 Month	1000
3.	POVIDING AND LAYING WATER SUPPLY LINE AT ABDUL REHMAN JOKHIO GOTH UC- KOTEARO DISTRICT COUNCIL KARACHI	827500	16500	03 Month	1000
4.	POVIDING AND LAYING WATER SUPPLY LINE AT MOLAI BASTI, ALLAH BUX HIMAITTI GOTH & NASEER ABAD UC- PIPRI DISTRICT COUNCIL KARACHI	660000	13200	03 Month	1000
5.	REPAIR AND MAINTENACE OF METALLED ROAD AT RANJERS HEAD QUARTER UC- CHAND PARO DISTRICT COUNCIL KARACHI	999989	20000	03 Month	1000

Tender Processing Schedule shall be as follows:-

1-Receiving of Applications & Issuance of Tenders	31-07-2017 To 14-08-2017 During office Hours	District Engineer, District Council Karachi
2-Dropping of Tenders	15-08-2017 1:00 PM	In the office of the District Engineer, District Council Karachi
3-Opening of Tenders	15-08-2017 2:00 PM	Tender opening Committee in the office of District Engineer, District Council Karachi

Terms & Conditions:

- The Tender Document will be issued to the Contractors on the submission of written request on their letterhead and on payment of non-refundable cost of tender price through pay order from any scheduled bank in favors of District Council, Karachi as mentioned above each work.
- In case of any reason beyond our control, if the tenders are not responded on the above date, the next date of submission & opening of Tenders will be 31-08-2017 at 12:00 pm and the tender documents will be available for sale from 16-08-2017 To 30-08-2017.
- In case the date of opening is declared as a public holiday by the government, the next official working day shall be deemed to the date for submission and opening of tenders of the same time as mentioned.
- Registration with income tax Department (NTN Copy) and Sindh Revenue Board.
- Documentary of work equivalent cost or above executed in last 3 years & Certificate of satisfactory completion showing date of start & completion from employer.
- List of machinery & equipment available with documentary proof of its ownership
- 2% of specified amount against each work in shape of Pay Order/Bank draft in favor of District Council, Karachi shall be attached with the tender documents.
- Tenders in unsealed covers / without 2% Earnest Money will not be entertained and discarded.
- The single envelop procedure adopted for tender work as per S.P.P.R.A Rules-2010.
- The total bid amount as well as the rates of items must be filled both in figure and words and incase any correction is made by the contractor himself then each correction must be initiated by the contractor otherwise the tenders are liable to be summarily rejected.
- If any fake documents are found then the tender is liable to be rejected-cancelled without any compensation but penalty as per rules.
- Tenders can be seen/download on Authority's web sites S.P.P.R.A www.sppra.sindh.gov.pk.
- The procuring agency may reject all or any bid subject to the relevant provision of S.P.P.R.A Rules-2010.


DISTRICT ENGINEER
DISTRICT COUNCIL KARACHI

DISTRICT ENGINEER
DISTRICT COUNCIL KARACHI

DIRECTOR (CB) S.P.P.R.A, GOS.

With a request to upload on the website of S.P.P.R.A (Authority) .A Soft copy is also enclosed.

Copy to:

- The Chief Officer District Council Karachi
- The Executive Engineer, Bin Qasim Zone DCK Karachi.
- The Accounts Officer DCK Karachi.A
- P.S. to Managing Director, S.P.P.R.A

SPPRA INWARD DIARY
NO: 503
DATED: 28-07-2017



DISTRICT COUNCIL, KARACHI

(BIN QASIM ZONE) ANNUAL PROCUREMENT PLAN (WORKS, GOODS & SERVICES) FINANCIAL YEAR 2017-2018

S.	Description of procurement	Allocated funds	Cost of ongoing works (Expenditure already incurred)	Funds earmarked for ongoing works	Cost of new work (Components)	Funds for new works (c-e)	Nature of Procurement	Method of procurement	Anticipated / Actual Date of Advertisement	Anticipated / Actual Date of Start	Anticipated / Actual Date of completion
1.	POVIDING AND LAYING WATER SUPPLY LINE AT DARYA KHAN JOKHIO GOTH UC-GHAGGAR DISTRICT COUNCIL KARACHI	998000	----	-----	998000	998000	Works and Services	SPPRA Rule 15 (b) & 16	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
2.	PROVIDING AND LAYING WATER SUPPLY LINE AT PEER SARHANDI GOTH & UNDERGROUND TANSK AT RAMZAN MUHALLAH UC-KOTIARO DCK	903435	----	-----	903435	903435	Works and Services	SPPRA Rule 15 (b) & 16	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
3.	POVIDING AND LAYING WATER SUPPLY LINE AT ABDUL REHMAN JOKHIO GOTH UC-KOTEARO DISTRICT COUNCIL KARACHI	827500	----	-----	827500	827500	Works and Services	SPPRA Rule 15 (b) & 16	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
4.	POVIDING AND LAYING WATER SUPPLY LINE AT MOLAI BASTI, ALLAH BUX HIMAITTI GOTH & NASEER ABAD UC- PIPRI DISTRICT COUNCIL KARACHI	660000	----	-----	660000	660000	Works and Services	SPPRA Rule 15 (b) & 16	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
5.	REPAIR AND MAINTENACE OF METALLED ROAD AT RANJERS HEAD QUARTER UC- CHAND PARO DISTRICT COUNCIL KARACHI	999989	----	-----	999989	999989	Works and Services	SPPRA Rule 15 (b) & 16	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE


EXECUTIVE ENGINEER
DISTRICT COUNCIL KARACHI


DISTRICT ENGINEER
DISTRICT COUNCIL, KARACHI

NAME OF WORK: - PROVIDING AND LAYING WATER SUPPLY LINE AT DARYA KHAN GOTH
UC- CHNAD PARO DISTRICT COUNCIL KARACHIBILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	13125.0Cft	Excavation for pipe line and trenches and pits in soft rock by hammering and chiseling where blast not applicable including trimming and dressing side to true alignment and shape leveling of beds of trenches to correct level and grade cutting joint hole and disposal of surplus earth with in one chain as directed by engineer guards light flags and temporary crossing for non vehicular traffic where ever require lift upto 5ft (1.52m) and lead up to one chain (30.5mm) (PHED Sch P-47 Item 6)	Rs.10770.00	%Ocft	Rs:141356.00
2.	3000.0Rft	Providing, laying & fixing in trench i/c fitting, jointing & testing etc complete in all respect the high Density polyethylene pipes (HDDE-100) for W/S conforming ISO 4427 / DIN 8071/8075 B.S 3580 & PSI 3051.(PN.8)(RA) 3"Dia	Rs:250.20	P.Rft	Rs:750600.00
3.	11812.0Cft	Refilling the excavated stuff in trenches 6" thick layers i/c watering, ramming to full compaction etc...complete	Rs.2760.00	%OCft	Rs:32601.00
4.	01 No	Providing and fitting of P.E fittings etc complete. Cross Tee Equal 90x90x90	Rs:2218.00	Each	Rs:2218.00
5.	03 Nos	Construction small wheel valve chamber clear inside size 18"x18"x18" with walls of 9"thick of B.B in cement mortar 1:3 over 4" thick cement concrete 1:3:6 cement plastered ½" thick 1:3 inside i/c supplying and fixing C.I light weight manhole cover with frame and locking arrangement of 18" x 18" clear opening etc complete.(P.H.Sch. P/53 I/9)	Rs.4103.00	Each	Rs:12309.00
6.	03 Nos	Providing & fixing full way gun metal valve with wheel, threaded or flanged ends with rubber washer standard pattern(C.Sch. Page No.15, Item No.6(b) 3"Dia	Rs.1940.84	Each	Rs:5823.00

7.	03 Nos	Providing and fixing Air Valve Double action etc complete 3" Dia	Rs.4000.00	Each	Rs:12000.00
----	--------	---	------------	------	-------------

Amount Total (a) **Rs:9,56,907.00**

_____ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A) = a + b in words

Contractor

Executive Engineer / Procuring Agency

(Cont.....Page No.02)

Summary of Bill of Quantities

Cost of Bid	Amount _____
1 (A) Cost based on composite Schedule of Rate	_____
2 (B) Cost of based on Non / Offered Schedule of Rates.	_____
TOTAL COST OF BID (C) = TOTAL (A) + Total (B)	_____

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK: - PROVIDING AND LAYING WATER SUPPLY LINE AT PEER SARHANDI GOTH & UNDERGROUND TANSK AT RAMZAN MUHALLAH UC- KOTIARO DCK.BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	720.0 Cft	Excavation for tanks and reservoir in all kind of soils murum hard average or soft i /c trimming and dressing sides to true alignment / design section profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layer for construction of banks and dressing and disposal of surplus earth. Excavation earth within a one chain as directed by engineer in charge i/c providing fence guards, lights flags and temporary crossing for non-vehicular traffic where ever required lift upto 5'ft (1.52m) and lead upto one chain (30.5m) (PHED Sch P-69 Item 5)	Rs.4050.00	%Cft	Rs:2916.00
2.	720.0 Cft	Excavation for tanks and reservoir in soft rock by hammering and chiseling where blast not applicable ore is prohibited including trimming and dressing side to true alignment/ design sections / profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layer for construction of banks and dressing and disposal of surplus earth. Excavation earth with in one chain as directed by engineer guards light flags and temporary crossing for non vehicular traffic where ever require lift upto 5ft (1.52m) and lead up to one chain (30.5mm) (PHED Sch P-70 Item 6)	Rs.10170.00	%Cft	Rs:7322.00
3.	121.0Cft	P/L cement concrete brick or stone ballast 1-1/2'to2' gauge 1:4:8 ratio etc complete (G. Sch: P-No: It/No:)	Rs:9416.28	%Cft	Rs:11394.00
4.	448.50Cft	RCC work in roof slab, beams Coolum's rafts, lintels and others structural member laid in situ or precast laid in position complete in all respects (b) ratio 1:2:4 90 lbs cement 2Cft sand 4cft shingle 1/8" to 3/4" gauge (G.Sch: P-No: It/No: ().	Rs:337.00	P.Cft	Rs:151145.00
5.	17.69Cwt	Fabrication of mild steel reinforcement for cement concrete including cutting, bending laying in position, making joints and fastening including cost of binding wire (also includes removal of rust bars) using tor bars(G.Sch:P-No:16 It/No:8(b).	Rs:5001.70	P.Cwt	Rs:88480.00
6.	608.0Sft	Cement plaster 1:4 up to 12' height 3/4" thick (G.Sch: P-No:51 It/No:11(b).	Rs.3191.76	%Sft	Rs:19407.00

7.	1.75 Cwt	P/F C.I manhole with frame 50KG i/c locking..etc	Rs:6985.00	P.Cwt	Rs:6985.00
8.	04.0Rft	Providing and fixing in position C.C foundation 1:3:6 M.S Ladder of MS angle iron 2"x2"x1/4" 1' apart with M.S bar 3/4" dia spaced 1' apart painting 3 coats with anticorrosive steel paint etc complete.(PEHD/Sch P.55 It/No:3)	Rs.799.00	P.Rft	Rs:8867.00
9.	8250.0Cft	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape leveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth with in one chain as directed by Engineer incharge providing fence guards light flags and temporary crossing for non-vehicular traffic where ever required lift up to 5ft and lead upto one chain. 3" Dia	Rs.4650.00	%0Cft	Rs:38363.00
10.	1092.0Rft	Providing, laying & fixing in trench i/c fitting, jointing & testing etc complete in all respect the high Density polyethylene pipes (HDDE-100) for W/S conforming ISO 4427 / DIN 8071/8075 B.S 3580 & PSI 3051.(PN.08)(RA) 3"Dia	Rs:178.00	P.Rft	Rs:194378.00
11.	7429.0Cft	Refilling the excavated stuff in trenches 6" thick layers i/c watering, ramming to full compaction etc...complete	Rs.2760.00	%0Cft	Rs:20504.00

Amount Total (a) **Rs:8,52,669.00**

_____ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A) = a + b in words

Contractor

Executive Engineer / Procuring Agency

Summary of Bill of Quantities

Cost of Bid

Amount _____

1 (A) Cost based on composite Schedule of Rate

2 (B) Cost of based on Non / Offered Schedule of Rates.

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK: - PROVIDING AND LAYING WATER SUPPLY LINE AT ABDUL REHMAN JOKHIO
GOTH UC- KOTEARO DISTRICT COUNCIL KARACHI.BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	15312.0Cft	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape leveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth with in one chain as directed by Engineer incharge providing fence guards light flags and temporary crossing for non-vehicular traffic where ever required lift up to 5ft and lead upto one chain.	Rs.4650.00	%Ocft	Rs:71200.00
2.	100.0Rft 150.0Rft 1500.0Rft	Providing, laying & fixing in trench i/c fitting, jointing & testing etc complete in all respect the high Density polyethylene pipes (HDDE-100) for W/S conforming ISO 4427 / DIN 8071/8075 B.S 3580 & PSI 3051.(PN.8)(RA) 8"Dia 6"Dia 3"Dia	Rs:1250.00 Rs:799.08 Rs:250.20	P.Rft P.Rft P.Rft	Rs:125000.00 Rs:119862.00 Rs:375300.00
3.	13780.0Cft	Refilling the excavated stuff in trenches 6" thick layers i/c watering, ramming to full compaction etc...complete	Rs.2760.00	%0Cft	Rs:38032.00
4.	09 Nos	Providing and fixing Air Valve Double action etc complete	Rs.6000.00	Each	Rs:54000.00
5.	05 Nos	Providing & fixing full way gun metal valve with wheel, threaded or flanged ends with rubber washer standard pattern(C.Sch. Page No.15, Item No.6(b)) 3"Dia	Rs.1940.84	Each	Rs:9704.00

Amount Total (a) **Rs:7,93,098.00**

_____%Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A) = a + b in words

Contractor

Executive Engineer / Procuring Agency

Summary of Bill of Quantities

Cost of Bid

Amount _____

1 (A) Cost based on composite Schedule of Rate

2 (B) Cost of based on Non / Offered Schedule of Rates.

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK: - PROVIDING AND LAYING OF WATER SUPPLY LINE AT MOLAI BASTI,
ALLAH BUX HIMAITTI GOTH UC- PIPRI BIN QASIM ZONE DCK.BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	10000.0Cft	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape leveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth with in one chain as directed by Engineer in charge providing fence guards light flags and temporary crossing for non-vehicular traffic where ever required lift up to 5ft and lead upto one chain.	Rs.4650.00	%Ocft	Rs:69750.00
2.	2000.0Rft	Providing, laying & fixing in trench i/c fitting, jointing & testing etc complete in all respect the high Density polyethylene pipes (HDDE-100) for W/S conforming ISO 4427 / DIN 8071/8075 B.S 3580 & PSI 3051.(PN.8)(RA) 3"Dia	Rs:250.20	P.Rft	Rs:500400.00
3.	13500.0Cft	Refilling the excavated stuff in trenches 6" thick layers i/c watering, ramming to full compaction etc...complete	Rs.2760.00	%Ocft	Rs:32260.00
4.	03 Nos	Providing and fitting of P.E fittings etc complete. Cross Tee Equal 90x90x90	Rs:2218.00	Each	Rs:6654.00
5.	03 Nos	Construction small wheel valve chamber clear inside size 18"x18"x18" with walls of 9"thick of B.B in cement mortar 1:3 over 4" thick cement concrete 1:3:6 cement plastered ½" thick 1:3 inside i/c supplying and fixing C.I light weight manhole cover with frame and locking arrangement of 18" x 18" clear opening etc complete.(P.H.Sch. P/53 I/9)	Rs.4103.00	Each	Rs:12309.00
6.	03 Nos	Providing and fixing Air Valve Double action etc complete 3"Dia	Rs.4000.00	Each	Rs:12000.00

Amount Total (a) **Rs:6,33,373.00**

_____ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A) = a + b in words

Contractor

Executive Engineer / Procuring Agency

(Cont.....Page No.02)

Summary of Bill of Quantities

Cost of Bid

Amount _____

1 (A) Cost based on composite Schedule of Rate

2 (B) Cost of based on Non / Offered Schedule of Rates.

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK: - REPAIR AND MAINTENANCE OF METALED ROAD AT RANJERS HEAD
QUARTER UC- CHAND PARO DISTRICT COUNCIL KARACHI

BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	4005.0Cft	Dismantling and removing road metalling...etc	Rs:605.00	%Cft	Rs:24230.00
2.	1348.Cft	Carriage of 100Cft / 5 Tons of all material like stone aggregate spawl coal lime -surkhi etc BG rail fastening & points & crossing Bridge Girder pipes sheets Rail M.s Bars etc or 1000 No. Tiles 12"x12" or 150 Cft of timber or 100 Mounds of fuel wood by truck or any other means owned by the contractors 3 mile lead etc...complete.	Rs.771.95	%Cft	Rs.10405.00
3.	3592.0Cft	Providing and laying aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting by approved mechanical means (Motor grader, Vibrator roller and smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the mix dry density (Rate i/c all cost of material T&P and carriage up to(H.W.Sch.P/5 I/ 13(b)	Rs:7606.09	%Cft	Rs:273210.00
4.	8520.0Sft	<u>1 1/2"Thick Asphalt Concrete Wearing Course Plant Mix</u> Laying mechanically to proper line and grade plant mixed Asphalt Concrete specified formula according to job mixed formula according to job mixed formula approved by the Engineer Incharge rolling and finishing to design Proper grade line level and comber etc (Machinery with POLs Cost) (H.W Sch P/09 I/24(A)	Rs:7248.40	% Sft	Rs:617563.00

5.	600.0Sft	Providing 1" thick (Consolidated) premix carpet in proper chamber and graded including supplying 10.cft bajri, 4cft hill sand (of approved quantity and grade) bitumen of 80/100 penetration including mixing in mechanical mixer in required proportion including heating material and cleaning the road surface (Hill sand 2cft: for mixing and 2cft for dusting) (Rate includes all cost of materials T&P and carriage upto 3 chains).H.W.Sch.Page.No.21	Rs:4411.81	%Sft	Rs:26470.00
----	----------	---	------------	------	-------------

Amount Total (a) **Rs: 9, 51,878.00**

_____ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A)= a + b in words :

Contractor

Executive Engineer / Procuring Agency

Summary of Bill of Quantities

Cost of Bid

Amount _____

1 (A) Cost based on composite Schedule of Rate

2 (B) Cost of based on Non / Offered Schedule of Rates.

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

Contractor

Executive Engineer / Procuring Agency



OFFICE OF THE DISTRICT COUNCIL KARACHI

Block-14 Sir Shah Suleman Road, Gulshan-e-Iqbal

Phone No. 021-99232531/99232593

Fax No. 99232594

NO: DCK/Chairman / 02 / 2017, dated. 09 / January, 2017

To,

The Managing Director,
Sindh Public Procurement Authority
Karachi.

SUBJECT: CONSTITUTION OF PROCUREMENT COMMITTEE OF DISTRICT COUNCIL KARACHI FOR 2016-17.

In partial modification of the Government approval issued by the Deputy Secretary (General) Local Government Department vide No. ^{50-V/LG/34-04/2015} dated 22/11/2016, the word which was by typing mistake typed at Sr. No. 3 as Mr. Tauqeer Abbas, "Ex. Engineer DMC (East)" may please be read as Mr. Tauqeer Abbas, "Executive Engineer DMC (East)" being member of the Procurement Committee from other than District Council Karachi.

Copy to:-

1. The Assistant Director, (Assessment), SPPRA.
2. The Chief Officer, DCK.
3. The District Engineer, DCK.


19/1/17




CHAIRMAN
DISTRICT COUNCIL KARACHI
o/c


- CHAIRMAN
DISTRICT COUNCIL KARACHI
o/c



NG.SO-V(LG)/34-04/2015
GOVERNMENT OF SINDH
LOCAL GOVERNMENT DEPARTMENT

Karachi Dated the 22nd November, 2016



To,

The Chairman
District Council Karachi
KARACHI

SUBJECT: CONSTITUTION OF PROCUREMENT COMMITTEE OF DISTRICT COUNCIL KARACHI FOR 2016-17

I am directed to refer to your letter No. DCK/Chairman/54/2016 dated: 18-11-2016, on the subject noted above and to convey the permission / approval regarding intends to start development activities in the current Financial year 2016-17 by tendering of development works as per Annual Development plan for the Council which will be opened by the Procurement Committee as required under Rule 7 of Sindh Public Procurement Rules 2010. As such Procurement Committee has to be constituted for the financial year 2016-17.

It is therefore requested that approval may kindly be accorded for constitution of Procurement Committee of District Council Karachi for the Financial year 2016-17 comprising following:-

S.NO	DESIGNATION	POSITION
01.	District Engineer, District Council Karachi	Chairman
02.	Accounts Officer, District Council Karachi	Member
03.	Mr. Tauqeer Abbas, Ex-Engineer DMC (East)	Member from other than DCK

The functions and responsibilities of procurement committee shall be as under (Section 7&8 of SPPRA Rule 2010).

- Preparing bidding documents
- Carrying out technical as well as financial evaluation of the bids
- Preparing evaluation report as provided in Rules 45
- Making recommendations for the award of contract to the competent authority, and
- Perform any other function ancillary and incidental to the above


(ALI GUL SANJRANI)
DEPUTY SECRETARY (GENERAL)

Copy for information & necessary action to:

- The Director, Sindh Public Procurement Regulatory Authority, Karachi
- The Director, Local Government Department, Govt. of Sindh Karachi
- The P.S. to Secretary Local Government Department, Govt. of Sindh Karachi
- Office order file

(ALI GUL SANJRANI)
DEPUTY SECRETARY (GENERAL)



DISTRICT COUNCIL KARACHI

NO: DCK/Chairman/ 56 /2016

Dated: - 07/12/2016

SUBJECT: CONSTITUTION OF COMMITTEE FOR COMPLAINT REDRESSAL OF GRIEVANCES AND SETTLEMENT OF DISPUTES.

As required under rule 31 of Sindh Public Procurement Rules 2010 a committee for complaint redressal of grievances and settlement of disputes is hereby constituted for District Council Karachi for the year 2016-17. consisting upon following:-

01	Mr. Masroor Ahmed Memon	Chief Officer DCK (BPS-19)	Chairman
02	Mr. Taufeeq Ahmed Jokhio	Assistant District Accounts Officer, DCK	Member
03	Mr. Tariq Rabbani Dahri	Assistant Resident Engineer, Techno Consultancy Karachi	Member

CHAIRMAN
DISTRICT COUNCIL KARACHI

Copy is forwarded for information to the:-

1. Director, (CB) SPPRA, GOS.
2. District Engineer, DCK.
3. Accounts Officer, DCK.
4. P.S to Managing Director, SPPRA.
5. Mr. Liaquat Ali Mughal A.E.E DMC Malir, Member Procurement Committee, DCK.


CHAIRMAN
DISTRICT COUNCIL KARACHI

DISTRICT COUNCIL KARACHI

CRITERIA FOR BIDDERS

Bidders are advised to submit following documents with bidding documents for Eligibility / Qualification Criteria.

Eligibility / Qualification Criteria

<u>S.No.</u>	<u>Eligibility / Qualification Criteria</u>
01	NTN.
02	Registration with Sindh Revenue Board (SRB).
03	Registration with Pakistan Engineering Council in relevant category/field (for works costing more than Rupees Four Million).

Qualification Criteria

<u>S.No.</u>	<u>Eligibility / Qualification Criteria</u>
01	Minimum Three years Experience of relevant field
02	Turnover of last three years (Attach Documentary)
03	Required Bid security may be attached.
04	Bid is designed named and stamped by the authorized person of the firm along with Authorization Letter.

DISTRICT ENGINEER
DISTRICT COUNCIL KARACHI