CONSTRUCTION OF SURFACE DRAIN AT MACHI GOTH W. NO 1 M.C MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	11,970.00	5,431.25	%0 Cft.	65,012
2	Dismatling C.C 1:2:4	1,330.00	3,327.50	% Cft.	44,256
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	1,330.00	9,416.28	% Cft.	125,237
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:2:4. (CSI No. 05, P. No. 17).	877.80	14,429.25	% Cft.	126,660
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,140.00	12,902.00	% Cft.	147,083
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	8,360.00	2,206.60	% Sft.	184,472
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	210.00	337.00	P. Cft.	70,770
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	8.4375	5,001.70	P.Cwt.	42,202
				TOTAL RS.	**805,691**

I, M/s _____ do hereby quotes the rates _____ % above / below

the rates of CSR in Words: (_____)

to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT MACHI GOTH W.NO 1 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	8,450.00	6,187.50	%0 Cft.	52284
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	8,450.00	1,361.25	%0 Cft.	11503
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,788.50	9,416.28	% Cft.	262573
4	C.C. 1:2:4 for topping.	2,788.50	14,429.25	% Cft.	402360
				TOTAL RS.	**728720**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF PAVER BLOCK AT IBRAHIM SHAH TO SHAHI BAZAR W.NO 1 M.C MORO

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Earth work excavation undressed lead upto extra one miles Kassi or Phawrah or Shovel in ordinary soil (G.S.I.NO. 1/B- P/i)	13,500.00	1,361.25	% Cft.	18377
2	Cement concrets brick or stone ballast 1 1/2" to 2" guage Ratio 1:4:8 G.S.I No: 4-P/15 (G.S.I.NO. 5/H- P/16	5,670.00	9,416.28	% Cft.	533903
4	Providing and fixing cement pavering block flooring having size (197x97x60) mmst city gudrra / cobble shape with natural clour. (G.S.I 71 P.NO .48)	13,500.00	223.97	% Cft.	3023595
				TOTAL RS.	**3575875**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT TO DADU ROAD TO MALLAH MUHALLA .NO 2 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,900.00	2,117.50	%0 Cft.	8258
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,900.00	1,361.25	%0 Cft.	5309
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,287.00	9,416.28	% Cft.	121188
4	C.C. 1:2:4 for topping.	975.00	14,429.25	% Cft.	140685
				TOTAL RS.	**275440**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT ROSHAN KORAI AND ZULFQAR KORAI .NO 2 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	6,500.00	2,117.50	%0 Cft.	13764
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	6,500.00	1,361.25	%0 Cft.	8848
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,145.00	9,416.28	% Cft.	201979
4	C.C. 1:2:4 for topping.	1,625.00	14,429.25	% Cft.	234475
				TOTAL RS.	**459066**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT VARIOUS STREET OF .NO 2 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	4,800.00	2,117.50	%0 Cft.	10164
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	4,800.00	1,361.25	%0 Cft.	6534
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,584.00	9,416.28	% Cft.	149154
4	C.C. 1:2:4 for topping.	1,200.00	14,429.25	% Cft.	173151
				TOTAL RS.	**339003**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT VARIOUS STREET OF MALAK COLONY.NO 2 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	7,200.00	2,117.50	%0 Cft.	15246
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	7,200.00	1,361.25	%0 Cft.	9801
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,376.00	9,416.28	% Cft.	223731
4	C.C. 1:2:4 for topping.	1,800.00	14,429.25	% Cft.	259727
				TOTAL RS.	**508504**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT NIAZ SHAH TO BABAR SHAHW.NO 2 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	7,200.00	2,117.50	%0 Cft.	15246
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	7,200.00	1,361.25	%0 Cft.	9801
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,376.00	9,416.28	% Cft.	223731
4	C.C. 1:2:4 for topping.	1,800.00	14,429.25	% Cft.	259727
				TOTAL RS.	**508504**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT DADU ROAD TO MALAK COLONY W. NO 2 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,687.50	3,176.25	%0 Cft.	5,360
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	371.25	9,416.28	% Cft.	34,958
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	450.00	94:00	P. Rft.	42,300
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,012.50	11,948.36	% Cft.	120,977
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	2,025.00	2,206.60	% Sft.	44,684
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**317,341**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT VARIOUS STREET W. NO 2 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	2,250.00	3,176.25	%0 Cft.	7,147
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	495.00	9,416.28	% Cft.	46,611
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	600.00	94.00	P. Rft.	56,400
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,350.00	11,948.36	% Cft.	161,303
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	2,700.00	2,206.60	% Sft.	59,578
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	70.00	337.00	P. Cft.	23,590
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	2.19	5,001.70	P.Cwt.	10,941
				TOTAL RS.	365,569

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT MALLAH MUHALLA W. NO 2 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,125.00	3,176.25	%0 Cft.	3,573
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	247.50	9,416.28	% Cft.	23,305
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	300.00	94.00	P. Rft.	28,200
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	675.00	11,948.36	% Cft.	80,651
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,350.00	2,206.60	% Sft.	29,789
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	100.00	337.00	P. Cft.	33,700
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	3.13	5,001.70	P.Cwt.	15,630
				TOTAL RS.	**214,849**

I, M/s _____ do hereby quotes the rates _____ % above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT VARIOUS STREET W. NO 3 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	2,417.50	3,176.25	%0 Cft.	7,679
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	797.78	9,416.28	% Cft.	75,121
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	967.00	94.00	P. Rft.	90,898
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,450.50	11,948.36	% Cft.	173,311
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	3,384.50	2,206.60	% Sft.	74,682
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	315.00	337.00	P. Cft.	106,155
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	9.84	5,001.70	P.Cwt.	49,235
				TOTAL RS.	**577,081**

I, M/s _____ do hereby quotes the rates _____ % above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

DETAIL WORK ESTIMATE FOR CONSTRUCTION OF PAVER BLOCK AT JAAM STREET W.NO 3 M.C MORO

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) Ratio: 1:2:4	30.00	14,429.25	% Cft.	4329
2	ement concereteBrick or Stone Ballast 1/2" to 2" gauge. 1:4:8	198.00	9,416.28	% Cft.	18644
3	Crush fix brick graded as band (G.S.(M) I 51 P. NO 16)	300.00	2,500.00	% Cft.	7500
4	Providing and fixing cement pavering block flooring having size (197x97x60) mmst city gudrra / cobble shape with natural clour. (G.S.I 71 P.NO .48)	600.00	199.77	% Cft.	119862
				TOTAL RS.	**150335**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT VARIOUS STREET W.NO 3 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	8,703.00	6,187.50	%0 Cft.	53850
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	8,703.00	453.75	%0 Cft.	3949
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	3,655.26	9,416.28	% Cft.	344190
5	C.C. 1:2:4 for topping.	2,871.99	14,429.25	% Cft.	414407
				TOTAL RS.	**816395**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT JAAM HOUSE TO DADU ROAD W.NO 3 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	9,800.00	6,187.50	%0 Cft.	60638
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	9,800.00	453.75	%0 Cft.	4447
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	4,116.00	9,416.28	% Cft.	387574
5	C.C. 1:2:4 for topping.	3,234.00	14,429.25	% Cft.	466642
				TOTAL RS.	**919300**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT JAAM HOUSE TO DADU ROAD W. NO 3 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	2,450.00	3,176.25	%0 Cft.	7,782
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	808.50	9,416.28	% Cft.	76,131
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	980.00	94.00	P. Rft.	92,120
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,470.00	11,948.36	% Cft.	175,641
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	3,430.00	2,206.60	% Sft.	75,686
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	315.00	337.00	P. Cft.	106,155
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	9.84	5,001.70	P.Cwt.	49,235
				TOTAL RS.	**582,750**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT DARIS ROAD TO AMANULLAH KHORO MORO.					W. NO 4
SCHEDULE - B					
S.NO.	**NAME OF ITEM**	**QTY**	**RATE**	**UNIT**	**AMOUNT**
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	3,150.00	3,176.25	%0 Cft.	10,005
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	693.00	9,416.28	% Cft.	65,255
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	700.00	174.00	P. Rft.	121,800
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,575.00	11,948.36	% Cft.	188,187
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	3,150.00	2,206.60	% Sft.	69,508
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**523,817**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT GHANWAR ALMANI TO SAIN RAKHYO W. NO 4 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,125.00	3,176.25	%0 Cft.	3,573
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	247.50	9,416.28	% Cft.	23,305
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	250.00	174.00	P. Rft.	43,500
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	562.50	11,948.36	% Cft.	67,210
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,125.00	2,206.60	% Sft.	24,824
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**231,474**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT JAMAL DIN BURIRO TO ASLAM BHAN W.NO 4 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	4,950.00	6,187.50	%0 Cft.	30628
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	4,950.00	453.75	%0 Cft.	2246
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,079.00	9,416.28	% Cft.	195764
5	C.C. 1:2:4 for topping.	1,633.50	14,429.25	% Cft.	235702
				TOTAL RS.	**464340**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING ATASAD CHAWAN TO KAMAL CHAWAN STREET W.NO 4 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	4,400.00	6,187.50	%0 Cft.	27225
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	4,400.00	453.75	%0 Cft.	1997
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,848.00	9,416.28	% Cft.	174013
5	C.C. 1:2:4 for topping.	1,452.00	14,429.25	% Cft.	209513
				TOTAL RS.	**412747**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT PIERAL FAQEER STREET W.NO 4 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,300.00	6,187.50	%0 Cft.	20419
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,300.00	453.75	%0 Cft.	1497
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,386.00	9,416.28	% Cft.	130510
5	C.C. 1:2:4 for topping.	1,089.00	14,429.25	% Cft.	157135
				TOTAL RS.	**309560**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT RAMZAN SOLANG TO MAIN NALA W.NO 4 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	2,205.00	6,187.50	%0 Cft.	13643
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	2,205.00	453.75	%0 Cft.	1001
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	926.10	9,416.28	% Cft.	87204
5	C.C. 1:2:4 for topping.	727.65	14,429.25	% Cft.	104994
				TOTAL RS.	**206843**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT AKBAR RAJPUT TO ALI GUL JESSAR W.NO 4 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	2,136.00	6,187.50	%0 Cft.	13217
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	2,136.00	453.75	%0 Cft.	969
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	897.12	9,416.28	% Cft.	84475
5	C.C. 1:2:4 for topping.	704.88	14,429.25	% Cft.	101709
				TOTAL RS.	**200370**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT DARIS ROAD KANDARO MACHI W. NO 4 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	2,700.00	3,176.25	%0 Cft.	8,576
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	594.00	9,416.28	% Cft.	55,933
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	600.00	174.00	P. Rft.	104,400
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,350.00	11,948.36	% Cft.	161,303
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	2,700.00	2,206.60	% Sft.	59,578
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**458,852**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

DETAIL WORKING ESTIMATE FOR CONSTRUCTION OF CC TOPPING AT VARIOUS SPOT OF W.NO 5 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	7,200.00	6,187.50	%0 Cft.	44550
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	7,200.00	453.75	%0 Cft.	3267
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	3,024.00	9,416.28	% Cft.	284748
5	C.C. 1:2:4 for topping.	2,376.00	14,429.25	% Cft.	342839
				TOTAL RS.	**675404**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT VARIOUS PLACES OF W. NO 5 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	3,250.00	3,176.25	%0 Cft.	10,323
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	1,072.50	9,416.28	% Cft.	100,990
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	1,300.00	94.00	P. Rft.	122,200
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,950.00	11,948.36	% Cft.	232,993
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	4,550.00	2,206.60	% Sft.	100,400
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	315.00	337.00	P. Cft.	106,155
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	9.84	5,001.70	P.Cwt.	49,235
				TOTAL RS.	**722,296**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

PROVIDING LAYING JOINTING AND TESTING RCC SEWER LINE 12" DIA AND MAIN HOLES AT DUSTAGHIR COLONY W.NO 5 MORO

SCHEDULE - B -II

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excation for pipe line in trenches and pits in soft soil i/c termming and dressing sides to true aligment shape leveling st beds stcorrect level surpls earth within a one chain is directed by engineer incharge	14,000.00	3600.00	%0	50,400
2	Stone Crushed graded 1" ing .(C.S.I.No: 77 P. No:,05).	2,800.00	9416.28	% Cft.	263,656
3	Providing RCC Pipe at ASTEMC-76-62 TC-7-70 Class B wall and fixing in trenches I/C cutting filling and jointing with rubber jesting fwith water to spcified presure (P.H.S.I. No: 1 P.NO: 8).	1,600.00	412.00	% Cft.	659,200
4	Reflling excavated stuff in treaches as 6" thick layers j/c watering remaning to full compaction etc comlete (P.H.S.I. No: 24 P.NO:77).	12,600.00	2760.00	% Cft.	34,776
	MAIN HOLES				**1,008,032**
1	Dismatling and removing Road mantling (C.S.I.No. 51-P. No:13).	923.16	605.00	%0 Cft.	5,585
2	Excation in foundation building bridge and other structure i/c dressing opening awarded the structure with ecavatedearth watering and remaning etc complete lead uoto chain till upto (P.H.S.I. NO. 18 P.NO. 18)	3,077.20	3,176.25	% Cft.	9,774
3	Extra for wet earth work (P.H.S.I. No: 15 P.NO: 04).	1,230.88	1058.75	%0 Cft.	1,303
4	Cement Concrete Plain 1:4:8 (P.H.S.I. No: 1 P.NO: 46). 5	307.72	9416.28	% Cft.	28,976
6	Earaction and Removal of Conting for RCC or plain cement concrete work part wood (P.H.S.I. No: 19	252.80	3,127.41	P. Cft.	7,906
7	RC C 1:2:4 Ratio (1:2:4) for Circular Main Hole	734.76	337.00	P.Cwt.	247,614
8	Fabrication of Mild Steel (C.S.I.No: 77 P. No:,05).	29.52	5,001.70	P.Cwt.	147,658
9	Providing fixing CI Main Hole Frame I/c Cost of	31.49	6,985.00	P.Cwt.	219,928

10	Providing and fixing pre cost RCC Main Hole Cover in Ratio (1:2:4) deep revts for concrete with 1/2 dia for steel bars 3" contec to contect (R.A Approval)	16.00	1,051.25	P.Cwt.	16,820
11	Rehandling of Earth Extra for every 50' additional lead is part there of ordinary soil (P.H.S.I. No: 08 P.NO:3).	2,000.18	502.50	P % Cft	10,051
				TOTAL RS.	**695,615**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT BADAL ZARDARI TO RAMZAN RAHOO W.NO 6 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,000.00	6,187.50	%0 Cft.	18563
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,000.00	453.75	%0 Cft.	1361
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,260.00	9,416.28	% Cft.	118645
5	C.C. 1:2:4 for topping.	990.00	14,429.25	% Cft.	142850
				TOTAL RS.	**281418**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT VARIOUS PLACES OF W. NO 6 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	2,700.00	3,176.25	%0 Cft.	8,576
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	594.00	9,416.28	% Cft.	55,933
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	600.00	174.00	P. Rft.	104,400
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,350.00	11,948.36	% Cft.	161,303
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	2,700.00	2,206.60	% Sft.	59,578
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	458,852

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT SACHAL COLONY W. NO 6 M.C MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	18,900.00	1,361.25	%0 Cft.	25,728
2	Dismatling C.C 1:2:4	612.50	3,327.50	% Cft.	20,381
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	2,100.00	9,416.28	% Cft.	197,742
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:2:4. (CSI No. 05, P. No. 17).	1,386.00	14,429.25	% Cft.	199,989
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,800.00	12,902.00	% Cft.	232,236
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	12,000.00	2,206.60	% Sft.	264,792
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	280.00	337.00	P. Cft.	94,360
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	11.2500	5,001.70	P.Cwt.	56,269
				TOTAL RS.	**1,091,497**

I, M/s _____ do hereby quotes the rates _____ % above / below

the rates of CSR in Words: (_____)

to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT IMAM ALI SHAITO TO NASIR RAJPUT .NO 6 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,900.00	6,187.50	%0 Cft.	24131
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,900.00	1,361.25	%0 Cft.	5309
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,287.00	9,416.28	% Cft.	121188
4	C.C. 1:2:4 for topping.	1,287.00	14,429.25	% Cft.	185704
				TOTAL RS.	**336332**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT VARIOUS STREET OF .NO 6 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	8,450.00	6,187.50	%0 Cft.	52284
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	8,450.00	1,361.25	%0 Cft.	11503
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,788.50	9,416.28	% Cft.	262573
4	C.C. 1:2:4 for topping.	2,788.50	14,429.25	% Cft.	402360
				TOTAL RS.	**728720**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT IMAM ALI SHAITO TO NASIR RAJPUT HOUSE W. NO 6 M.C MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	4,725.00	1,361.25	%0 Cft.	6,432
2	Dismatling C.C 1:2:4	52.50	3,327.50	% Cft.	1,747
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	525.00	9,416.28	% Cft.	49,435
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:2:4. (CSI No. 05, P. No. 17).	346.50	14,429.25	% Cft.	49,997
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	450.00	12,902.00	% Cft.	58,059
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	3,000.00	2,206.60	% Sft.	66,198
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	56.00	337.00	P. Cft.	18,872
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	2.2500	5,001.70	P.Cwt.	11,254
				TOTAL RS.	**261,994**

I, M/s _____ do hereby quotes the rates _____ % above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT ANWAR MEMON TO DADU CHOWK W.NO 7 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	4,800.00	6,187.50	%0 Cft.	29700
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	4,800.00	453.75	%0 Cft.	2178
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,016.00	9,416.28	% Cft.	189832
5	C.C. 1:2:4 for topping.	1,584.00	14,429.25	% Cft.	228559
				TOTAL RS.	**450270**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF PAVER BLOCK AT CHAIRMAN HOUSE TO BADAR SHAH MASJID W.NO 7 M.C MORO

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) Ratio: 1:2:4	475.00	14,429.25	% Cft.	68539
2	ement concereteBrick or Stone Ballast 1/2" to 2" gauge. 1:4:8	3,762.00	9,416.28	% Cft.	354240
3	Crush fix brick graded as band (G.S.(M) I 51 P. NO 16)	5,700.00	2,500.00	% Cft.	142500
4	Providing and fixing cement pavering block flooring having size (197x97x60) mmst city gudrra / cobble shape with natural clour. (G.S.I 71 P.NO .48)	11,400.00	199.77	% Cft.	2277378
				TOTAL RS.	**2842657**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF PAVER BLOCK AT SHAHEED CHOWK TO ANWAR MEMON W.NO 7 M.C MORO

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) Ratio: 1:2:4	225.00	14,429.25	% Cft.	32466
2	ement concereteBrick or Stone Ballast 1/2" to 2" gauge. 1:4:8	1,782.00	9,416.28	% Cft.	167798
3	Crush fix brick graded as band (G.S.(M) I 51 P. NO 16)	2,700.00	2,500.00	% Cft.	67500
4	Providing and fixing cement pavering block flooring having size (197x97x60) mmst city gudrra / cobble shape with natural clour. (G.S.I 71 P.NO .48)	5,400.00	199.77	% Cft.	1078758
				TOTAL RS.	**1346522**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT VARIOUS SRTEET W. NO 8 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	2,700.00	3,176.25	%0 Cft.	8,576
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	594.00	9,416.28	% Cft.	55,933
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	600.00	174.00	P. Rft.	104,400
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,350.00	11,948.36	% Cft.	161,303
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	2,700.00	2,206.60	% Sft.	59,578
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	420.00	337.00	P. Cft.	141,540
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	13.13	5,001.70	P.Cwt.	65,647
				TOTAL RS.	**596,977**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT IQSA MASJID TO SHAHBAQ SABKI W. NO 8 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	4,500.00	3,176.25	%0 Cft.	14,293
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	990.00	9,416.28	% Cft.	93,221
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	1,000.00	174.00	P. Rft.	174,000
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	2,250.00	11,948.36	% Cft.	268,838
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	4,500.00	2,206.60	% Sft.	99,297
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	420.00	337.00	P. Cft.	141,540
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	13.13	5,001.70	P.Cwt.	65,647
				TOTAL RS.	**856,836**

I, M/s _____ do hereby quotes the rates _____ % above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT HABIBULLAH ZARDARI TO SHAHNWAZ ZARDARI W. NO 8 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	750.00	3,176.25	%0 Cft.	2,382
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	165.00	9,416.28	% Cft.	15,537
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	200.00	94.00	P. Rft.	18,800
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	450.00	11,948.36	% Cft.	53,768
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	900.00	2,206.60	% Sft.	19,859
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**179,408**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT GULBHAR ZARDARI TO SOZ ZARDARI MORO.					W. NO 8
SCHEDULE - B					
S.NO.	**NAME OF ITEM**	**QTY**	**RATE**	**UNIT**	**AMOUNT**
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	937.50	3,176.25	%0 Cft.	2,978
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	206.25	9,416.28	% Cft.	19,421
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	250.00	94.00	P. Rft.	23,500
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	562.50	11,948.36	% Cft.	67,210
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,125.00	2,206.60	% Sft.	24,824
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**206,995**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT VARIOUS STREET OF W.NO 8 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	8,400.00	6,187.50	%0 Cft.	51975
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	8,400.00	453.75	%0 Cft.	3812
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	3,528.00	9,416.28	% Cft.	332206
5	C.C. 1:2:4 for topping.	2,772.00	14,429.25	% Cft.	399979
				TOTAL RS.	**787972**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT SIKANDAR SHAITI TO SHOUKAT ZARDARI W. NO 8 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,350.00	3,176.25	%0 Cft.	4,288
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	297.00	9,416.28	% Cft.	27,966
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	300.00	174.00	P. Rft.	52,200
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	675.00	11,948.36	% Cft.	80,651
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,350.00	2,206.60	% Sft.	29,789
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	175.00	337.00	P. Cft.	58,975
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	5.47	5,001.70	P.Cwt.	27,353
				TOTAL RS.	**281,223**

I, M/s _____ do hereby quotes the rates _____ % above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT SATTI STREET W.NO 9 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	2,400.00	6,187.50	%0 Cft.	14850
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	2,400.00	453.75	%0 Cft.	1089
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,008.00	9,416.28	% Cft.	94916
5	C.C. 1:2:4 for topping.	792.00	14,429.25	% Cft.	114280
				TOTAL RS.	**225135**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING ATRASOOLO BHATTI TO KANDARA GALI W.NO 9 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,840.00	6,187.50	%0 Cft.	23760
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,840.00	453.75	%0 Cft.	1742
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,612.80	9,416.28	% Cft.	151866
5	C.C. 1:2:4 for topping.	1,267.20	14,429.25	% Cft.	182847
				TOTAL RS.	**360216**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT GACHERO ROAD TO SYED AHSAN SHAH W.NO 9 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	1,920.00	6,187.50	%0 Cft.	11880
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	1,920.00	453.75	%0 Cft.	871
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	806.40	9,416.28	% Cft.	75933
5	C.C. 1:2:4 for topping.	633.60	14,429.25	% Cft.	91424
				TOTAL RS.	**180108**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT SAKHI IBRAHIM SHAH BACK SIDE STREET W.NO 9 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	2,400.00	6,187.50	%0 Cft.	14850
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	2,400.00	453.75	%0 Cft.	1089
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,008.00	9,416.28	% Cft.	94916
5	C.C. 1:2:4 for topping.	792.00	14,429.25	% Cft.	114280
				TOTAL RS.	**225135**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT KHAIR MOHD STREET W.NO 9 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,120.00	6,187.50	%0 Cft.	19305
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,120.00	453.75	%0 Cft.	1416
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,310.40	9,416.28	% Cft.	123391
5	C.C. 1:2:4 for topping.	1,029.60	14,429.25	% Cft.	148564
				TOTAL RS.	**292675**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT MOHD MUSA SOLANGI STREET W.NO 9 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	2,760.00	6,187.50	%0 Cft.	17078
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	2,760.00	453.75	%0 Cft.	1252
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,159.20	9,416.28	% Cft.	109154
5	C.C. 1:2:4 for topping.	910.80	14,429.25	% Cft.	131422
				TOTAL RS.	**258905**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT NAWAL MUHALLA W. NO 9 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	4,500.00	3,176.25	%0 Cft.	14,293
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	990.00	9,416.28	% Cft.	93,221
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	1,000.00	174.00	P. Rft.	174,000
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	2,250.00	11,948.36	% Cft.	268,838
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	4,500.00	2,206.60	% Sft.	99,297
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	315.00	337.00	P. Cft.	106,155
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	9.84	5,001.70	P.Cwt.	49,235
				TOTAL RS.	**805,039**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT NAJAF DIN BHATTI TO MUSTAFA BHATTI W. NO 9 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,440.00	3,176.25	%0 Cft.	4,574
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	316.80	9,416.28	% Cft.	29,831
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	320.00	174.00	P. Rft.	55,680
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	720.00	11,948.36	% Cft.	86,028
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,440.00	2,206.60	% Sft.	31,775
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**276,950**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT SAIN FAIZULLAH ZARDARI STREET MORO.					W. NO 9
SCHEDULE - B					
S.NO.	**NAME OF ITEM**	**QTY**	**RATE**	**UNIT**	**AMOUNT**
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	900.00	3,176.25	%0 Cft.	2,859
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	198.00	9,416.28	% Cft.	18,644
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	200.00	174.00	P. Rft.	34,800
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	450.00	11,948.36	% Cft.	53,768
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	900.00	2,206.60	% Sft.	19,859
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**198,992**

I, M/s _____ do hereby quotes the rates _____% above / below

the rates of CSR in Words: (_____)

to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

PROVIDING LAYING JOINTING AND TESTING RCC SEWER LINE 12" DIA AND MAIN HOLES AT JAMALI HOUSE W.NO 10 MORO.

#####

SCHEDULE - B -II

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUN
1	Excation for pipe line in trenches and pits in soft soil i/c termming and dressing sides to true aligment shape leveling st beds stcorrect level surpls earth within a one chain is directed by engineer incharge	1,750.00	3600.00	%0	6,300
2	Stone Crushed graded 1" ing .(C.S.I.No: 77 P. No:,05).	350.00	9416.28	% Cft.	32,957
3	Providing RCC Pipe at ASTEMC-76-62 TC-7-70 Class B wall and fixing in trenches I/C cutting filling and jointing with rubber jesting fwith water to spcified presure (P.H.S.I. No: 1 P.NO: 8).	200.00	412.00	% Cft.	82,400
4	Reflling excavated stuff in treaches as 6" thick layers j/c watering remaning to full compaction etc comlete (P.H.S.I. No: 24 P.NO:77).	1,575.00	2760.00	% Cft.	4,347
	MAIN HOLES				**126,004**
1	Dismatling and removing Road mantling (C.S.I.No. 51-P. No:13).	230.79	605.00	%0 Cft.	1,396
2	Excation in foundation building bridge and other structure i/c dressing opening awarded the structure with ecavatedearth watering and remaning etc complete lead upto chain till upto (P.H.S.I. NO. 18	769.30	3,176.25	% Cft.	2,443
3	Extra for wet earth work (P.H.S.I. No: 15 P.NO: 04).	307.72	1058.75	%0 Cft.	326
4	Cement Concrete Plain 1:4:8 (P.H.S.I. No: 1 P.NO: 46). 5	76.93	9416.28	% Cft.	7,244
6	Earaction and Removal of Conting for RCC or plain cement concrete work part wood (P.H.S.I. No: 19	63.20	3,127.41	P. Cft.	1,977
7	RC C 1:2:4 Ratio (1:2:4) for Circular Main Hole	442.74	337.00	P.Cwt.	149,203
8	Fabrication of Mild Steel (C.S.I.No: 77 P. No:,05).	17.79	5,001.70	P.Cwt.	88,974
9	Providing fixing CI Main Hole Frame I/c Cost of	7.87	6,985.00	P.Cwt.	54,982

10	Providing and fixing pre cost RCC Main Hole Cover in Ratio (1:2:4) deep revts for concrete with 1/2 dia for steel bars 3" contec to contect (R.A Approval)	4.00	1,051.25	P.Cwt.	4,205
11	Rehandling of Earth Extra for every 50' additional lead is part there of ordinary soil (P.H.S.I. No: 08 P.NO:3).	500.05	502.50	P % Cft.	2,513
				TOTAL RS.	**313,263**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT SADIQ ZARADRI TO WATTO HOUSE W.NO 10 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	4,000.00	6,187.50	%0 Cft.	24750
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	4,000.00	453.75	%0 Cft.	1815
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,680.00	9,416.28	% Cft.	158194
4	C.C. 1:2:4 for topping.	1,320.00	14,429.25	% Cft.	190466
				TOTAL RS.	**375225**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT ANWAR ARAIN TO MALAK W.NO 10 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,180.00	6,187.50	%0 Cft.	19676
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,180.00	453.75	%0 Cft.	1443
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,335.60	9,416.28	% Cft.	125764
4	C.C. 1:2:4 for topping.	1,049.40	14,429.25	% Cft.	151421
				TOTAL RS.	298304

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING ATJATOI COLONY STREET W.NO 10 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,600.00	6,187.50	%0 Cft.	22275
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,600.00	453.75	%0 Cft.	1634
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,512.00	9,416.28	% Cft.	142374
5	C.C. 1:2:4 for topping.	1,188.00	14,429.25	% Cft.	171419
				TOTAL RS.	**337702**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT SADULLAH KALHORO STREET W.NO 10 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,080.00	6,187.50	%0 Cft.	19058
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,080.00	453.75	%0 Cft.	1398
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,293.60	9,416.28	% Cft.	121809
4	C.C. 1:2:4 for topping.	1,016.40	14,429.25	% Cft.	146659
				TOTAL RS.	**288923**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR ENGINEER/PROCURING AGENCY

CONSTRUCTION OF PAVER BLOCK AT VARIOUS PLACES W.NO 10 M.C MORO

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) Ratio: 1:2:4	130.00	14,429.25	% Cft.	18758
2	ement concereteBrick or Stone Ballast 1/2" to 2" gauge. 1:4:8	858.00	9,416.28	% Cft.	80792
3	Crush fix brick graded as band (G.S.(M) I 51 P. NO 16)	1,300.00	2,500.00	% Cft.	32500
4	Providing and fixing cement pavering block flooring having size (197x97x60) mmst city gudrra / cobble shape with natural clour. (G.S.I 71 P.NO .48)	2,600.00	199.77	% Cft.	519402
				TOTAL RS.	**651452**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT ANWAR ARAIN TO MALAK HOUSE W. NO 10 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,431.00	3,176.25	%0 Cft.	4,545
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	314.82	9,416.28	% Cft.	29,644
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	318.00	174.00	P. Rft.	55,332
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	715.50	11,948.36	% Cft.	85,491
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,431.00	2,206.60	% Sft.	31,576
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	400.68	337.00	P. Cft.	135,029
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	12.52	5,001.70	P.Cwt.	62,628
				TOTAL RS.	**404,246**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT SADIQ MUGHAL TO AL MUSTAFA SCHOOLW.NO 10 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	2,000.00	6,187.50	%0 Cft.	12375
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	2,000.00	453.75	%0 Cft.	908
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	840.00	9,416.28	% Cft.	79097
5	C.C. 1:2:4 for topping.	660.00	14,429.25	% Cft.	95233
				TOTAL RS.	**187612**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF PAVER BLOCK AT VARIOUS PLACES W.NO 11 M.C MORO

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Earth work excavation undressed lead upto extra one miles Kassi or Phawrah or Shovel in ordinary soil (G.S.I.NO. 1/B- P/1)	8,400.00	1,361.25	% Cft.	11435
2	Cement concrets brick or stone ballast 1 1/2" to 2" guage Ratio 1:4:8 G.S.I No: 4-P/15 (G.S.I.NO. 5/H- P/16	3,528.00	9,416.28	% Cft.	332206
3	Providing and fixing cement pavering block flooring having size (197x97x60) mmst city gudrra / cobble shape with natural clour. (G.S.I 71 P.NO .48)	8,400.00	223.97	% Cft.	1881348
				TOTAL RS.	**2224989**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT MASTER ABDUL HAKEEM RAHO W. NO 11 M.C MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	7,087.50	1,361.25	%0 Cft.	9,648
2	Dismatling C.C 1:2:4	787.50	3,327.50	% Cft.	26,204
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	787.50	9,416.28	% Cft.	74,153
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:2:4. (CSI No. 05, P. No. 17).	519.75	14,429.25	% Cft.	74,996
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	675.00	12,902.00	% Cft.	87,089
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	4,500.00	2,206.60	% Sft.	99,297
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	5.6250	5,001.70	P.Cwt.	28,135
				TOTAL RS.	**446,701**

I, M/s _____ do hereby quotes the rates _____ % above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT ABDUL KARIM RAHO STREET W.NO 11 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	5,200.00	6,187.50	%0 Cft.	32175
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	5,200.00	453.75	%0 Cft.	2360
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,184.00	9,416.28	% Cft.	205652
4	C.C. 1:2:4 for topping.	1,716.00	14,429.25	% Cft.	247606
				TOTAL RS.	**487792**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT MANTHAR KHASALI - MAHAR SHAHID MEMON HOUSE W.NO 11 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	8,450.00	6,187.50	%0 Cft.	52284
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	8,450.00	453.75	%0 Cft.	3834
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	2,788.50	9,416.28	% Cft.	262573
4	C.C. 1:2:4 for topping.	2,788.50	14,429.25	% Cft.	402360
				TOTAL RS.	**721051**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT HAJI SHAMER SOLANGI W. NO 11 M.C MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	7,875.00	5,431.25	%0 Cft.	42,771
2	Dismatling C.C 1:2:4	875.00	3,327.50	% Cft.	29,116
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	875.00	9,416.28	% Cft.	82,392
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:2:4. (CSI No. 05, P. No. 17).	577.50	14,429.25	% Cft.	83,329
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	750.00	12,902.00	% Cft.	96,765
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	5,000.00	2,206.60	% Sft.	110,330
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	6.7500	5,001.70	P.Cwt.	33,761
				TOTAL RS.	**525,645**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT ALI GUL SOLANGI W.NO 12 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,000.00	6,187.50	%0 Cft.	18563
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,000.00	453.75	%0 Cft.	1361
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,260.00	9,416.28	% Cft.	118645
5	C.C. 1:2:4 for topping.	990.00	14,429.25	% Cft.	142850
				TOTAL RS.	**281418**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT SHAMAN SOLANGI TO BHATTI HOUSE BACK SIDE OF ANIMAL HUSBANDARI W.NO 12 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	6,000.00	6,187.50	%0 Cft.	37125
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	6,000.00	453.75	%0 Cft.	2723
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,980.00	9,416.28	% Cft.	186442
5	C.C. 1:2:4 for topping.	1,500.00	14,429.25	% Cft.	216439
				TOTAL RS.	**442729**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT HADI LAGHARI W.NO 12 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	3,300.00	6,187.50	%0 Cft.	20419
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	3,300.00	453.75	%0 Cft.	1497
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,386.00	9,416.28	% Cft.	130510
5	C.C. 1:2:4 for topping.	1,089.00	14,429.25	% Cft.	157135
				TOTAL RS.	**309560**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT LATUFULLAH BUGHIO W.NO 12 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	2,400.00	6,187.50	%0 Cft.	14850
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	2,400.00	453.75	%0 Cft.	1089
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,008.00	9,416.28	% Cft.	94916
5	C.C. 1:2:4 for topping.	792.00	14,429.25	% Cft.	114280
				TOTAL RS.	**225135**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

PROVIDING OF EARTH WORK AT VARIOUS PLACES W. NO 12 M.C MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	93,600.00	6,187.50	%0 Cft.	579150
2	Deressing and leveling of Earth Work to Designed Section .	93,600.00	96.80	%0 Cft.	9060
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	93,600.00	453.75	%0 Cft.	42471
				TOTAL RS.	**630681**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN ATSHAMAN SOLANGI HOUSE TO BHATTI HOUSE BACK SIDE ANIMAL HUSBOUNDARI W. NO 12 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,875.00	3,176.25	%0 Cft.	5,955
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	412.50	9,416.28	% Cft.	38,842
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	500.00	174.00	P. Rft.	87,000
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,125.00	11,948.36	% Cft.	134,419
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	2,250.00	2,206.60	% Sft.	49,649
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**384,927**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT SANAULLAH BUGHIO STREET W. NO 12 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	937.50	3,176.25	%0 Cft.	2,978
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	206.25	9,416.28	% Cft.	19,421
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	250.00	94.00	P. Rft.	23,500
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	562.50	11,948.36	% Cft.	67,210
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,125.00	2,206.60	% Sft.	24,824
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	120.00	337.00	P. Cft.	40,440
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	3.75	5,001.70	P.Cwt.	18,756
				TOTAL RS.	**197,129**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT GHULLAM HUSSAIN MALLAH STREET NO 12 MORO.					W.
SCHEDULE - B					
S.NO.	**NAME OF ITEM**	**QTY**	**RATE**	**UNIT**	**AMOUNT**
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,507.50	3,176.25	%0 Cft.	4,788
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	331.65	9,416.28	% Cft.	31,229
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	335.00	174.00	P. Rft.	58,290
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	753.75	11,948.36	% Cft.	90,061
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,507.50	2,206.60	% Sft.	33,264
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**286,695**

I, M/s _____ do hereby quotes the rates _____ % above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT GACHERO ROAD RAOF SOLANGI W. NO 12 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,350.00	3,176.25	%0 Cft.	4,288
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	297.00	9,416.28	% Cft.	27,966
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	300.00	174.00	P. Rft.	52,200
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	675.00	11,948.36	% Cft.	80,651
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,350.00	2,206.60	% Sft.	29,789
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**263,957**

I, M/s _____ do hereby quotes the rates _____ % above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT ATIF PANJAPI STREET W. NO 12 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,350.00	3,176.25	%0 Cft.	4,288
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	297.00	9,416.28	% Cft.	27,966
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	300.00	174.00	P. Rft.	52,200
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	675.00	11,948.36	% Cft.	80,651
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,350.00	2,206.60	% Sft.	29,789
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**263,957**

I, M/s _____ do hereby quotes the rates _____ % above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT ASGHAR FOJI STREET W. NO 12 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	937.50	3,176.25	%0 Cft.	2,978
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	206.25	9,416.28	% Cft.	19,421
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	250.00	94.00	P. Rft.	23,500
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	562.50	11,948.36	% Cft.	67,210
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,125.00	2,206.60	% Sft.	24,824
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	120.00	337.00	P. Cft.	40,440
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	3.75	5,001.70	P.Cwt.	18,756
				TOTAL RS.	197,129

I, M/s _____ do hereby quotes the rates _____ % above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CROSS AT VARIOUS PALCES OF W. NO 12 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	756.00	3,176.25	%0 Cft.	2,401
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	166.32	9,416.28	% Cft.	15,661
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	378.00	11,948.36	% Cft.	45,165
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	756.00	2,206.60	% Sft.	16,682
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	313.20	337.00	P. Cft.	105,548
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	9.79	5,001.70	P.Cwt.	48,954
				TOTAL RS.	**234,411**

I, M/s _____ do hereby quotes the rates _____% above / below

the rates of CSR in Words: (_____)

to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT ALI NAWAZ KALHORO STREETI W. NO 12 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	900.00	3,176.25	%0 Cft.	2,859
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	198.00	9,416.28	% Cft.	18,644
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	200.00	174.00	P. Rft.	34,800
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	450.00	11,948.36	% Cft.	53,768
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	900.00	2,206.60	% Sft.	19,859
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	140.00	337.00	P. Cft.	47,180
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	4.38	5,001.70	P.Cwt.	21,882
				TOTAL RS.	**198,992**

I, M/s _____ do hereby quotes the rates _____ % above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT GHULLAM ABBAS TO GHULLAM NABI W. NO 12 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	375.00	3,176.25	%0 Cft.	1,191
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	123.75	9,416.28	% Cft.	11,653
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	150.00	94.00	P. Rft.	14,100
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	225.00	11,948.36	% Cft.	26,884
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	675.00	2,206.60	% Sft.	14,895
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	126.00	337.00	P. Cft.	42,462
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	3.94	5,001.70	P.Cwt.	19,694
				TOTAL RS.	**130,878**

I, M/s _____ do hereby quotes the rates _____ % above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT GHULAB SHAITO TO MIR MAZAN CHANDIO W. NO 13 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	2,250.00	3,176.25	%0 Cft.	7,147
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	495.00	9,416.28	% Cft.	46,611
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	500.00	174.00	P. Rft.	87,000
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,125.00	11,948.36	% Cft.	134,419
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	2,250.00	2,206.60	% Sft.	49,649
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	126.00	337.00	P. Cft.	42,462
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	3.94	5,001.70	P.Cwt.	19,694
				TOTAL RS.	**386,981**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF PAVER BLOCK AT BHATTI SHOP TO NAFO NAWAL W.NO 13 M.C MORO

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSl No. 05, P. No. 17) Ratio: 1:2:4	60.00	14,429.25	% Cft.	8658
2	ement concereteBrick or Stone Ballast 1/2" to 2" gauge. 1:4:8	554.40	9,416.28	% Cft.	52204
3	Crush fix brick graded as band (G.S.(M) I 51 P. NO 16)	840.00	2,500.00	% Cft.	21000
4	Providing and fixing cement pavering block flooring having size (197x97x60) mmst city gudrra / cobble shape with natural clour. (G.S.I 71 P.NO .48)	1,680.00	199.77	% Cft.	335614
				TOTAL RS.	**417475**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT PUNHAL KORI TO YASEEN KORAI W.NO 13 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	6,300.00	6,187.50	%0 Cft.	38981
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	6,300.00	453.75	%0 Cft.	2859
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	882.00	9,416.28	% Cft.	83052
5	C.C. 1:2:4 for topping.	693.00	14,429.25	% Cft.	99995
				TOTAL RS.	**224886**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT PORHO MALLAH NEAR SIYAL MUHALLAH W. NO 13 M.C MORO.					
SCHEDULE - B					
S.NO.	**NAME OF ITEM**	**QTY**	**RATE**	**UNIT**	**AMOUNT**
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	1,355.00	5,431.25	%0	7,359
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	447.15	9,416.28	% Cft.	42,105
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:2:4. (CSI No. 05, P. No. 17).	270.48	14,429.25	% Cft.	39,028
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	5,472.50	12,902.00	% Cft.	706,062
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	4,161.00	2,206.60	% Sft.	91,817
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	237.24	337.00	P. Cft.	79,950
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	9.5300	5,001.70	P.Cwt.	47,677
				TOTAL RS.	**1,013,998**

I, M/s _____ do hereby quotes the rates _____ % above / below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT MEHBOB HAB SHOP TO HASSAN CHANDIO W.NO 13 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	5,600.00	6,187.50	%0 Cft.	34650
3	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	5,600.00	453.75	%0 Cft.	2541
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,176.00	9,416.28	% Cft.	110735
5	C.C. 1:2:4 for topping.	924.00	14,429.25	% Cft.	133326
				TOTAL RS.	**281253**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT RUSTMANI TO ASAD KHOSO W. NO 13 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	875.00	3,176.25	%0 Cft.	2,779
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	288.75	9,416.28	% Cft.	27,190
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	350.00	94.00	P. Rft.	32,900
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	2,712.50	11,948.36	% Cft.	324,099
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	700.00	2,206.60	% Sft.	15,446
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	126.00	337.00	P. Cft.	42,462
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	3.94	5,001.70	P.Cwt.	19,694
				TOTAL RS.	**464,570**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT SAGEER BHUTTO TO ZULFQAR BHATTI W. NO 13 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	875.00	3,176.25	%0 Cft.	2,779
2	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering RATIO 1:4:8. (CSI No. 05, P. No. 17).	288.75	9,416.28	% Cft.	27,190
3	Construction of standard open drain cunette block of cement concret (1:2:4) cost in situ to design profile i/c cost of mold as per drawing i/c applying floating coat of cement 1/32 thick be the exposed face finished along with curring etc. complete as per detail drawing Type1-2	350.00	94.00	P. Rft.	32,900
4	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	1,837.50	11,948.36	% Cft.	219,551
5	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	700.00	2,206.60	% Sft.	15,446
6	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	126.00	337.00	P. Cft.	42,462
7	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	3.94	5,001.70	P.Cwt.	19,694
				TOTAL RS.	**360,022**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF SURFACE DRAIN AT GHARO ROAD W. NO 13 MORO.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building and other structurs including dag belling dressing reflling around the structure with excavated earth watering and remmaing lead up to 5" (b) in ordinory soil (C.S.I.No. 18-B P. No: 5).	750.00	3,176.25	%0 Cft.	2,382
2	Pacca brick work in foundation and plainth cement sand mortor (C.S.I. No: 4 P. No: 22).	375.00	11,948.36	% Cft.	44,806
3	Cement plaster 1:4 upto 20" hight 1/2 thick (C.S.I. No: 11 P. No: 53)	1,125.00	2,206.60	% Sft.	24,824
4	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	126.00	337.00	P. Cft.	42,462
5	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	3.94	5,001.70	P.Cwt.	19,694
				TOTAL RS.	**134,169**

I, M/s _____ do hereby quotes the rates _____% above/ below the rates of CSR in Words: (_____)
to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT MEHBOB SOLANGI TO ALLAHYAR SCHOOL AND GADA HOUSE UMRANI TO RASHEED UMRANI M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	8,280.00	6,187.50	%0 Cft.	51233
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	8,280.00	453.75	%0 Cft.	3757
3	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	3,477.60	9,416.28	% Cft.	327461
4	C.C. 1:2:4 for topping.	2,732.40	14,429.25	% Cft.	394265
				TOTAL RS.	**776715**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF R.C.C COVERED NALA AT GACHERO CHOWK M.C MORO.					
SCHEDULE - B					
S.NO.	**NAME OF ITEM**	**QTY**	**RATE**	**UNIT**	**AMOUNT**
1	RCC work including all labour and material except the cost of steel reinforcement and its labour for banding ands lintels and other structural members laid in situ or present laid in position complete in all respects.RATIO 1:2:4 (C.S.I.No: 6P. No: 29	507.75	337.00	P. Cft.	171,112
2	Fabrication mild steel reinforcement concret for cc i/c cutting bending laying in podsition makinmg joints and fasting including cost of binding wire i/c removal of rust from bars (ration 1:2:4).(C.S.I.No: 7 P. No:,19)	15.8700	5,001.70	P.Cwt.	79,363
				TOTAL RS.	**250,475**

I, M/s _____ do hereby quotes the rates _____% above/

below the rates of CSR in Words: (_____)

to be added/deducted on the basis of Premium quoted

Rs._____

Total Rs._____

Total (a) Rs._____

Total (b) Rs._____

Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

CONSTRUCTION OF CC TOPPING AT MIDWAY HOTEL TO TARIQ ZARDARI HOUSE W.NO 5 M.C MORO TOWN.

SCHEDULE - B

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Borrow pit excavation undressed lead upto 100' (a) in ordinary soil (CSI No. 3, P. No. 1)	4,320.00	6,187.50	%0 Cft.	26730
2	Earth Work compaction (soft, ordinary or very hard soil) (d) ramming earth work all types of soil. (CSI NO. 13 P. No. 3)	4,320.00	453.75	%0 Cft.	1960
4	Cement concerete plain i/c placing, compacting, finishing & curing complete i/c screeing and washing of stone aggregrate without shuttering (CSI No. 05, P. No. 17) RATIO. 1:4:8	1,814.40	9,416.28	% Cft.	170849
4	C.C. 1:2:4 for topping.	1,425.60	14,429.25	% Cft.	205703
				TOTAL RS.	**405243**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

DETAILED WORKING ESTIMATE FOR PROVIDING LAYING JOINTING AND TESTING RCC SEWER LINE 18" DIA AND MAIN HOLE AT GACHERO CHOWK W.NO 9 MORO.

SCHEDULE - B -II

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excation for pipe line in trenches and pits in soft soil i/c termming and dressing sides to true aligment shape leveling st beds stcorrect level surpls earth within a one chain is directed by engineer incharge	2,677.50	3600.00	%0 Cft.	9,639
2	Stone Crushed graded 1" ing .(C.S.I.No: 77 P. No:,05).	535.50	9416.28	% Cft.	50,424
3	Providing RCC Pipe at ASTEMC-76-62 TC-7-70 Class B wall and fixing in trenches I/C cutting filling and jointing with rubber jesting fwith water to spcified presure (P.H.S.I. No: 1 P.NO: 8).	306.00	618.00	% Cft.	189,108
4	Reflling excavated stuff in treaches as 6" thick layers j/c watering remaning to full compaction etc comlete (P.H.S.I. No: 24 P.NO:77).	2,409.75	2760.00	% Cft.	6,651
	MAIN HOLES				**255,822**
1	Dismatling and removing Road mantling (C.S.I.No. 51-P. No:13).	346.19	605.00	%0 Cft.	2,094
2	Excation in foundation building bridge and other structure i/c dressing opening awarded the structure with ecavatedearth watering and remaning etc complete lead upto chain till upto (P.H.S.I. NO. 18	1,153.95	3,176.25	% Cft.	3,665
3	Extra for wet earth work (P.H.S.I. No: 15 P.NO: 04).	461.58	1058.75	%0 Cft.	489
4	Cement Concrete Plain 1:4:8 (P.H.S.I. No: 1 P.NO: 46). 5	115.40	9416.28	% Cft.	10,866
6	Earaction and Removal of Conting for RCC or plain cement concrete work part wood (P.H.S.I. No: 19	94.80	3,127.41	P. Cft.	2,965
7	RC C.1:2:4 Ratio (1:2:4) for Circular Main Hole	275.54	337.00	P.Cwt.	92,855
8	Fabrication of Mild Steel (C.S.I.No: 77 P. No:,05).	11.07	5,001.70	P.Cwt.	55,372
9	Providing fixing CI Main Hole Frame I/c Cost of	11.81	6,985.00	P.Cwt.	82,473
10	Providing and fixing pre cost RCC Main Hole Cover in Ratio (1:2:4) deep revts for concrete with 1/2 dia for steel bars 3" contec to contect (R.A Approval)	6.00	1,051.25	P.Cwt.	6,308
11	Rehandling of Earth Extra for every 50' additional lead is part there of ordinary soil (P.H.S.I. No: 08 P.NO:3).	750.07	502.50	P % Cft.	3,769

TOTAL RS. 260,856

/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY

PROVIDING LAYING JOINTING AND TESTING RCC SEWER LINE 12" DIA MIDWAY HOTEL TO TARIQ ZARDARI W.NO.5 MORO.

SCHEDULE - B -II

S.NO.	NAME OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Excation for pipe line in trenches and pits in soft soil i/c termming and dressing sides to true aligment shape leveling st beds stcorrect level surpls earth within a one chain is directed by engineer incharge	3,071.25	3600.00	%0 Cft.	11,057
2	Stone Crushed graded 1" ing .(C.S.I.No: 77 P. No:,05).	614.25	9416.28	% Cft.	57,839
3	Providing RCC Pipe at ASTEMC-76-62 TC-7-70 Class B wall and fixing in trenches I/C cutting filling and jointing with rubber jesting fwith water to spcified presure (P.H.S.I. No: 1 P.NO: 8).	351.00	412.00	Rft.	144,612
4	Reflling excavated stuff in treaches as 6" thick layers j/c watering remaning to full compaction etc comlete (P.H.S.I. No: 24 P.NO:77).	2,764.13	2,760.00	%0 Cft.	7,629
	MAIN HOLES				**221,137**
1	Dismatling and removing Road mantling (C.S.I.No. 51-P. No:13).	519.28	605.00	%0 Cft.	3,142
2	Excation in foundation building bridge and other structure i/c dressing opening awarded the structure with ecavatedearth watering and remaning etc complete lead upto chain till upto (P.H.S.I. NO. 18	1,730.93	3,176.25	% Cft.	5,498
3	Extra for wet earth work (P.H.S.I. No: 15 P.NO: 04).	692.37	1058.75	%0 Cft.	733
4	Cement Concrete Plain 1:4:8 (P.H.S.I. No: 1 P.NO: 46). 5	173.09	9416.28	% Cft.	16,299
6	Earaction and Removal of Conting for RCC or plain cement concrete work part wood (P.H.S.I. No: 19	142.20	3,127.41	P. Cft.	4,447
7	RC C 1:2:4 Ratio (1:2:4) for Circular Main Hole	423.90	337.00	P.Cwt.	142,854
8	Fabrication of Mild Steel (C.S.I.No: 77 P. No:,05).	17.03	5,001.70	P.Cwt.	85,187
9	Providing fixing CI Main Hole Frame I/c Cost of	17.71	6,985.00	P.Cwt.	123,709

0	,Providing and fixing pre cost RCC Main Hole Cover in Ratio (1:2:4) deep revts for concrete with 1/2 dia for steel bars 3" contec to contect (R.A Approval)	9.00	1,051.25	P.Cwt.	9,461
11	Rehandling of Earth Extra for every 50' additional lead is part there of ordinary soil (P.H.S.I. No: 08 P.NO:3).	1,125.10	502.50	P % Cft.	5,654
				TOTAL RS.	**396,985**

I, M/s _____ do hereby quotes the rates _____% above / below the rates of CSR in Words: (_____) to be added/deducted on the basis of Premium quoted

Rs._____
Total Rs._____
Total (a) Rs._____
Total (b) Rs._____
Grand Total Rs._____

CONTRACTOR

ENGINEER/PROCURING AGENCY