


**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DISTRICT CENTRAL,
SCHOOL EDUCATION & LITERACY DEPARTMENT GOVERNMENT OF SINDH,
KARACHI.**

Tender form issued to M/S. _____, Government Contractor, and
charged Rs. _____ Vide D.R. No. _____, Dated: _____


**EXECUTIVE ENGINEER
EDUCATION WORKS DISTRICT CENTRAL
KARACHI**

NAME OF WORK:- **CONSTRUCTION OF SPORTS STADIUM/ STADIA IN KARACHI (5 UBNITS)
@ GULBERG KARACHI. (REMAINING WORK).**

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the under written memorandum within the time modified in each memorandum at:

Part-A: Rs. _____

Part-B: Rs. _____

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

i).	Estimated Cost	:-	15000000/-
ii).	Earnest Money 5%	:-	750000/-
iii).	Security Deposit (8%) in/c Earnest Money (2%) Total (10%)	:-	1500000/-
iv).	Income Tax (7.50%)	:-	1125000/-
v).	Time allowed for completion of work	:-	24 Months

**EXECUTIVE ENGINEER
EDUCATION WORKS DISTRICT CENTRAL
KARACHI**

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

- i) **Schedule-A:** Nil
ii) **Schedule-B:** Attached herewith

(SIGNATURE OF CONTRACTOR)

Schedule - B (Civil)

NAME OF WORK :- Construction of Sports stadium / Stadia in Karachi (05 Nos) in Karachi at Gulberg Town, Karachi (Remaining Work) (ADP No:2356 / 2017-2018)

S No	Description of Item	Qty	Rate	Unit	Amount
Schedule Items					
1	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle (a) RCC work in roof slab, beams, columns, rafts, and other structural members laid in situ or precast laid in position. Completed in all respect (i) Ration 1:2:4 90 lbs.	4218.41	337.00	P Cft	1421605.00
2	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle (a) RCC work in roof slab, beams, columns, rafts, and other structural members laid in situ or precast laid in position. Completed in all respect (i) Ration 1:1-1/2:3 90 lbs.	1046.16	349.00	P Sft	365110.00
3	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust Using Tor bars (P-17/8-b)	282.03	5001.70	P Cwt	1410633.00
4	Providing and laying 1 : 3 : 6 Cement concrete solid Block masorany wall above 6" in thickness set In 1:6 cement mortar in G.F ground floor superstructure including raking out joints & curing etc, complete (P.19/23)	4817.37	14621.44	% Cft	704369.00
5	Providing and laying 1 : 3 : 6 cement concrete solid block masonry wall 6" and below in thickness set in 1 : 6 cement mortar in ground floor Super Structure including raking out joints & curring etc, complete (P-19/24)	1150.79	15771.01	% Cft	181491.21
6	Excavation in foundation of Building Bridges and other structures including dagbelling dressing, refilling around structure with excavated earth Watering lead upto 5ft. In ordinary soil (P-4/18-b)	11696.00	3176.25	%0 Cft	37149.42
7	Cement concrete brick or stone 1 1/2" to 2" gauge, Ration 1:3:6 (P-15/4-b)	5886.00	9416.25	% Cft	554240.48
8	Erection and removal of centering for Reinforced concrete works of deodar wood (2nd class). (a) vertical (S.I.No. 18(ii)/C-4)	11696.00	3127.41	% Cft	365781.87
9	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering. 1:3:6(P-16/5-h)	3918.16	12595.00	% Cft	493492.25
10	Providing & Fixing Precast Edge Block 3750 PSI Industrial Made Size 6 Inches thick x 12 Inches long x 12 Inches High including the cost of Cartage, excavation, from Work for haunching, 1450 PSI lean concrete for haunching, 1 : 4 cement sand mortar (Kerb Stone) (P.No: 16/14) (Public Highways Works Schedule or Rates)	2924.00	297.01	P Rft	868457.24
11	Providing & Fixing cement paving blocks flooring having size of 197 x 97 x 80 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 psi l/c filling the joints with hill sand and laying in specifited manner / patter and design etc; completed. (P-50/74)	5924.00	248.17	P Sft	1470159.08
12	Cement plaster 1:4 upto 20 height 3/4" (S.I.No: 11-c/C-9)	53740.24	3191.76	% Sft	1715259.48

CHECKED
RAFTSMAN
 Education Works District Central
 Karachi