

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DISTRICT CENTRAL,
SCHOOL EDUCATION & LITERACY DEPARTMENT GOVERNMENT OF SINDH,
KARACHI.**

Tender form issued to M/S. _____, Government Contractor, and
charged Rs. _____ Vide D.R. No. _____, Dated: _____


EXECUTIVE ENGINEER
EDUCATION WORKS DISTRICT CENTRAL
KARACHI

NAME OF WORK:- **CONSTRUCTION OF SPORTS STADIUM/ STADIA IN KARACHI (5 UBNITS)
@ NEW KARACHI. (REMAINING WORK).**

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the under written memorandum within the time modified in each memorandum at:

Part-A: Rs. _____

Part-B: Rs. _____

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

i).	Estimated Cost	:-	15000000/-
ii).	Earnest Money 5%	:-	750000/-
iii).	Security Deposit (8%) in/c Earnest Money (2%) Total (10%)	:-	1500000/-
iv).	Income Tax (7.50%)	:-	1125000/-
v).	Time allowed for completion of work	:-	24 Months

EXECUTIVE ENGINEER
EDUCATION WORKS DISTRICT CENTRAL
KARACHI

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

- i) Schedule-A: Nil
ii) Schedule-B: Attached herewith

(SIGNATURE OF CONTRACTOR)

SCHEDULE - B

NAME OF WORK:-

CONSTRUCTION OF SPORTS STADIUM / STADIA AT NEW KARACHI TOWN (EXTERNAL DEVELOPMENT).

S.No	Description.	Quantity	Rate	Unit	Amount
SCHEDULE WORK					
1	Excavation in foundation of building bridges and other structure i/c degabilling dressing refilling, around structure with excavated earth waterig and ramming lead upto 5 ft in ordinary soil (s.i.no:18-b/p-5).	8135.00	@Rs 3176.25	%0Cft	25,839.00
2	RANDOM RUBBLE MASONARY (UNCOURSED) DRY MASONARY(S.I.I-a/31)	2515.00	@Rs 13051.50	% Cft	328,245.00
3	Cement concrete brick or stone ballast 1.5" to 2" gauge (b) Ratio 1:4:8. (S.I.No. 15/4-b)	10137.00	@Rs 9416.28	% Cft	954,528.00
4	CEMENT CONCRETE PLAIN IN/C PLACING COMPACTING FINISHING CURING COMPLETE & SCREENING & WASHING OF STONE AGGREGATE WITHOUT SHUTTERING RATIO 1:3:6 (S.I.NO.5-H P-18).	4232.00	@Rs 12595.00	% Cft	533,020.00
5	Filling watering and ramming new earth from out side lead upto one chain and lift upto 5 feet (S.I.4/22)	50912.00	@Rs 3630.00	%0 Cft	184,811.00
7	ERRECTION & REMOVAL OF VERTICAL CENTERING FOR R.C.C PLAIN OR CEMENT CONCRETE WORK OF PARTAL WOOD (2ND CLASS) (S.I.18-B/P-21).	9216.00	@Rs 3127.41	% Sft	288,222.00
8	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which is to be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs. (S.I.No. 16-a-ii/P-17)	1535.00	@Rs 337.00	P Cft	517,295.00
9	Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding wire (also includes removal of rust from bars. (S.I.No. 17/8-b)	95.94	@Rs 5001.70	P.Cwt	1,235,170.00
10	CEMENT PLASTER 1:4 UPTO 20 HEIGHT (C) 3/4" THICK. (S.I.NO.11-c/P-52)	7612.00	@Rs 3015.76	%Sft	229,559.65
11	M/F STEEL GRATED DOOR WITH 1/16" THICK SHEETING I/C ANGLE IRON FRAME 2"X2"3/8" AND 3/4" SQUARE BAR 4" C/C WITH LOCKING ARRAGEMENT (S.I.NO.24/P-92)	224.00	@Rs 726.72	P.sft	162,785.28
12	Providing and Laying 1:3:6 cement concrete Block Masonary set in 1:6 cement sand mortor in Plinth and Foundation including racking out joints. (S.I.No.22/P-19)	493.33	@Rs 14268.53	% Cft	70,391.00
13	Split tile 1/4"thick matt glazed or double glazed jointed in white cement and lead over 1:2 grey cement sand mortar 3/4"thick in/c finishing complete (Flooring and Facing)(S.I.49/69)	10132.00	@Rs 21021.11	% Sft	2,129,859.00
14	Painting new surface and painting gurd bars, gates of iron bars, gratings, railings (in/c standard braces, etc) 3 coats. (S I No 4-d/P70).	1137.00	@Rs 1645.27	% Sft	18,707.00

- 15 P/F cement Paving Blocks Flooring Hanving of 197x97x80 mm of city / quddra / cobble shape with natural colour, having strength b/w psi 5000 to 8500 psi in/c filling the joints with hill sand and laying In specific manner / patteren and design etc complete.

22336.00 @Rs 248.17 P.sft 5,543,125.00

- 16 P/F precast edging block 3750 PSI industrial made size 6 inch thike x 12 inch long x 12 inch hight in/c the cost of cartage,excavation from work for haunching,1450 PSI lean concrete,2250 PSI concrete for haunching,1:4 cement sand mortor (S.I.16/14) (Highway Shedule)

4500.00 @Rs 297.01 P.Rft 1,336,545.00

Total 13,558,101.93

CHECKED
DRAFTSMAN
Education Works District (Central)
Karachi

EXECUTIVE ENGINEER
EDUCATION WORKS DISTRICT CENTRAL
GOVT. OF SINDH KARACHI

NAME OF WORK:-

**CONSTRUCTION OF SPORTS STADIUM / STADIA AT
NEW KARACHI TOWN (EXTERNAL DEVELOPMENT).**

S.No	Description.	Quantity		Rate	Unit	Amount
------	--------------	----------	--	------	------	--------

NON SCHEDULE WORK

- 1 Add Lead Upto 10 Miles. (R.A.Approved)

CHECKED
C. L. Khan
DRAFTSMAN
Education Works District (Central)
Karachi

50912.00 @Rs 1065.00 % Cft 542,213.00

Total 542,213.00

Shahin Khan
EXECUTIVE ENGINEER
EDUCATION WORKS DISTRICT CENTRAL
GOVT. OF SINDH KARACHI
Ag