


## BILL OF QUANTITIES (C)

**Name of Work:-** CEMENT CONCRETE LINING OF PURAN DISTRY FROM RD-49.300 TO 135.5  
CONSTRUCTION OF HEAD REGULATOR & OUTLETS

S. No.	Description	Unit	Quantity	Rate (Rs)		Amount (Rs)
				Figure	Words	
1	Dismantling brick work in lime or Cement mortor	%Cft	33,119.30			
2	Dismantling reinforced cement concrete separating reinforcement from cement concrete cleaning and straightening the same.	%Cft	6,636			
3	Excavation in Foundation of building bridges and other strutures including dag-belling dressing refilling around struture with excavated eath watering and ramming lead up to 5 ft. (b) in ordinary soil.	%0Cft	242,041			
4	Cement Concrete Plain including Placing compaction, finishing and washing of stone aggregate without shuttering Ratio 1:3:6	%Cft	30,918.5			
5	Cement Concrete Plain including Placing compaction, finishing and washing of stone aggregate without shuttering Ratio 1:2:4	%Cft	66,102.63			
6	Pacca brick work in foundition and plinth in cement sand mortar ratio 1:4	%Cft	49,740.0			
7	Pacca brick work other than building, including striking of joints up to 20 feet height (a) cemend sand mortar ration 1:4	%Cft	90,235.0			
8	Reinforcement cement concrete work i/c all labour and material except the cost of steel reinfoerment ans its labour for its bending & binding which will be paid separately. this rate also i/c all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface and washing for shingle Ratio 1:2:4	Per Cft	18,299.96			
9	Febrication of mild steel reinforcement for cement concrete i/c cutting, bending wire (aslo includes removal of rust from bars)	P.Cwt	2,157.32			
10	Cement Plaster 1:4 up to 20 feet height 1/2" thick (P-52, I-11 b)	%Cft	48,299.0			
11	Cement Plaster 1:3 up to 20 feet height 3/8" thick	%Cft	48,299.0			
12	Erection and removal fo centering for R.C.C or plain cement concret works Partal Wood (2nd Class) for partial wood ( i ) Vertical	%Sft	9,165.4			
13	Providing and Fixing steel fram / APM block	Each	80.0			
14	Providing and Fixing steel Gate Complete Accessories	Per Sft	191.3			
Total of Head Regulator & Outlets Rs:-						

  
**Executive Engineer**  
 Jamrao Division Mirpurkhas