

SCHEDULE - B.

Name of Work:- ADP.136 PROVIDING OF MISSING FACILITIES IN VARIOUS EXISTING SCHOOLS IN DISTRICT BADIN.(2012-13 PROGRAMME) @ GBPS NAZAR HUSSAIN KHOSO (C/WALL) TALUKA MATLI DISTRICT BADIN.

S.No	Description.	Qty.	Rate.	Unit.	Amount.
------	--------------	------	-------	-------	---------

PART - A CIVIL WORK (i).

- 1 Excavation in foundation of building bridges and other structure i/c dagbelling dressing, refilling around the structure with excavated earth watering and ramming lead upto 5 feet, (b) In ordinary soil. (S.I.No.18.b/P-4).

TOTAL 336.00 3176.25 %Cft Rs. **1067**

(Rs.Three thousand one hundred seventy six & ps twenty five only).

- 2 Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I.No:- 4.C/P-15).

TOTAL 86.00 8694.95 %Cft Rs: **7478**

(Rs.Eight thousand six hundred ninety four & ps ninety five only).

- 3 R.C.C. work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sperately. This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle)(a) R.C.work in roof slab, beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect(I) Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to

TOTAL 477.00 337.00 P/Cft Rs: **160749**

(Rs.Three hundred thirty seven & ps zero only).

- 4 (a) Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position, making joints and fastening i/c cost of binding wire (also i/c removal of (b) using Tor Bars) (S.I.No:8-(a)+(b)/P-17).

a) Using Tor Bar

TOTAL 21.29 5001.70 P/Cwt Rs: **106486**

(Rs.Five Thousand one & ps seventy only).

b) Using Mild Steel

TOTAL 4.25 4820.20 P/Cwt Rs: **20486**

(Rs.Four Thousand eight hundred twenty & ps twenty only).

- 5 Pacca brick work other than building i/c striking of joints upto 20 feet height in cement sand mortar ratio 1:6 (S.I.No: 7,(I)(e) /P-22).

TOTAL 488.00 12346.65 %Cft Rs: **60252**

(Rs.Twelth thousand three hundred fourty six & ps sixty five only).

6. Cement plaster 1:6 upto 12' ft height 1/2" thick. (S.I.No.13(b) /P-52)

TOTAL	<u>1383.00</u>	2206.60	%Sft	Rs:	30517
--------------	----------------	---------	------	-----	--------------

(Rs.Two Thousand two hundred six & ps sixty only).

7. Cement plaster 1:4 upto 12' ft height 3/8" thick. (S.I.No.11(a) /P-52)

TOTAL	<u>1383.00</u>	2197.52	%Sft	Rs:	30392
--------------	----------------	---------	------	-----	--------------

(Rs.Two Thousand one hundred ninty seven & ps fifty two only).

8. Cement plaster 1:4 upto 12' ft height 3/4" thick. (S.I.No.11(c) /P-52)

TOTAL	<u>150.00</u>	3015.76	%Sft	Rs:	4524
--------------	---------------	---------	------	-----	-------------

(Rs.Three Thousand fifteen & ps seventy six only).

9. Extra labour rate for making cement plaster pattas/band around straight or carved openings and around the edges of roof slabs, the width not less than 6" with fine finishing as directed by Engineer Incharge.(S.I.No.35/P-55)

TOTAL	<u>300.00</u>	19.36	P/Rft	Rs.	5808
--------------	---------------	-------	-------	-----	-------------

(Rs.Ninteen & ps thirty six only).

10. Cement pointing struck joints on walls ratio 1:2 (S.I.No.19(a)/P-53).

TOTAL	<u>1156.00</u>	1287.44	%Sft	Rs:	14883
--------------	----------------	---------	------	-----	--------------

(Rs.One Thousand two hundred eighty seven & ps fourty four only).

11. Making & fixing steel grated door with 1/16" thick sheeting l/c angle iron frame 2"x2"and 3/4" square bars 4" center to center with locking arrangmant (S.I.No.24/P-92)

TOTAL	<u>60.00</u>	726.72	P/Sft	Rs:	43603
--------------	--------------	--------	-------	-----	--------------

(Rs.Seven hundred twenty six & ps seventy two only).

12. Primary coat of chalk under distemper (S.I.No.23/P-54).

TOTAL	<u>3673.00</u>	442.75	%Sft	Rs:	16262
--------------	----------------	--------	------	-----	--------------

(Rs.Four hundred fourty two & ps seventy five only).

13. Distemper three coats.(S.I.No.24(c) /P-54).

TOTAL	<u>3673.00</u>	1079.65	%Sft	Rs:	39656
--------------	----------------	---------	------	-----	--------------

(Rs.One thousand seventy nine & ps sixty five only).

- 14 Painting new surface (d) preparing surface and painting guard bars. gates of iron bars, gratings, railings (i/c standards braces, etc.) and similar open work. (S.I.No.5(d) i,ii

TOTAL	<u>120.00</u>	1270.83	%Sft	Rs.	1525
--------------	---------------	---------	------	-----	-------------

(Rs. One Thousand two hundred seventy & ps eighty three only).

TOTAL:-	RS:	543680
----------------	------------	---------------