

SUBJECT :- PROVIDING AND LAYING 6"DIA PIPE FROM C-1 TO D-8 BLOCK-04 FOR IMPROVEMENT OF WATER SUPPLY OF GULBERG TOWN.

SL. NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words		
5	Providing & fixing M.S. split collar on PRCC pipe 18" wide fabricated with 3/8" thick M.S. plat 1 1/4 wide 3/8" thick ring at centre, 3/4" thick M.S. Squire bars on both ends with a total weight as mentioned against each item. It includes the cost of 4 Nos. 3/4" thick flanges, nut bolts, rubber packing labor, sealing material etc. 24" dia	01 No.			Each	
6	Providing & fixing 0-9" long 3/8" thick M.S. neck to existing M.S pipe of to a split collar tee having a total weight as mentioned against each item. It include the cost of fabrication and welding to the split collar tee. 6" dia	01 No.			Each	
7	C.I. sluice valve heavy pattern (Test pressure) 21.0 Kg/sq.com or 300 lb Sq. inch (imported). 6" dia	03 Nos.			Each	
8	Fixing of sluice valve with 2 cast iron tail pieces, one end flanged and other with socket including the cost of nuts bolts and rubber packing, labour etc. compete. 6" dia	03 Nos.			Each	
9	Construction of C.C. Chamber 4 x 4 x 4 with 24"x24" cover / frame (50Kg) RCC 1:2:4 slab & thick with steel 1:3:6 block masonry wall 6" thick 1:4:8 in foundation thick C.C. 1:2:4 flooring 1/2" thick C.P. 1:4 wall surface 1-0 deep outer side plaster up to roof slab 5/8" dia bars foot rest every 2'-0" deep etc complete.	03 Nos.			Each	

(Cont....on page No.3)