

**OFFICE OF THE EXECUTIVE ENGINEER (WATER), (GULBERG TOWN).
BLOCK-B, KMC MARKET, SINDHI MUSLIM SOCIETY**

**SUBJECT :- PROVIDING AND LAYING 6"DIA PIPE FROM C-1 TO D-8 BLOCK-04
IMPROVEMENT OF WATER SUPPLY OF GULBERG TOWN.**

SL. NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words		
1	Dismantling and removing road metalling.	3000 Cft			%Cft	
2	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence, guards, lights, flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft. (1.52m) and lead upto one chain (30.5m).					
	i. Lift 0'-5'	17500 Cft			%0Cft	
	ii. Lift 5'-8'	7000 Cft			%0Cft	
3	Full hire charges of the pumping set per day i/c of wages of driver and Assistant fuel or electric energy plate forms required for placing pumps etc at lower depth with suction and delivery pipe for pumping out water found at various depth from trenches i/c the cost of erection and dismantling after completion of the job.	14 Days			P/Day	
4	Providing, laying & jointing P.E Pipe Providing & fixing in trenches including fitting joining & testing etc complete in all respect the high density polythene P.E pipes (HDPE-100) for W/S confirming ISO 4427/Din-8074/8075 BS-3580 & PSI 3051. PN-8.	6"dia 1400 Rft			P/Rft	

(Cont....on page No.2)