

**OFFICE OF THE EXECUTIVE ENGINEER  
KARACHI DIVISION CIVIL-I, KW&SB**

**B.O.Q.**

**SUBJECT: REPAIR / MAINTENANCE OF QUARTER NO.C-9, SYDHNEM  
RESERVOIR STAFF COLONY.**

ITEM NO.	DESCRIPTION OF ITEMS	QTY	RATE		PER	AMOUNT
			Word	Figure		
Item 1	P/F in position, door, windows and ventilator of 2"x2", 1/4" angle iron frame and 1 3/4" thick commercial ply wood veneer shutters of deodar wood (3 Ply) on both sides i/c hold fast, cheats, iron towel bolts, handles, hinges and once mortice lock.	196 Sft			P/Sft	
Item 2	Glazed tiles dodo 1/4" thick laid in pigment over 1:2 cement sand mortar 3/4" thick i/c finishing	468.99 Sft			%Sft	
Item 3	Laying floor of approved coloured glazed tile 1/4" thick laid in white cement and pigment ona bed of 3/4" thick cement mortar 1:2	961 Sft			%Sft	
Item 4	P/L 1 1/2" thick topping cement concrete (1:2:4) i/c surface finishing and dividing into panel 1 1/2" thick.	1707.50 Sft			%Sft	
Item 5	P/F deodar wooden wardrobe including boxing with back shelves, shutter draws & brass fittings such as handle locking arrangement hanger rod shoe rod & mirror measuring 2'x1 complete as per approved design.	40 Sft			P/Sft	
Item 6	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size flat iron of approved design i/c painting 3 coats etc complete hot to be less than 3.7 sq. feet of finishing grill.	280 Sft			P/Sft	
Item 7	S/F fiber glass tank of approved quality and design and wall thickness as specified i/c cost of nuts, bolts and fixing in platform of C.C. 1:3:6 and making correction for inlet & outlet & over flow pipes etc complete. 500 Gallons wall thickness 4.5 mm.	01 No.			Each	
Item 8	Wiring for light or fan point with (3/.029) PVC insulated wire in	50 Points			P/ Point	