

**CONSTRUCTION OF ROAD FROM NOORJA PATANI TO SHAKOORANI BUGHIO
MILE 0/3-1/5 (03NOS. 3'SPAN CULVERTS)**

(SCHEDULE "B")

(PART-A)

Qty	Item of work	Rate	Unit	Amount
	1. Excavation in foundation of bridges and other structures i/c deg belling dressing refilling around the structure with excavated earth watering remaining lead upto one chain and life upto 5'-0 (in ordinary soil).			
1056 CFT		@ 3176/25	P.%0 CFT	Rs.3354/-
	2.C.C Brick or stone ballast 1 ½" to 2" gauge Ratio 1:4:8			
224 CFT		@ Rs.9416/28	P.% CFT	Rs.21092/-
	3. Pacca Brick work in foundation cement sand mortar Ratio 1:4			
374 CFT		@ Rs.12501/41	P/% CFT	Rs.46755/-
	4. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
109 SFT		@ Rs.3127/41	P % SFT	Rs. 3409/-
	5 Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
89 CFT		@ Rs.14429/25	P.% CFT	Rs.12842/-
	6. Fabrication of mild steel reinforcement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire (also includes removal of rust from bars.)			
5.67 CWT		@ Rs.5001/70	P.CWT	Rs.28360/-
	7. R.C.C work i/cs all labour and materials except the cost of steel reinforcement for cement concrete i/c bending binding which will be paid sepretly. This rate also i/c kind of forms mould lifting shuttering curring i/c screening and rendering the exposed surface R.C.C work roof slab beams lintels rafts columns and other structure member laid in situ laid in position in all respect.			
92 CFT		@ Rs.337/-	P % CFT	Rs.31004/-
	8. Cement Plaster ½" thick 20' height Ratio 1:3			
313 SFT		@ Rs.2283/93	P % SFT	<u>Rs.7149/-</u>
	Therefore, cost of 03Nos.153965x3=461895/-		TOTAL	Rs.153965/-

NOTE:- Error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU

**M&R OF 8'SPAN CULVERTS ALONG ROAD FROM BAHAWALPUR TO F.P BUND
MILE 0/0-4/0**

(SCHEDULE "B")

(PART-C)

Qty	Item of work	Rate	Unit	Amount
	1. Excavation in foundation of bridges and other structures i/c deg belling dressing refilling around the structure with excavated earth watering remaining lead upto one chain and life upto 5'-0 (in ordinary soil).			
2676 CFT		@ 3176/25	P.%0 CFT	Rs.8500/-
	2.C.C Brick or stone ballast 1 ½" to 2" gauge Ratio 1:4:8			
684 CFT		@ Rs.9416/28	P.% CFT	Rs.64407/-
	3. Pacca Brick work in foundation cement sand mortar Ratio 1:4			
2471 CFT		@ Rs.12501/41	P/% CFT	Rs.308910/-
	4. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
132 SFT		@ Rs.3127/41	P % SFT	Rs. 4128/-
	5 Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
232 CFT		@ Rs.14429/25	P.% CFT	Rs.33476/-
	6. Fabrication of mild steel reinforcement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire (also includes removal of rust from bars.)			
32.30 CWT		@ Rs.5001/70	P.CWT	Rs.161555/-
	7. R.C.C work i/cs all labour and materials except the cost of steel reinforcement for cement concrete i/c bending binding which will be paid sepretly. This rate also i/c kind of forms mould lifting shuttering curring i/c screening and rendering the exposed surface R.C.C work roof slab beams lintels rafts columns and other structure member laid in situ laid in position in all respect.			
445 CFT		@ Rs.337/-	P % CFT	Rs.149965/-
	8. Cement Plaster ½" thick 20' height Ratio 1:3			
515 SFT		@ Rs.2283/93	P % SFT	<u>Rs.11762/-</u>
	TOTAL			Rs.742703/-

NOTE:- Error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU