

**IMPROVEMENT OF ROAD FROM MAIN LIAQUAT ROAD TO MEMON MASJID
VIA HAJI INTAKHAB HOUSE KOTRI MILE 0/0-1/3**

(SCHEDULE "B")

SR.NO. 29

(PART-A)

Qty	Item of work	Rate	Unit	Amount
-----	--------------	------	------	--------

1.Preparing base course including supplying and spreading stone metal of approved quality from approved quarry properly graded to maximum size of 1 ½" and required thickness to proper camber and grade including supplying and spreading 15 RFT screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting modified AASHO specifications. (This includes providing and using templates, camber plates screen forms as directed). Rate I/Cs all costs of materials T and P and carriage upto 3 chains.

84900 CFT	Rs.7220/14	% CFT	Rs.6129902/-
-----------	------------	-------	--------------

2.Providing two coats of surface dressing on new or existing surface with 55 lbs of bitumen of 80/100 penetration and 7.5 CFT crush Bajri of ½"-3/4" inch gauge including cleaning roads surface and rolling etc complete. Rate includes all costs of materials T and P and carriage of three Chain.

162000 SFT	Rs.2838/44	% SFT	Rs.4598273/-
------------	------------	-------	--------------

3. Supplying to laying proper line and grade plant mixed ASPHALT concrete power finished hyderlic / electric control prepare to specified formula exceeding to job of finishing to proper line and grade level and camber etc complete rate i/c take coats with bitumen 80/100 penetration and all cost of material from source of supply of plant to site of work 2" thick.

162000 SFT	Rs.8690/90	%SFT	<u>Rs.14079252/-</u>
------------	------------	------	----------------------

TOTAL Rs.24807427/-

Ded: diff: cost of bitumen 124.60 tons
@ Rs.22606/- P.ton

(-) Rs. 2816708/-

NOTE:- Any error / omission if any, will be correct.

CONTRACTOR


**EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU**

**NEW DRAIN ALONG IMPROVEMENT OF ROAD FROM MAIN LIAQUAT ROAD TO
MEMON MASJID VIA HAJI INTAKHAB HOUSE KOTRI MILE 0/0-1/3**

(SCHEDULE “B”)

(PART-B)

Qty	Item of work	Rate	Unit	Amount
	1. Excavation in shingle gravel formation rock not requiring blasting undressed lead upto 100ft			
21600 CFT	@ 5747/50	P.%0 CFT		Rs.124146/-
	2.C.C Brick or stone ballast 1 ½” to 2” gauge Ratio 1:4:8			
5400 CFT	@ Rs.9416/28	P.% CFT		Rs.508479/-
	3. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
28800 SFT	@ Rs.3127/41	P % SFT		Rs. 900694/-
	4. Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
10800 CFT	@ Rs.14429/25	P.% CFT		Rs.1558359/-
	5. Construction of standard open drain of concrete block of C.C 1:2:4 in situ to design profile i/c cost of mould as per drawing applying floating coat of cement 1/32 to the exposed face finshedsmooth curring etc complete			
3600 RFT	@ Rs.174/-	P.RFT		<u>Rs.626400/-</u>
TOTAL				Rs.3718078/-

NOTE:- Error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU

**REISING DRAIN ALONG IMPROVEMENT OF ROAD FROM MAIN LIAQUAT
ROAD TO MEMON MASJID VIA HAJI INTAKHAB HOUSE KOTRI MILE 0/0-1/3**

(SCHEDULE “B”)

(PART-C)

Qty	Item of work	Rate	Unit	Amount
	1. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
21600 SFT		@ Rs.3127/41	P % SFT	Rs. 675521/-
	2. Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
8100 CFT		@ Rs.14429/25	P.% CFT	<u>Rs.1168769/-</u>
			TOTAL	Rs.1844290/-

NOTE:- Error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU

**DRAIN CROSS ALONG IMPROVEMENT OF ROAD FROM MAIN LIAQUAT ROAD
TO MEMON MASJID VIA HAJI INTAKHAB HOUSE KOTRI MILE 0/0-1/3**

(SCHEDULE “B”)

(PART-D)

Qty	Item of work	Rate	Unit	Amount
	1. Excavation in shingle gravel formation rock not requiring blasting undressed lead upto 100ft			
6300 CFT		@ 5747/50	P.%0 CFT	Rs.36209/-
	2.C.C Brick or stone ballast 1 ½” to 2” gauge Ratio 1:4:8			
1050 CFT		@ Rs.9416/28	P.% CFT	Rs.98871/-
	3. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
5600 SFT		@ Rs.3127/41	P % SFT	Rs. 175135/-
	4. Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
2363 CFT		@ Rs.14429/25	P.% CFT	Rs.340963/-
	5. Fabrication of mild steel reinforcement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire (also includes removal of rust from bars.)			
53.16 CWT		@ Rs.5001/70	P.CWT	Rs.265890/-
	6. R.C.C work i/cs all labour and materials except the cost of steel reinforcement for cement concrete i/c bending binding which will be paid sepretly. This rate also i/c kind of forms mould lifting shuttering curring i/c screening and rendering the exposed surface R.C.C work roof slab beams lintels rafts columns and other structure member laid in situ laid in position in all respect.			
1428 CFT		@ Rs.337/-	P % CFT	<u>Rs.481236/-</u>
TOTAL				Rs.1398305/-

NOTE:- Error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU