

**M&R OF 3'SPAN CULVERTS ALONG ROAD FROM HABKAN TO DAMACH  
MILE 0/0-4/0 TALUKA BULA KHAN  
(SCHEDULE "B")**

**(PART-A)**

Qty	Item of work	Rate	Unit	Amount
1.	Excavation in foundation of bridges and other structures i/c deg belling dressing refilling around the structure with excavated earth watering remaining lead upto one chain and life upto 5'-0 (in ordinary soil).			
950 CFT		@ 3176/25	P.%0 CFT	Rs.3017/-
	2.C.C Brick or stone ballast 1 ½" to 2" gauge Ratio 1:4:8			
224 CFT		@ Rs.9416/28	P.% CFT	Rs.21092/-
	3. Coursed Rubble Masonry i/c hammer dressed in cement sand ratio (1:4)			
374 CFT		@ Rs.26475/-	P/% CFT	Rs.99017/-
	4. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
109 SFT		@ Rs.3127/41	P % SFT	Rs. 3409/-
	5 Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
89 CFT		@ Rs.14429/25	P.% CFT	Rs.12842/-
	6. Fabrication of mild steel reinforcement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire (also includes removal of rust from bars.)			
5.67 CWT		@ Rs.4820/20	P.CWT	Rs.27331/-
	7. R.C.C work i/cs all labour and materials except the cost of steel reinforcement for cement concrete i/c bending binding which will be paid sepretly. This rate also i/c kind of forms mould lifting shuttering curring i/c screening and rendering the exposed surface R.C.C work roof slab beams lintels rafts columns and other structure member laid in situ laid in position in all respect.			
92 CFT		@ Rs.337/-	P % CFT	Rs.31004/-
	8. Pointing flash on stone work raised (Ratio 1:3)			
185 SFT		@ Rs.1758/08	P % SFT	<u>Rs.3252/-</u>
	Therefore cost of 03 Nos. 200964x3=602892/-			
			<b>TOTAL</b>	<b>Rs.200964/-</b>

**NOTE:- Error / omission if any, will be corrected.**

**CONTRACTOR**

  
**EXECUTIVE ENGINEER  
PROVL:HIGHWAY DIVISION DADU**

**REPAIR OF 3'SPAN CULVERTS ALONG ROAD FROM HABKAN TO DAMACH  
MILE 0/0-4/0 TALUKA BULA KHAN  
(SCHEDULE "B")**

**(PART-B)**

Qty	Item of work	Rate	Unit	Amount
	1. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
109 SFT		@ Rs.3127/41	P % SFT	Rs. 3034/-
	2 Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
89 CFT		@ Rs.14429/25	P.% CFT	Rs.12842/-
	3. Fabrication of mild steel reinforcement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire (also includes removal of rust from bars.)			
5.67 CWT		@ Rs.4820/20	P.CWT	Rs.27331/-
	4. R.C.C work i/cs all labour and materials except the cost of steel reinforcement for cement concrete i/c bending binding which will be paid sepretly. This rate also i/c kind of forms mould lifting shuttering curring i/c screening and rendering the exposed surface R.C.C work roof slab beams lintels rafts columns and other structure member laid in situ laid in position in all respect.			
92 CFT		@ Rs.337/-	P % CFT	Rs.31004/-
	5. Pointing flash on stone work raised ratio (1:3)			
185 SFT		@ Rs.1758/08	P % SFT	<u>Rs.3252/-</u>
	Therefore cost of 05 Nos. 77838x5=389190/-		<b>TOTAL</b>	<b>Rs.77838/-</b>

**NOTE:- Error / omission if any, will be corrected.**

**CONTRACTOR**

  
**EXECUTIVE ENGINEER**  
**PROVL:HIGHWAY DIVISION DADU**