

**M&R OF APPROACHES OF BILAWALPUR BRIDGE MILE 0/0-0/5
(SCHEDULE "B")**

(PART-A)

Qty	Item of work	Rate	Unit	Amount
	1.Earth work for road embankment by bulldozers i/c ploughing, Mixing, clod breaking dressing and compacting with optimum moisture content lead up to 100Ft and lift up to 5-0 Ft in all types of soil except rock.			
	<u>Compacting upto 85% Modified AASHO Density without lead</u>			
72100 Cft		Rs.7723/95	%0 CFT	Rs.556897/-
	2.Laying bricks on end edging including supply of 9" 4 1/2 " x 3" 1 st Class burnt bricks excavation for laying edging with small side parallel to the road. Rate includes all cost of materials labour and carriage of 3 chains.			
4500 RFT		Rs.2792/48	% RFT	Rs.125661/-
	3.Preparing base course including supplying and spreading stone metal of approved quality from approved quarry properly graded to maximum size of 1 1/2" and required thickness to proper camber and grade including supplying and spreading 15 RFT screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting modified AASHO specifications. (This includes providing and using templates, camber plates screen forms as directed). Rate I/Cs all costs of materials T and P and carriage upto 3 chains.			
10100 CFT		Rs.8757/30	% CFT	Rs.884487/-
	4.Providing 1 st coats of surface dressing on new or existing surface with 30 lbs of bitumen of 80/100 penetration and 4 CFT crush Bajri of 3/4 inch to 1/2 inch gauge including cleaning roads surface and rolling etc complete. Rate includes all costs of materials T and P and carriage of three Chain.			
26900 SFT		Rs.1670/83	% SFT	Rs.435189/-
	5.Providing 1 " thick consolidated premixed carpet in proper camber and grade including supply of 10 Cft Bajri 4 CT hill sand of approved quality and gauge and bitumen 67lbs of 80/100 penetration including maxing in machanical mixer in required proportions including heating the materials and cleaning the road surface. Rate includes all costs of materials T and P carriage upto site of work.			
26900 SFT		Rs.4511/55	%SFT	<u>Rs.1213606/-</u>
TOTAL				Rs.3215841/-
Ded: diff: cost of bitumen 11.65 tons @ Rs.22606/- P.ton				(-) Rs. 263360/-

NOTE:- Error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU

M&R OF STONE PITCHING APPROACHES OF BILAWALPUR BRIDGE
MILE 0/0-0/5
(SCHEDULE "B")

(PART-B)

Qty	Item of work	Rate	Unit	Amount
	1. Stone Pitching hand packed with surface leveled off to the correct section with Hammer dressed Stone and Voids filled in 1:8 Cement Mortar in floors of bridges and along hands and in aprons etc i/c three chains lead.			
2640 CFT		@ 7708/47	P.%0 CFT	<u>Rs.203504/-</u>
		TOTAL		Rs.203504/-

NOTE:- Error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU

M&R OF TOE WALL APPROACHES OF BILAWALPUR BRIDGE
MILE 0/0-0/5
(SCHEDULE “B”)

(PART-C)

Qty	Item of work	Rate	Unit	Amount
	1. Excavation in foundation of bridges and other structures i/c deg belling dressing refilling around the structure with excavated earth watering remaining lead upto one chain and life upto 5'-0 (in ordinary soil).			
2400 CFT		@ 3176/25	P.%0 CFT	Rs.7623/-
	2.C.C Brick or stone ballast 1 ½” to 2” gauge Ratio 1:4:8			
800 CFT		@ Rs.9416/28	P.% CFT	Rs.75330/-
	3. Pacca Brick work in foundation cement sand mortar Ratio 1:4			
3420 CFT		@ Rs.12501/41	P/% CFT	Rs.427548/-
	4. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
80 SFT		@ Rs.3127/41	P % SFT	Rs. 2502/-
	5 Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
60 CFT		@ Rs.14429/25	P.% CFT	Rs.8658/-
	6. Cement Plaster ½” thick 20’ height Ratio 1:3			
360 SFT		@ Rs.2344/59	P % SFT	<u>Rs.8441/-</u>
			TOTAL	Rs.530101/-

NOTE:- Error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU