

**M&R OF ROAD FROM NANGAR KHAN BROHI TO SHAFI JO THALHO**  
**MILE 0/0-2/1**  
**(SCHEDULE “B”)**

**(PART-A)**

Qty	Item of work	Rate	Unit	Amount
	1.Earth work for road embankment by bulldozers i/c ploughing, Mixing, clod breaking dressing and compacting with optimum moisture content lead up to 100Ft and lift up to 5-0 Ft in all types of soil except rock.			
	<b><u>Compacting upto 85% Modified AASHO Density without lead</u></b>			
241500Cft		Rs.7723/95	%0 CFT	Rs.1865334/-
	2.Laying bricks on end edging including supply of 9” 4 ½ “ x 3” 1 <sup>st</sup> Class burnt bricks excavation for laying edging with small side parallel to the road. Rate includes all cost of materials labour and carriage of 3 chains.			
13900 RFT		Rs.2729/96	% RFT	Rs.379464/-
	3.Preparing base course including supplying and spreading stone metal of approved quality from approved quarry properly graded to maximum size of 1 ½” and required thickness to proper camber and grade including supplying and spreading 15 RFT screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting modified AASHO specifications. (This includes providing and using templates, camber plates screen forms as directed). Rate I/Cs all costs of materials T and P and carriage upto 3 chains.			
31300 CFT		Rs.8516/36	% CFT	Rs.2665620/-
	4.Providing 1 <sup>st</sup> coats of surface dressing on new or existing surface with 30 lbs of bitumen of 80/100 penetration and 4 CFT crush Bajri of 3/4 inch to ½ inch gauge including cleaning roads surface and rolling etc complete. Rate includes all coasts of materials T and P and carriage of three Chain.			
83500 SFT		Rs.1610/64	% SFT	Rs.1344882/-
	5.Providing 1 ” thick consolidated premixed carpet in proper camber and grade including supply of 10 Cft Bajri 4 CT hill sand of approved quality and gauge and bitumen 67lbs of 80/100 penetration including maxing in machnical mixer in required proportions including heating the materials and cleaning the road surface. Rate includes all costs of materials T and P carriage upto site of work.			
83500 SFT		Rs.4487/29	%SFT	<u>Rs.3746891/-</u>
<b>TOTAL</b>				<b>Rs.10002191/-</b>
Ded: diff: cost of bitumen 36.16 tons @ Rs.22606/- P.ton				(-) Rs. 817433/-

**NOTE:- Error / omission if any, will be corrected.**

**CONTRACTOR**

  
**EXECUTIVE ENGINEER**  
**PROVL:HIGHWAY DIVISION DADU**