


KARACHI WATER AND SEWERAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (SEWERAGE), (GULBERG TOWN).

SUBJECT :- P/L OF 12"DIA & 8"DIA SEWERAGE PIPE LINE IN BLOCK-12 AND DIFFERENT BLOCKS OF DIFFERENT AREAS IN GULBERG TOWN.

SL. NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words		
1	Dismantling and removing road metalling.	2500 Cft			%Cft	
2	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guards, lights, flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft. (1.52m) and lead upto one chain (30.5m). i. Lift 0'-5'	12500 Cft			%0Cft	
	ii. Lift 5'-8'	7500 Cft			%0Cft	
	iii. Lift 8'-11'	1750 Cft			%0Cft	
3	Full hire charges of the pumping set per day i/c of wages of driver and Assistant fuel or electric energy plate forms required for placing pumps etc at lower depth with suction and delivery pipe for pumping out water found at various depth from trenches i/c the cost of errection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench.	30 Days			P/Day	
4	Providing, laying RCC pipes with (Rubber Ring Joint and fitting in trench i/c cutting, fitting and jointing with rubber ring i/c testing with water to specified pressure. i. 12" dia	500 Rft			P/Rft	
	ii. 8" dia	300 Rft			P/Rft	

(Cont....on page No.2)


Muhammad Abdul Saleem
EXECUTIVE ENGINEER (W/S)
GULBERG K.W.& S.B.