

SUBJECT :- P/L OF 12"DIA & 8"DIA SEWERAGE PIPE LINE IN BLOCK-12 AND DIFFERENT BLOC
OF DIFFERENT AREAS IN GULBERG TOWN.

SL. NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words		
5	Providing M/H 4ft inside without manhole cover with CI frame (15 kg) and 5 feet clear depth 1:2:4 cast in situ in 9 inch thick wall 1:4:8 cement concrete in 6ft dia and 6" inch thick in foundation 1:2:4 c.c in benching, ½" thick cement plastering with 1:3 cement mortar on inside wall and surface of channel/benching i/c making required Nos of main and branch channels, ¾" dia bar footrest at 12" C/C i/c cost of excavation of all kinds of soil, backfilling and disposal of excavated stuff etc complete, as per design and instruction of the Engineer Incharge.	20 Nos.			Each	
6	Extra depth beyond 5ft for depth lesser than 5ft deducted at same rate including C.I. foot of depth.	(+) 70 Ft.			P/Ft	
7	Making connection with the existing manhole i/c the cost of cutting hole in wall, making them good in C.C 1:2:4 and making required channel etc complete.	20 Nos.			Each	
8	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete.	20973.18 Cft			%0Cft	
Total Rs.						


Muhammad Abdul Salam
EXECUTIVE ENGINEER (SEW)
GULBERG TOWN, KW&SB.

I/We hereby quoted bid amount of Rs. _____/= (Rupees _____)

Note :- All existing SPPRA Rule will be abide.

Signature of Contractor _____

Address. _____