

OFFICE OF THE EXECUTIVE ENGINEER
KARACHI DIVISION CIVIL-I, KW&SB

B.O.Q.

SUBJECT: EMERGENT PROTECTION WORK OF 140 MGD CONDUIT, 84"
DIA PRCC, 36" DIA M.S. PIPE LINE (BULK TRANSMISSION
SYSTEM) PHASE NO.II IN MALIR RIVER

Item No.	DESCRIPTION OF ITEM	QTY.	RATE		PER	AMOUNT
			In Figure	In Word		
1)	Sand Horo or any other source sand of the same modulus of the fineness (Hill Sand).	35086.66 Cft			%Cft	
2)	Carriage of 100 Cft / 5 ton of all materials, coal, lime, surki etc B.G. rail, fastening points sheet rail, M.S. bars etc or 1000 Nos. bricks, 10" x 5" x 3" or 1000 Nos. tiles 12" x 6" x 2" or 150 Cft of timbers 12" x 6" x 2" or 100 munds of fuel wood by trucks, or any other mean owned by the contractor carriage for 5 miles.	35086.66 Cft			% Cft	
3)	Laying earth in 6" layer leveling dressing and watering for compaction etc complete.	35086.66 Cft			%0 Cft	
4)	Stone pitching including sub base with hammer dressed stone on surface laid in courses including carriage of materials (5 chians)	16875 Cft			%Cft	