



**OFFICE OF THE EXECUTIVE ENGINEER**  
**PUBLIC HEALTH ENGG: DIVISION GHOTKI @ MIRPUR MATHELO**

No: TC/G-148/ 80 of 2018.  
M.Mathelo dt: 19.01.2018

Email address [xenphedmirpurmathelo@yahoo.com](mailto:xenphedmirpurmathelo@yahoo.com)

**"SAY NO TO CORRUPTION"**

**INVITATION FOR BIDS**

01. Sealed bids are invited on SPPRA Standard Bidding Documents (SBD) from the eligible bidders registered with Pakistan Engineering Council (PEC) in relevant category (CE09) experience of similar nature of works for the below mentioned work as per Sindh Public Procurement Regulatory Authority.

Sr. No.	Name of Work	Estimate & Cost (In Million)	Bid Security	Tender Fee (In Rupees) (Non refundable)	Time Period (In Months)
<b>DISTRICT ADP 2017-2018.</b>					
01	Construction of CC Paver in village Younis Chachar (Ghulam Hussain Chachar) Taluka Khan Garh.	5.00	100000/00	3000/00	12 Months
02	Construction of CC Paver Drains in village Ali Mahar Taluka Khan Garh.	5.00	100000/00	3000/00	12 Months
03	Construction of CC Paver i/c Surface Drains Earth work at Eid Gah Mohallah from Bago Wah Masjid Abdul Bari Mirani, via Abdul Hameed Qureshi, near Rajpur Colony, Nazar Mohammad Rajpar, Salamat Rajpar Rajpoot Colony upto Menghwar House, Ghulam Sarwar Mahar Street Daya Street Machi & Chachar Street Abdul Rashid Abbasi Street city Ghotki	15.00	300000/00	3000/00	12 Months
04	Construction of CC Paver & Drains at village Raees Mohammad Ibrahim Chachar Taluka Ghotki	3.00	60000/00	3000/00	12 Months
05	Construction of CC Paver & Drains at village Khunhara Taluka Ghotki	3.00	60000/00	3000/00	12 Months
06	Construction of CC Paver & Drains at village Ghulam Leghari Taluka Ghotki	2.00	40000/00	3000/00	12 Months
07	Construction of CC Paver & Drains at village Aslam Leghari Mohallah Taluka Ghotki	1.00	20000/00	2000/00	12 Months
08	Construction of CC Paver & Drains at village Jamal Goh Memon Mohallah Taluka Ghotki	2.00	40000/00	3000/00	12 Months
09	Construction of CC Paver & Drains at village Karim Dino Ghoto Taluka Ghotki	2.00	40000/00	3000/00	12 Months
10	Construction of CC Paver & Drains at village Jumo Ghoto Taluka Ghotki	2.00	40000/00	3000/00	12 Months
11	Construction of CC Paver & Drains at village Jalal Ghoto Taluka Ghotki	2.00	40000/00	3000/00	12 Months
12	Construction of CC Paver & Drains at village Hayat Malik Taluka Ghotki	1.00	20000/00	2000/00	12 Months
13	Construction of CC Paver & Drains village Kambir Kolachi, Mohallah Ali Gohar Kolachi & Ustad Haroon Kolachi Taluka Ghotki.	3.00	60000/00	3000/00	12 Months

02. The bidding documents can be had from the office of the under signed during office Hours on any working day from the date of publication upto **13.02.2018** on the payment of the tender fee not refundable, specified against each work.

03. The tenders will be received back on **14.02.2018** up to **01:00PM** and open on the same day at **02:00PM**.

4. If the work remains un-responded, the Bid Documents will be issued up to **04.03.2018 @ 1:00 PM** and will be received back on the same day 1.00 PM and opened immediately after receiving time in-front of above Persons in Para-3.

**5. TERMS & CONDITIONS.**

- i) Documentary evidence of works of same nature (PHED related works) of equivalent cost or above, executed during last three years, along with certificate of satisfactory completion showing date of start and completion from employer.
- ii) List of works and copy of Letter of Award/Work Order of equivalent cost or above.
- iii) List of machinery and equipment available with documentary proof of its ownership.
- iv) Registration with Income Tax Department (NTN copy), Sindh Revenue Board (Sales Tax Registration) and copy of CNIC.
- v) Undertaking on stamp paper that Firm is not involved in any litigation, Departmental rift, has abandoned or made unnecessary delay in completion of any work in the Government Departments.

SPPRA INWARD DIARY  
NO: 4874  
DATED 23-01-2018

- vi) The application shall accompany along with tender fee (Non Refundable) as shown against the work for purchase of bidding documents.
  - vii) The 2% earnest money shall be submitted in the shape of Call Deposit issued from scheduled bank at the time of submission of bidding document in favour of undersigned.
  - viii) Certificate of Bank showing credit worthiness along with last three years audited Bank Statement.
  - ix) Affidavit to the effect that Firm has not been black-listed previously by any Executing Agency.
  - x) Affidavit to the effect that all documents/particulars/ information furnished are true and correct.
  - xi) Conditional tenders will not be entertained.
  - xii) Registration with Pakistan Engineering Council, in category C6 and above, duly renewed for year 2018, with field of specialization CE 09.
  - xiii) The condition shown at serial No: 12 will not be applicable in case of works costing below **Rs.4.000(M)**.
  - xiv) If Firm / Partner involved in partnership deed, then complete details/instructions and power of attorney will be submitted on affidavit by the proprietor.
  - xv) Financial turn over for last 03 years being average not less than thrice the cost of work under procurement.
  - xvi) License from Electrical Inspector for Electric / Diesel Engine Generating Sets / Pumping Machinery.
  - xvii) Current Bank Statement confirming cash availability / credit facility equivalent to 40% of cost of work under procurement.
  - xviii) Provide information of Technical Staff working with firm.
6. Procuring agency reserves the right to accept or reject any bid and to annul the bidding process and reject all bids at any time prior to award of contract as per provision of (SPP rules 25).

Note: This N.I T along with bid documents can be seen / down loaded from SPPRA Website at [www.ppra.sindh.gov.pk](http://www.ppra.sindh.gov.pk)

**EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO**

**C.C for Information to:-**

1. The Director Information (Advertisement), Block No.96 Sindh Secretariat Karachi (in seven copies) for insertion / publication in three leading Newspapers viz: ENGLISH, URDU, SINDHI Languages for wide publicity.
2. The Director (A&F), Sindh Public Procurement Regulatory Authority Barrack No.08 Sindh Secretariat No.4A Court Road Karachi Tel: 92-21-99205369 for hoisting on SPPRA's Website.
3. The Secretary, Information & Technology Department, Government of Sindh, Sindh Secretariat No. 6 Karachi and C.D of this is also enclosed herewith for placement on Government Website.
2. The Chief Engineer, Public Health Engineering Department, Govt: of Sindh, Sukkur.
3. The Superintending Engineer, Public Health Engg: Circle Sukkur.
4. The Deputy Commissioner, Ghotki @ Mirpur Mathelo.
5. The Assistant Engineers (All), under Public Health Engg: Division, Ghotki @ M.Mathelo
6. Notice Board.

**EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO**



Ph: 071-9310448  
Fax: 071-9310447  
Email: cephedsukkur@gmail.com

NO. E/PHED/ 495 of 2016.  
OFFICE OF THE CHIEF ENGINEER,  
PUBLIC HEALTH ENGG: DEPARTMENT  
GOVERNMENT OF SINDH SUKKUR  
Sukkur, Dated. 10 / 2 / 2016.

### OFFICE ORDER.

In exercise of the power confirmed under Rule 31 of the Sindh Public Procurement Rules 2010. The following committee is hereby constituted to redress grievance / complaints that may arise during procuring proceedings in Public Health Engineering Division Ghotki @ M.Mathelo.

Superintending Engineer, Public Health Engineering Circle Sukkur	Chairman
Executive Engineer Education Works Division Ghotki	Member
Divisional Accounts Officer Roads Division Ghotki	Member

The committee shall act in accordance with rule 31 of Sindh Public Procurement Rules 2010 (amended 2013).

*Raj SAC*  
*Sec*

*Raj - idia*  
(RAM CHAND.P.SANJHIRA)  
CHIEF ENGINEER,  
PUBLIC HEALTH ENGG: DEPARTMENT,  
GOVT: OF SINDH SUKKUR

CC. to the

Manager Assessment-IV Sindh Public Procurement Regulatory Authority Karachi for information.

Superintending Engineer, Public Health Engineering Circle Sukkur for information.

✓ Executive Engineer, Public Health Engineering Division Ghotki @ M.Mathelo for information.

Executive Engineer, Education Works Division Ghotki for information.

Divisional Accounts Officer, Roads Division Ghotki for information.



NO.GM/PHED/ 406 of 2017  
OFFICE OF THE CHIEF ENGINEER  
PUBLIC HEALTH ENGINEERING DEPARTMENT  
GOVERNMENT OF SINDH, SUKKUR  
Sukkur Dated, 2-1-2017

Phone No.071-9310448  
Fax No.071-9310447  
(Email Add: cphedsukkur@gmail.com)

To,

The Superintending Engineer,  
Public Health Engineering Circle,  
Sukkur & Larkana.

SUBJECT:- NOTIFICATION.

Under Rule-7 & 8 of SPP Rules-2010, worthy Secretary, Public Health Engineering & Rural Development Department Government of Sind, Karachi has re-constituted the Division wise Department Procurement Committee vide Notification No: SO(T)/PHE/SPPRA-Rules/2013/(Pt-II) dated 27<sup>th</sup> January, 2017 copy of the same is sent herewith for information & necessary compliance.

You are further directed to circulate among the Executive Engineers, under your jurisdiction and make assurance for compliance of SPPRA rules, under intimation to this office.

*Ro-ih.*

(RAM CHAND P.SANJHIRA)  
CHIEF ENGINEER  
PUBLIC HEALTH ENGG. DEPARTMENT,  
GOVT. OF SINDH SUKKUR

D.A/As above.

CC. to the:-

- Secretary, Public Health Engineering & Rural Development Department Government of Sindh, Karachi for favour of his kind information w/r to his letter No: cited above.



GOVERNMENT OF SINDH  
PUBLIC HEALTH ENGINEERING AND  
RURAL DEVELOPMENT DEPARTMENT

Karachi dated the 27<sup>th</sup> January, 2017.


## NOTIFICATION

NO. 50(T)/PHE/SPPRA-Rules/2013/(Pt-II)- In exercise of powers conferred by rule-7 & 8 of SPP Rules, 2010, the division wise procurement committees in Public Health Engineering Department are hereby re-constituted as under:-

S. NO.	NAME OF PHE DIVISION	PROCUREMENT COMMITTEE	CHAIRMAN/ MEMBER
01.	Hyderabad-I	Executive Engineer, Public Health Engineering Division No.I, Hyderabad-I  Executive Engineer, Education Works Division, Hyderabad  Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Chairman  Member  Member
02.	Hyderabad-II	Executive Engineer, Public Health Engineering Division No.II, Hyderabad  Executive Engineer, Education Works Division, Hyderabad  Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Chairman  Member  Member
03.	Jamshoro	Executive Engineer, Public Health Engineering Division, Jamshoro  Executive Engineer, Education Works Division, Jamshoro  Section Officer(Admn.), PHE, Public Health Engineering & Rural Development Department	Chairman  Member  Member


*[Handwritten Signature]*

04.	Tando Mohammad Khan	Executive Engineer, Public Health Engineering Division, Tando Mohammad Khan	Chairman
		Executive Engineer, Education Works Division, Tando Mohammad Khan	Member
		Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Member
05.	Matlari	Executive Engineer, Public Health Engineering Division, Matlari	Chairman
		Divisional Accounts Officer, Hala Division, Irrigation Department, Hyderabad	Member
		Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Member
06.	Karachi-I	Executive Engineer, Public Health Engineering Division, Karachi-I	Chairman
		Executive Engineer, Local Govt. Department, Karachi	Member
		Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Member
07.	Karachi-II	Executive Engineer, Public Health Engineering Division, Karachi-II	Chairman
		Executive Engineer, Local Govt. Department, Karachi	Member
		Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Member



08.	Mirpurkhas	Executive Engineer, Public Health Engineering Division, Mirpurkhas	Chairman
		Assistant Engineer, Building Division Works & Services Department, Mirpurkhas	Member
		Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Member
09.	Tando Allahyar	Executive Engineer, Public Health Engineering Division, Tando-Allahyar	Chairman
		Executive Engineer, Highway Division, Tando Allahyar	Member
		Section Officer(Admn.)PHE, Public Health Engineering & Rural Development Department	Member
10.	Sanghar	Executive Engineer, , Public Health Engineering Division, Sanghar	Chairman
		Assistant Engineer, Education Works Sub-Division, Sinjhor	Member
		Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Member
11.	Tharparkar @ Mithi	Executive Engineer, Public Health Engineering Division, Tharparkar @ Mithi	Chairman
		Executive Engineer, Education Works Division, Tharparkar @ Mithi	Member
		Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Member


12.	Umerkot	Executive Engineer, Public Health Engineering Division, Umerkot	Chairman
		Executive Engineer, Education Works Division, Umerkot	Member
		Section Officer(Admn.) PHE, Public Health Engineering & Rural Development Department	Member
13.	Sukkur	Executive Engineer, Public Health Engineering Division, Sukkur	Chairman
		Executive Engineer, Highway Division, Sukkur	Member
		Section Officer(Tech.) PHE, Public Health Engineering & Rural Development Department	Member
14.	Ghotki @ Mirpur-Mathelo	Executive Engineer, Public Health Engineering Division, Ghotki @ Mirpur-Mathelo	Chairman
		Executive Engineer, Education Works District Ghotki	Member
		Section Officer (Tech.), PHE, Public Health Engineering & Rural Development Department	Member
15.	Khairpur-I	Executive Engineer, Public Health Engineering Division No. I Khairpur	Chairman
		Assistant Engineer, Education Works, Sub-Division, Khairpur	Member
		Section Officer (Tech.), PHE, Public Health Engineering & Rural Development Department	Member





16.	Khairpur-I Ranipur	@	Executive Engineer, Public Health Engineering Division No. II Khairpur @ Ranipur	Chairman
			Assistant Engineer, Education Works, Sub-Division, Khairpur	Member
			Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Member
17.	Naushahroferoze		Executive Engineer, Public Health Engineering Division, Naushahroferoze	Chairman
			Assistant Engineer, Highway, Sub-Division, Mehrabpur	Member
			Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Member
18.	Shaheed Benazirabad		Executive Engineer, Public Health Engineering Division No. 5, Shaheed -Benazirabad	Chairman
			Executive Engineer, Education Works Division, Shaheed - Benazirabad	Member
			Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Member
19.	Larkana-I		Executive Engineer, Public Health Engineering Division, Larkana-I	Chairman
			Executive Engineer, Building Provincial Division, Larkana	Member
			Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Member

20.	Larkana-II	Executive Engineer, Public Health Engineering Division, Larkana-II Executive Engineer, Building Provincial Division, Larkana Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Chairman Member Member
21.	Dadu	Executive Engineer, Public Health Engineering Division, Dadu Executive Engineer, Highway Division, Dadu Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Chairman Member Member
22.	Jacobabad	Executive Engineer, Public Health Engineering Division, Jacobabad Executive Engineer, Highway Division, Jacobabad Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Chairman Member Member
23.	Kamber Shahdadt @ Kamber	Executive Engineer, Public Health Engineering Division Kamber Shahdadt @ Kamber Executive Engineer, Education Works Division, Kamber Shahdadt @ Kamber Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Chairman Member Member



24.	Shikarpur		Executive Engineer Public Health Engineering Division, Shikarpur	Chairman
			Executive Engineer, Machinery & Maintenance Division, Khairpur @ Shikarpur	Member
			Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Member
25.	Kashmore Kandhkot	@	Executive Engineer, Public Health Engineering Division Kashmore @ Kandhkot	Chairman
			Executive Engineer, Roads, Kashmore @ Kandhkot	Member
			Section Officer (Tech.) PHE, Public Health Engineering & Rural Development Department	Member
26.	Thatta		Executive Engineer, Public Health Engineering Division Thatta	Chairman
			Executive Engineer, Highway Division, Thatta	Member
			Section Officer (Admn.) PHE, Public Health Engineering & Rural Development Department	Member
27.	Sujawal		Executive Engineer, Public Health Engineering Division Sujawal	Chairman
			Executive Engineer, Highway Division, Thatta/Sujawal	Member
			Section Officer (Admn.) PHE, Public Health Engineering & Rural Development Department	Member

28.	Badin	Executive Engineer, Public Health Engineering Division Badin	Chairman
		Executive Engineer, Highway Division, Badin	Member
		Section Officer(Admn.)PHE, Public Health Engineering & Rural Development Department	Member

**Terms of reference of the Committees:-**

01. Preparing bidding documents
02. Carrying out technical as well as financial evaluation of the bids
03. Preparing evaluation report as provided in Rule- 45
04. Making recommendations for the award of contract to the competent authority and
05. Perform any other function ancillary and incidental to the above


The Procurement Committees constituted vide this department Notification No. SO(T)/PHE/SPPRA-Rules/2013(pt-II) dated 16-05-2013 dated 05-05-201, dated September, 2015 & letter No. SO(T)/PHE/SPPRA-Rules/2013 dated 19-12-2016 are hereby repeated.

**TAMEEZUDDIN KHERO**  
SECRETARY TO GOVERNMENT OF SINDH

N.O. SO(T)/PHE/SPPRA-Rules/2013/(Pt-II):- Karachi dated the 27<sup>th</sup> January, 2017.


**CC to:-**

01. The Secretary, Works & Services Department, Govt. of Sindh, Karachi.
02. The Secretary, Local Government Department, Govt. of Sindh, Karachi.
03. The Secretary, Irrigation Department, Govt. of Sindh, Karachi.
04. The Secretary, School Education Department, Govt. of Sindh, Karachi
05. The Chief Engineers, Public Health Engineering Deptt. Hyderabad/Sukkur.
06. The Managing Director, Procurement Regulatory Authority, Sindh, Karachi.
07. The PS to Minister, Public Health Engineering & Rural Dev. Deptt. Sindh, Karachi.
08. The PS to Secretary, Public Health Engineering & Rural Dev. Deptt. Sindh, Karachi.
09. The Members concerned.

  
(MOHAMMAD BUX JARWAR)  
SECTION OFFICER (TECH.)


**ANNUAL PROCUREMENT PLAN FOR THE YEAR 2017-18.  
UNDER DISTRICT ADP (DISTRICT GHOTKI.**

S. No:	Description of Procurement	Quality where applicable	Est unit /cost where applicable.	Estimated total cost in Million.	Funds allocation ( Million) Rs.	Release of funds by the FD.	Source of funds ADP/Non ADP	Timing of Procurement 2017-18.
01	Construction of CC Paver in village Younis Chachar (Ghulam Hussain Chachar) Taluka Khan Garh.	where applicable	5.00	5.00			District ADP 2017-18	4 <sup>th</sup> Quarter
02	Construction of CC Paver Drains in village Ali Mahar Taluka Khan Garh.	where applicable	5.00	5.00				4 <sup>th</sup> Quarter
03	Construction of CC Paver i/c Surface Drains Earth work at Eid Gah Mohallah from Bago Wah Masjid Abdul Bari Mirani, via Abdul Hameed Qureshi, near Rajpur Colony, Nazar Mohammad Rajpar, Salamat Rajpar Rajpoot Colony upto Menghwar House, Ghulam Sarwar Mahar Street Daya Street Machi & Chachar Street Abdul Rashid Abbasi Street city Ghotki	where applicable	15.00	15.00				4 <sup>th</sup> Quarter
04	Construction of CC Paver & Drains at village Raees Mohammad Ibrahim Chachar Taluka Ghotki	where applicable	3.00	3.00				4 <sup>th</sup> Quarter
05	Construction of CC Paver & Drains at village Khunhara Taluka Ghotki	where applicable	3.00	3.00				4 <sup>th</sup> Quarter
06	Construction of CC Paver & Drains at village Ghulam Leghari Taluka Ghotki	where applicable	2.00	2.00				4 <sup>th</sup> Quarter
07	Construction of CC Paver & Drains at village Aslam Leghari Mohallah Taluka Ghotki	where applicable	1.00	1.00				4 <sup>th</sup> Quarter
08	Construction of CC Paver & Drains at village Jamal Goth Memon Mohallah Taluka Ghotki	where applicable	2.00	2.00				4 <sup>th</sup> Quarter
09	Construction of CC Paver & Drains at village Karim Dino Ghoto Taluka Ghotki	where applicable	2.00	2.00				4 <sup>th</sup> Quarter
10	Construction of CC Paver & Drains at village Jumo Ghoto Taluka Ghotki	where applicable	2.00	2.00				4 <sup>th</sup> Quarter
11	Construction of CC Paver & Drains at village Jalal Ghoto Taluka Ghotki	where applicable	2.00	2.00				4 <sup>th</sup> Quarter
12	Construction of CC Paver & Drains at village Hayat Malik Taluka Ghotki	where applicable	1.00	1.00				4 <sup>th</sup> Quarter
13	Construction of CC Paver & Drains village Kambir Kolachi, Mohallah Ali Gohar Kolachi & Ustad Haroon Kolachi Taluka Ghotki.	where applicable	3.00	3.00				4 <sup>th</sup> Quarter

  
**EXECUTIVE ENGINEER**  
**PUBLIC HEALTH ENGG. DIVI. GHOTKI**  
**@ MIRPUR MATHELO.**

**ANNUAL PROCUREMENT PLAN FOR THE YEAR 2017-18.**  
**UNDER PROVINCIAL ADP (DISTRICT GHOTKI.**

S. No:	Description of Procurement	Quality where applicable	Estimated unit cost where applicable.	Estimated total cost in Million.	Funds allocation in Million Rs.	Release of funds by the FD.	Source of funds ADP/Non ADP	Timing of Procurement 2017-18.
04	Construction of Surface Drains Type-I,II &III & CC Paver for Improvement & Extension Drainage Scheme Raharki Taluka Daharki	where applicable	17.300	17.300	10.00 Million	2.500 Million	Provincial ADP 2017-18	4 <sup>th</sup> Quarter

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG.DIV.I.GHOTKI  
**@ MIRPUR MATHELO.**

**PUBLIC HEALTH ENGINEERING DEPARTMENT**  
**GOVERNMENT OF SINDH**

ISSUE TO  
D.R NO:& DATE  
FOR Rs.

---

---

---

**Executive Engineer,**  
**Public Health Engineering**  
**Ghotki @ Mirpur Mathelo.**

**STANDRAD FORM OF BIDDING DOCUMENTS**

**FOR**

**FOR THE WORK**

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents. The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference:-**

#### **1.1 Name of Procuring Agency :-**

**Executive Engineer, Public Health Engg: Division Ghotki @ Mirpur Mathelo**

#### **Brief Description of Works :-**

##### **(a) Procuring Agency's address:**

**Opposite Old Taluka Hospital Mirpur Mathelo**

##### **(b) Engineer's address:**

**Same as above**

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows:

##### **i. Financial capacity:**

***(See N.I.T Eligibility Criteria at Para-5)***

##### **ii. Technical capacity:;**

***(See N.I.T Eligibility Criteria at Para-5)***

##### **iii. Construction Capacity:**

***(See N.I.T Eligibility Criteria at Para-5)***

12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

***(As Per Technically Sanctioned Estimate)***



- (b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

***(As Per Technically Sanctioned Estimate)***

**13.1 Amount of Bid Security**

**2% of Rs: 0.206 Million i.e Rs: 10.300 Million**

**14.1 Period of Bid Validity**

**90 Days**

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (--) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

**Opposite Old Taluka Hospital Mirpur Mathelo**

**15.1 Deadline for Submission of Bids**

Time: **1:00** PM on \_\_\_\_\_

**16.1 Venue, Time, and Date of Bid Opening**

Venue: **Executive Engineer, Public Health Engineering Division Ghotki @ Mirpur Mathelo.**

Time: **2:00** P.M Date: \_\_\_\_\_

**16.4 Responsiveness of Bids**

- (i) Bid is valid till required period,
- (ii) Bid prices are firm during currency of contract.

- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

**Fixed Price contract:-** In this contract no escalation will be provided during currency of the contract and normally period of completion of this work is upto **(12) months.**

**FORM OF BID**  
(LETTER OF OFFER)

Bid Reference ;- *construction of cc drains & cc block at various laces of Adilpur i/c sheikh Mohallah for improvement & extension of Drainage Scheme Adilur .*

To:-

**Executive Engineer,**  
**Public Health Engg: Division,**  
**Ghotki @ Mirpur Mathelo.**

Gentlemen,

1. Having examined the Bidding Documents including Instructions to Bidders, Bidding Data, Conditions of Contract, Contract Data, Specifications, Drawings, if any, Schedule of Prices and Addenda Nos.  
  
\_\_\_\_\_ for the execution of the above-named works, we, the undersigned, being a company doing business under the name of and address \_\_\_\_\_  
  
\_\_\_\_\_ and being duly incorporated under the laws of Pakistan hereby offer to execute and complete such works and remedy any defects therein in conformity with the said Documents including Addenda thereto for the Total Bid Price of Rs \_\_\_\_\_ (Rupees \_\_\_\_\_) or such other sum as may be ascertained in accordance with the said Documents.
2. We understand that all the Schedules attached hereto form part of this Bid.
3. As security for due performance of the undertakings and obligations of this Bid, we submit herewith a Bid Security in the amount of \_\_\_\_\_  
  
\_\_\_\_\_ drawn in your favour or made payable to you and valid for a period of twenty eight (28) days beyond the period of validity of Bid.
4. We undertake, if our Bid is accepted, to commence the Works and to deliver and complete the Works comprised in the Contract within the time(s) stated in Contract Data.
5. We agree to abide by this Bid for the period of \_\_\_\_\_ days from the date fixed for receiving the same and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
6. Unless and until a formal Agreement is prepared and executed, this Bid, together

8. We understand that you are not bound to accept the lowest or any bid you may receive.
9. We do hereby declare that the Bid is made without any collusion, comparison of figures or arrangement with any other person or persons making a bid for the Works.

Dated this \_\_\_\_\_ day of \_\_\_\_\_, 20

Signature \_\_\_\_\_

in the capacity of \_\_\_\_\_ duly authorized to sign bid for and on behalf of

\_\_\_\_\_  
*(Name of Bidder in Block Capitals)*

*(Seal)*

Address

---

---

---

Witness:

(Signature) \_\_\_\_\_

Name: \_\_\_\_\_

Address: \_\_\_\_\_

---

**[SCHEDULES TO BID INCLUDE THE FOLLOWING:**

- Schedule A to Bid: Schedule of Prices
- Schedule B to Bid: Specific Works Data
- Schedule C to Bid: Works to be Performed by Subcontractors
- Schedule D to Bid: Proposed Program of Works
- Schedule E to Bid: Method of Performing Works
- Schedule F to Bid: Integrity Pact]

SCHEDULE - A TO BID

SCHEDULE OF PRICES – SUMMARY OF BID PRICES

Bill No.	Description	Total Amount (Rs)
1.	<p><b><u>Public Health Engineering Works.</u></b></p> <p><i>construction of cc drains &amp; cc block at various laces of Adilpur i/c sheikh Mohallah for improvement &amp; extension of Drainage Scheme Adilur .</i></p> <p><i>Add. below / above</i></p> <p><i>Total.</i></p> <p>-</p>	<p>Rs.</p> <p>Rs.</p> <p>Rs.</p>
<p>Total Bid Price (The amount to be entered in Paragraph 1 of the Form of Bid)  (In words). Rupees:- _____</p>		

**PUBLIC HEALTH ENGINEERING DEPARTMENT**  
**GOVERNMENT OF SINDH**

**PUBLIC HEALTH ENGINEERING DIVISION GHOTKI**



**BIDDING DOCUMENTS WITH FINANCIAL PROPOSAL**

**FOR**

**Name of Work:-** \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Name of Department:-**

**Public Health Engineering Department.**

**Name of Procuring Agency:-**

**Executive Engineer, Public Health Engineering  
Division Ghotki @ Mirpur Mathelo.**

**Documents Issued to:-** \_\_\_\_\_

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents. The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

**1.1 Name of Procuring Agency :-**

**Executive Engineer, Public Health Engg: Division Ghotki @ Mirpur Mathelo**

**Brief Description of Works :-**

---

---

---

**5.1 (a) Procuring Agency's address:**

**Opposite Old Taluka Hospital Mirpur Mathelo**

**(b) Engineer's address:**

**Same as above**

**10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.**

**11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows:**

**i. Financial capacity:**

***(See N.I.T Eligibility Criteria at Para-5)***

**ii. Technical capacity:;**

***(See N.I.T Eligibility Criteria at Para-5)***

**iii. Construction Capacity:**

***(See N.I.T Eligibility Criteria at Para-5)***

**12.1 (a) A detailed description of the Works, essential technical and performance characteristics.**

***(As Per Technically Sanctioned Estimate)***



- (b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

***(As Per Technically Sanctioned Estimate)***

**13.1 Amount of Bid Security**

**2% of Rs: 0.100 Million i.e Rs: 5.00 Million**

**14.1 Period of Bid Validity**

**90 Days**

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (--) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

**Opposite Old Taluka Hospital Mirpur Mathelo**

**15.1 Deadline for Submission of Bids**

Time: **1:00** PM on \_\_\_\_ - \_\_\_\_ -**2018.**

**16.1 Venue, Time, and Date of Bid Opening**

Venue: **Executive Engineer, Public Health Engineering Division Ghotki @ Mirpur Mathelo.**

Time: **2:00** P.M Date: \_\_\_\_ - \_\_\_\_ -**2018.**

**16.4 Responsiveness of Bids**

- (i) Bid is valid till required period,
- (ii) Bid prices are firm during currency of contract.

- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

**Fixed Price contract:-** In this contract no escalation will be provided during currency of the contract and normally period of completion of this work is upto **(12) months.**

**FORM OF BID  
(LETTER OF OFFER)**

Bid Reference No.

---

---

---

To:

**Executive Engineer,**  
**Public Health Engg: Division,**  
**Ghotki @ Mirpur Mathelo.**

Gentlemen,

1. Having examined the Bidding Documents including Instructions to Bidders, Bidding Data, Conditions of Contract, Contract Data, Specifications, Drawings, if any, Schedule of Prices and Addenda Nos.

\_\_\_\_\_ for the execution of the above-named works, we, the undersigned, being a company doing business under the name of and address \_\_\_\_\_

\_\_\_\_\_ and being duly incorporated under the laws of Pakistan hereby offer to execute and complete such works and remedy any defects therein in conformity with the said Documents including Addenda thereto for the Total Bid Price of Rs \_\_\_\_\_ (Rupees \_\_\_\_\_) or such other sum as may be ascertained in accordance with the said Documents.

2. We understand that all the Schedules attached hereto form part of this Bid.
3. As security for due performance of the undertakings and obligations of this Bid, we submit herewith a Bid Security in the amount of \_\_\_\_\_  
\_\_\_\_\_ drawn in your favour or made payable to you and valid for a period of twenty eight (28) days beyond the period of validity of Bid.
4. We undertake, if our Bid is accepted, to commence the Works and to deliver and complete the Works comprised in the Contract within the time(s) stated in Contract Data.

5. We agree to abide by this Bid for the period of \_\_\_\_\_ days from the date fixed for receiving the same and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
6. Unless and until a formal Agreement is prepared and executed, this Bid, together with your written acceptance thereof, shall constitute a binding contract between us.
7. We undertake, if our Bid is accepted, to execute the Performance Security referred to in Conditions of Contract for the due performance of the Contract.
8. We understand that you are not bound to accept the lowest or any bid you may receive.
9. We do hereby declare that the Bid is made without any collusion, comparison of figures or arrangement with any other person or persons making a bid for the Works.

Dated this \_\_\_\_\_ day of \_\_\_\_\_, 20

Signature \_\_\_\_\_

in the capacity of \_\_\_\_\_ duly authorized to sign bid for and on behalf of

\_\_\_\_\_  
*(Name of Bidder in Block Capitals)*  
*(Seal)*

Address \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Witness:  
 (Signature) \_\_\_\_\_

Name: \_\_\_\_\_

Address: \_\_\_\_\_  
 \_\_\_\_\_

**[SCHEDULES TO BID INCLUDE THE FOLLOWING:**

- Schedule A to Bid: Schedule of Prices
- Schedule B to Bid: Specific Works Data
- Schedule C to Bid: Works to be Performed by Subcontractors
- Schedule D to Bid: Proposed Program of Works
- Schedule E to Bid: Method of Performing Works
- Schedule F to Bid: Integrity Pact]

**SCHEDULE - A TO BID**

**SCHEDULE OF PRICES – SUMMARY OF BID PRICES**

Bill No.	Description	Total Amount (Rs)
1.	<u>Public Health Engineering Works.</u>	
Total Bid Price (The amount to be entered in Paragraph 1 of the Form of Bid) (In words). Rupees:- _____		

**SCHEDULE OF PRICES**

**NAME OF WORK**      **CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE YOUNIS CHACHAR MOHALLAH  
GHULAM HUSSAIN CHACHAR TALUKA KHAN  
GARH.**

**A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing ruffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	2560.00 CFT	RS: 3176/25	P%0 CFT	RS: 8131/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	527.50 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 59548/00
	39.93 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 5762/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)			
	500.00 RFT Type-I	RS:94/00	P.RFT	RS: 47000/00
	300.00 RFT Type-II	RS:174/00	P.RFT	RS: 52200/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	1425.00 CFT	RS: 11948/36	P% CFT	RS: 170264/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	1900.00 CFT	RS: 2283/93	P% CFT	RS: 43395/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 457443/00</b>

**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	13200.00CFT	RS: 2117/50	P.%0CFT	RS: 27951/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	13200.00CFT	RS: 502/52	P.%CFT	RS: 66333/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	13200.00CFT	RS: 354/00	P.%0CFT	RS: 4673/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	2244.00CFT	RS: 1800/00	P.%CFT	RS: 40392/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	4356.00CFT	RS: 9416/28	P.%CFT	RS: 410173/00
06	Providing fixing-Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	13200.00SFT	RS: 199/77	P.SFT	RS: 2636964/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	275.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 31044/00
			<b>TOTAL</b>	<b>RS: 3217530/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	457443/00	--	457443/00
2	CC Paver	3217530/00	--	3217530/00
	<b>TOTAL</b>	<b>3674973/00</b>	<b>--</b>	<b>3674973/00</b>

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO



**SCHEDULE OF PRICES****NAME OF WORK CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE ALI MAHAR TALUKA KHAN  
GARH.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing ruffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	917.00 CFT	RS: 3176/25	P%0 CFT	RS: 2913/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	173.00 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 19530/00
	7.99 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 1152/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)			
	100.00 RFT Type-I	RS:94/00	P.RFT	RS: 9400/00
	150.00 RFT Type-II	RS:174/00	P.RFT	RS: 26100/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	487.50 CFT	RS: 11948/36	P% CFT	RS: 58248/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	650.00 CFT	RS: 2283/93	P% CFT	RS: 14846/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cast laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 203332/00</b>


**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	14304.00CFT	RS: 2117/50	P.%0CFT	RS: 30289/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	14304.00CFT	RS: 502/52	P.%CFT	RS: 71880/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	14304.00CFT	RS: 354/00	P.%0CFT	RS: 5064
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	2431.68CFT	RS: 1800/00	P.%CFT	RS: 43770/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	4720.32CFT	RS: 9416/28	P.%CFT	RS: 444479/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Qudra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	14304.00SFT	RS: 199/77	P.SFT	RS: 2857510/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	298.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 33640/00
			<b>TOTAL</b>	<b>RS: 3486632/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	203332/00	--	203332/00
2	CC Paver	3486632/00	--	3486632/00
	<b>TOTAL</b>	<b>3689964/00</b>	<b>--</b>	<b>3689964/00</b>

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

**SCHEDULE OF PRICES**

<b>NAME OF WORK</b>	<b><u>CONSTRUCTION OF SURFACE DRAINS &amp; CC PAVER AT EARTH WORK @ EID GAH MOHALLAH FROM BAGO WAH MASJID ABDUL BARI MIRANI, VIA ABDUL HAMEEN QURESHI, NEAR RAJPOOT COLONY, NAZAR MOHAMMAD RAJPOOT, SALAMAT RAJPOOT UPTO MENGHWAR HOUSE GHULAM SARWAR MAHAR STREET, DAYA STREET MACHI STREET, CHACHAR STREET ABDUL RASHEED ABBASI STREET GHOTKI CITY TALUKA GHOTKI.</u></b>
---------------------	---

**A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing ruffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)	4851.68 CFT	RS: 3176/25	P%0 CFT	RS: 15410/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)	1081.67 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 122107/00
		108.13 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 15602/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc compete as per detailed drawing (PHSI No 5 P.44)	1354.00 RFT Type-I	RS:94/00	P.RFT	RS: 127276/00
		350.00 RFT Type-II	RS:174/00	P.RFT	RS: 60900/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)	2818.50 CFT	RS: 11948/36	P% CFT	RS: 339765/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)	3758.00 CFT	RS: 2283/93	P% CFT	RS: 85830/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
				<b>TOTAL</b>	<b>RS: 835033/00</b>

**B CC PAVER**


01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)	42724.00CFT	RS: 2117/50	P.%0CFT	RS: 90468/00
02	Carraige of Earth (CSI No:08 P No: 02)	42724.00CFT	RS: 502/52	P.%CFT	RS: 214697/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete	42724.00CFT	RS: 354/00	P.%0CFT	RS: 15124/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4	7263.08CFT	RS: 1800/00	P.%CFT	RS: 130735/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)	14098.92CFT	RS: 9416/28	P.%CFT	RS: 1327594/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)	42724.00SFT	RS: 199/77	P.SFT	RS: 8534973/00

07 Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)  
971.00CFT 1:4:8 RS: 11288/75 P.%CFT RS: 109614/00  
**TOTAL RS: 10423205/00**

### ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	835033/00	--	835033/00
2	CC Paver	10423205/00	--	10423205/00
	<b>TOTAL</b>	<b>11258238/00</b>	<b>--</b>	<b>11258238/00</b>

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

**SCHEDULE OF PRICES****NAME OF WORK      CONSTRUCTION OF SURFACE DRAINS & CC PAVER AT  
VILLAGE RAEES MOHAMMAD IBRAHIM CHAHCAR  
TALUKA GHOTKI.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing riffing around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	692.00 CFT	RS: 3176/25	P%0 CFT	RS: 2198/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	135.50 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 15296/00
	7.99 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 1152/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)			
	100.00 RFT Type-I	RS:94/00	P.RFT	RS: 9400/00
	100.00 RFT Type-II	RS:174/00	P.RFT	RS: 17400/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	375.00 CFT	RS: 11948/36	P% CFT	RS: 44806/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	500.00 CFT	RS: 2283/93	P% CFT	RS: 11420/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 172815/00</b>

**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	8415.00CFT	RS: 2117/50	P.%0CFT	RS: 17819/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	8415.00CFT	RS: 502/52	P.%CFT	RS: 42287/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	8415.00CFT	RS: 354/00	P.%0CFT	RS: 2979/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	1430.55CFT	RS: 1800/00	P.%CFT	RS: 25750/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	2776.95CFT	RS: 9416/28	P.%CFT	RS: 261485/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	4115.00SFT	RS: 199/77	P.SFT	RS: 1681065/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	233.75CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 26387/00
			<b>TOTAL</b>	<b>RS: 2057772/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	172815/00	--	172815/00
2	CC Paver	2057772/00	--	2057772/00
	<b>TOTAL</b>	<b>2230587/00</b>	<b>--</b>	<b>2230587/00</b>


**CONTRACTOR**

  
**EXECUTIVE ENGINEER**  
**PUBLIC HEALTH ENGG: DIVISION**  
**GHOTKI @ MIRPUR MATHELO**

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

**CONTRACTOR**

  
**EXECUTIVE ENGINEER**  
**PUBLIC HEALTH ENGG: DIVISION**  
**GHOTKI @ MIRPUR MATHELO**

**SCHEDULE OF PRICES****NAME OF WORK**      **CONSTRUCTION OF SURFACE DRAINS & CC PAVER AT VILLAGE KHUNHARA TALUKA GHOTKI.****A**    **SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing riffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	1304.20 CFT	RS: 3176/25	P%0 CFT	RS: 4142/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	269.80 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 30457/00
	20.76 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 2996/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)			
	260.00 RFT Type-I	RS:94/00	P.RFT	RS: 24440/00
	150.00 RFT Type-II	RS:174/00	P.RFT	RS: 26100/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	727.50 CFT	RS: 11948/36	P% CFT	RS: 86924/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	970.00 CFT	RS: 2283/93	P% CFT	RS: 22154/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 268356/00</b>


**B**    **CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	8480.00CFT	RS: 2117/50	P.%0CFT	RS: 17956/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	8480.00CFT	RS: 502/52	P.%CFT	RS: 42614/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	8480.00CFT	RS: 354/00	P.%0CFT	RS: 3002/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	1441.60CFT	RS: 1800/00	P.%CFT	RS: 25949/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	2798.40CFT	RS: 9416/28	P.%CFT	RS: 263505/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	8480.00CFT	RS: 199/77	P.SFT	RS: 1694050/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	265.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 29915/00
			<b>TOTAL</b>	<b>RS: 2076991/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	268356/00	--	268356/00
2	CC Paver	2076991/00	--	2076991/00
	<b>TOTAL</b>	<b>2345347/00</b>	<b>--</b>	<b>2345347/00</b>

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO



**SCHEDULE OF PRICES****NAME OF WORK**      **CONSTRUCTION OF SURFACE DRAINS & CC PAVER**  
**AT VILLAGE GHULAM LEGHARI TALUKA GHOTKI.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing riffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	1183.20 CFT	RS: 3176/25	P%0 CFT	RS: 3758/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	239.55 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 27042/00
	16.77 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 2420/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc compete as per detailed drawing (PHSI No 5 P.44)			
	210.00 RFT Type-I	RS:94/00	P.RFT	RS: 19740/00
	150.00 RFT Type-II	RS:174/00	P.RFT	RS: 26100/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	652.50 CFT	RS: 11948/36	P% CFT	RS: 77963/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	870.00 CFT	RS: 2283/93	P% CFT	RS: 19870/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 248036/00</b>

**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	5040.00CFT	RS: 2117/50	P.%0CFT	RS: 10672/00
02	Carrage of Earth (CSI No:08 P No: 02)			
	5040.00CFT	RS: 502/52	P.%CFT	RS: 25327/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	5040.00CFT	RS: 354/00	P.%0CFT	RS: 1784/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	856.80CFT	RS: 1800/00	P.%CFT	RS: 15422/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	1663.20CFT	RS: 9416/28	P.%CFT	RS: 156612/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	5040.00CFT	RS: 199/77	P.SFT	RS: 1006841/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	120.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 13547/00
			<b>TOTAL</b>	<b>RS: 1230205/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	248036/00	--	248036/00
2	CC Paver	1230205/00	--	1230205/00
	<b>TOTAL</b>	<b>1478241/00</b>	--	<b>1478241/00</b>


CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

**SCHEDULE OF PRICES****NAME OF WORK      CONSTRUCTION OF SURFACE DRAINS & CC PAVER  
AT VILLAGE ASLAM LEGHARI TALUKA GHOTKI.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing riffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)	941.20 CFT	RS: 3176/25	P%0 CFT	RS: 2989/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)	179.05 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 20213/00
		08.78 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 1268/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)	110.00 RFT Type-I	RS:94/00	P.RFT	RS: 10340/00
		150.00 RFT Type-II	RS:174/00	P.RFT	RS: 26100/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)	502.50 CFT	RS: 11948/36	P% CFT	RS: 60041/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)	670.00 CFT	RS: 2283/93	P% CFT	RS: 15302/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
				<b>TOTAL</b>	<b>RS: 207396/00</b>


**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)	2160.00CFT	RS: 2117/50	P.%0CFT	RS: 4874/00
02	Carraige of Earth (CSI No:08 P No: 02)	2160.00CFT	RS: 502/52	P.%CFT	RS: 10854/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete	2160.00CFT	RS: 354/00	P.%0CFT	RS: 765/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4	367.20CFT	RS: 1800/00	P.%CFT	RS: 6610/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)	712.80CFT	RS: 9416/28	P.%CFT	RS: 67119/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)	2160.00CFT	RS: 199/77	P.SFT	RS: 431503/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)	60.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 6773/00
				<b>TOTAL</b>	<b>RS: 528198/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	207396/00	--	207396/00
2	CC Paver	528198/00	--	528198/00
	<b>TOTAL</b>	<b>735594/00</b>	--	<b>735594/00</b>


CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

**SCHEDULE OF PRICES**

**NAME OF WORK**                      **CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE JAMAL GOTH MEMON  
MOHALLAH TALUKA GHOTKI.**

**A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing ruffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)	1183.20 CFT	RS: 3176/25	P%0 CFT	RS: 3758/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)	239.55 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 27042/00
		16.77 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 2420/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)	210.00 RFT Type-I	RS:94/00	P.RFT	RS: 19740/00
		150.00 RFT Type-II	RS:174/00	P.RFT	RS: 26100/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)	652.50 CFT	RS: 11948/36	P% CFT	RS: 77963/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)	870.00 CFT	RS: 2283/93	P% CFT	RS: 19870/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
				<b>TOTAL</b>	<b>RS: 248036/00</b>

**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)	5040.00CFT	RS: 2117/50	P.%0CFT	RS: 10672/00
02	Carraige of Earth (CSI No:08 P No: 02)	5040.00CFT	RS: 502/52	P.%CFT	RS: 25327/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete	5040.00CFT	RS: 354/00	P.%0CFT	RS: 1784/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4	856.80CFT	RS: 1800/00	P.%CFT	RS: 15422/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)	1663.20CFT	RS: 9416/28	P.%CFT	RS: 156612/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)	5040.00CFT	RS: 199/77	P.SFT	RS: 1006841/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)	120.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 13547/00
				<b>TOTAL</b>	<b>RS: 1230205/00</b>

**SCHEDULE OF PRICES****NAME OF WORK      CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE KARIM DINO GHOTO TALUKA  
GHOTKI.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing riffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	1995.50 CFT	RS: 3176/25	P%0 CFT	RS: 3797/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	229.50 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 25908/00
	11.98 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 1728/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc compete as per detailed drawing (PHSI No 5 P.44)			
	150.00 RFT Type-I	RS:94/00	P.RFT	RS: 14100/00
	185.00 RFT Type-II	RS:174/00	P.RFT	RS: 32190/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	641.25 CFT	RS: 11948/36	P% CFT	RS: 76619/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	855.00 CFT	RS: 2283/93	P% CFT	RS: 19528/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 245013/00</b>

**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	5130.00CFT	RS: 2117/50	P.%0CFT	RS: 10863/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	5130.00CFT	RS: 502/52	P.%CFT	RS: 25779/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	5130.00CFT	RS: 354/00	P.%0CFT	RS: 1816/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	872.10CFT	RS: 1800/00	P.%CFT	RS: 15698/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	1692.90CFT	RS: 9416/28	P.%CFT	RS: 159408/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	5130.00CFT	RS: 199/77	P.SFT	RS: 1024820/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	135.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 15240/00
			<b>TOTAL</b>	<b>RS: 1253624/00</b>

**SCHEDULE OF PRICES****NAME OF WORK      CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE KARIM DINO GHOTO TALUKA  
GHOTKI.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing riffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)	1995.50 CFT	RS: 3176/25	P%0 CFT	RS: 3797/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)	229.50 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 25908/00
		11.98 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 1728/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)	150.00 RFT Type-I	RS:94/00	P.RFT	RS: 14100/00
		185.00 RFT Type-II	RS:174/00	P.RFT	RS: 32190/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)	641.25 CFT	RS: 11948/36	P% CFT	RS: 76619/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)	855.00 CFT	RS: 2283/93	P% CFT	RS: 19528/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
				<b>TOTAL</b>	<b>RS: 245013/00</b>

**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)	5130.00CFT	RS: 2117/50	P.%0CFT	RS: 10863/00
02	Carraige of Earth (CSI No:08 P No: 02)	5130.00CFT	RS: 502/52	P.%CFT	RS: 25779/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete	5130.00CFT	RS: 354/00	P.%0CFT	RS: 1816/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4	872.10CFT	RS: 1800/00	P.%CFT	RS: 15698/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)	1692.90CFT	RS: 9416/28	P.%CFT	RS: 159408/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)	5130.00CFT	RS: 199/77	P.SFT	RS: 1024820/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)	135.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 15240/00
				<b>TOTAL</b>	<b>RS: 1253624/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	245013/00	--	245013/00
2	CC Paver	1253624/00	--	1253624/00
	<b>TOTAL</b>	<b>1498637/00</b>	<b>--</b>	<b>1498637/00</b>

CONTRACTOR

  
**EXECUTIVE ENGINEER**  
**PUBLIC HEALTH ENGG: DIVISION**  
**GHOTKI @ MIRPUR MATHELO**

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
**EXECUTIVE ENGINEER**  
**PUBLIC HEALTH ENGG: DIVISION**  
**GHOTKI @ MIRPUR MATHELO**



**SCHEDULE OF PRICES****NAME OF WORK      CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE JUMO GHOTO TALUKA  
GHOTKI.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing ruffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	1995.50 CFT	RS: 3176/25	P%0 CFT	RS: 3797/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	229.50 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 25908/00
	11.98 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 1728/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)			
	150.00 RFT Type-I	RS:94/00	P.RFT	RS: 14100/00
	185.00 RFT Type-II	RS:174/00	P.RFT	RS: 32190/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	641.25 CFT	RS: 11948/36	P% CFT	RS: 76619/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	855.00 CFT	RS: 2283/93	P% CFT	RS: 19528/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 245013/00</b>


**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	5130.00CFT	RS: 2117/50	P.%0CFT	RS: 10863/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	5130.00CFT	RS: 502/52	P.%CFT	RS: 25779/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	5130.00CFT	RS: 354/00	P.%0CFT	RS: 1816/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	872.10CFT	RS: 1800/00	P.%CFT	RS: 15698/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	1692.90CFT	RS: 9416/28	P.%CFT	RS: 159408/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	5130.00CFT	RS: 199/77	P.SFT	RS: 1024820/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	135.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 15240/00
			<b>TOTAL</b>	<b>RS: 1253624/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	245013/00	--	245013/00
2	CC Paver	1253624/00	--	1253624/00
	<b>TOTAL</b>	<b>1498637/00</b>	<b>--</b>	<b>1498637/00</b>


CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

**SCHEDULE OF PRICES****NAME OF WORK      CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE JALAL GHOTO TALUKA  
GHOTKI.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing ruffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	1995.50 CFT	RS: 3176/25	P%0 CFT	RS: 3797/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	229.50 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 25908/00
	11.98 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 1728/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc compete as per detailed drawing (PHSI No 5 P.44)			
	150.00 RFT Type-I	RS:94/00	P.RFT	RS: 14100/00
	185.00 RFT Type-II	RS:174/00	P.RFT	RS: 32190/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	641.25 CFT	RS: 11948/36	P% CFT	RS: 76619/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	855.00 CFT	RS: 2283/93	P% CFT	RS: 19528/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 245013/00</b>


**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	5130.00CFT	RS: 2117/50	P.%0CFT	RS: 10863/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	5130.00CFT	RS: 502/52	P.%CFT	RS: 25779/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	5130.00CFT	RS: 354/00	P.%0CFT	RS: 1816/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	872.10CFT	RS: 1800/00	P.%CFT	RS: 15698/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	1692.90CFT	RS: 9416/28	P.%CFT	RS: 159408/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	5130.00CFT	RS: 199/77	P.SFT	RS: 1024820/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	135.00CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 15240/00
			<b>TOTAL</b>	<b>RS: 1253624/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	245013/00	--	245013/00
2	CC Paver	1253624/00	--	1253624/00
	<b>TOTAL</b>	<b>1498637/00</b>	<b>--</b>	<b>1498637/00</b>

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

**SCHEDULE OF PRICES****NAME OF WORK      CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE HAYAT MALIK TALUKA  
GHOTKI.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing ruffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	692.00 CFT	RS: 3176/25	P%0 CFT	RS: 2198/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	135.50 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 15296/00
	07.99 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 1152/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)			
	100.00 RFT Type-I	RS:94/00	P.RFT	RS: 9400/00
	100.00 RFT Type-II	RS:174/00	P.RFT	RS: 17400/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	375.00 CFT	RS: 11948/36	P% CFT	RS: 44806/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	500.00 CFT	RS: 2283/93	P% CFT	RS: 11420/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 172815/00</b>


**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)			
	2472.00CFT	RS: 2117/50	P.%0CFT	RS: 5234/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	2472.00CFT	RS: 502/52	P.%CFT	RS: 12422/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	2472.00CFT	RS: 354/00	P.%0CFT	RS: 875/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	420.24CFT	RS: 1800/00	P.%CFT	RS: 7564/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	815.76CFT	RS: 9416/28	P.%CFT	RS: 76814/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	2472.00CFT	RS: 199/77	P.SFT	RS: 493831/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	77.25CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 8721/00
			<b>TOTAL</b>	<b>RS: 605461/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	172815/00	--	172815/00
2	CC Paver	605461/00	--	605461/00
	<b>TOTAL</b>	<b>778276/00</b>	<b>--</b>	<b>778276/00</b>

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

**SCHEDULE OF PRICES**

**NAME OF WORK**                      **CONSTRUCTION OF SURFACE DRAINS & CC PAVER  
AT VILLAGE KAMBIR KOLACHI, MOHALLAH ALI  
GOHAR KOLACHI & USTAD HAROON KOLACHI  
TALUKA GHOTKI.**

**A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing ruffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)			
	1280.00 CFT	RS: 3176/25	P%0 CFT	RS: 4066/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.17)			
	263.75 CFT 1:4:8	RS: 11288/75	P% CFT	RS: 29774/00
	19.97 CFT 1:2:4	RS: 14429/25	P% CFT	RS: 2881/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc compete as per detailed drawing (PHSI No 5 P.44)			
	250.00 RFT Type-I	RS:94/00	P.RFT	RS: 23500/00
	150.00 RFT Type-II	RS:174/00	P.RFT	RS: 26100/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)			
	712.50 CFT	RS: 11948/36	P% CFT	RS: 85132/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)			
	950.00 CFT	RS: 2283/93	P% CFT	RS: 21697/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)			
	138.00 SFT	RS: 337/00	P.SFT	RS: 46506/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)			
	4.93 CWT	RS: 5001/70	P CWT	RS: 24637/00
			<b>TOTAL</b>	<b>RS: 264293/00</b>


**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11			
	8030.00CFT	RS: 2117/50	P.%0CFT	RS: 17004/00
02	Carraige of Earth (CSI No:08 P No: 02)			
	8030.00CFT	RS: 502/52	P.%CFT	RS: 40352/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete			
	8030.00CFT	RS: 354/00	P.%0CFT	RS: 2843/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4			
	1365.10FT	RS: 1800/00	P.%CFT	RS: 24572/00
05	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (CSI No: 4 P No: 14)			
	2649.90CFT	RS: 9416/28	P.%CFT	RS: 249522/00
06	Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)			
	8030.00CFT	RS: 199/77	P.SFT	RS: 1604153/00
07	Cement concrete plain i/c placing compacting finishing & curing etc complete i/c screening washing of stone aggregate without shuttering (CSI No: 5 P No:16)			
	182.50CFT 1:4:8	RS: 11288/75	P.%CFT	RS: 20602/00
			<b>TOTAL</b>	<b>RS: 1959048/00</b>

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	264293/00	--	264293/00
2	CC Paver	1959048/00	--	1959048/00
	<b>TOTAL</b>	<b>2223341/00</b>	--	<b>2223341/00</b>


CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO



**SCHEDULE OF PRICES****NAME OF WORK CONSTRUCTION OF SURFACE DRAINS & CC  
PAVER AT VILLAGE YOUNIS CHACHAR MOHALLAH  
GHULAM HUSSAIN CHACHAR TALUKA KHAN  
GARH.****A SURFACE DRIANS**

01	Excavation in foundation of building bridges and other structures i/c dag belling dressing riffling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5"fit (CSI No 18 P.5)	38977.87 CFT	RS: 3176/25	P%0 CFT	RS: 123803/00
02	Cement concrete plain i/c placing compacting finishing curing complete i/c screening and washing of stone aggregate w/o shuttering Ratio1:4:8 (CSI No 5 P.16)	6306.07 CFT	RS: 14429/75	P% CFT	RS: 711876/00
03	Construction of standard open drain cunnette block of CC 1:2:4 in situ to design profile i/c applying floating coat of cement 1/3 thick to the exposed face finished smooth curing etc complete as per detailed drawing (PHSI No 5 P.44)	5865.00 RFT Type-I	RS:94/00	P.RFT	RS: 551310/00
		2445.00 RFT Type-II	RS:174/00	P.RFT	RS: 425430/00
		800.00 RFT Type-III	Rs: 309/00	P.RFT	RS: 247200/00
04	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (CSI No 11 P.25)	21014.00 CFT	RS: 11948/36	P% CFT	RS: 2510947/00
05	Cement plaster 1:4 upto 20"fit height ½ thick (CSI No11 P.58)	24575.00 CFT	RS: 2283/93	P% CFT	RS: 561285/00
06	RCC work in roof slabs beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respect (CSI No 6 P.19)	4373.94 SFT	RS: 337/00	P.SFT	RS: 1474018/00
07	Fabrication of M.S rain forcemeat for CC i/c cutting bending lying in position making joints and fastening i/c cost of binding wire also removal of rust from bars (CSI No 7 P.29)	156.21 CWT	RS: 5001/70	P CWT	RS: 781316/00
				<b>TOTAL</b>	<b>RS: 7387185/00</b>

**B CC PAVER**

01	Barrow pit excavation undressed lead up to 100 ft( CSI No. 3 P. 11)	1365.00CFT	RS: 2117/50	P.%0CFT	RS: 2890/00
02	Carraige of Earth (CSI No:08 P No: 02)	1365.00CFT	RS: 502/52	P.%CFT	RS: 6859/00
03	Laying earth in 6" layer leveling dressing & watering for compaction etc complete	10460.00CFT	RS: 354/00	P.%0CFT	RS: 3703/00
04	Hard Murrum or fine powdery murrum SMI No: 71 P No:4	2690.00CFT	RS: 1800/00	P.%CFT	RS: 48420/00
05	Cement concrete plain compacting finishing and queering etc complete 1:2:4 i/c surface finishing and dividng in to panels 3" thick (CSI No: 5 P No: 16)	138.00CFT	RS: 14429/25	P.%SFT	RS: 19912/00

06. Erection and removal of centering of RCC or plain cement concrete work of partial wood vertical (CSI No. 19 (B) (III) P-18) 1:2:4  
 225.83 Sft                      RS: 3127/41                      P.% SFT                      RS: 7063/00
07. Providing fixing Cement Paving Blocks flooring having size of 197x97x60(M.M) of city Quddra / Cobble shape with natural colours having strength between 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern & design / etc complete (CSI No: 71 P No: 49)  
 10995.00SFT                      RS: 199/77                      P.SFT                      RS: 2196471/00

**TOTAL RS: 2285318/00**

**C.C. Block**

- 1/ Barrow pit excavation undressed lead up to 100 ft in ordinary soil( C.S.I.NO:1 P-NO:1)  
 54813.25 cft                      @ Rs: 2117/50 p-% cft                      Rs: 116068/00
- 2/ Carriage of earth (C.S.I NO: 08 P-NO: 02) Lead 2 miles  
 Qty same as item No: 1                      = 54813.25 cft  
 54813.25 cft                      @Rs: 502/52 P-% cft                      Rs: 275448/00
- 3/ Laying earth in 6" layers leveling dressing & watering for compaction etc. ( C.S.I NO:13-b P-3 )  
 83712.00 cft                      @Rs: 354/00 p-% cft                      Rs: 29634/00
- 4/ Cement Concrete brick or stone ballast 1 1/2" to 2" gauge ( C.S.I NO: 4 p-no 15)  
 For c.c block  
 18416.64 cft                      @Rs: 9416/28 p-% cft                      Rs: 1734162/00
5. Cement concrete plain i/c placing, compacting, finishing curing i/c screening & Washing of stone aggregate w/o shuttering Ratio 1:2:4 (c.s.i no 05 p-no16)  
 13952.0 ft                      @Rs: 14429/25 p-% sft                      Rs: 2013168/00

**Total Rs: 4168480/00**

## ABSTRACT

S#	NAME OF WORK	SCHEDULE	NON-SCHEDULE	TOTAL
1	Surface Drains	7387185/00	--	7387185/00
2	CC Paver	2285318/00	--	2285318/00
3.	CC Block	4168480/00		4168480/00
	<b>TOTAL</b>	<b>13840983/00</b>	--	<b>13840983/00</b>

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO

### CONDITION

- 01 The work shall have to be executed according to PWD/PHE specification
- 02 No premium on non schedule item shall be allowed to the contractor
- 03 Any error omission in the description of item of work and the rate shall be governed with the relevant schedule of rate and estimate
- 04 The contractor shall have to bring the material to be used from the quarries mentioned in the estimate

CONTRACTOR

  
EXECUTIVE ENGINEER  
PUBLIC HEALTH ENGG: DIVISION  
GHOTKI @ MIRPUR MATHELO