



OFFICE OF THE
EXECUTIVE ENGINEER
BUILDINGS DIVISION N'FEROZE

NO:TC/G-55/ 219 /2018

N'Feroze,dt:/ 22/01/ 2018

To,

The Director Information,
(Advertisement) Relation Sindh,
Government of Sindh,
KARACHI.

SUBJECT: TENDER INVITING NOTICE.

Enclosed kindly find herewith the N.I.T (07 copies) for vide publication
in the three Wews papers English, Urdu and sindhi.

D/A as above

EXECUTIVE ENGINEER
Buildings Division,
NAUSHAHERO FEROZE.

Copy of N.I.T alongwith C.D to the Director (C.B) Sindh Public
Procurement Regulatory Authority (SPPRA) Barrack 8, Secretariat 4A,
Court Road Karachi for information and hoisting on Authority's
website.

EXECUTIVE ENGINEER
Buildings Division,
NAUSHAHERO FEROZE.

SPPRA INWARD DIARY

NO :

4929

DATED :

24-01-2018

4000
FEROZE CD
24-01-18

ANNUAL PROCUREMENT PLAN

WORKS & SERVICES DEPARTMENT IN RESPECT OF BUILDINGS DIVISION N'FEROZE

FOR THE FINANCIAL YEAR 2017-18 OFFICE OF THE EXECUTIVE ENGINEER BUILDINGS DIVISION N'FEROZE

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	IIIrd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
ADP SCHEMES											
1	Construction of Brick Pavement, C.C. topping, Surface Drains and Culverts Taluka Bhiria (13 units) District N'feroze	-	-	4.525	ADP	National competition Bidding	1.131	-	-	-	
2	Construction of Brick Pavement, C.C. topping, Surface Drains and Culverts Taluka Bhiria (08 units) District N'feroze	-	-	4.525	ADP	National competition Bidding	1.131	-	-	-	
3	Construction of Brick Pavement, C.C. topping, Surface Drains and Culverts Taluka Bhiria (06 units) District N'feroze	-	-	4.153	ADP	National competition Bidding	1.038	-	-	-	
4	Construction of Brick Pavement, C.C. topping, Surface Drains, Culverts & Compound wall Taluka Bhiria (09 units) District N'feroze	-	-	4.500	ADP	National competition Bidding	1.125	-	-	-	
5	Construction of Brick Pavement, C.C. topping, Surface Drains, Culverts & Compound wall Taluka Bhiria (06 units) District N'feroze	-	-	4.300	ADP	National competition Bidding	1.075	-	-	-	
6	Construction of Brick Pavement, C.C. topping, Surface Drains, Culverts & Compound wall Taluka Bhiria (16 units) District N'feroze	-	-	4.150	ADP	National competition Bidding	1.038	-	-	-	
7	Construction of Brick Pavement, C.C. topping, Surface Drains, Culverts & Compound wall Taluka Bhiria & Kandiaro (08 units) District N'feroze	-	-	4.097	ADP	National competition Bidding	1.024	-	-	-	
8	Construction of Brick Pavement, C.C. topping, Surface Drains, C.C. Paver Blocks & Compound wall Taluka Kandiaro (02 units) District N'feroze	-	-	4.500	ADP	National competition Bidding	1.125	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
9	Construction of Brick Pavement, C.C. topping, Surface Drains, Taluka Kandiaro (03 units) District N'feroze	-	-	4.300	ADP	National competition Bidding	1.075	-	-	-	
10	Construction of Brick Pavement, C.C. topping, Surface Drains & Compound wall Taluka Kandiaro (07 units) District N'feroze	-	-	4.500	ADP	National competition Bidding	1.125	-	-	-	
11	Construction of Brick Pavement, C.C. topping, Surface Drains, & Compound wall Taluka Kandiaro (03 units) District N'feroze	-	-	4.500	ADP	National competition Bidding	1.125	-	-	-	
12	Construction of Surface Drains, C.C. topping and Brick Pavement Union Council Daris & Manaheen (08 units) Taluka Moro District N'feroze	-	-	4.100	ADP	National competition Bidding	1.025	-	-	-	
13	Construction of Surface Drains, C.C. topping and Brick Pavement Union Council Daris (10 units) Taluka Moro District N'feroze	-	-	4.100	ADP	National competition Bidding	1.025	-	-	-	
14	Construction of Surface Drains, C.C. topping and Brick Pavement Union Council Khairwah, Lundki & Khaliso (08 units) Taluka Moro District N'feroze	-	-	4.100	ADP	National competition Bidding	1.025	-	-	-	
15	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts (14 units) Taluka Moro District N'feroze	-	-	4.325	ADP	National competition Bidding	1.081	-	-	-	
16	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts (13 units) Taluka Moro District N'feroze	-	-	4.500	ADP	National competition Bidding	1.125	-	-	-	
17	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts (08 units) Taluka Moro District N'feroze	-	-	4.250	ADP	National competition Bidding	1.063	-	-	-	
18	Construction of Surface Drains / Nala at Shahi Bazar Moro city Taluka Moro District N'feroze	-	-	4.100	ADP	National competition Bidding	1.025	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	IIIrd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
19	Construction of Surface Drains, cc topping and Brick Pavement (12 units) Taluka & District N'feroze	-	-	4.500	ADP	National competition Bidding	1.125	-	-	-	
20	Construction of Surface Drains, cc topping, Brick Pavement & Culverts (09 units) Taluka & District N'feroze	-	-	4.225	ADP	National competition Bidding	1.056	-	-	-	
21	Construction of Surface Drains, cc topping, Brick Pavement & Culverts (11 units) Taluka & District N'feroze	-	-	4.400	ADP	National competition Bidding	1.100	-	-	-	
22	Revovation / Rehabilitation of Residential Quarters and Compound wall (02 units) Taluka N'feroze District N'feroze	-	-	5.000	ADP	National competition Bidding	1.250	-	-	-	
23	Construction of C.C. Paver, Surface Drains, c.c. topping and Brick Pavement (03 units) Taluka N'Feroze	-	-	4.700	ADP	National competition Bidding	1.175	-	-	-	
24	Construction of Medical Dispensary at village Sahib Khan Rajper U/C Jiando Rajper Taluka Mehrabpur District N'feroze	-	-	4.300	ADP	National competition Bidding	1.075	-	-	-	
25	Constuction of Medical Dispensary at village Mubarak Buriro Taluka Moro District N'feroze	-	-	4.300	ADP	National competition Bidding	1.075	-	-	-	
COMMUNITY DEVELOPMENT PROGRAMME								-	-	-	
26	Construction of Surface Drains & Brick Pavement U/C Abran (08 units) Taluka & District N'feroze	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	
27	Construction of Surface Drains, Brick Pavement, Culverts & UPVC Pipes U/C Bhurnd (11 Units) Taluka & District N'feroze	-	-	4.400	CDP	National competition Bidding	4.400	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
28	Construction of Surface Drains, Brick Pavement & Culverts U/C Bhurnd (08 Units) Taluka & District N'feroze	-	-	4.600	CDP	National competition Bidding	4.600	-	-	-	
29	Construction of Surface Drains, Brick Pavement & Culverts U/C Bhurnd & TC Mithiani (09 Units) Taluka & District N'feroze	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	
30	Construction of Surface Drains, Brick Pavement & Culverts U/C Bhurnd (07 Units) Taluka & District N'feroze	-	-	4.100	CDP	National competition Bidding	4.100	-	-	-	
31	Construction of Surface Drains, Brick Pavement & C.C. Paver Blocks U/C Bhurnd & TC N'Feroze (03 Units) Taluka & District N'feroze	-	-	4.400	CDP	National competition Bidding	4.400	-	-	-	
32	Construction of Surface Drains, Brick Pavement & C.C. Paver Blocks TC N'Feroze & U/C Wagan (05 Units) Taluka & District N'feroze	-	-	4.200	CDP	National competition Bidding	4.200	-	-	-	
33	Construction of Surface Drains, Brick Pavement & Culverts U/C Dalipota (10 Units) Taluka Bhiria District N'feroze	-	-	4.300	CDP	National competition Bidding	4.300	-	-	-	
34	Construction of Surface Drains & Brick Pavement U/C Koor Hassan, Serhal and TC N'Feroze (12 Units) Taluka & District N'feroze	-	-	4.100	CDP	National competition Bidding	4.100	-	-	-	
35	Construction of Surface Drains, Brick Pavement & Culverts U/C Koor Hassan (07 Units) Taluka & District N'feroze	-	-	4.100	CDP	National competition Bidding	4.100	-	-	-	
36	Construction of Surface Drains, Brick Pavement & Culverts U/C Lalia & Lett (12 Units) Taluka Moro District N'feroze	-	-	4.800	CDP	National competition Bidding	4.800	-	-	-	
37	Construction of Surface Drains, Brick Pavement & Culverts U/C Lett & Dejarja (07 Units) Taluka Moro District N'feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
38	Construction of Surface Drains & Brick Pavement U/C Lett (07 Units) Taluka Moro District N'feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
39	Construction of Surface Drains & Brick Pavement T/C Mithiani (06 Units) Taluka & District N'feroze	-	-	4.200	CDP	National competition Bidding	4.200	-	-	-	
40	Construction of Surface Drains & Brick Pavement U/C New Jatoi & Salehpur (08 Units) Taluka Moro District N'feroze	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	
41	Construction of Surface Drains & Brick Pavement U/C Noorpur, Serhal & Thatt(10 Units) Taluka & District N'feroze	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	
42	Construction of Surface Drains & Brick Pavement U/C Thatt (07 Units) Taluka & District N'feroze	-	-	4.400	CDP	National competition Bidding	4.400	-	-	-	
43	Construction of Surface Drains & Brick Pavement U/C Wagan (10 Units) Taluka & District N'feroze	-	-	4.400	CDP	National competition Bidding	4.400	-	-	-	
44	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Khahi Qasim & Jalbani Taluka Bhiria District N'Feroze (14 units)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
45	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Dali & Jalbani Taluka Bhiria District N'Feroze (11 units)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
46	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Dali Taluka Bhiria District N'Feroze (15 units)	-	-	4.400	CDP	National competition Bidding	4.400	-	-	-	
47	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Dali & Kot Bahadur Taluka Bhiria District N'Feroze (09 units)	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
48	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Kot Bahadur & Khahi Maman Taluka Bhiria District N'Feroze (13 units)	-	-	4.900	CDP	National competition Bidding	4.900	-	-	-	
49	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Khahi Maman & Khahi Qasim Taluka Bhiria District N'Feroze (10 units)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
50	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Jalbani Taluka Bhiria District N'Feroze (17 units)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
51	Construction of Surface Drains, C.C. topping, Brick Pavement, Culverts & Compound wall at Union Council Mad Aleem, Detha, Kamal Dero, Abad, Ladho Rano & Bhorthi	-	-	4.100	CDP	National competition Bidding	4.100	-	-	-	
52	Construction of C.C. paver Block, Surface Drains, Brick Pavement & C.C topping at Town Committee Tharushah & Union Council Molhan Taluka Bhiria District N'Feroze (05	-	-	4.600	CDP	National competition Bidding	4.600	-	-	-	
53	Construction of C.C. paver Block, C.C. topping & Surface Drains at ward No: 01 to 07 at Bhiria city Taluka Bhiria District N'Feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
54	Construction of C.C. Paver Blocks, C.C. topping, Surface Drains, Compound wall & Brick Pavement at TC Bhiria city & TC Tharushah (03 units) Taluka Bhiria District N'Feroze	-	-	4.103	CDP	National competition Bidding	4.103	-	-	-	
55	Construction of Surface Drains, C.C. topping & Brick Pavement at Union Council Shaikhani, Muhabatdero, Kouro Khan Khushik & Kamaldero (09 Units) Taluka Kandiaro	-	-	4.700	CDP	National competition Bidding	4.700	-	-	-	
56	Construction of C.C. Paver Blocks, Surface Drains, C.C. topping & Brick Pavement at TC Halani & Union Council Behlani (05 Units) Taluka Mehrabpur District Naushahro	-	-	4.200	CDP	National competition Bidding	4.200	-	-	-	
57	Construction of C.C. Paver Blocks, Surface Drains, C.C. topping & Brick Pavement at Union Council Kotri Kabir (07 Units) Taluka Mehrabpur District Naushahro Feroze	-	-	4.200	CDP	National competition Bidding	4.200	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
58	Construction of Surface Drains, C.C. topping & Brick Pavement at Union Council Dehat & Kotri Kabir (05 Units) Taluka Mehrabpur District Naushahro Feroze	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	
59	Construction of Surface Drains, C.C. topping & Brick Pavement at TC Mehrabpur (04 Units) Taluka Mehrabpur District Naushahro Feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
60	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Ghullam Shah (10 Units) Taluka Kandiaro District Naushahro Feroze	-	-	4.600	CDP	National competition Bidding	4.600	-	-	-	
61	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Ghanghra (08 Units) Taluka Kandiaro District Naushahro Feroze	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	
62	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Moria & Jam Noorullah (10 Units) Taluka Kandiaro District N'Feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
63	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Jam Noorullah, Kandhar & Abad (10 Units) Taluka Kandiaro District Naushahro Feroze	-	-	4.900	CDP	National competition Bidding	4.900	-	-	-	
64	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Shaikhani, Kamaldero, Kouro Khan Khushik & Khan wahan (08 Units) Taluka Kandiaro	-	-	4.800	CDP	National competition Bidding	4.800	-	-	-	
65	Construction of Surface Drains, C.C. topping & Brick Pavement at Town Committee Mehrabpur, U/C Kotri Kabir & Behlani (06 units) Taluka Mehrabpur District N'Feroze	-	-	4.100	CDP	National competition Bidding	4.100	-	-	-	
66	Construction of Surface Drains, Brick Pavement & C.C. Paver Blocks at Union Council Muhabatdero & Shakhani (03 Units) Taluka Kandiaro & Mehrabpur District N'Feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
67	Construction of C.C. topping and Surface Drains & Brick Pavement (02 units) Taluka Moro District N'feroze	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
68	Construction of Surface Drains, C.C. topping Brick Pavement at Union Council Kot Satabo, Deparja, Salehpur, Lalia and Manaheen Taluka Moro District N'feroze (13units)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
69	Construction of Surface Drains, C.C. topping Brick Pavement at Municipal Committee Taluka Moro District N'feroze (13 units)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
70	Construction of Surface Drains, C.C. topping Brick Pavement at Union Council Vessar & Masur-ji-wah Taluka & District N'feroze (11 units)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
71	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts at Union Council Chanari, Cheeho & Bhambhri (07 units) Taluka & District N'feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
72	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts at Town Committee Mithiani, Union Council Koor Hassan, Abran & Bhurnd (10 units) Taluka & District N'feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
73	Providing / Fixing Solar Lights at various Places of Taluka Moro District N'feroze	-	-	17.000	CDP	National competition Bidding	17.000	-	-	-	
74	Providing / Fixing Solar Lights at various Places of Taluka N'feroze District N'feroze	-	-	4.800	CDP	National competition Bidding	4.800	-	-	-	
75	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Dr. Ayaz Colony N'feroze city Taluka & District N'feroze (Part-A)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
76	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Dr. Ayaz Colony N'feroze city Taluka & District N'feroze (Part-B)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
77	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Channa & Siyal Muhalla ward No: 8 N'feroze city Taluka & District N'feroze.	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	IIIrd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
78	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Mehran Colony N'feroze city Taluka & District N'feroze (Part-A)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
79	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Mehran Colony N'feroze city Taluka & District N'feroze (Part-B)	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
80	Construction of Common Toilet 03 Nos., RCC Shade over Graves & Solar Light at Shaheed Sanhiee Gwader at village Muhammad Siddique Lakho Kandiaro District N'feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
81	Construction / Renovation of Drainage ward No: 01, 02 & 03 at Naushahro Feroze city Taluka & District N'feroze	-	-	4.400	CDP	National competition Bidding	4.400	-	-	-	
82	Construction / Renovation of Drainage ward No: 04, 05 & 06 at Naushahro Feroze city Taluka & District N'feroze	-	-	4.300	CDP	National competition Bidding	4.300	-	-	-	
83	Construction / Renovation of Drainage ward No: 06 & 07 at Naushahro Feroze city Taluka & District N'feroze	-	-	4.300	CDP	National competition Bidding	4.300	-	-	-	
84	Construction of Compound wall i/c Steel gate at Eid Gah village Cheeho Taluka & District N'feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
85	Renovation of Mehran Club Moro city Taluka Moro	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
86	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Lakha Road (12 units) Taluka Mehrabpur District N'feroze.	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	
87	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Lakha Road & Saeedpur (15 units) Taluka Mehrabpur District N'feroze.	-	-	4.300	CDP	National competition Bidding	4.300	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
88	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Ghanghra & Dabhro (04 units) Taluka Kandiaro District N'feroze	-	-	4.900	CDP	National competition Bidding	4.900	-	-	-	
89	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Mad Aleem & TC Tharushah (10 units) Taluka Bhiria District N'feroze	-	-	4.100	CDP	National competition Bidding	4.100	-	-	-	
90	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Mad Aleem & Molhan (09 units) Taluka Bhiria District N'feroze	-	-	4.050	CDP	National competition Bidding	4.050	-	-	-	
91	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Dabhro & Manjuth (07 units) Taluka Kandiaro District N'feroze	-	-	5.000	CDP	National competition Bidding	5.000	-	-	-	
92	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Soomar Channar & Darbelow (08 units) Taluka Kandiaro District N'feroze	-	-	4.500	CDP	National competition Bidding	4.500	-	-	-	
93	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Darbelow (07 units) Taluka Kandiaro District N'feroze	-	-	4.800	CDP	National competition Bidding	4.800	-	-	-	
94	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Darbelow & Deh Pir Murad (07 units) Taluka Kandiaro District N'feroze	-	-	4.200	CDP	National competition Bidding	4.200	-	-	-	
95	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Jam Noorullah, Khan wahan and Manjuth (05 units) Taluka Kandiaro	-	-	4.800	CDP	National competition Bidding	4.800	-	-	-	
96	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Halani & Dabhro (08 units) Taluka Kandiaro District N'feroze	-	-	4.700	CDP	National competition Bidding	4.700	-	-	-	
97	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Molhan, Ladho Rano and Dali (04 units) Taluka Bhiria District N'feroze	-	-	4.100	CDP	National competition Bidding	4.100	-	-	-	

S.#	Name of Schemes	Quantity (Where applicable)	Estimated Unit Cost (Where applicable)	Estimated Cost	Source of Funds ADP / Non-ADP / Community	Proposed Procurement method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	2	3	4	5	6	7	8	9	10	11	12
98	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Dabhro, Saeedpur Ghullam Shah & Kandhar (06 units) Taluka Kandiaro District	-	-	4.800	CDP	National competition Bidding	4.800	-	-	-	
99	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains Ladho Rano & TC Tharushah (06 units) Taluka Bhiria District N'feroze	-	-	4.050	CDP	National competition Bidding	4.050	-	-	-	
100	Providing & Fixing Solar Lights at various Locations in Taluka Mehrabpur District N'feroze	-	-	4.620	CDP	National competition Bidding	4.620	-	-	-	
101	Providing & Fixing Solar Lights at various Locations in Taluka Kandiaro District N'feroze	-	-	4.620	CDP	National competition Bidding	4.620	-	-	-	
102	Providing & Fixing Solar Lights at various Locations in Taluka Bhiria District N'feroze	-	-	4.620	CDP	National competition Bidding	4.620	-	-	-	
103	Providing & Fixing Solar Lights at various Locations in Taluka Mehrabpur & Kandiaro District N'feroze	-	-	4.620	CDP	National competition Bidding	4.620	-	-	-	
104	Providing & Fixing Solar Lights at various Locations in Taluka Kandiaro and Bhiria District N'feroze	-	-	4.620	CDP	National competition Bidding	4.620	-	-	-	
105	Construction of C.C Paver, C/wall & Jointing & Testing PE Rinsing main from disposal (03 units) Taluka Kandiaro	-	-	4.500	ADP	National competition Bidding	1.125	-	-	-	
106	Construction of C.C Paver, Surface Drains, (A&B) c.c topping 2 Nos. Culverts & Brick Pavement N'feroze & Moro (03 units)	-	-	5.000	ADP	National competition Bidding	1.250	-	-	-	
107	Construction of Auditorium Hall at DC Complex N'feroze (Furniture)	-	-	10.000	ADP	National competition Bidding	2.500	-	-	-	

OFFICE OF THE EXECUTIVE ENGINEER BUILDINGS DIVISION NAUSHAHRO FEROZE

NO:TC/G-55/ 218 /of 2018

Dated 22/01/2018.

Sealed Bids on standard Bidding Document forms are invited from all interested persons / parties Contractors / firms of SPPRA Rules 2010 (Amended 2017) for the following works.

S.#	Name of Schemes	Taluka	Estimated Cost	Earnest Money	Tender Fee	Time Period
1	2	3	4	5	6	7
	ADP SCHEMES 2017-18					
1	Construction of Brick Pavement, C.C. topping, Surface Drains and Culverts Taluka Bhiria (13 units) District N'feroze	Bhiria	4.525	0.226	3000	24-Months
2	Construction of Brick Pavement, C.C. topping, Surface Drains and Culverts Taluka Bhiria (08 units) District N'feroze	Bhiria	4.525	0.226	3000	24-Months
3	Construction of Brick Pavement, C.C. topping, Surface Drains and Culverts Taluka Bhiria (06 units) District N'feroze	Bhiria	4.153	0.208	3000	24-Months
4	Construction of Brick Pavement, C.C. topping, Surface Drains, Culverts & Compound wall Taluka Bhiria (09 units) District N'feroze	Bhiria	4.500	0.225	3000	24-Months
5	Construction of Brick Pavement, C.C. topping, Surface Drains, Culverts & Compound wall Taluka Bhiria (06 units) District N'feroze	Bhiria	4.300	0.215	3000	24-Months
6	Construction of Brick Pavement, C.C. topping, Surface Drains, Culverts & Compound wall Taluka Bhiria (16 units) District N'feroze	Bhiria	4.150	0.208	3000	24-Months
7	Construction of Brick Pavement, C.C. topping, Surface Drains, Culverts & Compound wall Taluka Bhiria & Kandiaro (08 units) District N'feroze	Bhiria	4.097	0.205	3000	24-Months
8	Construction of Brick Pavement, C.C. topping, Surface Drains, C.C. Paver Blocks & Compound wall Taluka Kandiaro (02 units) District N'feroze	Kandiaro	4.500	0.225	3000	24-Months
9	Construction of Brick Pavement, C.C. topping, Surface Drains, Taluka Kandiaro (03 units) District N'feroze	Kandiaro	4.300	0.215	3000	24-Months
10	Construction of Brick Pavement, C.C. topping, Surface Drains & Compound wall Taluka Kandiaro (07 units) District N'feroze	Kandiaro	4.500	0.225	3000	24-Months
11	Construction of Brick Pavement, C.C. topping, Surface Drains, & Compound wall Taluka Kandiaro (03 units) District N'feroze	Kandiaro	4.500	0.225	3000	24-Months
12	Construction of Surface Drains, C.C. topping and Brick Pavement Union Council Daris & Manaheen (08 units) Taluka Moro District N'Feroze	Moro	4.100	0.205	3000	24-Months
13	Construction of Surface Drains, C.C. topping and Brick Pavement Union Council Daris (10 units) Taluka Moro District N'Feroze	Moro	4.100	0.205	3000	24-Months
14	Construction of Surface Drains, C.C. topping and Brick Pavement Union Council Khairwah, Lundki & Khaliso (08 units) Taluka Moro District N'Feroze	Moro	4.100	0.205	3000	24-Months
15	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts (14 units) Taluka Moro District N'Feroze	Moro	4.325	0.216	3000	24-Months
16	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts (13 units) Taluka Moro District N'Feroze	Moro	4.500	0.225	3000	24-Months
17	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts (08 units) Taluka Moro District N'Feroze	Moro	4.250	0.213	3000	24-Months
18	Construction of Surface Drains / Nala at Shahi Bazar Moro city Taluka Moro District N'feroze	Moro	4.100	0.205	3000	24-Months
19	Construction of Surface Drains, cc topping and Brick Pavement (12 units) Taluka & District N'feroze	N.Feroze	4.500	0.225	3000	24-Months

20	Construction of Surface Drains, cc topping, Brick Pavement & Culverts (09 units) Taluka & District N'feroze	N.Feroze	4.225	0.211	3000	24-Months
21	Construction of Surface Drains, cc topping, Brick Pavement & Culverts (11 units) Taluka & District N'feroze	N.Feroze	4.400	0.220	3000	24-Months
22	Revovation / Rehabilitation of Residential Quarters and Compound wall (02 units) Taluka N'feroze District N'feroze	N.Feroze	5.000	0.250	3000	24-Months
23	Construction of C.C. Paver, Surface Drains, c.c. topping and Brick Pavement (03 units) Taluka N'Feroze	N.Feroze	4.700	0.235	3000	24-Months
24	Construction of Medical Dispensary at village Sahib Khan Rajper U/C Jiando Rajper Taluka Mehrabpur District N'feroze	M'Pur	4.300	0.215	3000	24-Months
25	Constuction of Medical Dispensary at village Mubarak Buriro Taluka Moro District N'feroze	Moro	4.300	0.215	3000	24-Months
	COMMUNITY DEVELOPMENT PROGRAMME 2017-18					
26	Construction of Surface Drains & Brick Pavement U/C Abran (08 units) Taluka & District N'feroze	N'Feroze	4.500	0.225	3000	6-Months
27	Construction of Surface Drains, Brick Pavement, Culverts & UPVC Pipes U/C Bhurnd (11 Units) Taluka & District N'feroze	N'Feroze	4.400	0.220	3000	6-Months
28	Construction of Surface Drains, Brick Pavement & Culverts U/C Bhurnd (08 Units) Taluka & District N'feroze	N'Feroze	4.600	0.230	3000	6-Months
29	Construction of Surface Drains, Brick Pavement & Culverts U/C Bhurnd & TC Mithiani (09 Units) Taluka & District N'feroze	N'Feroze	4.500	0.225	3000	6-Months
30	Construction of Surface Drains, Brick Pavement & Culverts U/C Bhurnd (07 Units) Taluka & District N'feroze	N'Feroze	4.100	0.205	3000	6-Months
31	Construction of Surface Drains, Brick Pavement & C.C. Paver Blocks U/C Bhurnd & TC N'Feroze (03 Units) Taluka & District N'feroze	N'Feroze	4.400	0.220	3000	6-Months
32	Construction of Surface Drains, Brick Pavement & C.C. Paver Blocks TC N'Feroze & U/C Wagan (05 Units) Taluka & District N'feroze	N'Feroze	4.200	0.210	3000	6-Months
33	Construction of Surface Drains, Brick Pavement & Culverts U/C Dalipota (10 Units) Taluka Bhiria District N'feroze	Bhiria	4.300	0.215	3000	6-Months
34	Construction of Surface Drains & Brick Pavement U/C Koor Hassan, Serhal and TC N'Feroze (12 Units) Taluka & District N'feroze	N'Feroze	4.100	0.205	3000	6-Months
35	Construction of Surface Drains, Brick Pavement & Culverts U/C Koor Hassan (07 Units) Taluka & District N'feroze	N'Feroze	4.100	0.205	3000	6-Months
36	Construction of Surface Drains, Brick Pavement & Culverts U/C Lalia & Lett (12 Units) Taluka Moro District N'feroze	Moro	4.800	0.240	3000	6-Months
37	Construction of Surface Drains, Brick Pavement & Culverts U/C Lett & Deparja (07 Units) Taluka Moro District N'feroze	Moro	5.000	0.250	3000	6-Months
38	Construction of Surface Drains & Brick Pavement U/C Lett (07 Units) Taluka Moro District N'feroze	Moro	5.000	0.250	3000	6-Months
39	Construction of Surface Drains & Brick Pavement T/C Mithiani (06 Units) Taluka & District N'feroze	N'Feroze	4.200	0.210	3000	6-Months
40	Construction of Surface Drains & Brick Pavement U/C New Jatoi & Salehpur (08 Units) Taluka Moro District N'feroze	N'Feroze	4.500	0.225	3000	6-Months
41	Construction of Surface Drains & Brick Pavement U/C Noorpur, Serhal & Thatt(10 Units) Taluka & District N'feroze	N'Feroze	4.500	0.225	3000	6-Months
42	Construction of Surface Drains & Brick Pavement U/C Thatt (07 Units) Taluka & District N'feroze	N'Feroze	4.400	0.220	3000	6-Months
43	Construction of Surface Drains & Brick Pavement U/C Wagan (10 Units) Taluka & District N'feroze	N'Feroze	4.400	0.220	3000	6-Months
44	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Khahi Qasim & Jalbani Taluka Bhiria District N'Feroze (14 units)	Bhiria	5.000	0.250	3000	6-Months
45	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Dali & Jalbani Taluka Bhiria District N'Feroze (11 units)	Bhiria	5.000	0.250	3000	6-Months

46	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Dali Taluka Bhiria District N'Feroze (15 units)	Bhiria	4.400	0.220	3000	6-Months
47	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Dali & Kot Bahadur Taluka Bhiria District N'Feroze (09 units)	Bhiria	4.500	0.225	3000	6-Months
48	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Kot Bahadur & Khahi Maman Taluka Bhiria District N'Feroze (13 units)	Bhiria	4.900	0.245	3000	6-Months
49	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Khahi Maman & Khahi Qasim Taluka Bhiria District N'Feroze (10 units)	Bhiria	5.000	0.250	3000	6-Months
50	Construction of Brick Pavement, Surface Drains, C.C. topping & Culverts at Union Council Jalbani Taluka Bhiria District N'Feroze (17 units)	Bhiria	5.000	0.250	3000	6-Months
51	Construction of Surface Drains, C.C. topping, Brick Pavement, Culverts & Compound wall at Union Council Mad Aleem, Detha, Kamal Dero, Abad, Ladho Rano & Bhorti Taluka Bhiria & Kandiaro District N'Feroze (10 units)	Bhiria	4.100	0.205	3000	6-Months
52	Construction of C.C. paver Block, Surface Drains, Brick Pavement & C.C topping at Town Committee Tharushah & Union Council Molhan Taluka Bhiria District N'Feroze (05 units)	Bhiria	4.600	0.230	3000	6-Months
53	Construction of C.C. paver Block, C.C. topping & Surface Drains at ward No: 01 to 07 at Bhiria city Taluka Bhiria District N'Feroze	Bhiria	5.000	0.250	3000	6-Months
54	Construction of C.C. Paver Blocks, C.C. topping, Surface Drains, Compound wall & Brick Pavement at TC Bhiria city & TC Tharushah (03 units) Taluka Bhiria District N'Feroze	Bhiria	4.103	0.205	3000	6-Months
55	Construction of Surface Drains, C.C. topping & Brick Pavement at Union Council Shaikhani, Muhabatdero, Kouro Khan Khushik & Kamaldero (09 Units) Taluka Kandiaro District Naushahro Feroze	Kandiaro	4.700	0.235	3000	6-Months
56	Construction of C.C. Paver Blocks, Surface Drains, C.C. topping & Brick Pavement at TC Halani & Union Council Behlani (05 Units) Taluka Mehrabpur District Naushahro Feroze	M'Pur	4.200	0.210	3000	6-Months
57	Construction of C.C. Paver Blocks, Surface Drains, C.C. topping & Brick Pavement at Union Council Kotri Kabir (07 Units) Taluka Mehrabpur District Naushahro Feroze	M'Pur	4.200	0.210	3000	6-Months
58	Construction of Surface Drains, C.C. topping & Brick Pavement at Union Council Dehat & Kotri Kabir (05 Units) Taluka Mehrabpur District Naushahro Feroze	M'Pur	4.500	0.225	3000	6-Months
59	Construction of Surface Drains, C.C. topping & Brick Pavement at TC Mehrabpur (04 Units) Taluka Mehrabpur District Naushahro Feroze	M'Pur	5.000	0.250	3000	6-Months
60	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Ghullam Shah (10 Units) Taluka Kandiaro District Naushahro Feroze	Kandiaro	4.600	0.230	3000	6-Months
61	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Ghanghra (08 Units) Taluka Kandiaro District Naushahro Feroze	Kandiaro	4.500	0.225	3000	6-Months
62	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Moria & Jam Noorullah (10 Units) Taluka Kandiaro District N'Feroze	Kandiaro	5.000	0.250	3000	6-Months
63	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Jam Noorullah, Kandhar & Abad (10 Units) Taluka Kandiaro District Naushahro Feroze	Kandiaro	4.900	0.245	3000	6-Months

64	Construction of Surface Drains, C.C. topping & Brick Pavement at U/C Shaikhani, Kamaldero, Kouro Khan Khushik & Khanwahani (08 Units) Taluka Kandiaro	Kandiaro	4.800	0.240	3000	6-Months
65	Construction of Surface Drains, C.C. topping & Brick Pavement at Town Committee Mehrabpur, U/C Kotri Kabir & Behlani (06 units) Taluka Mehrabpur District N'Feroze	M'Pur	4.100	0.205	3000	6-Months
66	Construction of Surface Drains, Brick Pavement & C.C. Paver Blocks at Union Council Muhabatdero & Shakhani (03 Units) Taluka Kandiaro & Mehrabpur District N'Feroze	Kandiaro/ M'Pur	5.000	0.250	3000	6-Months
67	Construction of C.C. topping and Surface Drains & Brick Pavement (02 units) Taluka Moro District N'feroze	Moro	4.500	0.225	3000	6-Months
68	Construction of Surface Drains, C.C. topping Brick Pavement at Union Council Kot Satabo, Deparja, Salehpur, Lalia and Manaheen Taluka Moro District N'feroze (13units)	Moro	5.000	0.250	3000	6-Months
69	Construction of Surface Drains, C.C. topping Brick Pavement at Muncipal Committee Taluka Moro District N'feroze (13 units)	Moro	5.000	0.250	3000	6-Months
70	Construction of Surface Drains, C.C. topping Brick Pavement at Union Council Vessar & Masur-ji-wah Taluka & District N'feroze (11 units)	N'Feroze	5.000	0.250	3000	6-Months
71	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts at Union Council Chanari, Cheeho & Bhambhri (07 units) Taluka & District N'feroze	N'Feroze	5.000	0.250	3000	6-Months
72	Construction of Surface Drains, C.C. topping, Brick Pavement & Culverts at Town Committee Mithiani, Union Council Koor Hassan, Abran & Bhurnd (10 units) Taluka & District N'feroze	N'Feroze	5.000	0.250	3000	6-Months
73	Providing / Fixing Solar Lights at various Places of Taluka Moro District N'feroze	Moro	17.000	0.850	3000	6-Months
74	Providing / Fixing Solar Lights at various Places of Taluka N'Feroze District N'feroze	N'Feroze	4.800	0.240	3000	6-Months
75	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Dr. Ayaz Colony N'feroze city Taluka & District N'feroze (Part-A)	N'Feroze	5.000	0.250	3000	6-Months
76	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Dr. Ayaz Colony N'feroze city Taluka & District N'feroze (Part-B)	N'Feroze	5.000	0.250	3000	6-Months
77	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Channa & Siyal Muhalla ward No: 8 N'feroze city Taluka & District N'feroze.	N'Feroze	5.000	0.250	3000	6-Months
78	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Mehran Colony N'feroze city Taluka & District N'feroze (Part-A)	N'Feroze	5.000	0.250	3000	6-Months
79	Construction of C.C. Paver Block, C.C. topping & Surface Drains at Mehran Colony N'feroze city Taluka & District N'feroze (Part-B)	N'Feroze	5.000	0.250	3000	6-Months
80	Construction of Common Toilet 03 Nos., RCC Shade over Graves & Solar Light at Shaheed Sanhiee Gwader at village Muhammad Siddique Lakho Kandiaro District N'feroze	Kandiaro	5.000	0.250	3000	6-Months
81	Construction / Renovation of Drainage ward No: 01, 02 & 03 at Naushahro Feroze city Taluka & District N'feroze	N'Feroze	4.400	0.220	3000	6-Months
82	Construction / Renovation of Drainage ward No: 04, 05 & 06 at Naushahro Feroze city Taluka & District N'feroze	N'Feroze	4.300	0.215	3000	6-Months
83	Construction / Renovation of Drainage ward No: 06 & 07 at Naushahro Feroze city Taluka & District N'feroze	N'Feroze	4.300	0.215	3000	6-Months
84	Constrcution of Compound wall i/c Steel gate at Eid Gah village Cheeho Taluka & District N'feroze	N'Feroze	5.000	0.250	3000	6-Months

85	Renovation of Mehran Club Moro city Taluka Moro	Moro	5.000	0.250	3000	6-Months
86	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Lakha Road (12 units) Taluka Mehrabpur District N'feroze.	M'Pur	4.500	0.225	3000	6-Months
87	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Lakha Road & Saeedpur (15 units) Taluka Mehrabpur District N'feroze.	M'Pur	4.300	0.215	3000	6-Months
88	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Ghanghra & Dabhro (08 units) Taluka Kandiaro District N'feroze	Kandiaro	4.900	0.245	3000	6-Months
89	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Mad Aleem & TC Tharushah (11 units) Taluka Bhiria District N'feroze	Bhiria	4.100	0.205	3000	6-Months
90	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Mad Aleem & Molhan (09 units) Taluka Bhiria District N'feroze	Bhiria	4.050	0.203	3000	6-Months
91	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Dabhro & Manjuth (07 units) Taluka Kandiaro District N'feroze	Kandiaro	5.000	0.250	3000	6-Months
92	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Soomar Channar & Darbelow (08 units) Taluka Kandiaro District N'feroze	Kandiaro	4.500	0.225	3000	6-Months
93	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Darbelow (07 units) Taluka Kandiaro District N'feroze	Kandiaro	4.800	0.240	3000	6-Months
94	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Darbelow & Deh Pir Murad (07 units) Taluka Kandiaro District N'feroze	Kandiaro	4.200	0.210	3000	6-Months
95	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Jam Noorullah, Khan wahan and Manjuth (05 units) Taluka Kandiaro	Kandiaro	4.800	0.240	3000	6-Months
96	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Halani & Dabhro (08 units) Taluka Kandiaro District N'feroze	Kandiaro	4.700	0.235	3000	6-Months
97	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Molhan, Ladho Rano and Dali (08 units) Taluka Bhiria District N'feroze	Bhiria	4.100	0.205	3000	6-Months
98	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains at union Council Dabhro, Saeedpur Ghullam Shah & Kandhar (06 units) Taluka Kandiaro District N'feroze	Kandiaro	4.800	0.240	3000	6-Months
99	Construction of CC Topping, Brick Pavement, C.C. Paver Block & Surface Drains Ladho Rano & TC Tharushah (06 units) Taluka Bhiria District N'feroze	Bhiria	4.050	0.203	3000	6-Months
100	Providing & Fixing Solar Lights at various Locations in Taluka Mehrabpur District N'feroze	M'Pur	4.620	0.231	3000	6-Months
101	Providing & Fixing Solar Lights at various Locations in Taluka Kandiaro District N'feroze	Kandiaro	4.620	0.231	3000	6-Months
102	Providing & Fixing Solar Lights at various Locations in Taluka Bhiria District N'feroze	Bhiria	4.620	0.231	3000	6-Months
103	Providing & Fixing Solar Lights at various Locations in Taluka Mehrabpur & Kandiaro District N'feroze	Kandiaro	4.620	0.231	3000	6-Months
104	Providing & Fixing Solar Lights at various Locations in Taluka Kandiaro and Bhiria District N'feroze	Bhiria	4.620	0.231	3000	6-Months
105	Construction of C.C Paver, C/wall & Jointing & Testing PE Rinsing main from disposal (03 units) Taluka Kandiaro	Kandiaro	4.500	0.230	3000	24-Months
106	Construction of C.C Paver, Surface Drains, (A&B) c.c topping 2 Nos. Culverts & Brick Pavement N'Feroze & Moro (03 units)	N'Feroze/Moro	5.000	0.250	3000	24-Months
107	Construction of Auditorium Hall at DC Complex N'Feroze (Furniture)	N'Feroze	10.000	0.500	3000	24-Months

TERMS AND CONDITIONS:-

1. The complete set of Bidding Documents may be purchased by an interested eligible/bidder on submission of a written application on pad to the Office given below payment of bid price/ bid fee mentioned against each work from the date of publication of NIT upto 15-02-2018 at 1.00 P.M
2. All bids must be accompanied by Bid Security/Earnest money of the amount mentioned against each work in the form of Call Deposit from any schedule Bank duly pledged in the name of Executive Engineer Buildings Division Naushahro Feroze and must be submitted to this office on or before 16-02-2018 upto 2.00 P.M Bids which will be opened at 3.00 P.M on the same day in the presence of Procurement committee bidders /representatives who choose to attend.
3. If the undersigned or any member of Procurement Committee is out of Head Quarter, the bids will be opened on next working day as per given time.
4. Registration with Pakistan Engineering Council for the year 2017 in the relevant field also specialization of work and Competency to the extent of tender amount of each work.
5. Registration with Income Tax Department (NTN Certificate) and copy of CNIC
6. Registration with SRB (Sindh Revenue Board).
7. Bio-data of Engineers and Technical Staff working with the firm alongwith N.I.C Copies.
8. In case of Works costing to above Rs. 4.000 (M) the PEC Certificate will be applicable.
9. Documentary evidence of works executed / works in progress and certificate of satisfactory completion of works by the employers.
10. List of works in progress indicating cost of each work and copy of the letter of award of work.
11. List of Machinery and equipment available with documentary evidence of its ownership.
12. Bank Statement for Last financial three years to know the soundness of the contractor/firm/agency.
13. Affidavit to the effect that the firm / contractor has not been black listed previously by any executing agency.
14. The detail of all works can be seen at Website www.sindh.gov.pk
15. In case the tenders are cancelled / rejected or un-responded, the next date for issue and opening will be as under.
16. No Conditional Tender and will be entertained.
17. The competent authority reserve the right to reject any or all tenders / bid proposals as per provision of SPPRA Rules 2010 amended in 2017.
18. Blank Tender forms will only be issued personal appearance or representative having authority from owner.
19. Bid validity period 90 days.
20. No bid would be receiving after fixed date and time.
21. In complete bids as per instructions given in bidding documents will be rejected.
Schedule of un-responded and rejected tenders

Date of issue up to at 5/3/18 1.00 P.M & will be received back on 6/3/18 up to 2.00 P.M and open on same day at 3.00 P.M

EXECUTIVE ENGINEER
BUILDINGS DIVISION
NAUSHAHRO FEROZE

Copy is forwarded with compliments to the:

1. The Director Information (Advertisement) Relation Sindh Directorate Block No. 96 Sindh Karachi, for publication in three leading News papers English, Urdu & Sindhi (7 copies NIT enclosed).
2. The Director (CB) Sindh Public Procurement Regularity Authority (SPPRA) Barrack 8, Secretariat 4A Court road Karachi for information and hoisting on Authority's Website.
3. The Deputy Commissioner Naushahro Feroze for information.
4. The Superintending Engineer (W&S) Department Naushahro Feroze for information.
5. The Executive Engineer all under Superintending Engineer (W&S) Department Naushahro Feroze for information.
6. The Assistant Engineer (all) under Executive Engineer Buildings Division Naushahro Feroze.
7. The Divisional Accounts Officer / Draftsman / head Clerk.
8. Copy to Notice Board / C.B/D.B/(Local)

EXECUTIVE ENGINEER
BUILDINGS DIVISION
NAUSHAHRO FEROZE



GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT

16/A

Karachi, dated: March, 2016.

NOTIFICATION

No.E&A(W&S)3-9/91-2016(N.Feroze): With the approval of Competent Authority, a Complaint Redressal Committees with the following composition, in terms of Rule-31 of Sindh Public Procurement Rules-2010 (Amended 2013), is hereby constituted in the Office of Executive Engineer, Buildings Division Naushahro Feroze for the purpose of redressal of grievances and settlement of disputes, if any, arises between procuring agency and bidders:-

- | | |
|--|------------|
| 1. Chief Engineer (Highways), Sukkur. | Chairman ✓ |
| 2. Executive Engineer, Rohri Division,
Irrigation Department. | Member |
| 3. District Accounts Officer, Naushahro Feroze. | Member |

2. The Functions & Responsibilities of the Committee as specified in Rules-31(4) and (5) of Sindh Public Procurement Rules-2010 (Amended 2013) are as under: -


AIJAZ AHMED MEMON
SECRETARY TO GOVT. OF SINDH

No.E&A(W&S)3-9/91-2016(N.Feroze)

Karachi, dated the ^{16/A} March, 2016.

A copy is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Managing Director, SPPRA, Karachi.
3. The Chief Engineer (Highways), Sukkur.
4. ✓ The Chairman / Members of the Committee.
5. The Deputy Director (Monitoring), PM&E Cell, W&SD.
6. P.S to Secretary, W&S Department.
7. Notification file.


SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH

Karachi, dated the 12th July, 2013.

NOTIFICATION

No. E&A(W&S)3-9/91/2013: With the approval of competent authority, a Procurement Committee with the following composition, in terms of Rule-7 of Sindh Public Procurement Rules-2010, is hereby constituted for procurement of "Goods & Works" in the office of Executive Engineer, Buildings Division, Naushahro Feroze, excluding procurement involving foreign exchange with the following composition:-

- | | | |
|------|---|------------|
| i) | Executive Engineer,
Buildings Division,
Naushahro Feroze. | Chairman ✓ |
| ii) | Assistant Engineer,
Buildings Sub-Division,
Kandiaro. | Member |
| iii) | Assistant Engineer,
Public Health Engineering Sub-Division,
Naushahro Feroze. | Member |

2. The Functions & Responsibilities of the Committee, in term of Rule-7 & 8 of SPPRA-2010, shall be as under:

- Preparing of bidding documents.
- Carrying out Technical as well as Financial Evaluation of the bids.
- Preparing Evaluation report as provided in Rule-45;
- Making recommendation for the award of contract to the competent authority; and
- Perform any other function ancillary and incidental to the above.

QAZI SHAHID PERVEZ
SECRETARY TO GOVT. OF SINDH

Karachi dated the 12th July, 2013.

No. E&A(W&S)3-9/91-2013

A copy is forwarded for information to:-

- The Accountant General, Sindh, Karachi.
- The Secretary to Govt. of Sindh, Public Health Engg. Department, Karachi.
- The Managing Director, SPPRA, Karachi.
- The Chief Engineer (Buildings), Sukkur.
- The Superintending Engineer, Works & Services Department, Naushahro Feroze.
- The Deputy Secretary (Tech) Works & Services Department.
- The Deputy Secretary (Admin) Works & Services Department.
- The Deputy Director, PMU - Govt. W&S.
- PS to Secretary Works & Services Department.
- PA to Additional Secretary (Tech), Works & Services Department.
- The Chairman / members of the Committee.
- Notification file.

Signature

(Signature)
Secretary to Govt. of Sindh,
Karachi

T.C.
22/7

T.C.
16/8/13

BIDDING DATA

(This section should be filled in the Engineer / Provincial Agency before issuance of the bidding documents). The following specific data for the works to be tendered shall complementation, or supplement the provisos in the instructions to bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the instructions to bidders).

Instructions to Bidders
Clause Reference

- 1.1 Name of Procuring Agency: **Executive Engineer Buildings Division Naushahro Feroze**
 (Insert name of the Procuring Agency)
- Brief Description of Works: **Construction of Brick Pavement, C.C. topping Surface Drains Culverts Taluka Bhiria (13 units) District N.Feroze**
- 5.1 (a) Procuring Agency's address:- **Near District Accounts Office Naushahro Feroze**
 (Insert Address of the procuring agency with telex/fax) **Telephone No. 0242 – 920029**
- (b) Engineer's address **Near District Accounts Office Naushahro Feroze**
- 10.3 Bid shall be quoted entirely in Pak Rupees. The payment shall be made in Pak Rupees.
- 11.2 The bidder has the financial, Technical and constructional capability necessary to perform the Contract as follows: *(Insert required capabilities and documents)*
- i. Financial capacity: (must have turnover of **Rs. 4.525 (Million)**)
- ii. Technical capacity: (mention the appropriate category of registration with PEC and qualification and experience of the staff)
- iii. Construction of Capacity: (mention the names and number of equipments required for the work)
- Sindh Public Procurement Regulatory Authority www.pprasindh.gov.pk
- 12.1 (a) A detailed description description of the works essential technical and performance classification.
- (b) Complete set of technical information, description data, literature and drawing as required in accordance with Schedule B to Bid. Specific works Data. This will include but not limited to a sufficient number of drawing Photo graphs catalogues. Illustrations and such other information as is necessary in illucate clearly, the significant characteristics such as general construction dimensions and other relevant information about the works to performed.
- 12.1 **Amount of Bid Security** **5%**
 (Fill in lump sum amount or in % age of bid / estimate cost, but not below 1% and not exceeding 5%)
- 14.1 Period of bid validity **90 Days**

(Fill in number of days not exceeding 90)

14.4 Number of copies of the Bid to be submitted

One original Plus 01 copies

14.6 Procuring Agency's Address for the Purpose of Bid submission

**Office of the Executive Engineer Buildings Division
Naushahro Feroze near District Accounts Office at
Naushahro Feroze**

15.1 Deadline for submission of Bid

Time 01:00 PM on 15/12/2018

16.1 Venue, Time and Date of Bid Opening

Venue XEN Buildings Office N'Feroze

Time 02:00 PM on 16/12/2018

16.4 Responsiveness of Bids

(i) Bid is valid till required period

Sindh Public Procurement Regularity Authority | www.pprasindh.gov.pk

(ii) Bid Prices are firm during currency of contract/Price adjustment.

(iii) Completion period offered is within specified limits.

(iv) Bidder is eligible to Bid and possession the requisite experience capacity and qualification.

(v) Bid does not deviate from basic technical requirements and is eligible to Bid and possession the requisite experience capacity and qualification.

(vi) Bid are Generally in order etc does not deviate from basic technical requirements and is eligible to Bid and possession the requisite experience capacity and qualification.

Procuring Agency can adopt either of two options (Select eight of them)

(a) Fixed Price Contractor: In these contracts no escalation will be provided during currency of the contract and namely period of completion of these works is upto 15 months.

(b) Price adjustment Contract:- In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh after Bid opening during currency.


**EXECUTIVE ENGINEER
BUILDINGS DIVISION
NAUSHAHRO FEROZE**

**CONSTITUTION OF BRICK PAVEMENT, CC TOPPING, S/DRAINS
& CULVERTS TALUKA BHIRIA (13-UNITS) DISTRICT
NAUSHAHRO FEROZE (PACKAGE NO.01)**

(SCHEDULE - B)

S.No.	Name of Work	Taluka	Amount
01.	Construction of Brick Pavement ,CC Topp: , Surface Drains & Culverts Taluka Bhiria (13-Units) District N/Feroze.		4.525
1.	Construction of Brick Pavement at Village Peroz Shah Muhalla Chandio Muhalla & Solangi Muhalla at U.C.Dalipota	Bhiria.	0.350
2.	Construction of Brick Pavement at Village Arbab Chandio Muhalla Ghulam Rasool Faqeer U.C.Dalipota Taluka Bhiria.	Bhiria.	0.225
3.	Construction of Surface Drains at Village Raheem Khan Baladi Yar Mohd.Baladi, Mir Mohd.Baladi At U.C.Ladho Rano	Bhiria.	0.350
4.	Construction of Surface Drains & B/Pavement At Village Fazal Mohammad Motmal U.C.Ladho Rano Taluka Bhiria.	Bhiria.	0.375
5.	Construction of Surface Drains & B/Pavement at Village Mohd. Moosa Siyal, Usman Bhangu Syed Muhalla Piyaro U.C.Ladho Rano Taluka Bhiria.	Bhiria.	0.450
6.	Construction of Surface Drains & B/Pavement at Village Buxial Siyal Muhalla Qalander Bux Siyal U.C. Molhan Taluka Bhiria.	Bhiria.	0.375
7.	Construction of Surface Drains, CC Topping & B/Pavement At Village Molvi Rahmatullah Brohi U.C.Raju Keerio	Bhiria	0.400
8.	Construction of Surface Drains, CC Topping & B/Pavement At Village Faqeer Ghulam Hussain U.C.Raju Keerio.	Bhiria	0.400
9.	Construction of Surface Drains, CC Topping & B/Pavement At Village Changal Keerio U.C.Raju Keerio Taluka Bhiria.	Bhiria	0.300
10.	Construction of Surface Drains, CC Topping & B/Pavement At Village Kot Muhajreen U.C.Raju Keerio Taluka Bhiria.	Bhiria	0.300
11.	Construction of Surface Drains, CC Topping & B/Pavement At Village Usman Brohi U.C.Raju Keerio Taluka Bhiria	Bhiria	0.400
12.	Construction of Surface Drains, CC Topping & B/Pavement At Village Usman Brohi U.C.Raju Keerio Taluka Bhiria	Bhiria	0.200
13.	Construction of Surface Drains, CC Topping & B/Pavement At Village Dhengo Muhalla Mian U.C.Raju Keerio Taluka Bhiria.	Bhiria	0.400

TOTAL RS. 4.525(M)

Name of Scheme:- Unit No.1, Constt. of Brick Pavement & Surface Drain at Village Peroz Shah Muhalla, Chandio Muhalla & Solangi Muhalla UC Dalipota (Package No.01).

(SCHEDULE - B)

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

1. PART - A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed
Lead upto 100-feet(a) ordinary soil.

1 x 150.0 x 10.0 x 1.50 = 2250-CFT

Total:- 2250-CFT Rs.2117/50 %Cft. Rs.4764/00

2. Lying earth in 6" layers levelling
Dressing and watering etc.

Same Qty. as item No.2 as above. 2250-CFT

Total:- 2250-CFT Rs.354/00 %Cft. Rs.797/00

3. Dry Brick on dge paving sand
grouted i/c preparation of bed by
watering ramming lead and digging
the same to proper camber by 1/2"
mund plaster.

1 x 320.0 x 10.00 = 3200-SFT

Total:- 3200-Sft. Rs.3823/57 %Sft. Rs.122354/00

TOTAL:- Rs.127915/

2. PART - (B) (SURFACE DRAINS)

1. Excavation found:of Building bridges i/c Dag
Belling-dressing refilling around the structure
with excavated earth watering & ramming lead
upto one chain

T-I 1 x 100.0 x 2.42 x 1.00 = 242-Cft.

T-II 1 x 100.0 x 3.00 x 1.50 = 450-Cft

Total:- 692-CFT. Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting
Finishing & curing complete i/c screening
Washing of stone aggregate w/out shuttering
Ration: 1: 4: 8.

T-I 1 x 100.0 x 2.42 x 0.33 = 80-Cft.

T-II 1 x 100.0 x 3.00 x 0.33 = 179-Cft.

Total:- 230-Cft. Rs.11288/75 %Cft. Rs.20207/00

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I 1 X 100.0 = $\frac{100-Rft}{100-Rft}$ Rs.94/00 P/Rft Rs.9400/00

T-II 1 x100.0 = $\frac{100-Rft}{100-Rft}$
Total:- $\frac{100-Rft}{100-Rft}$ R s.174/00 P/Rft. Rs.17400/00

4. Pacca Brick work in found:plinth in cement

Sand mortor Ratio 1: 6.

T-I 2 x 100.0 x 0.75 x 1.00 = 150-Cft

T-II 2 x 100.0 x 0.75 x 1.50 = 225-Cft

Total:- $\frac{375-Cft}{375-Cft}$ Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster 1/2" thick in cement sand upto 20-ft. height Ratio: 1: 4.

1 x 2 x 100.0 x 1.25 = 250-Cft.

1 x 2 x 100.0 x 1.75 = 350-Cft

Total:- $\frac{600-Cft}{600-Cft}$ Rs.2283/93 %Cft. Rs.13704/00

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. 3 x 10.0 x 3.0 x 0.50 = 45-Cft
Total:- $\frac{45-Cft}{45-Cft}$ Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item $\frac{45 \times 5.0}{112}$ = 2.008-Cwt.

No.6 as bove.

Total:- $\frac{2.008Cwt.}{2.008Cwt.}$ Rs.5000/70 P/CWT Rs.10043/00

Total Rs.132923/00

Name of Scheme:- Unit No.2,Constt.of Brick Pavement at Village Arbab Chandio Muhalla, Muhalla Ghulam Rasool Faqeer UC Dalipota (Package No.01).

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

1. PART – A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed
Lead upto 100-feet(a) ordinary soil.

1 x 392.0 x 10.0 x 1.50 = 5880-CFT

Total:- 5880-CFT Rs.2117/50 %Cft. Rs.12451/00

2. Lying earth in 6" layers levelling
Dressing and watering etc.

Same Qty. as item No.2 as above. 5880-CFT

Total:- 5880-CFT Rs.354/60 %Cft. Rs.2082/00

3. Dry Brick on dge paving sand
grouted i/c preparation of bed by
watering ramming lead and digging
the same to proper camber by 1/2"
mund plaster.

1 x 380.0 x 10.00 = 3800--SFT

Total:- 3800/Sft. Rs.3823/57 %Sft. Rs.145296/00

TOTAL:- Rs.159829/-

Name of Scheme:- Unit No.3,Constt.of Brick Pavement & Surface Drain at Village Raheem Khan Baladi,Yar Mohd. Baladi & Mir Mohd. Baladi UC Ladho Rano (Package No.01).

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

1. PART – A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed
Lead upto 100-feet(a) ordinary soil.

1 x 150.0 x 10.0 x 1.50 = 2250-CFT

Total:- 2250-CFT Rs.2117/50 %Cft. Rs.4764/00

2. Lying earth in 6" layers levelling Dressing and watering etc.

Same Qty. as item No.2 as-above.

2250-CFT

Total:- ~~2250-CFT~~ Rs.354/00 %Cft. Rs.797/00

3. Dry Brick on dge paving sand grouted i/c preparation of bed by watering ramming lead and digging the same to proper camber by 1/2" mund plaster.

1 x 320.0 x 10.00 =

3200--SFT

Total:- ~~3200/Sft.~~ Rs.3823/57 %Sft. Rs.122354/00

TOTAL:- Rs.127915/-

2. PART - (B) (SURFACE DRAINS)

1. Excavation found:of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain

T-I 1 x 100.0 x 2.42 x 1.00 = 242-Cft.

T-II 1 x 100.0 x 3.00 x 1.50 = 450-Cft

Total:-~~692-CFT.~~ Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8.

T-I 1 x 100.0 x 2.42 x 0.33 = 80-Cft.

T-II 1 x 100.0 x 3.00 x 0.33 = 179-Cft

Total:-~~230-Cft.~~ Rs.11288/75 %Cft. Rs.20207/00

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I 1 X 100.0 = 100-Rft

100-RFT Rs.94/00 P/RFT Rs.9400/00

T-II 1 x 100.0 = 100-RFT

Total:- ~~100-Rft.~~ R s.174/00 P/Rft. Rs.17400/00

4. Pacca Brick work in found:plinth in cement Sand mortor Ratio 1: 6.

T-I 2 x 100.0 x 0.75 x 1.00 = 150-Cft

T-II 2 x 100.0 x 0.75 x 1.50 = 225-Cft

Total:-~~375-Cft~~ Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster 1/2" thick in cement sand upto 20-ft. height Ratio: 1: 4.

$$1 \times 2 \times 100.0 \times 1.25 = 250\text{-Cft.}$$

$$- 1 \times 2 \times 100.0 \times 1.75 = 350\text{-Cft}$$

Total:- ~~600-Cft~~ Rs.2283/93 %Cft. Rs.13704/00

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. 3 x 10.0 x 3.0 x 0.50

~~45-Cft~~
Total:- ~~45-Cft~~ Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item 45 x 5.0 = 2.008-Cwt.
No.6 as bove. 112

Total:- ~~2.008Cwt.~~ Rs.5001/79 P/CWT Rs.10043/00

Total Rs.132923/00

Name of Scheme:- Unit No.4,Constt.of Brick Pavement & Surface Drain at Village Fazal Mohd.
Motmal UC Ladho Rano (Package No.01).

1. PART - A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed Lead upto 100-feet(a) ordinary soil.

$$1 \times 150.0 \times 10.0 \times 1.50 = 2250\text{-CFT}$$

Total:- ~~2250-CFT~~ Rs.2117/50 %Cft. Rs.4764/00

2. Lying earth in 6" layers levelling Dressing and watering etc.

Same Qty. as item No.2 as above. 2250-CFT

Total:- ~~2250-CFT~~ Rs.354/00 %Cft. Rs.797/00

3. Dry Brick on dge paving sand grouted i/c preparation of bed by watering ramming lead and digging the same to proper camber by 1/2" mund plaster.

$$1 \times 380.0 \times 10.00 = 3800\text{-SFT}$$

Total:- ~~3800-Sft.~~ Rs.3823/57 %Sft. Rs.145296/00

TOTAL:- ~~Rs.150857/-~~

2. PART - (B) (SURFACE DRAINS)

1. Excavation found: of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain

T-I $1 \times 100.0 \times 2.42 \times 1.00 = 242\text{-Cft.}$

T-II $1 \times 100.0 \times 3.00 \times 1.50 = 450\text{-Cft.}$

Total:-692-CFT. Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8.

T-I $1 \times 100.0 \times 2.42 \times 0.33 = 80\text{-Cft.}$

T-II $1 \times 100.0 \times 3.00 \times 0.33 = 179\text{-Cft.}$

Total:-230-Cft. Rs.11288/75 %Cft. Rs.20207/00

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I $1 \times 100.0 = 100\text{-Rft}$

$\frac{100\text{-RFT}}{100\text{-RFT}}$ Rs.94/00 P/RFT Rs.9400/-

T-II $1 \times 100.0 = 100\text{-Rft}$

Total:- 100-Rft. R s.174/00 P/Rft. Rs.17400/00

4. Pacca Brick work in found:plinth in cement Sand mortar Ratio 1: 6.

T-I $2 \times 100.0 \times 0.75 \times 1.00 = 150\text{-Cft}$

T-II $2 \times 100.0 \times 0.75 \times 1.50 = 225\text{-Cft}$

Total:-375-Cft Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster 1/2" thick in cement sand upto 20-ft. height Ratio:1: 4.

$1 \times 2 \times 100.0 \times 1.25 = 250\text{-Cft.}$

$1 \times 2 \times 100.0 \times 1.75 = 350\text{-Cft}$

Total:-600-Cft Rs.2283/93 %Cft. Rs.13704/00

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. $3 \times 10.0 \times 3.0 \times 0.50 = 45\text{-Cft}$

Total:- 45-Cft Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item $\frac{45 \times 5.0}{112} = 2.008\text{-Cwt.}$

No.6 as bove. $\frac{45 \times 5.0}{112}$

Total:- 2.008Cwt. Rs.5001/70 P/CWT Rs.10043/00

Total Rs.132923/00

Name of Scheme:- Unit No.5,Constt.of Brick Pavement & Surface Drain at Village Muhammad Moosa Siyal,Usman Bhangu Syed Muhalla Piyaro UC Ladho Rano (Package No.01).

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

1. PART – A (BRICK PAVEMENT).

1.	Borrowpit Excavation undressed Leadupto 100-feet(a) ordinary soil. 1 x 200.0 x 10.0 x 1.50 =				3000-CFT			
					<u>3000-CFT</u>	Rs.2117/50	%Cft.	Rs.6353/00
2.	Lying earth in 6"layers levelling Dressing and watering etc. Same Qty. as item No.2 as above.				3000-CFT			
					<u>3000-CFT</u>	Rs.354/00	%Cft.	Rs.1062/00
3.	Dry Brick on dge paving sand grouted i/c preparation of bed by watering ramming lead and digging the same to proper camber by 1/2" mund plaster. 1 x 530.0 x 10.00 =				5300--SFT			
					<u>5300-Sft.</u>	Rs.3823/57	%Sft.	Rs.202649/00
TOTAL:-								Rs.210064/-

2. PART – (B) (SURFACE DRAINS)

1.	Excavation found:of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain T-I 1 x 100.0 x 2.42 x 1.00 = T-II 1 x 100.0 x 3.00x 1.50 =				242-Cft. 450-Cft			
					<u>Total:-692-CFT.</u>	Rs.3176/25	%Cft.	Rs.2198/00
2.	Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8. T-I 1 x 100.0 x 2.42 x 0.33 = T-II 1 x 100.0 x 3.00x 0.33 =				80-C'ft. 179-Cft.			
					<u>Total:-230-Cft.</u>	Rs.11288/75	%Cft.	Rs.20207/00
3.	Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete. T-I 1 X 100.0 = T-II 1 x 100.0 =				100-Rft 100-RFT 100-RFT			
					<u>Total:- 100-Rft</u>	Rs.174/00	P/Rft.	Rs.17400/00

4. Pack Brick work in found: plinth in cement
Sand mortar Ratio 1: 6.

T-I $2 \times 100.0 \times 0.75 \times 1.00 = 150\text{-Cft}$

T-II $2 \times 100.0 \times 0.75 \times 1.50 = 225\text{-Cft}$

Total:- 375-Cft Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster $\frac{1}{2}$ " thick in cement sand upto
20-ft. height Ratio: 1: 4.

$1 \times 2 \times 100.0 \times 1.25 = 250\text{-Cft.}$

$1 \times 2 \times 100.0 \times 1.75 = 350\text{-Cft}$

Total:- 600-Cft Rs.2283/93 %Cft. Rs.13704/00

6. R.C.C.work in all labour and material except the
Cost of steel reinforcement and its labour for
Bending and binding which will be paid separately
And ratio for all kinds of forms moulds lifting
Shuttering curing lintels of shingle ratio 1:2: 4 the
Cement 2-cft.sand 4-cft. $\frac{1}{8}$ to $\frac{1}{4}$ " gauge.

Slab. $3 \times 10.0 \times 3.0 \times 0.50 = 45\text{-Cft}$

Total:- 45-Cft Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c.
i/c cutting bending laying in position making joints
and fastening i/c the cost of binding wires etc.
removal of rust from bars.

Same Qty. as item $\frac{45 \times 5.0}{112} = 2,008\text{-Cwt.}$

No.6 as above.

Total:- 2,008-Cwt. Rs.5001/70 P/CWT Rs.10043/00

Total Rs.132923/00

Name of Scheme:- Unit No.6,Constt.of Brick Pavement & Surface Drain at Village Buxial Siyal
Muhalla Qalander Bux Siyal UC Molhan (Package No.01).

1. PART - A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed
Lead upto 100-feet(a) ordinary soil.

$1 \times 150.0 \times 10.0 \times 1.50 = 2250\text{-CFT}$

Total:- 2250-CFT Rs.2117/50 %Cft. Rs.4764/00

2. Lying earth in 6" layers levelling
Dressing and watering etc.

Same Qty. as item No.2 as above. 2250-CFT

Total:- 2250-CFT Rs.354/00 %Cft. Rs.797/00

3. Dry Brick on dge paving sand grouted i/c preparation of bed by watering ramming lead and digging the same to proper camber by 1/2" mund plaster.

$$1 \times 380.0 \times 10.00 = 3800\text{-Sft}$$

$$\text{Total:- } \underline{3800\text{-Sft.}} \quad \text{Rs.3823/57} \quad \% \text{Sft.} \quad \text{Rs.145296/00}$$

$$\text{TOTAL:- } \underline{\text{Rs.150857/}}$$

2. PART - (B) (SURFACE DRAINS)

1. Excavation found:of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain

$$\text{T-I} \quad 1 \times 100.0 \times 2.42 \times 1.00 = 242\text{-Cft.}$$

$$\text{T-II} \quad 1 \times 100.0 \times 3.00 \times 1.50 = 450\text{-Cft.}$$

$$\text{Total:- } \underline{692\text{-Cft.}} \quad \text{Rs.3176/25} \quad \% \text{Cft.} \quad \text{Rs.2198/00}$$

2. Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8.

$$\text{T-I} \quad 1 \times 100.0 \times 2.42 \times 0.33 = 80\text{-Cft.}$$

$$\text{T-II} \quad 1 \times 100.0 \times 3.00 \times 0.33 = 179\text{-Cft.}$$

$$\text{Total:- } \underline{230\text{-Cft.}} \quad \text{Rs.11288/75} \quad \% \text{Cft.} \quad \text{Rs.20207/00}$$

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

$$\text{T-I} \quad 1 \times 100.0 = \underline{100\text{-Rft}}$$

$$\underline{100\text{-RFT}} \quad \text{Rs.94/00} \quad \text{P/RFT} \quad \text{Rs.9400/-}$$

$$\text{T-II} \quad 1 \times 100.0 = \underline{100\text{-RFT}}$$

$$\text{Total:- } \underline{100\text{-Rft.}} \quad \text{R s.174/00} \quad \text{P/Rft.} \quad \text{Rs.17400/00}$$

4. Pacca Brick work in found:plinth in cement Sand mortar Ratio 1: 6.

$$\text{T-I} \quad 2 \times 100.0 \times 0.75 \times 1.00 = 150\text{-Cft}$$

$$\text{T-II} \quad 2 \times 100.0 \times 0.75 \times 1.50 = 225\text{-Cft}$$

$$\text{Total:- } \underline{375\text{-Cft}} \quad \text{Rs.11948/36} \quad \% \text{Cft.} \quad \text{Rs.44806/00}$$

5. Cement Plaster 1/2" thick in cement sand upto 20-ft. height Ratio: 1: 4.

$$1 \times 2 \times 100.0 \times 1.25 = 250\text{-Cft.}$$

$$1 \times 2 \times 100.0 \times 1.75 = 350\text{-Cft}$$

$$\text{Total:- } \underline{600\text{-Cft}} \quad \text{Rs.2283/93} \quad \% \text{Cft.} \quad \text{Rs.13704/00}$$

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. 3 x 10.0 x 3.0 x 0.50

= 45-Cft
Total:- 45-Cft Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item 45 x 5.0
No.6 as bove. 112

= 2.008-Cwt.
Total:- 2.008-Cwt. Rs.5001/70 P/CWT Rs.10043/00

Total Rs.132923/00

Name of Scheme:- Unit No.7,Constt.of Surface Drains , CC Topping & B/Pavement at Village Rehmatullah Brohi U.C.Raju Keerio Taluka Bhiria (Package No.01).

1. PART – A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed
Lead upto 100-feet(a) ordinary soil.

1 x 10.0 x 10.0 x 1.50 = 150-Cft

Total:- 150-cft. Rs.2117/50 %Cft. Rs.318/00

2. Lying earth in 6"layers levelling
Dressing and watering etc.

Same Qty. as item No.2 as above. 150-Cft.

Total:- 150-Cft. Rs.354/00 %Cft. Rs.53/00

3. Dry Brick on dge paving sand
grouted i/c preparation of bed by
watering ramming lead and digging
the same to proper camber by 1/2"
mund plaster.

1 x 15.0 x 10.00 = 150--Sft.

Total:- 150-Sft. Rs.3823/57 %Sft. Rs.5735/00

TOTAL:- Rs.6106/-

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

2. PART - (B) (SURFACE DRAINS)

1. Excavation found:of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain

T-I 1 x 100.0 x 2.42 x 1.00 = 242-Cft.
T-II 1 x 100.0 x 3.00 x 1.50 = 450-Cft

Total:-692-CFT. Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8.

T-I 1 x 100.0 x 2.42 x 0.33 = 80-Cft.
T-II 1 x 100.0 x 3.00 x 0.33 = 99-Cft.

Total:-179-Cft. Rs.11288/75 %Cft. Rs.20207/00

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I 1 X 100.0 = 100-Rft
100-RFT

Rs.94/00 P/RFT Rs.9400/-

T-II 1 x 100.0 = 100-RFT

Total:- 100-Rft R s.174/00 P/Rft. Rs.17400/00

4. Pacca Brick work in found:plinth in cement Sand mortar Ratio 1: 6.

T-I 2 x 100.0 x 0.75 x 1.00 = 150-Cft
T-II 2 x 100.0 x 0.75 x 1.50 = 225-Cft

Total:-375-Cft Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster 1/2" thick in cement sand upto 20-ft. height Ratio: 1: 4.

1 x 2 x 100.0 x 1.25 = 250-Cft.
1 x 2 x 100.0 x 1.75 = 350-Cft

Total:-600-Cft Rs.2283/93 %Cft. Rs.13704/00

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. 3 x 10.0 x 3.0 x 0.50 = 45-Cft

Total:- 45-Cft Rs.337/00 P/Cft Rs.15165/00

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

7. Fabrication of Mild Steel reinforcement for c.c.
i/c cutting bending laying in position making joints
and fastening i/c the cost of binding wires etc.
removal of rust from bars.

Same Qty. as item $\frac{45 \times 5.0}{112}$
No.6 as above.

= 2.008-Cwt.
Total:- 2.008Cwt. Rs.5001/70 P/CWT Rs.10043/00

Total Rs.132923/00

3. PART - C (CC TOPPING).

1. Borrow pit excavation undressed lead
Upto 100-feet (a) ordinary soils.

1 x 318.0 x 10.0 x 1.50

= 4770-Cft.
Total:- 4770-cft. Rs.2117/50 %Cft. Rs.10100/00

2. Lying earth in 6"layers leveling dressing
Dressing and watering etc.
Same Qty. as item No.2 as above.

= 4770-CFT
Total:- 4770-Cft. Rs.354/00 %Cft. Rs.1689/00

3. Cement concrete Brick or stone Ballast
1-1/2" to 2" gauge Ratio:1:6:12.

1 x 159.0 x 10 x 0.33

= 525-Cft
Total:- 525-Cft. Rs.8122/95 %Cft. Rs.42645/00

4. Cement concrete plain i/c placing compacting
Finishing and curring complete i/c screening
Washing of stone aggregate without shuttering
Ratio 1: 2: 4.

1 x 159.0 x 10 x 0.25

= 398-Cft
Total:- 398-Cft Rs.14429/00 (%CFT Rs.57428/00

TOTAL :- RS.111862/00

Name of Scheme:- Unit No.8,Constt.of Surface Drains , CC Topping & B/Pavement at Village Faqeer Ghulam Hussain Keerio U.C.Raju Keerio Taluka Bhiria (Package No.01).

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

1. PART - A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed
Lead upto 100-feet(a) ordinary soil.

$$1 \times 10.0 \times 10.0 \times 1.50 = 150\text{-Cft}$$

Total:- 150-cft. Rs.2117/50 %Cft. Rs.318/00

2. Lying earth in 6" layers levelling
Dressing and watering etc.

Same Qty. as item No.2 as above. 150-Cft.

Total:- 150-Cft. Rs.354/00 %Cft. Rs.53/00

3. Dry Brick on dge paving sand
grouted i/c preparation of bed by
watering ramming lead and digging
the same to proper camber by 1/2"
mund plaster.

$$1 \times 15.0 \times 10.00 = 150\text{-Sft.}$$

Total:- 150-Sft. Rs.3823/57 %Sft. Rs.5735/00

TOTAL:- Rs.6106/-

2. PART - (B) (SURFACE DRAINS)

1. Excavation found:of Building bridges i/c Dag
Belling dressing refilling around the structure
with excavated earth watering & ramming lead
upto one chain

T-I $1 \times 100.0 \times 2.42 \times 1.00 = 242\text{-Cft.}$

T-II $1 \times 100.0 \times 3.00 \times 1.50 = 450\text{-Cft}$

Total:- 692-Cft. Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting
Finishing & curing complete i/c screening
Washing of stone aggregate w/out shuttering
Ration: 1: 4: 8.

T-I $1 \times 100.0 \times 2.42 \times 0.33 = 80\text{-Cft.}$

T-II $1 \times 100.0 \times 3.00 \times 0.33 = 99\text{-Cft.}$

Total:- 179-Cft. Rs.11288/75 %Cft. Rs.20207/00

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I 1 X 100.0 = ~~100-Rft~~
~~100-RFT~~ Rs.94/00 P/RFT Rs.9400/-

T-II 1 x100.0 = ~~100-RFT~~
Total:- ~~100-Rft.~~ Rs.174/00 P/Rft. Rs.17400/00

4. Pacca Brick work in found:plinth in cement Sand mortor Ratio 1: 6.

T-I 2 x 100.0 x 0.75 x 1.00 = 150-Cft

T-II 2 x 100.0 x 0.75 x 1.50 = ~~225-Cft~~

Total:- ~~375-Cft~~ Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster 1/2" thick in cement sand upto 20-ft. height Ratio: 1: 4.

1 x 2 x 100.0 x 1.25 = 250-Cft.

1 x 2 x 100.0 x 1.75 = ~~350-Cft~~

Total:- ~~600-Cft~~ Rs.2283/93 %Cft. Rs.13704/00

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. 3 x 10.0 x 3.0 x 0.50 = ~~45-Cft~~

Total:- ~~45-Cft~~ Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item $\frac{45 \times 5.0}{112}$ = ~~2.008-Cwt.~~

No.6 as bove.

Total:- ~~2.008Cwt.~~ Rs.5001/70 P/CWT Rs.10043/00

Total Rs.132923/00

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

3. PART - C (CC TOPPING).

1. Borrow pit excavation undressed lead Upto 100-feet (a) ordinary soils.

1 x 318.0 x 10.0 x 1.50 = 4770-Cft.
Total:- 4770-cft. Rs.2117/50 %Cft. Rs.10100/00

2. Lying earth in 6"layers leveling dressing Dressing and watering etc. Same Qty. as item No.2 as above.

4770-Cft.
Total:- 4770-Cft. Rs.354/00 %Cft. Rs.1689/00

3. Cement concrete Brick or stone Ballast 1-1/2" to 2" gauge Ratio:1:6:12.

1 x 159.0 x 10 x 0.33 = 525-Cft.
Total:- 525-Cft. Rs.8122/95 %Cft. Rs.42645/00

4. Cement concrete plain i/c placing compacting Finishing and curring complete i/c screening Washing of stone aggregate without shuttering Ratio 1: 2: 4.

1 x 159.0 x 10 x 0.25 = 398-Cft.
Total:- 398-Cft. Rs.14429/00 %CFT Rs.57428/00

TOTAL :- RS.111862/00

Name of Scheme:- Unit No.9,Constt.of B/P & Surface Drains at Village Chungal Keerio U.C.Raju Keerio Taluka Bhiria District N.Feroze.(Package No.01).

1. PART - A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed Lead upto 100-feet(a) ordinary soil.

1 x 200.0 x 10.0 x 1.50 = 3000-Cft.
Total:- 3000-cft. Rs.2117/50 %Cft. Rs.6353/00

2. Lying earth in 6"layers levelling Dressing and watering etc. Same Qty. as item No.2 as above.

3000-Cft.
Total:- 3000-Cft. Rs.354/00 %Cft. Rs.1062/00

3. Dry Brick on dge paving sand grouted i/c preparation of bed by watering ramming lead and digging the same to proper camber by 1/2" mund plaster.

1 x 180.0 x 10.00 = 1800--Sft.
Total:- 1800-Sft. Rs.3827/57 %Sft. Rs.68824/00

TOTAL:- Rs.76239/-

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

2. PART - (B) (SURFACE DRAINS)

1. Excavation found:of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain

T-I 1 x 100.0 x 2.42 x 1.00 = 242-Cft.

T-II 1 x 100.0 x 3.00 x 1.50 = 450-Cft.

Total:-~~692-CFT.~~ Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8.

T-I 1 x 100.0 x 2.42 x 0.33 = 80-Cft.

T-II 1 x 100.0 x 3.00 x 0.33 = 99-Cft.

Total:-~~179-Cft.~~ Rs.11288/75 %Cft. Rs.20207/00

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I 1 X 100.0 = ~~100-Rft~~
100-RFT

Rs.94/00 P/RFT Rs.9400/-

T-II 1 x 100.0 = ~~100-RFT~~

Total:- ~~100-Rft.~~ R s.174/00 P/Rft. Rs.17400/00

4. Pacca Brick work in found:plinth in cement Sand mortar Ratio 1: 6.

T-I 2 x 100.0 x 0.75 x 1.00 = 150-Cft

T-II 2 x 100.0 x 0.75 x 1.50 = 225-Cft

Total:-~~375-Cft~~ Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster 1/2" thick in cement sand upto 20-ft. height Ratio: 1: 4.

1 x 2 x 100.0 x 1.25 = 250-Cft.

1 x 2 x 100.0 x 1.75 = 350-Cft

Total:-~~600-Cft~~ Rs.2283/93 %Cft. Rs.13704/00

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. 3 x 10.0 x 3.0 x 0.50 = ~~45-Cft~~
 Total:- ~~45-Cft~~ Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item, 45 x 5.0 = 2.008-Cwt
 No.6 as bove. 112
 Total:- 2.008Cwt. Rs.5001/70 P/CWT Rs.10043/00

Total Rs.132923/00

Name of Scheme:- Unit No.10,Constt.of B/P & Surface Drains at Village Kot Muhajreen
U.C.Raju Keerio Taluka Bhiria District N.Feroze.(Package No.01).

1. PART - A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed Lead upto 100-feet(a) ordinary soil.

1 x 200.0 x 10.0 x 1.50 = 3000-Cft
 Total:- ~~3000-cft.~~ Rs.2117/50 %Cft. Rs.6353/00

2. Lying earth in 6" layers levelling Dressing and watering etc.

Same Qty. as item No.2 as above. 3000-Cft.
 Total:- ~~3000-Cft.~~ Rs.354/00 %Cft. Rs.1062/00

3. Dry Brick on dge paving sand grouted i/c preparation of bed by watering ramming lead and digging the same to proper camber by 1/2" mund plaster.

1 x 180.0 x 10.00 = 1800--Sft.
 Total:- ~~1800-Sft.~~ Rs.3823/57 %Sft. Rs.68824/00

TOTAL:- Rs.76239/-

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

2. PART - (B) (SURFACE DRAINS)

1. Excavation found: of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain

T-I $1 \times 100.0 \times 2.42 \times 1.00 = 242\text{-Cft.}$

T-II $1 \times 100.0 \times 3.00 \times 1.50 = 450\text{-Cft.}$

Total: 692-Cft. Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8.

T-I $1 \times 100.0 \times 2.42 \times 0.33 = 80\text{-Cft.}$

T-II $1 \times 100.0 \times 3.00 \times 0.33 = 99\text{-Cft.}$

Total: 179-Cft. Rs.11288/75 %Cft. Rs.20207/00

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I $1 \times 100.0 = 100\text{-Rft}$

100-Rft Rs.94/00 P/Rft Rs.9400/-

T-II $1 \times 100.0 = 100\text{-Rft}$

Total: 100-Rft Rs.174/00 P/Rft. Rs.17400/00

4. Pacca Brick work in found: plinth in cement Sand mortar Ratio 1: 6.

T-I $2 \times 100.0 \times 0.75 \times 1.00 = 150\text{-Cft}$

T-II $2 \times 100.0 \times 0.75 \times 1.50 = 225\text{-Cft}$

Total: 375-Cft Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster $\frac{1}{2}$ " thick in cement sand upto 20-ft. height Ratio: 1: 4.

$1 \times 2 \times 100.0 \times 1.25 = 250\text{-Cft.}$

$1 \times 2 \times 100.0 \times 1.75 = 350\text{-Cft}$

Total: 600-Cft Rs.2283/93 %Cft. Rs.13704/00

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab: 3 x 10.0 x 3.0 x 0.50 = 45-Cft
 Total:- ~~45-Cft~~ Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item No.6 as bove. $\frac{45 \times 5.0}{112} = 2.008\text{-Cwt.}$
 Total:- ~~2.008Cwt.~~ Rs.5001/70 P/CWT Rs.10043/00

Total Rs.132923/00

Name of Scheme:- Unit No.II,Constt.of Surface Drains, CC Topping & B/Pavement at Village Usman Brohi U.C.Raju Keerio Taluka Bhiria (Package No.01).

1. PART - A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed Leadupto 100-feet(a) ordinary soil.

1 x 10.0 x 10.0 x 1.50 = 150-Cft
 Total:- ~~150-cft.~~ Rs.2117/50 %Cft. Rs.318/00

2. Lying earth in 6"layers levelling Dressing and watering etc.

Same Qty. as item No.2 as above. 150-Cft.
 Total:- ~~150-Cft.~~ Rs.354/00 %Cft. Rs.53/00

3. Dry Brick on dge paving sand grouted i/c preparation of bed by watering ramming lead and digging the same to proper camber by 1/2" mund plaster.

1 x 15.0 x 10.00 = 150--Sft.
 Total:- ~~150-Sft.~~ Rs.3823/57 %Sft. Rs.5735/00

TOTAL:- Rs.6106/-

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

2. PART - (B) (SURFACE DRAINS)

1. Excavation found:of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain

T-I $1 \times 100.0 \times 2.42 \times 1.00 = 242\text{-Cft.}$

T-II $1 \times 100.0 \times 3.00 \times 1.50 = 450\text{-Cft.}$

Total:-692-Cft. Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8.

T-I $1 \times 100.0 \times 2.42 \times 0.33 = 80\text{-Cft.}$

T-II $1 \times 100.0 \times 3.00 \times 0.33 = 99\text{-Cft.}$

Total:-179-Cft. Rs.11288/75 %Cft. Rs.20207/00

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I $1 \times 100.0 = 100\text{-Rft}$

100-RFT Rs.94/00 P/RFT Rs.9400/-

T-II $1 \times 100.0 = 100\text{-RFT}$

Total:- 100-Rft. Rs.17400 P/Rft. Rs.17400/00

4. Pacca Brick work in found:plinth in cement Sand mortor Ratio 1: 6.

T-I $2 \times 100.0 \times 0.75 \times 1.00 = 150\text{-Cft}$

T-II $2 \times 100.0 \times 0.75 \times 1.50 = 225\text{-Cft}$

Total:-375-Cft Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster 1/2" thick in cement sand upto 20-ft. height Ratio: 1: 4.

$1 \times 2 \times 100.0 \times 1.25 = 250\text{-Cft.}$

$1 \times 2 \times 100.0 \times 1.75 = 350\text{-Cft}$

Total:-600-Cft Rs.2283/93 %Cft. Rs.13704/00

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. 3 x 10.0 x 3.0 x 0.50

$$= \frac{45\text{-Cft}}{\text{Total:- } 45\text{-Cft}} \text{ Rs.337/00 P/Cft Rs.15165/00}$$

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item No.6 as bove. $\frac{45 \times 5.0}{112}$

$$= \frac{2.008\text{-Cwt}}{\text{Total:- } 2.008\text{Cwt.}} \text{ Rs.5001/70 P/CWT Rs.10043/00}$$

Total Rs.132923/00

3. PART - C (CC TOPPING).

1. Borrow pit excavation undressed lead Upto 100-feet (a) ordinary soils. 1.x 318.0 x 10.0 x 1.50

$$= \frac{4770\text{-Cft.}}{\text{Total:- } 4770\text{-cft.}} \text{ Rs.2117/50 \%Cft. Rs.10100/00}$$

2. Lying earth in 6" layers leveling dressing Dressing and watering etc. Same Qty. as item No.2 as above.

$$\frac{4770\text{-CFT}}{\text{Total:- } 4770\text{-Cft.}} \text{ Rs.354/00 \%Cft. Rs.1689/00}$$

3. Cement concrete Brick or stone Ballast 1-1/2" to 2" gauge Ratio:1:6:12. 1 x 159.0 x 10 x 0.33

$$= \frac{525\text{-Cft}}{\text{Total:- } 525\text{-Cft.}} \text{ Rs.8132/95 \%Cft. Rs.42645/00}$$

4. Cement concrete plain i/c placing compacting Finishing and curring complete i/c screening Washing of stone aggregate without shuttering Ratio 1: 2: 4.

1 x 159.0 x 10 x 0.25

$$= \frac{398\text{-Cft}}{\text{Total:- } 398\text{-Cft}} \text{ Rs.14429/00 \%CFT Rs.57428/00}$$

TOTAL :- RS.111862/00

Name of Scheme:- Unit No.12,Constt.of Brick Pavement at Village Usman Brohi
U.C. Raju Keerio Taluka Bhiria (Package No.01).

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

1. PART – A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed
Lead upto 100-feet(a) ordinary soil.
1 x 200.0 x 10.0 x 1.50 = 3000-Cft
Total:- 3000-cft. Rs.2117/50 %Cft. Rs.6353/00
 2. Lying earth in 6"layers levelling
Dressing and watering etc.
Same Qty. as item No.2 as above. 3000-Cft.
Total:- 3000-Cft. Rs.354/00 %Cft. Rs.1062/00
 3. Dry Brick on dge paving sand
grouted i/c preparation of bed by
watering ramming lead and digging
the same to proper camber by 1/2"
mund plaster.
1 x 380.0 x 10.00 = 3800--Sft.
Total:- 3800-Sft. Rs.3823/57 %Sft. Rs.145296/00
- TOTAL:- Rs.152711/-**

Name of Scheme:- Unit No.13,Constt.of Surface Drains , CC Topping & B/Pavement at Village
Dhengo Muhalla Mian U.C.Raju Keerio Taluka Bhiria (Package No.01).

1. PART – A (BRICK PAVEMENT).

1. Borrowpit Excavation undressed
Lead upto 100-feet(a) ordinary soil.
1 x 10.0 x 10.0 x 1.50 = 150-Cft
Total:- 150-cft. Rs.2117/50 %Cft. Rs.318/00
 2. Lying earth in 6"layers levelling
Dressing and watering etc.
Same Qty. as item No.2 as above. 150-Cft.
Total:- 150-Cft. Rs.354/00 %Cft. Rs.53/00
 3. Dry Brick on dge paving sand
grouted i/c preparation of bed by
watering ramming lead and digging
the same to proper camber by 1/2"
mund plaster.
1 x 15.0 x 10.00 = 150--Sft.
Total:- 150-Sft. Rs.3823/57 %Sft. Rs.5735/00
- TOTAL:- Rs.6106/-**

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

2. PART – (B) (SURFACE DRAINS)

1. Excavation found:of Building bridges i/c Dag Belling dressing refilling around the structure with excavated earth watering & ramming lead upto one chain

T-I 1 x 100.0 x 2.42 x 1.00 = 242-Cft.

T-II 1 x 100.0 x 3.00 x 1.50 = 450-Cft

Total:-~~692-CFT~~ Rs.3176/25 %Cft. Rs.2198/00

2. Cement concrete plain i/c placing compacting Finishing & curing complete i/c screening Washing of stone aggregate w/out shuttering Ratio: 1: 4: 8.

T-I 1 x 100.0 x 2.42 x 0.33 = 80-Cft.

T-II 1 x 100.0 x 3.00 x 0.33 = 99-Cft

Total:-~~179-Cft~~ Rs.11288/75 %Cft. Rs.20207/00

3. Constt..of standard open Drains Block or Concrete ratio:1: 2: 4 cost in situ in Drains Profile etc. complete.

T-I 1 X 100.0 = 100-Rft

~~100-RFT~~ Rs.94/00 P/RFT Rs.9400/-

T-II 1 x 100.0 = 100-RFT

Total:-~~100-Rft~~ R s.174/00 P/Rft. Rs.17400/00

4. Pacca Brick work in found:plinth in cement Sand mortar Ratio 1: 6.

T-I 2 x 100.0 x 0.75 x 1.00 = 150-Cft

T-II 2 x 100.0 x 0.75 x 1.50 = 225-Cft

Total:-~~375-Cft~~ Rs.11948/36 %Cft. Rs.44806/00

5. Cement Plaster ½"thick in cement sand upto 20-ft. height Ratio: 1: 4.

1 x 2 x 100.0 x 1.25 = 250-Cft.

1 x 2 x 100.0 x 1.75 = 350-Cft

Total:-~~600-Cft~~ Rs.2287/93 %Cft. Rs.13704/00

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

6. R.C.C.work in all labour and material except the Cost of stell reinforcement and its labour for Bending and binding which will be paid separately And ratio for all kinds of forms moulds lifting Shuttering curing lintels of shingle ratio 1:2: 4 the Cement 2-cft.sand 4-cft. 1/8 to 1/4" gauge.

Slab. $3 \times 10.0 \times 3.0 \times 0.50 = \frac{45\text{-Cft}}{45\text{-Cft}}$
 Total:- 45-Cft Rs.337/00 P/Cft Rs.15165/00

7. Fabrication of Mild Steel reinforcement for c.c. i/c cutting bending laying in position making joints and fastening i/c the cost of binding wires etc. removal of rust from bars.

Same Qty. as item $\frac{45 \times 5.0}{112} = 2.008\text{-Cwt.}$
 No.6 as bove. 2.008Cwt. Rs.5001/70 P/CWT Rs.10043/00
 Total:-

Total Rs.132923/00

3. PART - C (CC TOPPING).

1. Borrow pit excavation undressed lead Upto 100-feet (a) ordinary soils.

$1 \times 318.0 \times 10.0 \times 1.50 = \frac{4770\text{-Cft}}{4770\text{-cft}}$
 Total:- 4770-cft. Rs.2117/50 %Cft. Rs.10100/00

2. Lying earth in 6" layers leveling dressing Dressing and watering etc. Same Qty. as item No.2 as above.

$\frac{4770\text{-CFT}}{4770\text{-Cft.}}$ Rs.354/00 %Cft. Rs.1689/00
 Total:- 4770-Cft.

3. Cement concrete Brick or stone Ballast 1-1/2" to 2" gauge Ratio:1:6:12.

$1 \times 159.0 \times 10 \times 0.33 = \frac{525\text{-Cft}}{525\text{-Cft.}}$
 Total:- 525-Cft. Rs.8122/95 %Cft. Rs.42645/00

S.No	Item of work	L	B	H/D	QTY.	RATE	UNIT	AMOUNT
------	--------------	---	---	-----	------	------	------	--------

4. Cement concrete plain i/c placing compacting
Finishing and curing complete i/c screening
Washing of stone aggregate without shuttering
Ratio 1: 2: 4.

$$1 \times 159.0 \times 10 \times 0.25 =$$

$$\text{Total:- } \frac{398\text{-Cft}}{398\text{-Cft}}$$

Rs.14429/00 %CFT Rs.57428/00

TOTAL :- RS.111862/00

ABSTRACT.

- 1) PART - A :- RS.1257050/00 (BRICK PAVEMENT)
2) PART - B :- RS.1727999/00 ¹⁴⁶²¹⁵³ (SURFACE DRAINS)
3) PART - C :- RS.447448/00 (CC TOPPING)

TOTAL:-RS.3432497/00

³¹⁶⁶⁶⁵¹
above / below on the


amount to be

Added/deducted on the basis of rates of CSR

of premium quoted.

Total (A + B+C):- in words Rupees.Thirty Four Lacs Thirty Two Thousand Four Hundred Ninty Seven only)

CONTRACTOR


EXECUTIVE ENGINEER,
BUILDINGS DIVISION
NAUSHAHRO FEROZES