

**OFFICE OF THE
LARKANA MUNICIPAL CORPORATION
LARKANA**

No. GB/Estt./LMC-L/ **3933**
Larkana dated: **05-03-2018**

/of/2018
/Feb- 2018

SAY NO TO CORRUPTION

Invitation for Bids

1. This office invites sealed bids from eligible bidders, procurers, firms & companies for the following works as per SPPRA procedure.

S.No.	Name of Work / Scheme and Location	Estimated Cost in Million	Earnest Money in Rs.	Tender Fee in Million	Time for Completion
1.	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 01 Ward No. 02 & 04 Larkano City	4.240	212000	0.0050	04 Months
2	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 01 Ward No. 01 & 03 Larkano City	4.650	232500	0.0050	04 Months
3	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 02 Ward No. 01 & 02 Larkano City	5.000	250000	0.0050	04 Months
4	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 02 Ward No. 03 & 04 Larkano City	5.600	280000	0.0060	04 Months
5	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 03 Ward No. 04 Larkano City	5.312	265600	0.0060	04 Months
6	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 03 Ward No. 04 Larkano City	4.471	223550	0.0050	04 Months
7	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 04 Ward No. 01 & 02 Larkano City	7.600	380000	0.0060	04 Months
8	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 04 Ward No. 03 & 04 Larkano City	5.250	260000	0.0060	04 Months
9	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 05 Ward No. 01 & 03 Larkano City	5.300	265000	0.0060	04 Months
10	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 05 Ward No. 02 & 04 Larkano City	6.300	315000	0.0060	04 Months
11	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 07 Ward No. 01, 02 & 04 Larkano City	4.300	215000	0.0050	04 Months
12	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 07 Ward No. 02 Larkano City	5.150	257500	0.0060	04 Months
13	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 08 Ward No. 01 & 02 Larkano City	5.000	250000	0.0050	04 Months
14	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 08 Ward No. 03 Larkano City	4.550	227500	0.0050	04 Months
15	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 09 Ward No. 03 & 04 Larkano City	5.200	260000	0.0060	04 Months
16	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 09 Ward No. 02 Larkano City	7.600	380000	0.0060	04 Months

SPPRA INWARD DIARY

NO : 6723


DATED : 05-03-2018

17	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 10 Ward No. 01 & 04 Larkano City	4.300	215000	0.0050	04 Months
18	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 10 Ward No. 01 Larkano City	5.275	263800	0.0060	04 Months
19	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 11 Ward No. 01 & 03 Larkano City	4.975	248800	0.0050	04 Months
20	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 11 Ward No. 02 & 04 Larkano City	4.200	210000	0.0050	04 Months
21	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 12 Ward No. 02, 03 & 04 Larkano City	5.200	260000	0.0060	04 Months
22	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 12 Ward No. 01 Larkano City	4.700	235000	0.0050	04 Months
23	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 13 Ward No. 02 & 03 Larkano City	4.225	211300	0.0050	04 Months
24	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 13 Ward No. 01 & 3 Larkano City	4.240	212000	0.0050	04 Months
25	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 13 Ward No. 04 Larkano City	4.560	228000	0.0050	04 Months
26	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-14 Ward No. 04 Larkano City	7.550	377500	0.0060	04 Months
27	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee -14 Ward No. 02 & 03 Larkano City	4.850	242500	0.0050	04 Months
28	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee -15 Ward No. 01 & 03 Larkano City	4.730	236500	0.0050	04 Months
29	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee -15 Ward No. 02 & 04 Larkano City	6.320	316000	0.0060	04 Months
30	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee -16 Ward No. 03 & 04 Larkano City	5.300	265000	0.0060	04 Months
31	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee -16 Ward No. 03 & 04 Larkano City	4.325	216300	0.0050	04 Months
32	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 16 Ward No. 01 & 02 & 04 Larkano City	4.325	216300	0.0050	04 Months
33	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 17 Ward No. 01, 02 & 03 Larkano City	6.670	333500	0.0060	04 Months
34	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 17 Ward No. 04 Larkano City	4.450	222500	0.0050	04 Months
35	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 18 Ward No. 03 & 04 Larkano City	4.350	217500	0.0050	04 Months
36	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 18 Ward No. 01 Larkano City	4.350	217500	0.0050	04 Months
37	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 18 Ward No. 02 Larkano City	4.790	239500	0.0050	04 Months
38	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 19 Ward No. 01 Larkano City	5.000	250000	0.0050	04 Months
39	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 19 Ward No. 02 Larkano City	4.550	227500	0.0050	04 Months
40	Construction of C.C Blocks & Paver Blocks in various streets of Union Committee No. 19 Ward No. 03 & 04 Larkano City	4.650	232500	0.0050	04 Months

41	Construction of C.C Blocks & Paver Blocks in various streets of Union Committee No. 19 Ward No. 03 Larkano City	5.190	259500	0.0060	04 Months
42	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-20 Ward No. 03 & 04 Larkano City	5.100	255000	0.0060	04 Months


Interested eligible bidders may obtain further information and bidding documents from office of the undersigned.

3. The interested participants can purchase the tender documents on payment of tender fee for the work with effect from 16-03-2018 up to 30-03-2018 till 1.00 P.M the bidding documents can also be downloaded from SPPRA website.
4. The Bid documents will be received back on 02-04-2018 upto 1.30 P.M & will be opened on same date @ 2.00 P.M in presence of tender opening/ evaluation Committee in Office of the **Mayor Larkana Municipal Corporation Larkana** and bidders or their authorized representatives whosoever be present.
5. If the undersigned remains out of Head Quarter on the next date of issue will commence from 03-04-2018 to 17-04-2018, till 2.30 P.M
The bid documents will be received back on 18-04-2018 upto 1.30 P.M & will be opened on same date @ 2.0 P.M respectively
6. Eligibility criteria for intending participants is as under.
 - i) Documentary evidence of works of same nature (PWD related works) of equivalent cost or above, executed during last three years, along with certificate of satisfactory completion showing date of start and completion from employer.
 - ii) List of works and copy of Letter of Award / Work Order of equivalent cost or above.
 - iii) List of machinery and equipment available with documentary proof of its ownership.
 - iv) Registration with Pakistan Engineering Committee (PEC) in Category C-6 (CE-09) National Tax Number (NTN), Sindh Revenue Board (SRB) and copy of CNIC.
 - v) Undertaking on stamp paper that Firm is not involved in any litigation, Departmental rift, has abandoned or made unnecessary delay in completion of any work in the Government Departments.
 - vi) The application shall accompany along with tender fee as shown against each work for purchase of bidding documents.
 - vii) The 5% earnest money shall be submitted in the shape of Call Deposit issued from scheduled bank at the time of submission of bidding document in favor of undersigned, pay order & demand draft is not considered.
 - viii) Certificate of Bank showing credit worthiness along with last three years audited Bank Statement.
 - ix) Affidavit to the effect that Firm has not been black-listed previously by any Executing Agency.
 - x) Affidavit to the effect that all documents/ particulars/ information furnished are true and correct.
 - xi) Conditional tenders will not be entertained.
7. The undersigned and other competent authority reserves the right to reject any one or all the Bids as per provision of SPPRA Rules.


MAYOR
Larkana Municipal Corporation
Larkana

C.C. for information to:

- Sindh Public Procurement Regulatory Authority, Barrack 8 Secretariat 4A Court Road Karachi Tel: 92-21-99205369 for hoisting on SPPRA's website.
- Deputy Commissioner Larkana.
- Superintending, PHE Circle, Larkana.
- Executive Engineer LMC Larkana.
- Director Local Govt: Larkana
- The Assistant Director LG Larkano.
- Procurement Committee Members (all) .
- Notice Board.



**GOVERNMENT OF SINDH
LOCAL GOVERNMENT DEPARTMENT**

Karachi dated the 03rd January, 2018

NOTIFICATION

NO.SOIV (LG)/1-156/2016/LAR: With the approval of Competent Authority, a Procurement committee consisting on following for under taking Development Schemes in Municipal Corporation Larkana is hereby constituted under Section-7 of SPPRA Rules, 2010:-

- | | | |
|----|---|----------|
| 1. | Executive Engineer LMC, Larkana | Chairman |
| 2. | Assistant Engineer PHED, Sub-Div: Larkana | Member |
| 3. | Accounts Officer. LMC. Larkana | Member |

The Function and responsibilities of Procurement Committee shall be as under Section-8 of SPPRA Rule 2010):-

1. Preparing bidding documents.
2. Carrying out technical as well as financial evaluation of the bids.
3. Preparing evaluation report as provided in Rule 45.
4. Making recommendations for the award of contract to the competent authority, and
5. Perform any other function ancillary and incidental to the above.

-: SECRETARY TO GOVT. OF SINDH:-

NO.SOIV (LG)/1-156/2016/LAR

Karachi, dated the 03rd January, 2016.

A copy is forwarded for information and necessary action to:-

1. The Director, Sindh Public Procurement Regularity Authority, Karachi.
2. The Commissioner, Larkana, Division Larkana.
3. The Director, Local Government, Larkana.
4. The Assistant Director, Local Fund Audit, Larkana.
5. The Mayor, Larkana Municipal Corporation, Larkana.
- ✓ 6. Officers Concerned (Chairman/Members), Procurement Committee.
7. P.S to Secretary. Local Government Department.
8. Office order file.

**(LIAQUAT ALI MANGI)
SECTION OFFICER-IV**



**GOVERNMENT OF SINDH
LOCAL GOVERNMENT DEPARTMENT**

Karachi dated the 03rd January, 2018

NOTIFICATION

NO.SOIV (LG)/1-156/2016/LAR: With the approval of Competent Authority, a Complaint Redressal Committee is hereby constituted under Rule-31(1) (2) of SPPRA, Rules-2010. of Municipal Corporation Larkana, during the year 2017-18:-

- | | |
|--|----------|
| 1. Municipal Commissioner, LMC, Larkana | Chairman |
| 2. Executive Engineer PHED, Sub-Div: Larkana | Member |
| 3. Budget Superintendent, LMC, Larkana | Member |

The Function and responsibilities of Complaint Redressal Committee, shall be under Rule-31(1)(2) of SPPRA Rule-2010:-

-: SECRETARY TO GOVT. OF SINDH:-

NO.SOIV (LG)/1-156/2016/LAR

Karachi, dated the 03rd January, 2018

A copy is forwarded for information and necessary action to:-

1. The Director, Sindh Public Procurement Regularity Authority, Karachi.
2. The Commissioner, Larkana, Division Larkana.
3. The Director, Local Government, Larkana.
4. The Assistant Director, Local Fund Audit, Larkana.
5. The Mayor, LMC, Larkana.
6. Officers Concerned (Chairman/Members), Procurement Committee.
7. P.S to Secretary, Local Government Department, Govt. of Sindh, Karachi.
8. Office order file.

**(LIAQUAT ALI MANGI)
SECTION OFFICER-IV**

OFFICE OF THE MAYOR, LARKANO MUNICIPAL CORPORATION LARKANA
ANNUAL PROCUREMENT PLAN
FINANCIAL YEAR 2017-2018


S.No	Name of Work	Quantity (Where Applicable)	Estimated Unit Cost (Where applicable) Million	Funds Allocated (In Million)	Source of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
1	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 01 Ward No. 02 & 04 Larkano City	District Larkana	-	4.240	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.240	-	-	-	All Procurements will be made as per SPPRA Rule-2010 (Amended 2013)
2	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 01 Ward No. 01 & 03 Larkano City	District Larkana	-	4.650	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.650	-	-	-do....
3	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 02 Ward No. 01 & 02 Larkano City	District Larkana	-	5.000	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.000	-	-	-do....
4	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 02 Ward No. 03 & 04 Larkano City	District Larkana	-	5.600	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.600	-	-	-do....
5	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 03 Ward No. 04 Larkano City	District Larkana	-	5.312	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.312	-	-	-do....
6	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 03 Ward No. 04 Larkano City	District Larkana	-	4.471	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.471	-	-	-do....
7	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 04 Ward No. 01 & 02 Larkano City	District Larkana	-	7.600	Saving of LMC Funds	Single Stage (One Envelope Procedure)	7.600	-	-	-do....
8	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 04 Ward No. 03 & 04 Larkano City	District Larkana	-	5.250	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.250	-	-	-do....
9	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 05 Ward No. 01 & 03 Larkano City	District Larkana	-	5.300	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.300	-	-	-do....
10	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 05 Ward No. 02 & 04 Larkano City	District Larkana	-	6.300	Saving of LMC Funds	Single Stage (One Envelope Procedure)	6.300	-	-	-do....

S.No	Name of Work	Quantity (Where Applicable)	Estimated Unit Cost (Where applicable) Million	Funds Allocated (In Million)	Source of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
11	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 07 Ward No. 01, 02 & 04 Larkano City	District Larkana	-	4.300	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.300	-	-	-do....
12	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 07 Ward No. 02 Larkano City	District Larkana	-	5.150	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.150	-	-	-do....
13	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 08 Ward No. 01 & 02 Larkano City	District Larkana	-	5.000	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.000	-	-	-do....
14	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 08 Ward No. 03 Larkano City	District Larkana	-	4.550	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.550	-	-	-do....
15	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 09 Ward No. 03 & 04 Larkano City	District Larkana	-	5.200	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.200	-	-	-do....
16	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 09 Ward No. 02 Larkano City	District Larkana	-	7.600	Saving of LMC Funds	Single Stage (One Envelope Procedure)	7.600	-	-	-do....
17	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 10 Ward No. 01 & 04 Larkano City	District Larkana	-	4.300	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.300	-	-	-do....
18	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 10 Ward No. 01 Larkano City	District Larkana	-	5.275	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.275	-	-	-do....
19	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 11 Ward No. 01 & 03 Larkano City	District Larkana	-	4.975	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.975	-	-	-do....
20	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 11 Ward No. 02 & 04 Larkano City	District Larkana	-	4.200	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.200	-	-	-do....
21	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 12 Ward No. 02, 03 & 04 Larkano City	District Larkana	-	5.200	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.200	-	-	-do....
22	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 12 Ward No. 01 Larkano City	District Larkana	-	4.700	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.700	-	-	-do....


S.No	Name of Work	Quantity (Where Applicable)	Estimated Unit Cost (Where applicable) Million	Funds Allocated (In Million)	Source of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
23	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 13 Ward No. 02 & 03 Larkano City	District Larkana	-	4.225	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.225	-	-	-do....
24	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 13 Ward No. 01 & 3 Larkano City	District Larkana	-	4.240	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.240	-	-	-do....
25	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 13 Ward No. 04 Larkano City	District Larkana	-	4.560	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.560	-	-	-do....
26	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-14 Ward No. 04 Larkano City	District Larkana	-	7.550	Saving of LMC Funds	Single Stage (One Envelope Procedure)	7.550	-	-	-do....
27	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-14 Ward No. 02 & 03 Larkano City	District Larkana	-	4.850	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.850	-	-	-do....
28	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-15 Ward No. 01 & 03 Larkano City	District Larkana	-	4.730	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.730	-	-	-do....
29	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-15 Ward No. 02 & 04 Larkano City	District Larkana	-	6.320	Saving of LMC Funds	Single Stage (One Envelope Procedure)	6.320	-	-	-do....
30	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-16 Ward No. 03 & 04 Larkano City	District Larkana	-	5.300	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.300	-	-	-do....
31	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-16 Ward No. 03 & 04 Larkano City	District Larkana	-	4.325	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.325	-	-	-do....
32	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 16 Ward No. 01 & 02 & 04 Larkano City	District Larkana	-	4.325	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.325	-	-	-do....
33	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 17 Ward No. 01, 02 & 03 Larkano City	District Larkana	-	6.670	Saving of LMC Funds	Single Stage (One Envelope Procedure)	6.670	-	-	-do....
34	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 17 Ward No. 04 Larkano City	District Larkana	-	4.450	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.450	-	-	-do....

S.No	Name of Work	Quantity (Where Applicable)	Estimated Unit Cost (Where applicable) Million	Funds Allocated (In Million)	Source of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
35	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 18 Ward No. 03 & 04 Larkano City	District Larkana	-	4.350	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.350	-	-	-do....
36	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 18 Ward No. 01 Larkano City	District Larkana	-	4.350	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.350	-	-	-do....
37	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 18 Ward No. 02 Larkano City	District Larkana	-	4.790	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.790	-	-	-do....
38	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 19 Ward No. 01 Larkano City	District Larkana	-	5.000	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.000	-	-	-do....
39	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Committee No. 19 Ward No. 02 Larkano City	District Larkana	-	4.550	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.550	-	-	-do....
40	Construction of C.C Blocks & Paver Blocks in various streets of Union Committee No. 19 Ward No. 03 & 04 Larkano City	District Larkana	-	4.650	Saving of LMC Funds	Single Stage (One Envelope Procedure)	4.650	-	-	-do....
41	Construction of C.C Blocks & Paver Blocks in various streets of Union Committee No. 19 Ward No. 03 Larkano City	District Larkana	-	5.190	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.190	-	-	-do....
42	Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of UC-20 Ward No. 03 & 04 Larkano City	District Larkana	-	5.100	Saving of LMC Funds	Single Stage (One Envelope Procedure)	5.100	-	-	-do....


 EXECUTIVE ENGINEER
 LARKANA MUNICIPAL CORPORATION
 LARKANA


 ACCOUNTS OFFICER
 LARKANA MUNICIPAL CORPORATION
 LARKANA


 MUNICIPAL COMMISSIONER
 LARKANA MUNICIPAL CORPORATION
 LARKANA


 MAYOR
 LARKANA MUNICIPAL CORPORATION
 LARKANA

BILL OF QUANTITY

①

(A) Construction of CC Drains & C.C Blocks in various streets of
Union Council No. 01 Ward No. 02 & 04 of Larkano City

S.#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2983.50 cft		@Rs 3176.25	P%0Cft	Rs 9476
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	769.50 Cft		@Rs 11288.75	P%0Cft	Rs 86867
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 900.0 Rft		@Rs 94.00	P-Rft	Rs 84600
	Type B 300.0 Rft		@Rs 174.00	P-Rft	Rs 52200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2137.50 cft		@Rs 11948.36	P%0Cft	Rs 255396
5		Cement plaster (1:4) up to 20'height ½"thick (G.S.I-11(b) / P/52)			
	3150.00 Sft		@Rs 2283.93	P%0Sft	Rs 71944
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (G.S.I-6(a) P/17)			
	61.26 Cft		@Rs 337.00	P-Cft	Rs 20645
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	2.00 Cwt		@Rs 5001.70	P-Cwt	Rs 10003
8		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)			
	174.36 Cft		@Rs. 14429.25	P%0Cft	Rs 25159
G.Total:					Rs 616291

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 620291

PART-II CC BLOCKS

- 1 Barrow pit excavation undressed lead upto 100ft ordinary soil
(G.S.I. No. 3 (a) p/ 1)
27600.00 Cft @Rs 2117.50 P%0Cft Rs 58443
- 2 Laying arth in 6"thick layers levelling and dressing etc completed
(G.S.I.No. 13 a p/ 3)
27600.00 Cft @Rs 263.00 P%0Cft Rs 7259
- 3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)
27600.00 Cft @Rs 5039.00 P%0Cft Rs 139076
- 4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8)
(G.SI. No. 4(b) p/ 15)
9108 Cft @Rs 9416.28 P%cft Rs 857635
- 5 Cement concrete plain i/c placing compacting, finishing
and curing etc complete i/c sreening & washing of stone aggregate
without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)
6900 Cft @Rs 14429.25 P%cft Rs 995618
- 6 Erection and removal of centering for R.C.C or plain C.C works
of deodar wood (2nd class) (b) for partal wood (vertical).
(G.S.I.No. 19 p/ 18)
575.00 sft @Rs 3127.41 P%sft Rs 17983

Total: Rs 2076014

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	616291	4000	Rs 620291
2	Part-II C.C Blocks	2076014	0	Rs 2076014
	G.Total:	2692305	4000	Rs 2696305

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana

EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana

MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains & C.C Blocks in various streets of Union Council No. 01 Ward No. 01 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	4696.50 cft		@Rs 3176.25	P%0Cft	Rs 14917
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	1115.50 Cft		@Rs 11288.75	P%0Cft	Rs 125926
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 1100.0 Rft		@Rs 94.00	P-Rft	Rs 103400
	Type B 600.0 Rft		@Rs 174.00	P-Rft	Rs 104400
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	3225.00 cft		@Rs 11948.36	P%0Cft	Rs 385335
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	4550.00 Sft		@Rs 2283.93	P%0Sft	Rs 103919
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	69.39 Cft		@Rs 337.00	P-Cft	Rs 23386
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005
8		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)			
	155.46 Cft		@Rs. 14429.25	P%0Cft	Rs 22432
G.Total:					Rs 898719

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 902719

PART-II CC BLOCKS

- 1 Barrow pit excavation undressed lead upto 100ft ordinary soil
(G.S.I. No. 3 (a) p/ 1)
27600.00 Cft @Rs 2117.50 P%0Cft Rs 58443
- 2 Laying arth in 6"thick layers levelling and dressing etc completed
(G.S.I.No. 13 a p/ 3)
27600.00 Cft @Rs 263.00 P%0Cft Rs 7259
- 3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)
27600.00 Cft @Rs 5039.00 P%0Cft Rs 139076
- 4 Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8)
(G.SI. No. 4(b) p/ 15)
9108 Cft @Rs 9416.28 P%cft Rs 857635
- 5 Cement concrete plain i/c placing compacting, finishing
and curing etc complete i/c sreening & washing of stone aggregate
without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)
6900 Cft @Rs 14429.25 P%cft Rs 995618
- 6 Erection and removal of centering for R.C.C or plain C.C works
of deodar wood (2nd class) (b) for partal wood (vertical).
(G.S.I.No. 19 p/ 18)
575.00 sft @Rs 3127.41 P%sfst Rs 17983

Total: Rs 2076014

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	898719	4000	Rs 902719
2	Part-II C.C Blocks	2076014	0	Rs 2076014
	G.Total:	2974733	4000	Rs 2978733

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana

EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana

MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 02 Ward No. 01 & 02 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3607.50 cft		@Rs 3176.25	P%0Cft	Rs 11458
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	752.50 Cft		@Rs 11288.75	P%0Cft	Rs 84948
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
	Type A 500.0 Rft		@Rs 94.00	P-Rft	Rs 47000
	Type B 600.0 Rft		@Rs 174.00	P-Rft	Rs 104400
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2325.00 cft		@Rs 11948.36	P%0Cft	Rs 277799
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3050.00 Sft		@Rs 2283.93	P%0Sft	Rs 69660
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6	70.66 Cft		@Rs 337.00	P-Cft	Rs 23811
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	126.89	Cft	@Rs. 14429.25	P%Cft	Rs 18309
				G.Total:		Rs 652391
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1	No	@Rs 4000.00	P.Each	Rs 4000
				G.Total:		Rs 656391

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	4000.00	Cft	@Rs 2117.50	P%0Cft	Rs 8470
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	4000.00	Cft	@Rs 263.00	P%0Cft	Rs 1052
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	4000.00	Cft	@Rs 5039.00	P%0Cft	Rs 20156
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	2640	Cft	@Rs 9416.28	P%cft	Rs 248590
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2000	Cft	@Rs 14429.25	P%cft	Rs 288585
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	200.00	sft	@Rs 3127.41	P%sft	Rs 6255
				Total:		Rs 573108

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2750.00	Cft	@Rs 11288.75	P%Cft	Rs 310441
2	Supplying & laying hard Muram powderly find Muram (CSI NO: P-)	2750.00	Cft	@Rs 1800.00	P%Cft	Rs 49500
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	11000	sft	@Rs 199.77	P.sft	Rs 2197470
				Total:		Rs 2557411

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	652391	4000	Rs 656391
2	Part-II C.C Blocks	573108	0	Rs 573108
3	Part-III Paver Bricks	2557411	0	Rs 2557411
	G.Total:	3782909	4000	Rs 3786909

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 02 Ward No. 03 & 04 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3883.50 cft		@Rs 3176.25	P%0Cft	Rs 12335
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	919.50 Cft		@Rs 11288.75	P%0Cft	Rs 103800
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
	Type A 900.0 Rft		@Rs 94.00	P-Rft	Rs 84600
	Type B 500.0 Rft		@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2662.50 cft		@Rs 11948.36	P%0Cft	Rs 318125
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3750.00 Sft		@Rs 2283.93	P%0Sft	Rs 85647
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6					
	85.66 Cft		@Rs 337.00	P-Cft	Rs 28866
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7					
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	126.89	Cft	@Rs. 14429.25	P%Cft	Rs 18309
						<hr/>
				G.Total:		Rs 753688
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1	No	@Rs 4000.00	P.Each	Rs 4000
						<hr/>
				G.Total:		Rs 757688

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	6750.00	Cft	@Rs 2117.50	P%0Cft	Rs 14293
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	6750.00	Cft	@Rs 263.00	P%0Cft	Rs 1775
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	6750.00	Cft	@Rs 5039.00	P%0Cft	Rs 34013
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	2970	Cft	@Rs 9416.28	P%cft	Rs 279664
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2250	Cft	@Rs 14429.25	P%cft	Rs 324658
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	225.00	sft	@Rs 3127.41	P%0sft	Rs 7037
					Total:	Rs 661440

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	3025.00	Cft	@Rs 11288.75	P%Cft	Rs 341485
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	3025.00	Cft	@Rs 1800.00	P%Cft	Rs 54450
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	12100	sft	@Rs 199.77	P.sft	Rs 2417217
					Total:	Rs 2813152

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	753688	4000	Rs 757688
2	Part-II C.C Blocks	661440	0	Rs 661440
3	Part-III Paver Bricks	2813152	0	Rs 2813152
	G.Total:	4228279	4000	Rs 4232279

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

5

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 03 Ward No. 04 of Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3883.50 cft		@Rs 3176.25	P%0Cft	Rs 12335
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	919.50 Cft		@Rs 11288.75	P%Cft	Rs 103800
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying					
3		floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 900.0 Rft		@Rs 94.00	P-Rft	Rs 84600
	Type B 500.0 Rft		@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2662.50 cft		@Rs 11948.36	P%Cft	Rs 318125
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3750.00 Sft		@Rs 2283.93	P%Sft	Rs 85647
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface					
6		i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	93.79 Cft		@Rs 337.00	P-Cft	Rs 31606
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c					
7		cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	4.00 Cwt		@Rs 5001.70	P-Cwt	Rs 20007

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	190.07 Cft	@Rs. 14429.25	P% Cft	Rs 27425
			G.Total:		Rs 770546
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 774546

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	14000.00 Cft	@Rs 2117.50	P%0Cft	Rs 29645
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	14000.00 Cft	@Rs 263.00	P%0Cft	Rs 3682
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	14000.00 Cft	@Rs 5039.00	P%0Cft	Rs 70546
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	4620 Cft	@Rs 9416.28	P%cft	Rs 435032
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3500 Cft	@Rs 14429.25	P%cft	Rs 505024
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	350.00 sft	@Rs 3127.41	P%sft	Rs 10946
			Total:		Rs 1054875

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2200.00 Cft	@Rs 11288.75	P% Cft	Rs 248353
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00 Cft	@Rs 1800.00	P% Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800 sft	@Rs 199.77	P.sft	Rs 1757976
			Total:		Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	770546	4000	Rs 774546
2	Part-II C.C Blocks	1054875	0	Rs 1054875
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3871349	4000	Rs 3875349

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 03 Ward No. 04 Larkano City

6

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3339.00 cft		@Rs 3176.25	P%0Cft	Rs 10605
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	738.00 Cft		@Rs 11288.75	P%0Cft	Rs 83311
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A 600.0 Rft	@Rs 94.00	P-Rft	Rs 56400
		Type B 500.0 Rft	@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2212.50 cft		@Rs 11948.36	P%0Cft	Rs 264357
5		Cement plaster (1:4) up to 20'height ½"thick (G.S.I-11(b) / P/52)			
	3000.00 Sft		@Rs 2283.93	P%0Sft	Rs 68518
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (G.S.I-6(a) P/17)					
6	85.66 Cft		@Rs 337.00	P-Cft	Rs 28866
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	174.36 Cft	@Rs. 14429.25	P%Cft	Rs 25159
			G.Total:		Rs 639222
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 643222

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	18000.00 Cft	@Rs 2117.50	P%0Cft	Rs 38115
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	18000.00 Cft	@Rs 263.00	P%0Cft	Rs 4734
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	18000.00 Cft	@Rs 5039.00	P%0Cft	Rs 90702
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3960 Cft	@Rs 9416.28	P%cft	Rs 372885
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3000 Cft	@Rs 14429.25	P%cft	Rs 432878
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	300.00 sft	@Rs 3127.41	P%sft	Rs 9382
			Total:		Rs 948695

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	1800.00 Cft	@Rs 11288.75	P%Cft	Rs 203198
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	1800.00 Cft	@Rs 1800.00	P%Cft	Rs 32400
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	7200 sft	@Rs 199.77	P.sft	Rs 1438344
			Total:		Rs 1673942

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	639222	4000	Rs 643222
2	Part-II C.C Blocks	948695	0	Rs 948695
3	Part-III Paver Bricks	1673942	0	Rs 1673942
	G.Total:	3261859	4000	Rs 3265859

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 04 Ward No. 01 & 02 of Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	1263.00 cft		@Rs 3176.25	P%0Cft	Rs 4012
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	271.00 Cft		@Rs 11288.75	P%Cft	Rs 30593
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
	Type A 200.0 Rft		@Rs 94.00	P-Rft	Rs 18800
	Type B 200.0 Rft		@Rs 174.00	P-Rft	Rs 34800
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	825.00 cft		@Rs 11948.36	P%Cft	Rs 98574
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	1100.00 Sft		@Rs 2283.93	P%Sft	Rs 25123
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle.(a) R.C work in roof slab beams columns.rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6	93.79 Cft		@Rs 337.00	P-Cft	Rs 31606
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7	4.00 Cwt		@Rs 5001.70	P-Cwt	Rs 20007

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	114.11	Cft	@Rs. 14429.25	P%Cft	<u>Rs 16465</u>
				G.Total:		Rs 279980
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1	No	@Rs 4000.00	P.Each	<u>Rs 4000</u>
				G.Total:		Rs 283980

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	7200.00	Cft	@Rs 2117.50	P%0Cft	Rs 15246
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	7200.00	Cft	@Rs 263.00	P%0Cft	Rs 1894
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	7200.00	Cft	@Rs 5039.00	P%0Cft	Rs 36281
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3168	Cft	@Rs 9416.28	P%cft	Rs 298308
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2400	Cft	@Rs 14429.25	P%cft	Rs 346302
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	200.00	sft	@Rs 3127.41	P%sft	<u>Rs 6255</u>
				Total:		Rs 704285

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	4500.00	Cft	@Rs 11288.75	P%Cft	Rs 507994
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	5500.00	Cft	@Rs 1800.00	P%Cft	Rs 99000
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	22000	sft	@Rs 199.77	P.sft	<u>Rs 4394940</u>
				Total:		Rs 5001934

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	279980	4000	Rs 283980
2	Part-II C.C Blocks	704285	0	Rs 704285
3	Part-III Paver Bricks	5001934	0	Rs 5001934
	G.Total:	5986198	4000	Rs 5990198

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


✓
EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains & C.C Blocks in various streets of Union Council No. 04 Ward No. 03 & 04 of Larkano City

(A)

#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1	2983.50 cft	Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)	@Rs 3176.25	P%0Cft	Rs 9476
2	769.50 Cft	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)	@Rs 11288.75	P%Cft	Rs 86867
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 900.0 Rft		@Rs 94.00	P-Rft	Rs 84600
	Type B 300.0 Rft		@Rs 174.00	P-Rft	Rs 52200
4	2137.50 cft	Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)	@Rs 11948.36	P%Cft	Rs 255396
5	3150.00 Sft	Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)	@Rs 2283.93	P%Sft	Rs 71944
6	69.39 Cft	R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)	@Rs 337.00	P-Cft	Rs 23386
7	3.00 Cwt	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)	@Rs 5001.70	P-Cwt	Rs 15005
8	186.96 Cft	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	@Rs. 14429.25	P%Cft	Rs 26977
G.Total:					Rs 625851

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 629851

PART-II CC BLOCKS

- 1 Barrow pit excavation undressed lead upto 100ft ordinary soil
(G.S.I. No. 3 (a) p/ 1)
33120.00 Cft @Rs 2117.50 P%0Cft Rs 70132
- 2 Laying arth in 6"thick layers levelling and dressing etc completed
(G.S.I.No. 13 a p/ 3)
33120.00 Cft @Rs 263.00 P%0Cft Rs 8711
- 3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)
33120.00 Cft @Rs 5039.00 P%0Cft Rs 166892
- 4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8)
(G.SI. No. 4(b) p/ 15)
11880 Cft @Rs 9416.28 P%cft Rs 1118654
- 5 Cement concrete plain i/c placing compacting, finishing
and curing etc complete i/c sreening & washing of stone aggregate
without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)
9000 Cft @Rs 14429.25 P%cft Rs 1298633
- 6 Erection and removal of centering for R.C.C or plain C.C works
of deodar wood (2nd class) (b) for partal wood (vertical).
(G.S.I.No. 19 p/ 18)
750.00 sft @Rs 3127.41 P%sf Rs 23456

Total: Rs 2686476

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	625851	4000	Rs 629851
2	Part-II C.C Blocks	2686476	0	Rs 2686476
	G.Total:	3312327	4000	Rs 3316327

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana

✓ EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkano

MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 05 Ward No. 01 & 03 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3883.50 cft		@Rs 3176.25	P%0Cft	Rs 12335
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	919.50 Cft		@Rs 11288.75	P%Cft	Rs 103800
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying					
3		floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 900.0 Rft		@Rs 94.00	P-Rft	Rs 84600
	Type B 500.0 Rft		@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2662.50 cft		@Rs 11948.36	P%Cft	Rs 318125
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3750.00 Sft		@Rs 2283.93	P%Sft	Rs 85647
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface					
6		i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	85.66 Cft		@Rs 337.00	P-Cft	Rs 28866
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c					
7		cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	174.36 Cft	@Rs. 14429.25	P%Cft	Rs 25159
			G.Total:		Rs 760537
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 764537

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	14000.00 Cft	@Rs 2117.50	P%0Cft	Rs 29645
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	14000.00 Cft	@Rs 263.00	P%0Cft	Rs 3682
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	14000.00 Cft	@Rs 5039.00	P%0Cft	Rs 70546
4	Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	4620 Cft	@Rs 9416.28	P%cft	Rs 435032
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3500 Cft	@Rs 14429.25	P%cft	Rs 505024
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	350.00 sft	@Rs 3127.41	P%0sft	Rs 10946
			Total:		Rs 1054875

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2200.00 Cft	@Rs 11288.75	P%0Cft	Rs 248353
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00 Cft	@Rs 1800.00	P%0Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800 sft	@Rs 199.77	P.sft	Rs 1757976
			Total:		Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	760537	4000	Rs 764537
2	Part-II C.C Blocks	1054875	0	Rs 1054875
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3861341	4000	Rs 3865341

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 05 Ward No. 02 & 04 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I		C.C Drains			
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	5415.00 cft		@Rs 3176.25	P%0Cft	Rs 17199
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	1205.00 Cft		@Rs 11288.75	P%Cft	Rs 136029
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3					
	Type A 1000.0 Rft		@Rs 94.00	P-Rft	Rs 94000
	Type B 800.0 Rft		@Rs 174.00	P-Rft	Rs 139200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	3600.00 cft		@Rs 11948.36	P%Cft	Rs 430141
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	4900.00 Sft		@Rs 2283.93	P%Sft	Rs 111913
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6					
	131.92 Cft		@Rs 337.00	P-Cft	Rs 44457
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7					
	5.00 Cwt		@Rs 5001.70	P-Cwt	Rs 25009

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	174.36 Cft	@Rs. 14429.25	P%Cft	<u>Rs 25159</u>
			G.Total:		Rs 1023106
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	<u>Rs 4000</u>
			G.Total:		Rs 1027106

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	14000.00 Cft	@Rs 2117.50	P%0Cft	Rs 29645
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	14000.00 Cft	@Rs 263.00	P%0Cft	Rs 3682
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	14000.00 Cft	@Rs 5039.00	P%0Cft	Rs 70546
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	4620 Cft	@Rs 9416.28	P%cft	Rs 435032
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3500 Cft	@Rs 14429.25	P%cft	Rs 505024
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	350.00 sft	@Rs 3127.41	P%0sft	<u>Rs 10946</u>
				Total:	Rs 1054875

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2750.00 Cft	@Rs 11288.75	P%Cft	Rs 310441
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2750.00 Cft	@Rs 1800.00	P%Cft	Rs 49500
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	11000 sft	@Rs 199.77	P.sft	<u>Rs 2197470</u>
			Total:		Rs 2557411

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	1023106	4000	Rs 1027106
2	Part-II C.C Blocks	1054875	0	Rs 1054875
3	Part-III Paver Bricks	2557411	0	Rs 2557411
	G.Total:	4635392	4000	Rs 4639392

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains & C.C Blocks in various streets of
Union Council No. 07 Ward No. 01, 02 & 04 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3702.00 cft		@Rs 3176.25	P%0Cft	Rs 11758
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	859.00 Cft		@Rs 11288.75	P%Cft	Rs 96970
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 800.0 Rft		@Rs 94.00	P-Rft	Rs 75200
	Type B 500.0 Rft		@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2512.50 cft		@Rs 11948.36	P%Cft	Rs 300203
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3500.00 Sft		@Rs 2283.93	P%Sft	Rs 79938
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	61.26 Cft		@Rs 337.00	P-Cft	Rs 20645
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	2.00 Cwt		@Rs 5001.70	P-Cwt	Rs 10003
8		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)			
	155.46 Cft		@Rs. 14429.25	P%Cft	Rs 22432
G.Total:					Rs 704149

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 708149

PART-II CC BLOCKS

- 1 Barrow pit excavation undressed lead upto 100ft ordinary soil
(G.S.I. No. 3 (a) p/ 1)
27000.00 Cft @Rs 2117.50 P%0Cft Rs 57173
 - 2 Laying arth in 6"thick layers levelling and dressing etc completed
(G.S.I.No. 13 a p/ 3)
27000.00 Cft @Rs 263.00 P%0Cft Rs 7101
 - 3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)
27000.00 Cft @Rs 5039.00 P%0Cft Rs 136053
 - 4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8)
(G.SI. No. 4(b) p/ 15)
8910 Cft @Rs 9416.28 P%cft Rs 838991
 - 5 Cement concrete plain i/c placing compacting, finishing
and curing etc complete i/c sreening & washing of stone aggregate
without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)
6750 Cft @Rs 14429.25 P%cft Rs 973974
 - 6 Erection and removal of centering for R.C.C or plain C.C works
of deodar wood (2nd class) (b) for partal wood (vertical).
(G.S.I.No. 19 p/ 18)
562.50 sft @Rs 3127.41 P%0sft Rs 17592
- Total: Rs 2030883**

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	704149	4000	Rs 708149
2	Part-II C.C Blocks	2030883	0	Rs 2030883
	G.Total:	2735033	4000	Rs 2739033

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana

EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana
MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

12

(A)

Construction of CC Drains & C.C Blocks in various streets of
Union Council No. 07 Ward No. 02 of Larkano City

S.#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	4246.50 cft		@Rs 3176.25	P%0Cft	Rs 13488
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	1040.50 Cft		@Rs 11288.75	P%Cft	Rs 117459
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 1100.0 Rft		@Rs 94.00	P-Rft	Rs 103400
	Type B 500.0 Rft		@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2962.50 cft		@Rs 11948.36	P%Cft	Rs 353970
5		Cement plaster (1:4) up to 20' height 1/2" thick (G.S.I-11(b) / P/52)			
	4250.00 Sft		@Rs 2283.93	P%Sft	Rs 97067
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	85.66 Cft		@Rs 337.00	P-Cft	Rs 28866
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005
8		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)			
	177.82 Cft		@Rs. 14429.25	P%Cft	Rs 25658
G.Total:					Rs 841914

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 845914

PART-II CC BLOCKS

1 Barrow pit excavation undressed lead upto 100ft ordinary soil

(G.S.I. No. 3 (a) p/ 1)

32400.00 Cft

@Rs 2117.50 P%0Cft Rs 68607

2 Laying arth in 6"thick layers levelling and dressing etc completed

(G.S.I.No. 13 a p/ 3)

32400.00 Cft

@Rs 263.00 P%0Cft Rs 8521

3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

32400.00 Cft

@Rs 5039.00 P%0Cft Rs 163264

4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8)

(G.SI. No. 4(b) p/ 15)

10692 Cft

@Rs 9416.28 P%cft Rs 1006789

5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

8100 Cft

@Rs 14429.25 P%cft Rs 1168769

6 Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical).

(G.S.I.No. 19 p/ 18)

675.00 sft

@Rs 3127.41 P%sf Rs 21110

Total: Rs 2437060

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	841914	4000	Rs 845914
2	Part-II C.C Blocks	2437060	0	Rs 2437060
	G.Total:	3278974	4000	Rs 3282974

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the

basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana

EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkano

MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 08 Ward No. 01 & 02 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I		C.C Drains			
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3883.50 cft		@Rs 3176.25	P%0Cft	Rs 12335
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	919.50 Cft		@Rs 11288.75	P%0Cft	Rs 103800
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	900.0	Rft	
			@Rs 94.00	P-Rft	Rs 84600
		Type B	500.0	Rft	
			@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2662.50 cft		@Rs 11948.36	P%0Cft	Rs 318125
5		Cement plaster (1:4) up to 20"height 1/2"thick (G.S.I-11(b) / P/52)			
	3750.00 Sft		@Rs 2283.93	P%0Sft	Rs 85647
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6			100.66	Cft	
			@Rs 337.00	P-Cft	Rs 33921
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7			4.00	Cwt	
			@Rs 5001.70	P-Cwt	Rs 20007

- 8 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)

193.26 Cft

@Rs. 14429.25 P% Cft Rs 27886

G.Total: Rs 773321

- 9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 777321

Part- II CC BLOCKS

- 1 Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)

12000.00 Cft

@Rs 2117.50 P%0Cft Rs 25410

- 2 Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)

12000.00 Cft

@Rs 263.00 P%0Cft Rs 3156

- 3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

12000.00 Cft

@Rs 5039.00 P%0Cft Rs 60468

- 4 Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)

3960 Cft

@Rs 9416.28 P%cft Rs 372885

- 5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

3000 Cft

@Rs 14429.25 P%cft Rs 432878

- 6 Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)

300.00 sft

@Rs 3127.41 P%sft Rs 9382

Total: Rs 904178

Part-III PAVER TILE

- 1 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)

1800.00 Cft

@Rs 11288.75 P%Cft Rs 203198

- 2 Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)

2200.00 Cft

@Rs 1800.00 P%Cft Rs 39600

- 3 Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)

8800 sft

@Rs 199.77 P.sft Rs 1757976

Total: Rs 2000774

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	773321	4000	Rs 777321
2	Part-II C.C Blocks	904178	0	Rs 904178
3	Part-III Paver Bricks	2000774	0	Rs 2000774
	G.Total:	3678273	4000	Rs 3682273


Amount Total (a)


----- % above /below on the rates CSR


Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 08 Ward No. 03 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I		C.C Drains			
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	4602.00 cft		@Rs 3176.25	P%0Cft	Rs 14617
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	1009.00 Cft		@Rs 11288.75	P%Cft	Rs 113903
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 800.0 Rft		@Rs 94.00	P-Rft	Rs 75200
	Type B 700.0 Rft		@Rs 174.00	P-Rft	Rs 121800
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	3037.50 cft		@Rs 11948.36	P%Cft	Rs 362931
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	4100.00 Sft		@Rs 2283.93	P%Sft	Rs 93641
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	85.66 Cft		@Rs 337.00	P-Cft	Rs 28866
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	117.30	Cft	@Rs. 14429.25	P%Cft	Rs 16926
				G.Total:		Rs 842891
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1	No	@Rs 4000.00	P.Each	Rs 4000
				G.Total:		Rs 846891

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	12000.00	Cft	@Rs 2117.50	P%0Cft	Rs 25410
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	12000.00	Cft	@Rs 263.00	P%0Cft	Rs 3156
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	12000.00	Cft	@Rs 5039.00	P%0Cft	Rs 60468
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3960	Cft	@Rs 9416.28	P%cft	Rs 372885
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3000	Cft	@Rs 14429.25	P%cft	Rs 432878
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	300.00	sft	@Rs 3127.41	P% _s sft	Rs 9382
				Total:		Rs 904178

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	1650.00	Cft	@Rs 11288.75	P%Cft	Rs 186264
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	1650.00	Cft	@Rs 1800.00	P%Cft	Rs 29700
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	6600	sft	@Rs 199.77	P.sft	Rs 1318482
				Total:		Rs 1534446

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	842891	4000	Rs 846891
2	Part-II C.C Blocks	904178	0	Rs 904178
3	Part-III Paver Bricks	1534446	0	Rs 1534446
	G.Total:	3281515	4000	Rs 3285515


Amount Total (a)

----- % above /below on the rates CSR


Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains & C.C Blocks in various streets of Union Council No. 09 Ward No. 03 & 04 of Larkano City

(A)

#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2983.50 cft		@Rs 3176.25	P%0Cft	Rs 9476
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	769.50 Cft		@Rs 11288.75	P%0Cft	Rs 86867
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 900.0 Rft		@Rs 94.00	P-Rft	Rs 84600
	Type B 300.0 Rft		@Rs 174.00	P-Rft	Rs 52200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2137.50 cft		@Rs 11948.36	P%0Cft	Rs 255396
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3150.00 Sft		@Rs 2283.93	P%0Sft	Rs 71944
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	69.39 Cft		@Rs 337.00	P-Cft	Rs 23386
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005
8		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)			
	174.36 Cft		@Rs. 14429.25	P%0Cft	Rs 25159
G.Total:					Rs 624033

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 628033

PART-II CC BLOCKS

1 Barrow pit excavation undressed lead upto 100ft ordinary soil

(G.S.I. No. 3 (a) p/ 1)

27000.00 Cft

@Rs 2117.50 P%0Cft Rs 57173

2 Laying arth in 6"thick layers levelling and dressing etc completed

(G.S.I.No. 13 a p/ 3)

27000.00 Cft

@Rs 263.00 P%0Cft Rs 7101

3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

27000.00 Cft

@Rs 5039.00 P%0Cft Rs 136053

4 Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8)

(G.SI. No. 4(b) p/ 15)

11880 Cft

@Rs 9416.28 P%cft Rs 1118654

5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

9000 Cft

@Rs 14429.25 P%cft Rs 1298633

6 Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partial wood (vertical).

(G.S.I.No. 19 p/ 18)

750.00 sft

@Rs 3127.41 P%sft Rs 23456

Total: Rs 2641069

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	624033	4000	Rs 628033
2	Part-II C.C Blocks	2641069	0	Rs 2641069
	G.Total:	3265101	4000	Rs 3269101

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the


basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 09 Ward No. 02 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
-----	-----	------	------	------	--------

Part-I C.C Drains

1 Excavation in foundation of building bridges and other structures
i/c dag belling dressing refilling around the structures with excavated
earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)
1263.00 cft @Rs 3176.25 P%0Cft Rs 4012

2 Cement concrete plain i/c placing compacting finishing
and curing complete i/c screening and washing of stone
aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17
271.00 Cft @Rs 11288.75 P%Cft Rs 30593

Construction of standard open type drains cunette block of C.C 1:2:4 in
situ to the design profile i/c cost of mould as per drawing i/c applying
3 floating cost of cement 1/32" thick to the exposed face finished smooth
curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)

Type A 200.0 Rft @Rs 94.00 P-Rft Rs 18800
Type B 200.0 Rft @Rs 174.00 P-Rft Rs 34800

4 Pacca brick work in foundation and plinth in cement sand mortar(1:6)
(G.S.I No. 4 (e) P/ 21)
825.00 cft @Rs 11948.36 P%Cft Rs 98574

5 Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)
1100.00 Sft @Rs 2283.93 P%Sft Rs 25123

R.C.C work i/c all labour and material except the cost of steel
reinforcement and its labour for bending and binding which will
be paid separately. This rate also includes all kinds of forms moulds
lifting shuttering curing rendering and finishing the exposed surface
6 i/c screening and washing of shingle (a) R.C work in roof slab beams
columns.rafts lintels & other structural members
laid in situ or precast laid in position complete in a respect. (i)
Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge.
(G.S.I-6(a) P/17)
93.79 Cft @Rs 337.00 P-Cft Rs 31606

Fabrication of mild steel reinforcement for cement concrete i/c
cutting bending laying in position making joints and fastening i/c
7 cost of binding wire also includes removal of rust from bars.
(G.S.I-8-b P/17)
4.00 Cwt @Rs 5001.70 P-Cwt Rs 20007

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	76.04 Cft	@Rs. 14429.25	P% Cft	<u>Rs 10973</u>
			G.Total:		Rs 274487
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	<u>Rs 4000</u>
			G.Total:		Rs 278487

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	8100.00 Cft	@Rs 2117.50	P%0Cft	Rs 17152
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	8100.00 Cft	@Rs 263.00	P%0Cft	Rs 2130
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	8100.00 Cft	@Rs 5039.00	P%0Cft	Rs 40816
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3564 Cft	@Rs 9416.28	P%cft	Rs 335596
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2700 Cft	@Rs 14429.25	P%cft	Rs 389590
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	225.00 sft	@Rs 3127.41	P% <u>sft</u>	<u>Rs 7037</u>
			Total:		Rs 792321

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	5225.00 Cft	@Rs 11288.75	P% Cft	Rs 589837
2	Supplying & laying hard Muram powderly find Muram (CSI NO: P-)	5225.00 Cft	@Rs 1800.00	P% Cft	Rs 94050
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	20900 sft	@Rs 199.77	P.sft	<u>Rs 4175193</u>
			Total:		Rs 4859080

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	274487	4000	Rs 278487
2	Part-II C.C Blocks	792321	0	Rs 792321
3	Part-III Paver Bricks	4859080	0	Rs 4859080
	G.Total:	5925888	4000	Rs 5929888

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains & C.C Blocks in various streets of
Union Council No. 10 Ward No. 01 & 04 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	4515.00 cft		@Rs 3176.25	P%0Cft	Rs 14341
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	1055.00 Cft		@Rs 11288.75	P%0Cft	Rs 119096
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 1000.0 Rft		@Rs 94.00	P-Rft	Rs 94000
	Type B 600.0 Rft		@Rs 174.00	P-Rft	Rs 104400
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	3075.00 cft		@Rs 11948.36	P%0Cft	Rs 367412
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	4300.00 Sft		@Rs 2283.93	P%0Sft	Rs 98209
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	69.39 Cft		@Rs 337.00	P-Cft	Rs 23386
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005
8		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)			
	155.46 Cft		@Rs. 14429.25	P%0Cft	Rs 22432
G.Total:					Rs 858281

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

I No @Rs 4000.00 P.Each Rs 4000

G.Total: Rs 862281

PART-II CC BLOCKS

- 1 Barrow pit excavation undressed lead upto 100ft ordinary soil
(G.S.I. No. 3 (a) p/ 1)
25000.00 Cft @Rs 2117.50 P%0Cft Rs 52938
 - 2 Laying arth in 6"thick layers levelling and dressing etc completed
(G.S.I.No. 13 a p/ 3)
25000.00 Cft @Rs 263.00 P%0Cft Rs 6575
 - 3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)
25000.00 Cft @Rs 5039.00 P%0Cft Rs 125975
 - 4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8)
(G.SI. No. 4(b) p/ 15)
8250 Cft @Rs 9416.28 P%cft Rs 776843
 - 5 Cement concrete plain i/c placing compacting, finishing
and curing etc complete i/c sreening & washing of stone aggregate
without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)
6250 Cft @Rs 14429.25 P%cft Rs 901828
 - 6 Erection and removal of centering for R.C.C or plain C.C works
of deodar wood (2nd class) (b) for partal wood (vertical).
(G.S.I.No. 19 p/ 18)
625.00 sft @Rs 3127.41 P%sf Rs 19546
- Total: Rs 1883705**

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	858281	4000	Rs 862281
2	Part-II C.C Blocks	1883705	0	Rs 1883705
	G.Total:	2741986	4000	Rs 2745986

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana

EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana

MAJOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 10 Ward No. 01 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
-----	-----	------	------	------	--------

Part-I C.C Drains

- 1 Excavation in foundation of building bridges and other structures
i/c dag belling dressing refilling around the structures with excavated
earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)
4874.25 cft @Rs 3176.25 P%0Cft Rs 15482
- 2 Cement concrete plain i/c placing compacting finishing
and curing complete i/c screening and washing of stone
aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17
1099.75 Cft @Rs 11288.75 P%Cft Rs 124148
- 3 Construction of standard open type drains cunette block of C.C 1:2:4 in
situ to the design profile i/c cost of mould as per drawing i/c applying
floating cost of cement 1/32" thick to the exposed face finished smooth
curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)

Type A 950.0 Rft @Rs 94.00 P-Rft Rs 89300
Type B 700.0 Rft @Rs 174.00 P-Rft Rs 121800
- 4 Pacca brick work in foundation and plinth in cement sand mortar(1:6)
(G.S.I No. 4 (e) P/ 21)
3262.50 cft @Rs 11948.36 P%Cft Rs 389815
- 5 Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)
4475.00 Sft @Rs 2283.93 P%Sft Rs 102206
- 6 R.C.C work i/c all labour and material except the cost of steel
reinforcement and its labour for bending and binding which will
be paid separately. This rate also includes all kinds of forms moulds
lifting shuttering curing rendering and finishing the exposed surface
i/c screening and washing of shingle (a) R.C work in roof slab beams
columns,rafts lintels & other structural members
laid in situ or precast laid in position complete in a respect. (i)
Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge.
(G.S.I-6(a) P/17)
85.66 Cft @Rs 337.00 P-Cft Rs 28866
- 7 Fabrication of mild steel reinforcement for cement concrete i/c
cutting bending laying in position making joints and fastening i/c
cost of binding wire also includes removal of rust from bars.
(G.S.I-8-b P/17)
3.00 Cwt @Rs 5001.70 P-Cwt Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	164.78	Cft	@Rs. 14429.25	P% Cft	Rs 23776
				G.Total:		Rs 910398
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1	No	@Rs 4000.00	P.Each	Rs 4000
				G.Total:		Rs 914398

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	12000.00	Cft	@Rs 2117.50	P%0Cft	Rs 25410
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	12000.00	Cft	@Rs 263.00	P%0Cft	Rs 3156
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	12000.00	Cft	@Rs 5039.00	P%0Cft	Rs 60468
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3960	Cft	@Rs 9416.28	P%cft	Rs 372885
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3000	Cft	@Rs 14429.25	P%cft	Rs 432878
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	300.00	sft	@Rs 3127.41	P%0sft	Rs 9382
				Total:		Rs 904178

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2200.00	Cft	@Rs 11288.75	P% Cft	Rs 248353
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00	Cft	@Rs 1800.00	P% Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800	sft	@Rs 199.77	P.sft	Rs 1757976
				Total:		Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	910398	4000	Rs 914398
2	Part-II C.C Blocks	904178	0	Rs 904178
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3860505	4000	Rs 3864505

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


✓EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

19

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 11 Ward No. 01 & 03 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3702.00 cft		@Rs 3176.25	P%0Cft	Rs 11758
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	859.00 Cft		@Rs 11288.75	P%Cft	Rs 96970
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
	Type A 800.0 Rft		@Rs 94.00	P-Rft	Rs 75200
	Type B 500.0 Rft		@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2512.50 cft		@Rs 11948.36	P%Cft	Rs 300203
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3500.00 Sft		@Rs 2283.93	P%Sft	Rs 79938
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6	77.52 Cft		@Rs 337.00	P-Cft	Rs 26126
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)

110.92 Cft @Rs. 14429.25 P% Cft Rs 16004

G.Total: Rs 708204

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No @Rs 4000.00 P.Each Rs 4000

G.Total: Rs 712204

Part- II CC BLOCKS

1 Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)

12000.00 Cft @Rs 2117.50 P%0Cft Rs 25410

2 Laying arth in 6" thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)

12000.00 Cft @Rs 263.00 P%0Cft Rs 3156

3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

12000.00 Cft @Rs 5039.00 P%0Cft Rs 60468

4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)

3960 Cft @Rs 9416.28 P%cft Rs 372885

5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

3000 Cft @Rs 14429.25 P%cft Rs 432878

6 Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)

300.00 sft @Rs 3127.41 P%sft Rs 9382

Total: Rs 904178

Part-III PAVER TILE

1 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)

2200.00 Cft @Rs 11288.75 P% Cft Rs 248353

2 Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)

2200.00 Cft @Rs 1800.00 P% Cft Rs 39600

3 Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)

8800 sft @Rs 199.77 P.sft Rs 1757976

Total: Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	708204	4000	Rs 712204
2	Part-II C.C Blocks	904178	0	Rs 904178
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3658311	4000	Rs 3662311


Amount Total (a)


----- % above /below on the rates CSR


Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 11 Ward No. 02 & 04 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
-----	-----	------	------	------	--------

Part-I C.C Drains

1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2707.50 cft		@Rs 3176.25	P%0Cft	Rs 8600
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	602.50 Cft		@Rs 11288.75	P%Cft	Rs 68015
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
	Type A 500.0 Rft		@Rs 94.00	P-Rft	Rs 47000
	Type B 400.0 Rft		@Rs 174.00	P-Rft	Rs 69600
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1800.00 cft		@Rs 11948.36	P%Cft	Rs 215070
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	2450.00 Sft		@Rs 2283.93	P%Sft	Rs 55956
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6	69.39 Cft		@Rs 337.00	P-Cft	Rs 23386
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	69.66 Cft	@Rs. 14429.25	P%Cft	Rs 10051
			G.Total:		Rs 512683
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 516683

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	7360.00 Cft	@Rs 2117.50	P%0Cft	Rs 15585
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	7360.00 Cft	@Rs 263.00	P%0Cft	Rs 1936
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	7360.00 Cft	@Rs 5039.00	P%0Cft	Rs 37087
4	Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	2640 Cft	@Rs 9416.28	P%cft	Rs 248590
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2000 Cft	@Rs 14429.25	P%cft	Rs 288585
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partial wood (vertical). (G.S.I.No. 19 p/ 18)	200.00 sft	@Rs 3127.41	P%sft	Rs 6255
			Total:		Rs 598037

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2200.00 Cft	@Rs 11288.75	P%Cft	Rs 248353
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00 Cft	@Rs 1800.00	P%Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800 sft	@Rs 199.77	P.sft	Rs 1757976
			Total:		Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	512683	4000	Rs 516683
2	Part-II C.C Blocks	598037	0	Rs 598037
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3156648	4000	Rs 3160648

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains & C.C Blocks in various streets of Union Council No. 12 Ward No. 02, 03 & 04 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2983.50 cft		@Rs 3176.25	P%0Cft	Rs 9476
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	769.50 Cft		@Rs 11288.75	P%Cft	Rs 86867
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	900.0 Rft	@Rs 94.00	P-Rft Rs 84600
		Type B	300.0 Rft	@Rs 174.00	P-Rft Rs 52200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2137.50 cft		@Rs 11948.36	P%Cft	Rs 255396
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3150.00 Sft		@Rs 2283.93	P%Sft	Rs 71944
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface					
6		i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	69.39 Cft		@Rs 337.00	P-Cft	Rs 23386
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7					
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005
8		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 P/15)			
	174.36 Cft		@Rs. 14429.25	P%Cft	Rs 25159
G.Total:					Rs 624033

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 628033

PART-II CC BLOCKS

1 Barrow pit excavation undressed lead upto 100ft ordinary soil

(G.S.I. No. 3 (a) p/ 1)

27000.00 Cft

@Rs 2117.50 P%0Cft Rs 57173

2 Laying arth in 6"thick layers levelling and dressing etc completed

(G.S.I.No. 13 a p/ 3)

27000.00 Cft

@Rs 263.00 P%0Cft Rs 7101

3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

27000.00 Cft

@Rs 5039.00 P%0Cft Rs 136053

4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8)

(G.SI. No. 4(b) p/ 15)

11880 Cft

@Rs 9416.28 P%cft Rs 1118654

5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

9000 Cft

@Rs 14429.25 P%cft Rs 1298633

6 Erection and removal of centering for R.C.C or plain C.C works

of deodar wood (2nd class) (b) for partal wood (vertical).

(G.S.I.No. 19 p/ 18)

750.00 sft

@Rs 3127.41 P%sf Rs 23456

Total: Rs 2641069

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	624033	4000	Rs 628033
2	Part-II C.C Blocks	2641069	0	Rs 2641069
	G.Total:	3265101	4000	Rs 3269101

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the

basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana

EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana

MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 12 Ward No. 01 of Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3883.50 cft		@Rs 3176.25	P%0Cft	Rs 12335
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	919.50 Cft		@Rs 11288.75	P%Cft	Rs 103800
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 900.0 Rft		@Rs 94.00	P-Rft	Rs 84600
	Type B 500.0 Rft		@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2662.50 cft		@Rs 11948.36	P%Cft	Rs 318125
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3750.00 Sft		@Rs 2283.93	P%Sft	Rs 85647
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	69.39 Cft		@Rs 337.00	P-Cft	Rs 23386
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	101.33 Cft	@Rs. 14429.25	P%Cft	Rs 14622
			G.Total:		Rs 744520
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 748520

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	6460.00 Cft	@Rs 2117.50	P%0Cft	Rs 13679
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	6460.00 Cft	@Rs 263.00	P%0Cft	Rs 1699
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	6460.00 Cft	@Rs 5039.00	P%0Cft	Rs 32552
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3135 Cft	@Rs 9416.28	P%cft	Rs 295200
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2375 Cft	@Rs 14429.25	P%cft	Rs 342695
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	237.50 sft	@Rs 3127.41	P%sf	Rs 7428
			Total:		Rs 693253

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2200.00 Cft	@Rs 11288.75	P%Cft	Rs 248353
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00 Cft	@Rs 1800.00	P%Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800 sft	@Rs 199.77	P.sft	Rs 1757976
			Total:		Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	744520	4000	Rs 748520
2	Part-II C.C Blocks	693253	0	Rs 693253
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3483701	4000	Rs 3487701


Amount Total (a)


----- % above /below on the rates CSR


Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 13 Ward No. 02 & 03 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2257.50 cft		@Rs 3176.25	P%0Cft	Rs 7170
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	527.50 Cft		@Rs 11288.75	P%Cft	Rs 59548
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	500.0 Rft	@Rs 94.00	P-Rft Rs 47000
		Type B	300.0 Rft	@Rs 174.00	P-Rft Rs 52200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1537.50 cft		@Rs 11948.36	P%Cft	Rs 183706
5		Cement plaster (1:4) up to 20'height ½"thick (G.S.I-11(b) / P/52)			
	2150.00 Sft		@Rs 2283.93	P%Sft	Rs 49104
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (G.S.I-6(a) P/17)					
6			125.05 Cft	@Rs 337.00	P-Cft Rs 42142
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7			5.00 Cwt	@Rs 5001.70	P-Cwt Rs 25009

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	136.47 Cft	@Rs. 14429.25	P%Cft	Rs 19692
			G.Total:		Rs 485571
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 489571

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	7200.00 Cft	@Rs 2117.50	P%0Cft	Rs 15246
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	7200.00 Cft	@Rs 263.00	P%0Cft	Rs 1894
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	7200.00 Cft	@Rs 5039.00	P%0Cft	Rs 36281
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3168 Cft	@Rs 9416.28	P%cft	Rs 298308
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2400 Cft	@Rs 14429.25	P%cft	Rs 346302
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	200.00 sft	@Rs 3127.41	P%0sft	Rs 6255
			Total:		Rs 704285

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2100.00 Cft	@Rs 11288.75	P%Cft	Rs 237064
2	Supplying & laying hard Muram powderly find Muram (CSI NO: P-)	2100.00 Cft	@Rs 1800.00	P%Cft	Rs 37800
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8400 sft	@Rs 199.77	P.sft	Rs 1678068
			Total:		Rs 1952932





GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	485571	4000	Rs 489571
2	Part-II C.C Blocks	704285	0	Rs 704285
3	Part-III Paver Bricks	1952932	0	Rs 1952932
	G.Total:	3142788	4000	Rs 3146788

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 13 Ward No. 01 & 03 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2257.50 cft		@Rs 3176.25	P%0Cft	Rs 7170
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	527.50 Cft		@Rs 11288.75	P%Cft	Rs 59548
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	500.0 Rft	@Rs 94.00	P-Rft Rs 47000
		Type B	300.0 Rft	@Rs 174.00	P-Rft Rs 52200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1537.50 cft		@Rs 11948.36	P%Cft	Rs 183706
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	2150.00 Sft		@Rs 2283.93	P%Sft	Rs 49104
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6			123.79 Cft	@Rs 337.00	P-Cft Rs 41716
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7			5.00 Cwt	@Rs 5001.70	P-Cwt Rs 25009

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	126.89 Cft	@Rs. 14429.25	P% Cft	Rs 18309
			G.Total:		Rs 483763
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 487763

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	9600.00 Cft	@Rs 2117.50	P%0Cft	Rs 20328
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	9600.00 Cft	@Rs 263.00	P%0Cft	Rs 2525
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	9600.00 Cft	@Rs 5039.00	P%0Cft	Rs 48374
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3168 Cft	@Rs 9416.28	P%cft	Rs 298308
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2400 Cft	@Rs 14429.25	P%cft	Rs 346302
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	200.00 sft	@Rs 3127.41	P%sft	Rs 6255
			Total:		Rs 722092

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2100.00 Cft	@Rs 11288.75	P% Cft	Rs 237064
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2100.00 Cft	@Rs 1800.00	P% Cft	Rs 37800
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8400 sft	@Rs 199.77	P.sft	Rs 1678068
			Total:		Rs 1952932

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	483763	4000	Rs 487763
2	Part-II C.C Blocks	722092	0	Rs 722092
3	Part-III Paver Bricks	1952932	0	Rs 1952932
	G.Total:	3158786	4000	Rs 3162786

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 14 Ward No. 04 of Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I		C.C Drains			
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	1353.75 cft		@Rs 3176.25	P%0Cft	Rs 4300
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	301.25 Cft		@Rs 11288.75	P%0Cft	Rs 34007
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
	Type A 250.0 Rft		@Rs 94.00	P-Rft	Rs 23500
	Type B 200.0 Rft		@Rs 174.00	P-Rft	Rs 34800
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	900.00 cft		@Rs 11948.36	P%0Cft	Rs 107535
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	1225.00 Sft		@Rs 2283.93	P%0Sft	Rs 27978
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6	101.92 Cft		@Rs 337.00	P-Cft	Rs 34347
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7	4.00 Cwt		@Rs 5001.70	P-Cwt	Rs 20007

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	76.04 Cft	@Rs. 14429.25	P%Cft	Rs 10973
			G.Total:		Rs 297446
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 301446

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	14400.00 Cft	@Rs 2117.50	P%0Cft	Rs 30492
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	14400.00 Cft	@Rs 263.00	P%0Cft	Rs 3787
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	14400.00 Cft	@Rs 5039.00	P%0Cft	Rs 72562
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3168 Cft	@Rs 9416.28	P%cft	Rs 298308
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2400 Cft	@Rs 14429.25	P%cft	Rs 346302
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	200.00 sft	@Rs 3127.41	P%0sft	Rs 6255
			Total:		Rs 757705

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	5225.00 Cft	@Rs 11288.75	P%Cft	Rs 589837
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	5225.00 Cft	@Rs 1800.00	P%Cft	Rs 94050
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	20900 sft	@Rs 199.77	P.sft	Rs 4175193
			Total:		Rs 4859080

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	297446	4000	Rs 301446
2	Part-II C.C Blocks	757705	0	Rs 757705
3	Part-III Paver Bricks	4859080	0	Rs 4859080
	G.Total:	5914232	4000	Rs 5918232

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 13 Ward No. 04 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	4602.00 cft		@Rs 3176.25	P%0Cft	Rs 14617
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	1009.00 Cft		@Rs 11288.75	P%0Cft	Rs 113903
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 800.0 Rft		@Rs 94.00	P-Rft	Rs 75200
	Type B 700.0 Rft		@Rs 174.00	P-Rft	Rs 121800
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	3037.50 cft		@Rs 11948.36	P%0Cft	Rs 362931
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	4100.00 Sft		@Rs 2283.93	P%0Sft	Rs 93641
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	85.66 Cft		@Rs 337.00	P-Cft	Rs 28866
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	158.39 Cft	@Rs. 14429.25	P% Cft	Rs 22854
			G.Total:		Rs 848819
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 852819

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	12000.00 Cft	@Rs 2117.50	P%0Cft	Rs 25410
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	12000.00 Cft	@Rs 263.00	P%0Cft	Rs 3156
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	12000.00 Cft	@Rs 5039.00	P%0Cft	Rs 60468
4	Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3960 Cft	@Rs 9416.28	P%cft	Rs 372885
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3000 Cft	@Rs 14429.25	P%cft	Rs 432878
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	300.00 sft	@Rs 3127.41	P% sft	Rs 9382
			Total:		Rs 904178

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	1650.00 Cft	@Rs 11288.75	P% Cft	Rs 186264
2	Supplying & laying hard Muram powderly find Muram (CSI NO: P-)	1650.00 Cft	@Rs 1800.00	P% Cft	Rs 29700
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	6600 sft	@Rs 199.77	P.sft	Rs 1318482
			Total:		Rs 1534446

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	848819	4000	Rs 852819
2	Part-II C.C Blocks	904178	0	Rs 904178
3	Part-III Paver Bricks	1534446	0	Rs 1534446
	G.Total:	3287443	4000	Rs 3291443

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 14 Ward No. 02 & 03 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2707.50 cft		@Rs 3176.25	P%0Cft	Rs 8600
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	602.50 Cft		@Rs 11288.75	P%0Cft	Rs 68015
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
	Type A 500.0 Rft		@Rs 94.00	P-Rft	Rs 47000
	Type B 400.0 Rft		@Rs 174.00	P-Rft	Rs 69600
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1800.00 cft		@Rs 11948.36	P%0Cft	Rs 215070
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	2450.00 Sft		@Rs 2283.93	P%0Sft	Rs 55956
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6	115.66 Cft		@Rs 337.00	P-Cft	Rs 38976
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7	5.00 Cwt		@Rs 5001.70	P-Cwt	Rs 25009

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	158.57	Cft	@Rs. 14429.25	P% Cft	Rs 22880
						<hr/>
				G.Total:		Rs 551106
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1	No	@Rs 4000.00	P.Each	Rs 4000
						<hr/>
				G.Total:		Rs 555106

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	9000.00	Cft	@Rs 2117.50	P%0Cft	Rs 19058
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	9000.00	Cft	@Rs 263.00	P%0Cft	Rs 2367
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	9000.00	Cft	@Rs 5039.00	P%0Cft	Rs 45351
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	2970	Cft	@Rs 9416.28	P%cft	Rs 279664
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2250	Cft	@Rs 14429.25	P%cft	Rs 324658
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	225.00	sft	@Rs 3127.41	P% sft	Rs 7037
					Total:	Rs 678134

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2612.50	Cft	@Rs 11288.75	P% Cft	Rs 294919
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2612.50	Cft	@Rs 1800.00	P% Cft	Rs 47025
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	10450	sft	@Rs 199.77	P.sft	Rs 2087597
					Total:	Rs 2429540

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	551106	4000	Rs 555106
2	Part-II C.C Blocks	678134	0	Rs 678134
3	Part-III Paver Bricks	2429540	0	Rs 2429540
	G.Total:	3658779	4000	Rs 3662779

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 15 Ward No. 01 & 03 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2798.25 cft		@Rs 3176.25	P%0Cft	Rs 8888
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	632.75 Cft		@Rs 11288.75	P%0Cft	Rs 71430
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
	Type A 550.0 Rft		@Rs 94.00	P-Rft	Rs 51700
	Type B 400.0 Rft		@Rs 174.00	P-Rft	Rs 69600
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1875.00 cft		@Rs 11948.36	P%0Cft	Rs 224032
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	2575.00 Sft		@Rs 2283.93	P%Sft	Rs 58811
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6	70.66 Cft		@Rs 337.00	P-Cft	Rs 23811
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	177.29	Cft	@Rs. 14429.25	P%Cft	Rs 25581
				G.Total:		Rs 548858
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1	No	@Rs 4000.00	P.Each	Rs 4000
				G.Total:		Rs 552858

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	13500.00	Cft	@Rs 2117.50	P%0Cft	Rs 28586
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	13500.00	Cft	@Rs 263.00	P%0Cft	Rs 3551
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	13500.00	Cft	@Rs 5039.00	P%0Cft	Rs 68027
4	Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	2970	Cft	@Rs 9416.28	P%cft	Rs 279664
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2250	Cft	@Rs 14429.25	P%cft	Rs 324658
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	225.00	sft	@Rs 3127.41	P% <u>sft</u>	Rs 7037
				Total:		Rs 711522

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2475.00	Cft	@Rs 11288.75	P%Cft	Rs 279397
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2475.00	Cft	@Rs 1800.00	P%Cft	Rs 44550
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	9900	sft	@Rs 199.77	P.sft	Rs 1977723
				Total:		Rs 2301670

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	548858	4000	Rs 552858
2	Part-II C.C Blocks	711522	0	Rs 711522
3	Part-III Paver Bricks	2301670	0	Rs 2301670
	G.Total:	3562049	4000	Rs 3566049

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 15 Ward No. 02 & 04 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	5415.00 cft		@Rs 3176.25	P%0Cft	Rs 17199
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	1205.00 Cft		@Rs 11288.75	P%Cft	Rs 136029
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 1000.0 Rft		@Rs 94.00	P-Rft	Rs 94000
	Type B 800.0 Rft		@Rs 174.00	P-Rft	Rs 139200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	3600.00 cft		@Rs 11948.36	P%Cft	Rs 430141
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	4900.00 Sft		@Rs 2283.93	P%Sft	Rs 111913
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	156.31 Cft		@Rs 337.00	P-Cft	Rs 52677
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	6.00 Cwt		@Rs 5001.70	P-Cwt	Rs 30010

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	186.96 Cft	@Rs. 14429.25	P%Cft	Rs 26977
			G.Total:		Rs 1038147
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 1042147

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	14000.00 Cft	@Rs 2117.50	P%0Cft	Rs 29645
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	14000.00 Cft	@Rs 263.00	P%0Cft	Rs 3682
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	14000.00 Cft	@Rs 5039.00	P%0Cft	Rs 70546
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	4620 Cft	@Rs 9416.28	P%cft	Rs 435032
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3500 Cft	@Rs 14429.25	P%cft	Rs 505024
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	350.00 sft	@Rs 3127.41	P% sft	Rs 10946
			Total:		Rs 1054875

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2750.00 Cft	@Rs 11288.75	P% Cft	Rs 310441
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2750.00 Cft	@Rs 1800.00	P% Cft	Rs 49500
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	11000 sft	@Rs 199.77	P. sft	Rs 2197470
			Total:		Rs 2557411

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	1038147	4000	Rs 1042147
2	Part-II C.C Blocks	1054875	0	Rs 1054875
3	Part-III Paver Bricks	2557411	0	Rs 2557411
	G.Total:	4650432	4000	Rs 4654432


Amount Total (a)

----- % above /below on the rates CSR


Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 16 Ward No. 03 & 04 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3883.50 cft		@Rs 3176.25	P%0Cft	Rs 12335
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	919.50 Cft		@Rs 11288.75	P%Cft	Rs 103800
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 900.0 Rft		@Rs 94.00	P-Rft	Rs 84600
	Type B 500.0 Rft		@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2662.50 cft		@Rs 11948.36	P%Cft	Rs 318125
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3750.00 Sft		@Rs 2283.93	P%Sft	Rs 85647
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)			
	85.66 Cft		@Rs 337.00	P-Cft	Rs 28866
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	174.36 Cft	@Rs. 14429.25	P% Cft	<u>Rs 25159</u>
			G.Total:		Rs 760537
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	<u>Rs 4000</u>
			G.Total:		Rs 764537

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	14000.00 Cft	@Rs 2117.50	P%0Cft	Rs 29645
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	14000.00 Cft	@Rs 263.00	P%0Cft	Rs 3682
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	14000.00 Cft	@Rs 5039.00	P%0Cft	Rs 70546
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	4620 Cft	@Rs 9416.28	P%cft	Rs 435032
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3500 Cft	@Rs 14429.25	P%cft	Rs 505024
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	350.00 sft	@Rs 3127.41	P% sft	<u>Rs 10946</u>
			Total:		Rs 1054875

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2200.00 Cft	@Rs 11288.75	P% Cft	Rs 248353
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00 Cft	@Rs 1800.00	P% Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800 sft	@Rs 199.77	P.sft	<u>Rs 1757976</u>
			Total:		Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	760537	4000	Rs 764537
2	Part-II C.C Blocks	1054875	0	Rs 1054875
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3861341	4000	Rs 3865341

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 16 Ward No. 03 & 04 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2707.50 cft		@Rs 3176.25	P%0Cft	Rs 8600
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	602.50 Cft		@Rs 11288.75	P%Cft	Rs 68015
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	500.0 Rft	@Rs 94.00	P-Rft Rs 47000
		Type B	400.0 Rft	@Rs 174.00	P-Rft Rs 69600
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1800.00 cft		@Rs 11948.36	P%Cft	Rs 215070
5		Cement plaster (1:4) up to 20'height ½"thick (G.S.I-11(b) / P/52)			
	2450.00 Sft		@Rs 2283.93	P%Sft	Rs 55956
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (G.S.I-6(a) P/17)					
6			85.66 Cft	@Rs 337.00	P-Cft Rs 28866
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7			3.00 Cwt	@Rs 5001.70	P-Cwt Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	164.78 Cft	@Rs. 14429.25	P%Cft	<u>Rs 23776</u>
			G.Total:		Rs 531888
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	<u>Rs 4000</u>
			G.Total:		Rs 535888

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	10000.00 Cft	@Rs 2117.50	P%0Cft	Rs 21175
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	10000.00 Cft	@Rs 263.00	P%0Cft	Rs 2630
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	10000.00 Cft	@Rs 5039.00	P%0Cft	Rs 50390
4	Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3300 Cft	@Rs 9416.28	P%cft	Rs 310737
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2500 Cft	@Rs 14429.25	P%cft	Rs 360731
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	250.00 sft	@Rs 3127.41	P%sft	<u>Rs 7819</u>
			Total:		Rs 753482

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2062.50 Cft	@Rs 11288.75	P%Cft	Rs 232830
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2062.50 Cft	@Rs 1800.00	P%Cft	Rs 37125
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8250 sft	@Rs 199.77	P.sft	<u>Rs 1648103</u>
			Total:		Rs 1918058

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	531888	4000	Rs 535888
2	Part-II C.C Blocks	753482	0	Rs 753482
3	Part-III Paver Bricks	1918058	0	Rs 1918058
	G.Total:	3203428	4000	Rs 3207428

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)



EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana



MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana



MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 16 Ward No. 01, 02 & 04 Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
-----	-----	------	------	------	--------

Part-I C.C Drains

1 Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)
2707.50 cft @Rs 3176.25 P%0Cft Rs 8600

2 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17
602.50 Cft @Rs 11288.75 P%Cft Rs 68015

Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)

Type A 500.0 Rft @Rs 94.00 P-Rft Rs 47000

Type B 400.0 Rft @Rs 174.00 P-Rft Rs 69600

4 Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)
1800.00 cft @Rs 11948.36 P%Cft Rs 215070

5 Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)
2450.00 Sft @Rs 2283.93 P%Sft Rs 55956

R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)

85.66 Cft @Rs 337.00 P-Cft Rs 28866

Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)

3.00 Cwt @Rs 5001.70 P-Cwt Rs 15005

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	164.78	Cft	@Rs. 14429.25	P%Cft	Rs 23776
				G.Total:		Rs 531888
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1	No	@Rs 4000.00	P.Each	Rs 4000
				G.Total:		Rs 535888

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	10000.00	Cft	@Rs 2117.50	P%0Cft	Rs 21175
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	10000.00	Cft	@Rs 263.00	P%0Cft	Rs 2630
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	10000.00	Cft	@Rs 5039.00	P%0Cft	Rs 50390
4	Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3300	Cft	@Rs 9416.28	P%cft	Rs 310737
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2500	Cft	@Rs 14429.25	P%cft	Rs 360731
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partial wood (vertical). (G.S.I.No. 19 p/ 18)	250.00	sft	@Rs 3127.41	P% <u>sft</u>	Rs 7819
				Total:		Rs 753482

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2062.50	Cft	@Rs 11288.75	P%Cft	Rs 232830
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2062.50	Cft	@Rs 1800.00	P%Cft	Rs 37125
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8250	sft	@Rs 199.77	P.sft	Rs 1648103
				Total:		Rs 1918058

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	531888	4000	Rs 535888
2	Part-II C.C Blocks	753482	0	Rs 753482
3	Part-III Paver Bricks	1918058	0	Rs 1918058
	G.Total:	3203428	4000	Rs 3207428

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 17 Ward No.01, 02 & 03 of Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	1444.50 cft		@Rs 3176.25	P%0Cft	Rs 4588
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	331.50 Cft		@Rs 11288.75	P%Cft	Rs 37422
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 300.0 Rft		@Rs 94.00	P-Rft	Rs 28200
	Type B 200.0 Rft		@Rs 174.00	P-Rft	Rs 34800
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	975.00 cft		@Rs 11948.36	P%Cft	Rs 116497
5		Cement plaster (1:4) up to 20'height ½"thick (G.S.I-11(b) / P/52)			
	1350.00 Sft		@Rs 2283.93	P%Sft	Rs 30833
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (G.S.I-6(a) P/17)			
	85.66 Cft		@Rs 337.00	P-Cft	Rs 28866
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	3.00 Cwt		@Rs 5001.70	P-Cwt	Rs 15005

- 8 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)

76.04 Cft

@Rs. 14429.25 P%Cft Rs 10973

G.Total: Rs 307184

- 9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 311184

Part- II CC BLOCKS

- 1 Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)

4800.00 Cft

@Rs 2117.50 P%0Cft Rs 10164

- 2 Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)

4800.00 Cft

@Rs 263.00 P%0Cft Rs 1262

- 3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

4800.00 Cft

@Rs 5039.00 P%0Cft Rs 24187

- 4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)

3168 Cft

@Rs 9416.28 P%cft Rs 298308

- 5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

2400 Cft

@Rs 14429.25 P%cft Rs 346302

- 6 Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)

200.00 sft

@Rs 3127.41 P%0sft Rs 6255

Total: Rs 686478

Part-III PAVER TILE

- 1 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)

4500.00 Cft

@Rs 11288.75 P%Cft Rs 507994

- 2 Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)

4500.00 Cft

@Rs 1800.00 P%Cft Rs 81000

- 3 Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)

18000 sft

@Rs 199.77 P.sft Rs 3595860

Total: Rs 4184854

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	307184	4000	Rs 311184
2	Part-II C.C Blocks	686478	0	Rs 686478
3	Part-III Paver Bricks	4184854	0	Rs 4184854
	G.Total:	5178516	4000	Rs 5182516

Amount Total (a)

----- % above /below on the rates CSR


Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 17 Ward No. 04 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I		C.C Drains			
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2889.00 cft		@Rs 3176.25	P%0Cft	Rs 9176
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	663.00 Cft		@Rs 11288.75	P%0Cft	Rs 74844
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	600.0 Rft	@Rs 94.00	P-Rft Rs 56400
		Type B	400.0 Rft	@Rs 174.00	P-Rft Rs 69600
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1950.00 cft		@Rs 11948.36	P%0Cft	Rs 232993
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	2700.00 Sft		@Rs 2283.93	P%0Sft	Rs 61666
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6			145.66 Cft	@Rs 337.00	P-Cft Rs 49086
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7			6.00 Cwt	@Rs 5001.70	P-Cwt Rs 30010

8 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)

180.66 Cft @Rs. 14429.25 P%Cft Rs 26068

G.Total: Rs 609844

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No @Rs 4000.00 P.Each Rs 4000

G.Total: Rs 613844

Part- II CC BLOCKS

1 Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)

14000.00 Cft @Rs 2117.50 P%0Cft Rs 29645

2 Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)

14000.00 Cft @Rs 263.00 P%0Cft Rs 3682

3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

14000.00 Cft @Rs 5039.00 P%0Cft Rs 70546

4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)

4620 Cft @Rs 9416.28 P%cft Rs 435032

5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

3500 Cft @Rs 14429.25 P%cft Rs 505024

6 Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)

350.00 sft @Rs 3127.41 P%0sft Rs 10946

Total: Rs 1054875

Part-III PAVER TILE

1 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)

1650.00 Cft @Rs 11288.75 P%Cft Rs 186264

2 Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)

1650.00 Cft @Rs 1800.00 P%Cft Rs 29700

3 Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)

6600 sft @Rs 199.77 P.sft Rs 1318482

Total: Rs 1534446

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	609844	4000	Rs 613844
2	Part-II C.C Blocks	1054875	0	Rs 1054875
3	Part-III Paver Bricks	1534446	0	Rs 1534446
	G.Total:	3199165	4000	Rs 3203165

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 18 Ward No. 03 & 04 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2076.00 cft		@Rs 3176.25	P%0Cft	Rs 6594
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	467.00 Cft		@Rs 11288.75	P%Cft	Rs 52718
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	400.0	Rft	@Rs 94.00 P-Rft Rs 37600
		Type B	300.0	Rft	@Rs 174.00 P-Rft Rs 52200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1387.50 cft		@Rs 11948.36	P%Cft	Rs 165783
5		Cement plaster (1:4) up to 20'height ½"thick (G.S.I-11(b) / P/52)			
	1900.00 Sft		@Rs 2283.93	P%Sft	Rs 43395
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (G.S.I-6(a) P/17)					
6			115.66	Cft	@Rs 337.00 P-Cft Rs 38976
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7			5.00	Cwt	@Rs 5001.70 P-Cwt Rs 25009

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	158.65 Cft	@Rs. 14429.25	P%Cft	Rs 22893
			G.Total:		Rs 445168
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 449168

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	10000.00 Cft	@Rs 2117.50	P%0Cft	Rs 21175
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	10000.00 Cft	@Rs 263.00	P%0Cft	Rs 2630
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	10000.00 Cft	@Rs 5039.00	P%0Cft	Rs 50390
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3300 Cft	@Rs 9416.28	P%cft	Rs 310737
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2500 Cft	@Rs 14429.25	P%cft	Rs 360731
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	250.00 sft	@Rs 3127.41	P%sft	Rs 7819
			Total:		Rs 753482

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2200.00 Cft	@Rs 11288.75	P%Cft	Rs 248353
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00 Cft	@Rs 1800.00	P%Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800 sft	@Rs 199.77	P.sft	Rs 1757976
			Total:		Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	445168	4000	Rs 449168
2	Part-II C.C Blocks	753482	0	Rs 753482
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3244578	4000	Rs 3248578

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

26

BILL OF QUANTITY

(A) **Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 18 Ward No. 01 of Larkano City**

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	2076.00 cft		@Rs 3176.25	P%0Cft	Rs 6594
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	467.00 Cft		@Rs 11288.75	P%0Cft	Rs 52718
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	400.0 Rft	@Rs 94.00	P-Rft Rs 37600
		Type B	300.0 Rft	@Rs 174.00	P-Rft Rs 52200
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1387.50 cft		@Rs 11948.36	P%0Cft	Rs 165783
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	1900.00 Sft		@Rs 2283.93	P%0Sft	Rs 43395
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6			115.66 Cft	@Rs 337.00	P-Cft Rs 38976
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7			5.00 Cwt	@Rs 5001.70	P-Cwt Rs 25009

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	158.65 Cft	@Rs. 14429.25	P%Cft	Rs 22893
			G.Total:		Rs 445168
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 449168

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	10000.00 Cft	@Rs 2117.50	P%0Cft	Rs 21175
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	10000.00 Cft	@Rs 263.00	P%0Cft	Rs 2630
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	10000.00 Cft	@Rs 5039.00	P%0Cft	Rs 50390
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3300 Cft	@Rs 9416.28	P%cft	Rs 310737
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2500 Cft	@Rs 14429.25	P%cft	Rs 360731
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	250.00 sft	@Rs 3127.41	P%sft	Rs 7819
			Total:		Rs 753482

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2200.00 Cft	@Rs 11288.75	P%Cft	Rs 248353
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00 Cft	@Rs 1800.00	P%Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800 sft	@Rs 199.77	P.sft	Rs 1757976
			Total:		Rs 2045929

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	445168	4000	Rs 449168
2	Part-II C.C Blocks	753482	0	Rs 753482
3	Part-III Paver Bricks	2045929	0	Rs 2045929
	G.Total:	3244578	4000	Rs 3248578

Amount Total (a)


----- % above /below on the rates CSR


Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A) Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 19 Ward No. 01 of Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3883.50 cft		@Rs 3176.25	P%0Cft	Rs 12335
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	919.50 Cft		@Rs 11288.75	P%0Cft	Rs 103800
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A	900.0	Rft	@Rs 94.00 P-Rft Rs 84600
		Type B	500.0	Rft	@Rs 174.00 P-Rft Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2662.50 cft		@Rs 11948.36	P%0Cft	Rs 318125
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	3750.00 Sft		@Rs 2283.93	P%0Sft	Rs 85647
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6			100.66	Cft	@Rs 337.00 P-Cft Rs 33921
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7			4.00	Cwt	@Rs 5001.70 P-Cwt Rs 20007

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	193.26 Cft	@Rs. 14429.25	P%Cft	Rs 27886
			G.Total:		Rs 773321
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 777321

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	12000.00 Cft	@Rs 2117.50	P%0Cft	Rs 25410
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	12000.00 Cft	@Rs 263.00	P%0Cft	Rs 3156
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	12000.00 Cft	@Rs 5039.00	P%0Cft	Rs 60468
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	3960 Cft	@Rs 9416.28	P%cft	Rs 372885
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	3000 Cft	@Rs 14429.25	P%cft	Rs 432878
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	300.00 sft	@Rs 3127.41	P%sft	Rs 9382
			Total:		Rs 904178

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	1800.00 Cft	@Rs 11288.75	P%Cft	Rs 203198
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2200.00 Cft	@Rs 1800.00	P%Cft	Rs 39600
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	8800 sft	@Rs 199.77	P.sft	Rs 1757976
			Total:		Rs 2000774

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	773321	4000	Rs 777321
2	Part-II C.C Blocks	904178	0	Rs 904178
3	Part-III Paver Bricks	2000774	0	Rs 2000774
	G.Total:	3678273	4000	Rs 3682273

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 18 Ward No. 02 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	1626.00 cft		@Rs 3176.25	P%0Cft	Rs 5165
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	392.00 Cft		@Rs 11288.75	P%0Cft	Rs 44252
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3					
	Type A 400.0 Rft		@Rs 94.00	P-Rft	Rs 37600
	Type B 200.0 Rft		@Rs 174.00	P-Rft	Rs 34800
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	1125.00 cft		@Rs 11948.36	P%0Cft	Rs 134419
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	1600.00 Sft		@Rs 2283.93	P%0Sft	Rs 36543
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6					
	115.66 Cft		@Rs 337.00	P-Cft	Rs 38976
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7					
	5.00 Cwt		@Rs 5001.70	P-Cwt	Rs 25009

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	158.65 Cft	@Rs. 14429.25	P%Cft	Rs 22893
			G.Total:		Rs 379656
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 383656

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	13500.00 Cft	@Rs 2117.50	P%0Cft	Rs 28586
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	13500.00 Cft	@Rs 263.00	P%0Cft	Rs 3551
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	13500.00 Cft	@Rs 5039.00	P%0Cft	Rs 68027
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	2970 Cft	@Rs 9416.28	P%cft	Rs 279664
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2250 Cft	@Rs 14429.25	P%cft	Rs 324658
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	225.00 sft	@Rs 3127.41	P%0sft	Rs 7037
			Total:		Rs 711522

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2750.00 Cft	@Rs 11288.75	P%Cft	Rs 310441
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2750.00 Cft	@Rs 1800.00	P%Cft	Rs 49500
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	11000 sft	@Rs 199.77	P.sft	Rs 2197470
			Total:		Rs 2557411

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	379656	4000	Rs 383656
2	Part-II C.C Blocks	711522	0	Rs 711522
3	Part-III Paver Bricks	2557411	0	Rs 2557411
	G.Total:	3648588	4000	Rs 3652588

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

(A)

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 19 Ward No. 02 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
Part-I		C.C Drains			
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	4065.00 cft		@Rs 3176.25	P%0Cft	Rs 12911
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	980.00 Cft		@Rs 11288.75	P%Cft	Rs 110630
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3		Type A 1000.0 Rft	@Rs 94.00	P-Rft	Rs 94000
		Type B 500.0 Rft	@Rs 174.00	P-Rft	Rs 87000
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	2812.50 cft		@Rs 11948.36	P%Cft	Rs 336048
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	4000.00 Sft		@Rs 2283.93	P%Sft	Rs 91357
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6		92.52 Cft	@Rs 337.00	P-Cft	Rs 31181
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7		4.00 Cwt	@Rs 5001.70	P-Cwt	Rs 20007

- 8 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)

174.36 Cft

@Rs. 14429.25 P% Cft Rs 25159

G.Total: Rs 808293

- 9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 812293

Part- II CC BLOCKS

- 1 Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)

15000.00 Cft

@Rs 2117.50 P%0Cft Rs 31763

- 2 Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)

15000.00 Cft

@Rs 263.00 P%0Cft Rs 3945

- 3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

15000.00 Cft

@Rs 5039.00 P%0Cft Rs 75585

- 4 Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)

4950 Cft

@Rs 9416.28 P%cft Rs 466106

- 5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

3750 Cft

@Rs 14429.25 P%cft Rs 541097

- 6 Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)

375.00 sft

@Rs 3127.41 P% sft Rs 11728

Total: Rs 1130223

Part-III PAVER TILE

- 1 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)

1375.00 Cft

@Rs 11288.75 P% Cft Rs 155220

- 2 Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)

1375.00 Cft

@Rs 1800.00 P% Cft Rs 24750

- 3 Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)

5500 sft

@Rs 199.77 P.sft Rs 1098735

Total: Rs 1278705

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	808293	4000	Rs 812293
2	Part-II C.C Blocks	1130223	0	Rs 1130223
3	Part-III Paver Bricks	1278705	0	Rs 1278705
	G.Total:	3217221	4000	Rs 3221221

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the
basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 19 Ward No. 03 & 04 of Larkano City

(A)

S.#	Qty	Item	Rate	Unit	Amount
Part-I		C.C Drains			
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	994.50 cft		@Rs 3176.25	P%0Cft	Rs 3159
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17			
	256.50 Cft		@Rs 11288.75	P%Cft	Rs 28956
Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)					
3					
	Type A 300.0 Rft		@Rs 94.00	P-Rft	Rs 28200
	Type B 100.0 Rft		@Rs 174.00	P-Rft	Rs 17400
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	712.50 cft		@Rs 11948.36	P%Cft	Rs 85132
5		Cement plaster (1:4) up to 20'height 1/2"thick (G.S.I-11(b) / P/52)			
	1050.00 Sft		@Rs 2283.93	P%Sft	Rs 23981
R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1:2:4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I-6(a) P/17)					
6					
	155.05 Cft		@Rs 337.00	P-Cft	Rs 52252
Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)					
7					
	6.00 Cwt		@Rs 5001.70	P-Cwt	Rs 30010

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	123.52 Cft	@Rs. 14429.25	P% Cft	Rs 17822
			G.Total:		Rs 286912
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	Rs 4000
			G.Total:		Rs 290912

Part- II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	13500.00 Cft	@Rs 2117.50	P%0Cft	Rs 28586
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	13500.00 Cft	@Rs 263.00	P%0Cft	Rs 3551
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	13500.00 Cft	@Rs 5039.00	P%0Cft	Rs 68027
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	2970 Cft	@Rs 9416.28	P%cft	Rs 279664
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2250 Cft	@Rs 14429.25	P%cft	Rs 324658
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	225.00 sft	@Rs 3127.41	P% sft	Rs 7037
			Total:		Rs 711522

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	2750.00 Cft	@Rs 11288.75	P% Cft	Rs 310441
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	2750.00 Cft	@Rs 1800.00	P% Cft	Rs 49500
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	11000 sft	@Rs 199.77	P.sft	Rs 2197470
			Total:		Rs 2557411

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	286912	4000	Rs 290912
2	Part-II C.C Blocks	711522	0	Rs 711522
3	Part-III Paver Bricks	2557411	0	Rs 2557411
	G.Total:	3555844	4000	Rs 3559844

Amount Total (a)


----- % above /below on the rates CSR

Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

41

(A) **Construction of CC Drains, C.C Blocks & Paver Blocks in various streets of Union Council No. 19 Ward No. 03 of Larkano City**

S.#	Qty	Item	Rate	Unit	Amount
Part-I C.C Drains					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	1444.50 cft		@Rs 3176.25	P%0Cft	Rs 4588
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	331.50 Cft		@Rs 11288.75	P%0Cft	Rs 37422
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 300.0 Rft		@Rs 94.00	P-Rft	Rs 28200
	Type B 200.0 Rft		@Rs 174.00	P-Rft	Rs 34800
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	975.00 cft		@Rs 11948.36	P%0Cft	Rs 116497
5		Cement plaster (1:4) up to 20'height ½"thick (G.S.I-11(b) / P/52)			
	1350.00 Sft		@Rs 2283.93	P%Sft	Rs 30833
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (G.S.I-6(a) P/17)			
	100.66 Cft		@Rs 337.00	P-Cft	Rs 33921
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	4.00 Cwt		@Rs 5001.70	P-Cwt	Rs 20007

8	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)	164.78 Cft	@Rs. 14429.25	P%Cft	<u>Rs 23776</u>
			G.Total:		Rs 330044
9	Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)	1 No	@Rs 4000.00	P.Each	<u>Rs 4000</u>
			G.Total:		Rs 334044

Part-II CC BLOCKS

1	Barrow pit excavation undressed lead upto 100ft ordinary soil (G.S.I. No. 3 (a) p/ 1)	8000.00 Cft	@Rs 2117.50	P%0Cft	Rs 16940
2	Laying arth in 6"thick layers levelling and dressing etc completed (G.S.I.No. 13 a p/ 3)	8000.00 Cft	@Rs 263.00	P%0Cft	Rs 2104
3	Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)	8000.00 Cft	@Rs 5039.00	P%0Cft	Rs 40312
4	Cement concrete bricks or stone ballest ½" to 2" gauge.(Ratio 1:4:8) (G.SI. No. 4(b) p/ 15)	2640 Cft	@Rs 9416.28	P%cft	Rs 248590
5	Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)	2000 Cft	@Rs 14429.25	P%cft	Rs 288585
6	Erection and removal of centering for R.C.C or plain C.C works of deodar wood (2nd class) (b) for partal wood (vertical). (G.S.I.No. 19 p/ 18)	200.00 sft	@Rs 3127.41	P%sft	<u>Rs 6255</u>
			Total:		Rs 602786

Part-III PAVER TILE

1	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5 f P/15)	3300.00 Cft	@Rs 11288.75	P%Cft	Rs 372529
2	Supplying & laying hard Muram powdererly find Muram (CSI NO: P-)	3300.00 Cft	@Rs 1800.00	P%Cft	Rs 59400
3	Providing & fixing cement paving blocks of flooring having sixze of 197x97x60mm) of city quddra/ cobble shape with natural colour having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand and laying in specified manner / pattern and desing etc (CSI No.71 P-48)	13200 sft	@Rs 199.77	P.sft	<u>Rs 2636964</u>
			Total:		Rs 3068893

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	330044	4000	Rs 334044
2	Part-II C.C Blocks	602786	0	Rs 602786
3	Part-III Paver Bricks	3068893	0	Rs 3068893
	G.Total:	4001722	4000	Rs 4005722

Amount Total (a)


----- % above /below on the rates CSR


Amount to be added /deducted on the basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)


EXECUTIVE ENGINEER
Larkana Municipal Corporation
Larkana


MUNICIPAL COMMISSIONER
Larkana Municipal Corporation
Larkana


MAYOR
Larkana Municipal Corporation
Larkana

BILL OF QUANTITY

42

(A) Construction of CC Drains & C.C Blocks in various streets of Union Council No. 20 Ward No. 03 & 04 Larkano City

S.#	Qty	Item	Rate	Unit	Amount
PART-I C.C DRAINS					
1		Excavation in foundation of building bridges and other structures i/c dag belling dressing refilling around the structures with excavated earth watering ramming lead up to 5ft (b) in ordinary soil (G.S.I-18/ P/4)			
	3615.00 cft		@Rs 3176.25	P%0Cft	Rs 11482
2		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (G.S.I-5(ii) P/17)			
	1251.50 Cft		@Rs 11288.75	P%Cft	Rs 141279
3		Construction of standard open type drains cunette block of C.C 1:2:4 in situ to the design profile i/c cost of mould as per drawing i/c applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing . (P.H.S.I No D, P/ 58)			
	Type A 1000.0 Rft		@Rs 94.00	P-Rft	Rs 94000
	Type B 400.0 Rft		@Rs 174.00	P-Rft	Rs 69600
	Type C 300.0 Rft		@Rs 309.00	P-Rft	Rs 92700
4		Pacca brick work in foundation and plinth in cement sand mortar(1:6) (G.S.I No. 4 (e) P/ 21)			
	3450.00 cft		@Rs 11948.36	P%Cft	Rs 412218
5		Cement plaster (1:4) up to 20"height ½"thick (G.S.I-11(b) / P/52)			
	4900.00 Sft		@Rs 2283.93	P%Sft	Rs 111913
6		R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab beams columns,rafts lintels & other structural members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (G.S.I-6(a) P/17)			
	134.52 Cft		@Rs 337.00	P-Cft	Rs 45335
7		Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (G.S.I-8-b P/17)			
	5.00 Cwt		@Rs 5001.70	P-Cwt	Rs 25009
8		Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4 (G.S.I-5 f P/15)			
	193.26 Cft		@Rs. 14429.25	P%Cft	Rs 27886
G.Total:					Rs 1031421

9 Supplying & fixing marble stone board size (2.0x2.0) (N/S Item)

1 No

@Rs 4000.00 P.Each Rs 4000

G.Total: Rs 1035421

PART-II CC BLOCKS

1 Barrow pit excavation undressed lead upto 100ft ordinary soil

(G.S.I. No. 3 (a) p/ 1)

24900.00 Cft

@Rs 2117.50 P%0Cft Rs 52726

2 Laying arth in 6"thick layers levelling and dressing etc completed

(G.S.I.No. 13 a p/ 3)

24900.00 Cft

@Rs 263.00 P%0Cft Rs 6549

3 Extra lead for every 50' Ft: additional lead or part thereof.(GSI NO.8P-3)

24900.00 Cft

@Rs 5039.00 P%0Cft Rs 125471

4 Cement concrete bricks or stone ballest 1/2" to 2" gauge.(Ratio 1:4:8)

(G.SI. No. 4(b) p/ 15)

9900 Cft

@Rs 9416.28 P%cft Rs 932212

5 Cement concrete plain i/c placing compacting, finishing and curing etc complete i/c sreening & washing of stone aggregate without shuttering (Ratio 1:2:4) (G.S.I No. 5 p/ 16)

7500 Cft

@Rs 14429.25 P%cft Rs 1082194

6 Erection and removal of centering for R.C.C or plain C.C works

of deodar wood (2nd class) (b) for partal wood (vertical).

(G.S.I.No. 19 p/ 18)

625.00 sft

@Rs 3127.41 P%sft Rs 19546

Total: Rs 2218697

GENERAL ABSTRACT

S.#	Sub- Works	Schedule Amount	N/S Amount	G.Total:
1	Part-I C.C drains	1031421	4000	Rs 1035421
2	Part-II C.C Blocks	2218697	0	Rs 2218697
	G.Total:	3250118	4000	Rs 3254118

Amount Total (a)

----- % above /below on the rates CSR

Amount to be added /deducted on the

basis of premium quoted. TOTAL(b)

Total (A) = a+b in words & figure:

(CONTRACTOR)

MUNICIPAL COMMISSIONER

Larkana Municipal Corporation

Larkana

EXECUTIVE ENGINEER

Larkana Municipal Corporation

Larkana

MAYOR

Larkana Municipal Corporation

Larkana

**OFFICE OF THE
LARKANA MUNICIPAL CORPORATION
LARKANA**

BIDDING DOCUMENTS

FOR

Name of Contractor/ firm: _____

Dr No & Date of Issue: _____

Call Deposit Receipt No: Date: _____

Amount Rs: _____

Executive Engineer
Larkana Municipal Corporation
Larkana

Municipal Commissioner
Larkana Municipal Corporation
Larkana

Mayor
Larkana Municipal Corporation
Larkana

Preface

These Bidding Documents have been prepared for use by Procuring agencies and their implementing agencies in the procurement of goods through National Competitive Bidding (NCB).

In order to simplify the preparation of bidding documents for each procurement, the Bidding Documents are grouped in two parts based on provisions which are fixed and that which are specific for each procurement. Provisions which are intended to be used unchanged are in Part one, which includes Section I, Instructions to Bidders, and Section II, General Conditions of Contract. Data and provisions specific to each procurement and contract are included in Part Two which includes Section II, Bid Data Sheet; Section III, Special Conditions of Contract; Section-IV, Schedule of Requirements; Section V, Technical Specifications; and the forms to be used in Section I, Invitation for Bids, and Section VI, Sample Forms.

This is Part one which is fixed and contains provisions which are to be used unchanged. Each section is prepared with notes intended only as information for the Procuring agency or the person drafting the bidding documents. They shall not be included in the final documents.

Table of Contents- Part One

PART ONE - SECTION I. INSTRUCTIONS TO BIDDERS.....2

TABLE OF CLAUSES.....3

PART ONE - SECTION II. GENERAL CONDITIONS OF CONTRACT.....21

TABLE OF CLAUSES.....22

Part One - Section I.
Instructions to Bidders

Table of Clauses

A. INTRODUCTION.....	4
1. SOURCE OF FUNDS.....	4
2. ELIGIBLE BIDDERS.....	4
3. ELIGIBLE GOODS AND SERVICES.....	5
4. COST OF BIDDING.....	5
B. THE BIDDING DOCUMENTS.....	5
5. CONTENT OF BIDDING DOCUMENTS.....	5
6. CLARIFICATION OF BIDDING DOCUMENTS.....	6
7. AMENDMENT OF BIDDING DOCUMENTS.....	6
C. PREPARATION OF BIDS.....	6
8. LANGUAGE OF BID.....	6
9. DOCUMENTS COMPRISING THE BID.....	6
10. BID FORM.....	7
11. BID PRICES.....	7
12. BID CURRENCIES.....	7
13. DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY AND QUALIFICATION.....	7
14. DOCUMENTS ESTABLISHING GOODS' ELIGIBILITY AND CONFORMITY TO BIDDING DOCUMENTS.....	8
15. BID SECURITY.....	9
16. PERIOD OF VALIDITY OF BIDS.....	10
17. FORMAT AND SIGNING OF BID.....	10
D. SUBMISSION OF BIDS.....	11
18. SEALING AND MARKING OF BIDS.....	11
19. DEADLINE FOR SUBMISSION OF BIDS.....	11
20. LATE BIDS.....	12
21. MODIFICATION AND WITHDRAWAL OF BIDS.....	12
E. OPENING AND EVALUATION OF BIDS.....	12
22. OPENING OF BIDS BY THE PROCURING AGENCY.....	12
23. CLARIFICATION OF BIDS.....	13
24. PRELIMINARY EXAMINATION.....	13
25. EVALUATION AND COMPARISON OF BIDS.....	14
26. CONTACTING THE PROCURING AGENCY.....	18
F. AWARD OF CONTRACT.....	18
27. POST-QUALIFICATION.....	18
28. AWARD CRITERIA.....	18
29. PROCURING AGENCY'S RIGHT TO VARY QUANTITIES AT TIME OF AWARD.....	19
30. PROCURING AGENCY'S RIGHT TO ACCEPT ANY BID AND TO REJECT ANY OR ALL BIDS.....	19
31. NOTIFICATION OF AWARD.....	19
32. SIGNING OF CONTRACT.....	19
33. PERFORMANCE SECURITY.....	19
34. CORRUPT OR FRAUDULENT PRACTICES.....	20

Instructions to Bidders

A. Introduction

1. Source of Funds

- 1.1 The Procuring agency has received /applied for loan/grant/federal/provincial/local government funds from the source(s) indicated in the bidding data in various currencies towards the cost of the project/schemes specified in the bidding data and it is intended that part of the proceeds of this loan/grant/funds/will be applied to eligible payments under the contract for which these bidding documents are issued.
- 1.2 Payment by the Fund will be made only at the request of the Procuring agency and upon approval by the Government of Sindh, and in case of a project will be subject in all respect to the terms and conditions of the agreement. The Project Agreement prohibit a withdrawal from the allocate fund account for the purpose of any payment to persons or entities, or for any import of goods, if such payment or import, to the knowledge of the Federal Government/ Sindh Government, is prohibited by a decision of the United Nations Security Council taken under Chapter VII of the Charter of the United Nations. No party other than the Procuring agency shall derive any rights from the Project Agreement or have any claim to the allocate fund proceeds.

2. Eligible Bidders

- 2.1 This Invitation for Bids is open to all suppliers from eligible source as defined in the SPP Rules, 2009 and its Bidding Documents except as provided hereinafter.
- 2.2 Bidders should not be associated, or have been associated in the past, directly or in directly, with a firm or any of its affiliates which have been engaged by the Procuring agency to provide consulting services for the preparation of the design, specifications, and other documents to be used for the procurement of the goods to be purchased under this Invitation for Bids.
- 2.3 Government-owned enterprises in the Province of Sindh may participate only if they are legally and financially autonomous, if they operate under commercial law, and if they are not a dependent agency of the Government of Sindh.
- 2.4 Bidders shall not be eligible to bid if they are under a declaration of ineligibility for corrupt and fraudulent practices issued by the

- any government organization in accordance with sub clause 34.1
- 3. Eligible Goods and Services**
- 3.1 All goods and related services to be supplied under the contract shall have their origin in eligible source countries, defined in the SPP Rules, 2009 and its Bidding Documents, and all expenditures made under the contract will be limited to such goods and services.
- 3.2 For purposes of this clause, "origin" means the place where the goods are mined, grown, or produced, or the place from which the related services are supplied. Goods are produced when, through manufacturing, processing, or substantial and major assembly of components, a commercially-recognized product results that is substantially different in basic characteristics or in purpose or utility from its components.
- 3.3 The origin of goods and services is distinct from the nationality of the Bidder.
- 4. Cost of Bidding**
- 4.1 The Bidder shall bear all costs associated with the preparation and submission of its bid, and the Procuring agency named in the Bid Data Sheet, here in after referred to as "the Procuring agency," will in no case be responsible or liable for those costs, regardless of the conduct or outcome of the bidding process.

B. The Bidding Documents

- 5. Content of Bidding Documents**
- 5.1 the bidding documents include:
- (a) Instructions to Bidders(ITB)
 - (b) Bid Data Sheet
 - (c) General Conditions of Contract (GCC)
 - (d) Special Conditions of Contract (SCC)
 - (e) Schedule of Requirements
 - (f) Technical Specifications
 - (g) Bid Form and Price Schedules
 - (h) Bid Security Form
 - (i) Contract Form
 - (j) Performance Security Form
 - (k) Manufacturer's Authorization Form
- 5.2 The Bidder is expected to examine all instructions, forms, terms, and specifications in the bidding documents. Failure to furnish all information required by the bidding documents or to submit a bid not substantially responsive to the bidding documents in every respect will be at the Bidder's risk and may result in the

- rejection of its bid.
- 6. Clarification of Bidding Documents** 6.1 A interested Bidder requiring any clarification of the bidding documents may notify the Procuring agency in writing. The Procuring agency will respond in writing to any request for clarification of the bidding documents which it receives no later than three working days prior to the deadline for the submission of bids prescribed in the Bid Data Sheet. Written copies of the Procuring agency's response (including an explanation of the query but without identifying the source of inquiry) will be sent to all interested bidders that have received the bidding documents.
- 7. Amendment of Bidding Documents** 7.1 At any time prior to the deadline for submission of bids, the Procuring agency, for any reason, whether at its own initiative or in response to a clarification requested by a interested Bidder, may modify the bidding documents by amendment.
- 7.2 All interested bidders that have received the bidding documents will be notified of the amendment in writing, and will be binding on them.
- 7.3 In order to allow interested bidders reasonable time in which to take the amendment into account in preparing their bids, the Procuring agency, at its discretion, may extend the deadline for the submission of bids.

C. Preparation of Bids

- 8. Language of Bid** 8.1 The bid prepared by the Bidder, as well as all correspondence and documents relating to the bid exchanged by the Bidder and the Procuring agency shall be written in the language specified in the Bid Data Sheet. Supporting documents and printed literature furnished by the Bidder may be in another language provided they are accompanied by an accurate translation of the relevant passages in the language specified in the Bid Data Sheet, in which case, for purposes of interpretation of the Bid, the translation shall govern.
- 9. Documents Comprising the Bid** 9.1 The bid prepared by the Bidder shall comprise the following components:
- (a) a Bid Form and a Price Schedule completed in accordance with ITB Clauses 10, 11, and 12;
 - (b) documentary evidence established in accordance with ITB

Clause 13 that the Bidder is eligible to bid and is disqualified to perform the contract if its bid is accepted;

(c) documentary evidence established in accordance with ITB Clause 14 that the goods and ancillary services to be supplied by the Bidder are eligible goods and services and conform to the bidding documents; and

(d) bid security furnished in accordance with ITB Clause 15.

10. Bid Form

10.1 The Bidder shall complete the Bid Form and the appropriate Price Schedule furnished in the bidding documents, indicating the goods to be supplied, a brief description of the goods, their country of origin, quantity, and prices.

11. Bid Prices

11.1 The Bidder shall indicate on the appropriate Price Schedule the unit prices (where applicable) and total bid price of the goods it proposes to supply under the contract.

11.2 Prices indicated on the Price Schedule shall be delivered duty paid (DDP) prices, if applicable. The price of other (incidental) services, if any, listed in the Bid Data Sheet will be entered separately.

11.3 The Bidder's separation of price components in accordance with ITB Clause 11.2 above will be solely for the purpose of facilitating the comparison of bids by the Procuring agency and will not in any way limit the Procuring agency's right to contract on any of the terms offered.

11.5 Prices quoted by the Bidder shall be fixed during the Bidder's performance of the contract and not subject to variation on any account, unless otherwise specified in the Bid Data Sheet. A bid submitted with an adjustable price quotation will be treated as nonresponsive and will be rejected, pursuant to ITB Clause 24. If, however, in accordance with the Bid Data Sheet, prices quoted by the Bidder shall be subject to adjustment during the performance of the contract, a bid submitted with a fixed price quotation will not be rejected, but the price adjustment would be treated as zero.

12. Bid Currencies

12.1 Prices shall be quoted in Pak Rupees unless otherwise specified in the Bid Data Sheet.

13. Documents Establishing Bidder's

13.1 Pursuant to ITB Clause 9, the Bidders shall furnish, as part of its bid, documents establishing the Bidder's eligibility to bid and its qualifications to perform the contract if its bid is accepted.

**Eligibility and
Qualification**

- 13.2 The documentary evidence of the Bidder's eligibility to bid shall establish to the Procuring agency's satisfaction that the Bidder, at the time of submission of its bid, is from an eligible country as defined under ITB Clause 2.
- 13.3 The documentary evidence of the Bidder's qualifications to perform the contract fits bid is accepted shall establish to the Procuring agency's satisfaction:
- (a) that, in the case of a Bidder offering to supply goods under the contract which the Bidder did not manufacture or otherwise produce, the Bidder has been duly authorized by the goods' Manufacturer or producer to supply the goods in the Procuring agency's country;
 - (b) that the Bidder has the financial, technical, and production capability necessary to perform the contract;
 - (c) that, in the case of a Bidder not doing business within the Procuring agency's country, the Bidder is or will be (if awarded the contract) represented by an Agent in that country equipped, and able to carryout the Supplier's maintenance, repair, and spare parts-stocking obligations prescribed in the Conditions of Contract and/or Technical Specifications; and
 - (d) that the Bidder meets the qualification criteria listed in the Bid Data Sheet.

**14. Documents
Establishing
Goods'
Eligibility and
Conformityto
Bidding
Documents**

- 14.1 PursuanttoITBClause9,theBiddershallfurnish,aspartofits bid, documents establishing the eligibility and conformity to the bidding documents of all goods and services which the Bidder proposes to supply under the contract.
- 14.2 The documentary evidence of the eligibility of the goods and services shall consist of a statement in the Price Schedule of the country of origin of the goods and services offered which shall be confirmed by a certificate of origin issued at the time of shipment.
- 14.3 The documentary evidence of conformity of the goods and services to the bidding documents may be in the form of literature, drawings, and data, and shall consist of:
- (a) a detailed description of the essential technical and

performance characteristics of the goods;

- (b) a list giving full particulars, including available sources and current prices of spare parts, special tools, etc. ,necessary for the proper and continuing functioning of the goods for a period to be specified in the Bid Data Sheet, following commencement of the use of the goods by the Procuring agency; and
- (c) an item-by-item commentary on the Procuring agency's Technical Specifications demonstrating substantial responsiveness of the goods and services to those specifications, or a statement of deviations and exceptions to the provisions of the Technical Specifications.

14.4 For purposes of the commentary to be furnished pursuant to ITB Clause14.3(c) above, the Bidder shall note that standards for work man ship, material, and equipment, as well as references to brand names or catalogue numbers designated by the Procuring agency in its Technical Specifications, are intended to be descriptive only and not restrictive. The Bidder may substitute alternative standards, brand names, and/or catalogue numbers in its bid, provided that it demonstrates to the Procuring agency's satisfaction that the substitutions ensure substantial equivalence to those designated in the Technical Specifications.

15. Bid Security

15.1 PursuanttoITBClause9,theBiddershallfurnish,aspartofits bid, a bid security in the amount specified in the Bid Data Sheet.

15.2 The bid security is required to protect the Procuring agency against the risk of Bidder's conduct which would warrant the security's forfeiture, pursuant to ITB Clause 15.7.

15.3 The bid security shall be in Pak. Rupees and shall be in one of the following forms:

- (a) a bank guarantee or an irrevocable letter of credit issued by a reputable bank located in the Procuring agency's country, in the form provided in the bidding documents or another form acceptable to the Procuring agency and valid for thirty (30) days beyond the validity of the bid; or
- (b) irrevocable en-cashable on-demand Bank call-deposit.

15.4 AnybidnotsecuredinaccordancewithITBClauses15.1and 15.3willberejectedbytheProcuringagencyasnonresponsive, pursuant to ITB Clause 24.

- 15.5 Unsuccessful bidders' bid security will be discharged or returned as promptly as possible but not later than thirty (30) days after the expiration of the period of bid validity prescribed by the Procuring agency pursuant to ITB Clause 16.
- 15.6 The successful Bidder's bid security will be discharged up on the Bidder signing the contract, pursuant to ITB Clause32,and furnishing the performance security,pursuanttoITBClause33.
- 15.7 The bid security may be forfeited:
- (a) if a Bidder withdraws its bid during the period of bid validity specified by the Bidder on the Bid Form; or
 - (b) in the case of a successful Bidder, if the Bidder fails:
 - (i) to sign the contract in accordance with ITB Clause 32;
- or**
- (ii) to furnish performance security in accordance with ITBClause33.

**16. Period of
Validity of
Bids**

- 16.1 Bids shall remain valid for the period specified in the Bid Data Sheet after the date of bid opening prescribed by the Procuring agency,pursuanttoITBClause19. A bid valid for a shorter period shall be rejected by the Procuring agency as nonresponsive.
- 16.2 In exceptional circumstances, the Procuring agency may solicit the Bidder's consent to an extension of the period of validity. The request and the responses thereto shall be made in writing . The bid security provided under ITBClause15shallalsobe suitably extended. A Bidder may refuse the request without forfeiting its bid security. A Bidder granting the request will not be required nor permitted to modify its bid, except as provided in the bidding document.

**17. Format and
Signing of Bid**

- 17.1 The Bidder shall prepare an original and the number of copies of the bid indicated in the Bid Data Sheet, clearly marking each "ORIGINAL BID" and "COPY OF BID," as appropriate. In the event of any discrepancy between them, the original shall govern.
17. The original and the copy or copies of the bid shall be typed or written in indelible in kind shall be signed by the Bidder or a

person or persons duly authorized to bind the Bidder to the contract. All pages of the bid, except for un-amended printed literature, shall be initialed by the person or persons signing the bid.

- 17.3 Any inter lineation erasures, or over writing shall be valid only if they are initialed by the person or persons signing the bid.
- 17.4 The Bidder shall furnish information as described in the Form of Bid on commissions or gratuities, if any, paid or to be paid to agents relating to this Bid, and to contract execution if the Bidder is awarded the contract.

D. Submission of Bids

18. Scaling and Marking of Bids

- 18.1 The Bidder shall seal the original and each copy of the bid in separate envelopes, duly marking the envelopes as "ORIGINAL" and "COPY." The envelopes shall then be sealed in an outer envelope.
- 18.2 The inner and outer envelopes shall:
- (a) be addressed to the Procuring agency at the address given in the Bid Data Sheet; and
 - (b) bear the Project name indicated in the Bid Data Sheet, the Invitation for Bids (IFB) title and number indicated in the Bid Data Sheet, and a statement: "DONOTOPEN BEFORE," to be completed with the time and the date specified in the Bid Data Sheet, pursuant to ITB Clause 2.2.
- 18.3 The inner envelopes shall also indicate the name and address of the Bidder to enable the bid to be returned unopened in case it is declared "late".
- 18.4 If the outer envelope is not sealed and marked as required by ITB Clause 18.2, the Procuring agency will assume no responsibility for the bid's misplacement or premature opening.

19. Deadline for Submission of Bids

- 19.1 Bids must be received by the Procuring agency at the address specified under ITB Clause 18.2 no later than the time and date specified in the Bid Data Sheet.
- 19.2 The Procuring agency may, at its discretion, extend this deadline for the submission of bids by amending the bidding documents in accordance with ITB Clause 7, in which case all rights and

obligations of the Procuring agency and bidders previously subject to the dead line will thereafter be subject to the deadline as extended.

- 20. Late Bids** 20.1 Any bid received by the Procuring agency after the deadline for submission of bids prescribed by the Procuring agency pursuant to ITB Clause 19 will be rejected and returned unopened to the Bidder.
- 21. Modification and Withdrawal of Bids** 21.1 The Bidder may modify or withdraw its bid after the bid's submission, provided that written notice of the modification, including substitution or withdrawal of the bids, is received by the Procuring agency prior to the deadline prescribed for submission of bids.
- 21.2 The Bidder's modification or withdrawal notice shall be prepared, sealed, marked, and dispatched in accordance with the provisions of ITB Clause 18. by a signed confirmation copy, postmarked not later than the deadline for submission of bids.
- 21.3 No bid may be modified after the deadline for submission of bids.
- 21.4 No bid may be withdrawn in the interval between the deadline for submission of bids and the expiration of the period of bid validity specified by the Bidder on the Bid Form. Withdrawal of a bid during this interval may result in the Bidder's forfeiture of its bid security, pursuant to the ITB Clause 15.7.

E. Opening and Evaluation of Bids

- 22. Opening of Bids by the Procuring agency** 22.1 The Procuring agency will open all bids in the presence of bidders' representatives who choose to attend, at the time, on the date, and at the place specified in the Bid Data Sheet. The bidders' representatives who are present shall sign a register evidencing their attendance.
- 22.2 The bidders' names, bid modifications or withdrawals, bid prices, discounts, and the presence or absence of requisite bid security and such other details as the Procuring agency, at its discretion, may consider appropriate, will be announced at the opening. No bid shall be rejected at bid opening, except for late bids, which shall be returned unopened to the Bidder pursuant to ITB Clause 20.

- 22.3 Bids (and modifications sent pursuant to ITB Clause 21.2) that are not opened and read out at bid opening shall not be considered further for evaluation, irrespective of the circumstances. Withdrawn bids will be returned unopened to the bidders.
- 22.4 The Procuring agency will prepare minutes of the bid opening.
- 23. Clarification of Bids**
- 23.1 During evaluation of the bids, the Procuring agency may, at its discretion, ask the Bidder for a clarification of its bid. The request for clarification and the response shall be in writing, and no change in the prices or substance of the bid shall be sought, offered, or permitted.
- 24. Preliminary Examination**
- 24.1 The Procuring agency will examine the bids to determine whether they are complete, whether any computational errors have been made, whether required sureties have been furnished, whether the documents have been properly signed, and whether the bids are generally in order.
- 24.2 Arithmetical errors will be rectified on the following basis. If there is a discrepancy between the unit price and the total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail, and the total price shall be corrected. If the Supplier does not accept the correction of the errors, its bid will be rejected, and its bid security may be forfeited. If there is a discrepancy between words and figures, the amount in words will prevail.
- 24.3 The Procuring agency may waive any minor in formality, non conformity, or irregularity in a bid which does not constitute a material deviation, provided such waiver does not prejudice or affect the relative ranking of any Bidder.
- 24.4 Prior to the detailed evaluation, pursuant to ITB Clause 25 the Procuring agency will determine the substantial responsiveness of each bid to the bidding documents. For purposes of these Clauses, a substantially responsive bid is one which conforms to all the terms and conditions of the bidding documents without material deviations. Deviations from, or objections or reservations to critical provisions, **such as** those concerning Bid Security (ITB Clause 15), Applicable Law (GCC Clause 30), and Taxes and Duties (GCC Clause 32), will be deemed to be a material deviation. The Procuring agency's determination of a bid's responsiveness is to be based on the contents of the bid itself without recourse to extrinsic evidence.

25. Evaluation and Comparison of Bids

24.5 If a bid is not substantially responsive, it will be rejected by the Procuring agency and may not subsequently be made responsive by the Bidder by correction of the nonconformity.

25.1 The Procuring agency will evaluate and compare the bids which have been determined to be substantially responsive, pursuant to ITB Clause 24.

25.2 The Procuring agency's evaluation of a bid will be on delivered duty paid (DDP) price inclusive of prevailing duties and will exclude any allowance for price adjustment during the period of execution of the contract, if provided in the bid.

25.3 The Procuring agency's evaluation of a bid will take into account, in addition to the bid price quoted in accordance with ITB Clause 11.2, one or more of the following factors as specified in the Bid Data Sheet, and quantified in ITB Clause 25.4:

- (a) incidental costs
- (b) delivery schedule offered in the bid;
- (c) deviations in payment schedule from that specified in the Special Conditions of Contract;
- (d) the cost of components, mandatory spare parts, and service;
- (e) the availability Procuring agency of spare part-and after-sales services for the equipment offered in the bid;
- (f) the projected operation and maintenance costs during the life of the equipment;
- (g) the performance and productivity of the equipment offered; and/or
- (h) other specific criteria indicated in the Bid Data Sheet and/or in the Technical Specifications.

25.4 For factors retained in the Bid Data Sheet pursuant to ITB 25.3, one or more of the following quantification methods will be applied, as detailed in the Bid Data Sheet:

- (a) Incidental costs provided by the bidder will be added by Procuring agency to the delivered duty paid (DDP) price at

the final destination.

(b) *Delivery schedule.*

(i) The Procuring agency requires hat the goods under the Invitation for Bids shall be delivered at the time specified in the Schedule of Requirements which will be treated as the base, a delivery "adjustment" will be calculated for bids by applying a percentage, specified in the Bid Data Sheet, of the DDP price for each week of delay beyond the base, and this will be added to the bid price for evaluation. No credit shall be given to early delivery.

or

(ii) The goods covered under this invitation are required to be delivered (shipped) within an acceptable range of weeks specified in the Schedule of Requirement. No credit will be given to earlier deliveries, and bids offering delivery beyond this range will be treated as nonresponsive. Within this acceptable range, an adjustment per week, as specified in the Bid Data Sheet, will be added for evaluation to the bid price of bids offering deliveries later than the earliest delivery period specified in the Schedule of Requirements.

or

(iii) The goods covered under this invitation are required to be delivered in partial shipments, as specified in the Schedule of Requirements. Bids offering deliveries earlier or later than the specified deliveries will be adjusted in the evaluation by adding to the bid price a fact or equal to a percentage, specified in the Bid Data Sheet, of DDP price per week of variation from the specified delivery schedule.

(c) *Deviation in payment schedule.*

(i) Bidders shall state their bid price for the payment schedule outlined in the SCC. Bids will be evaluated on the basis of this base price. Bidders are, however, permitted to state an alternative payment schedule and indicate there suction in bid price they wish to offer for such alternative payment schedule. The Procuring agency may consider the alternative payment schedule offered by the selected Bidder.

or

(ii) The SCC stipulates the payment schedule offered by

The Procuring agency. If a bid deviates from the schedule and if such deviation is considered acceptable to the Procuring agency, the bid will be evaluated by calculating interest earned for any earlier payments involved in the terms outlined in the bid as compared with those stipulated in this invitation, at the rate per annum specified in the Bid Data Sheet.

(d) *Cost of spare parts.*

(i) The list of items and quantities of major assemblies, components, and selected spare parts, likely to be required during the initial period of operation specified in the Bid Data Sheet, is annexed to the Technical Specifications. The total cost of these items, at the unit prices quoted in each bid, will be added to the bid price.

or

(ii) The Procuring agency will draw up a list of high-usage and high-value items of components and spare parts, along with estimated quantities of usage in the initial period of operation specified in the Bid Data Sheet. The total cost of these items and quantities will be computed from spare parts unit prices submitted by the Bidder and added to the bid price.

or

(iii) The Procuring agency will estimate the cost of spare parts usage in the initial period of operation specified in the Bid Data Sheet, based on information furnished by each Bidder, as well as on past experience of the Procuring agency or other procuring agencies in similar situations. Such costs shall be added to the bid price for evaluation.

(e) *Spare parts and after sales service facilities in the Procuring agency's country.*

The cost to the Procuring agency of establishing the minimum service facilities and parts inventories, as outlined in the Bid Data Sheet or else where in the bidding documents, if quoted separately, shall be added to the bid price.

(f) *Operating and maintenance costs.*

Since the operating and maintenance costs of the goods under procurement form a major part of the life cycle cost of the equipment, these costs will be evaluated in accordance with the criteria specified in the Bid Data Sheet or in the Technical Specifications.

(g) *Performance and productivity of the equipment.*

(i) Bidders shall state the guaranteed performance or efficiency in response to the Technical Specification. For each drop in the performance or efficiency below the norm of 100, an adjustment for an amount specified in the Bid Data Sheet will be added to the bid price, representing the capitalized cost of additional operating costs over the life of the plant, using the methodology specified in the Bid Data Sheet or in the Technical Specifications.

or

(ii) Goods offered shall have a minimum productivity specified under the relevant provision in the Technical Specifications to be considered responsive. Evaluation shall be based on the cost per unit of the actual productivity of goods offered in the bid, and adjustment will be added to the bid price using the methodology specified in the Bid Data Sheet or in the Technical Specifications.

(h) *Specific additional criteria indicated in the Bid Data Sheet and/or in the Technical Specifications.*

The relevant evaluation method shall be detailed in the Bid Data Sheet and/or in the Technical Specifications.

Alternative

25.4 Merit Point System:

The following merit point system for weighing evaluation factors can be applied if none of the evaluation methods listed in 25.4 above has been retained in the Bid Data Sheet. The number of points allocated to each factor shall be specified in the Bid Data Sheet.

[In the Bid Data Sheet, choose from the range of]

Evaluated price of the goods	60 to 90
Cost of common list spare parts	0 to 20
Technical features, and maintenance and operating costs	0 to 20
Availability of service and spare parts	0 to 20
Standardization	0 to 20
Total	100

The bids coring the highest number of points will be deemed to be the lowest evaluated bid.

- 26. Contacting the Procuring agency**
- 26.1 Subject to ITB Clause 23, no Bidders shall contact the Procuring agency on any matter relating to its bid, from the time of the bid opening to the time the contract is awarded. If the Bidder wishes to bring additional information to the notice of the Procuring agency, it should do so in writing.
- 26.2 Any effort by a Bidder to influence the Procuring agency in its decisions on bid evaluation, bid comparison, or contract award may result in the rejection of the Bidder's bid.

F. Award of Contract

- 27. Post-qualification**
- 27.1 In the absence of prequalification, the Procuring agency will determine to its satisfaction whether the Bidder that is selected as having submitted the lowest evaluated responsive bid is qualified to perform the contract satisfactorily, in accordance with the criteria listed in ITB Clause 13.3.
- 27.2 The determination will take in to account the Bidder's financial, technical, and production capabilities. It will be based upon an examination of the documentary evidence of the Bidder's qualifications submitted by the Bidder, pursuant to ITB Clause 13.3, as well as such other information as the Procuring agency deems necessary and appropriate.
- 27.3 An affirmative determination will be a pre requisite for award of the contract to the Bidder. A negative determination will result in rejection of the Bidder's bid, in which event the Procuring agency will proceed to the next lowest evaluated bid to make a similar determination of that Bidder's capabilities to perform satisfactorily.
- 28. Award Criteria**
- 28.1 Subject to ITB Clause 30, the Procuring agency will award the contract to the successful Bidder whose bid has been determined to be substantially responsive and has been determined to be the lowest evaluated bid, provided further that the Bidder is

- determined to be qualified to perform the contract satisfactorily.
- 29. Procuring agency's Right to Vary Quantities at Time of Award**
- 29.1 The Procuring agency reserves the right at the time of contract award to increase or decrease, by the percentage indicated in the Bid Data Sheet, the quantity of goods and services originally specified in the Schedule of Requirements without any change in unit price or other terms and conditions.
- 30. Procuring agency's Right to Accept any Bid and to Reject any or All Bids**
- 30.1 The Procuring agency reserves the right to accept or reject any bid, and to annul the bidding process and reject all bids at any time prior to contract award, without there by incurring any liability to the affected Bidder or bidders or any obligation to inform the affected Bidder or bidders of the grounds for the Procuring agency's action.
- 31. Notification of Award**
- 31.1 Prior to the expiration of the period of bid validity, the Procuring agency will notify the successful Bidder in writing by registered letter or by cable, to be confirmed in writing by registered letter, that its bid has been accepted.
- 31.2 The notification of award will constitute the formation of the Contract.
- 31.3 Upon the successful Bidder's furnishing of the performance security pursuant to ITB Clause 33, the Procuring agency will promptly notify each unsuccessful Bidder and will discharge its bid security, pursuant to ITB Clause 15.
- 32. Signing of Contract**
- 32.1 At the same time as the Procuring agency notifies the successful Bidder that its bid has been accepted, the Procuring agency will send the Bidder the Contract Form provided in the bidding documents, incorporating all agreements between the parties.
- 32.2 Within thirty (30) days of receipt of the Contract Form, the successful Bidder shall sign and date the contract and return it to
The Procuring agency.
- 33 Performance Security**
- 33.1 Within twenty(20) days of the receipt of notification of award from the Procuring agency, the successful Bidder shall furnish the performance security in accordance with the Conditions of Contract, in the Performance Security Form provided in the bidding documents, or in another form acceptable to the Procuring agency.
- 33.2 Failure of the successful Bidder to comply with the requirement of ITB Clause 32 or ITB Clause 33.1 shall constitute sufficient grounds for the annulment of the award and for feature of the bid

34. Corrupt or Fraudulent Practices

security, in which event the Procuring agency may make the award to the next lowest evaluated Bidder or call for new bids.

34.1 The Government of Sindh requires that Procuring agency's (including beneficiaries of donor agencies' loans), as well as Bidders/Suppliers/Contractors under Government-financed contracts, observe the highest standard of ethics during the procurement and execution of such contracts. In pursuance of this policy, the SPPRA, in accordance with the SPP Act, 2009 and Rules made there under:

(a) defines, for the purposes of this provision, the terms set forth below as follows:

(i) "corrupt practice" means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution; and

(ii) "fraudulent practice" means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Procuring agency, and includes collusive practice among Bidders (prior to or after bid submission) designed to establish bid prices at artificial non-competitive levels and to deprive the Procuring agency of the benefits of free and open competition;

(b) will reject a proposal for award if it determines that the Bidder recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;

(c) will declare a firm ineligible, either indefinitely or for a stated period of time, to be awarded a Government-financed contract if it at any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a Government-financed contract.

34.2 Furthermore, Bidders shall be aware of the provision stated in sub-clause 5.4 and sub-clause 24.1 of the General Conditions of Contract.

Part One - Section II.
General Conditions of Contract

Table of Clauses

1. DEFINITIONS.....	23
2. APPLICATION.....	23
3. COUNTRY OF ORIGIN.....	24
4. STANDARDS.....	Error! Bookmark not defined.
5. USE OF CONTRACT DOCUMENTS AND INFORMATION; INSPECTION AND AUDIT BY THE BANK.....	24
6. PATENT RIGHTS.....	25
7. PERFORMANCE SECURITY.....	25
8. INSPECTIONS AND TESTS.....	25
9. PACKING.....	26
10. DELIVERY AND DOCUMENTS.....	26
11. INSURANCE.....	27
12. TRANSPORTATION.....	27
13. INCIDENTAL SERVICES.....	27
14. SPARE PARTS.....	27
15. WARRANTY.....	28
16. PAYMENT.....	29
17. PRICES.....	29
18. CHANGE ORDERS.....	29
19. CONTRACT AMENDMENTS.....	30
20. ASSIGNMENT.....	30
21. SUBCONTRACTS.....	30
22. DELAYS IN THE SUPPLIER'S PERFORMANCE.....	30
23. LIQUIDATED DAMAGES.....	30
24. TERMINATION FOR DEFAULT.....	31
25. FORCE MAJEURE.....	32
26. TERMINATION FOR INSOLVENCY.....	32
27. TERMINATION FOR CONVENIENCE.....	32
28. RESOLUTION OF DISPUTES.....	33
29. GOVERNING LANGUAGE.....	33
30. APPLICABLE LAW.....	33
31. NOTICES.....	33
32. TAXES AND DUTIES.....	33

General Conditions of Contract

1. Definitions

1.1 In this Contract, the following terms shall be interpreted as indicated:

- (a) "The Contract" means the agreement entered into between the Procuring agency and the Supplier, as recorded in the Contract Form signed by the parties, including all attachments and appendices thereto and all documents incorporated by reference therein.
- (b) "The Contract Price" means the price payable to the Supplier under the Contract for the full and proper performance of its contractual obligations.
- (c) "The Goods" means all of the equipment, machinery, and/or other materials which the Supplier is required to supply to the Procuring agency under the Contract.
- (d) "The Services" means those services ancillary to the supply of the Goods, such as transportation and insurance, and any other incidental services, such as installation, commissioning, provision of technical assistance, training, and other such obligations of the Supplier covered under the Contract.
- (e) "GCC" means the General Conditions of Contract contained in this section.
- (f) "SCC" means the Special Conditions of Contract.
- (g) "The Procuring agency" means the organization purchasing the Goods, as named in SCC.
- (h) "The Procuring agency's country" is the country named in SCC.
- (i) "The Supplier" means the individual or firm supplying the Goods and Services under this Contract.
- (j) "The Project Site," where applicable, means the place or places named in SCC.
- (k) "Day" means calendar day.

2. Application

2.1 These General Conditions shall apply to the extent that they are

not superseded by provisions of other parts of the Contract.

3. Country of Origin

3.1 All Goods and Services supplied under the Contract shall have their origin in the countries and territories eligible under the rules and further elaborated in the SCC.

3.2 For purposes of this Clause, "origin" means the place where the Goods were mined, grown, or produced, or from which the Services are supplied. Goods are produced when, through manufacturing, processing, or substantial and major assembly of components, a commercially recognized new product results that is substantially different in basic characteristics or in purpose or utility from its components.

3.3 The origin of Goods and Services is distinct from the nationality of the Supplier.

T

4.1 The Goods supplied under this Contract shall conform to the standards mentioned in the Technical Specifications, and, when no applicable standard is mentioned, to the authoritative standards appropriate to the Goods' country of origin. Such standards shall be the latest issued by the concerned institution.

5. Use of Contract Documents and Information; Inspection and Audit by the Government

5.1 The Supplier shall not, without the Procuring agency's prior written consent, disclose the Contract, or any provision thereof, or any specification, plan, drawing, pattern, sample, or information furnished by or on behalf of the Procuring agency in connection therewith, to any person other than a person employed by the Supplier in the performance of the Contract. Disclosure to any such employed person shall be made in confidence and shall extend only so far as may be necessary for purposes of such performance.

5.2 The Supplier shall not, without the Procuring agency's prior written consent, make use of any document or information enumerated in GCC Clause 5.1 except for purposes of performing the Contract.

5.3 Any document, other than the Contract itself, enumerated in GCC Clause 5.1 shall remain the property of the Procuring agency and shall be returned (all copies) to the Procuring agency on completion of the Supplier's performance under the Contract if so required by the Procuring agency.

5.4 The Supplier shall permit the Procuring agency to inspect the Supplier's accounts and records relating to the performance of the Supplier and to have them audited by auditors appointed by the procuring agency, if so required.

6. Patent Rights

6.1 The Supplier shall indemnify the Procuring agency against all third-party claims of infringement of patent, trademark, or industrial design rights arising from use of the Goods or any part thereof in the Procuring agency's country.

7. Performance Security

7.1 Within twenty(20) days of receipt of the notification of Contract award, the successful Bidder shall furnish to the Procuring agency the performance security in the amount specified in SCC.

7.2 The proceeds of the performance security shall be payable to the Procuring agency as compensation for any loss resulting from the Supplier's failure to complete its obligations under the Contract.

7.3 The performance security shall be denominated in the currency of the Contract acceptable to the Procuring agency and shall be in one of the following forms:

(a) a bank guarantee or an irrevocable letter of credit issued by a reputable bank located in the Procuring agency's country, in the form provided in the bidding documents or another form acceptable to the Procuring agency; or

(b) a cashier's or certified check.

7.4 The performance security will be discharged by the Procuring agency and returned to the Supplier not later than thirty (30)days following the date of completion of the Supplier's performance obligations under the Contract, including any warranty obligations, unless specified otherwise in SCC.

8. Inspections and Tests

8.1 The Procuring agency or its representative shall have the right to inspect and/or test the Goods to confirm their conformity to the Contract specification at no extra cost to the Procuring agency. SCC and the Technical Specifications shall specify what inspections and tests the Procuring agency requires and where they are to be conducted. The Procuring agency shall notify the Supplier in writing, in a timely manner, of the identity of any representatives retained for these purposes.

8.2 The inspections and tests may be conducted on the premises of the Supplier or its subcontractor(s), at point of delivery, and/or at

The Goods' final destination. If conducted on the premises of the Supplier or its sub contractor(s), all reasonable facilities and assistance, including access to drawings and production data, shall be furnished to the inspectors at no charge to the Procuring agency.

- 8.3 Should any inspected or tested Goods fail to conform to the Specifications, the Procuring agency may reject the Goods, and the Supplier shall either replace the rejected Goods or make alterations necessary to meet specification requirements free of cost to the Procuring agency.
- 8.4 The Procuring agency's right to inspect, test and, where necessary, reject the Goods after the Goods' arrival in the Procuring agency's country shall in no way be limited or waived by reason of the Goods having previously been inspected, tested, and passed by the Procuring agency or its representative prior to the Goods' shipment from the country of origin.
- 8.5 Nothing in GCC Clause 8 shall in any way release the Supplier from any warranty or other obligations under this Contract.

9. Packing

- 9.1 The Supplier shall provide such packing of the Goods as is required to prevent their damage or deterioration during transit to their final destination, as indicated in the Contract. The packing shall be sufficient to withstand, without limitation, rough handling during transit and exposure to extreme temperatures, salt and precipitation during transit, and open storage. Packing case size and weights shall take into consideration, where appropriate, the remoteness of the Goods' final destination and the absence of heavy handling facilities at all points in transit.
- 9.2 The packing, marking, and documentation within and outside the packages shall comply strictly with such special requirements as shall be expressly provided for in the Contract, including additional requirements, if any, specified in SCC, and in any subsequent instructions ordered by the Procuring agency.

10. Delivery and Documents

- 10.1 Delivery of the Goods shall be made by the Supplier in accordance with the terms specified in the Schedule of Requirements. The details of shipping and/or other documents to be furnished by the Supplier are specified in SCC.
- 10.2 Documents to be submitted by the Supplier are specified in SCC.

11. Insurance

11.1 The Goods supplied under the Contract shall be delivered duty paid(DDP) under which risk is transferred to the buyer after having been delivered, hence insurance coverage is sellers responsibility.

12. Transportation

12.1 The Supplier is required under the Contract to transport the Goods to a specified place of destination within the Procuring agency's country, transport to such place of destination in the Procuring agency's country, including insurance and storage, as shall be specified in the Contract, shall bear ranged by the Supplier, and related costs shall be included in the Contract Price.

13. Incidental Services

13.1 The Supplier may be required to provide any or all of the following services, including additional services, if any, specified in SCC:

- (a) performance or supervision of on-site assembly and/or start-up of the supplied Goods;
- (b) furnishing of tools required for assembly and/or maintenance of the supplied Goods;
- (c) furnishing of a detailed operations and maintenance manual for each appropriate unit of the supplied Goods;
- (d) performance or supervision or maintenance and/or repair of the supplied Goods, for a period of time agreed by the parties, provided that this service shall not relieve the Supplier of any warranty obligations under this Contract; and
- (e) training of the Procuring agency's personnel, at the Supplier's plant and/or on-site, in assembly, start-up, operation, maintenance, and/or repair of the supplied Goods.

13.2 Prices charged by the Supplier for incidental services, if not included in the Contract Price for the Goods, shall be agreed upon in advance by the parties and shall not exceed the prevailing rates charged for other parties by the Supplier for similar services.

14. Spare Parts

14.1 As specified in SCC, the Supplier may be required to provide any or all of the following materials, notifications, and information pertaining to spare parts manufactured or distributed by the Supplier:

- (a) such spare parts as the Procuring agency may elect to purchase from the Supplier, provided that this election shall not relieve the Supplier of any warranty obligations under the Contract; and
- (b) in the event of termination of production of the spare parts:
 - (i) advance notification to the Procuring agency of the pending termination, in sufficient time to permit the Procuring agency to procure needed requirements; and
 - (ii) following such termination, furnishing at no cost to the Procuring agency, the blueprints, drawings, and specifications of the spare parts, if requested.

15. Warranty

- 15.1 The Supplier warrants that the Goods supplied under the Contract are new, unused, of the most recent or current models, and that they incorporate all recent improvements in design and materials unless provided otherwise in the Contract. The Supplier further warrants that all Goods supplied under this Contract shall have no defect, arising from design, materials, or workmanship (except when the design and/or material is required by the Procuring agency's specifications) or from any act or omission of the Supplier, that may develop under normal use of the supplied Goods in the conditions prevailing in the country of final destination.
- 15.2 This warranty shall remain valid for twelve(12)months after the Goods, or any portion thereof as the case may be, have been delivered to and accepted at the final destination indicated in the Contract, or for eighteen (18) months after the date of shipment from the port or place of loading in the source country, whichever period concludes earlier, unless specified otherwise in SCC.
- 15.3 The Procuring agency shall promptly notify the Supplier in writing of any claims arising under this warranty.
- 15.4 Upon receipt of such notice, the Supplier shall, within the period specified in SCC and with all reasonable speed, repair or replace the defective Goods or parts thereof, without costs to the Procuring agency.
- 15.5 If the Supplier, having been notified, fails to remedy the defect(s)

Within the period specified in SCC, within are as on able period, the Procuring agency may proceed to take such remedial action as may be necessary, at the Supplier's risk and expense and without prejudice to any other rights which the Procuring agency may have against the Supplier under the Contract.

16. Payment

16.1 The method and conditions of payment to be made to the Supplier under this Contract shall be specified in SCC.

16.2 The Supplier's request(s) for payment shall be made to the Procuring agency in writing, accompanied by an invoice describing, as appropriate, the Goods delivered and Services performed, and by documents submitted pursuant to GCC Clause 10, and upon fulfillment of other obligations stipulated in the Contract.

16.3 Payments shall be made promptly by the Procuring agency, but in no case later than sixty (60) days after submission of an invoice or claim by the Supplier.

16.4 The currency of payment is Pak. Rupees.

17. Prices

17.1 Prices charged by the Supplier for Goods delivered and Services performed under the Contract shall not vary from the prices quoted by the Supplier in its bid, with the exception of any price adjustments authorized in SCC or in the Procuring agency's request for bid validity extension, as the case may be.

18. Change Orders

18.1 The Procuring agency may at any time, by a written order given to the Supplier pursuant to GCC Clause 31, make changes within the general scope of the Contract in any one or more of the following:

- (a) drawings, designs, or specifications, where Goods to be furnished under the Contract are to be specifically manufactured for the Procuring agency;
- (b) the method of shipment or packing;
- (c) the place of delivery; and/or
- (d) the Services to be provided by the Supplier.

18.2 If any such change causes an increase or decrease in the cost of, or the time required for, the Supplier's performance of any provisions under the Contract, an equitable adjustment shall be

Made in the Contract Price or delivery schedule, or both, and the Contract shall accordingly be amended. Any claims by the Supplier for adjustment under this clause must be asserted within thirty(30) days from the date of the Supplier's receipt of the Procuring agency's change order.

- 19. Contract Amendments** 19.1 Subject to GCC Clause 18, no variation in or modification of the terms of the Contract shall be made except by written amendment signed by the parties.
- 20. Assignment** 20.1 The Supplier shall not assign, in whole or in part, its obligations to perform under this Contract, except with the Procuring agency's prior written consent.
- 21. Subcontracts** 21.1 The Supplier shall notify the Procuring agency in writing of all subcontracts awarded under this Contract if not already specified in the bid. Such notification, in the original bid or later, shall not relieve the Supplier from any liability or obligation under the Contract.
- 21.2 Sub contracts must comply with the provisions of GCC Clause 3.
- 22. Delays in the Supplier's Performance** 22.1 Delivery of the Goods and performance of Services shall be made by the Supplier in accordance with the time schedule prescribed by the Procuring agency in the Schedule of Requirements.
- 22.2 If at any time during performance of the Contract, the Supplier or its subcontractor(s) should encounter conditions impeding timely delivery of the Goods and performance of Services, the Supplier shall promptly notify the Procuring agency in writing of the fact of the delay, its likely duration and its cause(s). As soon as practicable after receipt of the Supplier's notice, the Procuring agency shall evaluate the situation and may at its discretion extend the Supplier's time for performance, with or without liquidated damages, in which case the extension shall be ratified by the parties by amendment of Contract.
- 22.3 Except as provided under GCC Clause 25, a delay by the Supplier in the performance of its delivery obligations shall render the Supplier liable to the imposition of liquidated damages pursuant to GCC Clause 23, unless an extension of time is agreed upon pursuant to GCC Clause 22.2 without the application of liquidated damages.
- 23. Liquidated** 23.1 Subject to GCC Clause 25, if the Supplier fails to deliver any or

Damages

all of the Goods or to perform the Services within the period(s) specified in the Contract, the Procuring agency shall, without prejudice to its other remedies under the Contract, deduct from the Contract Price, as liquidated damages, a sum equivalent to the percentage specified in SCC of the delivered price of the delayed Goods or unperformed Services for each week or part thereof of delay until actual delivery or performance, up to a maximum deduction of the percentage specified in SCC. Once the maximum is reached, the Procuring agency may consider termination of the Contract pursuant to GCC Clause 24.

24. Termination for Default

24.1 The Procuring agency, without prejudice to any other remedy for breach of Contract, by written notice of default sent to the Supplier, may terminate this Contract in whole or in part:

- (a) if the Supplier fails to deliver any or all of the Goods within the period(s) specified in the Contract, or within any extension thereof granted by the Procuring agency pursuant to GCC Clause 22; or
- (b) if the Supplier fails to perform any other obligation(s) under the Contract.
- (c) if the Supplier, in the judgment of the Procuring agency has engaged in corrupt or fraudulent practices in competing for or in executing the Contract.

For the purpose of this clause:

“corrupt practice” means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution.

“fraudulent practice” means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Borrower, and includes collusive practice among Bidders (prior to or after bid submission) designed to establish bid prices at artificial non-competitive levels and to deprive the Borrower of the benefits of free and open competition.

24.2 In the event the Procuring agency terminates the Contract in whole or in part pursuant to GCC Clause 24.1, the Procuring agency may procure, upon such terms and in such manner as it deems appropriate, Goods or Services similar to those

undelivered, and the Supplier shall be liable to the Procuring agency for any excess costs for such similar Goods or Services. However, the Supplier shall continue performance of the Contract to the extent not terminated.

- 25. Force Majeure**
- 25.1 Notwithstanding the provisions of GCC Clauses 22, 23, and 24, the Supplier shall not be liable for failure of its performance security, liquidated damages, or termination for default if and to the extent that its delay in performance or other failure to perform its obligations under the Contract is the result of an event of Force Majeure.
- 25.2 For purposes of this clause, "Force Majeure" means an event beyond the control of the Supplier and not involving the Supplier's fault or negligence and not foreseeable. Such events may include, but are not restricted to, acts of the Procuring agency in its sovereign capacity, wars or revolutions, fires, floods, epidemics, quarantine restrictions, and freight embargoes.
- 25.3 If a Force Majeure situation arises, the Supplier shall promptly notify the Procuring agency in writing of such condition and the cause thereof. Unless otherwise directed by the Procuring agency in writing, the Supplier shall continue to perform its obligations under the Contract as far as is reasonably practical, and shall seek all reasonable alternative means for performance not prevented by the Force Majeure event.
- 26. Termination for Insolvency**
- 26.1 The Procuring agency may at any time terminate the Contract by giving written notice to the Supplier if the Supplier becomes bankrupt or otherwise insolvent. In this event, termination will be without compensation to the Supplier, provided that such termination will not prejudice or affect any right of action or remedy which has accrued or will accrue thereafter to the Procuring agency.
- 27. Termination for Convenience**
- 27.1 The Procuring agency, by written notice sent to the Supplier, may terminate the Contract, in whole or in part, at any time for its convenience. The notice of termination shall specify that termination is for the Procuring agency's convenience, the extent to which performance of the Supplier under the Contract is terminated, and the date upon which such termination becomes effective.
- 27.2 The Goods that are complete and ready for shipment within thirty (30) days after the Supplier's receipt of notice of termination shall be accepted by the Procuring agency at the

Contract terms and prices. For the remaining Goods, the Procuring agency may elect:

- (a) to have any portion completed and delivered at the Contract terms and prices; and/or
- (b) to cancel the remainder and pay to the Supplier an agreed amount for partially completed Goods and Services and for materials and parts previously procured by the Supplier.

28. Resolution of Disputes

28.1 The Procuring agency and the Supplier shall make every effort to resolve amicably by direct informal negotiation any disagreement or dispute arising between them under or in connection with the Contract.

28.2 If, after thirty (30) days from the commencement of such informal negotiations, the Procuring agency and the Supplier have been unable to resolve amicably a Contract dispute, either party may require that the dispute be referred for resolution to the formal mechanisms specified in SCC. These mechanisms may include, but are not restricted to, conciliation mediated by a third party, adjudication in an agreed manner and/or arbitration.

29. Governing Language

29.1 The Contract shall be written in the language specified in SCC. Subject to GCC Clause 30, the version of the Contract written in the specified language shall govern its interpretation. All correspondence and other documents pertaining to the Contract which are exchanged by the parties shall be written in the same language.

30. Applicable Law

30.1 The Contract shall be interpreted in accordance with the laws of the Procuring agency's country, unless otherwise specified in SCC.

31. Notices

31.1 Any notice given by one party to the other pursuant to this Contract shall be sent to the other party in writing or by cable, telex, or facsimile and confirmed in writing to the other party's address specified in SCC.

31.2 A notice shall be effective when delivered or on the notice's effective date, whichever is later.

32. Taxes and Duties

32.1 Suppliers shall be entirely responsible for all taxes, duties, license fees, etc., incurred until delivery of the contracted Goods to the Procuring agency.

Notes on the Instructions to Bidders

This section of the bidding documents provides the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring agency. It also provides information on bid submission, opening, and evaluation, and on the award of contract.

Part One Section I contains provisions that are to be used unchanged. Part Two Section II consists of provisions that supplement, amend, or specify in detail information or requirements included in Part One Section I and which are specific to each procurement.

Matters governing the performance of the Supplier, payments under the contract, or matters affecting the risks, rights, and obligations of the parties under the contract are not normally included in this section, but rather under Part one Section II, General Conditions of Contract, and / or Part Two Section III, Special Conditions of Contract. If duplication of a subject is inevitable in the other sections of the document prepared by the Procuring agency, care must be exercised to avoid contradictions between clauses dealing with the same matter.

These Instructions to Bidders will not be part of the contract.

Notes on the General Conditions of Contract

The General Conditions of Contract in Part One Section II, read in conjunction with the Special Conditions of Contract in Part Two Section III and other documents listed therein, should be a complete document expressing all the rights and obligations of the parties.

The General Conditions of Contract herein shall not be altered. Any changes and complementary information, which may be needed, shall be introduced only through the Special Conditions of Contract in Part Two Section III.