



OFFICE OF THE

EXECUTIVE ENGINEER, PROVINCIAL HIGHWAY DIVISION LARKANO.

Phone No. 074-4058111

No. TC/G-55 / 543 / of 2018

Larkano dated: 05-03-2018

NOTICE INVITING TENDERS.

Tenders are invited from interested persons / suppliers / contracts / companies / firms on standard Bidding Documents Forms for Procurement of the following work as per SPPRA Rules 2010.

Sr. No.	Name of Scheme	Estimated Cost	Bid Security 4% (in Rupees)	Tender Fee	Time Allowed for completion
LIST ATTACHED SEPRATELY					

TERMS & CONDITIONS

- The intending participants can purchase the blank bid documents on payment of tender fee not refundable from this office for each work from the date of publication upto 26.03.2018 @ 1.00 P.M.
- The tender will be received back on 27.03.2018 upto 01.00 P.M and will be opened on same date 27.03.2018 @ 2.00 P.M in the presence of intending contractors are their authorized representatives.
- Eligibility condition for intending participants are as under:-
 - Registration with Pakistan Engineering Council in the relevant field of specialization of work and also the renewal of 2017.
 - Bio-data of Engineers & Technical staff working with the firm alongwith Engineering Qualification Certificate.
 - Documentary evidence for works executed / works in progress and certificate of satisfactory completion of works of similar nature during last 3 years.
 - List of work in progress, indicating cost of each work and copy of letter of award of work.
 - List of machinery and equipment available with documentary evidence of its ownership, as required under chapter 4.2 (j) as SPPRA, certificate bank showing credit worthiness alongwith Bank statement.
 - No conditional or telegraphic tender will be entertained.
 - In case the tenders remain un-responded, the same will again be issued and opened in the presence of the committee on the following date.

Sr. No.	Issue of Blank Tenders	Received of Tender	Opened of Tender
1	2	3	4
	28.03.2018 TO 16.04.2018	17.04.2018 @ 100 P.M	17.04.2018 @ 2.00 P.M

- All the bids or proposal can be rejected at any time prior to the acceptance of the bid or proposals as per SPPRA Rules.
- Pakistan Engineering Council license is not mandatory for the works upto 4.00 million.
 - Registration with Income Tax Department (NTN Certificates), Income returns should be provided and copy of C.N.I.C.
 - The bidder should have Registrations with the Sindh Revenue Board.
 - Undertaking on Affidavit that the firm is not involved in any litigation or had not abandoned any work in the Department.
 - The bidders should submit earnest money as showing against each work in shape of Call Deposit prepared from any scheduled bank in favour of the undersigned.
 - Affidavits to the effect that the firm / contractor have not been blacklisted previously by any executing agency.
 - Affidavits to the effect that all documents / particulars / information furnished are true and correct. In case of Bogus / Tempered or false information / Certificate is provided by the company / firm shall be liable to be black listed at any stage.
 - In case of firm, list of partners / partnership deed, giving full particulars of directors / proprietors or other connected alongwith power of attorney. In case of being sole proprietors, such undertaking on affidavit be furnished.


Contd: P/2

SPPRA INWARD DIARY

NO : 6785


DATED 08-03-2018

- Details of owner alongwith CNIC on Judicial Stamp paper, A representative should have authority on Judicial Stamp Paper from owner and participation.
13. Call Deposit (Earnest money) will be refunded to the unsuccessful bidder(s) after issuance of Letter of Award to the successful Bidder.
 14. The tender should be submitted alongwith the above required documentation / information, if such lacks the tender will not be consider by the procurement committee and no excuse will be consider even if the work is in hand for execution .
 15. Bid Documents are available on deposition of non refundable price of Rs:3000/=
 16. Bid validity 90 days.
 17. In case of Public Holiday or the undersigned remains out of head quarter, the tenders will be opened on the next working day.


Executive Engineer,
Provincial Highways Division
Larkano


Copy forwarded with compliments to the:-

- ❖ Chief Engineer, Highways Department Sukkur, for favour of information please.
- ❖ Superintending Engineer, Provincial highways Circle Larkano, He is requested to kindly accord necessary approval of the N.I.T.
- ❖ Director Information Public Relation Department (Advertisement) alongwith spare copies of advertisement for publication in leading news papers.
- ❖ Secretary I.T Department Government of Sindh, Sindh Secretariat Building No.6, 1st: floor Karachi.
- ❖ Director (C.B) Sindh Public Procurement Regulatory Authority Government of Sindh Block 8-A, Sindh Secretariat 4-B Court road Karachi for favour of information.
- ❖ Assistant Engineers Provincial Highways Sub-Division Larkano / Shahdadkot for information and immediately they are requested to submit the estimate and schedule "B" of the works immediately for taken further necessary action.
- ❖ Divisional Head Draftsman / Head Clerk for information.
- ❖ Copy for NOTICE BOARD.


Executive Engineer,
Provincial Highways Division
Larkano

LIST OF WORKS

S.No:	Name of work	Estimate Cost (Million)	Earnest Money 5% (Million).	Tender fee (Rs.)	Time allowed for completion	Requirement
1	2	3	4	5	6	7
01/12	M&R of Re-Construction of 20' Rft: Bridge 01 No. at village Shadan Jato.	0.876	0.044	1,500	30-Jun-18	
02/12	M&R of Re-Construction of 20' Rft: Bridge 01 No. at village Taggar mile: 0/0-0/6.	0.873	0.044	1,500	30-Jun-18	
03/12	M&R of Re-Construction of 20' Rft: Bridge 01 No. at village Ali Jatoi mile: 0/0-0/5.	0.873	0.044	1,500	30-Jun-18	
04/12	M&R of Re-Construction of 10' Rft: Bridge 02 Nos. at village Mubarak Shaikh to Qurban Shaikh mile: 0/0-0/6.	0.760	0.038	1,500	30-Jun-18	
05/12	M&R of Re-Construction of 3' Ft: Span Culverts 02 Nos. along road from Bakrani Station to Qaim Khan Mangan mile: 0/0-	0.490	0.025	750	30-Jun-18	
06/12	M&R of Re-Construction of 10' Rft: Bridge 01 No. at village Bangul Abro Shaman Abro mile: 0/0-0/3.	0.381	0.019	750	30-Jun-18	
07/12	M&R of Re-Construction of 10' Rft: Bridge 01 No. at village Abro to Pathan Abro mile: 0/0-0/4.	0.380	0.019	750	30-Jun-18	
08/12	M&R of Re-Construction of 10' Rft: Bridge 01 No. at village Nooral Abro to Yar Mohammad Abro mile: 0/0-0/5.	0.380	0.019	750	30-Jun-18	
09/12	M&R Repair of 7' Rft: Bridge over Leghari minor from Jeand Jarwar to Shahdadt Jarwar road @ Leghari village	0.646	0.032	1,500	30-Jun-18	
10/12	M&R Construction 3' Rft: span culver @ Imam Bux Jamali to Mohammad Khan Bhutto (Taluka Kamber)	0.250	0.013	500	30-Jun-18	
11/12	M&R Re-decking of 10' Rft: Bridge slab along Punah Shakh @ point Warah City. (Taluka Warah)	0.241	0.012	500	30-Jun-18	
12/12	M&R / Repair of Governmetn Jeep No. GS 4789	0.050	0.003	500	30-Jun-18	
13/13	M&R / Repair of Governmetn Jeep No. GS 3282	0.050	0.003	500	30-Jun-18	


 Executive Engineer
 Provincial Highways Division
 Larkano

S:\S&R\WORKS\FORMS\01-18



Karachi, dated 27th June, 2013.

NOTIFICATION

No. E&A(W&S)3-9/91/2013: With the approval of competent authority, Procurement Committee in terms of Rule-7 of Sindh Public Procurement Rules-2010, is hereby constituted for procurement of "Goods/Works" in the office of Executive Engineer, Provincial Highways Division, Larkano, excluding procurement involving foreign exchange with the following composition:-

- | | | |
|------|--|----------|
| i) | Executive Engineer,
Provincial Highways Division,
Larkano. | Chairman |
| ii) | Executive Engineer,
Public Health Engineering Division,
Larkano. | Member |
| iii) | Assistant Engineer,
Provincial Highways Sub-Division,
Larkano. | Member |

2. The Functions & Responsibilities of the Committee, in term of Rule-8 of SPPR-2010, shall be as under:

- Preparing of bidding documents.
- Carrying out Technical as well as Financial Evaluation of the bids.
- Preparing Evaluation report as provided in Rule-45;
- Making recommendation for the award of contract to the competent authority; and
- Perform any other function ancillary and incidental to the above.

QAZI SHAHID PERVEZ
SECRETARY TO GOVT. OF SINDH

No. E&A(W&S)3-9/91-2013

Karachi dated the 27th June, 2013.

A copy is forwarded for information to:-

- The Accountant General, Sindh, Karachi.
- The Secretary to Govt. of Sindh, Public Health Engineering Department, Karachi.
- The Managing Director, SPIPRA, Karachi.
- The Chief Engineer (Highways), Sukkur.
- The Superintending Engineer, Provincial Highways Circle, Larkano.
- The Deputy Director, PM&E Cell, W&SD.
- P.A to Addl. Secretary (Tech.), W&SD.
- P.A to Dy. Secretary (Tech.), W&SD.
- The Chairman / Members of the Committee.
- Notification file.

M. Zakir
(MUHAMMAD ZAKIR)
SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH

1264
03-0713



GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT

Karachi, dated the 22nd May, 2014.

NOTIFICATION

No.E&A(W&S)3-9/91(PT-V): With the approval of Competent Authority, a Committee with the following composition, in terms of Rule-31 of Sindh Public Procurement Rules-2010, is hereby constituted in the Works & Services Department for redressal of grievances and settlement of disputes, if any, arises between procuring agency and bidders in the Region of Chief Engineer (Highways), Sukkur:-

- | | | |
|------|--|----------|
| i) | Chief Engineer (Highways),
Sukkur. | Chairman |
| ii) | Mr. Abdullah Memon,
Team Leader,
Flood Emergency Reconstruction Project,
ACC Consultants Private Limited,
Islamabad. | Member |
| iii) | District Accounts Officer,
Sukkur. | Member |

2. The Functions & Responsibilities of the Committee will be same as specified in Rules-31(4) and (5) of Sindh Public Procurement Rules-2010

QAZI SHAHID PERVEZ
SECRETARY TO GOVT. OF SINDH

No.E&A(W&S)3-9/91(PT-V):

Karachi dated the May, 2014.

A copy is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Managing Director, SPPRA, Karachi.
3. The Chief Engineer (Highways), Sukkur.
4. The Deputy Secretary (Staff) to Chief Secretary, Sindh, Karachi.
5. The Chairman / Members of the Committee
6. The Deputy Director (Monitoring), PM&E Cell, W&SD.
7. P.S to Secretary, W&S Department, Govt. of Sindh, Karachi.
8. The District Accounts Officer, Hyderabad.
9. Notification file.

SA

D. Hady

22/05/2014

SECTION OFFICER (GENERAL)
SECRETARY TO GOVT. OF SINDH

REVISED ANNUAL PROCUREMENT PLAN 2017-18.

PROVINCIAL HIGHWAYS DIVISION LARKANO

Sr. Nos.	Description of Procurement	Quantity (Where applicable)	Estimated unit cost (Where applicable Millions)	Funds allocated.	Scope of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1 st : Quarter	2 nd : Quarter	3 rd : Quarter	4 th : Quarter	
1	2	3	4	5	6	7	8	9	10	11	12
1	Improvement of road from Jumo Agham to Wassayo Bhutto mile: 0/0-12/0	-	210.000	52.500	2709	National complete bidding among PEC Registered Bidders.	-	-	-	-	-
2	Widening / Reconditioning of road from Larkana Airport road from Hatti to Rasheed Wagan via Dargah Mashori Shareef Taluka Bakrani mile: 0/0-5/0 (8.00 Kms.).	-	110.000	27.500	2720	--do--	-	-	-	-	-
3	Widening / Reconditioning of road form Moen-Jo-Daro road to Veehar via Karani (13.40 Kms.).	-	145.000	36.250	2721	--do--	-	-	-	-	-
4	Improvement of road from Saidudero road to Peer Wazeer Ali Shah Graveyard via village Abdul Qadir Pittafi (3.20 Kms.).	-	55.000	13.750	2723	--do--	-	-	-	-	-
5	Construction of road from Larkana Kamber road @ point Railway Phatak to connect Kamber Waggan road mile: 0/0-3/5 (5.83 Kms.)	-	348.198	87.500	2909	--do--	-	-	-	-	-

Sr. Nos.	Description of Procurement	Quantity (Where applicable)	Estimated unit cost (Where applicable Millions)	Funds allocated.	Scope of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1 st : Quarter	2 nd : Quarter	3 rd : Quarter	4 th : Quarter	
1	2	3	4	5	6	7	8	9	10	11	12
6	Widening / Reconditioning of road from Public Scholl Shahddkot to Dost Ali Banglow mile: 1/5-12/0 (16.69 Kms) i/c (76' Rft: Pre-Stressed Bridge).	-	313.848	74.589	2689	National complete bidding among PEC Registered Bidders.	-	-	-	-	-
7	Widening / Reconditioning of road from Mirokhan to Ratodero Shahdadkot Motorway via Village Shah-Jo-Lao road mile: 0/0-9/0 (14.48 Kms.).	-	247.174	63.101	2688	--do--	-	-	-	-	-
8	Reconditioning of road from Thouf Chosul to Bhand Chowk mile: 0/0-10/0 (16.09 Kms.).	-	225.620	53.219	2691	--do--	-	-	-	-	-
9	Widening / Reconditioning of road from Kamber to Dost Ali Banglow mile: 0/0-9/3 (15.08 Kms.).	-	213.556	83.383	2693	--do--	-	-	-	-	-
10	Reconditioning of road from Shahdadkot to Bago Daro mile: 0/0-15/0 (24.14 Kms.).	-	210.804	49.810	2690	--do--	-	-	-	-	-
11	Widening / Reconditioning of road from Nasirabad to Gaji Khuhawar mile: 0/3-6/4 (i/c M.Structure).	-	181.056	44.134	2686	--do--	-	-	-	-	-
12	Widening / Reconditioning of road form Dera to Bاده road mile: 0/0-6/0 (i/c M.structure).	-	165.475	47.117	2694	--do--	-	-	-	-	-
13	Reconditioning of road from Arzi Bhutto to Mohammad via Bux Sario, Hyder Chandio mile: 0/0-8/7 (14.20 Kms.).	-	124.696	29.383	2692	--do--	-	-	-	-	-


Sr. Nos.	Description of Procurement	Quantity (Where applicable)	Estimated unit cost (Where applicable Millions)	Funds allocated.	Scope of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1 st : Quarter	2 nd : Quarter	3 rd : Quarter	4 th : Quarter	
1	2	3	4	5	6	7	8	9	10	11	12
14	Reconditionin of road Larkana Kamber road to village Rawal Miyani via Aabri i/c Construction of Approach road (from Graveyar) to GGPS Aabri mile: 0/0-3/5 (5.83 Kms.) i/c (115' Rft:) Pre-Stress Bridge).	-	97.781	23.650	2682	National complete bidding among PEC Registered Bidders.	-	-	-	-	-
15	Reconditioning of road from Kamber to Khairpur Juso N-55 @ point 9/0 via village Sharifani mile: 0/0-5/5 (9.05 Kms.).	-	80.190	21.885	2687	--do--	-	-	-	-	-
16	Construction of Bridge at Dhamraho Branch of Rice Canal village Juma Khan Mugheri, Mubarak Mugheri & Mola Bux Mugheri (i/c approach & M. Structure).	-	58.414	15.000	2937	--do--	-	-	-	-	-
17	M&R Reconditioning of road from Larkana Moen-Jo-Daro road to New Gud via village Kandar Sehro 5.00 Kms. (2" thick Asphalt)	-	44.758	44.758	M&R	--do--	-	-	-	-	-
18	M&R Reconditioning of road from Ratodero Kohri Regulator to village Bosan mile: 0/0-2/7.	-	40.000	40.000	M&R	--do--	-	-	-	-	-
19	M&R of road of Both Sides of Railway Over Head Bridge from Attaturk Tower to Subhanallah Hotel mile: 0/0-0/7 + 327 = 1.50 Kms	-	25.000	25.000	M&R	--do--	-	-	-	-	-

Sr. Nos.	Description of Procurement	Quantity (Where applicable)	Estimated unit cost (Where applicable Millions)	Funds allocated.	Scope of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1 st : Quarter	2 nd : Quarter	3 rd : Quarter	4 th : Quarter	
1	2	3	4	5	6	7	8	9	10	11	12
20	M&R of road from I.P side of Rice Canal road to Nazar Mohalla road mile: 0/0-0/2 + 379 Ft.:	-	16.399	16.399	M&R	National complete bidding among PEC Registered Bidders.	-	-	-	-	-
21	M&R W/R of road from Larkana Khairpur road to Doulat Khokhar = 3.60 Kms. i/c M.Structure.	-	10.000	10.000	M&R	--do--	-	-	-	-	-
22	M&R Reconditioning of road from Bakrani by pass to Bakrani Tower via Bakrani city.	-	10.000	10.000	M&R	--do--	-	-	-	-	-
23	M&R Reconditioning of road from Radhan road to Wadha Bridge village mile: 0/0-1/3+330'	-	10.000	10.000	M&R	--do--	-	-	-	-	-
24	M&R Reconditioning of road from Larkana Radhan road to Seehar Station via village Seehar mile: 0/0-0/7.	-	10.000	10.000	M&R	--do--	-	-	-	-	-
25	M&R of W/R of road from Main Airport road to village Fazal Muhammad Abro =1.00 Kms. Taluka Bakirani.	-	10.000	10.000	M&R	--do--	-	-	-	-	-
26	M&R Reconditioning of road form Akil road to Sher Mohammad Jamali mile: 0/0-0/6 =1.20 Kms.	-	5.000	5.000	M&R	--do--	-	-	-	-	-
27	M&R of road from Lalu Raunk to Warah mile: 3/7-7/7. (Taluka Warah).	-	67.307	67.307	M&R	--do--	-	-	-	-	-

Sr. Nos.	Description of Procurement	Quantity (Where applicable)	Estimated unit cost (Where applicable Millions)	Funds allocated.	Scope of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1 st : Quarter	2 nd : Quarter	3 rd : Quarter	4 th : Quarter	
1	2	3	4	5	6	7	8	9	10	11	12
28	M&R Reconditioning of road from village Rasool Bux to Gul Buriro road mile: 1/7-4/0 = 3.40 Kms. i/c M.Structure (Taluka Warah).	-	16.991	16.991	M&R	National complete bidding among PEC Registered Bidders.	-	-	-	-	-
29	M&R of road from Larkana Wagan road to Langh Lake mile: 0/0-0/6 = 1.20 Kms. i/c Re-decking of Bridge	-	7.655	31.000	M&R	--do--	-	-	-	-	-
30	M&R of Road from Shahdadt to Qubo Saeed Khan alongwith Sim Drain road i/c M.Structure. (in portions). (Taluka Shahdadt.)	-	5.678	18.500	M&R	--do--	-	-	-	-	-
31	M&R Repair Construction 6' Rft: (01 No.) & 3' Rft: (04 Nos.) culverts road of taking from Ratodero Shahdadt Motorway bye pass to village Taj Mohammad Leghari (Taluka Shahdadt)	-	1.534	154.625	M&R	--do--	-	-	-	-	-
32	M&R Construction of Retaining Wall along road from Qubo bye Pass road to Ratodero Bye Pass road via Shahdadt City @ mile: 1/6. (Taluka Shahadt)	-	1.369	50.000	M&R	--do--	-	-	-	-	-
33	M&R Construction of 10' Rft: Bridge over sim drain @ village Ghulam Rasool Sasuli via road off taking from village Aitbar Khan Chandio to	-	1.300	40.000	M&R	--do--	-	-	-	-	-
34	Construction of Retaining Wall in village Sharifani (Taluka Kamber)	-	1.000	30.000	M&R	--do--	-	-	-	-	-

Sr. Nos.	Description of Procurement	Quantity (Where applicable)	Estimated unit cost (Where applicable Millions)	Funds allocated.	Scope of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1 st : Quarter	2 nd : Quarter	3 rd : Quarter	4 th : Quarter	
1	2	3	4	5	6	7	8	9	10	11	12
35	M&R of Re-Construction of 20' Rft: Bridge 01 No. at village Shadan Jato.	-	0.876	0.876	M&R	National complete bidding among PEC Registered Bidders.	-	-	-	-	-
36	M&R of Re-Construction of 20' Rft: Bridge 01 No. at village Taggar mile: 0/0-0/6.	-	0.873	0.873	M&R	--do--	-	-	-	-	-
37	M&R of Re-Construction of 20' Rft: Bridge 01 No. at village Ali Jatoi mile: 0/0-0/5.	-	0.873	0.873	M&R	--do--	-	-	-	-	-
38	M&R of Re-Construction of 10' Rft: Bridge 02 Nos. at village Mubarak Shaikh to Qurban Shaikh mile: 0/0-0/6.	-	0.760	0.760	M&R	--do--	-	-	-	-	-
39	M&R of Re-Construction of 3' Ft: Span Culverts 02 Nos. along road from Bakrani Station to Qaim Khan Mangan mile: 0/0-1/0.	-	0.490	0.490	M&R	--do--	-	-	-	-	-
40	M&R of Re-Construction of 10' Rft: Bridge 01 No. at village Bangul Abro Shaman Abro mile: 0/0-0/3.	-	0.381	0.381	M&R	--do--	-	-	-	-	-
41	M&R of Re-Construction of 10' Rft: Bridge 01 No. at village Abro to Pathan Abro mile: 0/0-0/4.	-	0.380	0.380	M&R	--do--	-	-	-	-	-
42	M&R of Re-Construction of 10' Rft: Bridge 01 No. at village Nooral Abro to Yar Mohammad Abro mile: 0/0-0/5.	-	0.380	0.380	M&R	--do--	-	-	-	-	-

Sr. Nos.	Description of Procurement	Quantity (Where applicable)	Estimated unit cost (Where applicable Millions)	Funds allocated.	Scope of Funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurement				Remarks
							1 st : Quarter	2 nd : Quarter	3 rd : Quarter	4 th : Quarter	
1	2	3	4	5	6	7	8	9	10	11	12
43	M&R Repair of 7' Rft: Bridge over Leghari minor from jeand Jarwar to Shahdaskot Jarwar road @ Leghari village (Taluka Shahdaskot)	-	0.650	0.650	M&R	National complete bidding among PEC Registered Bidders.	-	-	-	-	-
44	M&R Construction 3' Rft: span culver @ Imam Bux Jamali to Mohammad Khan Bhutto (Taluka Kamber)	-	0.250	0.250	M&R	--do--	-	-	-	-	-
45	M&R Re-decking of 10' Rft: Bridge slab along Punah Shakh @ point Warah City. (Taluka Warah)	-	0.241	0.241	M&R	--do--	-	-	-	-	-


 Executive Engineer,
 Provincial Highways Division
 Larkano

Annual P.Plan Work-45 P/07XL TC- 2017-18

Integrity Pact

DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC.
PAYABLE BY THE SUPPLIERS OF GOODS, SERVICES & WORKS IN
CONTRACTS WORTH RS.10.00 MILLION OR MORE

Contract Number: _____

Dated: _____

Contract Value: _____

Contract Title: _____

_____ [name of Supplier] hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Pakistan or any administrative subdivision or agency thereof or any other entity owned or controlled by it (GoP) through any corrupt business practice.


Without limiting the generality of the foregoing, _____ [name of Supplier] represents and warrants that it has fully declared the brokerage, commission, fees etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultation fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP, except that which has been expressly declared pursuant hereto.

_____ [name of Supplier] certifies that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with GoP and has not taken any action or will not take any action to circumvent the above declaration, representation or warranty.

_____ [name of Supplier] accepts full responsibility and strict liability for making any false declaration, not making full disclosure, misrepresenting facts or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right, interest, privilege or other obligation or benefit obtained or procured as aforesaid shall, without prejudice to any other right and remedies available to GoP under any law, contract or other instrument, be voidable at the option of GoP.

Notwithstanding any rights and remedies exercised by GoP in this regard, _____ [name of Supplier] agrees to indemnify GoP for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to GoP in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by _____ [name of Supplier] as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP.

[Buyer]



[Seller/Supplier]

WORKS & SERVICES DEPARTMENT


STANDARD BIDDING DOCUMENT

PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 2.5 MILLION)

NAME OF WORK:-

Standard Bidding Document is intended as a model for admeasurements (Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.


EXECUTIVE ENGINEER,
PROVINCIAL HIGHWAYS DIVISION
LARKANO

Email:- provincialhighwaysdivisionlrk@gmail.com

BILL OF QUANTITIES

01/11

20' RFT: BRIDGE

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	4,032 ✓ Cft	Excavation in foundation of building bridge other structure i/c dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25 ✓	P.0% Cft ✓	12,807 ✓
2	912 ✓ Cft	Extra wet earth.	1058.75 ✓	P.0% Cft ✓	966 ✓
3	1,188 ✓ Cft	Extra for slash of Duidal i/c Dewatering (Below bed leve).	2420.00 ✓	P.0% Cft ✓	2,875 ✓
4	948 ✓ Cft	Cement concrete with bricks are stone plaster 1 1/2" to 2" gauge ratio 1:4:8	9416.28 ✓	P.% Cft ✓	89,266 ✓
5	2,455 ✓ Cft	Pucca Brick work in foundation and plinth i/c cement sand mortar (1:4)	12501.41 ✓	P.% Cft ✓	306,910 ✓
6	91 ✓ Cft	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with shuttering ration 1:2:4	14429.25 ✓	P.% Cft ✓	13,131 ✓
7	45 ✓ Sft	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partial wood vertical)	3127.41 ✓	P.% Sft ✓	1,407 ✓
8	14.64 ✓ Cwt	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20 ✓	P. Cwt ✓	70,560 ✓
9	673 ✓ Rft	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to 3/4 gauge.	337.00 ✓	P. Rft ✓	226,801 ✓
10	944 ✓ Sft	Cement Plaster (1:3) upto 20' height 1 1/2" thick.	2344.59 ✓	P.% Sft ✓	22,133 ✓
			TOTAL		746,864 ✓

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Rs.

Total

Total Amount in words.

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highways Division

Executive Engineer
Provincial Highways Division
Larkano

M&R OF RE-CONSTRUCTION OF 20' RFT: BRIDGE 01 NO. AT VILLAGE TAGGAR

MILE: 0/0-0/6.

BILL OF QUANTITIES

02/11

20' RFT: BRIDGE

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	4,032 ✓ Cft:	Excavation in foundation of building bridge other structure i/c dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25 ✓	P.0% Cft: ✓	12,807 ✓
2	912 ✓ Cft:	Extra wet earth.	1058.75 ✓	P.0% Cft: ✓	966 ✓
3	1,188 ✓ Cft:	Extra for slash of Duldal i/c Dewatering (Below bed leve).	2420.00 ✓	P.0% Cft: ✓	2,875 ✓
4	948 ✓ Cft:	Cement concrete with bricks are stone plaster 1½" to 2" guage ratio 1:4:8	9416.28 ✓	P.% Cft: ✓	89,266 ✓
5	2,455 ✓ Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortor (1:4)	12501.41 ✓	P.% Cft: ✓	306,910 ✓
6	91 ✓ Cft:	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with shuttering ration 1:2:4	14429.25 ✓	P.% Cft: ✓	13,131 ✓
7	45 ✓ Sft:	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partial wood vertical)	3127.41 ✓	P.% Sft: ✓	1,407 ✓
8	14.64 ✓ Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20 ✓	P. Cwt: ✓	70,568 ✓
9	673 ✓ Rft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to ¼ gauge.	337.00 ✓	P. Rft: ✓	226,801 ✓
10	944 ✓ Sft:	Cement Plaster (1:3) upto 20' height 1½" thick.	2344.59 ✓	P.% Sft: ✓	22,133 ✓
			TOTAL		764,864

% Above / Below on the rates of CSR.

Rs.

746864/-

Amount to be added / deducted on the

Total

Rs.

Total Amount in words.

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division
Larkano

Executive Engineer,
Provincial Highways Division
Larkano

BILL OF QUANTITIES

03/11

20' RFT: BRIDGE

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	4,032 Cft:	Excavation in foundation of building bridge other structure i/c dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft:	12,807
2	912 Cft:	Extra wet earth.	1058.75	P.0% Cft:	966
3	1,188 Cft:	Extra for slash of Duldal i/c Dewatering (Below bed leve).	2420.00	P.0% Cft:	2,875
4	948 Cft:	Cement concrete with bricks are stone plaster 1 1/2" to 2" guage ratio 1:4:8	9416.28	P.% Cft:	89,266
5	2,455 Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortor (1:4)	12501.41	P.% Cft:	306,910
6	91 Cft:	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with shutering ration 1:2:4	14429.25	P.% Cft:	13,131
7	45 Sft:	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partial wood vertical)	3127.41	P.% Sft:	1,407
8	14.64 Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.% Cwt:	70,568
9	673 Rft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to 1/4 gauge.	337.00	P. Rft:	226,807
10	944 Sft:	Cement Plaster (1:3) upto 20' height 1 1/2" thick.	2344.59	P.% Sft:	22,133
			TOTAL		764,864

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Rs.

Total

Total Amount in words.

746864/-

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division
Larkana

Executive Engineer,
Provincial Highways Division
Larkano

M&R OF RE-CONSTRUCTION OF 10' RFT: BRIDGE 02 NOS. AT VILLAGE MUBARAK SHAIKH TO QURBAN SHAIKH MILE: 0/0-0/6.

04/11

BILL OF QUANTITIES

10' RFT: BRIDGE 02 NOS.

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	1,807 Cft:	Excavation in foundation of building bridge other structure i/c dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft:	5,739
2	660 Cft:	Extra wet earth.	1058.75	P.0% Cft:	699
3	790 Cft:	Extra for slash of Duldal i/c Dewatering (Below bed leve).	2420.00	P.0% Cft:	1,912
4	245 Cft:	Cement concrete with bricks are stone plaster 1 1/2" to 2" guage ratio 1:4:8	9416.28	P.% Cft:	23,070
5	1,232 Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortor (1:4)	12501.41	P.% Cft:	154,017
6	91 Cft:	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with shutering ration 1:2:4	14429.25	P.% Cft:	13,131
7	59 Sft:	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partal wood vertical)	3127.41	P.% Sft:	1,845
8	6.95 Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.% Cwt:	33,500
9	245 Rft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to 1/4 gauge.	337.00	P. Rft:	82,565
10	392 Sft:	Cement Plaster (1:3) upto 20' height 1 1/2" thick.	2344.59	P.% Sft:	9,191
			TOTAL		325,669

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Total

Rs.

_____ x 02 = Rs. _____

Total Amount in words.

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division
Larkana

Executive Engineer,
Provincial Highways Division
Larkana

06/11

BILL OF QUANTITIES

10' RFT. BRIDGE 01 NO.

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	1,807 Cft.	Excavation in foundation of building bridge other structure i/c daggelling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft.	5,739
2	660 Cft.	Extra wet earth.	1058.75	P.0% Cft.	699
3	790 Cft.	Extra for slash of Duldal i/c Dewatering (Below bed leve).	2420.00	P.0% Cft.	1,912
4	245 Cft.	Cement concrete with bricks are stone plaster 1 1/2" to 2" guage ratio 1:4:8	9416.28	P.% Cft.	23,070
5	1,234 Cft.	Pucca Brick work in foundation and plinth i/c cement sand mortar (1:4)	12501.41	P.% Cft.	154,017
6	91 Cft.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with shuttering ration 1:2:4	14429.25	P.% Cft.	13,131
7	59 Sft.	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partial wood vertical)	3127.41	P.% Sft.	1,845
8	6.95 Cwt.	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.% Cwt.	33,500
9	245 Rft.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to 1/4 gauge.	337.00	P. Rft.	82,565
10	392 Sft.	Cement Plaster (1:3) upto 20' height 1 1/2" thick.	2344.59	P.% Sft.	9,191
			TOTAL		325,669

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Total

Rs.

Total Amount in words.

CHECKED

Contractor

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division
Larkana

Executive Engineer,
Provincial Highways Division
Larkano

07/11

BILL OF QUANTITIES

10' RFT. BRIDGE 01 NO.

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	1,807 Cft.	Excavation in foundation of building bridge other structure i/c dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft.	5,779
2	660 Cft.	Extra wet earth.	1058.75	P.0% Cft.	699
3	790 Cft.	Extra for slash of Duldal i/c Dewatering (Below bed leve).	2420.00	P.0% Cft.	1,912
4	245 Cft.	Cement concrete with bricks are stone plaster 1 1/2" to 2" guage ratio 1:4:8	9416.28	P.% Cft.	23,070
5	1,232 Cft.	Pucca Brick work in foundation and plinth i/c cement sand mortor (1:4)	12501.41	P.% Cft.	154,017
6	91 Cft.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with shutering ration 1:2:4	14429.25	P.% Cft.	13,131
7	59 Sft.	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partial wood vertical)	3127.41	P.% Sft.	1,845
8	6.95 Cwt.	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.% Cwt.	33,500
9	245 Rft.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams column raft, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to 1/4 gauge.	337.00	P. Rft.	82,565
10	392 Sft.	Cement Plaster (1:3) upto 20' height 1 1/2" thick.	2344.59	P.% Sft.	9,191
			TOTAL		325,669

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Total

Rs.

Total Amount in words.

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division
Larkana

Executive Engineer,
Provincial Highways Division
Larkana

M&R OF RE-CONSTRUCTION OF 10' RFT: BRIDGE 01 NO. AT VILLAGE NOORAL ABRO TO YAR
MOHAMMAD ABRO MILE: 0/0-0/5.

08/11

BILL OF QUANTITIES

10' RFT: BRIDGE 01 NO.

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	1,807 Cft:	Excavation in foundation of building bridge other structure i/cs dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft:	5,739
2	660 Cft:	Extra wet earth.	1058.75	P.0% Cft:	699
3	790 Cft:	Extra for slash of Duldai i/c Dewatering (Below bed leve).	2420.00	P.0% Cft:	1,912
4	245 Cft:	Cement concrete with bricks are stone plaster 1½" to 2" guage ratio 1:4:8	9416.28	P.% Cft:	23,070
5	1,232 Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortor (1:4)	12501.41	P.% Cft:	154,017
6	91 Cft:	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with shuttering ration 1:2:4	14429.25	P.% Cft:	13,131
7	59 Sft:	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partal wood vertical)	3127.41	P.% Sft:	1,845
8	6.95 Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.% Cwt:	33,500
9	245 Rft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to ¼ guage.	337.00	P. Rft:	82,565
10	392 Sft:	Cement Plaster (1:3) upto 20' height 1½" thick.	2344.59	P.% Sft:	9,191
			TOTAL		325,669

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Total

Rs.

Total Amount in words.

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division

Executive Enigneer,
Provincial Highways Division
Larkano

M&R OF RE-CONSTRUCTION OF 3.0' SPAN CULVERTS (02 NOS.) ALONG ROAD FROM BAKRANI STATION TO QAIM KHAN MANGAN MILE: 0/0-1/0.

05/11

BILL OF QUANTITIES

(3' FT. SPAN CULVERTS 02 NOS.)

Item No.	Qty's	Description of item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	1,176 Cft:	Excavation in foundation of building bridge other structure i/c dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft:	3,735
2	206 Cft:	Cement concrete with bricks are stone plaster 1½" to 2" guage ratio 1:4:8	9416.28	P.% Cft:	19,398
3	796 Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortor (1:4)	12501.41	P.% Cft:	99,511
4	47 Cft:	Cement concrete plain i/c piacing compacting finishing and curing complete i/c screening and washing of stone aggregate with shutering ration 1:2:4	14429.25	P.% Cft:	6,782
5	48 Sft:	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partal wood vertical)	3127.41	P.% Sft:	1,501
6	6.23 Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.% Cwt:	30,030
7	120 Sft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to ¼ gauge.	337.00	P. Sft:	40,440
8	370 Sft:	Cement Plaster (1:3) upto 20' height 1½" thick.	2344.59	P.% Sft:	8,675
			TOTAL		210,072

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Total

Rs.

x 02 = Rs.

Total Amount in words.

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division
Larkana

Executive Engineer,
Provincial Highways Division
Larkana

M&R REPAIR OF 7' RFT: BRIDGE OVER LEGHARI MINOR, FROM JEAND JARWAR TO SHOUKAT
JARWAR ROAD @ LEGHARI VILLAGE.

09/11

BILL OF QUANTITIES

(7' RFT: REPAIR)

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	1,637 ✓ Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortar (1:4)	12501.41 ✓	P. % Cft: ✓	204,648 ✓
2	35.20 ✓ Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20 ✓	P. % Cwt: ✓	169,671 ✓
3	553 ✓ Sft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to 1/4 gauge.	337.00 ✓	P. % Sft: ✓	186,361 ✓
4	552 ✓ Sft:	Cement Plaster (1:3) upto 20' height 1 1/2" thick.	2344.59 ✓	P. % Sft: ✓	12,942 ✓
			TOTAL		573,622 ✓

_____ % Above / Below on the rates of CSR.

Rs.

_____ Amount to be added / deducted on the

Total

Rs.

Total Amount in words. _____

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division

Executive Engineer,
Provincial Highways Division
Larkano

M&R CONSTRUCTION 3' FT: SPAN CULVERT @ IMAM BUX JAMALI TO MOHAMMAD KHAN BHUTTO.

BILL OF QUANTITIES

10/11

(3' FT: SPAN CULVERTS)

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	1,201 Cft:	Excavation in foundation of building bridge other structure i/cs dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft:	3,815
2	251 Cft:	Cement concrete with bricks are stone plaster 1½" to 2" gauge ratio 1:4:8	9416.28	P.% Cft:	23,635
3	670 Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortar (1:4)	12501.41	P.% Cft:	83,759
4	54 Cft:	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with shutering ration 1:2:4	14429.25	P.% Cft:	7,792
5	53 Sft:	Erection and Removal of centering for R.C.C or plain cement work of deodar wood (2nd: Class for partal wood vertical)	3127.41	P.% Sft:	1,658
6	6.10 Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.% Cwt:	29,403
7	134 Sft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to ¼ gauge.	337.00	P. Sft:	45,158
8	506 Sft:	Cement Plaster (1:3) upto 20' height 1½" thick.	2344.59	P.% Sft:	11,864
			TOTAL		207,084

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Total

Rs.

Total Amount in words.

Contractor

CHECKED

Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division

Executive Engineer,
Provincial Highways Division
Larkano

BILL OF QUANTITIES

11/11

(10' RFT: BRIDGE)

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	195 Cft:	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning and straightening the same.	5445.00	P.0% Cft:	10,618
2	19.10 Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	5001.70	P.0% Cwt:	95,532
3	345 Rft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to 1/4 gauge.	337.00	P. Rft:	116,265
			TOTAL		222,415

% Above / Below on the rates of CSR.

Rs.


Amount to be added / deducted on the

Total


Rs.

Total Amount in words.

Contractor


Executive Engineer,
Provincial Highways Division
Larkano

CHECKED


Divisional Head Draftsman
office of the
Executive Engineer
Provincial Highway Division


BIDDING DATA

Name of Contractor:- _____

(This section should be filled in by the Executive Engineer/ Project Agency before issuance of the Biding Documents).

- (a). Name of Procuring Agency :- Executive Engineer,
Provincial Highways Division Larkano
1. Brief Description of Works:- M&R Program 2015-2016.
- (b). Procuring Agency's Address:- Provincial Highways Division Larkano.
- (c). Estimated Cost :- (Million)
- (d). Amount of Bid Security :- 04%
(Fill in lum sum amount in %age of bid amount / estimated cost, but not exceeding 5%)
- (e). Period of Bid Validity (days) :- Days / Month (Not More than sixty Days / Month)
- (f). Security Deposit (including bid security) :-
(in %age of bid amount / estimated cost equal to 10%)
- (g). Percentage, if any, to be deducted from bills:- 07.50% (I/Tax) & 05% Security Deposit.
- (h). Deadline for Submission of Bids alongwith time:- 21.03.2016, Time (1.00 P.M)
- (i). Venue, Time, and Date of Bid Opening:- Executive Engineer,
Provincial Highways Division Larkano
- (j). Time for Completion from written order of commence:- _____
- (k). Liquidity damages :-
(0.05 of Estimated Cost or NBid Cost per day of delay,
But total not exceeding 10%)
- (i). Call Deposit Receipt :- No. _____ Dated: _____ Amount:- _____ /-
- (m). D.R. No. _____ No. _____ Dated: _____ Amount:- _____ /-
- (m). Rate quoted by Contractor :- Part-A Rs. _____ Part-B Rs. _____
Part-C Rs. _____ Part-D Rs. _____

(CONTRACTOR)


EXECUTIVE ENGINEER,
PROVINCIAL HIGHWAYS DIVISION
LARKANO

Contd: P/2

Conditions of Contract**Clause – 1: Commencement & Completion Dates of work.**

The contractor shall not enter upon or commence any portion or work except with the written authority and instructions of the Executive Engineer-in-charge or of in subordinate-in-charge of the work. Failing such authority the contractor shall have no claim to ask for measurements of or payment for work.

The contractor shall proceed with the works with due expedition and without delay and complete the works in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckoned from the date on which the order to commence work is given to the contractor. And further to ensure good progress during the execution of the work, contractor shall be bound, in all in which the time allowed for completion of any work exceeds one month, to achieve progress on the prorated basis.

Clause – 2: Liquidated Damages.


The contractor shall pay liquidated damages to the Agency at the rate per day stated in the bidding data for each day that the completion date is later than the Intended completion date; the amount of liquidated damage paid by the contractor to the Agency shall not exceed 10 per cent of the contract price. Agency may deduct liquidated damages from payments due to the contractor. Payment of liquidated damages does not affect the contractor's liabilities.

Clause – 3: Termination of the Contract.

(A) Procuring Agency/ Executive Engineer may terminate the contract if either of the following conditions exists:-

- (i) Contractor causes a breach of any clause of the Contract
 - (ii) The progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired.
 - (iii) In the case of abandonment of the work owing to the serious illness or death of the contractor or any other cause.
 - (iv) Contractor can also request for termination of contract if a payment certified by the Executive Engineer is not paid to the contractor within 60 days of the date of the submission of the bill.
- (B) The Engineer has power to adopt any of the following courses as may deem fit:-
- (i) To forfeit the security deposit available except conditions mentioned at A (iii) and (iv) above
 - (ii) To finalize the work by measuring the work done by the contractor.

(CONTRACTOR)


 EXECUTIVE ENGINEER,
 PROVINCIAL HIGHWAYS DIVISION
 LARKANO

Contd: P/3

(C) In the event of any of the above courses being adopted by the Executive Engineer, the contractor shall have:-

(i) No claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work or the performance of the contract,

(ii) However, the contractor can claim for the work done at site duly certified by the Executive Engineer in writing regarding the performance of such work and has not been paid.

Procuring Agency / Engineer may invite fresh bids for remaining work.

Clause 4: Possession of the site and claims for compensation for delay.

The Executive Engineer shall give possession of all parts of the site to the contractor. If possession of site is not given by the date stated in the contract data, no compensation shall be allowed for any delay caused in starting of the work on account of any acquisition of land, water standing in borrow pits/ compartments or in according sanction to estimates. In such case, either date of commencement will be changed or period of completion is to be extended accordingly.

Clause -5: Extension of Intended Completion Date.


The Procuring Agency either at its own initiatives before the date of completion or on desire of the contractor may extend the intended completion date, if an event (which hinders the execution of contract) occurs or a variation order is issued which makes it impossible to complete the work by the intended completion date for such period as he may think necessary or proper. The decision of the Executive Engineer in this matter shall be final; where time has been extended under this or any other clause of this agreement, the date for completion of the work shall be the date fixed by the order giving the extension or by the aggregate of all such orders, made under this agreement.

When time has been extended as aforesaid, it shall continue to be the essence of the contract and all clauses of the contract shall continue to be operative during the extended period.

Clause -6: Specifications.

The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards materials and all other matters in strict accordance with the specifications lodged in the office of the Executive Engineer and initialed by the parties, the said specification being a part of the contract. The contractor shall also confirm exactly, fully and faithfully to the designs, drawing, and instructions in writing relating to the work signed by the Executive Engineer in-charge and lodge in his office and to which the contractor shall be entitled to have access at such office or on the site of work for the purpose of inspection during office hours and the contractor shall, if he so requires, be entitled at his own expense to make or cause to be made copies of the specifications, and of all such designs, drawings, and instructions as aforesaid.

(CONTRACTOR)


EXECUTIVE ENGINEER,
PROVINCIAL HIGHWAYS DIVISION
LARKANO

Contd: P/4

Clause - 7: Payments.

(A) **Interim/Running Bill.** A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill at least once in a month and the Executive Engineer in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as far as admissible, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose countersignature to the measurement list will be sufficient to warrant and the Executive Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

The Executive Engineer /Procuring Agency shall pass/certify the amount to be paid to the contractor, which he considers due and payable in respect thereof, subject to deduction of security deposit, advance payment if any made to him and taxes.

All such intermediate payment shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the Executive Engineer-in-charge from recoveries from final bill and rectification of defects and unsatisfactory items of works pointed out to him during defect liability period.

(B) **The Final Bill.** A bill shall be submitted by the contractor within one month of the date fixed for the completion of the work otherwise Executive Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

Clause - 8: Reduced Rates.


In cases where the items of work are not accepted as so completed, the Executive Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

Clause - 9: Issuance of Variation and Repeat Orders.

(A) Agency may issue a Variation Order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plans, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.

(B) Contractor shall not perform a variation until the Procuring Agency has authorized the variation in writing subject to the limit not exceeding the contract cost by of 15% on the same conditions in all respects on which he agreed to do them in the work, and at the same rates, as are specified in the tender for the main work. The contractor has no right to claim for compensation by reason of alterations or curtailment of the work.

(CONTRACTOR)


EXECUTIVE ENGINEER
PROVINCIAL HIGHWAYS DIVISION
LARKANO

Contd: P/5

(C) In case the nature of the work in the variation does not correspond with items in the Bill of Quantities, the quotation by the contractor is to be in the form of new rates for the relevant items of work, and if the Executive Engineer-in-charge is satisfied that the rate quoted is within the rate worked out by him on detailed rate analysis, and then only he shall allow him that rate after approval from higher authority.

(D) The time for the completion of the work shall be extended in the proportion that the additional work bear to the original contact work.

(E) In case of quantities of work executed result the Initial Contract Price to be exceeded by more than 15%, and then Executive Engineer can adjust the rates for those quantities causing excess the cost of contract beyond 15% after approval of Superintending Engineer.

(F) Repeat Order: Any cumulative variation, beyond the 15% of initial contract amount, shall be subject of another contract to be tendered out if the works are separable from the original contract.

Clause-10: Quality Control.

(A) Identifying Defects: If at any time before the security deposit is refunded to the contractor/during defect liability period mentioned in bid data, the Executive Engineer-in-charge or his subordinate-in-charge of the work may instruct the contractor to uncover and test any part of the works which he considers may have a defect due to use of unsound materials or unskillful workmanship and the contractor has to carry out a test at his own cost irrespective of work already approved or paid.


(B) Correction of Defects: The contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require. The contractor shall correct the notified defect within the Defects Correction Period mentioned in notice.

(C) Uncorrected Defects:

(i) In the case of any such failure, the Executive Engineer-in-charge shall give the contractor at least 14 days notice of his intention to use a third party to correct a defect. He may rectify or remove, and re-execute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor.

(ii) If the Executive Engineer considers that rectification/ correction of a defect is not essential and it may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fix therefore.

CONTRACTOR)


EXECUTIVE ENGINEER,
PROVINCIAL HIGHWAYS DIVISION
LARKANO

Contd: P/6

Clause - 11:

(A) Inspection of Operations. The Executive Engineer and his subordinates, shall at all reasonable times have access to the site for supervision and inspection of works under or in course of execution in pursuance of the contract and the contractor shall afford every facility for and every assistance in obtaining the right to such access.

(B) Dates for Inspection and Testing. The Executive Engineer shall give the contractor reasonable notice of the intention of the Executive Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, then he either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, orders given to the contractor's duly authorized agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

Clause - 12: Examination of work before covering up.

(A) No part of the works shall be covered up or put out of view/beyond the reach without giving notice of not less than five days to the Executive Engineer whenever any such part of the works or foundations is or are ready or about to be ready for examination and the Executive Engineer shall, without delay, unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations;

(B) If any work is covered up or placed beyond the reach of measurement without such notice having been given, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed.


Clause - 13: Risks.

The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or related services at the premises and of personal injury and death which arise during and in consequence of its performance of the contract. if any damage is caused while the work is in progress or become apparent within three months of the grant of the certificate of completion, final or otherwise, the contractor shall make good the same at his own expense, or in default the Executive Engineer may cause the same to be made good by other workmen, and deduct the expenses from retention money lying with the Executive Engineer.

Clause-14: Measures for prevention of fire and safety measures.

The contractor shall not set fire to any standing jungle, trees, bush-wood or grass without a written permit from the Executive Engineer. When such permit is given, and also in all cases when destroying, cutting or uprooting trees, bush-wood, grass, etc. by fire, the contractor shall take necessary measures to prevent such fire spreading to or otherwise damaging surrounding property. The contractor is responsible for the safety of all its activities including protection of the environment on and off the site. Compensation of all damage done intentionally or unintentionally on or off the site by the contractor's labour shall be paid by him.

CONTRACTOR)


EXECUTIVE ENGINEER
PROVINCIAL HIGHWAYS DIVISION
LARKANO

Contd: P/7

Clause-15:Sub-contracting.

The contractor shall not subcontract the whole of the works, except where otherwise provided by the contract. The contractor shall not subcontract any part of the works without the prior consent of the Executive Engineer. Any such consent shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts, defaults and neglects of any subcontractor, his agents, servants or workmen as if these acts, defaults or neglects were those of the contractor, his agents' servants or workmen. The provisions of this contract shall apply to such subcontractor or his employees as if he or it were employees of the contractor.

Clause - 16: Disputes.

All disputes arising in connection with the present contract, and which cannot be amicably settled between the parties, the decision of the Superintending Executive Engineer of the circle/officer/one grade higher to awarding authority shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions, hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other questions, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, of failure to execute the same, whether arising, during the progress of the work, or after the completion or abandonment thereof.

Clause -17: Site Clearance.

On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (hereinafter called the Executive Engineer in- charge) of such completion, but neither such certificate shall be given nor shall the work be considered to be complete until the contractor shall have removed all temporary structures and materials brought at site either for use or for operation facilities including cleaning debris and dirt at the site. If the contractor fails to comply with the requirements of this clause then Executive Engineer-in-charge, may at the expense of the contractor remove and dispose of the same as he thinks fit and shall deduct the amount of all expenses so incurred from the contractor's retention money. The contractor shall have no claim in respect of any surplus materials as aforesaid except for any sum actually realized by the sale thereof.

Clause -18: Financial Assistance /Advance Payment.

- (A) Mobilization advance is not allowed.
 (B) Secured Advance against materials brought at site.
 (i) Secured Advance may be permitted only against imperishable materials/quantities anticipated to be consumed/utilized on the work within a period of three months from the date of issue of secured advance and definitely not for full quantities of materials for the entire work/contract. The sum payable for such materials on site shall not exceed 75% of the market price of materials.

CONTRACTOR)


 EXECUTIVE ENGINEER,
 PROVINCIAL HIGHWAYS DIVISION
 LARKANO

Contd: P/8

P/8

(ii) Recovery of Secured Advance paid to the contractor under the above provisions shall be affected from the monthly payments on actual consumption basis, but not later than period more than three months (even if unutilized).

Clause -19: Recovery as arrears of Land Revenue.


Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

Clause -20: Refund of Security Deposit/Retention Money.

On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurements are checked by a competent authority, if such check is necessary otherwise from the last date of recording the final measurements), the defects notice period has also passed and the Executive Engineer has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor (in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

CONTRACTOR

**DIVISIONAL ACCOUNTS OFFICER,
PROVINCIAL HIGHWAYS DIVISION
LARKANO**


**EXECUTIVE ENGINEER
PROVINCIAL HIGHWAYS DIVISION
LARKANO**