

Schedule B/ Bill of Qauntities**PROVIDING AND FIXING PAVER @ FROM SABZI MANDI TO UBL BANK WARD NO.02**

S.No	Description	Qty	Unit	Rate	Amount
1	Dismantling and Removing Road metaling(CSI NO:51.P-13)	1046	P% Cft	605	6,328.00
2	Dismantling of cement concrete plain(1:3:6)(CSI NO:19/b.P-10)	2880	P% Cft	1306.8	37,636.00
3	CC plain including placing compacting finishing & curing complete including screening and washing of stone aggregate without shuttering (Ratio: 1:4:8) (GSI NO:5-i/P-16)	6426.0	P %Cft	11,288.75	725,415.00
4	CC plain including placing compacting finishing & curing complete including screening and washing of stone aggregate without shuttering (Ratio: 1:2:4) (GSI NO:5-f/P-15)	211.0	P %Cft	14,429.25	30,446.00
5	Erection and Removal of centering for R.C.C or plain cement concrete works etc.(GSI NO: 19/b(ii)P:18)	338.0	P %Sft	3,127.41	10,571.00
6	Providing and fixing cement paving blocks flooring having size of 197 x 97 x 80 (mm) of city/ quddra /cobble shape with pigmented natural colours,having strength between 5000psi to 8500 psi i/c filling the joits with hillsand and laying in specified manner / pattern and design etc complete (CSI NO: 74. P50)	15300.0	P /Sft	223.97	3,426,741.00
7	Rehandling of Earth work upto a single throw of Khassi Pharwa a showel with extra lead 1 mile(GSI NO: 1.P-1)	3926	P % Cft	5,431.25	21,323.00
TOTAL RS.					4,258,460.00

Conditions

- 1 The Work Shall have to be executed according to the PWD/PHE Specifications.
- 2 No premium on non schedule Items shall be paid to the contractor.
- 3 Any error & omission and description of Item of work will be governed with relevant Schedule of Rates
- 4 The Contractor shall have to bring the material to be used in the work from the quarries as mentioned in the estimate.

Contractor

TOWN ENGINEER
TOWN COMMITTEE
TANDO GHULAM ALI