



GOVERNMENT OF SINDH

BILL OF QUANTITIES

Sindh Government
Maintenance & Repair Works for External Development at
PMC HOSPITAL NAWABSHAH

ESTIMATE COST RS.		
		M



GOVERNMENT OF SINDH
PMC HOSPITAL NAWABSHAH
Maintenance & Repair Works for External Development
SUMMARY OF COST

S No.	DESCRIPTION	Amount
1	CIVIL WORKS	
	Total	



GOVERNMENT OF SINDH
PMC HOSPITAL NAWABSHAH
Maintenance & Repair Works for External Development
ABSTRACT OF COST

S.No	Description	Unit	Qty	Rate	Amount
<u>SCHEDULE ITEMS</u>					
1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structure with excavated earth Watering and ramming lead upto 5 ft.(SI.18/4) (b) In ordinary soil.	%Cft	2,880.00	3,176.25	91,476
2	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning and straightening the same.SCH/ item no.20 (p-10)	%Cft	8,579.00	5,445.00	467,127
3	cement concrete (1:2:4) including surface finishing and dividing into panels: 2" thick	%Sft	5,662.14	3,275.50	185,463
4	Dismantling cement block masonrySCH/ item no.14 (p-10)	%Cft	5,000.00	1,134.38	56,719
5	(c) Dismantling cement concrete plain 1:2:4.SCH/ item no.19c (p-10)	%Cft	8,579.00	3,327.50	285,466
6	Dismantling cement concrete plain 1:4:8.SCH/ item no.19a (p-10)	%Cft	8,579.00	1,663.75	142,733
7	Providing and fixing cement paving blocks flooring having size of 197x97x80 (mm) of city/ quddra/cobble shape with natural colours, having strength b/w 5000psi to 85000 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete (SN0 73/P-49)	%Sft.	11,028.00	223.97	2,469,941
8	Cement concrete plain including placing compacting, finishing and curing complete (including screening and washing at stone aggregate without shutting. Ratio1:4:8 (SI.51/16)	%Cft.	3,639.24	11,288.75	410,825
9	Supplying and filling sand under floor and plugging in walls. (SI-I-13(I)/52)	%Cft	3,639.24	114.25	4,158



Maintenance & Repair Works for External Development

ABSTRACT OF COST

S.No	Description	Unit	Qty	Rate	Amount
10	Providing and fixing PreCOST Edge Block 3750 PSI Industrial Made Size 6 inch thick x 12 inch long x 12 inch high including the cost of Cartage excavation form Work for haunching 1450 PSI lean concrete 2250 PSI concrete for haunching 1:4 cement sand motar. SCH/H-Waymisc/item no 14/ P16	Rft	1,196.00	297.10	355,329
	TOTAL				4,469,237
	Add _____ % Premium Above or Below On Schedule Items				
	GRAND TOTAL				
	NON SCHEDULE ITEMS				
1	Cutting to a required gradient in all kinds of soil (except rock) and dressing the ground by bulldozers, grader or scraper including disposal of excavated stuff within 3 chains (91.5 Km) including all lifts as required.	Cft	5,514.00		
2	Rolling the surface dry with light power roller (upto 6 tons or 6.09 m. ton) as directed by the Engineer-in-charge.	Sft	11,028.00		
3	Providing and fixing Fiberglass Sheds 4mm thick including cost of pipes, angle iron truss 1.1/2" x 1-1/2" with pulins complete with all respect as per drawings attached	Sft	3,000.00		
4	Providing & fixing wooden Park bench marine ply approved make & design 3 persons capacity as per drwaing attahced	Each	30.00		
5	Providing, Fixing, instlation, commisioning of water coolers having 60 ltr capacity, wall mounted along with the filtration unit as per the specification provided by the engineer (after test performed at site) including top basin & water drain & electrical connection complete in all respect to water storage treatment & make potable for drinking purpose etc.	Each	4.00		
	TOTAL OF NON-SCHEDULE				
	GRAND TOTAL				

