



GOVERNMENT OF SINDH

SINDH GOVERNMENT
PMC HOSPITAL NAWABSHAH
M & R WORKS AT STORE & OTHER OFFICES

BILL OF QUANTITIES

ESTIMATED COST RS.		
		M



**SINDH GOVERNMENT
PMC HOSPITAL NAWABSHAH
M & R WORKS AT STORE & OTHER OFFICES**

SUMMARY OF COST

S.No	ITEMS OF WORKS	AMOUNT
1	Composite Schedule Rate 2012 Electrical WORK	405,986
2	PREMIUM _____ % ABOVE OR BELOW ON SCHEDULE ITEMS	
3	NON SCHEDULE ITEMS Electrical WORK	
	A = TOTAL AMOUNT ELECTRIC WORK	
	TOTAL AMOUNT A	



**SINDH GOVERNMENT
PMC HOSPITAL NAWABSHAH
M & R WORKS AT STORE & OTHER OFFICES**

ABSTRACT OF COST

S.No	Description	Unit	Qty	Rate	Amount
ELECTRIFICATION SCHEDULE					
1	Wiring for light or fan point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.I.No. 124, Page No. 15).	P. pt	35.00	1,130.00	39,550
2	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.I.No.126, Page No. 15).	P. pt	35.00	985.00	34,475
3	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.I.No. 128, Page No. 15).	P. pt	5.00	1,764.00	8,820
4	Providing and laying (Main or sub Main)PVC insulated with size 3-7/.029 copper conductor in 3/4" dia PVC conduit on surface. (S.No 17 / Pg # 3).	rm	300.00	235.00	70,500
5	Providing and laying (Main or sub Main)PVC insulated with size 3-7/.036 copper conductor in 3/4" dia PVC conduit on surface. (S.No 18 / Pg # 3).	rm	300.00	279.00	83,700
6	Providing and laying (Main or sub Main)PVC insulated with size 3-7/.044 (6mm2) copper conductor in 1" dia PVC conduit on surface. (S.No 19 / Pg # 3).	rm	300.00	422.00	126,600
7	Providing & fixing Brass Ceiling fans 56" (good quality) E/C item no 235	Each	13.00	3185	41,405
8	Providing & fixing Bakelite ceiling rose with two terminals. (S.I.No. 228, Page No. 33)	rm	13.00	72.00	936
					405,986



**SINDH GOVERNMENT
PMC HOSPITAL NAWABSHAH
M & R WORKS AT STORE & OTHER OFFICES
NON SCHEDULE**

S.No	Description	Unit	QTY	Rate	Amount
	ELECTRIFICATION NON SCHEDULE				
1	Providing and fixing switches or sockets as per following specification and requirements (5 Amp): a) one gange	No.	10.00		
2	b) two gange	No.	10.00		
3	c) four gange	No.	10.00		
4	d) six gange	No.	10.00		
5	e) two pin 5 AMP sockets for half point	No.	10.00		
6	f) 5 pin plug socket for multiple use 10-15 amp	No.	10.00		
7	g) 3 pin power plug socket 20 amp	No.	10.00		
8	Providing and fixing bakelite holder (thread type) heavy and good quality with brass internal fittings complete with fixing accessories	No.	15.00		
9	P/F Fan dimmer fancy type pak/royal/millat/imported make with necessary connection. On sheet complete as required.	No.	15.00		
10	P/F Exhaust Fan 10" to 12" sweep with wall clamp Metal Body/Plastic Body Pak/Royal/Millat/Imported i/c necessary electric connection etc, complete.	No.	5.00		
11	P/F Earthing set with 1.5"x1.5' x.55' GI plate buried in the ground at depth of 12-ft: upto water level with salt and charcoal mixture etc i/c providing GI pipe and copper wire 8-SWG inspection chamber with MS cover plate.	job	1.00		
12	Providing & fixing Energy Saver 24 Watts approved quality etc, complete (Phillips).	No.	40.00		
13	providing & fixing of fan hooks with all accessories	each	25.00		
14	Providing and laying (Main or sub Main)PVC/PVC as per following specification. with 1-7/.044 copper conductor in 1-1/2" dia PVC conduit recessed in the wall or column as required.	rm	180.00		



**SINDH GOVERNMENT
PMC HOSPITAL NAWABSHAH
M & R WORKS AT STORE & OTHER OFFICES
NON SCHEDULE**

S.No	Description	Unit	QTY	Rate	Amount
15	Providing and laying (Main or sub Main)PVC/pvc as per following specification. With 1-7/.064 copper conductor in 1-1/2" dia PVC conduit recessed in the wall or column as required.	rm	180.00		
16	Providing and fixing of pvc pipe including specials 1" dia to be buried in the ground by excavation/cutting katcha floor and making surface good complete as required.	rm	180.00		
TOTAL AMOUNT					

