

S.#.	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	SECTION-D LV PANELS & DISTRIBUTION BOARDS				
	Supply, installation, testing and commissioning of following LV Panels & Distribution Boards made with 16 SWG sheet steel housing with approved color. Complete in all respect. Including any circuit joints with ferrul, heat shrink sleeves etc where ever required.				
1	New Cubical	1	No.		
2	SMDB	1	No.		
3	MDB-1	1	No.		
4	MDB-2	1	No.		
5	MDB-3	1	No.		
6	Temp Panel	1	No.		
7	Providing temporary connection to provide back-up power to critical load during installation, testing and commissioning of new panels. (i.e MDB-1, MDB-2, MDB-3)	1	Job		
8	Allow for any other item required for completion of job not covered in BOQ or specifications / drawings in accordance with the same standards and brands shown and approved by consultant. All such items shall be covered in this item but complete description, item rates, quantity required and brands shall be mentioned separately and to be attached with the BOQ.	1	Job.		
	Note: Relevant Shop to be submitted for approval from consultant prior to any manufacturing. Safety locking arrangement is required for main incoming circuit breakers of all distribution boards.				
	TOTAL RS. SEC - D (CARRIED FORWARD TO SUMMARY)				
	SECTION-E AS BUILT DRAWINGS				
1	Preparation of as-built drawings of all electrical and allied works after final approval from the consultant/client.	3	Set.		
	Note: Submission of as-build drawings 3 sets & soft copy of complete electrical works after final commissioning of project. Approval of final bills are subject to completion of as built drawings.				
	TOTAL RS. SEC -E (CARRIED FORWARD TO SUMMARY)				

