

S.#.	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	SECTION-B MAIN / SUB-MAIN CABLES				
	Supply, installation, testing, commissioning and termination of following size of CU/PVC, CU/PVC/PVC & CU/XLPE/PVC Cables for Distribution Board in already installed Cable Ladder/Cable Tray/Trench, including all accessories, Complete in all respect as shown on drawing.				
1	From New Cubical to SMDB 3No. 4C-185 Sq.mm Cu/XLPE/PVC + ECC 2x1C-70 Sqmm Cu/PVC	55	Rm.		
2	From SMDB to MDB-1 2No. 4C-240 Sq.mm Cu/XLPE/PVC + ECC 2x1C-70 Sqmm Cu/PVC	95	Rm.		
3	From SMDB to MDB-2 2No. 4C-150 Sq.mm Cu/XLPE/PVC + ECC 2x1C-70 Sqmm Cu/PVC	85	Rm.		
4	From SMDB to MDB-3 2No. 4C-150 Sq.mm Cu/XLPE/PVC + ECC 2x1C-70 Sqmm Cu/PVC	80	Rm.		
	Note: Contractor is advised to confirm the quantities, sizes, running lengths and termination as per site conditions before commencement of work.				
	TOTAL SECTION - B (CARRIED FORWARD TO SUMMARY)				
	SECTION-C CABLE CONTAINMENT				
	Supply and installation of following sizes 16 SWG G.I Cable Ladder with 18 SWG G.I Cover as per details given in the drawings and specifications. Complete with all supporting hangers, brackets, elbows, tee & mounting accessories etc.				
a	450 mm x 75 mm Cable Ladder	80	Rm.		
2	Allow for any other item required for completion of job not covered in BOQ or specifications / drawings in accordance with the same standards and brands shown and approved by consultant. All such items shall be covered in this item but complete description, item rates, quantity required and brands shall be mentioned separately and to be attached with the BOQ.	1	Job.		
	Note: Contractor is advised to confirm the quantities, sizes, running lengths and termination as per site conditions before commencement of work. All the conduits / cable tray crossings through partition walls shall be properly sealed by fire retardant material after installation.				
	TOTAL RS. SEC - C (CARRIED FORWARD TO SUMMARY)				

