



OFFICE OF THE TOWN COMMITTEE BAGARJI TALUKA NEW SUKKUR

No. TCB/ 56 of/ 2018


Dated: - 14 /03/2018

To,

The Director (Enf-I)
Sindh Public Procurement
Regularity Authority
Government of Sindh Karachi.

Subject:- Request for keep the Tender Notice on SPPRA website.

Kindly fine enclosed herewith copies of NIT of Town Committee Bagarji publish on website along payment towards charge of amounting to Rs:- 2000/= cheque No. 22789434 dated 14-03-2018 Bank of Sindh bank Minara Road Sukkur.


Town Officer

Town Committee Bagarji
Taluka New Sukkur

SPPRA INWARD DIARY

NO : 7170
DATED : 19-03-2018



OFFICE OF THE TOWN COMMITTEE BAGARJI TALUKA NEW SUKKUR

No. TCB/ 55 of/ 2018

Dated: - 14 /03/2018

To,

The Director (Enf-I)

Sindh Public Procurement

Regularity Authority

Government of Sindh Karachi.

Subject:- Request for keep the Tender Notice on SPPRA website.

I am sending herewith enclosed copy NIT Town Committee Bagarji along with CD/USB for Publish on SPPRA'S website as desired.

In this regards your co-operation will highly be appreciated.


Town Officer

Town Committee Bagarji
Taluka New Sukkur

OFFICE OF THE TOWN COMMITTEE
TOWN COMMITTEE BAGARJI TALUKA NEW
SUKKUR

No. TC/ 57 /2018
 Sukkur dated: 14-3-2018

NOTICE INVITING TENDERS

The sealed tender on B-I / II forms (estimated cost less than or within 1.0 Million) are invited from the bidders meeting the eligibility criteria of Sindh Public procurement Rules 2010.

S.No:	Name of Scheme	Estimated Cost in Million	Earnest Money in Million (2%)	Tender Fee in Millions	Completion Period
1	Construction Paver Block Flooring and drains at Umer Kot to Zahid Kumbhar House Town Committee Bagirji	0.500	0.010	500.00	12 Months
2	Construction Paver Block Flooring and drains at to Zahid Kumbhar to Pir Zahir Zakaria Mor Town Committee Bagirji	0.500	0.010	500.00	12 Months
3	Construction of Drainage System for Saba Goth Town Committee Bagirji	0.900	0.018	500.00	12 Months
4	Construction of Paver Block Flooring and drains at Talib Decoration to Ramesh Lal House Town Committee Bagirji	0.500	0.010	500.00	12 Months
5	Construction of Paver Block Flooring and drains at Memon Masjid to Talib Decoration Town Committee Bagirji	0.500	0.010	500.00	12 Months
6	Construction of Paver Block Flooring and drains at Raza Junejo Mill to Mandir Town Committee Bagirji	0.500	0.010	500.00	12 Months
7	Construction of Paver Block Flooring and drains at Bali Lal House to Raza Junejo Mill Town Committee Bagirji	0.500	0.010	500.00	12 Months
8	Construction of Paver Block Flooring and drains at Ramesh Lal House to Bali Lal House Town Committee Bagirji	0.500	0.010	500.00	12 Months
9	Construction of Paver Block Flooring and drains at Madir to Umer Kot Town Committee Bagirji	0.500	0.010	500.00	12 Months
10	Construction of Paver Block Flooring and drains at Ward No. 1 & 2 Town Committee Bagirji	0.500	0.010	500.00	12 Months
11	Desilting of Drainage Wall and open surface drains for various places of Town Committee Bagirji	0.600	0.012	500.00	12 Months
12	Construction of Pver Block Remaining streets of the Ward No. 3 Town Committee Bagirji	0.500	0.010	500.00	12 Months
13	Construction of Drains Daya House to House of Moor Shaikh Town Committee Bagirji	0.700	0.014	500.00	12 Months

- The Blank tender forms can be had from the office if the undersigned, during office hours on any working day up to 05-04-2018 on payment of the tender fee, specified against each work.

2. The tenders will be received back on 26-04-2018 up to 1.00 PM opened on the same day at 2.00 PM, if the undersigned is out of headquarter, the tenders will be opened on the next day. In case the tenders are non-responded the next date of issue & opening will be 25-04-2018 and 26-04-2018
3. The bidders who will provide following documents / information are eligible to participate as per **SPPRA Rules 2010 (Amended 2017)**.
 - i. Full name, permanent address, Telephone & Fax numbers, E-mail & the organization & structure.
 - ii. Bio Data of technical staff employed and to be made available for working on the Project.
 - iii. Details of work executed during the last five years including copy of certificate for satisfactory completion of works by client.
 - iv. Documentary proof and ownership of available Machinery and T & P.
 - v. List, Scope & Approximate cost of works in hand.
 - vi. Finance stability certificate issued by a scheduled bank.
 - vii. Affidavit in which the bidder undertakes that it is not involved in any litigation.
 - viii. Affidavit in which it should be undertaken that the information provided is true and correct.
 - ix. Affidavit that the bidders has not been black listed by any Government / Semi Government / Autonomous body.
 - x. Registration (NTN certificate) from Income Tax Department including CNIC.
4. The earnest money specified would be pledged in the name of Town Officer Town Committee Bagarji the shape of Call Deposit / pay order only from any scheduled bank and must be attached with bid documents, otherwise it will be not entertained.
5. If Firm / Partner involved in partnership deed, then complete details / instructions and power of attorney will be submitted on affidavit by the Proprietor.
6. Conditional & telegraphic tenders will not be entertained.
7. The undersigned and other competent authority reserve the rights to reject all or any one bid as per provision of SPPRA Rules 2010 (Amended 2013).
8. Works will be carried out as per PWD Specification.
9. All the contractors / firms shall be registered with Sindh Revenue Board (SRB) in term of Rule-46-I(ii) of SPPRA rule (Amended 2014)
10. The work orders shall be issued to the lowest bidder after receipt of funds from government.


TOWN OFFICER
TOWN COMMITTEE
BAGARJI

CC to the:

1. Manager (Assessment-III), Sindh Public Procurement Regulatory Authority (SPPRA), Government of Sindh, Barrack No. 8 Secretariat No. 4A, Court Road, Karachi for publishing on web.
2. Deputy Commissioner Sukkur.
3. Director Local Government Sukkur for favour of his kind information.
4. P.S Secretary LGD Karachi.
5. Assistant Director Local fund audit Sukkur.
6. Sub-Engineer, Town Committee Bagarji.
7. Notice Board.



No. SOII/(LG)/8-12/2017/SUK
GOVERNMENT OF SINDH
LOCAL GOVERNMENT DEPARTMENT

Karachi dated the 01st March, 2018

The Director,
Local Government,
DISTRICT SUKKUR.



SUBJECT:- PERMISSION FOR CALLING OF TENDER DEVELOPMENT WORKS ON (OWN SOURCE) 2017-18 PROPOSED TO CARRIED OUT IN TOWN COMMITTEE BAGERJI.

I am directed to refer to your letter No. DLG/0224/2018 dated 24-01-2018, on the subject noted above and to convey the permission regarding execution of (17) development work amounting to Rs. 8.8 (Million), in Town Committee, Bagerji, District Sukkur, subject to following Conditions:-

- i. Availability of provision in the Budget of the councils.
- ii. No liability will be created under any circumstances.
- iii. Change of location of schemes, if any, would be made with the approval of department.
- iv. Monthly progress report of Development Schemes would be communicated to the department.
- v. Completion of all codal formalities and rule / policy.
- vi. There is no dues / liabilities on account of salary and pension.
- vii. Water supply and drainage system is intact and proper working condition.

2. The above work approved and allowed subject to condition to issuance of certificate of satisfaction of Municipal Service by the Chairman, Town Committee, Bagerji, District Sukkur, and to implement the SPPRA Rule, 2010 in letter and spirit.

(SYED NAZAR MUHAMMAD SHAH)
SECTION OFFICER-II

Cc to:-

1. The Chairman, Town Committee, Bagerji, District Sukkur.
- ✓ 2. The Town Officer, Town Committee, Bagerji, District Sukkur.
3. The Assistant Director, Local Fund Audit, District Sukkur.
4. PS to Minister Local Govt. Deptt: Government of Sindh, Karachi.
5. P S to Secretary, Local Government Department, Govt. of Sindh, Karachi.
6. Office record / file.

SECTION OFFICER-II



No. SOII/(LG)/8-12/2017/SUK
GOVERNMENT OF SINDH
LOCAL GOVERNMENT DEPARTMENT

Karachi dated the 06th March, 2018

NOTIFICATION

With the approval of Competent Authority, Constitution of Procurement Committee consisting on following for undertaking Development Work in Town Committee, Bagarji, District Sukkur, during current Financial year 2017-18, is hereby constituted under Section-7 of SPPRA Rule, 2010:-

- | | |
|--|-----------|
| 1. The Deputy Director,
Local Government, Khairpur. | Chairman. |
| 2. Assistant Executive Engineer,
Sub Division Ii, Sukkur. | Member |
| 3. Town Officer,
Town Committee, Bagarji. | Member |

2. The Function and responsibilities of Procurement Committee shall be as under:
-Rule-7 (Section-8 of SPPRA Rule 2010)

- Preparing Bidding Documents.
- Carrying out technical as well as financial evolution of the bids
- Prepare evolution reports as provided in Rule 45.
- Making recommendations for the award of contract to the Competent Authority.
- Perform any other function ancillary and incidental to the above.


-SECRETARY TO GOVT: OF SINDH-


NO.SOII / (LG)/8-12/2017/SUK

Karachi, dated the 06th March, 2018

A copy is forwarded for information and necessary action to:-

1. The Director, Sindh Public Procurement Regularity Authority, Karachi.
2. The Deputy Director, Local Government, Sukkur, He is requested to ensure fulfillment of all codal formalities in accordance with rules /policy.
3. The Chairman, Town Committee, Bagarji, District Sukkur.
4. The Town officer, Town Committee, Bagarji, District Sukkur.
5. PS to Secretary, Local Govt. Department, Government of Sindh, Karachi.
6. PS to Special Secretary, (LGD), Government of Sindh, Karachi.
7. Members concerned.
8. Office order file.


(SYED NAZAR MUHAMMAD SHAH)
SECTION OFFICER-II



No. SOII/(LG)/8-12/2017/SUK
GOVERNMENT OF SINDH
LOCAL GOVERNMENT DEPARTMENT

Karachi dated the 06th March, 2018

NOTIFICATION

With the approval of Competent Authority, a compliant Redressal Committee is hereby consisted under Rule 31(!) (2) of SPPRA rules, 2010 of Town Committee, Bagarji, District Sukkur, during current Financial year 2017-18,

1. Town Officer, Chairman
Town Committee, Bagarji.
District Sukkur.
2. Assistant Executive Engineer,
Member
Sub Division II, PHED, Sukkur
3. Sub Engineer, Member
Town Committee, Bagarji.

2. The Function and responsibilities of complaint Redressal Committee shall be as under: - (Section-31(13)(a,b,c,d,e & f) of SPPRA Rule 2010).

-SECRETARY TO GOVT: OF SINDH-

NO.SO-II (LG)/8-12/2017/SUK

Karachi, dated the 06th March, 2018

A copy is forwarded for information and necessary action to:-

1. The Director, Sindh Public Procurement Regularity Authority, Karachi.
2. The Chairman, Town Committee, Bagarji. He is requested to ensure fulfillment of all codal formalities in accordance with rules /policy.
3. The Town Officer, Town Committee, Bagarji, District Sukkur.
3. PS to Secretary, Local Govt. Department, Government of Sindh, Karachi.
4. PS to Additional Secretary, (LGD), Government of Sindh, Karachi.
5. Members concerned.
6. Office order file.


(SYED NAZAR MUHAMMAD SHAH)
SECTION OFFICER-II

ANNUAL PROCUREMENT PLAN


(WORKS, GOOD & SERVICES)


FINANCIAL YEAR 2017 - 18

AGENDA NO.01

Sr no	Description of Procurement	Quality (where applicable)	Estimated unit cost where applicable	Estimated total cost	Funds allocated	Source of funds (ADP/Non ADP)	Proposed procurement method	Timing of Procurement				Remarks
								1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
01.	02.	03.	04.	05.	06.	07.	08.	09.	10.	11.	12.	13.
1	Construction Paver Block Flooring and drains at Umer Kot to Zahid Kumbhar House Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
2	Construction Paver Block Flooring and drains at to Zahid Kumbhar to Pir Zahir Zakaria Mor Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
3	Construction of Drainage System for Saba Goth Town Committee Bagirji			0.900	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
4	Construction of Paver Block Flooring and drains at Talib Decoration to Ramesh Lal House Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
5	Construction of Paver Block Flooring and drains at Memon Masjid to Talib Decoration Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
6	Construction of Paver Block Flooring and drains at Raza Junejo Mill to Mandir Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
7	Construction of Paver Block Flooring and drains at Bali Lal House to Raza Junejo Mill Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
8	Construction of Paver Block Flooring and drains at Ramesh Lal House to Bali Lal House Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	

Sr no	Description of Procurement	Quality (where applicable)	Estimated unit cost where applicable	Estimated total cost	Page 2 Funds allocated	Source of funds (ADP/Non ADP)	Proposed procurement method	Timing of Procurement				Remarks
								1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
01.	02.	03.	04.	05.	06.	07.	08.	09.	10.	11.	12.	13.
9	Construction of Paver Block Flooring and drains at Madir to Umer Kot Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
10	Construction of Paver Block Flooring and drains at Ward No. 1 & 2 Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
11	Desilting of Drainage Wall and open surface drains for various places of Town Committee Bagirji			0.600	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
12	Construction of Pver Block Remaining streets of the Ward No. 3 Town Committee Bagirji			0.500	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	
13	Construction of Drains Daya House to House of Moor Shaikh Town Committee Bagirji			0.700	OZT Share 2017-18	Non-ADP	Single Stage Single Envelop	-	-	-	-	


 SUB ENGINEER
 TOWN COMMITTEE
 BAGIRJI


 TOWN OFFICER
 TOWN COMMITTEE
 BAGIRJI

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Drainage System for Saba Goth Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____


**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.900 Million
3. Earnest Money @ (2%)	0.018 Million
4. Percentage if any to be deducted from Bill 8%	0.072 Million
5. Security deposit @ 10% Including Earnest Money	0.090 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


Town Officer
Town Committee
Bagirji
Taluka Bagirji Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Drainage System for Saba Goth Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.90 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 03
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee
Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Drainage System for Saba Goth Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty.	437.50 Cft	at Rs. 3176.25	P.%0cft.	Rs.	1390.00
------	------------	----------------	----------	-----	---------

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty.	87.50 Cft	at Rs. 11288.75	P.%cft.	Rs.	9878.00
------	-----------	-----------------	---------	-----	---------

a)Ratio 1:2:4

Qty.	297.50 Cft	at Rs. 14429.25	P.%cft.	Rs.	42927.00
------	------------	-----------------	---------	-----	----------

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty.	700.00 Sft	at Rs. 3127.41	P.%sft.	Rs.	21892.00
------	------------	----------------	---------	-----	----------

4)Reinforced cement concrete work including all labour and materialexcept the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles) (a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement 2cft.sand

Qty.	30.12 Cft	atRs. 337.00	P.cft.	Rs.	10150.00
------	-----------	--------------	--------	-----	----------

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars. (C.S.I.No.8(h)

Qty.	1.21 Cwt	at Rs. 5001.70	P.cwt.	Rs.	6052.00
------	----------	----------------	--------	-----	---------

	Total Part-I	Rs.	92289.00
--	---------------------	------------	-----------------

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items


1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead. (C.S.I.No.3P.No.1)

Qty.	3015.00 cft.	at Rs.	7142.70	P%0cft.	Rs.	21535.00
2)Earth work compaction (soft,Ordinary or hard soil)(a)Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)						
Qty.	3015.00 cft.	at Rs.	354.00	P%0cft.	Rs.	1067.00
3)Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape with natural Colours , having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete.(C.S.I. No.71 P.No.49)						
Qty.	3015.00 sft.	at Rs.	199.77		Rs.	602307.00
4)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering. (C.S.I.No.5 P.No.16)						
a)Ratio 1:4:8						
Qty.	82.91 cft.	at Rs.	11288.75	P.%cft.	Rs.	9360.00
(b)Ratio 1:2:4						
Qty.	83.75 cft.	at Rs.	14429.25	P.%cft.	Rs.	12084.00
5)Errection and removal of centering for R.C.C. or Plain cement concreete work of Partal wood. (
(a) Vertical						
Qty.	167.50 Cft	at Rs.	3127.41	P.%sft.	Rs.	5238.00
6)Hard Murrum or fine powdery murrum(SMI No.71)						
Qty.	753.75 Cft	at Rs.	1800.00	P.%sft.	Rs.	13568.00
					Total Part-I Rft	665159.00

ABSTRACT

Sub-Work No. 1	Drains	Rs.	92289.00
Sub-Work No. 2	Paving Blocks	Rs.	665159.00
		Total Rs.	757448.00

CONTRACTOR


 Sub-Engineer
 Town Committee
 Bagirji

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: Construction of Paver Block Flooring and drains at Talib Decoration to Ramesh Lal House Town Committee Bagirji

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

Town Officer
Town Committee
Bagirji

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh at _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


Town Officer
Town Committee
Bagirji
Taluka New Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Paver Block Flooring and drains at Talib Decoration to Ramesh Lal House Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 04
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
TOWN OFFICER
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Paver Block Flooring and drains at Talib Decoration to Ramesh Lal House Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty.	281.25 Cft	at Rs. 3176.25	P.%0cft.	Rs.	893.00
------	------------	----------------	----------	-----	--------

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty.	56.25 Cft	at Rs. 11288.75	P.%cft.	Rs.	6350.00
------	-----------	-----------------	---------	-----	---------

a)Ratio 1:2:4

Qty.	191.25 Cft	at Rs. 14429.25	P.%cft.	Rs.	27596.00
------	------------	-----------------	---------	-----	----------

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty.	450.00 Sft	at Rs. 3127.41	P.%sft.	Rs.	14073.00
------	------------	----------------	---------	-----	----------

4)Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles) (a)R.C. work in roof slab beams columns rafts lintels and other structural member laid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty.	30.12 Cft	atRs. 337.00	P.cft.	Rs.	10150.00
------	-----------	--------------	--------	-----	----------

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty.	1.21 Cwt	at Rs. 5001.70	P.cwt.	Rs.	6052.00
------	----------	----------------	--------	-----	---------

	Total Part-I	Rs.	65114.00
--	---------------------	------------	-----------------

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items


1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Qty.	1620.00 cft.	at Rs.	7142.70	P%0cft.	Rs.	11571.00
2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)						
Qty.	1620.00 cft.	at Rs.	354.00	P%0cft.	Rs.	573.00
3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape with natural Colours , having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)						
Qty.	1620.00 sft.	at Rs.	199.77		Rs.	323627.00
4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)						
a) Ratio 1:4:8						
Qty.	44.55 cft.	at Rs.	11288.75	P.%cft.	Rs.	5029.00
(b) Ratio 1:2:4						
Qty.	45.00 cft.	at Rs.	14429.25	P.%cft.	Rs.	6493.00
5) Erection and removal of centering for R.C.C. or Plain cement concrete work of Partial wood. (
(a) Vertical						
Qty.	90.00 Cft	at Rs.	3127.41	P.%sft.	Rs.	2815.00
6) Hard Murrum or fine powdery murrum (SMI No.71)						
Qty.	405.00 Cft	at Rs.	1800.00	P.%sft.	Rs.	7290.00
					Total Part-I Rft	357398.00

ABSTRACT

Sub-Work No. 1	Drains	Rs.	65114.00
Sub-Work No. 2	Paving Blocks	Rs.	357398.00
		Total Rs.	422512.00

CONTRACTOR


 Sub-Engineer
 Town Committee
 Bagirji

OFFICE OF THE TOWN OFFICER
TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Paver Block Flooring and drains at Memon Masjid to Talib
Decoration Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____

dated: _____

Town Officer
Town Committee
Bagirji

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates as entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


TOWN OFFICER
Town Committee Bagirji
Taluka Bagirji
Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Paver Block Flooring and drains at Memon Masjid to Talib Decoration Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 05
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
TOWN OFFICER
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Paver Block Flooring and drains at Memon Masjid to Talib Decoration Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 312.50 Cft at Rs. 3176.25 P.%cft. Rs. 993.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 62.50 Cft at Rs. 11288.75 P.%cft. Rs. 7055.00

a)Ratio 1:2:4

Qty. 212.50 Cft at Rs. 14429.25 P.%cft. Rs. 30662.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 500.00 Sft at Rs. 3127.41 P.%sft. Rs. 15637.00

4)Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles) (a)R.C. work in roof slab beams columns rafts lintels and other structural member laid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 70549.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Otv. 1575.00 cft. at Rs. 7142.70 P%0cft. Rs. 11250.00

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1575.00 cft. at Rs. 354.00 P%0cft. Rs. 558.00

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty. 1575.00 sft. at Rs. 199.77 | Rs. 314638.00

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty. 43.31 cft. at Rs. 11288.75 P.%cft. Rs. 4889.00

(b) Ratio 1:2:4

Qty. 43.75 cft. at Rs. 14429.25 P.%cft. Rs. 6313.00

5) Erection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty. 87.50 Cft at Rs. 3127.41 P.%sft. Rs. 2736.00

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty. 393.75 Cft at Rs. 1800.00 P.%sft. Rs. 7088.00

Total Part-I Rft 347472.00

ABSTRACT

Sub-Work No. 1 Drains Rs. 70549.00

Sub-Work No. 2 Paving Blocks Rs. 347472.00

Total Rs. 418021.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji

OFFICE OF THE CTOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction Paver Block Flooring and drains at to Zahid Kumbhar to Pir Zahir Zakaria Mor Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


**Town Officer
Town Committee
Bagirji
Taluka New Sukkur**

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction Paver Block Flooring and drains at to Zahid Kumbhar to Pir Zahir Zakaria Mor Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1	Furnish and Technical Proposal (in case	Single Stage / Single Envelope
(b)	of two envelope method) of Company	
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 02
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction Paver Block Flooring and drains at
to Zahid Kumbhar to Pir Zahir Zakaria Mor Town
Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 265.63 Cft at Rs. 3176.25 P.%0cft. Rs. 844.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 53.13 Cft at Rs. 11288.75 P.%cft. Rs. 5997.00

a)Ratio 1:2:4

Qty. 180.63 Cft at Rs. 14429.25 P.%cft. Rs. 26063.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 425.00 Sft at Rs. 3127.41 P.%sft. Rs. 13291.00

4)Reinforced cement concrete work including all labour and materialexcept the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles)(a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 62397.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1) Barrow pit excavation undressed lead upto 100 ft.
(b) In Ordinary soil with three miles extra lead. (C.S.I.No.3P.No.1)

Qty. 1620.00 cft. at Rs. 7142.70 P%0cft. Rs. 11571.00

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1620.00 cft. at Rs. 354.00 P%0cft. Rs. 573.00

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty. 1620.00 sft. at Rs. 199.77 Rs. 323627.00

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty. 44.55 cft. at Rs. 11288.75 P.%cft. Rs. 5029.00

(b) Ratio 1:2:4

Qty. 45.00 cft. at Rs. 14429.25 P.%cft. Rs. 6493.00

5) Erection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty. 90.00 Cft at Rs. 3127.41 P.%sft. Rs. 2815.00

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty. 405.00 Cft at Rs. 1800.00 P.%sft. Rs. 7290.00

Total Part-I Rft 357398.00

ABSTRACT

Sub-Work No. 1 Drains Rs. 62397.00

Sub-Work No. 2 Paving Blocks Rs. 357398.00

Total Rs. 419795.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction Paver Block Flooring and drains at Umer Kot to Zahid Kumbhar House Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


**Town Officer
Town Committee
Bagirji**
Taluka New Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction Paver Block Flooring and drains at Umer Kot to Zahid Kumbhar House Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 01
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction Paver Block Flooring and drains at Umer Kot to Zahid Kumbhar House Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 312.50 Cft at Rs. 3176.25 P.%cft. Rs. 993.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 62.50 Cft at Rs. 11288.75 P.%cft. Rs. 7055.00

a)Ratio 1:2:4

Qty. 212.50 Cft at Rs. 14429.25 P.%cft. Rs. 30662.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 500.00 Sft at Rs. 3127.41 P.%sft. Rs. 15637.00

4)Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles)(a)R.C. work in roof slab beams columns rafts lintels and other structural member laid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 70549.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Qty. 1575.00 cft. at Rs. 7142.70 P%0cft. Rs. 11250.00

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1575.00 cft. at Rs. 354.00 P%0cft. Rs. 558.00

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty. 1575.00 sft. at Rs. 199.77 1 Rs. 314638.00

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty. 43.31 cft. at Rs. 11288.75 P.%cft. Rs. 4889.00

(b) Ratio 1:2:4

Qty. 43.75 cft. at Rs. 14429.25 P.%cft. Rs. 6313.00

5) Errection and removal of centering for R.C.C. or Plain cement concrete work of Partial wood. (

(a) Vertical

Qty. 87.50 Cft at Rs. 3127.41 P.%sft. Rs. 2736.00

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty. 393.75 Cft at Rs. 1800.00 P.%sft. Rs. 7088.00

Total Part-I Rft 347472.00

ABSTRACT

Sub-Work No. 1	Drains	Rs.	70549.00
Sub-Work No. 2	Paving Blocks	Rs.	347472.00
Total Rs.			418021.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Paver Block Flooring and drains at Raza Junejo Mill to Mandir
Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh at _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


**TOWN OFFICER
Town Committee
Bagirji
Taluka New Sukkur**

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Paver Block Flooring and drains at Raza Junejo Mill to Mandir Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 06
20.1(a)	Dealine for submission of bids:-	Office of the Town Officer, Town Committee Bagirji.
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee
Town Committee Bagarji
Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Paver Block Flooring and drains at Raza Junejo Mill to Mandir Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 187.50 Cft at Rs. 3176.25 P.%cft. Rs. 596.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 37.50 Cft at Rs. 11288.75 P.%cft. Rs. 4233.00

a)Ratio 1:2:4

Qty. 127.50 Cft at Rs. 14429.25 P.%cft. Rs. 18397.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 300.00 Sft at Rs. 3127.41 P.%sft. Rs. 9382.00

4)Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles) (a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 48810.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Qty. 1710.00 cft at Rs. 7142.70 P.%cft. Rs. 12214.00

2)Earth work compaction (soft,Ordinary or hard soil)(a)Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1710.00 cft. at Rs. 354.00 P%0cft. Rs. 605.00

3)Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete.(C.S.I. No.71 P.No.49)

Qty. 1710.00 sft. at Rs. 199.77 1 Rs. 341607.00

4)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 47.03 cft. at Rs. 11288.75 P.%cft. Rs. 5309.00

(b)Ratio 1:2:4

Qty. 47.50 cft. at Rs. 14429.25 P.%cft. Rs. 6854.00

5)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty. 95.00 Cft at Rs. 3127.41 P.%sft. Rs. 2971.00

6)Hard Murrum or fine powdery murrum(SMI No.71)

Qty. 427.50 Cft at Rs. 1800.00 P.%sft. Rs. 7695.00

Total Part-I Rft 377255.00


ABSTRACT

Sub-Work No. 1 Drains Rs. 48810.00

Sub-Work No. 2 Paving Blocks Rs. 377255.00

Total Rs. 426065.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Paver Block Flooring and drains at Bali Lal House to Raza Junejo Mill Town Committee Bagirji**

Name of Firm / Contractor:

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR



TOWN OFFICER
Town Committee
Bagirji
Taluka Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Paver Block Flooring and drains at Bali Lal House to Raza Junejo Mill Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 07
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Paver Block Flooring and drains at Bali Lal House to Raza Junejo Mill Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 218.75 Cft at Rs. 3176.25 P.%cft. Rs. 695.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 43.75 Cft at Rs. 11288.75 P.%cft. Rs. 4939.00

a)Ratio 1:2:4

Qty. 148.75 Cft at Rs. 14429.25 P.%cft. Rs. 21464.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 350.00 Sft at Rs. 3127.41 P.%sft. Rs. 10946.00

4)Reinforced cement concrete work including all labour and materialexcept the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles)(a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings includiug cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 54246.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Otv. 1665.00 cft. at Rs. 7142.70 P%0cft. Rs. 11893.00

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1665.00 cft. at Rs. 354.00 P%0cft. Rs. 589.00

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / guddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty. 1665.00 sft. at Rs. 199.77 Rs. 332617.00

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty. 45.79 cft. at Rs. 11288.75 P.%cft. Rs. 5169.00

(b) Ratio 1:2:4

Qty. 46.25 cft. at Rs. 14429.25 P.%cft. Rs. 6674.00

5) Erection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty. 92.50 Cft at Rs. 3127.41 P.%sft. Rs. 2893.00

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty. 416.25 Cft at Rs. 1800.00 P.%sft. Rs. 7493.00

Total Part-I Rft 367328.00

ABSTRACT

Sub-Work No. 1 Drains Rs. 54246.00

Sub-Work No. 2 Paving Blocks Rs. 367328.00

Total Rs. 421574.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji
TOWN COMMITTEE
BAGARJI

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Paver Block Flooring and drains at Ramesh Lal House to Bali Lal House Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


**Town Officer
Town Committee
Bagirji
Taluk New Sukkur**

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Paver Block Flooring and drains at Ramesh Lal House to Bali Lal House Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 08
20.1(a)	Dealine for submission of bids:-	Office of the Town Officer, Town Committee Bagirji.
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Paver Block Flooring and drains at Ramesh Lal House to Bali Lal House Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 234.38 Cft at Rs. 3176.25 P.%cft. Rs. 744.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 46.88 Cft at Rs. 11288.75 P.%cft. Rs. 5292.00

a)Ratio 1:2:4

Qty. 159.38 Cft at Rs. 14429.25 P.%cft. Rs. 22997.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 375.00 Sft at Rs. 3127.41 P.%sft. Rs. 11728.00

4)Reinforced cement concrete work including all labour and materialexcept the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles) (a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 56963.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Otv. 1638.00 cft. at Rs. 7142.70 P%0cft. Rs. 11700.00

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1638.00 cft. at Rs. 354.00 P%0cft. Rs. 580.00

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty. 1638.00 sft. at Rs. 199.77 1 Rs. 327223.00

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty. 45.05 cft. at Rs. 11288.75 P.%cft. Rs. 5085.00

(b) Ratio 1:2:4

Qty. 45.50 cft. at Rs. 14429.25 P.%cft. Rs. 6565.00

5) Erection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty. 91.00 Cft at Rs. 3127.41 P.%sft. Rs. 2846.00

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty. 409.50 Cft at Rs. 1800.00 P.%sft. Rs. 7371.00

Total Part-I Rft 361370.00


ABSTRACT

Sub-Work No. 1 Drains Rs. 56963.00

Sub-Work No. 2 Paving Blocks Rs. 361370.00

Total Rs. 418333.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji

OFFICE OF THE TOWN OFFICER
TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Paver Block Flooring and drains at Madir to Umer Kot Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

Town Officer
Town Committee
Bagirji

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


Town Officer
TOWN OFFICER
Town Committee
Town Committee Bagirji
Bagirji
Taluka New Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Paver Block Flooring and drains at Madir to Umer Kot Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 09
20.1 (a)	Dealine for submission of bids:-	Office of the Town Officer, Town Committee Bagirji.
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Paver Block Flooring and drains at Madir to Umer Kot Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty.	359.38 Cft	at Rs.	3176.25	P.%cft.	Rs.	1141.00
------	------------	--------	---------	---------	-----	---------

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty.	71.88 Cft	at Rs.	11288.75	P.%cft.	Rs.	8114.00
------	-----------	--------	----------	---------	-----	---------

a)Ratio 1:2:4

Qty.	244.38 Cft	at Rs.	14429.25	P.%cft.	Rs.	35261.00
------	------------	--------	----------	---------	-----	----------

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty.	575.00 Sft	at Rs.	3127.41	P.%sft.	Rs.	17983.00
------	------------	--------	---------	---------	-----	----------

4)Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles) (a)R.C. work in roof slab beams columns rafts lintels and other structural member laid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty.	30.12 Cft	atRs.	337.00	P.cft.	Rs.	10150.00
------	-----------	-------	--------	--------	-----	----------

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty.	1.21 Cwt	at Rs.	5001.70	P.cwt.	Rs.	6052.00
------	----------	--------	---------	--------	-----	---------

	Total Part-I	Rs.	78701.00
--	---------------------	------------	-----------------

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Qty.	1530.00 cft.	at Rs.	7142.70	P%0cft.	Rs.	10928.00
------	--------------	--------	---------	---------	-----	----------

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty.	1530.00 cft.	at Rs.	354.00	P%0cft.	Rs.	542.00
------	--------------	--------	--------	---------	-----	--------

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty.	1530.00 sft.	at Rs.	199.77	Rs.	305648.00
------	--------------	--------	--------	-----	-----------

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty.	42.08 cft.	at Rs.	11288.75	P.%cft.	Rs.	4750.00
------	------------	--------	----------	---------	-----	---------

(b) Ratio 1:2:4

Qty.	42.50 cft.	at Rs.	14429.25	P.%cft.	Rs.	6132.00
------	------------	--------	----------	---------	-----	---------

5) Erection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty.	85.00 Cft	at Rs.	3127.41	P.%sft.	Rs.	2658.00
------	-----------	--------	---------	---------	-----	---------

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty.	382.50 Cft	at Rs.	1800.00	P.%sft.	Rs.	6885.00
------	------------	--------	---------	---------	-----	---------

Total Part-I Rft					Rs.	337543.00
-------------------------	--	--	--	--	------------	------------------

ABSTRACT

Sub-Work No. 1	Drains	Rs.	78701.00
----------------	--------	-----	----------

Sub-Work No. 2	Paving Blocks	Rs.	337543.00
----------------	---------------	-----	-----------

Total			Rs.	416244.00
--------------	--	--	------------	------------------

CONTRACTOR


 Sub-Engineer
 Town Committee
 Bagirji

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Paver Block Flooring and drains at Ward No. 1 & 2 Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh at _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


TOWN OFFICER
Town Committee Bagirji
Taluka New Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Paver Block Flooring and drains at Ward No. 1 & 2 Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 10
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee Bagirji
Taluk Bagirji Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Paver Block Flooring and drains at Madir to Umer Kot Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 359.38 Cft at Rs. 3176.25 P.%0cft. Rs. 1141.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 71.88 Cft at Rs. 11288.75 P.%cft. Rs. 8114.00

a)Ratio 1:2:4

Qty. 244.38 Cft at Rs. 14429.25 P.%cft. Rs. 35261.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 575.00 Sft at Rs. 3127.41 P.%sft. Rs. 17983.00

4)Reinforced cement concrete work including all labour and materialexcept the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles)(a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings includiug cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 78701.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Qty. 1530.00 cft at Rs. 7142.70 P%0cft. Rs. 10928.00

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1530.00 cft. at Rs. 354.00 P%0cft. Rs. 542.00

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty. 1530.00 sft. at Rs. 199.77 1 Rs. 305648.00

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty. 42.08 cft. at Rs. 11288.75 P.%cft. Rs. 4750.00

(b) Ratio 1:2:4

Qty. 42.50 cft. at Rs. 14429.25 P.%cft. Rs. 6132.00

5) Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty. 85.00 Cft at Rs. 3127.41 P.%sft. Rs. 2658.00

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty. 382.50 Cft at Rs. 1800.00 P.%sft. Rs. 6885.00

Total Part-I Rft 337543.00

ABSTRACT

Sub-Work No. 1 Drains Rs. 78701.00

Sub-Work No. 2 Paving Blocks Rs. 337543.00

Total Rs. 416244.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Desilting of Drainage Wall and open surface drains for various places of Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.600 Million
3. Earnest Money @ (2%)	0.012 Million
4. Percentage if any to be deducted from Bill 8%	0.048 Million
5. Security deposit @ 10% Including Earnest Money	0.060 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh at _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR



**Town Officer
Town Committee
Bagirji
Taluka New Sukkur**

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Desilting of Drainage Wall and open surface drains for various places of Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.60 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 11
20.1(a)	Dealine for submission of bids:-	Office of the Town Officer, Town Committee Bagirji.
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


Town Officer
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Desilting of Drainage Wall and open surface drains for various places of Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 312.50 Cft at Rs. 3176.25 P.%0cft. Rs. 993.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 62.50 Cft at Rs. 11288.75 P.%cft. Rs. 7055.00

a)Ratio 1:2:4

Qty. 212.50 Cft at Rs. 14429.25 P.%cft. Rs. 30662.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 500.00 Sft at Rs. 3127.41 P.%sft. Rs. 15637.00

4)Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles)(a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement 2cft.sand

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars. (C.S.I.No.8(b)

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 70549.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Qty. 1962.00 cft. at Rs. 7142.70 P%0cft. Rs. 14014.00

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1962.00 cft. at Rs. 354.00 P%0cft. Rs. 695.00

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape with natural Colours, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty. 1962.00 sft. at Rs. 199.77 | Rs. 391949.00

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty. 53.96 cft. at Rs. 11288.75 P.%cft. Rs. 6091.00

(b) Ratio 1:2:4

Qty. 54.50 cft. at Rs. 14429.25 P.%cft. Rs. 7864.00

5) Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty. 109.00 Cft at Rs. 3127.41 P.%sft. Rs. 3409.00

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty. 490.50 Cft at Rs. 1800.00 P.%sft. Rs. 8829.00

Total Part-I Rft 432851.00


ABSTRACT

Sub-Work No. 1 Drains Rs. 70549.00

Sub-Work No. 2 Paving Blocks Rs. 432851.00

Total Rs. 503400.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Pver Block Remaining streets of the Ward No. 3 Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____

**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.500 Million
3. Earnest Money @ (2%)	0.010 Million
4. Percentage if any to be deducted from Bill 8%	0.040 Million
5. Security deposit @ 10% Including Earnest Money	0.050 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


TOWN OFFICER
Town Committee Bagirji
Taluka Near Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Pver Block Remaining streets of the Ward No. 3 Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.50 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1	Furnish and Technical Proposal (in case	Single Stage / Single Envelope
(b)	of two envelope method) of Company	
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 12
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


TOWN OFFICER
Town Committee Bagirji
Taluka New Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Pver Block Remaining streets of the Ward No. 3 Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 250.00 Cft at Rs. 3176.25 P.%cft. Rs. 794.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 50.00 Cft at Rs. 11288.75 P.%cft. Rs. 5644.00

a)Ratio 1:2:4

Qty. 170.00 Cft at Rs. 14429.25 P.%cft. Rs. 24530.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 400.00 Sft at Rs. 3127.41 P.%sft. Rs. 12510.00

4)Reinforced cement concrete work including all labour and materialexcept the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles)(a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings includiug cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 59680.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Qty. 1620.00 cft. at Rs. 7142.70 P%0cft. Rs. 11571.00

2)Earth work compaction (soft,Ordinary or hard soil)(a)Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 1620.00 cft. at Rs. 354.00 P%0cft. Rs. 573.00

3)Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete.(C.S.I. No.71 P.No.49)

Qty. 1620.00 sft. at Rs. 199.77 | Rs. 323627.00

4)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 44.55 cft. at Rs. 11288.75 P.%cft. Rs. 5029.00

(b)Ratio 1:2:4

Qty. 45.00 cft. at Rs. 14429.25 P.%cft. Rs. 6493.00

5)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (

(a) Vertical

Qty. 90.00 Cft at Rs. 3127.41 P.%sft. Rs. 2815.00

6)Hard Murrum or fine powdery murrum(SMI No.71)

Qty. 405.00 Cft at Rs. 1800.00 P.%sft. Rs. 7290.00

Total Part-I Rft 357398.00


ABSTRACT

Sub-Work No. 1 Drains Rs. 59680.00

Sub-Work No. 2 Paving Blocks Rs. 357398.00

Total Rs. 417078.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji

OFFICE OF THE TOWN OFFICER

TOWN COMMITTEE BAGIRJI

Name of Work: **Construction of Drains Daya House to House of Moor Shaikh Town Committee Bagirji**

Name of Firm / Contractor

To whom tender issued: _____

Tender fee received vide D.R No: _____ dated: _____


**Town Officer
Town Committee
Bagirji**

MEMORANDUM

1. General description	As Above
2. Estimate Cost	0.700 Million
3. Earnest Money @ (2%)	0.014 Million
4. Percentage if any to be deducted from Bill 8%	0.056 Million
5. Security deposit @ 10% Including Earnest Money	0.070 Million
6. Time of completion.	12 Months

We hereby tender for the execution of the above work for the Government of Sindh @ _____ percent above/below the schedule rates at entered in the schedule "B" in tender. Rates specified in schedule "B" to be carried out in accordance with specification, design, drawing and instruction of Engineer Incharge etc. I shall execute the agreement on proper printed form in case the tender is accepted. Earnest money in the shape of Call deposit vide No. _____ dated _____ for Rs. _____ of _____ Bank Limited.

CONTRACTOR


Town Officer
Town Committee
Bagirji
Taluk Bagirji Sukkur

CONTRACT / BIDDING DATA.

The following specific data for the works to be tendered shall complement, amend, or supplement the provisions in the Instructions to Bidders. Whatever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.

Clause Reference

1.1	Name and Address of the Procuring Agency :-	Office of the Town Officer, Town Committee Bagirji.
1.2	Name of the Project and Summary of the Work:-	Construction of Drains Daya House to House of Moor Shaikh Town Committee Bagirji
2.1	Name of the Borrower/Source of Financing / Funding Agency / Funding	Government of Sindh
2.1	Amount and type of Financing / Scheme Cost and Allocation Funds:-	Rs. 0.70 Govt: of Sindh Allocation Rs. 5.00 Million
8.1	Time limit for clarification:-	Three days prior to submission of bids.
10.1	Bid Language:-	English
11.1 (a)	Prequalification Information to be	Company profile.
11.1 (b)	Furnish and Technical Proposal (in case of two envelope method) of Company	Single Stage / Single Envelope
13.1	Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency the require, if applicable:-	Pakistan Rupees.
14.1	Period of Bid Validity:-	90 Days
15.1	Amoun of Bid Security:-	2% Bid Price
17.1	Venue, time and date of the Pre-Bid meeting:-	N/A
18.4	Number of copies of the bid to be completed and returned:-	ONE
19.2 (a)	Procuring Agency's address for the purpose of bid submission :-	As Above
(b)	Name and Identification Number of the Contract:-	Sr. No. 13
20.1(a)	Dealine for submission of bids:-	
(b)	Venue, time and date of bid opening :-	Office of the Town Officer, Town Committee Bagirji.
32.1	Standard form and amount of	5% to be deducted from Payment
32.3	Stamp duty:-	0.3% will be paid by successful bidder as stamp duty.


TOWN OFFICER
Town Committee Bagirji
Taluka Bagirji
Sukkur

SCHEDULE "B"

NAME OF WORK: Construction of Drains Daya House to House of Moor Shaikh Town Committee Bagirji

HEAD OF ACCOUNT:

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

Sub-Work No. 1

Drains

Part-I Schedule Items

1)Excavation In foundation of Building Bridges and and other structures including dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 feet (a) In ordinary soil(C.S.I.No.18(b)P.No.4)

Qty. 468.75 Cft at Rs. 3176.25 P.%cft. Rs. 1489.00

2)Cement concrete plain including placing compacting finishing and curing complete(including screening and washing ofstone aggregate without shuttering (C.S.I.No.5 P.No.16)

a)Ratio 1:4:8

Qty. 93.75 Cft at Rs. 11288.75 P.%cft. Rs. 10583.00

a)Ratio 1:2:4

Qty. 318.75 Cft at Rs. 14429.25 P.%cft. Rs. 45993.00

3)Errection and removal of centering for R.C.C. or Plain cement concrete work of Partal wood. (C.S.I.No.18(b) P.No.21)

(a) Vertical

Qty. 750.00 Sft at Rs. 3127.41 P.%sft. Rs. 23456.00

4)Reinforced cement concrete work including all labour and materialexcept the cost of steel reinforcement and its labour for bending and binding ,witch will be paid separately .This rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingles) (a)R.C. work in roof slab beams columns rafts lintels and other structural memberlaid in situ or precast laid in position complete in all respests (i)Ratio (1:2:4)90Lbs cement

Qty. 30.12 Cft atRs. 337.00 P.cft. Rs. 10150.00

5)Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars). (b) using Tor bars.

Qty. 1.21 Cwt at Rs. 5001.70 P.cwt. Rs. 6052.00

Total Part-I Rs. 97723.00

Sub-Work No.2 Paving Block Flooring

Part-I Schedule Items

1)Barrow pit excavation undressed lead upto 100 ft. (b)In Ordinary soil with three miles extra lead.(C.S.I.No.3P.No.1)

Qty. 2205.00 cft. at Rs. 7142.70 P%0cft. Rs. 15750.00

2) Earth work compaction (soft, Ordinary or hard soil) (a) Laying earth in 6" layers levelling and dressing complete. (C.S.I.No.13(a) P.No.3)

Qty. 2205.00 cft. at Rs. 354.00 P%0cft. Rs. 781.00

3) Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape **with natural Colours**, having strength b/w 5000 psi to 8500 psi I/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (C.S.I. No.71 P.No.49)

Qty. 2205.00 sft. at Rs. 199.77 | Rs. 440493.00

4) Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering. (C.S.I.No.5 P.No.16)

a) Ratio 1:4:8

Qty. 60.64 cft. at Rs. 11288.75 P.%cft. Rs. 6845.00

(b) Ratio 1:2:4

Qty. 61.25 cft. at Rs. 14429.25 P.%cft. Rs. 8838.00

5) Erection and removal of centering for R.C.C. or Plain cement concrete work of Partial wood. (

(a) Vertical

Qty. 122.50 Cft at Rs. 3127.41 P.%sft. Rs. 3831.00

6) Hard Murrum or fine powdery murrum (SMI No.71)

Qty. 551.25 Cft at Rs. 1800.00 P.%sft. Rs. 9923.00

Total Part-I Rft 486461.00

ABSTRACT

Sub-Work No. 1 Drains Rs. 97723.00

Sub-Work No. 2 Paving Blocks Rs. 486461.00

Total Rs. 584184.00

CONTRACTOR


Sub-Engineer
Town Committee
Bagirji