


**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DISTRICT CENTRAL,  
SCHOOL EDUCATION & LITERACY DEPARTMENT, GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. \_\_\_\_\_, Government Contractor,  
and charged Rs. 3000/= Vide D.R. No. \_\_\_\_\_, Dated: \_\_\_\_\_

  
**EXECUTIVE ENGINEER  
EDUCATION WORKS DISTRICT CENTRAL  
KARACHI**

**NAME OF WORK:-** ESTABLISHMENT OF GOVERNMENT BOYS / GIRLS DEGREE COLLEGES IN SINDH (23 UNITS) (ADP NO. 484 OF 2017-2018) @ GULSHAN-E-MAYMAR SHIFTED TO SECTOR 5/A-3 NORTH KARACHI (GROUND FLOOR REMAINING WORK / FIRST FLOOR / COMPOUND WALL REMAINING WORK / EXTERNAL DEVELOPMENT / ALLIED WORKS)

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the underwritten memorandum within the time modified in each memorandum at:

Part-A-i: @ \_\_\_\_\_ (Above / Below),

Part-A-ii: Rs. \_\_\_\_\_

Part-B-i: @ \_\_\_\_\_ (Above / Below),

Part-B-ii: Rs. \_\_\_\_\_

Part-C-i: @ \_\_\_\_\_ (Above / Below),

Part-C-ii: Rs. \_\_\_\_\_

Part-D-i: @ \_\_\_\_\_ (Above / Below),

Part-D-ii: Rs. \_\_\_\_\_

Part-E-i: @ \_\_\_\_\_ (Above / Below),

Part-E-ii: Rs. \_\_\_\_\_

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

**GENERAL DESCRIPTION:**

i.	Estimated Cost	:-	Category C-5 limit from 25 Million to 65 Million
ii.	Bid Security / Earnest Money 5%	:-	5% of Total Bid Price
iii.	Total Deduction 10% (S/D-5% & E/M-5%)	:-	10% of Total Bid Price
iv.	Income Tax (7.50%)	:-	7.50% of Gross Amount from every Running Account Bill
v.	Time allowed for completion of work	:-	12 Months

**EXECUTIVE ENGINEER  
EDUCATION WORKS DISTRICT CENTRAL  
KARACHI**

**CONTRACTOR'S UNDERTAKING**

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

Schedule-A:

Nil

Schedule-B:

Attached herewith

(SIGNATURE OF CONTRACTOR)

## Schedule "B"

NAME OF WORK:-

**ESTABLISHMENT OF GOVT. GIRLS DEGREE COLLEGE GULSHAN-E-MAYMAR  
SHIFTED TO SECTOR 5-A/3, NORTH KARACHI. (GROUND FLOOR REMAINING WORK)  
(ADP No: 484 / 2017-2018)**

S.No	Description.	Qty	Rate	Unit	Amount
------	--------------	-----	------	------	--------

### Schedule Items

1	P/L 1:3:6 C.C SOLID BLOCK MASONARY WALL 6" BELOW IN THICKNESS SET IN 1:6 C.M IN G.F. SUPER STRUCTURE I/C RAKING OUTJOINTS & CURING ETC. COMPLETE. (S.I.NO: 23/P-22)	1541.73	@Rs 15771.01	% Cft	243,146.00
2	CEMENT PLASTER 1:4 UPTO 20 HEIGHT (C) 3/4" THICK. (S.I.NO.11(c) P-58)	5478.61	@Rs 3015.76	% Sft	165,222.00
3	Precast Reinforcement cement concrete in columns beams lintel stair case shelves etc (S.I.6-b-i/17)	21.28	@Rs 309.78	P.Cft	6,592.00
4	P/F with jute felt paper of 60 Lbs over roof in/c cleaning of roof with wire brush and removing dust applying bitumen coat @ 34 Lbs per %Sft as premix intercoat and then laying felt paper with 10% over labs then applying and spreading hill sand @ of 1Cft for %Sft the cost also in/c necessary fire material kerosene oil wood etc (S.I.39/42)	133.00	@Rs 106.73	P.Sft	14,195.00
5	P/F IRON STEEL GRILL USING SOLID SQUARE BARS OF SIZE 1/2"x1/2" PLACED AT 4" IN/C & FRAME OF FLAT IRON PATTI OF 3/4"x3/4" IN/C CIRCLE SHAPE AT 1-0 APART EQUIVALENT FITTED WITH SCREWS ARE PINS IN/C PAINTING 3 COATS WITH 1ST COAT OF RED OXIDE PAINT ETC. (S.I.NO. 30 P-94).	100.00	@Rs 194.16	P.sft	19,416.00
6	P/F IRON COLLAPSIBLE GATE WITH CHANNEL FRAMING OF SECTION 3/4" x 5/16" AT 4" IN/C REVITTED WITH 3/4" x 1/8" FLAT IRON PATTI PLACED DIAGONALLY & PROVIDED WITH TOP & BOTTOM T-SECTION 1" x 1" x 1/8" ALONGWITH ROLLERS ALSO IN/C LOCKING ARRANGEMENT & FIXING IN FLOOR / CEILING OR WALL ETC. COMPLETED. (S.I. 32/P-94)	128.00	@Rs 387.04	P.sft	49,541.00
7	S/F in position iron/steel grill door with angle iron frame of 1-1/2"x1-1/2"x1/4" and flat iron of 3/4"x1/4"with approved design and locking arrangement embeded in masonry as per instruction of Engineer/Incharge (S.I.31P-94)	48.00	@Rs 231.60	P.Sft	11,117.00
8	M/F grating in opening in/c fixing at site with flat iron 2"x3/8" and 3/4" square bar @ 4"centre to centre(S.I.92/25)	163.50	@Rs 293.15	P sft	47,930.00
9	Hard wood railing of any shape and design in/c bend and corner fixed in position in/c polishing as directed (S.I.62/30-a)	66.00	@Rs 375.75	PRft	24,800.00
10	P/F Aluminium sheet 6" to 9" with V Notch for expension joint in/c fixing with nails/screws (S.I.88/P-109)	62.50	@Rs 207.51	P.Rft	12,969.00
11	P/F G.I Expanded metal 3/32 ( 20 - guage ) fixed to chowkhats. (S.I. No. 67-B/P-66)	1540.00	@Rs 60.43	P.sft	93,062.00
12	FIRST CLASS DEODAR WOOD WROUGHT JOINERY IN DOORS AND WINDOWSTC FIXED IN POSITION INCLUDING CHOWKHATS HOLD FAST HINGES IRON TOWER BOLT CHOKTS CLEATS HANDLES CORDS WITH HOOKS ETC DEODAR PANELLED OR PANELLED AND GLAZED OR FULLY GLAZED (ONLY SHUTTERS). (S.I.58/7-b)	100.00	@Rs 902.93	P.Sft	90,293.00

13	P/F WITH SUNKUN IRON SCREWS WOODEN ARCHITRAVE APPROVED DESIGN /SHAPEMHAVING WIDTH NOT LESS THAN 2-1/2 INCHES AS DIRECTED BY ENGINEER INCHARGE (S.I.NO.60/P-66).	747.00	@Rs 49.97	P.Rft	37,328.00
14	P/F Deodar Almirah 9"- 12" depth in/c boxing with back shelves shutters rafts fitting colmlete (P.No. 61 /23)	150.00	@Rs 1778.50	P.sft	266,775.00
15	S/F IN POSITION ALUMINIUM CHANNELS FRAMING FOR SLIDING WINDOW & VENTILATORS OF ALCOP MADE WITH 5mm THICK TINTED GLASS GLAZING (BELGIUM) ETC COMPLETE. (S.I. 85/P-108) DELUXE MODEL (BRONZE)	150.00	@Rs 1449.69	P.Sft	217,454.00
16	PROVIDING AND LAYING TOPPING CEMENT CONCRETE 1:2:4 INCLUDING SURFACE FINISHING AND DIVIDING INTO PANELLS 2" THICK. (S.I. 16-C / P-47)	14442.38	@Rs 3275.50	% Sft	473,060.00
17	REINFORCEMENT CEMENT CONCRETE SPOUT (S.I.NO.13 P-21 ).	65	@Rs 261.25	Each	16,981.00
18	TWO COAT OF BITUMEN LAID HOT USING 34LBS FOR % SFT OVER ROOF BLINDED WITH SAND AT ONE PART CFT PER SFT (S.I. 13/P-40).	14442.38	@Rs 1887.40	%Sft	272,585.00
19	Split tile 1/4"thick matt glazed or double glazed jointed in white cement and lead over 1:2 grey cement sand mortar 3/4"thick in/c finishing complete (Flooring and Facing)(S.I.49/69)	3571.78	@Rs 21021.11	% Sft	750,828.00
20	PRIMARY COAT OF CHALK UNDER DISTEMPER (S.I.NO.23/P-54)	2595.00	@Rs 442.75	%Sft	11,489.00
21	DISTEMPERING THREE COATS (S.I.NO.24-C/P-54).	14442.38	@Rs 1079.65	%Sft	155,927.00
22	Painting new surface and painting gurd bars, gates of iron bars, gratings, railings (in/c standard braces, etc ) 3 coats. ( S.I No.4-d/P70).	1831.50	@Rs 1645.27	%Sft	30,133.00
23	Painting new surfaces (c) Preparing surface and painting of doors and windows any type (including edges) 3 coats. (S.I.No. 5(c)/I&ii/C-11)	200.00	@Rs 2116.41	%Sft	4,233.00
24	French Polish Complete on new work. ( S.I No.7-a/P-71).	300.00	@Rs 3841.75	%Sft	11,525.00

% Above / Below

Total 3026601.00

Contractor

*Handwritten Signature*  
EXECUTIVE ENGINEER  
EDUCATION WORKS DISTRICT CENTRAL  
GOVT. OF SINDH, KARACHI



### Schedule "B"

NAME OF WORK:-


ESTABLISHMENT OF GOVT. GIRLS DEGREE COLLEGE GULSHAN-E-MAYMAR  
SHIFTED TO SECTOR 5-A/3, NORTH KARACHI. (GROUND FLOOR REMAINING WORK)  
(ADP No: 484 / 2017-2018)

S.No	Description.	Qty	Rate	Unit	Amount
------	--------------	-----	------	------	--------

#### Non Schedule Items

1	P/L Marble flooring tiles of Botisina/China Verona size (12"x12"x3/4") fine dressed on the surface without winding set in grey cement laid over 3/4" thick bed of 1:2 grey cement mortar setting the tiles with grey cement slurry jointing and washing finishing tiles with slurry of white cement in/c pigment to match the colour of tiles in/c curring grinding rubbing and chemical polish etc complete as directed by Engineer Incharge (R.A.Approved)	204.00	@Rs 310.43	P.sft	63,328.00
2	P/F FLOOR OF VENORA MARBLE TILE OF SIZE 48"x12x3/4" FINE DRESSED ON THE SURFACE WITHOUT WINDING SET IN WHITE CEMENT LAID OVER 3/4" THICK BED OF 1:2 GREY CEMENT MORTAR SETTING THE TILES WITH GREY CEMENT SLURRY, GROUTING AND WASHING THE TILES WITH SLURRY OF WHITE CEMENT AND PIGMENT TO MATCH THE COLOUR OF TILES, IN/C CURRING, GRINDING, RUBBING AND CHEMICAL POLISHING ETC, COMPLETE I/C CUTTING TILES TO PROPER PROFILE (R.A.APPROVED)	182.50	@Rs 395.00	P.sft	72,088.00
3	P/L PROCELENCE TILE GLAZED AND POLISHED 2X2X5/16 ON FLOOR OR WALL FACING IN REQUIRED COLOUR AND PATTERN IN WHITE CEMENT SAND PIGMENT OVER A BASE OF 1:2 GREY CEMENT MORTAR 3/4" THICK IN/C WASHING AND FILLING OF JOINTS WITH SLURRY OF WHITE CEMENT AND PIGMENT IN DESIRED SHAPE WITH FINISHING CLEANING AND COST OF WAX POLISH ETC COMPLETE IN/C CUTTING TILES TO PROPER PROFILE. (R.A.APPROVED)	99.00	@Rs 406.00	P.sft	40,194.00
				Total	175,610.00

Contractor

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DISTRICT CENTRAL  
GOVT. OF SINDH, KARACHI

## Schedule "B"

NAME OF WORK:-

**ESTABLISHMENT OF GOVT. GIRLS DEGREE COLLEGE GULSHAN-E-MAYMAR  
SHIFTED TO SECTOR 5-A/3, NORTH KARACHI. ( FIRST FLOOR REMAINING WORK)  
(ADP No: 484 / 2017-2018)**

S.No	Description.	Qty	Rate	Unit	Amount
------	--------------	-----	------	------	--------

### Schedule Items

1	R.C.C WORK IN/C ALL LABOUR & MATERIAL EXCEPT THE COST OF STEEL R/F & BENDING & BINDING WHICH WILL BE PAID SEPARATELY. R.C.C WORK ROOF SLAB BEAMS COLUMNS RAFTS LINTEL AND OTHER STRUCTURE MEMBER LAID IN SITU OR PRE CAST LAID IN POSITION COMPLETE IN ALL RESPECT <u>RATIO 1:2:4</u> . (S.I.6-A-II/P-18)	6599.46	@Rs 337.00	P Cft	2,224,019.00
2	FABRICATION OF STEEL R/F FOR C.C IN/C CUTTING BENDING LAYING IN POSITION MAKING AND FASTENING IN/C COST OF BINDING WIRE (ALSO IN/C REMOVAL OF RUST FROM BARS)(S.I.NO.7 (A & B)/P-20) ( Deformed Bars)	441.93	@Rs 5001.70	P.Cwt	2,210,401.00
3	Precast Reinforcement cement concrete in columns beams lintel stair case shelves etc (S.I.6-b-i/17)	21.44	@Rs 309.78	P.Cft	6,642.00
4	ERRECTION & REMOVAL OF VERTICAL CENTERING FOR R.C.C PLAIN OR CEMENT CONCRETE WORK OF PARTIAL WOOD (2ND CLASS) (S.I.18-B/P-21).	560.70	@Rs 3127.41	% Sft	17,535.00
5	CEMENT CONCRETE PLAIN IN/C PLACING COMPACTING FINISHING CURING COMPLETE & SCREENING & WASHING OF STONE AGGREGATE WITHOUT SHUTTERING RATIO 1:3:6 (S.I.NO.5-H P-18).	141.00	@Rs 12595.00	% Cft	17,759.00
6	P/L 1:3:6 C.C SOLID BLOCK MASONARY WALL 6" BELOW IN THICKNESS SET IN 1:6 C.M IN G.F. SUPER STRUCTURE I/C RAKING OUTJOINTS & CURING ETC. COMPLETE. (S.I.NO: 23/P-22)	2193.24	@Rs 15771.01	% Cft	345,896.00
7	P/F G.I. FRAMES / CHOWKATS OF SIZE 7"x2" OR 4-1/2"x3" FOR DOORS USING 20 GAUGE G.I. SHEET IN/C WELDED HINGES & FIXING AT SITE WITH NECESSARY HOLD FASTS, FILLING WITH CEMENT SAND SLURRY OF RATIO 1:6 & REPAIRING THE JAMBS. THE COST ALSO IN/C ALL CARRIAGE TOOLS AND PLANTS IN MAKING AND FIXING. (S.I.29/P-93)	274.62	@Rs 228.90	P.Rft	62,861.00
8	P/F G.I frames / Chowkats of size 7"x2" or 4-1/2" x 3" for Windows using 20 gauge G.I. sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage tools and plants used making and fixing.(S.I.No: 28/P-93)	56.00	@Rs 240.50	P.Rft	13,468.00
9	CEMENT PLASTER 1:4 UPTO 20 HEIGHT (C) 3/4" THICK. (S.I.11-C/P-52)	14918.28	@Rs 3015.76	% Sft	449,900.00
10	Extra Labour rate for making Grooves of 1"x1/4" or 3/4"x1/2" plaster surface with trou egde both vetically and horizontally with uniform depth and with grooves base smoothly finished etc complete as per instruction of engineer / incharge .(S.I.No:34/P-55)	994.00	@Rs 7.31	P.Rft	7,266.00
11	DAMP PROOF COURSE WITH ( CEMENT SAND AND SHINGLE CONCRETE 1:2:4 ) INCLUDING 2 COATS OF ASPHALTIC MIXTURE 3" THICK.(S.I.19/28-c)	200.00	@Rs 4982.18	% Sft	9,964.00
12	VERTICAL DAMP PROOF COURSE OF 3/4" THICK CEMENT PLASTER 1:2 WITH BITUMEN AT ( 20 Lbs PER % Sft ).(S.I.107/70)	228.0	@Rs 2760.99	% Sft	6,295.00

13	Notice board made with cement. (S.I.No.1/P-95)	256.00	@Rs 58.11	P.Sft	14,876.00
14	FIRST CLASS DEODAR WOOD WROUGHT JOINERY IN DOORS AND WINDOWSTC FIXED IN POSITION INCLUDING CHOWKHATS HOLD FAST HINGES IRON TOWER BOLT CHOKTS CLEATS HANDLES CORDS WITH HOOKS ETC DEODAR PANELLED OR PANELLED AND GLAZED OR FULLY GLAZED (ONLY SHUTTERS). (S.I.58/7-b)	50.50	@Rs 902.93	P.Sft	45,598.00
15	P/F in position doors windows and ventilator of 1st Class deodar wood frame and 1-1/2" thick teak wood ply shutter of 2nd class deodar wood skilton solid stile and rails core of partial wood and teak ply wood 3 Ply on both sides in/c hold fasts hinges iron tower bolts handle cleats with cord etc complete (Only Shutters) (P.No.65/57)	255.50	@Rs 875.13	P.sft	223,596.00
16	S/F IN POSITION ALUMINIUM CHANNELS FRAMING FOR SLIDING WINDOW & VENTILATORS OF ALGOP MADE WITH 5mm THICK TINTED GLASS GLAZING (BELGIUM) ETC COMPLETE. (S.I. 85/P-108) DELUXE MODEL (BRONZE)	456.00	@Rs 1449.69	P.Sft	661,059.00
17	P/F WITH SUNKUN IRON SCREWS WOODEN ARCHITRAVE APPROVED DESIGN /SHAPEMHAVING WIDTH NOT LESS THAN 2-1/2 INCHES AS DIRECTED BY ENGINEER INCHARGE (S.I.NO.66/60).	646.50	@Rs 49.97	P.Rft	32,306.00
18	P/F IRON STEEL GRILL USING SOLID SQUARE BARS OF SIZE 1/2"x1/2" PLACED AT 4" IN/C & FRAME OF FLAT IRON PATTI OF 3/4"x3/4" IN/C CIRCLE SHAPE AT 1-0 APART EQUIVALENT FITTED WITH SCREWS ARE PINS IN/C PAINTING 3 COATS WITH 1ST COAT OF RED OXIDE PAINT ETC. (S.I.NO. 30 P-94).	634.50	@Rs 194.16	P.sft	123,195.00
19	P/F IRON COLLAPSIBLE GATE WITH CHANNEL FRAMING OF SECTION 3/4" x 5/16" AT 4" IN/C REVITTED WITH 3/4" x 1/8" FLAT IRON PATTI PLACED DIAGONALLY & PROVIDED WITH TOP & BOTTOM T-SECTION 1" x 1" x 1/8" ALONGWITH ROLLERS ALSO IN/C LOCKING ARRANGEMENT & FIXING IN FLOOR / CEILING OR WALL ETC. COMPLETED. (S.I. 32/P-94)	1194.00	@Rs 387.04	P.sft	462,126.00
20	S/F in position iron/steel grill door with angle iron frame of 1-1/2"x1-1/2"x1/4" and flat iron of 3/4"x1/4"with approved design and locking arrangement embeded in masonry as per instruction of Engineer/Incharge (S.I.31P-94)	104.00	@Rs 231.60	P.Sft	24,086.00
21	M/F grating in opening in/c fixing at site with flat iron 2"x3/8" and 3/4" square bar @ 4"centre to centre(S.I.92/25)	163.50	@Rs 293.15	P.sft	47,930.00
22	P/F G.I Expanded metal 3/32 ( 20 - guage ) fixed to chowkhats. (S.I. No. 67-B/P-66)	360.00	@Rs 60.43	P.sft	21,755.00
23	Hard wood railing of any shape and design in/c bend and corner fixed in position in/c polishing as directed (S.I.62/30-a)	66.00	@Rs 375.75	PRft	24,800.00
24	P/F Aluminum Sheet on doors pasted with glue as per requirement (S.I. No. 61/P-66)	67.50	@Rs 63.77	P.sft	4,304.00
25	P/F Aluminium sheet 6" to 9" with V Notch for expension joint in/c fixing with nails/screws (S.I.109/88)	59.00	@Rs 207.51	P.Rft	12,243.00
26	PROVIDING AND LAYING TOPPING CEMENT CONCRETE 1:2:4 INCLUDING SURFACE FINISHING AND DIVIDING INTO PANELLS 2" THICK. (S.I. 16-C / P-47)	6384.25	@Rs 3275.50	% Sft	209,116.00



27	P/F with jute felt paper of 60 Lbs over roof in/c cleaning of roof with wire brush and removing dust applying bitumen coat @ 34 Lbs per %Sft as premix intercoat and then laying felt paper with 10% over labs then applying and spreading hill sand @ of 1Cft for %Sft the cost also in/c necessary fire material kerosene oil wood etc (S.I.39/42)	134.00	@Rs 106.73	P.Sft	14,302.00
28	TWO COAT OF BITUMEN LAID HOT USING 34LBS FOR % SFT OVER ROOF BLINDED WITH SAND AT ONE PART CFT PER SFT (S.I. 13/P-40).	6384.25	@Rs 1887.40	%Sft	120,496.00
29	REINFORCEMENT CEMENT CONCRETE SPOUT (S.I.NO.13 P-21 ).	28	@Rs 261.25	Each	7,315.00
30	Split tile 1/4"thick matt glazed or double glazed jointed in white cement and lead over 1:2 grey cement sand mortar 3/4"thick in/c finishing complete (Flooring and Facing)(S.I.49/69)	7099.70	@Rs 21021.11	% Sft	1,492,435.00
31	Glazed tile dado 1/4" thick laid in pigment over 1:2 cement sand mortar 3/4" thick 1/c finishing.(S.I.No: 38/P-45)	745.50	@Rs 28299.30	% Sft	210,971.00
32	Laying floor of approved Coloured glazed tile 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 complete.(S.I.No: 25/ P-43).	228.50	@Rs 27747.06	% Sft	63,402.00
33	PRIMARY COAT OF CHALK UNDER DISTEMPER (S.I.NO.23/P-54)	7642.78	@Rs 442.75	%Sft	33,838.00
34	DISTEMPERING THREE COATS (S.I.NO.24-C/P-54).	7642.78	@Rs 1079.65	%Sft	82,515.00
35	Preparing the surface and painting with plastic emulsion of approved make in/c rubbing the surface with sand paper filling the wides with chalks, plaster of paris and then painting etc complete. (S.I.40/P-56)	6951.25	@Rs 1659.35	%Sft	115,346.00
36	Painting new surfaces (c) Preparing surface and painting of doors and windows any type (including edges) 3 coats. (S.I.No. 5(c)/I&ii/C-11)	101.00	@Rs 2116.41	%Sft	2,138.00
37	French Polish Complete on new work. ( S.I No.7-a/P-71).	511.00	@Rs 3841.75	%Sft	19,631.00
38	Painting new surface and painting gurd bars, gates of iron bars, gratings, railings (in/c standard braces, etc ) 3 coats. ( S.I No.4-d/P70).	1461.50	@Rs 1645.27	%Sft	24,046.00
39	P/F COLOUR CREATE TO WALL SURFACE TO PROVIDE, DURABLE CRUST AND AESTHETICS HAVING THICKNESS UPTO 3/4" WITH SPECIFIED COLOUR HAVING WATER, FIRE & TERMITE RESISTANCE (UPTO 20' HEIGHT) (S.I.NO.44/P-63).	6491.25	@Rs 6319.50	% Sft	410,215.00
40	Extra labour for R.c.c (S.I.17/6-d)	6599.46	@Rs 12.10	P.Sft	79,854.00
41	Extra labour for fabrication (S.I.19/29)	22.10	@Rs 151.25	P.Sft	3,342.00
45	Extra labour for First Floor Block Masonary (S.I.30-a /P-19 )	1580.94	@Rs 328.97	% Sft	5,201.00
43	Extra labour for Block Masonary (S.I.30-b /P-19 )	612.30	@Rs 760.03	% Sft	4,654.00

44 EXTRA LABOUR FOR EACH STORY ABOVE GROUND FLOOR FOR MOSAIC  
CONGLOMERATE OR TLES STONE AND WOODEN FLOOR (S.I.18/42)

14942.95

@Rs 226.88

% Sft

33,903.00

45 Extra labolur for bitumen 13% (S.I.35/13)

6384.25

@Rs 39.32

%Sft

2,510.00

46 EXTRA LABOUR For Plaster 13% (S.I.11-C /P-52 )

2825.78

@Rs 169.09

% Sft


4,778.00

Total

10009887.00

% Above / Below

Contractor

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DISTRICT CENTRAL  
GOVT. OF SINDH, KARACHI



## Schedule "B"

NAME OF WORK:-


ESTABLISHMENT OF GOVT. GIRLS DEGREE COLLEGE GULSHAN-E-MAYMAR  
SHIFTED TO SECTOR 5-A/3, NORTH KARACHI. ( FIRST FLOOR REMAINING WORK)  
(ADP No: 484 / 2017-2018)

S.No	Description.	Qty	Rate	Unit	Amount
------	--------------	-----	------	------	--------

### Non Schedule Items

1	P/L PROCELENCE TILE GLAZED AND POLISHED 2X2X5/16 ON FLOOR OR WALL FACING IN REQUIRED COLOUR AND PATTERN IN WHITE CEMENT SAND PIGMENT OVER A BASE OF 1:2 GREY CEMENT MORTAR 3/4" THICK IN/C WASHING AND FILLING OR JOINTS WITH SLURRY OF WHITE CEMENT AND PIGMENT IN DESIRED SHAPE WITH FINISHING CLEANING AND COST OF WAX POLISH ETC COMPLETE IN/C CUTTING TILES TO PROPER PROFILE. (R.A.APPROVED)	99.00	@Rs 406.00	P.sft	40,194.00
2	P/L Marble flooring tiles of Botisina/China Verona size (12"x12"x3/4") fine dressed on the surface without winding set in grey cement laid over 3/4" thick bed of 1:2 grey cement mortar setting the tiles with grey cement slurry jointing and washing finishing tiles with slurry of white cement in/c pigment to match the colour of tiles in/c curing grinding rubbing and chemical polish etc complete as directed by Engineer Incharge (R.A.Approved)	204.00	@Rs 310.43	P.sft	63,328.00
3	P/F FLOOR OF VENORA MARBLE TILE OF SIZE 48"x12x3/4" FINE DRESSED ON THE SURFACE WITHOUT WINDING SET IN WHITE CEMENT LAID OVER 3/4" THICK BED OF 1:2 GREY CEMENT MORTAR SETTING THE TILES WITH GREY CEMENT SLURRY, GROUTING AND WASHING THE TILES WITH SLURRY OF WHITE CEMENT AND PIGMENT TO MATCH THE COLOUR OF TILES, IN/C CURING, GRINDING, RUBBING AND CHEMICAL POLISHING ETC, COMPLETE I/C CUTTING TILES TO PROPER PROFILE (R.A.APPROVED)	182.50	@Rs 395.00	P.sft	72,088.00
				Total	175610.00

Contractor

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DISTRICT CENTRAL  
GOVT. OF SINDH, KARACHI

## Schedule "B"

NAME OF WORK:-

ESTABLISHMENT OF GOVT. GIRLS DEGREE COLLEGE GULSHAN-E-MAYMAR SHIFTED  
TO SECTOR 5-A/3, NORTH KARACHI.

(COMPOUND WALL)

(ADP NO.369)

S.No	Description.	Qty	Rate	Unit	Amount
<b>Schedule Items</b>					
1	Dismantling cement concrete solid block masonry 1:3:6.(S.I.10/14)	1290.00	@Rs 1134.38	%Cft	14,634.00
2	Excavation in foundation of building bridges and other structure i/c degabilling dressing refilling, around structure with excavated earth waterig and ramming lead upto 5 ft in ordinary soil (s.i.no:18-b/p-5).	2375.25	@Rs 3176.25	%0Cft	7,544.00
3	Cement concrete brick or stone ballast 1.5" to 2" gauge (b) Ratio 1:4:8. (S.I.No. 15/4-b)	524.88	@Rs 9416.28	% Cft	49,424.00
4	Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding wire (also includes removal of rust from bars. (S.I.No. 17/8-b)	85.14	@Rs 5001.70	P.Cwt	425,844.00
5	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs. (S.I.No. 17/6-a-i)	1252.21	@Rs 337.00	P Cft	421,994.00
6	ERRECTION & REMOVAL OF VERTICAL CENTERING FOR R.C.C PLAIN OR CEMENT CONCRETE WORK OF PARTAL WOOD (2ND CLASS) (S.I.18-B/P-21)..	2407.14	@Rs 3127.41	% Sft	75,281.00
7	CEMENT CONCRETE PLAIN IN/C PLACING COMPACTING FINISHING CURING COMPLETE & SCREENING & WASHING OF STONE AGGREGATE WITHOUT SHUTTERING RATIO 1:3:6 (S.I.NO.5H/18 45)	806.39	@Rs 12595.00	% Cft	101,565.00
8	Bitumen coating to plastered or cement concrete surface. (s.i.	288.10	@Rs 778.09	% Sft	2,242.00
9	P/L SINGLE PER LAYER OF POLYTHENE SHEET .13 MM THICK FOR WATER PROOFING AS PER SPECIFICATION AND INSTRUCTIONS OF ENGINEER INCHARGE (S.I.NO. 38/38)	288.10	@Rs 10.70	P.sft	3,083.00
10	P/I 1:3:6 c.c solid block masonry wall 6" below in thickness set in 1:6 c.m in G.F super structure I/c raking out joints & curing etc, complete. (S.I.No: 19/24)	1604.76	@Rs 15771.01	%Cft	253,087.00
11	Cement plaster 1:4 upto 20 height (c) 3/4" thick. (S.I.No.11(c)/P-52)	8720.3	@Rs 3056.62	%Sft	266,547.00
12	PREPARING THE SURFACE AND PAINTING WITH WEATHER COAT I/C RUBBING THE SURFACE WITH RUBBING BRICK / AND SAND PAPER, FILLING WITH VOIDS WITH WEATHER COAT OF APPROVED MAKE. (S.I.NO.38 A/P-56).	8740.32	@Rs 2567.95	%Sft	224,447.00
Total					1,845,692.00

% Above / Below

Contractor

*Ram*

EXECUTIVE ENGINEER  
EDUCATION WORKS DISTRICT CENTRAL