

BIDDING DATA

(This section should be filled in by the Executive Engineer Machinery Maintenance Division, (Hydrabad), Digri @ Kotdiji before issuance of the Bidding Documents).

- (a) Name of Procuring Agency:- **Executive Engineer Machinery Maintenance Division, (Hyderabad), Digri @ Kotdiji.**
- (b) Brief Description of Work:- **01) W/R & REHABILITATION OF ROAD FROM KHAIRPUR SHADI SHAHEED ROAD @ MILE 3.0 TO SHAH WARYAL OSTA GAHI ROAD VIA KHADIM HUSSAIN KATOHAR WITH LINK GOUNDARA, SONO SHAIKH AND KAJALO KATOHAR ROAD (20.00 KMS).**
- (c) Procuring Agency's address:- **Executive Engineer Machinery Maintenance Division, (Hyderabad), Digri @ Kotdiji**
- (d) Estimated Cost:- **Rs. 350.00 (M)**
- (e) Amount of Bid Security:- **05% Rs. 17.50 (M)**
- (f) Period of Bid validity (days):- **90 Days**
- (g) Security Deposit (including bid security):- **08% Rs. 28.00 (M)**
- (h) Percentage if any, to be deducted from bills:- **10.50%Rs. 36.750 (M)**
(Income Tax)
- (i) Deadline for submission of Bids along with time:- **16-04-2018**
- (j) Venue, Time and Date of Bid Opening:- **16-04-2018**
- (k) Time for Completion from written order of commence:- **24 Months**
- (l) Liquidity damages:- **0.5% Rs. 1750000/-**
- (m) Deposit Receipt No. _____ Date _____ Amount _____
- (n) D.R No. _____ Date & Amount _____ Rs. _____
- (o) Tender issued to _____

(Executive Engineer / Authority issuing bidding document)

**EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI**

FORM OF BID

Bid Reference No. 01) **W/R & REHABILITATION OF ROAD FROM KHAIRPUR SHADI SHAHEED ROAD @ MILE 3.0 TO SHAH WARYAL OSTA GAHI ROAD VIA KHADIM HUSSAIN KATOHAR WITH LINK GOUNDARA, SONO SHAIKH AND KAJALO KATOHAR ROAD (20.00 KMS).**

To,

Executive Engineer,
Machinery Maintenance Division,
(HYDERABAD), DIGRI @ KOTDIJI

1. Having examined the bidding documents including Instructions to Bidders, Bidding Data, and Conditions of Contract, Specifications, Drawings and Bill of Quantities and Addenda Nos. _____ for the execution of the above-named work, we, I, the undersigned, offer to execute and complete the work and remedy any defects therein in conformity with the conditions of Contract, Specifications. Drawing Bill of Quantities and Addenda for the sum of Rs. _____

other sum may be ascertained in accordance with the said conditions.

2. We/I understand that all the Appendices attached here to form part of this bid.
3. As security for due performance of the undertakings and obligations of this bid, we/ I submit herewith a bid security in the amount of Rupees _____

(Rs. _____ No. _____ Dated _____
_____ drawn in your favour or made payable to procuring agency and valid for a period of _____ days beginning from the date, bid is opened No.
4. We/ I undertake, if our Bid is accepted, to commence the works and to complete the whole of the works comprised in the contract within the same stated in Appendix-A to Bid.
5. We/ I agree to abide by this bid for the period of **24 Months** days from the date fixed for opening the same and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
6. Unless and until a formal / Agreement is prepared and executed, this bid, together with your written acceptance thereof, shall constitute a binding contract between us.
7. We do hereby declare that the bid is made without any collusion, comparison of figures or arrangement with any other bidder for the works.
8. We understand that you are not bound to accept the lowest or any bid you may receive.
9. We undertake, if our/my bid is accepted, to execute the Performance Security referred to in Clause-10 of Conditions of Contract for the due performance of the Contract.
10. We confirm, if our bid is accepted that all partners of the joint venture shall be liable jointly and severally for the execution of the Contract and the composition or the constitution.

EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI

of the joint venture shall not be altered without the prior consent of the procuring agency.
(Please delete this in case of Bid form a single bidder).

In the capacity _____ duly authorized to sign Bids for and on behalf of

Dated _____ day of _____

(Name of Bidder in Book Capitals)
(Seal)

Address:- _____

Witness:

Signature: _____

Name: _____

Address: _____

Occupation: _____


EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD) DIGRI @ KOTDIJI

NAME OF WORK: W/R & REHABILITATION OF ROAD FROM KHAIRPUR SHADI SHAHEED ROAD @ MILE 3.0 TO SHAH WARYAL OSTA GAHI ROAD VIA KHADIM HUSSAIN KATOHAR WITH LINK GOUNDARA, SONO SHAIKH AND KAJALO KATOHAR ROAD (20.00 KMS). (PART-A ROAD WORK).

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:-

Sr. No.	Quantities	Description of item to be executed as site	Rate	Units	Amount
01.	571032	Excavation in existing berms for widening the road including watering roller with power roller dressing excavated stuff etc complete.	526/27	P% Sft	3005170
02.	363992	Preparing Sub base course by supplying and spreading stone metal of 2"-1 1/2" gauge of approved quality from approved quarry in required thickness of 12" in 4 layers 2 to 3 each to proper camber and grade I/C hand packing filling voids with 20 cft of pit /canal of approved quality from approved quarry watering and compacting to achieve 98-100 % density as per modified AASHO specification. Rate i/c all cost of materials upto site of work.	6569/07	P.% Cft	23910889
03.	131881	Laying brick on end edging I/C supply of 9"x3"x41/2"x 3" 1st class burnt bricks excavation for laying edging with small side parallel to the road. Rate I/C all cost of materials T & P and carriage up to site of work.	2844/57	P.% Rft	3751447
04.	613247	Preparing Base course by supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness to proper camber and grade 1 1/2" supplying and stacking 15 Cft screening and non plastic quarry fines filling voids with stone metal after initial rolling I/C watering and compacting the same so as to achieve 100% density as per modified AASHO specification. (This i/c providing and using templates camber plates screen for as directed Rate i/c all cost of materials T&P and carriage up to site of work.	7557/46	P.% Cft	46345897
05.	1186931	Providing Two Coat on new or existing surface with 25 k.g bitumen 80/100 penetration and 0.20 Cum. Crush Bajri of required side i/c cleaning the road surface rolling complete. Rate i/c all cost of material T&P carriage upto site of work	2897/-	P.% Sft	34385391
06.	3500000	Earth work for road embankment by bulldozer i/c ploughing mixing cold breaking dressing remaining etc complete, load up to 100 ft. and lift up to 5 fts. In all types of except rock .	8679/15	P% 0 Cft	30377025
			TOTAL		141775819

% Above/ Below on the rates of CSR

Amount to be Added / Deducted on the

Total Amount _____

Total (A)

Total Amount _____

Diff Cost of Bitumen (B) 291.44 Tons @ Rs. 13485/- P.Ton

Total Amount (-) 3930068 _____

G.Total (A+B) Amount _____

Total Amount in work (A+B) _____

CONTRACTOR

[Signature]
EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI

NAME OF WORK: **WIDENING & RECONDITIONING OF ROAD FROM HAJINA STOP MAJEED BRIDGE TO LINK ROAD TAXI STAND KOT BANBLOW @ IMAM BARGAH MIR WAH CANAL ROAD (3.62 KM) (PART-B ASPHALT).**

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:-

Sr. No.	Quantities	Description of item to be executed as site	Rate	Units	Amount
01.	1186931	Laying to proper line and grade plant mixed ASPHALT concrete paver finished (Hydraulic/Electri control) prepared to specified formula according to job mix formula approved by Engineer in charge i/c rolling and finished to proper line grade level and camber etc complete. Rate i/cs all cost of materials with Bitumen 80/100 penetration and all cost of materials roller tend and carriage of materials (2" thick ASPHALT).	8699/70	P% Sft	106428779
			TOTAL		106428799

% Above/ Below on the rates of CSR

Amount to be Added / Deducted on the

Total Amount _____

Total (A)

Total Amount _____

(i) Diff Cost of Bitumen (B) 79.48 Tons @ Rs. 13485 P.Ton

Total Amount (-) 1071788


(ii) Diff Cost of Bitumen (B) 542.01 Tons @ Rs. 24938 P.Ton

Total Amount (-) 13516645

G.Total (A+B) Amount _____

Total Amount in work (A+B) _____

CONTRACTOR


EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI

NAME OF WORK: **W/R & REHABILITATION OF ROAD FROM KHAIRPUR SHADI SHAHEED ROAD @ MILE 3.0 TO SHAH WARYAL OSTA GAHI ROAD VIA KHADIM HUSSAIN KATOHAR WITH LINK GOUNDARA, SONO SHAIKH AND KAJALO KATOHAR ROAD (20.00 KMS). (PART-C CONSTRUCTION OF WORK).**

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:-

Sr. No.	Quantities	Description of item to be executed as site	Rate	Units	Amount
01.		Earth work for road embankment by bulldozer i/c ploughing mixing cold breaking dressing remaining etc complete, load up to 100 ft. and lift up to 5 fts. In all types of soil except Rock			
	40788	95-100% Density With Extra Lead	11208/92	P.% 0 Cft	457189
	580000	85% Density With Extra Lead	8679/15	P.% 0 Cft	5033907
02.	33772	Preparing Sub base course by supplying and spreading stone metal of 2"-1 1/2" gauge of approved quality from approved quarry in required thickness of 12" in 4 layers 2 to 3 each to proper camber and grade I/C hand packing filling voids with 20 cft of pit /canal of approved quality from approved quarry watering and compacting to achieve 98-100 % density as per modified AASHO specification. Rate i/c all cost of materials upto site of work.	6569/07	P.% Cft	2218506
03.	4079	Laying brick on end edging I/C supply of 9"x3"x4 1/2"x 3" 1st class brunt bricks excavation for laying edging with small side parallel to the road. Rate I/C all cost of materials T & P and carriage up to site of work.	2844/57	P.% Rft	116030
04.	18355	Preparing Base course by supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness to proper camber and grade 1 1/2 supplying and stacking 15 Cft screening and non plastic quarry fines filling voids with stone metal after initial rolling I/C watering and compacting the same so as to achieve 100% density as per modified AASHO specification. (This i/c providing and using templates camber plates screen for as directed Rate i/c all cost of materials T&P and carriage up to site of work.	7557/46	P.% Cft	1387172
05.	36709	Providing Two Coat on new or existing surface with 55 Lbs bitumen 80/100 penetration and 0.20 Cum. Crush Bajri of required side i/c cleaning the road surface rolling complete. Rate i/c all cost of material T&P carriage upto site of work	2897/00	P% Sft	1063460
			TOTAL		10276264

% Above/ Below on the rates of CSR

Amount to be Added / Deducted on the

Total Amount _____

Total (A)

Total Amount _____

Diff Cost of Bitumen (B) 9.01 Tons @ Rs. 13485 P.Ton

Total Amount (-) 121500

G.Total (A+B) Amount _____

Total Amount in work (A+B) _____

CONTRACTOR

EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI

NAME OF WORK: **WIDENING & RECONDITIONING OF ROAD FROM HAJINA STOP MAJEED BRIDGE TO LINK ROAD TAXI STAND KOT BANBLOW @ IMAM BARGAH MIR WAH CANAL ROAD (3.62 KM) (PART-D ASPHALT).**

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:-

Sr. No.	Quantities	Description of item to be executed as site	Rate	Units	Amount
01.	36709	Laying to proper line and grade plant mixed ASPHALT concrete paver finished (Hydraulic/Electri control) prepared to specified formula according to job mix formula approved by Engineer in charge i/c rolling and finished to proper line grade level and camber etc complete. Rate i/cs all cost of materials with Bitumen 80/100 penetration and all cost of materials roller tend and carriage of materials (2" thick ASPHALT).	8699/72	P% Sft	3291593
			TOTAL		3291593

% Above/ Below on the rates of CSR

Amount to be Added / Deducted on the

Total Amount _____

Total (A)

Total Amount _____

(i) Diff Cost of Bitumen (B) 2.45 Tons @ Rs. 13485 P.Ton

Total Amount (-) 33038

(ii) Diff Cost of Bitumen (B) 16.76 Tons @ Rs. 24938 P.Ton

Total Amount (-) 417961

G.Total (A+B) Amount _____

Total Amount in work (A+B) _____

CONTRACTOR

EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI

NAME OF WORK:

WIDENING & RECONDITIONING OF ROAD FROM HAJINA STOP MAJEED
BRIDGE TO LINK ROAD TAXI STAND KOT BANBLOW @ IMAM BARGAH
MIR WAH CANAL ROAD (3.62 KM) (PART-E RETAINING WALL 3960 RFT).

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:-

Sr. No.	Quantities	Description of item to be executed as site	Rate	Units	Amount
01.	2100	Excavation in foundation of building bridges and other structure i/c dagbelling dressing refilling around structure with excavation earth watering and remaining lead upto 5.0 ft. ordinary soil.	3176/25	P.% 0 Cft	6670
02.	2100	Extra slush or daldal i/c de-water.	2420/-	P.% 0 Cft	2420
03.	1050	Cement concrete brick or stone ballast 1 ½ -2" gauge Ratio 1:4:8.	9416/28	P.% Cft	98871
04.	4312	Pacca bricks work in foundation and plinth in cement Sand 1:4.	12501/41	P.% Cft	539061
05.	056	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with out shuttering Ration.1:2:4	14429/25	P.% Cft	8080
06.	14.28	Fabrication of mild steel reinforcement for cement concrete i/c cutting beading laying in position making joint and fasting i/c cost of steel and binding wire also i/c removal of rust from bar.	4820/20	P. Cwt	68832
07.	700	R.C.C work i/c all labour and materials except the cost of steel reinforcement and its labor for bending and binding which will be paid separately this rate also i/c all kinds of forms moulds lifting shuttering currying rending and finishing the exposed surface (i/c screening and washing of shingle) R.C.C work in roof slab beams columns rafts lintels and other structural laid in site or recast in position complete in all respect.Ration1:2:4 90 Lbs Cement 2 cft Sand 4 cft Shingle 1/8"-1/4" gauge .	337/-	P. Cft	235900
08.	1000	Cement plaster (1:3) upto 20'height ½ "thick.	2344/59	P.% Sft	23446
TOTAL					985942

Therefore the cost of __ Nos. Culverts

% Above / Below on the rates of CSR

Amount to be Added / Deducted on the

**Total
Amount
G.Total**

Total Amount in work (A+B) _____

CONTRACTOR

EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD) DIGRI @ KOTDIJI

NAME OF WORK:

WIDENING & RECONDITIONING OF ROAD FROM HAJINA STOP MAJEED
BRIDGE TO LINK ROAD TAXI STAND KOT BANBLOW @ IMAM BARGAH
MIR WAH CANAL ROAD (3.62 KM) (PART-F T.P COLOUR ROAD
MARKING).

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:-

Sr. No.	Quantities	Description of item to be executed as site	Rate	Units	Amount
01.	169950	Pavement making in reflective thermo paint for lines of 6" width.	41/24	P.% Sft	7008738
			TOTAL		7008738

Therefore the cost of _ Nos. Culverts
% Above / Below on the rates of CSR
Amount to be Added / Deducted on the

Total
Amount
G.Total

Total Amount in work (A+B)

CONTRACTOR

EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI

NAME OF WORK:

WIDENING & RECONDITIONING OF ROAD FROM HAJINA STOP MAJEED
BRIDGE TO LINK ROAD TAXI STAND KOT BANBLOW @ IMAM BARGAH
MIR WAH CANAL ROAD (3.62 KM) (PART-G 3' SPAN CULVERTS).

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:-

Sr. No.	Quantities	Description of item to be executed as site	Rate	Units	Amount
01.	1089	Excavation in foundation of building bridges and other structure i/c dagbelling dressing refilling around structure with excavation earth watering and remaining lead upto 5.0 ft. ordinary soil.	3176/25	P.% 0 Cft	3459
02.	239	Cement concrete brick or stone ballast 1 ½ -2" gauge Ratio 1:4:8.	9416/28	P.% Cft	22505
03.	476	Pacca bricks work in foundation and plinth in cement Sand 1:4.	12501/41	P.% Cft	59507
04.	53	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with out shuttering Ration.1:2:4	14429/25	P.% Cft	7648
05.	5.88	Fabrication of mile steel reinforcement for cement concrete i/c cutting beading laying in position making joint and fasting i/c cost of steel and binding wire also i/c removal of rust from bar.	4820/20	P. Cwt	28343
06.	133	R.C.C work i/c all labour and materials except the cost of steel reinforcement and its labor for bending and binding which will be paid separately this rate also i/c all kinds of forms moulds lifting shuttering currying rending and finishing the exposed surface (i/c screening and washing of shingle) R.C.C work in roof slab beams columns rafts lintels and other structural laid in site or recast in position complete in all respect.Ration1:2:4 90 Lbs Cement 2 cft Sand 4 cft Shingle 1/8"-1/4" gauge .	337/-	P. Cft	44821
07.	266	Cement plaster (1:3) upto 20'height ½ "thick.	2344/59	P.% Sft	6237
TOTAL					172500

Therefore the cost of _ Nos. Culverts

% Above / Below on the rates of CSR

Amount to be Added / Deducted on the

Total

Amount

G.Total

Total Amount in work (A+B) _____

CONTRACTOR

EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI

NAME OF WORK:

WIDENING & RECONDITIONING OF ROAD FROM HAJINA STOP MAJEED
BRIDGE TO LINK ROAD TAXI STAND KOT BANBLOW @ IMAM BARGAH
MIR WAH CANAL ROAD (3.62 KM) (PART-H 3' SPAN R.C.C SLAB
CULVERTS).

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:-

Sr. No.	Quantities	Description of item to be executed as site	Rate	Units	Amount
01.	268	Excavation in foundation of building bridges and other structure i/c dagbelling dressing refilling around structure with excavation earth watering and remaining lead upto 5.0 ft. ordinary soil.	3176/25	P.% 0 Cft	851
02.	073	Cement concrete brick or stone ballast 1 ½ -2" gauge Ratio 1:4:8.	9416/28	P.% Cft	6874
03.	182	Pacca bricks work in foundation and plinth in cement Sand 1:4.	12501/41	P.% Cft	22753
04.	25	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate with out shuttering Ration.1:2:4	14429/25	P.% Cft	3607
05.	1.10	Fabrication of mile steel reinforcement for cement concrete i/c cutting beading laying in position making joint and fasting i/c cost of steel and binding wire also i/c removal of rust from bar.	4820/20	P. Cwt	5302
06.	016	R.C.C work i/c all labour and materials except the cost of steel reinforcement and its labor for bending and binding which will be paid separately this rate also i/c all kinds of forms moulds lifting shuttering currying rending and finishing the exposed surface (i/c screening and washing of shingle) R.C.C work in roof slab beams columns rafts lintels and other structural laid in site or recast in position complete in all respect.Ration1:2:4 90 Lbs Cement 2 cft Sand 4 cft Shingle 1/8"-1/4" gauge.	337/-	P. Cft	5392
07.	115	Cement plaster (1:3) upto 20'height ½ "thick.	2344/59	P.% Sft	2696
TOTAL					47471

Therefore the cost of _ Nos. Culverts

% Above / Below on the rates of CSR

Amount to be Added / Deducted on the

Total
Amount
G.Total

Total Amount in work (A+B) _____

CONTRACTOR

EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI

SCHEDULE-A TO BID

- 4.5. (a) The bidder shall be deemed to have obtained all information as to and all requirements related there to which may affect the bid price.
- (b) The Contractor shall be responsible to make complete arrangements for the transportation of the Plant to the Site.

(Procuring Agency may modify as appropriated)

- 4.6 The Contractor shall provide for all parts of the works to be completed in every respect. Notwithstanding that any details, accessories, etc required for the complete installation and satisfactory operation of the Works, are not specifically mentioned in the Specifications, such details shall be considered as included in the Contract Price.

5. BID PRICE

- 5.1 Break-up of Bid Prices.
The various elements of Bid Prices shall be quoted as detailed by the Procuring Agency in the format of Schedule of Prices.
The bidder shall recognize such elements of the costs which he expects to incur the performance of the Works and shall include all such costs in the rates and amounts entered in the Schedule of Price.
- 5.2 Total Bid Price
The total of bid prices in the Schedule of Prices shall be entered in the Summary of Bid Prices.

6. PROVISIONAL SUMS AND DAY WORK

- 6.1 Provisional Sums included and so designated in the Schedule of Prices if any, shall be expended in whole or in part at the direction and discretion of the Engineer/ Procuring Agency. The Contractor will only receive payment in respect of Provisional Sums, if he has been instructed by the Engineer/ Procuring Agency to utilize such sums.
- 6.2 Day work rates in the contractors bid are to be used for small additional amounts of work and only when the Engineer have given written instructions in advance for additional work to be paid for in that way.

CONTRACTOR


EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
HYDERABAD, DIGRI @ KOTDIJI

PREAMBLE TO SCHEDULE OF PRICES**1. GENERAL**

- 1.1 The Schedule of Prices shall be read in conjunction with the Conditions of Contract, Contract Data together with the Specifications and Drawings, if any.
- 1.2 The Contract shall be for the whole of the works as described in these Bidding Documents. Bids must be for the complete scope of works.

2. DESCRIPTION

- 2.1 The general directions and descriptions of works and materials are not necessarily repeated nor summarized in the Schedule of Prices. References to the relevant sections of the Bidding Documents shall be made before entering prices against each item in the Schedule of Prices.

3. UNITS & ABBREVIATIONS

- 3.1 Units of measurement, symbols and abbreviations expressed in the Bidding Documents shall comply with the System International d' Unites (SI Units).
-
-

4. RATES AND PRICES

- 4.1 Except as otherwise expressly provided under the Conditions of Contract, the rates and amounts entered in the Schedule of Prices shall be the rates at which the Contractor shall be paid and shall be the full inclusive value of the works set from or implied in the Contract, except for the amount reimbursable, if any to the Contractor under the Contract.
- 4.2 Unless otherwise stipulated in the Contract Data, the premium, rates and prices entered by the bidder shall not be subject to adjustment during the performance of the Contract.
- 4.3 All duties, taxes and other levies payable by the Contractor shall be included in the rates and prices.
- 4.4 The whole cost of complying with the provisions of the Contract shall be included in items provided in the Schedule of Prices, and where no items are provided, the cost shall be deemed to be distributed among the rates and prices entered items of the Works and no separate payment will be made for those items.

The rates, prices and amounts shall be entered against each item in the Schedule of Prices. Any item against which no rate or price is entered by the bidder will not be paid for by the Procuring Agency when executed and shall be deemed covered by the rates and prices for other items in the Schedule of Prices.

CONTRACTOR


EXECUTIVE ENGINEER
MACHINERY MAINTENANCE DIVISION
(HYDERABAD), DIGRI @ KOTDIJI