



Phone# 074-9411054
Email: xenbuilding@gmail.com

**OFFICE OF THE EXECUTIVE ENGINEER
(BUILDINGS) DIVISION KAMBER-SHAHDADKOT**

No: TC/XEN/ (B) 224 2018,
Kamber, dated: 30/03/ 2018,

To,

The Director (information)
Advertisement Block-96.
Government of Sindh Karachi.

SUBJECT: PUBLICATION TO NOTICE INVITING TENDER (NIT)

Kindly find enclosed herewith notice inviting tender (NIT) along with six extra copies with a request with to please get it published in Six (06) leading Newspapers i.e. Sindhi, Urdu, English for wide publicity as required under SPPRA rule 2010.

**EXECUTIVE ENGINEER
(BUILDINGS) DIVISIO
KAMBER-SHAHDADKOT**

Copy Fwc's

1. The Managing Director, Sind Public Procurement Regulatory Authority (SPPRA) planning and Development Department Government of Sindh, Block – 8, 4-A Sind Secretariat Karachi request kindly to Advertise the N.I.T on (SPPRA) website (Copy attached)

2. The Secretary, information technology Department, Building No: 6 1st floor Government of Sindh, new Sindh Secretariat Karachi, with a request kindly afloat the on website of Sindh Government, please (Copy attached)

**EXECUTIVE ENGINEER
(BUILDINGS) DIVISION
KAMBER-SHAHDADKOT**

SPPRA INWARD DIARY
No: 7669
DATED 02/04/2018



**OFFICE OF THE EXECUTIVE ENGINEER, BUILDINGS DIVISION,
DISTRICT KAMBER-SHAHDADKOT @ D.C. SECRETARIAT KAMBER**

Phone No: 074 -9411054 & E-mail: hussainjaved345@gmail.com

No. XEN/(B) TC/ 220 Dated: 29 / 03 / 2018

NOTICE INVITING TENDERS

Sealed tenders are invited from all the interested persons/suppliers/contractors/companies for procurement of the following works as per SPPRA Rules 2010.

TERMS AND CONDITIONS

1. i) **Issuance:** Documents will be issued from date of publication i.e. in the newspapers upto **18.04.2018**.
ii) **Submission:** Last dated will be **19.04.2018** upto 1:00 P.M.
iii) **Opening:** will be opened on **19.04.2018** @ 2:00 P.M. (on the same day of submission).
iv) **Un-responded Tenders:** will be again issued/submitted/opened on following dated.

Attempt	Issue Date	Submission Date	Opening Date
2 nd	From 07.05.2018	08.05.2018 1:00 P.M	08.05.2018 on the same day @ 2:00 P.M

2. No conditional/Telegraphic Tender will be entertained.
3. No Tenders without Call Deposit or received after specified date and time will be considered.
4. Bid should contain least cost method (Single stage one Envelop).
5. If the undersigned remains out of head quarter on date of opening of tenders, the same will be opened on the next working day at the same schedule as mentioned above.
6. The Procuring agency reserves the right to reject all or any bid subject to the relevant provision of SPPRA Rules 2010.
7. Undertaking on stamp paper that Firm has never been black listed, any kind of litigation Departmental rift, abandoned or unnecessary delay in completion of any work in the Government and as well as in Private Organization. As ordered by Worthy Secretary (Works and Services Department) Karachi vide letter No.DDM/W&S/Misc:/2014 dated:28.08.2014.
8. Bid validity period (90) days.
9. Bidders are required to submit following documents with Bid.
 - i) List of similar assignments with cost (mention the number of Projects) under-taken and completed over the past 02 years.
 - ii) Details of Equipments/Machineries and Transport owned by Firm/Contractor.
 - iii) Financial Statement (Bank Statement) and Income Tax return for the last 02 years.
 - iv) The Firm must be registered in PEC with specialization code CE-10 and renewed up to 2017 above limit of 4.00 (Million).
 - v) Registration with Sindh Revenue Board.

D.....A

Executive Engineer
Buildings Division
Kamber-Shahdadkot


C.F.W.C's TO:-

1. The Deputy Commissioner, Kamber- Shahdadkot for favour of his kind information.
2. The Director Information Public Relation Department (Advertisement) alongwith (06) six copies of N.I.T for publication in News papers.
3. The Superintending Engineer, (W&S) Kamber-Shahdadkot for favour of information and approval please.
4. The Assistant Engineer, Highways Sub-Divisions, Shahdadkot, Miro Khan, Warah & Kamber for vide publicity.
5. Copy to Divisional Accounts Officer/Draftsman/Establishment Branch/Head Clerk & Notice Board Local.

Executive Engineer
Buildings Division
Kamber-Shahdadkot

LIST OF WORKS

S.#	NAME OF SCHEME	Amount in (M)	Bid Security 5% (in Rupees)	Tender Fee	Time Allowed
	COMMUNITY DEVELOPMENT PROGRAMME 2017-18 PS-42				
1	Construction of Community Centre at Warah City Taluka Warah .	5.000	250,000	3,000	03 Month
2	Construction of Library at Warah City Taluka Warah	3.300	165,000	3,000	03 Month
3	Construction of Press Club at Warah City.	3.300	165,000	3,000	03 Month
4	Construction of Community centre , Library & Press Club at Warah City (C/Wall)	2.000	100,000	3,000	03 Month
5	Construction of Community centre Library, & Press Club at Warah City (Electric Work)	0.500	25,000	1500	03 Month
6	Construction of Community centre (Balance Work) at Warah .	1.000	50,000	3,000	03 Month
7	Construction of Paver Block & Drains at Barkat Shah Muhallah from Ghulam Rasool Chandio House to by pass road Taluka Kamber, District Kamber-Shahdadkot. (Balance Work)	0.980	50,000	3,000	03 Month
8	Repair/ Renovation of old District Council Staff Office at DC Office Kamber. (Non - Salary Components)	0.600	30,000	750	03 Month


EXECUTIVE ENGINEER
 (BUILDINGS) DIVISION
 KAMBER-SHAHDADKOT

ANNUAL PROCUREMENT PLAN 2017-18

BUILDING DIVISION KAMBER-SHAHDADKOT

S.#	Description of Procurement	Estimated Cost unit cost (Rs in Million)	Estimated Total Cost	Funds Release	Scope of Funds (ADP's Non ADPs)	Proposed Procurement Method	Timing of Procurement				Rema
							1st: Quarter	2nd: Quarter	3rd: Quarter	4th: Quarter	
01	02	03	04	05	06	07	08	09	10	11	12
	COMMUNITY DEVELOPMENT PROGRAMME 2017-18 (PS-42)										
1	Construction of Community Centre at Warah City Taluka Warah.	15.00 (M)	5.000 (M)	15.00 (M)	ADP	National Opening Competitive Bidding	15.00 (M)	--	--	--	--
2	Construction of Library at Warah City Taluka Warah.		3.300 (M)		ADP	National Opening Competitive Bidding	--	--	--	--	--
3	Construction of Press Club at Warah City.		3.300 (M)		ADP	National Opening Competitive Bidding	--	--	--	--	--
4	Construction of Community centre, Library & Press Club at Warah City (C/Wall)		1.900 (M)		ADP	National Opening Competitive Bidding	--	--	--	--	--
5	Construction of Community centre Library, & Press Club at Warah City (Electric Work)		0.500 (M)		ADP	National Opening Competitive Bidding	--	--	--	--	--
6	Construction of Community centre (Balance Work) at Warah.		1.000 (M)		ADP	National Opening Competitive Bidding	--	--	--	--	--
7	Construction of Paver Block & Drains at Barkat Shah Muhallah from Ghulam Rasool Chandio House to by pass road Taluka Kamber, District Kamber-Shahdadkot. (Balance Work)	0.980 (M)	0.980 (M)	0.980 (M)	ADP	National Opening Competitive Bidding	0.980 (M)	--	--	--	--
8	Repair/ Renovation of old District Council Staff Office at DC Office Kamber. (Non - Salary Components)	0.600 (M)	0.600 (M)	0.600 (M)	ADP	National Opening Competitive Bidding	0.600 (M)	--	--	--	--

EXECUTIVE ENGINEER (BUILDINGS)
BUILDING DIVISION KAMBER-SHAHDADKOT

GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT

Karachi, dated the 23rd February, 2017

CORRIGENDUM

No.E&A(W&S)3-9/91-16: with the approval of Competent Authority a Procurement Committee with the following composition, in terms of Rule-07 of Sindh Public Procurement Rules-2010 (Amended 2013) in the Office of Executive Engineer, Buildings Division, Kambar Shahdadkot with the following composition:-

- | | |
|---|----------|
| 1. Executive Engineer, Buildings Division, Kambar Shahdadkot. | Chairman |
| 2. Divisional Accounts Officer, Buildings Division, Kambar Shahdadkot | Member |
| 3. Assistant Engineer, Education Works Sub-Division, Shahdadkot. | Member |

2. The Functions & Responsibilities of the Committee will be same as specified in Rules-7 of Sindh Public Procurement Rules-2010 (Amended 2013).

SECRETARY TO GOVT. OF SINDH

No. E&A(W&S)3-9/91-16


Karachi, dated the 23rd February, 2017.

is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Managing Director, SPPRA, Karachi.
3. The Chief Engineer (Buildings), Hyderabad.
- ✓ 4. The Chairman / Members of the Committee.
5. The Deputy Director (Monitoring), PM&E Cell, W&SD.
6. P.S to Secretary, W&S Department.
7. Notification file.


23/02/17
SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH

EXECUTIVE ENGINEER BUILDING DIVISION KAMBER-SHAHDADKOT



**SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY
(SPPRA)
STANDARD BIDDING DOCUMENT**

Name of Work:- CONSTRUCTION OF COMMUNITY CENTRE AT WARAH
CITY TALUKA WARAH.

N.I.T No. & Date: XEN/(B)TC/ 220 **Dated:** 29-03-2018

Date of Issue up to: 19-04-2018


Date of Opening: 19-04-2018

Tender Issued to.

D.R No. & Date:

Amount of Tender Fee:

3000/-


EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT

Email:- xenbuildingskamber@gmail.com

**NIT S.NO. 1
CONTRACT / BIDDING DATA**

The following specific data for the works to be tendered shall complement, amend or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instruction to Bidders.

Instruction to Bidders.

Clause Reference

- | | | |
|---------|---|--|
| 1. | Name and Address of the Procuring Agency:- | Office of the Executive Engineer, Buildings Division
Kamber-Shahdadkot @ D.C Secretariat Kamber. |
| 2. | Name of the Project and Summary of the Work:- | CONSTRUCTION OF COMMUNITY CENTRE AT WARAH
CITY TALUKA WARAH. |
| 3. | Name of the Borrower/Source of Financing / Funding Agency / Funding Source. | Government of Sindh |
| 4. | Amount and Type of Financing / Scheme Cost and Allocation Funds:- | Cost of scheme Rs: 5.000 Million
Allocation Rs: Million |
| 5. | Time for clarification:- | Three days prior to submission of bids. |
| 6. | Bid Language:- | English |
| 7. | Prequalification Information to be updated (Where applicable) :- | |
| 8. | Furnish and Technical Proposal (in case of two evolve method) of Company Profile in single stage Single Envelope:- | Single Stage / Single Envelope |
| 9. | Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency they require, if applicable:- | Pakistan Rupees. |
| 10. | Period of Bid Validity:- | 90 Days |
| 11. | Amount of Bid Security:- | 5% of Bid Price |
| 12. | Venue, time and date of the Pre-Bid meeting:- | -- |
| 13. | Number of copies of the bid to be completed and returned:- | ONE |
| 14. | Procuring Agency's address for the purpose of bid submission :- | As Above |
| 15. | Name and Identification Number of the Contract:- | Various Development schemes of District Kamber-Shahdadkot (31 Nos.) (Provincial ADP No.1129) 2015-16 |
| 16. (a) | Deadline for submission of bids: | Bid submission 19-04-2018 upto 1.00 P.M
19-14-2018 up to 2.00 PM |
| (b) | Venue, time and date of bid opening :- | Bid opening 08-05-2018 at 1.30 P.M
08-05-2018 at 2.30 |
| 17. | Standard form and amount of Performance Security acceptable to the procuring agency:- | Office of the Executive Engineer, Buildings Division
Kamber-Shahdadkot @ D.C Secretariat Kamber. |
| 18. | Stamp duty | 5%
0.30% will be paid by successful bidder as stamp duty. |


CONTRACTOR

Executive Engineer
Buildings Division
Kamber-Shahdadkot


**CONSTRUCTION OF COMMUNITY CENTER AT WARAH TALUKA WARAH DISTRICT KAMBER-
SHAHDADKOT**

SCHEDULE-B


S.No.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
Main Building Cicil Work					
1	Excavation in foundation of buildings in other structure with excavated earth watering and ramming lead upto one chain 5 ft in ordinary soil (SINO: 18-P-4).	2540	Cft	3176.25	%0Cft 8,068
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (SINO: 4 (C) P 15).	635	Cft	8694.95	% Cft 55,213
3	Pacca brick work in foundation and plinth in 1:6 ratio.(SINO: 04(E)(P21)	1895	Cft	11948.36	% Cft 226,421
4	Reinforced cement concrete work i/c in all labor and material except the cost of steel reinforced and labor for bending and which will be paid separately. This rate also i/c all kinds of forms molds lifting shiting Curring rendering and finishing the exposed surface i/c screening and washing of shingle. Ratio (1:2:4) 90 lbs cement 2 cft. Sand 4 cft shingle 1/8" to 1/4" gauge. (SINO: 6(a)-P-17).	870	Cft	337	P.Cft 293,190
5	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints fastening i/c coat of binding wire also i/c removal of rust from bars. (SINO: 8 (b) P-17).	45	Cwt.	5001.70	P.Cwt 223,402
6	Filling watering ramming earth under floor with new earth (excavated from out side) lead upto 1 chain lift upto 5 ft(SINO:22-P-4).	6248	Cft	3630	%0Cft 22,680
(B)	Extra lead of earth filling 3 miles.	6248	Cft	579.41	%0Cft 3,620
7	Supplying and filling sand under floor and plaguing in to walls (SINO: 29 P-26.)	2582	Sft	1141.25	% Sft: 29,467
(B)	Extra lead of earth filling 3 miles.	2582	Cft	579.41	%Cft 14,960
8	Providing single layer of polythine sheet 0.13" thick for water proofing as per specifying and instruction of Engineer (S.I.No. 38 P-38)	316	Sft	10.70	P.Sft 3,381
9	Cement concrete plain 1:2:4 ratio i/c placing compacting finishing and curring complete i/c scering and washing of stones aggagate without shuttering (S.I.No. 5(f) P-17).	866	Cft	14429.25	% Cft 124,957
10	Pacca Brick Work in G. Floor (1:6) Cement Sand mortor(S.No:5(E) P-21).	3305	Cft	12674.36	% Cft 418,888


 Engineer
 District Engineer
 Kamber-Shahdadkot

11	Cement concrete plain 1:2:4 ratio i/c placing compacting finishing and curring complete i/c scering and washing of stones aggagate without shuttering (S.I.No. 5(f) P-17).	656	Cft	14429.25	% Cft	94,656
12	S/Fixing M.S Girder at site of work.	53.0	Cwt	3850.00	P.Cwt	204050
13	S/ Fixing T-iron at site of work.	55.0	Cwt	3575.00	P.Cwt	196625
14	Erecting rail steel beams or old rail in roofs etc correction and fixing in position.(S.I.No:6-P.91)	108	Cwt	186.34	P.Cwt	20125
15	Second class tile roofing consisting of 4"earth and 1"mud plaster with gobri leaping over 1/2" thick cement plaster. 1:6 with 34lbs. of hot bitumen coating sand blinded provide over 2, layers of tiles 12" x 6" 1/4 " laid in 1:6 cement mortar with 1/2" thick sand witched layer of 1:6 cement pointing under side of tiles complete including curing etc.(S.I.No:02-P.33)	2833	Sft	7607.25	%Sft	215513
16	Providing single layer of polythine sheet 0.13" thick for water proofing as per specifying and instruction of Engineer.(S.I.No: 38-P.38)	2833	Sft:	10.70	P.Sft:	30,313
17	Single layer of tiles 9" x4 1/2" x 2" laid over 4" earth 1" mud plaster without Bhoosa grouted with cement sand 1:3 on top of R.C.C slab provide with 34 Lbs. Bitumen coating sand blinded. (SINO:05-P.34)	2833	Sft:	5310.35	%Sft	150,442
18	Cement plaster 1:6 upto 20'ft height 3/4" thick (SINO.13(b)-P-52).	6446	Sft	2206.60	% Sft	142,237
19	Cement plaster 1:4 3/8" thick upto 20'ft height (SINO:11(A)-P-52).	6446	Sft	2197.52	% Sft	141,652
20	Cement Pointing Strking joints on walls 1:3 ratio. (S.I.No. 19(a) P-53).	2107	Sft	1287.44	% Sft	27,126
21	Providing and fixing G.I. frame/chowkats of size 7"x2" x41/2"x3" for door using 20 gauge G.I. sheet welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost also i/c all carriage, tools and plants used in making and fixing(SINO:28-29-P-93.)					
	Doors	40	Rft	228.90	P.Rft	9,156
	Windows	231	Rft	240.50	P.Rft	55,556
22	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" i/c and frame of flate iron patti of 3/4" x 3/4" i/c cilcle shape at 1-0 apart equivalent fitted with screw or pins i/c painting 3 coats with 1 coat of red oxide paint etc.(S.I.No.30 P-94).	132	Sft	194.16	P.Sft	25,629



 1007-2
 Executive Engineer
 Civil Division
 Mumbai Cantonment

23	First Class deodar wood wrought joinery in doors and windows etc fixed in position i/c chowkats hold fasts hinges, iron, tower bolts, handles and cords with hooks, Deodar paneled or paneled and glazed or fully glazed (b) 1x3/4" thick etc complete.(SI NO: 7a P-58) (Only Shutters).	148	Sft	902.93	P.Sft:	133,634
24	laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 (S.I.No. 60 P-47).	2134	Sft	27747.06	% Sft	592,122
25	White Glazed tiles 1/4 "thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4 "thick i/c finishing. (SI NO 37 P-45).	155	Sft	28253.61	% Sft	43,793
26	Laying white marble flooring fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (a) 3/4" thick flooring. (SINO:28(a) P-43).	525	Sft:	567.48	P.Sft:	297,927
27	First class deodar wood wrought joinery work in wire gauze door and windows with 22 S.W.G Galvanized wire gauze 144 mesh per square inch iron fittings complete. Glavanized wire gauze fixed to chowkats with 3/4" deodar stips and screws (S.I.No. 14(d) P-60).	132	Sft	190.72	P.Sft:	25,175
28	Providing & fixing false ceiling of thermopile in panels of required design and size including frame work of Aluminum T-section hanged with nail wire to ceiling etc: completed(SINO:43 P-39).	2624	Sft:	91.5	P.Sft:	240,096
29	Providing & fixing plaster of pairs ceiling border of 8" or 10" with of specified design and thikness i/c fixing besidees ceiling with nails / screws with jetties.(SINO:44 P-39).	338	Rft:	104.22	P.Rft:	35,226
30	Priming coat of chalk distemper (S.I.No. 23 P-54).	2624	Sft	442.75	% Sft	11,618
31	Distempering in three Coats. (SINo.24(c)P-54).	2624	Sft	1079.65	% Sft	28,330
32	Preparing the surface and painting with matt finish I/c rubbing the surface with	5408	Sft:	2717.0	% Sft	146,935
33	Preparing the surface and painting % sft with weather coat i/c rubbing th surface paper filling the weather coat appr: new surface (SINO: 38(a-b) P-56).	4210	Sft	2567.95	% Sft	108,111
34	Painting doors and windows any type etc complete New surface painting door and windows (SINO:5(C) - P-69/70).	392	Sft	2116.41	% Sft	8,296



 Engineer in Charge
 District Engineer
 District Engineer

35 (d) Preparing surface and painting guard bars, 2983 Sft 896.39 % Sft 26,739
gates of iron bars, gratings, railings (including
standards braces, etc). And similar open
work.(SINO:5(d)-P-70)

TOTAL RS:- 4,435,332


**Executive Engineer
(Buildings) Division
Kamber-Shahdadt.**

EXECUTIVE ENGINEER BUILDING DIVISION KAMBER-SHAHDADKOT



**SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY
(SPPRA)
STANDARD BIDDING DOCUMENT**

**Name of Work:- CONSTRUCTION OF LIBRARY AT WARAH CITY
TALUKA WARAH**

N.I.T No. & Date: XEN/(B)TC/ 220 Dated: 29-03-2018

Date of Issue up to: 19-04-2018

Date of Opening: 19-04-2018

Tender Issued to.

D.R No. & Date:

Amount of Tender Fee:

3000/-

**EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT**

Email:- xenbuildingskamber@gmail.com

**NIT S.NO. 2
CONTRACT / BIDDING DATA**

The following specific data for the works to be tendered shall complement, amend or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instruction to Bidders.

Instruction to Bidders.

Clause Reference

- | | | |
|---------|---|--|
| 1. | Name and Address of the Procuring Agency:- | Office of the Executive Engineer, Buildings Division
Kamber-Shahdadkot @ D.C Secretariat Kamber. |
| 2. | Name of the Project and Summary of the Work:- | CONSTRUCTION OF LIBRARY AT WARAH CITY
TALUKA WARAH |
| 3. | Name of the Borrower/Source of Financing /
Funding Agency / Funding Source. | Government of Sindh |
| 4. | Amount and Type of Financing / Scheme Cost
and Allocation Funds:- | Cost of scheme Rs: 3.300 Million
Allocation Rs: Million |
| 5. | Time for clarification:- | Three days prior to submission of bids. |
| 6. | Bid Language:- | English |
| 7. | Prequalification Information to be updated
(Where applicable) :- | |
| 8. | Furnish and Technical Proposal (in case of
two evolve method) of Company Profile in
single stage Single Envelope:- | Single Stage / Single Envelope |
| 9. | Bidders to quote entirely in Pak. Rupees but
specify the percentage of foreign currency
they require, if applicable:- | Pakistan Rupees. |
| 10. | Period of Bid Validity:- | 90 Days |
| 11. | Amount of Bid Security:- | 5% of Bid Price |
| 12. | Venue, time and date of the Pre-Bid meeting:- | -- |
| 13. | Number of copies of the bid to be completed
and returned:- | ONE |
| 14. | Procuring Agency's address for the purpose
of bid submission :- | As Above |
| 15. | Name and Identification Number of the
Contract:- | Various Development schemes of District Kamber-
Shahdadkot (31 Nos.) (Provincial ADP No.1129) 2015-16 |
| 16. (a) | Deadline for submission of bids: | Bid submission 19-04-2018 upto 1.00 P.M
19-14-2018 upto 2.00 PM |
| (b) | Venue, time and date of bid opening :- | Bid opening 08-05-2018 at 1.30 P.M
08-05-2018 at 2.30 |
| 17. | Standard form and amount of Performance
Security acceptable to the procuring agency:- | Office of the Executive Engineer, Buildings Division
Kamber-Shahdadkot @ D.C Secretariat Kamber. |
| 18. | Stamp duty | 5%
0.30% will be paid by successful bidder as stamp duty. |

CONTRACTOR

Executive Engineer

Buildings Division

Kamber-Shahdadkot


CONSTRUCTION OF LIBRARY AT WARAH DISTRICT KAMBER-SHAHDADKOT

SCHEDULE-B


S.No.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
Main Building Cical Work					
1	Excavation in foundation of buildings in other structure with excavated earth watering and ramming lead upto one chain 5 ft in ordinary soil (SINO: 18-P-4).	1719	Cft	3176.25	%0Cft 5,460
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (SINO: 4(C) P 15).	430	Cft	8694.95	% Cft 37,388
3	Pacca brick work in foundation and plinth in 1:6 ratio.(SINO: 04(E)(P21)	1747	Cft	11948.36	% Cft 208,738
4	Reinforced cement concrete work i/c in all labor and material except the cost of steel reinforced and labor for bending and which will be paid separately. This rate also i/c all kinds of forms molds lifting shiting Curring rendering and finishing the exposed surface i/c screening and washing of shingle. Ratio (1:2:4) 90 lbs cement 2 cft. Sand 4 cft shingle 1/8" to 1/4" gauge. (SINO: 6(a)-P-17).	418	Cft	337	P.Cft 140,866
5	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints fastening i/c coat of binding wire also i/c removal of rust from bars. (SINO: 8 (b) P-17).	19.107	Cwt.	5001.70	P.Cwt 95,568
6	Filling watering ramming earth under floor with new earth (excavated from out side) lead upto 1 chain lift upto 5 ft(SINO:22-P-4).	4576	Cft	3630	%0Cft 16,611
(B)	Extra lead of earth filling 3 miles.	4576	Cft	579.41	%Cft 26,514
7	Supplying and filling sand under floor and plaguing in to walls (SINO: 29 P-26.)	1144	Sft	1141.25	% Sft: 13,056
(B)	Extra lead of earth filling 3 miles.	1144	Cft	579.41	%Cft 6,628
8	Providing single layer of polythine sheet 0.13" thick for water proofing as per specifying and instruction of Engineer (S.I.No. 38 P-38)	241	Sft	10.70	P.Sft 2,579
9	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:4:8 (SINO: 4 (b) P 15).	755	Cft	9416.28	% Cft 71,093
10	Pacca Brick Work in G. Floor (1:6) Cement Sand mortor(S.No:5(E) P-21).	1663	Cft	12674.36	% Cft 210,775
11	Cement concrete plain 1:2:4 ratio i/c placing compacting finishing and curring complete i/c scering and washing of stones aggagate without shuttering (S.I.No. 5(f) P-17).	694	Cft	14429.25	% Cft 100,139
12	S/Fixing M.S Girder at site of work.	20.0	Cwt	3850.00	P.Cwt 77000

[Signature]
Executive Engineer

13	S/ Fixing T-iron at site of work.	17.0	Cwt	3575.00	P.Cwt	60775
14	Erecting rail steel beams or old rail in roofs etc correction and fixing in position.(S.I.No:6-P.91)	37.00	Cwt	186.34	P.Cwt	6895
15	Second class tile roofing consisting of 4"earth and 1"mud plaster with gobri leaping over 1/2" thick cement plaster. 1:6 with 34lbs. of hot bitumen coating sand blinded provide over 2, layers of tiles 12" x 6" 1/4 " laid in 1:6 cement mortar with 1/2" thick sand witched layer of 1:6 cement pointing under side of tiles complete including curing etc.(S.I.No:02-P.33)	1098	Sft	7607.25	%Sft	83528
16	Providing single layer of polythine sheet 0.13" thick for water proofing as per specifying and instruction of Engineer.(S.I.No: 38-P.38)	1098	Sft:	10.70	P.Sft:	11,749
17	Single layer of tiles 9" x4 1/2" x 2" laid over 4" earth 1" mud plaster without Bhoosa grouted with cement sand 1:3 on top of R.C.C slab provide with 34 Lbs. Bitumen coating sand blinded. (SINO:05-P.34)	1098	Sft:	5310.35	%Sft	58,308
18	Cement plaster 1:6 upto 20'ft height 3/4" thick (SINO.13(b)-P-52).	4689	Sft	2206.60	% Sft	103,467
19	Cement plaster 1:4 3/8" thick upto 20'ft height (SINO:11(A)-P-52).	4689	Sft	2197.52	% Sft	103,042
20	Cement Pointing Strking joints on walls 1:3 ratio. (S.I.No. 19(a) P-53).	1265	Sft	1287.44	% Sft	16,286
21	Providing and fixing G.I. frame/chowkats of size 7"x2" x4 1/2"x3" for door using 20 gauge G.I. sheet welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost also i/c all carriage, tools and plants used in making and fixing(SINO:28-29-P-93.)					
	Doors	146	Rft	228.90	P.Rft	33,419
	Windows	355	Rft	240.50	P.Rft	85,378
22	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" i/c and frame of flate iron patti of 3/4" x 3/4" i/c cilcle shape at 1-0 apart equivalent fitted with screw or pins i/c painting 3 coats with 1 coat of red oxide paint etc.(S.I.No.30 P-94).	210	Sft	194.16	P.Sft	40,774


Executive Engineer
Buildings Division
Kamher-Shahdadt

23	First Class deodar wood wrought joinery in doors and windows etc fixed in position i/c chowkats hold fasts hinges, iron, tower bolts, handles and cords with hooks, Deodar paneled or paneled and glazed or fully glazed (b) 1x3/4" thick etc complete.(SI NO: 7a P-58) (Only Shutters).	240	Sft	902.93	P.Sft:	216,703
24	laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 (S.I.No. 60 P-47).	891	Sft	27747.06	% Sft	247,226
25	White Glazed tiles 1/4 "thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4 "thick i/c finishing. (SI NO 37 P-45).	330	Sft	28253.61	% Sft	93,237
26	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and a pattern of still specification in white cement and pigment over a base of	60	Sft	30509.77	% Sft:	18,306
27	First class deodar wood wrought joinery work in wire gauze door and windows with 22 S.W.G Galvanized wire gauze 144 mesh per square inch iron fittings complete. Glvanized wire gauze fixed to chowkats with 3/4" deodar strips and screws (S.I.No. 14(d) P-60).	204	Sft	190.72	P.Sft:	38,907
28	Priming coat of chalk distemper (S.I.No. 23 P-54).	921	Sft	442.75	% Sft	4,078
29	Distempering in three Coats. (SINO.24(c)P-54).	921	Sft	1079.65	% Sft	9,944
30	Preparing the surface and painting with matt finish I/c rubbing the surface with Bathy (silicon carbide rubbing brick) filling the voids with zink /chalk / plaster of paris	2794	Sft:	2717	% Sft	75,913
31	Preparing the surface and painting % sft with weather coat i/c rubbing th surface paper filling the weather coat appr: new surface (SINO:(a-b) 38 P-56).	2248	Sft:	2567.95	% Sft	57,728
32	Painting doors and windows any type etc complete New surface painting door and windows (SINO:5(C) - P-69/70).	597	Sft	2116.41	% Sft	12,635
33	(d) Preparing surface and painting guard bars, gates of iron bars, gratings, railings (including standards braces, etc). And similar open work.(SINO:5(d)-P-70)	949	Sft	896.39	% Sft	8,507
34	Providing & fixing false ceiling of thermopile in panels of required design and size including frame work of Aluminum T-section hanged with nail wire to ceiling etc: completed(SINO:43 P-39).	945	Sft:	91.5	P.Sft:	86,468


Executive Engineer
Building Division
Kambar Chaudhokot

35 Providing & fixing plaster of pairs ceiling
border of 8" or 10" with of specified design
and thikness i/c fixing besidees ceiling with
nails / screws with jetties.(SINO:44 P-39).

240 Rft: 104.22 P.Rft: 25,013

TOTAL RS:- 2,510,697


**Executive Engineer
(Buildings) Division
Kamber-Shahdadkot.**

EXECUTIVE ENGINEER BUILDING DIVISION KAMBER-SHAHDADKOT



**SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY
(SPPRA)
STANDARD BIDDING DOCUMENT**

Name of Work:- CONSTRUCTION OF PRESS CLUB AT WARAH CITY .

N.I.T No. & Date: XEN/(B)TC/ 220 Dated: 29-03-2018

Date of Issue up to: 19-04-2018

Date of Opening: 19-04-2018

Tender Issued to.

D.R No. & Date:

Amount of Tender Fee:

3000/-

**EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT**

Email:- xenbuildingskamber@gmail.com

**NIT S.NO. 3
CONTRACT / BIDDING DATA**


The following specific data for the works to be tendered shall complement, amend or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instruction to Bidders.

Instruction to Bidders.

Clause Reference

- | | | |
|---------|---|---|
| 1. | Name and Address of the Procuring Agency:- | Office of the Executive Engineer, Buildings Division
Kamber-Shahdadt@ D.C Secretariat Kamber. |
| 2. | Name of the Project and Summary of the Work:- | CONSTRUCTION OF PRESS CLUB AT WARAH CITY. |
| 3. | Name of the Borrower/Source of Financing / Funding Agency / Funding Source. | Government of Sindh |
| 4. | Amount and Type of Financing / Scheme Cost and Allocation Funds:- | Cost of scheme Rs: 3.300 Million
Allocation Rs: Million |
| 5. | Time for clarification:- | Three days prior to submission of bids. |
| 6. | Bid Language:- | English |
| 7. | Prequalification Information to be updated (Where applicable) :- | |
| 8. | Furnish and Technical Proposal (in case of two evolve method) of Company Profile in single stage Single Envelope:- | Single Stage / Single Envelope |
| 9. | Bidders to quote entirely in Pak. Rupees but specify the percentage of foreign currency they require, if applicable:- | Pakistan Rupees. |
| 10. | Period of Bid Validity:- | 90 Days |
| 11. | Amount of Bid Security:- | 5% of Bid Price |
| 12. | Venue, time and date of the Pre-Bid meeting:- | -- |
| 13. | Number of copies of the bid to be completed and returned:- | ONE |
| 14. | Procuring Agency's address for the purpose of bid submission :- | As Above |
| 15. | Name and Identification Number of the Contract:- | Various Development schemes of District Kamber-Shahdadt (31 Nos.) (Provincial ADP No.1129) 2015-16 |
| 16. (a) | Deadline for submission of bids: | Bid submission 19-04-2018 upto 1.00 P.M
19-14-2018 up to 2.00 PM |
| (b) | Venue, time and date of bid opening :- | Bid opening 08-05-2018 at 1.30 P.M
08-05-2018 at 2.30 |
| 17. | Standard form and amount of Performance Security acceptable to the procuring agency:- | Office of the Executive Engineer, Buildings Division
Kamber-Shahdadt@ D.C Secretariat Kamber. |
| 18. | Stamp duty | 5%
0.30% will be paid by successful bidder as stamp duty. |

CONTRACTOR


Executive Engineer
Buildings Division
Kamber-Shahdadt


CONSTRUCTION OF PRESS CLUB AT WARAH DISTRICT KAMBER-SHAHDADKOT

SCHEDULE-B


S.No.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
Main Building Cical Work					
1	Excavation in foundation of buildings in other structure with excavated earth watering and ramming lead upto one chain 5 ft in ordinary soil (SINO: 18-P-4).	1719	Cft	3176.25	%0Cft 5,460
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (SINO: 4(C) P 15).	430	Cft	8694.95	% Cft 37,388
3	Pacca brick work in foundation and plinth in 1:6 ratio.(SINO: 04(E)(P21)	1747	Cft	11948.36	% Cft 208,738
4	Reinforced cement concrete work i/c in all labor and material except the cost of steel reinforced and labor for bending and which will be paid separately. This rate also i/c all kinds of forms molds lifting shiting Curring rendering and finishing the exposed surface i/c screening and washing of shingle. Ratio (1:2:4) 90 lbs cement 2 cft. Sand 4 cft shingle 1/8" to 1/4" gauge. (SINO: 6(a)-P-17).	418	Cft	337	P.Cft 140,866
5	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints fastening i/c coat of binding wire also i/c removal of rust from bars. (SINO: 8 (b) P-17).	19.107	Cwt.	5001.70	P.Cwt 95,568
6	Filling watering ramming earth under floor with new earth (excavated from out side) lead upto 1 chain lift upto 5 ft(SINO:22-P-4).	4576	Cft	3630	%0Cft 16,611
(B)	Extra lead of earth filling 3 miles.	4576	Cft	579.41	%Cft 26,514
7	Supplying and filling sand under floor and plaguing in to walls (SINO: 29 P-26.)	1144	Sft	1141.25	% Sft: 13,056
(B)	Extra lead of earth filling 3 miles.	1144	Cft	579.41	%Cft 6,628
8	Providing single layer of polythine sheet 0.13" thick for water proofing as per specifying and instruction of Engineer (S.I.No. 38 P-38)	241	Sft	10.70	P.Sft 2,579
9	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:4:8 (SINO: 4 (b) P 15).	755	Cft	9416.28	% Cft 71,093
10	Pacca Brick Work in G. Floor (1:6) Cement Sand mortor(S.No:5(E) P-21).	1663	Cft	12674.36	% Cft 210,775
11	Cement concrete plain 1:2:4 ratio i/c placing compacting finishing and curring complete i/c scerring and washing of stones aggagate without shuttering (S.I.No. 5(f) P-17).	694	Cft	14429.25	% Cft 100,139
12	S/Fixing M.S Girder at site of work.	20.0	Cwt	3850.00	P.Cwt 77000

Executive Engineer

13	S/ Fixing T-iron at site of work.	17.0	Cwt	3575.00	P.Cwt	60775
14	Erecting rail steel beams or old rail in roofs etc correction and fixing in position.(S.I.No:6-P.91)	37.00	Cwt	186.34	P.Cwt	6895
15	Second class tile roofing consisting of 4" earth and 1" mud plaster with gobri leaping over 1/2" thick cement plaster. 1:6 with 34lbs. of hot bitumen coating sand blinded provide over 2, layers of tiles 12" x 6" 1/4 " laid in 1:6 cement mortar with 1/2" thick sand witched layer of 1:6 cement pointing under side of tiles complete including curing etc.(S.I.No:02-P.33)	1098	Sft	7607.25	%Sft	83528
16	Providing single layer of polythine sheet 0.13" thick for water proofing as per specifying and instruction of Engineer.(S.I.No: 38-P.38)	1098	Sft:	10.70	P.Sft:	11,749
17	Single layer of tiles 9" x4 1/2" x 2" laid over 4" earth 1" mud plaster without Bhoosa grouted with cement sand 1:3 on top of R.C.C slab provide with 34 Lbs. Bitumen coating sand blinded. (SINO:05-P.34)	1098	Sft:	5310.35	%Sft	58,308
18	Cement plaster 1:6 upto 20'ft height 3/4" thick (SINO.13(b)-P-52).	4689	Sft	2206.60	% Sft	103,467
19	Cement plaster 1:4 3/8" thick upto 20'ft height (SINO:11(A)-P-52).	4689	Sft	2197.52	% Sft	103,042
20	Cement Pointing Strking joints on walls 1.3 ratio. (S.I.No. 19(a) P-53).	1265	Sft	1287.44	% Sft	16,286
21	Providing and fixing G.I. frame/chowkats of size 7"x2" x41/2"x3" for door using 20 gauge G.I. sheet welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost also i/c all carriage, tools and plants used in making and fixing(SINO:28-29-P-93.)					
	Doors	146	Rft	228.90	P.Rft	33,419
	Windows	355	Rft	240.50	P.Rft	85,378
22	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" i/c and frame of flate iron patti of 3/4" x 3/4" i/c cilcle shape at 1-0 apart equivalent fitted with screw or pins i/c painting 3 coats with 1 coat of red oxide paint etc.(S.I.No.30 P-94).	210	Sft	194.16	P.Sft	40,774


Executive Engineer
Buildings Division
Ramber-Shahandkot


23.	First Class deodar wood wrought joinery in doors and windows etc fixed in position i/c chowkats hold fasts hinges, iron, tower bolts, handles and cords with hooks, Deodar paneled or paneled and glazed or fully glazed (b) 1x3/4" thick etc complete.(SI NO: 7a P-58) (Only Shutters).	240	Sft	902.93	P.Sft:	216,703
24	laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 (S.I.No. 60 P-47).	891	Sft	27747.06	% Sft	247,226
25	White Glazed tiles 1/4 "thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4 "thick i/c finishing. (SI NO 37 P-45).	330	Sft	28253.61	% Sft	93,237
26	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and a pattern of still specification in white cement and pigment over a base of	60	Sft	30509.77	% Sft:	18,306
27	First class deodar wood wrought joinery work in wire gauze door and windows with 22 S.W.G Galvanized wire gauze 144 mesh per square inch iron fittings complete. Glvanized wire gauze fixed to chowkats with 3/4" deodar strips and screws (S.I.No. 14(d) P-60).	204	Sft	190.72	P.Sft:	38,907
28	Priming coat of chalk distemper (S.I.No. 23 P-54).	921	Sft	442.75	% Sft	4,078
29	Distempering in three Coats. (SINO:24(c)P-54).	921	Sft	1079.65	% Sft	9,944
30	Preparing the surface and painting with matt finish i/c rubbing the surface with Bathy (silicon carbide rubbing brick) filling the voids with zink /chalk / plaster of paris	2794	Sft:	2717	% Sft	75,913
31	Preparing the surface and painting % sft with weather coat i/c rubbing th surface paper filling the weather coat appr: new surface (SINO:(a-b) 38 P-56).	2248	Sft:	2567.95	% Sft	57,728
32	Painting doors and windows any type etc complete New surface painting door and windows (SINO:5(C) - P-69/70).	597	Sft	2116.41	% Sft	12,635
33	(d) Preparing surface and painting guard bars, gates of iron bars, gratings, railings (including standards braces, etc). And similar open work.(SINO:5(d)-P-70)	949	Sft	896.39	% Sft	8,507
34	Providing & fixing false ceiling of thermopile in panels of required design and size including frame work of Aluminum T-section hanged with nail wire to ceiling etc: completed(SINO:43 P-39).	945	Sft:	91.5	P.Sft:	86,468


 Executive Engineer
 Building Division
 Kamber-Sachdalkot

35. Providing & fixing plaster of pairs ceiling
border of 8" or 10" with of specified design
and thikness i/c fixing besidees ceiling with
nails / screws with jetties.(SINO:44 P-39).

240 Rft: 104.22 P.Rft: 25,013

TOTAL RS:- 2,510,697


**Executive Engineer
(Buildings) Division
Kamber-Shahdadkot.**

EXECUTIVE ENGINEER BUILDINGS DIVISION KAMBER-SHAHDADKOT

**STANDARD BIDDING DOCUMENT
PROCUREMENT OF WORKS
(For Contracts Costing up to Rs 2.5 MILLION)**

**NAME OF WORK:- CONSTRUCTION OF COMMUNITY CENTRE , LIBRARY & PRESS
CLUB AT WARAH CITY (C/WALL)**

Standard Bidding Document is intended as a model for admeasurements (Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.


**EXECUTIVE ENGINEER,
BUILDINGS DIVISION**

KAMBER-SHAHDADKOT

Email:- xenbuildingskamber@gmail.com

NIT S.NO: 04

BIDDING DATA

Name of Contractor:- _____

(This section should be filled in by the Executive Engineer/ Project Agency before issuance of the Biding Documents).

Name of Contractor:- _____

(a). Name of Procuring Agency :-

Executive Engineer, Buildings Division
Kamber-Shahdadt @ D.C Secretariat Kamber.

1. Brief Description of Works:-

CONSTRUCTION OF COMMUNITY CENTRE , LIBRARY & PRESS
CLUB AT WARAH CITY (C/WALL)

(b). Procuring Agency's Address:-

D.C Complex Kamber.

(c). Estimated Cost: -

Rs. 2.000 (Million)

(d). Amount of Bid Security: -

05%

(Fill in lum sum amount in %age of bid
amount / estimated cost, but not exceeding 5%)

(e). Period of Bid Validity (days) :-

90 Days

(f). Security Deposit (including bid security) :-

(in %age of bid amount / estimated cost equal to 10%)

1.

(g). Percentage, if any, to be deducted from bills:- 07.50% (I/Tax) & 5% Security Deposit.

(h). Deadline for Submission of Bids along with time:- Dated: 19-04-2018 up to Time 1.00 P.M
19-04-2018 up to Time 2.00 P.M

(i). Venue, Time, and Date of Bid Opening:- Dated: 08-05-2018 at Time 1.00 P.M
08-05-2018 at Time 2.00 P.M

Office of the Executive Engineer, Buildings Division
Kamber-Shahdadt @ D.C Secretariat Kamber.

(j). Time for Completion from written order of commence:- _____

(k). Liquidity damages:-

(0.05 of Estimated Cost or N\Bid Cost per day of delay,
But total not exceeding 10%)

(i). Call Deposit Receipt :- No. _____ Dated: _____ Amount:- _____/-

(m). D.R. No. No. _____ Dated: _____ Amount:- 3000/-

(m). Rate quoted by Contractor: - Part-A Rs. _____ Part-B Rs. _____
Part-C Rs. _____ Part-D Rs. _____

(CONTRACTOR)


EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT

Contd: P/2

ESTIMATE for the Work:

SCHEDULE "B"

S#	NAME OF ITEM	Qty	Rate	UNIT	Amount
1	Excavation of foundation of Buildings and other structure i/c doge belling dressing refilling around structure with excavated earth watering and ramming lead up to 5'ft. (S.I.No: 18(b) P- 4).	4977 Cft	3176.25	%oCft	15808
2	Cement Concrete Brick or stone ballast 1 ½ " to 2" gage 1:5:10 (S.I.No:4, (c) P-15).	830 Cft	8694.95	%Cft	72168
3	Reinforced cement concrete work i/c in all labor and material except the cost of steel reinforced and labor for bending and which will be paid separately. This rate also i/c all kinds of forms molds lifting shiting Curring rendering and finishing the exposed surface i/c screening and washing of shingle. Ratio (1:2:4) 90 lbs cement 2 cft. Sand 4 cft shingle 1/8" to ¼"	1500 Cft	337.00	P.Cft	505500
4	Fabrication of mild steel reinforcement for cement concrete including cutting bending, laying in position. Making joints and fastenings including cost of binding wire (also include removal of rust from bars. (S.I.No:8(b) P-17).	67.0 Cwt	5001.70	P.Cwt	334935
5	Pacca brick work in foundation and plinth in 1:6 ratio.(SINO: 04(E)(P21)	1464 Cft	11948.36	%Cft	174924
6	Pacca brick work other than building i/c stricking joints upto 20' feet height in (SI NO. 7(E) P-22).	972 Cft.	12346.7	%Cft	120009
7	Cement plaster 1:6 upto 20'ft height 1/2" thick (SINO.13(b)-P-52).	5184 Sft	2206.60	% Sft	114390
8	Cement plaster 1:4 3/8" thick upto 20'ft height (SINO:11(A)-P-52).	5184 Sft	2197.52	% Sft	113919
9	Cement Pointing Strking joints on walls 1.2 ratio. (S.I.No. 19(a) P-53).	2592 Sft	1287.44	% Sft	33370
10	Preparing the surface and painting % sft with weather coat i/c rubbing th surface paper filling the weather coat appr: new surface (SINO:(a-b) 38 P-56).	8400 Sft	2567.95	% Sft	215708
11	Making & fixing steel grated doors with complete locking arrangements angle iron frame 2"x2"x3/8" & ¾" square bars 4" centre (S.I.No. 24 P-92).	60 Sft:	726.72	P.Sft:	43,603

TOTALRS 1744336


Executive Engineer,
(Buildings) Division
Ramber-Shahdadt.

EXECUTIVE ENGINEER BUILDINGS DIVISION KAMBER-SHAHDADKOT

**STANDARD BIDDING DOCUMENT
PROCUREMENT OF WORKS
(For Contracts Costing up to Rs 2.5 MILLION)**

**NAME OF WORK:- CONSTRUCTION OF COMMUNITY CENTRE LIBRARY, & PRESS
CLUB AT WARAH CITY (ELECTRIC WORK)**

Standard Bidding Document is intended as a model for admeasurements (Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.


**EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT**

Email:- xenbuildingskamber@gmail.com

NIT S.NO: 05

BIDDING DATA

Name of Contractor:- _____

(This section should be filled in by the Executive Engineer/ Project Agency before issuance of the Biding Documents).

Name of Contractor:-

(a). Name of Procuring Agency :-

Executive Engineer, Buildings Division
Kamber-Shahdadkot @ D.C Secretariat Kamber.

1. Brief Description of Works:-

CONSTRUCTION OF COMMUNITY CENTRE LIBRARY, & PRESS
CLUB AT WARAH CITY (ELECTRIC WORK)

(b). Procuring Agency's Address:-

D.C Complex Kamber.

(c). Estimated Cost: -

Rs. 0.500 (Million)

(d). Amount of Bid Security: -

05%

(Fill in lum sum amount in %age of bid
amount / estimated cost, but not exceeding 5%)

(e). Period of Bid Validity (days) :-

90 Days

(f). Security Deposit (including bid security) :-

(in %age of bid amount / estimated cost equal to 10%)

1.

(g). Percentage, if any, to be deducted from bills:-

07.50% (I/Tax) & 5% Security Deposit.

(h). Deadline for Submission of Bids along with time:- Dated: 19-04-2018 up to Time 1.00 P.M

19-04-2018 up to Time 2.00 P.M

(i). Venue, Time, and Date of Bid Opening:- Bid opening Dated: 08-05-2018 at Time 1.00 P.M

08-05-2018 at Time 2.00 P.M

Office of the Executive Engineer, Buildings Division
Kamber-Shahdadkot @ D.C Secretariat Kamber.

(j). Time for Completion from written order of commence:-

(k). Liquidity damages:-

(0.05 of Estimated Cost or N\Bid Cost per day of delay,
But total not exceeding 10%)

(i). Call Deposit Receipt :- No. _____ Dated: _____ Amount:- _____/-

(m). D.R. No. _____ No. _____ Dated: _____ Amount:- 1500/-

(m). Rate quoted by Contractor: - Part-A Rs. _____ Part-B Rs. _____
Part-C Rs. _____ Part-D Rs. _____

(CONTRACTOR)

EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT

Contd: P/2

**CONSTRUCTION OF COMMUNITY CENTER LIBRARY & PRESS CLUB AT WARAH CITY TALUKA
WARAH (ELECTRIC WORK) DISTRICT KAMBER-SHAHDADKOT**

SCHEDULE-B


S.N o.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
<u>ELECTRIC WORK</u>					
<u>"A". SCHEDULE ITEMS</u>					
1	Wiring for light or fan point with 3/.029 PVC insulated wire in 20mm (3/4") PVC channel patti on surface as required. (SINO: 129-P-15)	150 Nos	910.0	P.NO	136,500
2	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4") PVC channel patti on surface as required. (SINO: 130-P-15)	50 Nos	742.0	P.NO	37,100
3	Wiring for light point or fanpoint with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (SINO: 124-P-15)	10 Nos	1130.0	P.NO	11,300
4	Wiring for light point or fanpoint with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (SINO: 124-P-15)	8 Nos	797.0	P.NO	6,376
5	Providing and laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 2-7/4" dia PVC conduit on surface. (SINO:3-P-1)	95 Nos	171.0	P.M	16,245
6	Providing and laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044(6mm2) copper conductor in 1" dia PVC conduit on surface. (SINO:5-P-1)	90	305	P.M	27,450
7	Providing and laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.052(10mm2) copper conductor in 1" dia PVC conduit on surface. (SINO:6-P-1)	90	428.00	P.M	38,520
8	Providing and fixing one way SP 5amp switch flush type.(SINO:219-P-33)	5 Nos	54.00	P.NO	270
9	Providing and fixing 2 pin 5amp plug and socket flush type.(SINO:225-P-33)	5 Nos	83.00	P.NO	415
10	Providing and fixing brass pattern holder.(SINO:232-P-33)	40 Nos	70.00	P.NO	2,800
11	Providing and fixing brass back light ceiling rose with 2 terminals.(SINO:228-P-33)	11 Nos	72.00	P.NO	792
12	Providing and fixing brass ceiling fan 56" (good quality).(SINO:235-P-34)	16 Nos	3185	P.NO	50,960
13	Providing and fixing circuit breaker 15,20,30,40,50,and 60 amp TP (XS-100NS) on prepared board as required.(SINO:207-P-31)	2 Nos	9261	P.NO	18,522
14	Providing and fixing circuit breaker 6,10,15,20,30,40,50,and 63 amp SP on prepared board as required.(SINO:203-P-31)	18 Nos	916	P.NO	16,488
15	Providing and fixing volt meter size 96/96mm500 volts as required and as per instruction of EI (SINO:285 P-41.)	1 Nos	599.00	P.NO	599
16	Providing and fixing DP/ i/c change over switch 500 volts 60 amp on prepared board as required.(SINO:196-P-30)	1 Nos	3559.5	P.NO	3,560
TOTAL:-					367,897

Schedule B

**Executive Engineer
Buildings Division
Kamber-Shahdadt**

S.N.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
PART "B" NON-SCHEDULE ITEMS					
1	Embossed Fan	3 Nos	5000	P.NO	15,000
2	Providing and fixing A.C ceiling fan regulator on S.W board.	15 Nos	500	P.NO	7,500
3	Providing & Fixing Mild steel bar fan clamp 15.8 mm (5/8") dia suitable for roof.	10 Nos	224	P.NO	2,240
4	Providing and fixing 2 pin lamp plug and socket flush type (China)	100 Nos	250.00	P.NO	25,000
5	Providing and fixing bulk head external light	10 Nos	600	P.NO	6,000
6	Providing and fixing 3 pin 40 amp plug and socket flush type. (China)	10 Nos	450.00	P.NO	4,500
7	Providing and fixing Energy saver quality i/c finishing on existing holder etc complete.	50 Nos	497.00	P.NO	24,850
8	Providing and fixing False Ceiling LED light i/c finishing on existing holder etc complete.	50 Nos	800.00	P.NO	40,000

TOTAL:-	131,834
----------------	----------------



Executive Engineer
Buildings Division
Kamber-Shahdada Kot

EXECUTIVE ENGINEER BUILDINGS DIVISION KAMBER-SHAHDADKOT

**STANDARD BIDDING DOCUMENT
PROCUREMENT OF WORKS
(For Contracts Costing up to Rs 2.5 MILLION)**

NAME OF WORK:- CONSTRUCTION OF COMMUNITY CENTRE (BALANCE WORK) AT WARAH .

Standard Bidding Document is intended as a model for admeasurements (Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.


**EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT**

Email:- xenbuildingskamber@gmail.com

NIT S.NO: 06

BIDDING DATA

Name of Contractor:- _____

(This section should be filled in by the Executive Engineer/Project Agency before issuance of the Biding Documents).

Name of Contractor:-

(a). Name of Procuring Agency :-

Executive Engineer, Buildings Division
Kamber-Shahdadt @ D.C Secretariat Kamber.

1. Brief Description of Works:-

CONSTRUCTION OF COMMUNITY CENTRE (BALANCE WORK) AT
WARAH.

(b). Procuring Agency's Address:-

D.C Complex Kamber.

(c). Estimated Cost: -

Rs. 1.000 (Million)

(d). Amount of Bid Security: -

05%

(Fill in lum sum amount in %age of bid
amount / estimated cost, but not exceeding 5%)

(e). Period of Bid Validity (days) :-

90 Days

(f). Security Deposit (including bid security) :-

(in %age of bid amount / estimated cost equal to 10%)

1.

(g). Percentage, if any, to be deducted from bills:- 07.50% (I/Tax) & 5% Security Deposit.

(h). Deadline for Submission of Bids along with time:- Dated: 19-04-2018 up to Time 1.00 P.M

19-04-2018 up to Time 2.00 P.M

(i). Venue, Time, and Date of Bid Opening:- Bid opening Dated: 08-05-2018 at Time 1.00 P.M

08-05-2018 at Time 2.00 P.M

Office of the Executive Engineer, Buildings Division
Kamber-Shahdadt @ D.C Secretariat Kamber.

(j). Time for Completion from written order of commence:-

(k). Liquidity damages:-

(0.05 of Estimated Cost or NBid Cost per day of delay,
But total not exceeding 10%)

(i). Call Deposit Receipt :- No. _____ Dated: _____ Amount:- _____/-

(m). D.R. No. _____ No. _____ Dated: _____ Amount:- 3000/-

(m). Rate quoted by Contractor: - Part-A Rs. _____ Part-B Rs. _____
Part-C Rs. _____ Part-D Rs. _____

(CONTRACTOR)

EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT


Contd: P/2

CONSTRUCTION OF CUMMUNITY CENTRE (BALANCE WORK) AT WARAH DISTRICT KAMBER-SHAHDADKOT


SCHEDULE-B

S.No	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
1	Excavation in foundation of building, Bridges & other structures including digbelling, dressing, refilling around structure with excavated earth watering and ramming lead upto 5 ft, in ordinary soil. (SINO: 18(b)-P-4).	505 Cft:	3176.25	%0Cft:	1,604
2	Cement concret brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (SINO. 4(b) P-16)	173 Cft:	9416.28	%Cft	16,290
3	Pacca brick work in foundation and plinth in 1:6 ratio. (S.I.No:04(e)P-21)	200 Cft:	11948.36	%Cft	23,897
4	Reinforced cement concrete work i/c in all labor and material except the cost of steel reinforced and labor for bending and which will be paid separately. This rate also i/c all kinds of forms molds lifting shiting Curring rendering and finishing the exposed surface i/c screening and washing of shingle. Ratio (1:2:4) 90 lbs cement 2 cft. Sand 4 cft shingle 1/8" to 1/4" gauge. (SINO: 6-P-19).	283 Cft:	337	P.Cft:	95,371
5	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints fastening i/c coat of binding wire also i/c removal of rust from bars. (SINO: 7 (b) P-20).	13.27 Cwt.	5001.70	P.Cwt	66,351
6	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lead upto one chain and lift upto 5 feet(S.I.NO:22P-04)	1250 Cft:	3630.00	%0Cft:	4,538
B	Extra lead of 3 miles	1250 Cft.	579.41	%Cft	7243
7	Supplying and filling sand under floor and plaguing in to walls. (S.I.NO:29-P.26)	469 Cft:	1141.25	%Cft	5,352
B	Extra lead of 3 miles	469 Cft.	579.41	%Cft	2717
8	Pacca brick work other than building i/c striking joints upto 20' feet height in (SI NO. 7 P-26).	375 Cft.	12346.65	%Cft	46300
9	Pacca brick work in Ground Floor in (e) Cement sand mortor 1:6 (SINO. 5(e) P-25)	35 Cft.	12674.36	%Cft	4,436
10	Cement plaster 1:6 upto 20'ft height 1/2" thick (SINO.13(b) P-58).	203 Sft:	2206.60	%Sft	4,479

Schedule B


Executive Engineer
Building Division


S.No	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
11	Cement plaster 1:4 3/8" thick upto 20'ft height (SINO:10 P-57).	203 Sft:	2197.52	%Sft	4,461
12	Providing and fixing ornament Cement jali 2" thick 1:2:4 without steel.	280 Sft:	226.02	P.Sft:	63,286
13	First Class deodar wood wrought joinery in doors and windows etc fixed in position i/c chowkats hold fasts hinges, iron, tower bolts, handles and cords with hooks, Deodar paneled or paneled and glazed or fully glazed (b) 1x3/4" thick etc complete. (SI NO: 7 P-65) (Only Shutters).	419 Sft:	902.93	P.Sft:	378,328
14	Providing and fixing G.I. frame/chowkats of size 7"x2" x41/2"x3" for door using 20 gauge G.I. sheet welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost also i/c all carriage, tools and plants used in making and fixing(SINO:29 P-98.)				
A	Doors	37 Rft	228.90	P. Rft:	8,469
B	Windows	114 Rft	240.50	P-Rft:	27,417
15	Cement concrete plain 1:2:4 ratio i/c placing compacting finishing and curring complete i/c scering and washing of stones aggagate without shuttering (S.I.No. 5(f) P-17).	313 Cft:	14429.25	%Cft	45,164
16	Priming coat of chalk distemper(SINo.23P-53).	701 Sft:	442.75	%Sft	3,104
17	Distempering in three Coats.(SINo.24P-54).	701 Sft:	1079.65	%Sft	7,568
18	Preparing the surface and painting with matt finish I/c rubbing the surface with Bathy (silicon carbide rubbing brick) filling the voids with zink /chalk / plaster of paris mixture, applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete .(new surface)..(SINo.36A. P-55).	760 Sft:	2717	%Sft	20,649
19	Preparing the surface and painting % sft with weather coat i/c rubbing th surface paper filling the weather coat appr: new surface 3 coats. (SINO: 38 P-56).	700 Sft:	2567.95	%Sft	17,976


 Executive Engineer
 Buildings Division
 Kamber-Shahdadi Kot

S.No	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
20	Painting doors and windows any type etc complete New surface painting door and windows 3 coats. (SINO:5(C) / P-69/70).New Surface	87 Sft:	2116.41	%Sft	1,845
21	P/F angle iron vertical plsts for barbed wire fencing of sizes 2" x 2" x1/4" embedded in R.C.C / masonry pillars i/c making cutts / holders @ 12" i/c fixing in pillars by chiseling & filling the with cement sand mortor sapring and finishing the surface.(SINO:08-P-95)	250 P.Rft	169.18	P.Rft	42,295

G.TOTAL:-	899,139
------------------	----------------

CONTRACTOR



 Executive Engineer
 (Buildings) Division
 Kamber-Shahdadkot.

EXECUTIVE ENGINEER BUILDINGS DIVISION KAMBER-SHAHDADKOT

**STANDARD BIDDING DOCUMENT
PROCUREMENT OF WORKS
(For Contracts Costing up to Rs 2.5 MILLION)**

**NAME OF WORK:- CONSTRUCTION OF PAVER BLOCK & DRAINS AT BARKAT SHAH
MUHALLAH FROM GHULAM RASOOL CHANDIO HOUSE TO BY PASS
ROAD TALUKA KAMBER, DISTRICT KAMBER-SHAHDADKOT.
(BALANCE WORK)**

Standard Bidding Document is intended as a model for admeasurements (Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.


**EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT**

Email:- xenbuildingskamber@gmail.com

NIT S.NO: 07

BIDDING DATA

Name of Contractor:- _____

(This section should be filled in by the Executive Engineer/ Project Agency before issuance of the Biding Documents).

Name of Contractor:-

(a). Name of Procuring Agency :-

Executive Engineer, Buildings Division
Kamber-Shahdadt @ D.C Secretariat Kamber.

1. Brief Description of Works:-

CONSTRUCTION OF PAVER BLOCK & DRAINS AT BARKAT SHAH
MUHALLAH FROM GHULAM RASOOL CHANDIO HOUSE TO BY
PASS ROAD TALUKA KAMBER, DISTRICT KAMBER-SHAHDADKOT.
(BALANCE WORK)

(b). Procuring Agency's Address:-

D.C Complex Kamber.

(c). Estimated Cost: -

Rs. 0.980 (Million)

(d). Amount of Bid Security: -

05%

(Fill in lump sum amount in %age of bid
amount / estimated cost, but not exceeding 5%)

(e). Period of Bid Validity (days) :-

90 Days

(f). Security Deposit (including bid security) :-

(in %age of bid amount / estimated cost equal to 10%)

1.

(g). Percentage, if any, to be deducted from bills:- 07.50% (I/Tax) & 5% Security Deposit.

(h). Deadline for Submission of Bids along with time:- Dated: 19-04-2018 up to Time 1.00 P.M

19-04-2018 up to Time 2.00 P.M

(i). Venue, Time, and Date of Bid Opening:- Bid opening Dated: 08-05-2018 at Time 1.00 P.M

08-05-2018 at Time 2.00 P.M

Office of the Executive Engineer, Buildings Division
Kamber-Shahdadt @ D.C Secretariat Kamber.

(j). Time for Completion from written order of commence:-

(k). Liquidity damages:-

(0.05 of Estimated Cost or N\Bid Cost per day of delay,
But total not exceeding 10%)

(i). Call Deposit Receipt :- No. _____ Dated: _____ Amount: _____/-

(m). D.R. No.

No. _____ Dated: _____ Amount:- 3000/-

(m). Rate quoted by Contractor: - Part-A Rs. _____ Part-B Rs. _____

Part-C Rs. _____ Part-D Rs. _____

(CONTRACTOR)


EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT

Contd: P/2

DETAILED WORKING ESTIMATE FOR CONSTRUCTION OF PAVER BLOCK & DRAINS
AT BARKAT SHAH MUHALLAH FROM GHULAM RASOOL CHANDIO HOUSE TO BY
PASS ROAD TALUKA KAMBER, DISTRICT KAMBER SHAHDADKOT.(BALANCE WORK)

PART "A" CIVIL WORK
SCHEDULE-B

S.No.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
1	Excavation in foundation of buildings in other structure with excavated earth watering and ramming lead upto one chain 5 ft in ordinary soil (SINO: 18-P-4).	23 Cft:	3176.25	%0 Cft:	71
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (SINO: 4 (b) P 17).	1181 Cft:	8694.1	% Cft	8,608
3	Cement concrete plain 1:2:4 ratio i/c placing compacting finishing and curring complete i/c scering and washing of stones aggagate without shuttering (S.I.No. 5(f) P-18).	47 Cft:	14429.25	% Cft:	6,765
4	Pacca brick work in foundation and plinth in 1:6 ratio (SINO: 04,P-24).	397 Cft:	11948.36	% Cft	47,435
5	Construction of standard open type drain concrete block of cc 1:2:4 of site drawing i/c B) Type-B Drain	65 Rft	174	P. Rft	11,310
6	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints fastening i/c coat of binding wire also i/c removal of rust from bars. (SINO: 7 (b) P-20).	0.536 Cwt.	5001.70	P. Cwt	2,679
7	Reinforced cement concrete work i/c in all labor and material except the cost of steel reinforced and labor for bending and which will be paid separately. This rate also i/c all kinds of forms molds lifting shiting Curring rendering and finishing the exposed surface i/c screening and washing of shingle. Ratio (1:2:4) 90 lbs cement 2 cft. Sand 4 cft shingle 1/8" to 1/4" gauge. (SINO: 6-P-18).	25 Cft:	337	P Cft:	8,425
8	Filling watering ramming earth under floor surplus earth excavated from foundation lead upto 1 chain lift upto 5 ft(SINO:22, P-4).	5336 Cft:	3630.00	%0 Cft:	19,370
9	Extra lead 3.0 miles for earth filling & sand	5336 Cft	579.94	% Cft:	30,946


Executive Engineer
Building Division
Kamber-Shahdadkot

- 10 Laying Murum flooring consisting of 1" layer of fine powdery or flakey variety of Murum laid over 6" good hard layer of Murum spread over 9" thick sub-base comprising of hand pcked rubble or broken bricks properly watered and rammed provided over well rammed earth. (S.I.No:01-P-40) 605 Cft: 1800.00 % Cft: 10,890
- 11 Cement plaster 1:4 upto 20'ft height ½" thick (SINO.13(b) P-58). 576 Sft: 2283.90 % Sft 13,155

TOTAL:- 159,655


PART "B" CEMENT PAVER BLOCK.
SCHEDULE-B

S.No.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6

- 1 Providing and fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city/quddra/cobble shape with ntural colours having strength b/w 5000 PSI to 8500 PSI including filling joints with hill sand and laying in specified manner/pattern and design etc complete.(S.I.No:73-P-50) 3562 Cft: 199.70 P Sft: 711,331

TOTAL:- 711,331

Contractor


Executive Engineer
Building Division
Kamber-Shahdadkot

DETAILED WORKING ESTIMATE FOR CONSTRUCTION OF PAVER BLOCK & DRAINS
AT BARKAT SHAH MUHALLAH FROM GHULAM RASOOL CHANDIO HOUSE TO BY
PASS ROAD TALUKA KAMBER, DISTRICT KAMBER SHAHDADKOT.(BALANCE WORK)

PART "A" CIVIL WORK
SCHEDULE-B

S.No.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
1	Excavation in foundation of buildings in other structure with excavated earth watering and ramming lead upto one chain 5 ft in ordinary soil (SINO: 18-P-4).	23 Cft:	3176.25	%0 Cft:	71
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (SINO: 4 (b) P 17).	1181 Cft:	8694.1	% Cft	8,608
3	Cement concrete plain 1:2:4 ratio i/c placing compacting finishing and curring complete i/c scering and washing of stones aggagate without shuttering (S.I.No. 5(f) P-18).	47 Cft:	14429.25	% Cft:	6,765
4	Pacca brick work in foundation and plinth in 1:6 ratio (SINO: 04,P-24).	397 Cft:	11948.36	% Cft	47,435
5	Construction of standard open type drain concrete block of cc 1:2:4 of site drawing i/c B) Type-B Drain	65 Rft	174	P. Rft	11,310
6	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints fastening i/c coat of binding wire also i/c removal of rust from bars. (SINO: 7 (b) P-20).	0.536 Cwt.	5001.70	P. Cwt	2,679
7	Reinforced cement concrete work i/c in all labor and material except the cost of steel reinforced and labor for bending and which will be paid separately. This rate also i/c all kinds of forms molds lifting shiting Curring rendering and finishing the exposed surface i/c screening and washing of shingle. Ratio (1:2:4) 90 lbs cement 2 cft. Sand 4 cft shingle 1/8" to 1/4" gauge. (SINO: 6-P-18).	25 Cft:	337	P Cft:	8,425
8	Filling watering ramming earth under floor surplus earth excavated from foundation lead upto 1 chain lift upto 5 ft(SINO:22, P-4).	5336 Cft:	3630.00	%0 Cft:	19,370
9	Extra lead 3.0 miles for earth filling & sand	5336 Cft	579.94	% CFT:	30,946


Executive Engineer
Building Division
Kamber-Shahdadt

- 10 Laying Murum flooring consisting of 1" layer of fine powdery or flakey variety of Murum laid over 6" good hard layer of Murum spread over 9" thick sub-base comprising of hand pcked rubble or broken bricks properly watered and rammed provided over well rammed earth. (S.I.No:01-P-40) 605 Cft: 1800.00 % Cft: 10,890
- 11 Cement plaster 1:4 upto 20ft height ½" thick (SINO.13(b) P-58). 576 Sft: 2283.90 % Sft 13,155

TOTAL:- 159,655


PART "B" CEMENT PAVER BLOCK.
SCHEDULE-B

S.No.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6

- 1 Providing and fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city/quddra/cobble shape with ntural colours having strength b/w 5000 PSI to 8500 PSI including filling joints with hill sand and laying in specified manner/pattern and design etc complete.(S.I.No:73-P-50) 3562 Cft: 199.70 P Sft: 711,331

TOTAL:- 711,331

Contractor



Executive Engineer
Buildings Division
Kamher-Subhadrakot

EXECUTIVE ENGINEER BUILDINGS DIVISION KAMBER-SHAHDADKOT

**STANDARD BIDDING DOCUMENT
PROCUREMENT OF WORKS
(For Contracts Costing up to Rs 2.5 MILLION)**

**NAME OF WORK:- REPAIR/ RENOVATION OF OLD DISTRICT COUNCIL STAFF OFFICE
AT DC OFFICE KAMBER. (NON - SALARY COMPONENTS)**

Standard Bidding Document is intended as a model for admeasurements (Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.


**EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT**

Email:- xenbuildingskamber@gmail.com

NIT S.NO: 08

BIDDING DATA

Name of Contractor:- _____

(This section should be filled in by the Executive Engineer/ Project Agency before issuance of the Biding Documents).

Name of Contractor:-

(a). Name of Procuring Agency :-

Executive Engineer, Buildings Division
Kamber-Shahdadt @ D.C Secretariat Kamber.

1. Brief Description of Works:-

REPAIR/ RENOVATION OF OLD DISTRICT COUNCIL STAFF OFFICE
AT DC OFFICE KAMBER. (NON - SALARY COMPONENTS)

(b). Procuring Agency's Address:-

D.C Complex Kamber.

(c). Estimated Cost: -

Rs. 0.600 (Million)

(d). Amount of Bid Security: -

05%

(Fill in lum sum amount in %age of bid
amount / estimated cost, but not exceeding 5%)

(e). Period of Bid Validity (days) :-

90 Days

(f). Security Deposit (including bid security) :-

(in %age of bid amount / estimated cost equal to 10%)

1.

(g). Percentage, if any, to be deducted from bills:-

07.50% (I/Tax) & 5% Security Deposit.

(h). Deadline for Submission of Bids along with time:-

Dated: 19-04-2018 up to Time 1.00 P.M

19-04-2018 up to Time 2.00 P.M

(i). Venue, Time, and Date of Bid Opening:-

Bid opening Dated: 08-05-2018 at Time 1.00 P.M

08-05-2018 at Time 2.00 P.M

Office of the Executive Engineer, Buildings Division

Kamber-Shahdadt @ D.C Secretariat Kamber.

(j). Time for Completion from written order of commence:-

(k). Liquidity damages:-

(0.05 of Estimated Cost or NBid Cost per day of delay,
But total not exceeding 10%)

(i). Call Deposit Receipt :- No. _____ Dated: _____ Amount:- _____/-

(m). D.R. No.

No. _____ Dated: _____ Amount:- 750/-

(m). Rate quoted by Contractor: - Part-A Rs. _____

Part-B Rs. _____

Part-C Rs. _____

Part-D Rs. _____

(CONTRACTOR)

EXECUTIVE ENGINEER,
BUILDINGS DIVISION
KAMBER-SHAHDADKOT

Contd: P/2

**REPAIR/RENOVATION OF OLD DISTRICT COUNCIL STAFF OFFICE AT D.C
OFFICE KAMBER DISTRICT KAMBER SHAHDADKOT.**

SCHEDULE-B

S.N o.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6

PART-A (CIVIL WORK)

1	Removing door with chowket.(S.I.No:33(a)-P.12)				
A	Door	3	No	142.18	P.No 427
B	Window	3	No	102.85	P.No 309
2	First class deodar wood wrought joinery work in wire gauze door and windows with 22 S.W.G Galvanized wire gauze 144 mesh per square inch iron fittings complete. Glvanized wire gauze fixed to chowkats with 3/4" deodar stips and screws. (S.I.No:14(d)-P.60)	20	Sft:	190.72	P.Sft: 3,814
3	Providing & fixing false ceiling of thermopile in panels of required design and size including frame work of Aluminum T- section hanged with nail wire to ceiling etc: completed(SINO:43 P-39).	45	Sft	91.5	P.Sft 4,118
4	S/f in position Alminium chanals for hinged doors or alcop	146	Sft:	1507.72	P.Sft: 220,127
5	Distempering in three Coats. (S.I.No:24(c)-P.54)	984	Sft:	1565.85	% Sft: 15,408
6	(d) Preparing surface and painting guard bars, gates of iron bars, gratings, railings (including standards braces, etc). And similar open work. (S.I.No:5(d)-P.70)	200	Sft:	896.39	% Sft: 1,793
7	Painting doors and windows any type etc complete New surface painting door and windows. (S.I.N:05(C)-P.70)	192	Sft:	1489.68	% Sft: 2,860
8	White wash of three coats. (S.I.N:26-P.54)	64	Sft:	829.95	% Sft 531

249,386

"PART B "

NON-SCHEDULE ITEMS(MARKET

1	Candian Wall Panalling	1000	Sft:	160.00	% Sft: 160,000
TOTAL:-					160,000


CONTRACTOR

(Signature)
Executive Engineer
(Buildings) Division
Kamber-Shahdadkot.

**REPAIR/RENOVATION OF OLD DISTRICT COUNCIL STAFF OFFICE AT D.C
OFFICE KAMBER DISTRICT KAMBER SHAHDADKOT.**

SCHEDULE-B (PART C) W/S & S/F

S.No.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
1	Providing & Fixing Orisa type white or coloured glazed earthen ware W.C pan with cost of low level plastic flush tank of 3 gallons capacity of approved quality i/c making requisite number of holes to wall plinth & floor & making good in cement concrete 1:2:4.(i)with 4" dia C.I trap (SINO:03(i)-P-2)	1 Nos.	5836.60	P.No	5,837
2	Providing & Fixing 24"x18" lavatory basin in white glazed earthen ware complete with i/c the cost of W.I or C.I canti lever bracket 6 inches built in to wall painted white in two coat after a primary coat of red lead paint a pair of 1/2" good in cement concrete (1:2:4) standard pattern (SINO.8-P-3)	1 Nos.	4253.70	P.No	4,254
3	Add extra for labour for providing & fixing of earthen ware Padestal white or coloured glazed (SINO.9-P-3)	1 Nos.	938.47	P.No	938
4	Providing and fixing European white glazed earthen ware wash down W.C pan complete with and i/c the cost of white/black plastic seat (Best Quality) and lid c.p brass hineges and buffers 3 gallons white glazed earthen ware low level foushing cistern with siphon fitting 1-1/2" dia white porcelain enamelled flush bend 3/4" dia and making requisite number of holes in wall and plinth and floor for pipe connection and making good in cement concrete (1:2:4) (SINO.05-P-07)	1 Nos.	11477.40	P.No	11,477
5	Providing and fixing steel sinks stainless local make complete with cast iron or wrught iron brackets 6 inches built in wall 1-1/2" c.p bubbler plug chrome plated brass chain 1-1/2" c.p brass waste with 1-1/2" P.V.C waste pipe and making requisite number of holes in wall and plinth and floor for pipe connection and making good in cement concrete 1:2:4 (b)steel sink stainless size 36"x18" local make.(standard pattern) (SINO.19(b)-P-6)	1 Nos.	5162.30	P.No	5,162


Executive Engineer
Building Division
Kamber-Shahdadt

6	Providing & Fixing 6"x2" or 6"x3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with i/c making requisite number of holes in walls, plinth and floor for pipe connections and making good cement concrete 1;2;4(SINO.20-P-6)	4 Nos	2042.43	P.No	8,170
7	P/F in position nylon connection complete with ½" dia brass stop cock of brass nuts and lining jointed to nylon connection (SINO.23 -P-6)	4 Nos.	447.15	P.No	1,789
8	Providing & Fixing 4" dia C.I Soil and Vent Pipes including cutting and fitting and extra paint to match the colour of the building (SINO.1- P-9)	10 Rft:	333.29	P-Rft:	3,333
9	Providing & Fixing M.S Clamps of the approved design to 4" dia C.I Pipes sockets i/c the cost of cutting and making good to wall or M.S Bolts and nuts 4" into wall i/c pipe distance pieces extra painting to match the colour of the building (SINO. 2-P-9)	5 Nos.	72.16	P.No	361
10	Providing & Fixing 4"x4"x4" dia C.I floor branchen of the required degree with access doors rubber washer 1/8" thick and bolts and nuts and extra painting to match the colour of the building(SINO.5-P-09)	1 Nos	270.60	P.No	271
11	Providing & Fixing 4" dia C.I off sets of various length including extra painting to match the colour of the building(SINO.8-P-10)	1 Nos	702.00	P.No	702
12	Providing & Fixing 4" dia bend of the require degree with access door rubber washer 1/8" thick with bolt & nuts & extra painting to match the colour of the Building (SINO.9-P-10)	1 Nos	599.60	P.No	600
13	P/F 3" dia C.I Waste and vent pipe including cutting fitting and extra painting to match the colour of buildings (SINO.13-P-10)	1 Nos	289.25	P.No	289
14	P/F 4" dia C.I offset of various lengths including extra painting to match the colour of building. (SINO.20-P-11)	1 Nos	584.40	P.No	584
15	P/F 3" dia C.I bend of the Each required degree with access door, rubber washer 1/8" thick bolts and nuts and extra painting to match the colour of the building. (SINO.21-P-11)	1 Nos	508.80	P.No	509


Executive Engineer
Buildings Division
Kamber-Shandakot

16	P/F 3" dia C.I terminal guard Each including extra painting to match the colour of building (SIN0.23-P-11)	1 Nos	342.70	P.No	343
17	Providing & Laying UPVC pressure pipes of class (D) (equivalent make) fixing in trench i/c cutting fitting and jointing with solvent cement i/c				
	b) 3/4" dia Pipe	10 Rft:	19.00	P.Rft	190
	c) 1" dia Pipe	10 Rft:	27.00	P.Rft	270
	d) 1-1/4" dia Pipe	10 Rft:	33.00	P.Rft	330
	h) 3" dia Pipe	10 Rft:	136.00	P.Rft	1,360
	i) 4" dia Pipe	10 Rft:	226.00	P.Rft	2,260
18	Supplying & fixing cancelled stop cock of superior quality C.P hed 1/2" dia. (SIN0.11-P-18)	1 Nos.	478.28	P.No	478
19	Supplying & fixing cancelled Tee stop cock of superior quality with C.P head 1/2" dia. (SIN0.12(a)-P-18)	1 Nos.	843.92	P.No	844
20	Supplying & Fixing long bib cock of crystal head with 1/2" dia. (SIN.13(b)- P-19)	1 Nos.	1384.24	P.No	1,384
21	Supplying & fixing swan type pillar cock of superior quality single C.P head 1/2" dia. (SIN0.16(b) P-19)	1 Nos.	795.30	P.No	795
22	Supplying & Fixing jet shower with rod of superior quality single C.P head 1/2" dia. (SIN0.15-P-19)	1 Nos.	1142.24	P.No	1,142
23	Canceled C.P fitting of superior quality for tiles bathrooms.(b)Suppling & Fixing canceled stop cock of superior quality with C.P head 1/2" dia. (SIN0.11 (b)-P-18)	1 Nos.	509.74	P.No	510
24	Supplying & Fixing washbasen mixture of superior quality with C.P head 1/2" dia (SIN0.14(b)-P-19)	1 Nos.	3179.00	P.No	3,179
25	Supplying & Fixing C.P muslim showerer with double bib cock & ring pipe etc complete.(SIN0.19(a)-P-19).	1 Nos.	3432.00	P.No	3,432
26	Providing & Fixing handle Valves (China).(SIN0.5-P-17)				
	(i) 1/2" dia.	1 Nos	200.42	P.No	200
	(ii) 3/4" dia	1 Nos	271.92	P.No	272
	(iii) 1" dia	1 Nos	365.42	P.No	365
27	Supplying & Fixing bathroom accessories set (7 pieces) including towel rod,brush hloder,soap tray,shelf of approved quality & design etc complete.(SIN0.27-P-19)	1 Nos.	10322.00	P.No	10,322

TOTAL Rs:-

71,952


Executive Engineer
Building Division
Kamber-Shahdaskot

WSS)

REPAIR/RENOVATION OF OLD DISTRICT COUNCIL STAFF OFFICE AT D.C

OFFICE KAMBER DISTRICT KAMBER SHAHDADKOT.

SCHEDULE-B

S.N o.	Item of work.	Quantity	Rate.	Unit	Amount.
1	2	3	4	5	6
	PART-"D" ELECTRIC WORK.				
	"A".SCHEDULE ITEMS				
1	Wiring for light or fan point with 3/.029 PVC insulated wire in 20mm (3/4") PVC channel patti on surface as required. (SINO: 129-P-15)	5 Nos	910.0	P.NO	4,550
2	Wiring for light or fan point with 3/.029 PVC insulated wire in 20mm (3/4") PVC wall or column required on surface as required. (SINO: 129-P-15)	20 Nos	1130.0	P.NO	22,600
3	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4") PVC channel patti on surface as required. (SINO: 130-P-15)	6 Nos	742.0	P.NO	4,452
4	Providing and laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit on surface. (SINO:3-P-1)	100 Nos	171.0	P.M	17,100
5	Providing and laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044(6mm2) copper conductor in 1" dia PVC conduit on surface. (SINO:5-P-1)	30 Nos	305	P.M	9,150
6	Providing and laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.052(10mm2) copper conductor in 1" dia PVC conduit on surface. (SINO:6-P-1)	30 Nos	428.00	P.M	12,840
7	Providing and fixing one way SP 5amp switch flush type.(SINO:219-P-33)	20 Nos	54.00	P.NO	1,080
8	Providing and fixing 2 pin 5amp plug and socket flush type.(SINO:225-P-33)	5 Nos	83.00	P.NO	415
9	Providing and fixing 3 pin 15 amp plug and socket flush type.(SINO:227-P-33)	3 Nos	162.00	P.NO	486
10	Providing and fixing brass pattern holder.(SINO:232-P-33)	6 Nos	70.00	P.NO	420
11	Providing and fixing brass back light ceiling rose with 2 terminals.(SINO:228-P-33)	10 Nos	72.00	P.NO	720
12	Providing and fixing double tube lights (good quality).(SINO:235-P-34)	1 Nos	2200	P.NO	2,200
13	Providing and fixing brass ceiling fan 56" (good quality).(SINO:235-P-34)	4 Nos	3185	P.NO	12,740
14	Providing and fixing circuit breaker 6, 10,15,20,30,40,50and 63 amp SP (TB-S5) on prepared board as required.(SINO:207-P-31)	2 Nos	916	P.NO	1,832
15	Providing and fixing Energy saver quality i/c finshing on exiting holder etc complete.	10 Nos	497.00	P.NO	4,970
16	Providing & Fixing Mild steel bar fan clamp 15.8 mm (5/8") dia suitable for roof.	4 Nos	224	P.NO	896
17	Providing and fixing A.C ceiling fan regulator on S.W board.	4 Nos	224	P.NO	896

" TOTAL:- 97,347


ELECTRIC

**Executive Engineer
Building Division**

"PART- E"

NON-SCHEDULE ITEMS(MARKET

1	L.E.D lights 6" dia	19	No	1000	P.NO	19,000
2	L.E.D lights 3" dia	5	No	650	P.NO	3,250
" TOTAL:-						22,250


Executive Engineer
Building Division
Kamber-Sheela Kot