

## SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Primary Schools Taluka Ratodero (2010-11 Programme)  
(13 Units) at: GBPS Banguldero ( Electric). ADP 329

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	23.00	@ Rs: 910	P.Point	Rs: 20,930.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	25	@ Rs: 171	P.Meter	Rs: 4275.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	10.00	@ Rs: 428	P.Meter	Rs: 4280.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	25.00	@ Rs: 54	P.Each	Rs: 1,350.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	9.00	@ Rs: 70	P.Each	Rs: 630.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	16.00	@ Rs: 72	P.Each	Rs: 1,152.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)	16.00	@ Rs: 3185	P.No	Rs: 50,960.00
11	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs: 916	P.No	Rs: 3,664.00

Part "A" TOTAL: Rs: 89,878.0

### Part "B" (Old Schedule 2004)

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	16.00	@ Rs: 91	Each	Rs: 1,456.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	16.00	@ Rs: 141.71	P.Each	Rs: 2,267.36
13	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar in painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft	Rs: 1,426.34
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	10.00	@ Rs: 497	P.Each	Rs: 4,970.00

Part "B" TOTAL: Rs: 10,119.7

Part "A" TOTAL: Rs: 39,878.0

G: TOTAL: Rs: 59,997.7

  
**XEN**

**SCHEDULE 'B'**

Name of Work:- Integrated Rehabilitation of Primary Schools Taluka Bakrani (2011-12 Programme)  
(13 Units) at: GBPS Bhanho Jatol ( Electric). ADP 330

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	16.00	@ Rs: 910	P.Point	Rs: 14,560.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	36.00	@ Rs: 171	P.Meter	Rs: 6156.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-1.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	33.00	@ Rs: 428	P.Meter	Rs: 14124.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	16.00	@ Rs: 54	P.Each	Rs: 864.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70	P.Each	Rs: 700.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	6.00	@ Rs: 72	P.Each	Rs: 432.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)	6.00	@ Rs: 3185	P.No	Rs: 19,110.00
11	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs: 916	P.No	Rs: 3,664.00

Part "A" TOTAL: Rs: 62,247.0

**Part "B" (Old Schedule 2004)**

12	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
13	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
14	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq.ft:	Rs: 1,426.00
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	10.00	@ Rs: 497	P.Each	Rs: 4,970.00

Part "B" TOTAL: Rs: 7,792.3

Part "A" TOTAL: Rs: 62,247.0

G: TOTAL: Rs: 70,039.3

**XEN**

## SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Primary Schools Taluka Bakrani (2011-12 Programme)  
(13 Units) at: GBPS Ghuhrum Magsi ( Electric). ADP 330

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	18.00	@ Rs: 910	P.Point	Rs: 16,380.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	35.00	@ Rs: 171	P.Meter	Rs: 5985.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	37.00	@ Rs: 428	P.Meter	Rs: 15836.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	18.00	@ Rs: 54	P.Each	Rs: 972.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70	P.Each	Rs: 700.00
8	Providing & Fixing Baklite Ceiling rose with two terminals. (S.I.No: 228 P 33)	8.00	@ Rs: 72	P.Each	Rs: 576.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)	8.00	@ Rs: 3185	P.No	Rs: 25,480.00
11	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs: 916	P.No	Rs: 3,664.00

Part "A" TOTAL: Rs: 72,230.0


### Part "B" (Old Schedule 2004)

12	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
13	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
14	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq.ft:	Rs: 1,426.00
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	10.00	@ Rs: 497	P.Each	Rs: 4,970.00

Part "B" TOTAL: Rs: 7,792.3

Part "A" TOTAL: Rs: 72,230.0

G: TOTAL: Rs: 80,022.3



**SCHEDULE 'B'**

Name of Work:- Rehabilitation of building for existing Primary Schools in Taluka Larkano  
(2011-12 Programme) (14 Units) at: GBPS Syed Sardar Shah ( Electric). ADP 336

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	18.00	@ Rs: 910	P.Point	Rs: 16,380.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	64	@ Rs: 171	P.Meter	Rs: 10944.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	48.00	@ Rs: 428	P.Meter	Rs: 20544.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	19.00	@ Rs: 54	P.Each	Rs: 1,026.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70	P.Each	Rs: 840.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	6.00	@ Rs: 72	P.Each	Rs: 432.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	5.00	@ Rs: 916	P.No	Rs: 4,580.00

Part "A" TOTAL: Rs: 58,208.0

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
13	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 1,426.34
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	12.00	@ Rs: 497	P.Each	Rs: 5,964.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	6.00	@ Rs: 5500	P.No	Rs: 33,000.00

Part "B" TOTAL: Rs: 41,786.6

Part "A" TOTAL: Rs: 58,208.0

G: TOTAL: Rs: 99,994.6

  
XEN

## SCHEDULE 'B'

Name of Work:- Rehabilitation of building for existing Primary Schools in Taluka Bakrani & Dokri  
(2016-17 Programme) (24 Units) at: GBPS Jakhra ( Electric). ADP 338

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	21.00	@ Rs: 910	P.Point	Rs: 19,110.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	50	@ Rs: 171	P.Meter	Rs: 8550.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	43.00	@ Rs: 428	P.Meter	Rs: 18404.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	21.00	@ Rs: 54	P.Each	Rs: 1,134.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	15.00	@ Rs: 70	P.Each	Rs: 1,050.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	6.00	@ Rs: 72	P.Each	Rs: 432.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	5.00	@ Rs: 916	P.No	Rs: 4,580.00

Part "A" TOTAL: Rs: 56,722.0

### Part "B" (Old Schedule 2004)

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
13	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 1,426.34
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	15.00	@ Rs: 497	P.Each	Rs: 7,455.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	6.00	@ Rs: 5500	P.No	Rs: 33,000.00

Part "B" TOTAL: Rs: 43,277.6

Part "A" TOTAL: Rs: 56,722.0

G: TOTAL: Rs: 99,999.6

  
**XEN**

# SCHEDULE-B

Name of work:- Rehabilitation of Building for Existing Primary Schools in  
Taluka Dokri & Bakrani (2011-12 Prog) ( 24-Units)  
At:GBMS Saindud Junejo Taluka Dokri ADP :338

S.No	Description	Quantity	Rate	Unit	Rs.	Amount
1	Dismantlin C.C plain 1:2:4. (S.I.No 19 ( c ) P/11).	51.20	@Rs: 3327.50	%Cft	Rs: 1704.00	
	(Rs: Three thousand Three Hundred Twenty Seven & P.S Fifty only)					
2	Dismantling Pacca Brick Work in Cement Mortar	215.63	@Rs: 1285.63	%Cft	Rs: 2772.00	
	(Rs: Twolve thousand Eighty Five & P.S Sixty Three only)					
3	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	623.00	@Rs: 8694.95	% Cft	Rs: 54169.54	
	( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)					
4	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 ( C ) 23.	435.00	@ Rs: 11948.36	% S.ft	Rs: 51975.37	
	( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six only)					
5	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)	28.25	@Rs: 337.0	P.Cft	Rs: 9520.00	
	( Three Hundred Thirty Seven only)					
6	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	1.261	@ Rs: 5001.70	P.CWt	Rs: 6308.00	
	(Five Thousand One &P.S Seventy ).					
7	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 ( C ) P/24)	354.38	@Rs: 12674.36	% Cft	Rs: 44914.00	
	(Twlove thousand Six Hundred Seventy Four & Thirty Six only)					
8	S/F sand floor and plugging into walls (S.I.No 29 P/31).	1640.00	@Rs: 1141.25	%Cft	Rs: 18260.00	
	(Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)					
9	Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 ( C ) P/24)	450.00	@Rs: 12346.65	% Cft	Rs: 55560.00	
	(Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five only)					
10	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	150.00	@ Rs: 902.93	P.Sft	Rs: 135439.50	
	( Nine Hundrad Two P.S Ninty Three only)					
11	Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	1668.00	@Rs: 2206.60	% Sft	Rs: 36817.00	
	( Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)					
12	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)	1668.00	@ Rs: 2197.52	%S.ft	Rs: 36665.00	
	( Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)					
13	Removing Cement or Lime Plaster	3573.0	@Rs: 121.0	%Cft	Rs: 4323.33	
14	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" square bars 4" centre to centers.	17.50	@ Rs: 726.72	%Sft	Rs: 12,718.00	
	(Rs: Seven Hundred Twenty Six & P.S Seventy Two only)					
15	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3 " thick. (S.I.No c P/46).	2800.00	@ Rs: 4411.82	% S.ft	Rs: 123530.96	
	(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)					
16	S/Fin position iron steel grill of 3/4" X 1/4"flate iron of approved design i/c painting three coats etc complete with weight not to beless than 3.7 Lbs sq: ft: of finished grill.	280.00	@Rs: 194.16	P.Sft	Rs: 54364.80	
	(Rs: One hundred Ninty Four & P.S Sixteen only)					
17	White wash three coats (S.I.No 26 ( c ) 59).	928.00	@Rs: 829.95	% Sft	Rs: 3948.00	
	(Rs: Eight hundred twenty nine rupes only)					

  
**XEN**

S.No	Discription	Quantity	Rate	Unit	Rs:	Amount
------	-------------	----------	------	------	-----	--------

- 18 Primary coat of chalk under distempring ( S.I No: 23 P 59)  
2305.00 @ Rs; 442.75 % Sft Rs: 23451.00  
(Four Hundred Fourty Two & P.S Seventy Five only)
- 19 Distempring three coats, (S.I.No 24 (b) P/59)  
2305.00 @ Rs: 1079.65 % Sft Rs: 24886.00  
(Rs: One Thousand Seventy Nine & P.S Sixty Five only)
- 20 Preparing surface painting guards bars gates iron grating railling i/c standards brass etc similar open work.  
(S.I.No 4 d P/76 ii)  
102.00 @Rs: 1270.83 %Cft Rs: 1296.00  
(Rs: One thousands two hundred seventy reups only)
- 21 Painting doors & Window any type.  
262.00 @ Rs: 2116.41 %Cft Rs: 5545.00  
(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One only)
- 22 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with  
brick /sen paper filling the voilds with chalk plaster of paris and then painting with weather coat of approved  
make old surface.  
2300.00 @Rs: 1948.10 %Sft Rs: 44806.30  
( One Thousand Nine Hundred Fourty Eight & P.S Ten only)

**Total Rs: 752,974**

  
**XEN**

## SCHEDULE 'B'

Name of Work:- Rehabilitation of bulding for existing Primary Schools in Taluka Bakrani & Dokri  
(2016-17 Programme) (24 Units) at: GBPS Fazal Kalhoro ( Electric). ADP 338

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	18.00	@ Rs: 910	P.Point	Rs: 16,380.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	39	@ Rs: 171	P.Meter	Rs: 6669.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	48.00	@ Rs: 428	P.Meter	Rs: 20544.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	18.00	@ Rs: 54	P.Each	Rs: 972.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70	P.Each	Rs: 840.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	7.00	@ Rs: 72	P.Each	Rs: 504.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs: 916	P.No	Rs: 3,664.00

**Part "A" TOTAL: Rs: 52,210.0**

### **Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
13	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 1,426.34
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	12.00	@ Rs: 497	P.Each	Rs: 5,964.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	6.00	@ Rs: 5500	P.No	Rs: 33,000.00

**Part "B" TOTAL: Rs: 41,786.6**

**Part "A" TOTAL: Rs: 52,210.0**

**G: TOTAL: Rs: 93,996.6**

  
**XEN**



## SCHEDULE 'B'

Name of Work:- Rehabilitation of bulding for existing Primary Schools in Taluka Bakrani & Dokri  
(2016-17 Programme) (24 Units) at: GBPS Ali Akbar Shah ( Electric). ADP 338

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	18.00	@ Rs: 910	P.Point	Rs: 16,380.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	39	@ Rs: 171	P.Meter	Rs: 6669.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	48.00	@ Rs: 428	P.Meter	Rs: 20544.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	18.00	@ Rs: 54	P.Each	Rs: 972.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70	P.Each	Rs: 840.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	7.00	@ Rs: 72	P.Each	Rs: 504.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs: 916	P.No	Rs: 3,664.00

**Part "A" TOTAL: Rs: 52,210.0**

### **Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546 00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
13	Providing & Fixing main pannel board double shutter to accomodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 1,426.34
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	12.00	@ Rs: 497	P.Each	Rs: 5,964.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan.Pak Fan)	6.00	@ Rs: 5500	P.No	Rs: 33,000.00

**Part "B" TOTAL: Rs: 41,786.6**

**Part "A" TOTAL: Rs: 52,210.0**

**G: TOTAL: Rs: 93,996.6**

**XEN**

**SCHEDULE 'B'**

9

Name of Work:- Rehabilitation of building for existing Primary Schools in Taluka Bakrani & Dokri  
(2016-17 Programme) (24 Units) at: GBPS Ghulam Ali Umrani ( Electric). ADP 338

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	18.00	@ Rs: 910	P.Point	Rs: 16,380.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	39	@ Rs: 171	P.Meter	Rs: 6669.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	48.00	@ Rs: 428	P.Meter	Rs: 20544.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	18.00	@ Rs: 54	P.Each	Rs: 972.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70	P.Each	Rs: 840.00
8	Providing & Fixing Baklite Ceiling rose with two terminals ..(S.I.No: 228 P 33)	7.00	@ Rs: 72	P.Each	Rs: 504.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs: 916	P.No	Rs: 3,664.00

Part "A" TOTAL: Rs: 52,210.0

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
13	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 1,426.34
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	12.00	@ Rs: 497	P.Each	Rs: 5,964.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/029 PVC (R.A) (Royal Fan, younis Fan.Pak Fan)	6.00	@ Rs: 5500	P.No	Rs: 33,000.00

Part "B" TOTAL: Rs: 41,786.6

Part "A" TOTAL: Rs: 52,210.0

G: TOTAL: Rs: 93,996.6



**SCHEDULE 'B'**

Name of Work:- Rehabilitation of bulding for existing Primary Schools in Taluka Bakrani & Dokri  
(2016-17 Programme) (24 Units) at: GBPS Bakrani ( Electric). ADP 338

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	18.00	@ Rs: 910	P.Point	Rs: 16,380.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	48	@ Rs: 171	P.Meter	Rs: 8208.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	48.00	@ Rs: 428	P.Meter	Rs: 20544.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	18.00	@ Rs: 54	P.Each	Rs: 972.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70	P.Each	Rs: 840.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	7.00	@ Rs: 72	P.Each	Rs: 504.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs: 916	P.No	Rs: 3,664.00

Part "A" TOTAL: Rs: 53,749.0

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
13	Providing & Fixing main pannel board double shutter to accomodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft	Rs: 1,426.34
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	12.00	@ Rs: 497	P.Each	Rs: 5,964.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod. cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	5.00	@ Rs: 5500	P.No	Rs: 27,500.00

Part "B" TOTAL: Rs: 36,286.6

Part "A" TOTAL: Rs: 53,749.0

G: TOTAL: Rs: 90,035.6

  
**XEN**

## SCHEDULE 'B'

Name of Work:- Construction of Additional Class rooms in existing Primary Schools Taluka Larkano  
(2011-12 Programme) (16 C/R) at: GBPS Doulat Chandio (1 C/R) ( Electric). ADP 340

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	14.00	@ Rs:	910	P.Point	Rs: 12,740.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs:	742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	37.00	@ Rs:	171	P.Meter	Rs: 6327.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	33.00	@ Rs:	428	P.Meter	Rs: 14124.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	13.00	@ Rs:	54	P.Each	Rs: 702.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs:	83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs:	70	P.Each	Rs: 700.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	4.00	@ Rs:	72	P.Each	Rs: 288.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs:	162	P.Each	Rs: 162.0
11	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs:	916	P.No	Rs: 3,664.00

Part "A" TOTAL: Rs: 41,182.0

### Part "B" (Old Schedule 2004)

12	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	4.00	@ Rs:	91	Each	Rs: 364.00
13	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	4.00	@ Rs:	141.71	P.Each	Rs: 566.84
14	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs:	1426.34	P.Sq.ft:	Rs: 1,426.00
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	10.00	@ Rs:	497	P.Each	Rs: 4,970.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade. suitable (Double beering) internal electric connection with 3/029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	3.00	@ Rs:	5500	P.No	Rs: 16,500.00

Part "B" TOTAL: Rs: 23,826.8

Part "A" TOTAL: Rs: 41,182.0

G: TOTAL: Rs: 65,008.8

  
**XEN**

**SCHEDULE 'B'**

12

Name of Work:- Construction of Additional Class rooms in existing Primary Schools Taluka Larkano  
(2011-12 Programme) (16 C/R) at: GGPS Waleed (2 C/R) ( Electric). ADP 340

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	21.00	@ Rs: 910	P.Point	Rs: 19,110.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	61	@ Rs: 171	P.Meter	Rs: 10431.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	48.00	@ Rs: 428	P.Meter	Rs: 20544.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	21.00	@ Rs: 54	P.Each	Rs: 1,134.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	15.00	@ Rs: 70	P.Each	Rs: 1,050.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	6.00	@ Rs: 72	P.Each	Rs: 432.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	5.00	@ Rs: 916	P.No	Rs: 4,580.00

Part "A" TOTAL: Rs: 60,743.0

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
13	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar in painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 1,426.34
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	15.00	@ Rs: 497	P.Each	Rs: 7,455.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	6.00	@ Rs: 5500	P.No	Rs: 33,000.00

Part "B" TOTAL: Rs: 43,277.6

Part "A" TOTAL: Rs: 60,743.0

G: TOTAL: Rs: 104,020.6



**XEN**

**SCHEDULE 'B'**

13

Name of Work:- Construction of Additional Class rooms in existing Primary Schools Taluka Bakrani / Dokri  
(2011-12 Programme) (16 C/R) at: GBPS Raza Muhammad Brohi (1 C/R) ( Electric). ADP 341

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	14.00	@ Rs:	910	P.Point	Rs: 12,740.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs:	742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	37.00	@ Rs:	171	P.Meter	Rs: 6327.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	33.00	@ Rs:	428	P.Meter	Rs: 14124.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	13.00	@ Rs:	54	P.Each	Rs: 702.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs:	83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs:	70	P.Each	Rs: 700.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	4.00	@ Rs:	72	P.Each	Rs: 288.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs:	162	P.Each	Rs: 162.0
11	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	4.00	@ Rs:	916	P.No	Rs: 3,664.00

**Part "A" TOTAL: Rs: 41,182.0**

**Part "B" (Old Schedule 2004)**

12	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	4.00	@ Rs:	91	Each	Rs: 364.00
13	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	4.00	@ Rs:	141.71	P.Each	Rs: 566.84
14	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs:	1426.34	P.Sq:ft:	Rs: 1,426.00
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	10.00	@ Rs:	497	P.Each	Rs: 4,970.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan.Pak Fan)	3.00	@ Rs:	5500	P.No	Rs: 16,500.00

**Part "B" TOTAL: Rs: 23,826.8**

**Part "A" TOTAL: Rs: 41,182.0**

**G: TOTAL: Rs: 65,008.8**

**SCHEDULE 'B'**

Name of Work:- Reconstruction of dangerous Primary / Middle Schools in Taluka Larkano  
(2011-12 Programme) (6 Units) at: GGMS Channa Muhalla ( Electric). ADP 342

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	32.00	@ Rs:	910	P.Point	Rs: 29,120.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	8.00	@ Rs:	742	P.Point	Rs: 5,936.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	128	@ Rs:	171	P.Meter	Rs: 21888.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	41.00	@ Rs:	305	P.Meter	Rs: 12,505.00
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	94.00	@ Rs:	428	P.Meter	Rs: 40232.0
6	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	31.00	@ Rs:	54	P.Each	Rs: 1,674.00
7	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	8.00	@ Rs:	83	P.Each	Rs: 664.00
8	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	23.00	@ Rs:	70	P.Each	Rs: 1,610.00
9	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs:	72	P.Each	Rs: 576.00
10	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs:	162	P.Each	Rs: 162.0
11	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	7.00	@ Rs:	916	P.No	Rs: 6,412.00

Part "A" TOTAL: Rs: 120,779.0

**Part "B" (Old Schedule 2004)**

12	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	8.00	@ Rs:	91	Each	Rs: 728.00
13	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	8.00	@ Rs:	141.71	P.Each	Rs: 1,133.68
14	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs:	1426.34	P.Sq:ft	Rs: 1,426.34
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	24.00	@ Rs:	497	P.Each	Rs: 11,928.00
16	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	8.00	@ Rs:	5500	P.No	Rs: 44,000.00

Part "B" TOTAL: Rs: 59,216.0

Part "A" TOTAL: Rs: 120,779.0

G: TOTAL: Rs: 179,995.0

  
**XEN**

**SCHEDULE 'B'**

Name of Work:- Reconstruction of dangerous Primary Schools Buildings in Taluka Ratodero  
(2011-12 Programme) (9 Units) at: GBPS Wandh Jogi Naudero ( Electric). ADP 343

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	40.00	@ Rs: 910	P.Point	Rs: 36,400.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	6.00	@ Rs: 742	P.Point	Rs: 4,452.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	146	@ Rs: 171	P.Meter	Rs: 24966.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-/.044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	20.00	@ Rs: 305	P.Meter	Rs: 6,100.00
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	50.00	@ Rs: 428	P.Meter	Rs: 21400.0
6	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	40.00	@ Rs: 54	P.Each	Rs: 2,160.00
7	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	6.00	@ Rs: 83	P.Each	Rs: 498.00
8	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	26.00	@ Rs: 70	P.Each	Rs: 1,820.00
9	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	14.00	@ Rs: 72	P.Each	Rs: 1,008.00
10	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
11	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	7.00	@ Rs: 916	P.No	Rs: 6,412.00

Part "A" TOTAL: Rs: 105,378.0

**Part "B" (Old Schedule 2004)**

12	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	14.00	@ Rs: 91	Each	Rs: 1,274.00
13	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	14.00	@ Rs: 141.71	P.Each	Rs: 1,983.94
14	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft	Rs: 1,426.34
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	26.00	@ Rs: 497	P.Each	Rs: 12,922.00
16	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade. suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	14.00	@ Rs: 5500	P.No	Rs: 77,000.00

Part "B" TOTAL: Rs: 94,606.3

Part "A" TOTAL: Rs: 105,378.0

G: TOTAL: Rs: 199,984.3



# SCHEDULE "B"

Name of Work:-

Construction of Building For Shelterless Primary Schools in  
Taluka Dokri & Bakrani (06-Units) (2013-14 Prog) At GBPS  
Raza Muhammad Abro Taluka Dokri

S.N	Description	Qnty:	Rate		Amount
-----	-------------	-------	------	--	--------

- 1 Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).  
= 5,490  
@ Rs: 3176.25 %0 CFT Rs: 17,438  
(Thirty one Hundred seventy six rup: & twenty five paisa only)
- 2 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:4:8 (S.I.No 4 (C) P/16).  
= 428  
@ Rs: 9416.18 % CFT Rs: 40,301  
(Nine thousands four hundred sixteen Eighteen P.S only)
- 3 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).  
= 435  
(Eighty six hund: ninty four rup: & ninty five paisa only)  
@ Rs: 8694.95 % CFT Rs: 37,823
- 4 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 23.  
= 2,260  
@ Rs: 11948.36 % CFT Rs: 270,033  
(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)
- 5 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)  
= 2,560  
@ Rs: 337.00 P.CFT Rs: 862,720  
(Three hundred Thirty seven rup: only)
- 6 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)  
= 125  
@ Rs: 5001.70 P.CWT Rs: 625,213  
( Five thousand one rup: & seventy paisa only)
- 7 S/F sand floor and plugging into walls (S.I.No 29 P/31).  
= 3,387  
@ Rs: 1141.25 %SFT Rs: 38,654  
(Eleven hundred forty one rupees & twenty five paisa only)
- 8 Extra Lead 3 Miles  
= 3,387  
@ Rs: 579.41 %SFT Rs: 19,625  
(Five hundred seventy nine fourty one P.S only)
- 9 Providing and laying single per layer of polythen sheet 0.13 mm thick for water proffing as per specification instruments of Engineer Incharge.  
= 321  
@ Rs: 10.70 P.sft Rs: 3,435  
(Ten rupees & seventy paisa only)

XER

S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

10 Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P/24)

= 1,754

@ Rs: 12674.36 %SFT Rs: 222,308

(Twelve thousand six hundred seventy four rup: & thity six paisa only)

11 Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P

= 750

@ Rs: 12346.65 %SFT Rs: 92,600

(Twelve thousand three hund: forty six rup: & sixty five paisa only)

12 Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and s bars 4" centre to cement .

= 48

@ Rs: 726.72 P.Sft Rs: 34,883

(Seven hundred twenty six rupees & seventy two paisa only)

13 P/F G.I frame chokats of size 7" x2" or 4" x 3" for Doors using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand reparing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)

= 77

@ Rs: 228.90 P.Sft Rs: 17,625

(Two hundred twenty eight rupees & ninty paisa only)

14 P/F G.I frame chokats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand reparing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)

= 190

@ Rs: 240.50 P.Sft Rs: 45,695

(Two hundred forty rupees & fifty paisa only)

15 Supplying M.S Sqaure bar 5/8 dia ( Sch: of material)

= 1,429

@ Rs: 3350.00 P.Sft Rs: 4,787

(Three Thousand Five hundred Fifty rupees & only)

16 Cutting & Fixing iron bar for barrid windows

= 52.00

@ Rs: 28.23 P.Sft Rs: 1,468

( Twenty Eihgt rupees & Twenty Three Paisa only)

17 S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with not to beless than 3.7 Lbs sq: ft: of finished grill.

= 203

@ Rs: 194.16 %Cft Rs: 39,414

( One hundre ninty four rupees & sixteen paisa only)

18 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)

= 180

@ Rs: 902.93 P.CFT Rs: 162,527

(Nine hund: two rup: & ninty three paisa only)

19 Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)

= 3,477

@ Rs: 2206.60 %Cft Rs: 76,723

(Twenty tow hund: six rup: & sixty paisa only)

  
XEN

S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

20 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)

= 3,477

@ Rs: 2197.52 %SFT Rs: 76,408

(Twenty one hund: ninty seven rup: & fifty two paisa only)

21 Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.19 (a) P/53)

= 2,470

@ Rs: 1287.44 %SFT Rs: 31,800

(Twelve hundred eighty seven rupees & forty for paisa only)

22 Notice Board mad with cement. (S.I.No 1 P/100).

= 64

@ Rs: 58.11 %SFT Rs: 3,719

( Fifty Eight Eleven P.S only)

23 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick.  
(S.I No:16 ( C ) P/46)

= 995

@ Rs: 4411.82 %SFT Rs: 43,898

( Forry four hundred eleven rup: & eighty two paisa only)

(B) Ratio 2" thick,

= 459

@ Rs: 3275.50 %SFT Rs: 15,035

(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

24 Two coat of bitumen laid not using 34 lbs for over foof and blinded with stand at Cft per ( S.I No: 13 P/40)

= 1,465

@ Rs: 1887.40 %SFT Rs: 27,650

( Eighteen hundred eighty seven rupees & forty paisa only)

25 Providing and Fixing ornamental cement jalli 2" thick (1:2:4) with out steel (s.i.no:11p/17)

= 100

@ Rs: 226.00 %SFT Rs: 226

( Two hundred twenty six only)

26 Primary coat of chalk under distempring ( S.I No: 23 P 59)

= 6,110

@ Rs: 442.75 %CFT Rs: 27,052

(Four hundred forty two rupees & seventy five paisa only)

27 Distempering three coats ( S.I No: 24( B ) P 59)

= 6,555

@ Rs: 1079.65 %CFT Rs: 70,771

28 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface w  
brick /sen paper filling the voilds with chalk plaster of paris and then painting with weather coat of approv  
make New surface. (S.I.No 39 (a) P/62).

= 1,166

@ Rs: 1948.10 %CFT Rs: 22,715

Twenty on hundred sixteen rupees & forty one paisa only)

29 Painting doors & window any type, (S.I.No 05 P/ 76)

= 470

@ Rs: 2116.41 %Cft Rs: 9,947

( Twenty one hundred sixteen rup & forty one paisa only)

  
XEN

S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

30 Painting guards bars , gates iron bars gratings railings i/c standard bares etc smiller open works

= 96

@ Rs: 1270.83

%Cft

Rs;

1,220

(Twelve Hundred seventy rupees & eithy three paisa only)

Total Rs: 2,943,713

  
XEN

## Schedule-B

17

Name of  
Work:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING PRIMARY  
SCHOOLS IN TALUKA RATODERO (09 UNITS) (2013-14 PROGRAMME) @  
GBPS CHAWAN (01 C/R) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	848.00	@ Rs: 3,176.25 % OCft (Thirty one Hundred seventy six rup: & twenty five paisa only)	Rs:	2,693
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	308.00	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)	Rs:	26,780
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	669.00	@ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)	Rs:	79,935
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	513.24	@ Rs: 337.00 P.Cft (Thiree hundred Thirtly seven rup: only)	Rs:	172,962
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)	22.913	@ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)	Rs:	114,604
6	Filling watering and ramming earth in floor with surplus earth from foundation laed upto one chain and lift upto 5 ft. (S.I.No: 2 P/5).	565.330	@ Rs: 1,512.50 0.Cft (Fifteen hundred twelve rup: & fifty paisa only)	Rs:	855
7	Supply and fixing sand under floor including plugging in to walls	1100.00	@ Rs: 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)	Rs:	12,554
9	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.	1269.19	@ Rs. 12,674.36 % Cft (Twelve thousand six hundred seventy four rup: & thity six paisa only)	Rs.	160,862
10	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	1965.00	@ Rs. 2,206.60 % Cft	Rs.	43,360

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(Twenty tow hund: six rup: & sixty paisa only)

- 11 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

1965.00 @ Rs: 2,197.52 % Sft Rs: 43,181  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

- 12 Making Notice board made with cement.

32.00 @ Rs: 58.11 P. Sft Rs: 1,860  
(Nnety Three rupees & Thirty Seven paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges  
13 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs.  
The cost also i/c all carriage, tools and pla

28.00 @ Rs: 228.90 P. Rft Rs: 6,409  
(Two hundred twenty eight rupees & ninty paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded  
14 hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the  
jambs. The cost also i/c all carriage, tools

96.00 @ Rs: 240.50 P. Rft Rs: 23,088  
(Two hundred forty rupees & fifty paisa only)

- 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts  
15 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25  
P/60)

76.00 @ Rs: 902.93 P. Sft Rs: 68,623  
(Nine hund: two rup: & ninty three paisa only)

- 16 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

839.38 @ Rs: 1,287.44 % Sft Rs: 10,807  
(Twelve hundred eighty seven rupees & forty for paisa only)

- Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved  
17 design including painting 3 coats etc. complee ( weight not to be less than 3.7  
Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

98.00 @ Rs: 180.50 P. Sft Rs: 17,689  
( One hundre ninty four rupees & sixteen paisa only)

- 18 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

0.950 @ Rs: 3,550.00 P. Sft Rs: 3,373  
(Three Thousand Five hundred Fifty rupees & only)

- 19 Cutting & Fixing iron bars for barred windows.

20.00 @ Rs: 28.23 P. Sft Rs: 565  
( Twenty Eihgt rupees & Twenty Three Paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification

125.00 @ Rs. 10.70 P.Sft Rs. 1,338  
(Ten rupees & seventy paia only)

21 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

440.00 @ Rs: 4,411.82 % Sft Rs: 19,412  
( Forry four hundred eleven rup: & eighty two paia only)

**(B) 1-1/2" Thick.**

720.00 @ Rs: 3,275.50 Rs: 23,584  
(Thirty Two hundred Seventy Five rup: & Fifty paia only)

22 Primary coat of chalk distemper( S.I No. 23 P/53)

1965.17 @ Rs: 442.75 % Sft Rs: 8,701  
(Four hundred forty two rupees & seventy five paia only)

23 Distemping Three Coats (S.I No. 24 ©P/53)

1965.17 @ Rs: 1,079.65 % Sft Rs: 21,217  
(One thousand Seventy nine rup: & sixty five paia only)

24 White wash Three Coats (S.I No. 26 © P/53)

440.00 @ Rs: 829.95 % Sft Rs: 3,652  
(Eight hundred twenty nine rup: & ninty five paia only)

25 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

839.38 @ Rs. 1,948.10 % Sft Rs. 16,352  
Twenty on hundred sixteen rupees & forty one paia only)

**Total Rs. 879,980**

  
**XEN**

**SCHEDULE 'B'**

Name of Work:- Construction of Additional Class rooms in existing Primary Schools Taluka Ratodero  
(9 C/R) (2013-14 Programme) at: GBPS Chawan (1 C/R) ( Electric). ADP 347

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	12.00	@ Rs: 910	P.Point	Rs: 10,920.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	36.00	@ Rs: 171	P.Meter	Rs: 6156.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	32.00	@ Rs: 428	P.Meter	Rs: 13696.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	12.00	@ Rs: 54	P.Each	Rs: 648.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	9.00	@ Rs: 70	P.Each	Rs: 630.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	4.00	@ Rs: 72	P.Each	Rs: 288.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	3.00	@ Rs: 916	P.No	Rs: 2,748.00

**Part "A" TOTAL: Rs: 36,898.0**

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	3.00	@ Rs: 91	Each	Rs: 273.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	3.00	@ Rs: 141.71	P.Each	Rs: 425.13
13	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar in painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft	Rs: 1,426.00
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	9.00	@ Rs: 497	P.Each	Rs: 4,473.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, canopy blade, suitable (Double bearing) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	3.00	@ Rs: 5500	P.No	Rs: 16,500.00

**Part "B" TOTAL: Rs: 23,097.1**

**Part "A" TOTAL: Rs: 36,898.0**

**G: TOTAL: Rs: 59,995.1**

**XEN**



## Schedule-B

Name of  
Work:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING PRIMARY  
SCHOOLS IN TALUKA RATODERO (09 UNITS) (2013-14 PROGRAMME) @  
GBPS NAO GOATH (01C/R) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		848.00	@ Rs: 3,176.25 % 0Cft (Thirty one Hundred seventy six rup: & twenty five paisa only)		Rs: 2,693
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 @ P/14)				
		308.00	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)		Rs: 26,780
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
		669.00	@ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)		Rs: 79,935
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
		513.24	@ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)		Rs: 172,962
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)				
		22.913	@ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)		Rs: 114,604
6	Filling watering and ramming earth in floor with surplus earth from foundation laed upto one chain and lift upto 5 ft. (S.I.No: 2 P/5).				
		565.330	@ Rs: 1,512.50 0.Cft (Fifteen hundred twelve rup: & fifty paisa only)		Rs: 855
7	Supply and fixing sand under floor including plugging in to walls				
		1100.00	@ Rs: 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)		Rs: 12,554
9	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.				
		1269.19	@ Rs: 12,674.36 % Cft (Twelve thousand six hundred seventy four rup: & thity six paisa only)		Rs. 160,862
10	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
		1965.00	@ Rs. 2,206.60 % Cft		Rs. 43,360

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(Twenty tow hund: six rup: & sixty paisa only)

- 11 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

1965.00 @ Rs: 2,197.52 % Sft Rs: 43,181  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

- 12 Making Notice board made with cement.

32.00 @ Rs: 58.11 P. Sft Rs: 1,860  
(Nnety Three rupees & Thirty Seven paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

28.00 @ Rs: 228.90 P. Rft Rs: 6,409  
(Two hundred twenty eight rupees & ninty paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools

96.00 @ Rs: 240.50 P. Rft Rs: 23,088  
(Two hundred forty rupees & fifty paisa only)

- 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

76.00 @ Rs: 902.93 P. Sft Rs: 68,623  
(Nine hund: two rup: & ninty three paisa only)

- 16 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

839.38 @ Rs: 1,287.44 % Sft Rs: 10,807  
(Twelve hundred eighty seven rupees & forty for paisa only)

- Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

98.00 @ Rs: 180.50 P. Sft Rs: 17,689  
( One hundre ninty four rupees & sixteen paisa only)

- 18 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

0.950 @ Rs: 3,550.00 P. Sft Rs: 3,373  
(Three Thousand Five hundred Fifty rupees & only)

- 19 Cutting & Fixing iron bars for barred windows.

20.00 @ Rs: 28.23 P. Sft Rs: 565  
( Twenty Eihgt rupees & Twenty Three Paisa only)

  
XEN

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification

125.00 @ Rs. 10.70 P.Sft Rs. 1,338  
(Ten rupees & seventy paisa only)

21 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

440.00 @ Rs. 4,411.82 % Sft Rs. 19,412  
( Forry four hundred eleven rup: & eighty two paisa only)

(B) 1-1/2" Thick.

720.00 @ Rs. 3,275.50 Rs. 23,584  
(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

22 Primary coat of chalk distemper( S.I No. 23 P/53)

1965.17 @ Rs. 442.75 % Sft Rs. 8,701  
(Four hundred forty two rupees & seventy five paisa only)

23 Distemping Three Coats (S.I No. 24 ©P/53)

1965.17 @ Rs. 1,079.65 % Sft Rs. 21,217  
(One thousand Seventy nine rup: & sixty five paisa only)

24 White wash Three Coats (S.I No. 26 © P/53)

440.00 @ Rs. 829.95 % Sft Rs. 3,652  
(Eight hundred twenty nine rup: & ninty five paisa only)

25 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

839.38 @ Rs. 1,948.10 % Sft Rs. 16,352  
Twenty on hundred sixteen rupees & forty one paisa only)

**Total Rs.**

**879,980**

  
**XEN**

**SCHEDULE 'B'**

20

Name of Work:- Construction of Additional Class rooms in existing Primary Schools Taluka Ratodero  
(9 C/R) (2013-14 Programme) at: GBPS Nau Goth (1 C/R) ( Electric). ADP 347

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	12.00	@ Rs: 910	P.Point	Rs: 10,920.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	36.00	@ Rs: 171	P.Meter	Rs: 6156.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	32.00	@ Rs: 428	P.Meter	Rs: 13696.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	12.00	@ Rs: 54	P.Each	Rs: 648.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	9.00	@ Rs: 70	P.Each	Rs: 630.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	4.00	@ Rs: 72	P.Each	Rs: 288.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	3.00	@ Rs: 916	P.No	Rs: 2,748.00

**Part "A" TOTAL: Rs: 36,898.0**

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	3.00	@ Rs: 91	Each	Rs: 273.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	3.00	@ Rs: 141.71	P.Each	Rs: 425.13
13	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 1,426.00
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	9.00	@ Rs: 497	P.Each	Rs: 4,473.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	3.00	@ Rs: 5500	P.No	Rs: 16,500.00

**Part "B" TOTAL: Rs: 23,097.1**

**Part "A" TOTAL: Rs: 36,898.0**

**G: TOTAL: Rs: 59,995.1**



## Schedule-B

Name of  
Work:-

21

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING PRIMARY  
SCHOOLS IN TALUKA RATODERO (09 UNITS) (2013-14 PROGRAMME) @  
GBPS ARABI AT ALI HASSAN KHUHHO (02 C/R) TALUKA RATODERO  
DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	1434.00	@ Rs: 3,176.25 % 0Cft (Thirty one Hundred seventy six rup: & twenty five paisa only)		Rs: 4,555
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	972.00	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)		Rs: 84,515
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	131.01	@ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)		Rs: 15,654
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	1008.00	@ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)		Rs: 339,696
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)	45.000	@ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)		Rs: 225,077
6	Supply and fixing sand under floor including plugging in to walls	3230.00	@ Rs: 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)		Rs: 36,862
7	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.	2205.00	@ Rs: 12,674.36 % Cft (Twelve thousand six hundred seventy four rup: & thity six paisa only)		Rs. 279,470
8	P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification	217.00	@ Rs. 10.70 P.Sft (Ten rupees & seventy paisa only)		Rs. 2,322
9	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	3309.00	@ Rs. 2,206.60 % Cft (Twenty tow hund: six rup: & sixty paisa only)		Rs. 73,016

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

10 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

3309.00 @ Rs: 2,197.52 % Sft Rs: 72,716  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

11 Making Notice board made with cement.

64.00 @ Rs: 58.11 P. Sft Rs: 3,719  
(Nnety Three rupees & Thirty Seven paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges  
12 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs.  
The cost also i/c all carriage, tools and pla

61.00 @ Rs: 228.90 P. Rft Rs: 13,963  
(Two hundred twenty eight rupees & ninty paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded  
13 hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the  
jambs. The cost also i/c all carriage, tools

270.00 @ Rs: 240.50 P. Rft Rs: 64,935  
(Two hundred forty rupees & fifty paisa only)

1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts  
14 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25  
P/60)

200.00 @ Rs: 902.93 P. Sft Rs: 180,586  
(Nine hund: two rup: & ninty three paisa only)

Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved  
15 design including painting 3 coats etc. complee ( weight not to be less than 3.7  
Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

131.00 @ Rs: 180.50 P. Sft Rs: 23,646  
( One hundre ninty four rupees & sixteen paisa only)

16 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing  
into panels: (S.I. No. 16 P/41)

927.00 @ Rs: 4,411.82 % Sft Rs: 40,898  
( Forry four hundred eleven rup: & eighty two paisa only)

**(B) 2" Thick.**

1362.00 @ Rs: 3,275.50 Rs: 44,612  
(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

17 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

1153.00 @ Rs: 1,287.44 % Sft Rs: 14,844  
(Twelve hundred eighty seven rupees & forty for paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
18	Primary coat of chalk distemper( S.I No. 23 P/53)				
		3309.00	@ Rs: 442.75 % Sft		Rs: 14,651
	(Four hundred forty two rupees & seventy five paisa only)				
19	Distemping Three Coats (S.I No. 24 ©P/53)				
		3309.00	@ Rs: 1,079.65 % Sft		Rs: 35,726
	(One thousand Seventy nine rup: & sixty five paisa only)				
20	White wash Three Coats (S.I No. 26 © P/53)				
		1242.00	@ Rs: 829.95 % Sft		Rs: 10,308
	(Eight hundred twenty nine rup: & ninty five paisa only)				
21	Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).				
		1673.00	@ Rs. 1,948.10 % Sft		Rs. 32,592
	Twenty on hundred sixteen rupees & forty one paisa only)				
22	Prepairing surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c ) P. 76 (ii) ).				
		400.00	@ Rs: 2,116.41 % Sft		Rs: 8,466
	( Twenty one hundred sixteen rup & forty one paisa only)				
23	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)				
		1362.00	@ Rs. 1,887.40 % Sft		Rs. 25,706
	( Eighteen hundred eighty seven rupees & forty paisa only)				
24	M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).				
		2.468	@ Rs: 3,550.00 P. Sft		Rs: 8,761
	(Three Thousand Five hundred Fifty rupees & only)				
25	Cutting & Fixing iron bars for barred windows.				
		52.00	@ Rs. 28.23 P. Sft		Rs. 1,468
	( Twenty Eihgt rupees & Twenty Three Paisa only)				

**Total Rs.**

**1,802,140**

  
**XEN**

**SCHEDULE 'B'**

72

Name of Work:- Construction of Additional Class rooms in existing Primary Schools Taluka Ratodero  
(9 C/R) (2013-14 Programme) at: GBPS Arbi at Ali Hassan Khuhro (2 C/R) ( Electric). ADP 347

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	22.00	@ Rs:	910	P.Point	Rs: 20,020.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs:	742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68	@ Rs:	171	P.Meter	Rs: 11628.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	66.00	@ Rs:	428	P.Meter	Rs: 28248.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	22.00	@ Rs:	54	P.Each	Rs: 1,188.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs:	83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	16.00	@ Rs:	70	P.Each	Rs: 1,120.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	7.00	@ Rs:	72	P.Each	Rs: 504.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs:	162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	5.00	@ Rs:	916	P.No	Rs: 4,580.00

Part "A" TOTAL: Rs: 69,925.0

  
**XEN**



SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	6.00	@ Rs: 91	Each	Rs: 546.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	6.00	@ Rs: 141.71	P.Each	Rs: 850.26
13	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 1,426.34
14	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	1.00	@ Rs: 3341	P.Set	Rs: 3,341.00
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	16.00	@ Rs: 497	P.Each	Rs: 7,952.00
16	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	6.00	@ Rs: 497	Each	Rs: 2,982.00
17	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	6.00	@ Rs: 5500	P.No	Rs: 33,000.00

Part "B" TOTAL: Rs: 50,097.6

Part "A" TOTAL: Rs: 69,925.0

G: TOTAL: Rs: 120,022.6

## Schedule-B

23

Name of  
Work:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING PRIMARY  
SCHOOLS IN TALUKA RATODERO (09 UNITS) (2013-14 PROGRAMME) @  
GBPS SHAH-JI-WANDH (01C/R) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	848.00	@ Rs: 3,176.25 % 0Cft (Thirty one Hundred seventy six rup: & twenty five paisa only)	Rs:	2,693
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	308.00	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)	Rs:	26,780
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	669.00	@ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)	Rs:	79,935
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	513.24	@ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)	Rs:	172,962
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)	22.913	@ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)	Rs:	114,604
6	Filling watering and ramming earth in floor with surplus earth from foundation laed upto one chain and lift upto 5 ft. (S.I.No: 2 P/5).	565.330	@ Rs: 1,512.50 0.Cft (Fifteen hundred twelve rup: & fifty paisa only)	Rs:	855
7	Supply and fixing sand under floor including plugging in to walls	1100.00	@ Rs: 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)	Rs:	12,554
9	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.	1269.19	@ Rs. 12,674.36 % Cft (Twelve thousand six hundred seventy four rup: & thity six paisa only)	Rs.	160,862
10	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	1965.00	@ Rs. 2,206.60 % Cft	Rs.	43,360

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(Twenty tow hund: six rup: & sixty paisa only)

- 11 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

1965.00 @ Rs: 2,197.52 % Sft Rs: 43,181  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

- 12 Making Notice board made with cement.

32.00 @ Rs: 58.11 P. Sft Rs: 1,860  
(Nnety Three rupees & Thirty Seven paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges  
13 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs.  
The cost also i/c all carriage, tools and pla

28.00 @ Rs: 228.90 P. Rft Rs: 6,409  
(Two hundred twenty eight rupees & ninty paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded  
14 hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the  
jambs. The cost also i/c all carriage, tools

96.00 @ Rs: 240.50 P. Rft Rs: 23,088  
(Two hundred forty rupees & fifty paisa only)

- 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts  
15 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25  
P/60)

76.00 @ Rs: 902.93 P. Sft Rs: 68,623  
(Nine hund: two rup: & ninty three paisa only)

- 16 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

839.38 @ Rs: 1,287.44 % Sft Rs: 10,807  
(Twelve hundred eighty seven rupees & forty for paisa only)

- Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved  
17 design including painting 3 coats etc. complee ( weight not to be less than 3.7  
Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

98.00 @ Rs: 180.50 P. Sft Rs: 17,689  
( One hundre ninty four rupees & sixteen paisa only)

- 18 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

0.950 @ Rs: 3,550.00 P. Sft Rs: 3,373  
(Three Thousand Five hundred Fifty rupees & only)

- 19 Cutting & Fixing iron bars for barred windows.

20.00 @ Rs: 28.23 P. Sft Rs: 565  
( Twenty Eihgt rupees & Twenty Three Paisa only)

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification

125.00 @ Rs. 10.70 P.Sft Rs. 1,338  
(Ten rupees & seventy paisa only)

21 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

440.00 @ Rs: 4,411.82 % Sft Rs: 19,412  
( Forry four hundred eleven rup: & eighty two paisa only)

**(B) 1-1/2" Thick.**

720.00 @ Rs: 3,275.50 Rs: 23,584  
(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

22 Primary coat of chalk distemper( S.I No. 23 P/53)

1965.17 @ Rs: 442.75 % Sft Rs: 8,701  
(Four hundred forty two rupees & seventy five paisa only)

23 Distemping Three Coats (S.I No. 24 ©P/53)

1965.17 @ Rs: 1,079.65 % Sft Rs: 21,217  
(One thousand Seventy nine rup: & sixty five paisa only)

24 White wash Three Coats (S.I No. 26 © P/53)

440.00 @ Rs: 829.95 % Sft Rs: 3,652  
(Eight hundred twenty nine rup: & ninty five paisa only)

25 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

839.38 @ Rs. 1,948.10 % Sft Rs. 16,352  
Twenty on hundred sixteen rupees & forty one paisa only)

**Total Rs.**

**879,980**

  
**XEN**

**SCHEDULE 'B'**

24

Name of Work:- Construction of Additional Class rooms in existing Primary Schools Taluka Ratodero  
(9 C/R) (2013-14 Programme) at: GBPS Shah-ji-Wandh (1 C/R) ( Electric). ADP 347

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	12.00	@ Rs: 910	P.Point	Rs: 10,920.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	36.00	@ Rs: 171	P.Meter	Rs: 6156.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-/.052} (10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	32.00	@ Rs: 428	P.Meter	Rs: 13696.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	12.00	@ Rs: 54	P.Each	Rs: 648.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	9.00	@ Rs: 70	P.Each	Rs: 630.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	4.00	@ Rs: 72	P.Each	Rs: 288.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	3.00	@ Rs: 916	P.No	Rs: 2,748.00

Part "A" TOTAL: Rs: 36,898.0

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	3.00	@ Rs: 91	Each	Rs: 273.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	3.00	@ Rs: 141.71	P.Each	Rs: 425.13
13	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft	Rs: 1,426.00
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	9.00	@ Rs: 497	P.Each	Rs: 4,473.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, canopy blade, suitable (Double bearing) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	3.00	@ Rs: 5500	P.No	Rs: 16,500.00

Part "B" TOTAL: Rs: 23,097.1

Part "A" TOTAL: Rs: 36,898.0

G: TOTAL: Rs: 59,995.1

  
XEN

**SCHEDULE " B "**

S.No: 25

NAME OF WORK:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING  
PRIMARY SCHOOLS IN TALUKA LARKANO (8-UNITS) (2013-14  
PROGRAMME) AT GBPS MUNAWARABAD (4-C/R) TALUKA  
LARKANO**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Cement concrete brick or stone ballast 1/2" to 2" gauge. (S.I.No: 4 (d) P/ 14).				
		157.00	@ Rs: 8122/95	% Cft	Rs: 12,753.00
					(Rs: eight thous: one hund: twenty two & ninty five only)
2	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		537.00	@ Rs: 1141/25	% Cft	Rs: 6,129.0
					(Rs: one thous: one hund: forty one & twenty five only)
3	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		28.00	@ Rs:12674/36	% Cft	Rs: 3,549.00
					(Rs: twelve thous: six hund: seventy four & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		1872.00	@ Rs:337/-	P.Cft	Rs: 630,864.0
					(Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		100.00	@ Rs:5001/70	P.Cwt	Rs: 500,170.0
					(Rs: five thous: one & seventy only)
6	Pacca brick work in First floor in cement sand mortar. 1:6.				
		1999.00	@ Rs:13112/99	P.Cwt	Rs: 262,129.00
					(Rs: thirteen thous: one hund; twelve & ninty nine only)
7	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 28 P. 92 ).				
		156.00	@ Rs:228/90	P.Rft	Rs: 35,708.00
					(Rs: two hund: twenty eight & ninty only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
8	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).	684.00	@ Rs: 240/50 (Rs: two hund: forty & fifty only)	P.Rft	Rs: 164,502.00
9	M.S barred windows squars bars 5/8" dia.	6.00	@ Rs: 3550/- (Rs: three thous: five hund: fifty only)	P.Sft	Rs: 21,300.00
10	Cutting and fixing iron bars for barred windows.	128.00	@ Rs: 28/23 (Rs: twenty eight & twenty three only)	P.Cwt	Rs: 3,613.00
11	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	268.00	@ Rs:180/50 (Rs: one hund: eighty & fifty only)	P. Sft	Rs: 48,374.0
12	Cement plaster (1:6) upto 12' ft: height 1/2" thick. (S.I.No: 13 (b) P.58).				
(B)	<u>First Floor.</u>	6446.00	@ Rs:2308/84 (Rs: two thous: three hund: eight & eighty four only)	%Sft	Rs: 148,828.00
13	Cement plaster 1:4 upto 12' ft; height 3/8" thick. (S.I.No: 11 (a) P.58).				
(B)	<u>First Floor.</u>	6446.00	@ Rs:2299/76 (Rs: two thous: two hund; ninty nine & seventy six only)	%Sft	Rs: 148,243.00
14	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).	508.00	@ Rs: 902/93 (Rs: nine hud: two & ninty three only)	P.Sft	Rs: 458,688.00
15	P/F deodar Almirah 9"x12" depth i/c boxing with back shalves shutters bars fittings complete (Without Box) (S.I.No: 23 P.68).	160.00	@ Rs:1748/- (Rs: one thous: seven hund; fourty eight only)	P.Sft	Rs: 279,680.00
16	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	1112.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 14,316.0

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 17 Extra labour rate making grooves of 1"x1/4" or 3/4"x1/2" plastered surface with true edges both vertically and horizontally with uniform depth and with groove base smoothly finished etc complete as per instruction of Engineer incharge.(S.I.NO: 34 P.54).

388.00	@ Rs: 7/71	P.Rft	Rs:	2,991.00
(Rs: seven & seventy one only)				

- 18 Cement Concreate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).

276.00	@ Rs: 14429/25	%Cft	Rs:	39,825.00
(Rs: fourteen thous: four hund: twenty nine & twenty five only)				

- 19 Providing and laying 1" thick topping cement concreate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

474.00	@ Rs: 4411/82	%Sft	Rs:	20,912.00
(Rs: four thous: four hund: eleven & eighty two only)				

**(B) 2"Thick (2ND FLOOR)**

2289.00	@ Rs: 3729/56	% S.ft	Rs:	85,370.00
(Rs: three thous: seven hund: twenty nine & fifty six only)				

- 20 Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).

1074.00	@ Rs:27747/06	%Sft	Rs:	298,003.0
(Rs: twenty seven thous: seven hund forty seven & six only)				

- 21 Providing and laying marble flooring super / china Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without windings, set in Cement Slurry. laid over 3/4" thick Cement mortar 1:2 & filling the joints with white cement and pigment i/c grinding, rubbing and Chemical polishing as directed by the Engineer Incharge. (R.A)

1037.00	@ Rs:307/-	%Sft	Rs:	318,359.00
(Rs: three hund: seven only)				

- 22 Providing & fixing 3/8" thick marble tiles of approved quality and colour and shade size 8"x4"/6"x4" in dado skirting and facing removal / tucking of existing plaster surface etc. Over 1/2" thick base of cement mortar 1:3 setting of tiles in slurry of white cement over mortar base i/c filling the joints and washing the tiles with white cement slurry current finishing cleaning and (i) For new works. (S.I.No: 68 (i) P/48).

142.00	@ Rs: 186/04	P.Sft	Rs:	26,418.00
(Rs: one hund: eighty six & four only)				

- 23 Notice board made with cement. (S.I.No: 1 P/94)

128.00	@ Rs: 58/11	P.Sft	Rs:	7,438.00
(Rs: fifty eight & eleven only)				

  
**XEN**



S.No:	Description	Qty:	Rate	Unit	Amount
24	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).				
		2289.00	@ Rs:1887/40	% Sft	Rs: 43,203.00
			(Rs: one thous: eight hund; eighty seven & fourteen only)		
25	Distempering two coats. (S.I.No.24 (b) P/53).				
		3416.00	@ Rs:1043/90	% Sft	Rs: 35,660.00
			(Rs: ten hund; forty three & ninty only)		
26	Primary coat of chalk under distempring.				
		5286.00	@ Rs: 442/75	% S.ft	Rs: 46,807.00
			(Rs: four hund; fourty tow & seventy five only)		
27	Distempring three coats				
		10572.00	@ Rs:1079/65	% Sft	Rs: 114,140.00
			(Rs: one thous: seventy nine & sixty five only)		
28	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		2272.00	@ Rs: 1948/10	% Sft	Rs: 44,261.00
			(Rs: one thous: nine hund: fourty eight & ten only)		
29	Painting doors and windows any type				
		632.00	@ Rs:1489/68	% S.ft	Rs: 9,415.00
			(Rs: one thous: four hund: eighty nine & sixty eight only)		
30	Painting guard bars , gates iron bars gratings railings i/c standard barse etc: smiler open works.				
		96.00	@ Rs:1270/83	% S.ft	Rs: 1,430.00
			(Rs: one thous: two hund: seventy & eighty three only)		
G.Total:					Rs: 3,833,078.0

  
XEN

**SCHEDULE " B "**

S.No: 26

NAME OF WORK:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING  
PRIMARY SCHOOLS IN TALUKA LARKANA (8-UNITS) (2013-14)  
AT GBPS SAWAYO AGHAM (2-C/ROOMS) TALUKA LARKANA.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		2541.00	@ Rs:13112/99	%Cft	Rs: 333,201.00
			(Rs: thirteen thous: one hund; twelve & ninty nine only)		
2	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		925.00	@ Rs: 349/10	%Cft	Rs: 322,918.00
			(Rs: three hund: forty nine & ten only)		
3	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending and laying in position, making joints and fastenings i/c cost of binding wire ( also includes removal of rust from bars). (B) Using Tor bars. (S.I.No.8(b) P/16).				
		54.00	@ Rs:5001/70	P.Cwt	Rs: 270,092.00
			(Rs: five thous: one & seventy only)		
4	Extra labour for lifting of steel above first floor for every additional floor (S.I.No: 29 P/18).				
		54.00	@ Rs: 151/25	P.Cwt	8,168.00
			(Rs: one hund: fifty one & twenty five only)		
5	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		53.00	@ Rs:228/90	P.Rft	Rs: 12,132.00
			(Rs: two hund: twenty eight & ninty only)		
6	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		265.00	@ Rs: 240/50	P.Rft	Rs: 63,733.00
			(Rs: two hund: forty & fifty only)		
7	M.S barred windows squars bars 5/8" dia.				
		2.992	@ Rs: 3550/-	P.Sft	Rs: 10,622.00
			(Rs: three thous: five hund: fifty only)		
8	Cutting and fixing iron bars for barred windows.				
		63.00	@ Rs: 28/23	P.Cwt	Rs: 1,778.00
			(Rs: twenty eight & twenty three only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	S/F in position approved grill of 3/4" x 1/4" size flat iron of approved design including painting three coats etc complete (weight not to be less than 3.7 Lbs/ sq. foot of finished grill). (S.I.No: 26 P.97).	40.00	@ Rs: 194/16	P.Sft	Rs: 7,766.00
			(Rs: one hund: ninty four & sixteen only)		
10	Cement plaster (1:6) upto 20' ft: height 1/2" thick. (First Floor) (S.I.No: 13(b) P/56).	3400.00	@ Rs:2308/84	% S.ft	Rs: 78,501.00
			(Rs: two thous: three hund; eight & eighty four only)		
11	Cement plaster ratio (1:4) upto 20' ft: height 3/4" thick (S.I.No:11 P/56).	3400.00	@ Rs:2299/76	% S.ft	Rs: 78,192.00
			(Rs: two thous: two hund; ninty nine & seventy six only)		
12	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).	228.00	@ Rs: 902/93	P.Sft	Rs: 205,868.00
			(Rs: nine hund: two & ninty three only)		
13	P/F deodar Almirah 9"x12" depth i/c boxing with back shalves shutters bars fittings complete (Without Box) (S.I.No: 23 P.68).	51.00	@ Rs:1748/-	P.Sft	Rs: 89,148.00
			(Rs: one thous: seven hund; fourty eight only)		
14	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).	30.00	@ Rs:14429/25	%Cft	Rs: 4,329.00
15	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).	233.00	@ Rs:27747/06	% Sft	Rs: 64,651.00
16	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	778.00	@ Rs: 4411/82	% Sft	Rs: 34,324.00
(B)	<b>2"Thick (FIRST FLOOR)</b>	1442.00	@ Rs: 3502/38	% S.ft	Rs: 50,504.00
			(Rs: three thous: five hund: two & thirty eight only)		

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
17	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).				
		1442.00	@ Rs:1887/40	% Sft	Rs: 27,216.00
			(Rs: one thous: eight hund: eighty seven & fourteen only)		
18	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		1329.00	@ Rs:1287/44	% Sft	Rs: 17,110.0
			(Rs: one thous: two hund: eighty seven & fourty four only)		
19	Providing and laying Halla pattern tiles glazed 8"x8"x3/4" on floor or wall facing in required pattern of sitile specication joints in white cement and pigment over a base shape with finishing cleaning and cost lof wax polish etc complete including cutting tiles to proper profile.				
		120.00	@ Rs:34520/31	% Sft	Rs: 41,425.00
20	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).				
		92.00	@ Rs:226/02	P.Sft	Rs: 20,794.00
			(Rs: two hund: twenty six & two only)		
21	Primary coat of chalk under distemping.				
		2967.00	@ Rs: 442/75	% S.ft	Rs: 13,136.00
			(Rs: four hund: fourty tow & seventy five only)		
22	Distemping three coats				
		4238.00	@ Rs:1079/65	% Sft	Rs: 45,756.00
			(Rs: one thous: seventy nine & sixty five only)		
23	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		1329.00	@ Rs: 1948/10	% Sft	Rs: 25,890.00
			(Rs: one thous: nine hund: fourty eight & ten only)		
24	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).				
		558.00	@ Rs:2116/41	% Sft	Rs: 11,810.00
			(Rs: two thous: one hund sixteen & fourty one only)		
G.Total:					Rs: 1,839,064.00

  
**XEN**

**SCHEDULE " B "**

S.No: 27

NAME OF WORK:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN  
EXISTING PRIMARY SCHOOLS IN TALUKA LARKANO  
(8-UNITS) (2013-14 PROGRAMME) AT GBPS TALBANI  
(1-C/R) TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	816.00	@ Rs: 3176/25	% 0 Cft	Rs: 2,591.00 (Rs: three thous: one hund: seventy hund: twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/ ).	245.00	@ Rs: 8694/95	% Cft	Rs: 21,302.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	665.00	@ Rs:11948/36	%.Cft	Rs: 79,456.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	219.00	@ Rs:337/-	P.Cft	Rs: 73,803.00 (Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	977.00	@ Rs:5001/70	P.Cwt	Rs: 48,900.00 (Rs: five thous: one & seventy only)
6	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	1272.00	@ Rs: 1141/25	%.Cft	Rs: 14,516.00 (Rs: one thous: one hund: forty one & twenty five only)
7	Extra lead 3.0 miles	1272.00	@ Rs: 579/41	%.Cft	Rs: 7,370.00 (Rs: five hund: sevnty nine & fourty one only)
8	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	163.00	@ Rs:10/70	P.Sft	Rs: 1,744.00 (Rs: ten & seventy only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	Dry rammed brick or stone ballast 11/2" to 2" guage. (S.I.No.2 P/14).				
		137.00	@ Rs: 3327/50	% Cft	Rs: 4,558.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
10	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1184.00	@ Rs:12674/36	% Cft	Rs: 150,064.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
11	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jams. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		28.00	@ Rs:228/90	P.Rft	Rs: 6,409.00
			(Rs: two hund: twenty eight & ninty only)		
12	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jams. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		114.00	@ Rs: 240/50	P.Rft	Rs: 27,417.00
			(Rs: two hund: forty & fifty only)		
13	Suppling M.S square, bar 5/8" dia (Sch: of matrial).				
		1.00	@ Rs: 3350/-	P.Cwt	Rs: 3,550.00
			(Rs: three thous: three hund; fifty only)		
14	Cutting and fixing iron bars for barred windows. (S.I.No.18 P/97).				
		26.00	@ Rs: 28/23	P.Bar	Rs: 733.00
			(Rs: twenty eight & twenty five only)		
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).				
		114.00	@ Rs: 902/93	P.Sft	Rs: 102,934.00
			(Rs: nine hud: two & ninty three only)		
16	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2013.00	@ Rs:2206/60	% Sft	Rs: 44,418.00
			(Rs: two thous: two hund: six & sixty only)		
17	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1981.00	@ Rs:2197/52	% Sft	Rs: 43,532.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		
18	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		580.00	@ Rs:1287/44	% Sft	Rs: 7,467.00
			(Rs: one thous: two hund: eighty seven & fourty four only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
19	Notice board made with cement. (S.I.No: 1 P/94)				
		32.00	@ Rs: 58/11 (Rs: fifty eight & eleven only)	P.Sft	Rs: 1,859.00
20	Providing and laying 1" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		440.00	@ Rs: 4411/82 (Rs: four thous: four hund: eleven & eighty two only)	%Sft	Rs: 19,412.00
21	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).				
		59.00	@ Rs:226/02 (Rs: two hund; twenty six & two only)	P.Sft	Rs: 13,335.00
22	Suppling of T.Girders at site of Works				
		10.76	@ Rs: 3850/- (Rs: three thous: eight hund; fifty only)	P.Cwt	Rs: 41,426.00
23	Supplying of T-Iron at the site of work				
		9.78	@ Rs: 3575/- (Rs: three thous: five hund; seventy five only)	P.Cwt	Rs: 34,964.00
24	Errection and rolled steel beams or old rails in roof etc errection and fixing in position. (S.I.No. P/ ).				
		20.54	@ Rs: 186/34 (Rs: one hund; eighty six & thirty four only)	P.Cwt	Rs: 3,827.00
25	First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortor with 1/2" thick sand wiched layer of 1:6 cement mortor including 1:2 cement pointing underside of tiles complete including curing etc. (S.I.No: 1 P/32).				
		565.000	@ Rs: 11443/10 (Rs: eleven thous: four hund: forty three & ten only)	%Sft	Rs: 64,654.00
26	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).				
		728.00	@ Rs:10/70 (Rs: ten & seventy only)	P.Sft	Rs: 7,790.0

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 27 Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).

530.00	@ Rs:1887/40	% Sft	Rs:	10,003.00
(Rs: one thous: eight hund; eighty seven & fourteen only)				

- 28 P/F deodar Almirah 9"x12" depth i/c boxing with back shalves shutters bars fittings complete (Without Box) (S.I.No: 23 P.68).

17.00	@ Rs:1748/-	P.Sft	Rs:	29,716.00
(Rs: one thous: seven hund; fourty eight only)				

- 29 Primary coat of chalk distempering. (S.I.No.23 P/57).

1691.00	@ Rs:442/75	% Sft	Rs:	7,487.00
(Rs: four hund; fourty two & seventy five only)				

- 30 Distempering three coats. (S.I.No.24 (c) P/53).

1691.00	@ Rs:1079/65	% Sft	Rs:	18,257.00
(Rs: one thos: seventy nine & sixty five only)				

(B) Two coats.

440.00	@ Rs:1043/90	% Sft	Rs:	4,593.00
(Rs: ten hund; forty three & ninty only)				

- 31 Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).

1029.00	@ Rs: 1948/10	% Sft	Rs:	20,046.00
(Rs: one thous: nine hund: fourty eight & ten only)				

- 32 Preparing surface and painting of doors and windows any type (including edges)  
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

241.00	@ Rs:2116/41	% Sft	Rs:	5,100.00
(Rs: two thous: one hund: sixteen & fourty one only)				

- 33 Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.

343.00	@ Rs:1270/83	% S.ft	Rs:	4,359.00
(Rs: one thous: two hund: seventy & eighty three only)				

<b>G.Total:</b>	Rs:	<b>927,592.0</b>
-----------------	-----	------------------

  
**XEN**



**SCHEDULE 'B'**

Name of Work:- Construction of building for existing Shelterless Primary Schools in Taluka Balrani / Dokri  
(06 Units) (2013-14 Programme) at: GBPS Dahar Muhalla Karani (2 C/R) ( Electric). ADP 349

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	24.00	@ Rs:	910	P.Point	Rs: 21,840.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs:	742	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	160	@ Rs:	171	P.Meter	Rs: 27360.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}{10mm2} Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	66.00	@ Rs:	428	P.Meter	Rs: 28248.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	23.00	@ Rs:	54	P.Each	Rs: 1,242.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs:	83	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	16.00	@ Rs:	70	P.Each	Rs: 1,120.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs:	72	P.Each	Rs: 576.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs:	162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	5.00	@ Rs:	916	P.No	Rs: 4,580.00

Part "A" TOTAL: Rs: 88,428.0

  
**XEN**

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	8.00	@ Rs: 91	Each	Rs: 728.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	8.00	@ Rs: 141.71	P.Each	Rs: 1,133.68
13	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq:ft	Rs: 1,426.34
14	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	1.00	@ Rs: 3341	P.Set	Rs: 3,341.00
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	16.00	@ Rs: 497	P.Each	Rs: 7,952.00
16	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	6.00	@ Rs: 497	Each	Rs: 2,982.00
17	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	8.00	@ Rs: 5500	P.No	Rs: 44,000.00

**Part "B" TOTAL: Rs: 61,563.0**

**Part "A" TOTAL: Rs: 88,428.0**

**G: TOTAL: Rs: 149,991.0**

  
**XEN**

## Schedule-B

29

**INTEGRATED REHABILITATION OF ELEMENTARY SCHOOLS IN**  
Name of Work:- **TALUKA RATODERO (12 UNITS) (2013-14 PROGRAMME) @GBPS**  
**IBRAHIM JI WANDH TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 20 P/10)	574.00	@ Rs. 5,445.00	% Cft	Rs. 31,254
	(Fifty four hundred & forty five rupees only)				
2	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)	1091.00	@ Rs. 1,285.63	% Cft	Rs: 14,026
	( Twelve hundred eighty five rup & sixty three paisa only)				
3	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	324.00	@ Rs. 3,176.25	% 0Cft	Rs: 1,029
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
4	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)	175.00	@ Rs. 8,694.95	% Cft	Rs: 15,216
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	542.00	@ Rs. 11,948.36	% Cft	Rs: 64,760
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
6	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	307.00	@ Rs. 337.00	P.Cft	Rs: 103,459
	(Three hundred Thirty seven rup: only)				
7	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	13.705	@ Rs. 5,001.70	P.Cwt	Rs: 68,548
	( Five thousand one rup: & seventy paisa only)				
8	Supply and fixing sand under floor including plugging in to walls	638.00	@ Rs. 1,141.25	% Cft	Rs: 7,281
	(Eleven hundred forty one rupees & twenty five paisa only)				
9	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.	924.00	@ Rs. 12,674.36	% Cft	Rs. 117,111
	(Twelve thousand six hundred seventy four rup: & thity six paisa only)				
10	Supplying of Girders at Site of Work ( Schedule of Material).	16.839	@ Rs. 3,850.00	P.Cwt	Rs. 64,830
	(Thirty Eight Hundred & Fifty Rupees only)				

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

11 Supplying of T-Iron at Site of Work (Schedule of Material).

17.089 @ Rs. 3,575.00 P.Cwt Rs. 61,093  
(Thirty Five Hundred & Seventy five Rupees only)

12 Errection of Rolled Steel Beam etc (S.I No. 6 P/91).

33.929 @ Rs. 186.34 P.Cwt Rs. 6,322  
(One Hundred & Eighty Six Rupees Thirty Four Pessas only)

13 First Class Tile Roofing consiisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layer of tile 12" x6" x1-1/4" laid in 1:6 cement mortar with 1/2" wiched layer of 1:6 cement mortar incliding 1:2 cement pointin underside of tiles complete incliding curing etc (S.I No. 1 P/33).

1100.00 @ Rs: 11,443.10 % Sft Rs: 125,874  
(Eleven Thousand Forty hundred Forty Three rup: & Ten paisa only)

14 Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.

478.00 @ Rs. 12,346.65 % Cft Rs. 59,017  
(Twelve thousand three hund: forty six rup: & sixty five paisa only)

15 Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)

3719.00 @ Rs. 2,206.60 % Cft Rs. 82,063  
(Twenty tow hund: six rup: & sixty paisa only)

16 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

3719.00 @ Rs: 2,197.52 % Sft Rs: 81,726  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

17 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

1409.00 @ Rs: 1,287.44 % Sft Rs: 18,140  
(Twelve hundred eighty seven rupees & forty for paisa only)

18 Providing and laying single per layer of poly then sheet 0.13 mm thick for water proofing as per specification and Instruction of Engineer in charge. (S.I.No: 38 P.44).

1102.00 @ Rs: 10.70 P.Cft Rs: 11,791  
(Ten rupees & seventy paisa only)

19 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

1432.00 @ Rs: 4,411.82 % Sft Rs: 63,177  
( Forry four hundred eleven rup: & eighty two paisa only)

(B) **2" Thick.**

78.00 @ Rs: 3,275.50 % Sft Rs: 2,555  
(Thirty Two hundred Seventy Fine rup: & Fifty paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges  
20 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

35.32 @ Rs: 228.90 P. Rft Rs: 8,085  
(Two hundred twenty eight rupees & ninty paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded
- 21 hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla
- 44.60 @ Rs: 240.50 P. Rft Rs: 10,726  
(Two hundred forty rupees & fifty paisa only)
- 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts
- 22 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)
- 40.16 @ Rs: 902.93 P. Sft Rs: 36,262  
(Nine hund: two rup: & ninty three paisa only)
- Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including
- 23 painting 3 coats etc. complete ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)
- 95.00 @ Rs: 180.50 P. Sft Rs: 17,148  
( One hundre ninty four rupees & sixteen paisa only)
- 24 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.
- 39 @ Rs. 14,429.25 % Cft Rs. 5,627  
(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)
- 25 Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.( S.I No. 23 P/45)
- 246.00 @ Rs. 27,678.86 % Cft Rs. 68,090  
( Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)
- 26 White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)
- 47.00 @ Rs. 28,253.61 % Cft Rs. 13,279  
(Twenty seven thousand seven hund: forty seve rupp: & six paisa only)
- 27 Making & fixing steel gated doors with 1 1/6" thick sheeting i/c angle iron frame 2"x2"x3/4" and square bars 4" centre to cement.
- 48.00 @ Rs. 726.72 P. Sft Rs. 34,883  
(Seven hundred twenty six rupees & seventy two paisa only)
- 28 Making Notice board made with cement.
- 64.00 @ Rs: 58.11 P. Sft Rs: 3,719  
(Ninty Three rupees & Thirty Seven paisa only)
- 29 White wash Three Coats (S.I No. 26 © P/53).
- 916.00 @ Rs: 829.95 % Sft Rs: 7,602  
(Eight hundred twenty nine rup: & ninty five paisa only)
- 30 Primary coat of chalk distemper( S.I No. 23 P/53)
- 10069.00 @ Rs: 442.75 % Sft Rs: 44,580  
(Four hundred forty two rupees & seventy five paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

31 Distemping Three Coats (S.I No. 24 ©P/53)

10069.00 @ Rs: 1,079.65 % Sft Rs: 108,710  
(One thousand Seventy nine rup: & sixty five paisa only)

32 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper  
filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)

3010.00 @ Rs: 1,948.10 % Sft Rs: 58,638  
( Ninteen hundred forty eight rupees & ten paisa only)

33 Prepairng surface and painting of doors and widows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c ) P. 76 (ii) ).

(a) 184.00 @ Rs: 2,116.41 % Sft Rs: 3,894  
( Twenty one hundred sixteen rup & forty one paisa only)

(b) Old Surface.

132.00 @ Rs: 1,212.21 % Sft Rs: 1,600  
(Twelve hundred twelve rup :& twenty one paisa only)

34 Preparing surface & painting Guard bars, gates/ iron bars gating, rakings (i/c standard braces etc) & lar  
open work. (New Surface) (S. I No. 5 (d) P/70)

96.00 @ Rs. 1,270.83 % Sft Rs. 1,220  
(Twelve Hundred seventy rupees & eithy three paisa only)

Total Rs: 1,423,342

  
XEN

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

**PART-B**

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605  
(Forty Eight hundred Two rup: & Sixty paisa only)

- 2 S/F concealed stop cock of superior quality with C.P head 1/2" dia.

2.0 @ Rs: 889/46 P.No Rs: 1,779  
(Eight hundred Eighty Nine rup: & Forty Six paisa only)

- 3 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.0 @ Rs: 1384/24 P.No Rs: 2,768  
(Thirteen hundred Eighty Four rup: & Twenty Four paisa only)

- 4 Providing & Fixing Handle valve (China)

2.0 @ Rs: 365.42 P.No Rs: 731  
(Seven hundred Seventy Seven rup: & Eighty paisa only)

- 5 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (150 gallons).

150.0 87.95 P.Gallan Rs: 13,193  
(ThartyThousand Seven hundred Seventy Three rup: & Forty Two Pessa only)

**G.Total:**

**Rs: 28,076**

**(B) N.S.I**

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

60.0 @ Rs: 78/01 P.No Rs: 4,681  
(Seventy Eight rup: & One Pessa only)

20.0 @ Rs: 97/91 P.No Rs: 1,958  
(Ninety Seven rup: & Ninety One Pessa only)

15.0 @ Rs: 397/77 P.No Rs: 5,967  
(Three Hund: Ninety Seven rup: & Seventy Seven Pessa only)

- 2 P/F approved quality A.C Motor Mono Block Set made 1-1/4"x1" suction and Delivery 1 H Power Single Phase Motor (Diamond / Siemence make or equal) i/c Cost of C.I Fitting Nats Bolts etc complete (R.A)

1.0 @ Rs: 14201.00 P.No Rs: 14,201  
(Forteen Thousand Two Hund: OPne rup: & only)

**XEN**

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

- 3 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

(a) Filter 10.0 @ Rs: 76/05 P.Rft Rs: 760  
(Seventy Six rup: & Five Pessa only)

(b) G.I Pipe 90.0 @ Rs: 77 P.Rft Rs: 6,930  
(Tharty Eight Six rup: & Ninety Five Pessa only)

(C) Machine 1.0 @ Rs: 4500 Each Rs: 4,500  
(Fourteen Hund: Forty One rup: & Sixty Five Pessa only)

G.Total: Rs: 38,997

S.I Rs. 28,076

N.S.I Rs. 38,997

G.Total: Rs. 67,073

  
XEN



## Schedule-B

30

**INTEGRATED REHABILITATION OF ELEMENTARY SCHOOLS IN TALUKA**  
**Name of** RATODERO (12 UNITS) (2013-14 PROGRAMME) @GBPS GHULAM  
**Work:-** QADIR DAKHAN TALUKA RATODERO DISTRICT LARKANO.

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling 2nd Class tile roofing (S.I No. 22 (b) P/11)				
	567 @ Rs: 378.13 % Cft (Three Hundred Seventy eight rup & Thirteen paisa only)				Rs: 2,144
2	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)				
	892.00 @ Rs: 1,285.63 % Cft ( Twelve hundred eighty five rup & sixty three paisa only)				Rs: 11,468
3	Removing cement or lime plaster. (S.I No. 53 P/13)				
	1445 @ Rs: 121.00 % Cft ( One hundred & twenty rup: only)				Rs: 1,748
4	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
	334 @ Rs: 3,176.25 % OCft (Thirty one Hundred seventy six rup: & twenty five paisa only)				Rs: 1,061
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
	655.00 @ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				Rs: 78,262
6	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)				
	311 @ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)				Rs: 27,041
7	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
	212.00 @ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)				Rs: 71,444
8	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)				
	9.464 @ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)				Rs: 47,336
9	Supply and fixing sand under floor including plugging in to walls				
	4743.00 @ Rs: 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)				Rs: 54,129

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

10 Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.

1484 @ Rs. 12,674.36 % Cft Rs. 188,088  
(Twelve thousand six hundred seventy four rup: & thity six paisa only)

11 P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification

755 @ Rs. 10.70 P.Sft Rs. 8,079  
(Ten rupees & seventy paisa only)

12 Supplying of Girders at Site of Work ( Schedule of Material).

10.679 @ Rs. 3,850.00 P.Cwt Rs. 41,114  
(Thirty Eight Hundred & Fifty Rupees only)

13 Supplying of T-Iron at Site of Work (Schedule of Materal).

9.429 @ Rs. 3,575.00 P.Cwt Rs. 33,709  
(Thirty Five Hundred & Seventy five Rupees only)

14 Errection of Rolled Steel Beam etc (S.I No. 6 P/91).

20.107 @ Rs. 186.34 p.Cwt Rs. 3,747  
(Eleven thousand four hund:forty three rup: & ten paisa only)

15 Reinforcement Cement Concrete spout including fixing in position 2 1/2" x6"x5".

3 @ Rs. 261.25 P.No. Rs. 784  
(Two hundred sixty one rupees & twenty five paisa only)

16 First Class Tile Roofing consiisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layer of tile 12" x6" x1-1/4" laid in 1:6 cement mortar with 1/2" wi

611 @ Rs. 11,443.10 % Cft Rs. 69,917  
(Eleven thousand four hund:forty three rup: & ten paisa only)

17 Cement Plaster 1:4 upto 12" height. 3/4" thick ( S.I No. 11 (c) P/51)

1445 @ Rs: 3,015.76 % Sft Rs: 43,578  
(Three thousand fifteen rup: & seventy six paisa only)

18 Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)

2761 @ Rs. 2,206.60 % Cft Rs. 60,924  
(Twenty tow hund: six rup: & sixty paisa only)

19 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

2729 @ Rs: 2,197.52 % Sft Rs: 59,970  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 Making Notice board made with cement.

32 @ Rs: 58.11 P. Sft Rs: 1,860  
(Ninty Three rupees & Thirty Seven paisa only)

21 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

68 @ Rs: 228.90 P. Rft Rs: 15,565  
(Two hundred twenty eight rupees & ninty paisa only)

22 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

192.00 @ Rs: 240.50 P. Rft Rs: 46,176  
(Two hundred forty rupees & fifty paisa only)

23 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

236 @ Rs: 902.93 P. Sft Rs: 213,091  
(Nine hund: two rup: & ninty three paisa only)

24 M.S Barred Windows Squars Bars 5/8" Dia.

0.86 @ Rs: 3,550.00 P. Sft Rs: 3,053  
(Thirty Five hundred & fifty rupees only)

25 Cutting and fixing iron bars for barred windows.

18.00 @ Rs: 28.23 P. Sft Rs: 508  
(Twenty Eight rupees & Twenty Three paisa only)

26 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

855.00 @ Rs: 4,411.82 % Sft Rs: 37,721  
( Forry four hundred eleven rup: & eighty two paisa only)

27 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

1000.00 @ Rs: 1,287.44 % Sft Rs: 12,874  
(Twelve hundred eighty seven rupees & forty for paisa only)

28 Primary coat of chalk distemper( S.I No. 23 P/53)

4639 @ Rs: 442.75 % Sft Rs: 20,539  
(Four hundred forty two rupees & seventy five paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

29 Distemping Three Coats (S.I No. 24 ©P/53)

6039 @ Rs: 1,079.65 % Sft Rs: 65,200  
(One thousand Seventy nine rup: & sixty five paisa only)

30 Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complete ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

148.00 @ Rs: 180.50 P. Sft Rs: 26,714  
( One hundre ninty four rupees & sixteen paisa only)

31 Providing and fixing iron steel grill door with angle iron frame of 1 1/2" x 1 1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in charg.(S.I No. 31 P No. 93)

76.00 @ Rs. 231.60 P. Sft Rs. 17,602  
( Two hundred thiry one rup: & sixty Paisa only)

32 Prepairing surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).

187 @ Rs: 2,116.41 % Sft Rs: 3,958  
( Twenty one hundred sixteen rup & forty one paisa only)

34 Making & fixing steel gated doors with 1 1/6" thick sheeting i/c angle iron frame 2"x2"x3/4" and square bars 4" centre to cement.

63 @ Rs. 726.72 P. Sft Rs. 45,783  
(Seven hundred twenty six rupees & seventy two paisa only)

35 Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.

483 @ Rs. 1,270.83 % Sft Rs. 6,138  
(Twelve Hundred seventy rupees & eithy three paisa only)

36 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)

2643 @ Rs: 1,948.10 % Sft Rs: 51,488  
( Ninteen hundred forty eight rupees & ten paisa only)

Total Rs: 1,372,814

  
**XEN**

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

**PART-B**

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19' clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605  
(Forty Eight hundred Two rup: & Sixty paisa only)

- 2 S/F concealed stop cock of superior quality with C.P head 1/2" dia.

2.0 @ Rs: 889/46 P.No: Rs: 1,779  
(Eight hundred Eighty Nine rup: & Forty Six paisa only)

- 3 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.0 @ Rs: 1384/24 P.No: Rs: 2,768  
(Thirteen hundred Eighty Four rup: & Twenty Four paisa only)

- 4 Providing & Fixing Handle valve (China)

2.0 @ Rs: 365.42 P.No: Rs: 731  
(Seven hundred Seventy Seven rup: & Eighty paisa only)

- 5 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commocion for inlet- outlet and over flow pipe etc complete (150 gallons).

150.0 87.95 P.Gallan Rs: 13,193  
(ThartyThousand Seven hundred Seventy Three rup: & Forty Two Pessa only)

**G.Total: Rs: 28,076**

**(B) N.S.I**

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

60.0 @ Rs: 78/01 P.No: Rs: 4,681  
(Seventy Eight rup: & One Pessa only)

20.0 @ Rs: 97/91 P.No: Rs: 1,958  
(Ninety Seven rup: & Ninety One Pessa only)

15.0 @ Rs: 397/77 P.No: Rs: 5,967  
(Three Hund: Ninety Seven rup: & Seventy Seven Pessa only)

- 2 P/F approved quality A.C Motor Mono Block Set made 1-1/4"x1" suction and Delivery 1 H Power Single Phase Motor (Diamond / Siemence make or equal) i/c Cost of C.I Fitting Nats Bolts etc complete (R.A)

1.0 @ Rs: 14201.00 P.No: Rs: 14,201  
(Forteen Thousand Two Hund: OPne rup: & only)

**XEN**

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

- 3 Hand pump all accessorial i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

**(a) Filter** 10.0 @ Rs: 76/05 P.Rft Rs: 760  
(Seventy Six rup: & Five Pessa only)

**(b) G.I Pipe** 90.0 @ Rs: 77 P.Rft Rs: 6,930  
(Tharty Eight Six rup: & Ninety Five Pessa only)

**(C) Machine** 1.0 @ Rs: 4500 Each Rs: 4,500  
(Fourteen Hund: Forty One rup: & Sixty Five Pessa only)

**G.Total:** Rs: 38,997

S.I Rs. 28,076

N.S.I Rs. 38,997

**G.Total:** Rs. 67,073

  
**XEN**

**SCHEDULE " B "**

S.No: 21

NAME OF WORK:-

**INTEGRATED RTEHABILITATION OF ELEMENTARY  
SCHOOLS IN TALUKA LARKANO (11-UNITS) (2013-14  
PROGRAMME) AT GBPS GARHI MUHABAT LANGAH  
TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement 2nd class tile roofing. (S.I.No: 22 (b) P/11).				
		626.00	@ Rs: 378/13	% Cft	Rs: 2,367.00
			(Rs: three hund: seventy eight & thirteen only)		
2	Dismantling rolled steel beams, iron rails etc. (S.I.No.42 P/13).				
		16.42	@ Rs:126/04	P.Cft	Rs: 2,076.00
			(Rs: one hund: twenty six & four only)		
3	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		1813.00	@ Rs: 1285/63	% Cft	Rs: 23,308.00
			(Rs: one two hund: eighty five & sixty three only)		
4	Removing cement or lime plaster. (S.i.No.53 P/13).				
		625.00	@ Rs:121/-	% Sft	Rs: 756.00
			(Rs: one hund: twenty one only)		
5	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		1963.00	@ Rs: 3176/25	% 0 Cft	Rs: 6,235.00
			(Rs: three thous: one hund: seventy hund: twenty five or		
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/ ).				
		833.00	@ Rs: 8694/95	% Cft	Rs: 72,429.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
7	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		1329.00	@ Rs:11948/36	% Cft	Rs: 158,794.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		517.00	@ Rs:337/-	P.Cft	Rs: 174,229.00
			(Rs: three hund: thirty seven only)		


  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No.8 (b) P/16)				
		23.080	@ Rs:5001/70	P.Cwt	Rs: 115,441.00
			(Rs: five thous: one & seventy only)		
10	Supplying and filling sand under floor and plugging in walls. (S.I.No: 29 P/25).				
		1994.00	@ Rs: 1141/25	% Cft	Rs: 22,757.00
			(Rs: one thous: one hund: forty one & twenty five only)		
11	Extra lead 3 miles				
		1994.00	@ Rs: 579/41	% Cft	Rs: 11,553.0
			(Rs: five hund: sevnty nine & forty one only)		
12	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		2506.00	@ Rs:12674/36	% Cft	Rs: 317,619.00
			(Rs: twelve thous: six hund: seventy four & thirty six on		
13	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		142.00	@ Rs:12346/65	% Cft	Rs: 17,532.00
			(Rs: twelve thous: three forty six & sixty five only)		
14	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		67.00	@ Rs:228/90	P.Rft	Rs: 15,336.00
			(Rs: two hund: twenty eight & ninty only)		
15	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		180.00	@ Rs: 240/50	P.Rft	Rs: 43,200.00
			(Rs: two hund: forty & fifty only)		
16	M.S barred windows squars bars 5/8" dia.				
		1.99	@ Rs: 3550/-	P.Sft	Rs: 7,064.00
			(Rs: three thous: five hund: fifty only)		
17	Cutting and fixing iron bars for barred windows.				
		42.00	@ Rs:28/23	P.Cwt	Rs: 1,186.00
			(Rs: twenty eight & twenty three only)		



S.No.	Description	Qty:	Rate	Unit	Amount
18	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).				
		187.00	@ Rs: 902/93	P.Sft	Rs: 168,847.00
			(Rs: nine hund: two & ninty three only)		
19	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).				
		71.00	@ Rs:180/50	P. Sft	Rs: 12,815.0
			(Rs: one hund: eighty & fifty only)		
20	Suppling of T.Girders at site of Works				
		23.10	@ Rs: 3850/-	P.Cwt	Rs: 88,935.00
			(Rs: three thous: eight hund; fifty only)		
21	Supplying of T-Iron at the site of work				
		20.00	@ Rs: 3575/-	P.Cwt	Rs: 71,500.00
			(Rs: three thous: five hund; seventy fiv e only)		
22	Errection and rolled steel beams or old rails in roof etc errection and fixing in position. (S.I.No. P/ ).				
		43.10	@ Rs: 186/34	P.Cwt	Rs: 8,031.00
			(Rs: one hund; eighty six & thirty four only)		
23	First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortor with 1/2" thick sand wiched layer of 1:6 cement mortor including 1:2 cement pointing underside of tiles complete including curing etc. (S.I.No: 1 P/32).				
		1270.00	@ Rs:11443/10	% Sft	Rs: 145,327.00
			(Rs: eleven thous: four hund: fourty three & ten only)		
24	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).				
		1270.00	@ Rs:10/70	P.Sft	Rs: 13,589.00
			(Rs: ten & seventy only)		
25	Cement Pointing 1:2 flash on floor. (S.I.No: 18 P/52).				
		1270.00	@ Rs: 939/57	% S.ft	Rs: 500.00
			(Rs: nine hund: thirty nine & fifty seven only)		

**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

26 Cement plaster (1:6) upto 12' ft: height 1/2" thick. (S.I.No: 13 (b) P.58).

4901.00 @ Rs: 2206/60 % Sft Rs: 108,145.00  
(Rs: two thous: two hund: six & sixty only)

27 Cement plaster 1:4 upto 12' ft; height 3/8" thick. (S.I.No: 11 (a) P.58).

4901.00 @ Rs: 2197/52 % S.ft Rs: 107,700.00  
(Rs: two thous: one hund: ninty seven & twenty two on

28 Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

1014.00 @ Rs: 4411/82 % Sft Rs: 44,736.00  
(Rs: four thous: four hund: eleven & eighty two only)

29 Notice board made with cement. (S.I.No: 1 P/94)

64.00 @ Rs: 58/11 P.Sft Rs: 3,719.00  
(Rs: fifty eight & eleven only)

30 Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).

1748.00 @ Rs:1287/44 % Sft Rs: 22,504.00  
(Rs: one thous: two hund: eighty seven & forty four on

31 Extra labour rate for making cemet plaster patta/band around straight are couyard oppening and around the edges of roof slabs the wight not less tham 6' with fine finishing as directed by Engineer Incharge. (S.I.NO.35 P/54)

72.00 @ Rs: 19/36 % Sft Rs: 1,394.0  
(Rs: ninteen & thirty six only)

32 Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment. (S.I.No.24P/91).

48.00 @ Rs:726/72 P. Sft Rs: 34,883.00  
(Rs: seven hund: twenty six & seventy two only)

33 White washing three coats. (S.I.No.26 ( c ) P/53).

1011.00 @ Rs:829/95 % Sft Rs: 8,391.00  
(Rs: eight hund: twenty nine & ninty five only)

34 Primary coat of chalk under distempring.

4901.00 @ Rs: 442/75 % S.ft Rs: 21,699.00  
(Rs: four hund; forty two & seventy five only)

 XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

35 Distemping three coats. (S.I.No.24 (c) P/53).

4901.00 @ Rs:1079/65 % Sft Rs: 52,914.0  
(Rs: one thos: seventy nine & sixty five only)

36 Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).

520.00 @ Rs:1498/48 % Sft Rs: 7,792.00  
(Rs: one thous: four hund; ninty eight & forty eight only)

39 Preparing surface and painting of doors and windows any type (including edges)  
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

438.00 @ Rs:2116/41 % Sft Rs: 9,270.00  
(Rs: two thous: one hund: sixteen & fourty one only)

40 Painting guard bars , gates iron bars gratings railings i/c standard barse etc:  
smiler open works.

676.00 @ Rs:1270/83 % S.ft Rs: 8,590.00  
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 1,933,163.0

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sxity only)

- 2 S/F conceled stop cock of superior quality with C.P head 1/2" dia.

2.00 @ Rs: 889/46 P.No Rs: 1,778.00  
(Rs: eight hund; eighty nine forty six only)

- 3 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.00 @ Rs: 1384/24 P.No Rs: 2,768.00  
(Rs: one thous: three hund; eighty four & twenty four or

- 4 P/f water pumping set 3 HP mono block single phase 220 volls with 11/2"x11/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of requred size fixing with units + hoolis E.S.I.No: 23P/33).

1.00 @ Rs:15254/48 P.No: Rs: 15,254.00  
(Rs: fifteen thous: two hund: fifty four & fouty eight only)

- 5 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (150 gallons)

1.00 @ Rs: 87/95 P.Gallon Rs: 13,192.00  
(Rs: eighty seven & ninty five only)

**Total:** Rs: **42,597.00**

### N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(A) 4" Dia 4.00 @ Rs: 397/77 P.No Rs: 1,591.00  
(Rs: three hund: ninty seven & seventy seven only)

(b) 3/4" Dia 40.00 @ Rs: 78/01 P.No Rs: 3,120.00  
(Rs: sevnty eight & One only)

(C) 1" Dia 5.00 @ Rs: 97/91 P.No Rs: 489.00  
(Rs: ninety seven & ninty one only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>(a) 3/4" Dia</u>	15.00	@ Rs: 103/05	P.No	Rs:	1,546.00
(Rs: one hund; three & five only)					

<u>(b ) 1" Dia</u>	2.00	@ Rs: 125/90	P.No	Rs:	251.00
(Rs: one hund; twenty five & ninty only)					

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>(b) 3/4" Dia</u>	3.00	@ Rs: 110/40	P.No	Rs:	330.00
(Rs: one hund; ten & fourteen only)					

<u>(C ) 1" Dia</u>	2.00	@ Rs: 132/43	P.No	Rs:	265.00
(Rs: one hund: thirty two & fourty three only)					

<u>(f) 4" Dia</u>	2.00	@ Rs:712/75	P.No	Rs:	1,425.00
(Rs: seven hund: tweleve & seventy five only)					

- 4 P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete.(R.A)

<u>Nyloon Plastic pi</u>	60.00	@ Rs: 77/-	P.Rft	Rs:	4,620.00
(Rs: seventy seven only)					

- 5 Providing & Fixing Hand pump Machine (R.A)

<u>Machine</u>	1.00	@ Rs: 4500/-	Each	Rs:	4,500.00
(Rs: four thous: five hund: only)					

- 6 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).

	1.00	@ Rs:14201/-	P.No:	Rs:	14,201.00
(Rs: fourteen thous: two hund: one only)					

- 7 Boring fixing 11/2" dia pressure pipe (in ordinary soil). (S.I.No: 26 (a) P/101).

	60.00	@ Rs: 53/44	P.No:	Rs:	3,206.00
--	-------	-------------	-------	-----	----------

<b>G.Total:</b>				Rs:	35,544.0
-----------------	--	--	--	-----	----------

**SCHEDULE " B "****S.No:** 12**NAME OF WORK:-****INTEGRATED REHABILITATION OF ELEMENTARY  
SCHOOLS IN TALUKA LARKANO (11-UNITS) (2013-14  
PROGRAMME) AT GGPS MEHMOOD DEERO TALUKA  
LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		10.00	@ Rs: 3327/50	% Cft	Rs: 332.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
2	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).				
		579.00	Rs 5445/-	% Cft	Rs: 31,526.00
			(Rs: five thous: four hund: forty five only)		
3	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		1739.00	@ Rs: 1285/63	% Cft	Rs: 22,357.00
			(Rs: one two hund: eighty five & sixty three only)		
4	Removing cement or lime plaster (S.I.No: 53 P/13).				
		288.00	@ Rs: 121/-	% Sft	Rs: 348.00
			(Rs: one hund: twenty one only)		
5	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		27.00	@ Rs: 3176/25	% 0 Cft	Rs: 86.00
			(Rs: three thous: one hund: seventy six & twenty five only)		
6	Cement concerte brick or stone ballast 1 1/2" to 2" gauge (c ) Ratio. 1:5:10. (s.I.No: 4 ( c ) P/14).				
		14.00	@ Rs: 8694/95	% 0 Cft	Rs: 1,217.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
(B)	<b><u>Ratio: 1:6:12.</u></b>	256.00	@ Rs: 8122/95	% Cft	Rs: 20,792.00
			(Rs: eight thous: one hund: twenty two & ninty five only)		
7	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		73.00	@ Rs:11948/36	% Cft	Rs: 8,722.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		910.00	@ Rs:337/-	P.Cft	Rs: 306,670.00
			(Rs: three hund: thirty seven only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		41.00	@ Rs:5001/70	P.Cwt	Rs: 205,069.00
			(Rs: five thous: one & seventy only)		
10	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		2054.00	@ Rs: 1141/25	% Cft	Rs: 23,441.00
			(Rs: one thous: one hund: forty one & twenty five only)		
11	Extra Lead 3.0 Miles				
		2054.00	@ Rs: 579/41	% 0.Cft	Rs: 11,901.00
			(Rs: five hund: sevnty nine & fourty one only)		
12	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1430.00	@ Rs:12674/36	% Cft	Rs: 181,243.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
13	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		10.00	@ Rs:12346/65	% Cft	Rs: 1,234.00
			(Rs: twelve thous: three forty six & sixty five only)		
14	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		17.00	@ Rs:228/90	P.Rft	Rs: 3,891.00
			(Rs: two hund: twenty eight & ninty only)		
15	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded higues and fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and planst used in making and fixing .( S.I.No: P/ ).				
		22.00	@ Rs: 240/50	P.Rft	Rs: 5,291.00
			(Rs: two hund: forty & fifty only)		
16	Supplying M-S bars 5/8" dia (Schedule of Material).				
		0.28	@ Rs: 3700/-	% S.ft	Rs: 1,036.00
			(Rs: three thous: seven hund: only)		
17	Cutting and fixing iron bars for barred windows. (S.I.No: P/ ).				
		6.00	@ Rs: 28/25	P.Cwt	Rs: 170.00
			(Rs: twenty eight & twenty five only)		
18	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		288.00	@ Rs:660/-	% Sft	Rs: 1,900.00
			(Rs: six hund: sixty only)		

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
19	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		4056.00	@ Rs:2206/60 % Sft	Rs:	89,500.00
			(Rs: two thous: two hund: six & sixty only)		
20	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		4056.00	@ Rs:2197/52 % Sft	Rs:	89,131.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		
21	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		1043.00	@ Rs:1287/44 % Sft	Rs:	13,427.00
			(Rs: one thous: two hund: eighty seven & fourty four only)		
22	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).				
		32.00	@ Rs: 902/93 P.Sft	Rs:	28,893.00
			(Rs: nine hund: two & ninty three only)		
23	S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with weight not to beless than 3.7 Lbs sq: ft: of finished grill. (S.I.No: P/ ).				
		6.00	@ Rs:194/16 P.Sft	Rs:	1,165.00
			(Rs: one hund: ninty four & sixteen only)		
24	Notice board made with cement. (S.I.No: 1 P/94).				
		64.00	@ Rs: 58/11 P.Sft	Rs:	3,719.00
			(Rs: fifty eight & eleven only)		
25	Extra labour rate for making cemet plaster patta/band around straight are couyard oppening and around the edges of roof slabs the wight not less tham 6' with fine finishing as directed by Engineer Incharge. (S.I.NO.35 P/54)				
		72.00	@ Rs: 19/36 % S.ft	Rs:	1,394.00
			(Rs: ninteen & thirty six only)		
26	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		776.00	@ Rs: 4411/82 % Sft	Rs:	34,236.00
			(Rs: four thous: four hund: eleven & eighty two only)		
(B)	<b>2"Thick</b>	1271.00	@ Rs: 3275/50 % S.ft	Rs:	41,631.00
			(Rs: three thous: two hund; seventy five & fifty only)		
27	Providing and laying Halla pattern tiles glazed 8"x8"x3/4" on floor or wall facing in required pattern of sitile specication joints in white cement and pigment over a base shape with finishing cleaning and cost lof wax polish etc complete including cutting tiles to proper profile.				
		9.00	@ Rs:34520/31 % Sft	Rs:	3,107.00
			(Rs: thirty four thous: five hund: twenty & thirty one only)		



S.No:	Description	Qty:	Rate	Unit	Amount
28	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).				
		12.00	@ Rs:726/72	P. Sft	Rs: 8,720.00
			(Rs: seven hund: twenty six & seventy two only)		
29	White washing three coats. (S.I.No.26 ( c ) P/53).				
		848.00	@ Rs:829/95	% Sft	Rs: 7,038.00
			(Rs: eight hund: twenty nine & ninty five only)		
30	Primary coat of chalk distempering. (S.I.No.23 P/57).				
		2790.00	@ Rs:442/75	% Sft	Rs: 12,352.00
			(Rs: four hund: forty two & seventy five only)		
31	Distempering three coats. (S.I.No.24 (c) P/53).				
		3064.00	@ Rs:1079/65	% Sft	Rs: 33,080.00
			(Rs: one thous: seventy nine & sixty five only)		
32	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		1565.00	@ Rs: 1948/10	% Sft	Rs: 30,487.00
			(Rs: one thous: nine hund: forty eight & ten only)		
33	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).				
		304.00	@ Rs:2116/41	% Sft	Rs: 6,433.00
			(Rs: two thous: one hund: sixteen & forty one only)		
34	Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.				
		24.00	@ Rs:1270/83	% S.ft	Rs: 305.00
			(Rs: one thous: two hund: seventy & eighty three only)		
G.Total:					Rs: 1,231,844.00

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sixty only)

- 2 Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed

1.00 @ Rs: 2533/47 P.No: Rs: 2,533.00  
(Rs: four thous: five hund; thirty three & forty seven only)

- 3 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.

3.00 @ Rs: 447/15 P.No: Rs: 1,341.00  
(Rs: four hund: forty seven & fifteen only)

- 4 S/F conceled stop cock of superior quality with C.P head 1/2" dia.

3.00 @ Rs: 889/46 P.No: Rs: 2,668.00  
(Rs: eight hund; eighty nine forty six only)

- 5 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.00 @ Rs: 1384/24 P.No: Rs: 2,768.00  
(Rs: one thous: three hund; eighty four & twenty four only)

- 6 S/F Swan type piller cock of superior quality etc:

1.00 @ Rs: 877/80 P.Gallan Rs: 878.00  
(Rs: eight hund; seventy seven & eighty only)

- 7 P/f water pumping set 3 HP unonablock single phase 220 volls with 1 1/2"x1 1/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of requred size fixing with units + hoolls E.S.I.No: 23P/33).

1.00 @ Rs:15254/48 P.No: Rs: 15,254.00  
(Rs: fifteen thous: two hund: fifty four & fouty eight only)

- 8 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (150 gallons).

1.00 @ Rs: 87/95 P.Gallan Rs: 13,193.00  
(Rs: eighty seven & ninty five only)



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 9 providing chambers (15"X19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 block set-on 1:6 cement mortar 6" thick C.C.1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) etc fixed in cement concrete 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).

1.00	@ Rs: 5913/22	Each	Rs:	5,913.00
------	---------------	------	-----	----------

(Rs: five thous: nine hund; thirteen & twenty two only)

<b>G.Total:</b>	<b>Rs:</b>	<b>54,153.00</b>
-----------------	------------	------------------

#### N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

<u>(a) 4" Dia</u>	40.00	@ Rs: 397/77	P.No	Rs:	15,910.00
-------------------	-------	--------------	------	-----	-----------

(Rs: three hund: ninty seven & seventy seven only)

<u>(b) 1" Dia</u>	20.00	@ Rs: 97/91	P.No	Rs:	1,958.00
-------------------	-------	-------------	------	-----	----------

(Rs: ninety seven & ninty one only)

<u>(c) 3/4" Dia</u>	50.00	@ Rs: 78/01	P.No	Rs:	3,900.00
---------------------	-------	-------------	------	-----	----------

(Rs: sevnty eight & One only)

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>(a) 4" Dia</u>	5.00	@ Rs: 425/45	P.No	Rs:	2,127.00
-------------------	------	--------------	------	-----	----------

(Rs: four hund: twenty five & fourty five only)

<u>(b) 1" Dia</u>	5.00	@ Rs: 125/90	P.No	Rs:	629.00
-------------------	------	--------------	------	-----	--------

(Rs: one hund; twenty five & ninty only)

<u>(c) 3/4" Dia</u>	10.00	@ Rs: 103/05	P.No	Rs:	1,030.00
---------------------	-------	--------------	------	-----	----------

(Rs: one hund; three & five only)

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>(a) 4" Dia</u>	6.00	@ Rs:712/75	P.No	Rs:	4,277.00
-------------------	------	-------------	------	-----	----------

(Rs: seven hund: tweleve & seventy five only)

<u>(b) 1" Dia</u>	10.00	@ Rs:132/43	P.No	Rs:	1,324.00
-------------------	-------	-------------	------	-----	----------

(Rs: one hund: thirty two & fourty three only)

<u>(c) 3/4" Dia</u>	8.00	@ Rs: 110/40	P.No	Rs:	883.00
---------------------	------	--------------	------	-----	--------

(Rs: one hund: ten & fourty only)

**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

<u>3/4" Dia</u>	10.00	@ Rs:98/15	P.Rft	Rs:	9,815.00
(Rs: ninty eight & fifteen only)					

- 5 P/F UNION of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>3/4" Dia</u>	2.00	@ Rs: 312/81	P.Rft	Rs:	626.00
(Rs: three hund; tweleve & eighty one only)					

G.Total:	Rs:	42,479.00
----------	-----	-----------

  
XEN

## SCHEDULE-B

**Name of work:-** Constuction / Reconstruction of Dangerous of Primary Schools  
Taluka Dokri (8-Units ) (2015-16 Prog ) At : GBPS Babul Jarwar  
Taluka Dokri

S.n	Discription	Qnty	Rate	Unit Rs	Amount
1	Dismantling R.C.C Work 1:2:4	767.0	@Rs: 5445.0	%Cft Rs:	41763 (Rs: Five thousand Four Hundred Fourty Five on
2	Dismantling Pacca brick work in cement mortor ( s.no (a) P/10)	1154.0	@Rs: 1285.63	%Cft Rs:	14836 (Rs: Twolive thousand Eighty Five & P.S Sixty Thr
3	Excavation in foundation of building bridges and other structure member with excavate chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	35.00	@ Rs: 3176.25	%0 Cft Rs:	111 (Three Thousand One Hund:Sevnty Six & P.S Twi
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) I	12.0	@Rs: 8694.95	% Cft Rs:	1043 ( Eight Thousand Six Hund:Ninty Four & P.S Ninty
5	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C	731.0	@ Rs: 11948.36	% S.ft Rs:	87343 ( Eleven Thousand Nine Hund: Fourty Eight & F
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	332.0	@Rs: 337.0	P.Cft Rs:	111884 ( Three Hundred Thirty Seven only)
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and layin i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	14.821	@ Rs: 5001.70	P.CWt Rs:	74130 (Five Thousand One &P.S Sevnty ).
8	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S	854.0	@Rs: 12674.36	% Cft Rs:	108239 (Twlove thousand Six Hundred Seventy Four & 1
9	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio	900.0	@Rs: 12346.65	% Cft Rs:	111120 (Tolive Thousand Three Hundred Fourty Six & P.
10	Supplying Girders at site of work(Sch: of Material)	22.10	@ Rs: 3850.0	P.Cwt Rs:	85085 (Three Thousand Eight Hundred Fifty only)
11	Supplying T-iron at site of work (Sch: of Material).	18.92	@ Rs: 3375.0	P.Cwt Rs:	63855 (Three Thousand Three Hundred Seventy Five on
12	First class tiles roofing consisting of 4" earth and 1" plaster wilth Gobri leeping over 1/1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" mortor with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)	1134.00	@ Rs: 11443.10	%Sft Rs:	129765 (Rs:Eleven thousand Four Hundred Fourty Three

  
**XEN**

S.N	Discription	Qty	Rate	Unit	Rs	Amount
13	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	3921.0	@Rs; 2206.60	% Sft	Rs:	86521 ( Two hundred Three Hund: Fifty Six & P.S Sever
14	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)	3921.0	@ Rs: 2197.52	%S.ft	Rs:	86165 ( Two Twousand One Hund: Ninty Seven & P.S Fil
15	Notice board made with cement.	64.0	@Rs; 58.11	P.Sft	Rs:	3719 ( Fifty Eight Eleven rupes only)
16	Cement pointing and stricking of joints on walls ratio. 1: 2 ( S.I No.19 (a) P/53)	1574.0	@ Rs: 1287.44	%Cft	Rs:	20264 ( Twolive Thousand Eighty Seven & P.S Fourty Fo
17	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c panelled and glazed (b) 1-3/4thicks.	95.0	@ Rs: 902.93	P.Sft	Rs:	85778 ( Nine Hundraed Two P.S Ninty Three only)
18	S/F iron steel grill 1/4"*3/4" size flate iron of approved made shade in 3 white weight t lbs:/Sq:/Ft: of finished grill.	235.0	@ Rs: 180.50	%C.ft	Rs:	42,418 (Rs:One Hndrad Eighty & P.S Fifty )
19	S/F sand floor and plugging into walls (S.I.No 29 P/31).	3465.0	@Rs: 1141.25	%Cft	Rs:	39544 (Rs:One Thousand One Hund: Fourty One & P.S T
20	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenl:	1002.0	@ Rs: 4411.82	% S.ft	Rs:	44206 (Rs: Four Thousand Four Hundred Eleven & P.S Ei
21	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" squar	48.0	@ Rs: 726.72	%Sft	Rs:	34,883 (Rs: Seven Hundred Twenty Six & P.S Seventy Tw
22	White wash three coats (S.I.No 26 ( c ) 59).	948.0	@Rs: 829.95	% Sft	Rs:	7868 (Rs: Eight hundred twenty nine rupes & P.S Nine f
23	Distempring three coats, (S.I.No 24 (b) P/59)	4963.0	@ Rs: 1079.65	% Sft	Rs:	53583 (Rs: One Thousand Seventy Nine & P.S Sixty Five
24	Painting doors & Window any type.	374.0	@ Rs: 2116.41	%Cft	Rs:	7915 (Rs:Two Thousand one Hund: Sixteen & P.S Fourt
25	Preparing surface painting guards bars gates iron grating railling i/c standards brass et (S.I.No 4 d P/76 ii)	96.0	@Rs: 1270.83	%Cft	Rs:	1220 (Rs: One thousand two hundred rupes only)

Total	1343259
-------	---------

XEN

**SCHEDULE-B**

**Name of work:-** Constuction / Reconstruction of Dangerous of Primary Schools  
Taluka Dokri (8-Units ) (2015-16 Prog ) At : GBPS Tatri  
Taluka Dokri

S.n	Discription	Qnty	Rate	Unit	Rs	Amount
1	Dismantling R.C.C Work 1:2:4	700.0	@Rs: 5445.0	%Cft	Rs:	38115 (Rs: Five thousand Four Hundred Fourty Five on
2	Dismantling Pacca brick work in cement mortar ( s.no (a) P/10)	1100.0	@Rs: 1285.63	%Cft	Rs:	14142 (Rs: Twolve thousand Eighty Five & P.S Sixty Thr
3	Excavation in foundation of building bridges and other structure member with excavate chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	35.00	@ Rs: 3176.25	%0 Cft	Rs:	111 (Three Thousand One Hund:Seventy Six & P.S Two
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) I	12.0	@Rs: 8694.95	% Cft	Rs:	1043 ( Eight Thousand Six Hund:Ninty Four & P.S Ninty
5	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 ( (	700.0	@ Rs: 11948.36	% S.ft	Rs:	83639 ( Eleven Thousand Nine Hund: Fourty Eight & F
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a) P/18)	332.0	@Rs: 337.0	P.Cft	Rs:	111884 ( Three Hundred Thirty Seven only)
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and layin i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	14.821	@ Rs: 5001.70	P.CWt	Rs:	74130 (Five Thousand One &P.S Seventy ).
8	Pacca brick work in Ground floor i/c stricking of joints cement sand mortar Ratio 1:6 (S	800.0	@Rs: 12674.36	% Cft	Rs:	101395 (Twlove thousand Six Hundred Seventy Four & 1
9	Pacca brick work in other than building i/c stricking of joints cement sand mortar Ratio	800.0	@Rs: 12346.65	% Cft	Rs:	98773 (Tolive Thousand Three Hundred Fourty Six & P.
10	Supplying Girders at site of work(Sch: of Material)	22.10	@ Rs: 3850.0	P.Cwt	Rs:	85085 (Three Thousand Eight Hundred Fifty only)
11	Supplying T-iron at site of work (Sch: of Material).	18.92	@ Rs: 3375.0	P.Cwt	Rs:	63855 (Three Thousand Three Hundred Seventy Five on

**XEN**

S.n	Discription	Qty	Rate	Unit	Rs	Amount
12	First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leeping over 1/1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" mortor with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)	1100.00	@ Rs: 11443.10	%Sft	Rs:	125874 (Rs:Eleven thousand Four Hundred Fourty Three
13	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	3500.0	@Rs; 2206.60	% Sft	Rs:	77231 ( Two hundred Three Hund: Fifty Six & P.S Sever
14	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)	3500.0	@ Rs: 2197.52	%S.ft	Rs:	76913 ( Two Twousand One Hund: Ninty Seven & P.S Fil
15	Notice board made with cement.	64.0	@Rs; 58.11	P.Sft	Rs:	3719 ( Fifty Eight Eleven rupes only)
16	Cement pointing and stricking of joints on walls ratio. 1: 2 ( S.I No.19 (a) P/53)	1500.0	@ Rs: 1287.44	%Cft	Rs:	19312 ( Twolive Thousand Eighty Seven & P.S Fourty Fo
17	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c panelled and glazed (b) 1-3/4thicks.	95.0	@ Rs: 902.93	P.Sft	Rs:	85778 ( Nine Hundraed Two P.S Ninty Three only)
18	S/F iron steel grill 1/4"*3/4" size flate iron of approved made shade in 3 white weight t lbs:/Sq:/Ft: of finished grill.	235.0	@ Rs: 180.50	%C.ft	Rs:	42,418 (Rs:One Hndrad Eighty & P.S Fifty )
19	S/F sand floor and plugging into walls (S.I.No 29 P/31).	3500.0	@Rs: 1141.25	%Cft	Rs:	39944 (Rs:One Thousand One Hund: Fourty One & P.S T
20	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenll	1050.0	@ Rs: 4411.82	% S.ft	Rs:	46324 (Rs: Four Thousand Four Hundred Eleven & P.S Ei
21	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" squar	48.0	@ Rs: 726.72	%Sft	Rs:	34,883 (Rs: Seven Hundred Twenty Six & P.S Seventy Tw
22	White wash three coats (S.I.No 26 ( c ) 59).	948.0	@Rs: 829.95	% Sft	Rs:	7868 (Rs: Eight hundred twenty nine rupes & P.S Nine f
23	Distempring three coats, (S.I.No 24 (b) P/59)	4963.0	@ Rs: 1079.65	% Sft	Rs:	53583 (Rs: One Thousand Seventy Nine & P.S Sixty Five
24	Painting doors & Window any type.	374.0	@ Rs: 2116.41	%Cft	Rs:	7915 (Rs:Two Thousand one Hund: Sixteen & P.S Fourt

*Handwritten signature*  
**XEN**



S.n	Discription	Qty	Rate	Unit Rs	Amount
25	Preparing surface painting guards bars gates iron grating railling i/c standards brass et (S.I.No 4 d P/76 ii)	96.0	@Rs: 1270.83	%Cft Rs: 1220	
			(Rs: One thousand two hundred rupes only)		

Total	1295154
-------	---------

  
XEN

# SCHEDULE "B"

35

Name of Work:- Integrated Rehabilitation of Elemenary Schools in Taluka Bakrani & Dokri  
(14-Units) (2013-14 Prog) At ; GGPS Gerrelow Taluka Bakrani

S.N	Description	Qnty:	Rate		Amount
-----	-------------	-------	------	--	--------

- 1 Removing cement or lime plaster. (S.I.No 53 P/14)  
 = 507  
 @ Rs: 121.00 %SFT Rs: 613  
 ( One hundred & twenty rup: only)
- 2 Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).  
 = 2,012  
 @ Rs: 3176.25 %0 CFT Rs: 6,391  
 (Thirty one Hundred seventy six rup: & twenty five paisa only)
- 3 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).  
 = 734  
 @ Rs: 8694.95 % CFT Rs: 63,821  
 (Eighty six hund: ninty four rup: & ninty five paisa only)
- 4 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) 23).  
 = 1,465  
 @ Rs: 11948.36 % CFT Rs: 175,043  
 (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)
- 5 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)  
 = 272  
 @ Rs: 337.00 P.CFT Rs: 91,664  
 (Three hundred Thirty seven rup: only)
- 6 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)  
 = 12,143  
 @ Rs: 5001.70 P.CWT Rs: 60,736  
 ( Five thousand one rup: & seventy paisa only)
- 7 Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P).  
 = 900  
 @ Rs: 12346.65 %SFT Rs: 111,120  
 (Twelve thousand thiree hund: forty six rup: & sixty five paisa only)
- 8 Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/24)  
 = 339  
 @ Rs: 12674.36 %SFT Rs: 42,966  
 (Twelve thousand six hundred seventy four rup: & thity six paisa only)
- 9 S/F sand floor and plugging into walls (S.I.No 29 P/31).  
 = 2,363  
 @ Rs: 1141.25 %SFT Rs: 26,968  
 (Eleven hundred forty one rupees & twenty five paisa only)
- 10 Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)  
 = 2,570  
 @ Rs: 2206.60 %SFT Rs: 56,710

N	Description	Qty:	Rate		Amount
13	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)			=	11
		@ Rs: 14429.25	%SFT	Rs:	1,587
	(Fourteen thousand four hundred twenty nine rup: & twenty paisa only)				
14	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ratio 3" thick. (S.I No:16 (C) P/46)			=	805
		@ Rs: 4411.82	%SFT	Rs:	35,515
	(Forty four hundred eleven rup: & eighty two paisa only)				
(B)	Ratio 2" thick,			=	111
		@ Rs: 3275.50	%SFT	Rs:	3,636
	(Thirty Two hundred Seventy Five rup: & Fifty paisa only)				
15	P/L Hala pattern tiles glazed 4"x4 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cement and pigment desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile. (S.I No: 62 P/53)			=	127
		@ Rs: 34520.31	%CFT	Rs:	43,841
	(Thirty four thousand five hundred twenty rupees & thirty one paisa only)				
16	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)			=	35
		@ Rs: 902.93	P.CFT	Rs:	31,603
	(Nine hund: two rup: & ninty three paisa only)				
17	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement sand mortar 3/4" i/c finishing complete (Flooring and Facing ) (S.I.No 69 P/55).			=	50
		@ Rs: 21021.11	%CFT	Rs:	10,511
	(Twenty one thousands twenty one rupes Eleven P.S only)				
18	White wash three coats.			=	50
		@ Rs: 829.95	%CFT	Rs:	415
	(Eight hundred twenty nine rup: & ninty five paisa only)				
19	Primary coat of chalk under distempring (S.I No: 23 P 59)			=	360
		@ Rs: 442.75	%CFT	Rs:	1,594
	(Four hundred forty two rupees & seventy five paisa only)				
20	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approved make New surface. (S.I.No 39 (a) P/62).			=	5,880
		@ Rs: 1948.10	%CFT	Rs:	114,548
	Twenty on hundred sixteen rupees & forty one paisa only)				
21	Distempering three coats (S.I No: 24( B) P 59)			=	360
		@ Rs: 1079.65	% Sft	Rs:	3,758
	(One thousand Seventy nine rup: & sixty five paisa only)				
22	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and s bars 4" centre to cement.			=	360

N	Description	Qty:	Rate		Amount
---	-------------	------	------	--	--------

23 Painting doors & window any type, (S.I.No 05 P/ 76)

= 70

@Rs: 2116.41 %Cft Rs; 1,481

( Twenty one hundred sixteen rup & forty one paisa only)

24 S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with not to be less than 3.7 Lbs sq: ft: of finished grill.

= 70

@Rs: 194.16 %Cft Rs; 15,165

( One hundre ninty four rupees & sixteen paisa only)

Total Rs: 1,020,466

  
XEN

# SCHEDULE "B"

Name of Work:- Integrated Rehabilitation of Elementary Schools Taluka Dokri & Bakrani  
(14-Units)(2013-14 Prog ) At : GBPS Umar Bhayo Taluka Bakrani

36

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
1	Dismantling R.c.c work.			=	1362.00	Cft
	@Rs: 5445.00	% Cft			Rs: 74161.00	
	( Five thousands Four hundred fourty five only)					
2	Dismantlin C.C plain 1:2:4. (S.I.No 19 ( c ) P/11).			=	121.00	CFT
	@Rs: 3327.50	% Cft			Rs: 4026.00	
	( Three thousands three hundred seventy seven only)					
3	Removing cementor lime Plaster 1:6. (S.I.No: 53 P 13 ).			=	805.00	Sft
	@Rs: 121.00	%			Rs: 974.00	
	( One hundred twenty one only)					
4	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 1p1).			=	560.00	CFT
	@Rs: 3176.25	%0 Cft			Rs: 1779.00	
	(Thirty one Hundred seventy six rup: & twenty five paisa only)					
5	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P- 14).			=	301.00	Cft
	@Rs: 8694.95	% Cft			Rs: 26171.80	
	(Eighty six hund: ninty four rup: & ninty five paisa only)					
6	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) P- 20.)			=	2197.00	Sft
	@Rs: 11948.36	% S.ft			Rs: 262505.47	
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)					
7	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/16)			=	199.00	Pcft
	@Rs: 337.00	P.CFT			Rs: 67063.00	
	(Three hundred Thirty seven rup: only)					
8	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 8 (b) P/16)			=	8.884	Pcwt
	@Rs: 5001.70	P.CWT			Rs: 44435.10	
	( Five thousand one rup: & seventy paisa only)					
9	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P/20)			=	225.00	CFT
	@Rs: 12674.36	%CFT			Rs: 28517.31	
	(Twelve thousand six hundred seventy four rup: & thity six paisa only)					
10	Supplying filling Sand under floor plugging into walls, (S.I.No 29 P/ 25).			=	322.00	Cft
	@Rs: 1141.25	%Sft			Rs: 3675.00	
	(Eleven hundred forty one rupees & twenty five paisa only)					
11	Supplying Girders at site of work (Sch: of Material).			=	16.107	Cft
	@Rs: 3850.00	P.CWT			Rs: 62012.00	
	(Thirty Eight Hundred & Fifty Rupees only)					

XEN

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
------	-------------	----------	------	------	----------	--------

12 Supplying T-iron at site of work (Sch: of Material).

=

19.008 Cft

@Rs: 3575.00

P.CWt

Rs: 67954.00

(Thirty Five Hundred & Seventy five Rupees only)

13 Ist class tilesroofing Consisting of 4" earth and 1" plaster with Gobri leeping over 1/4" thick cement plaster 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in 1:6 cen mortor with 1/4" thick t

=

1100.30 SFT

@Rs: 11443.10

%SFT

Rs: 125874.00

(Eleven thousand four hund: forty three rup: & ten paisa only)

14 Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 7 ( E ) P/

=

375.00 Cft

@Rs: 12346.65

%Cft

Rs: 46299.94

(Twelve thousand three hund: forty six rup: & sixty five paisa only)

15 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.

=

79.00 SFT

@Rs: 902.93

P.SFT

Rs: 71331.00

(Nine hund: two rup: & ninty three paisa only)

16 Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13(b) P/57)

=

3646.00 SFT

@Rs: 2206.60

%SFT

Rs: 80453.00

(Twenty tow hund: six rup: & sixty paisa only)

17 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 51)

=

3646.00 SFT

@Rs: 2197.52

%CFT

Rs: 80122.00

(Twenty one hund: ninty seven rup: & fifty two paisa only)

18 Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.11(a) P/51)

=

262.00 CFT

@Rs: 1287.44

%Cft

Rs: 3373.09

(Twelve hundred eighty seven rupees & forty for paisa only)

19 S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete wi not to beless than 3.7 Lbs sq: ft: of finished grill.

=

126.00

@Rs: 194.16

P.SFT

Rs: 24464.16

( One hundre ninty four rupees & sixteen paisa only)

20 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick. (S.I No:16 ( C ) P/41)

=

675.00 Cft

@Rs: 4411.82

%Cft

Rs: 29780.00

( Forry four hundred eleven rup: & eighty two paisa only)

(b) P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2" thick. (S.I No:16 ( C ) P/41)

=

721.00 CFT

@Rs: 3275.50

%Cft

Rs: 23616.36

(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

21 White wash two coats.

=

730.00 Cft

@Rs: 829.95

%Cft

Rs: 6059.00

(Eight hundred twenty nine rup: & ninty five paisa only)

  
XEN

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
------	-------------	----------	------	------	----------	--------

22 Primary coat of chalk under distempring ( S.I No: 23 P 59)

= 7215.00  
Rs: 31944.00

@Rs: 442.75 %Cft

(Four hundred forty two rupees & seventy five paisa only)

23 Distempering three coats ( S.I No: 24( B ) P 53)

= 7215.00 Cft  
Rs: 77897.00

@Rs: 1079.65 %Cft

(One thousand Seventy nine rup: & sixty five paisa only)

24 Painting doors & window any type, (S.I.No 05 P/ 76)

= 374.00 Cft  
Rs: 7915.00

@Rs: 2116.41 %Cft

( Twenty one hundred sixteen rup & forty one paisa only)

25 Preparing surface painting guards bars gates iron grating railling i/c standards brass etc similar open work.  
(S.I.No 4 H d P/76)

= 96.00 Cft

@Rs: 1270.83 %Cft Rs: 1220.00

(Twelve Hundred seventy rupees & eithy three paisa only)

**Total Rs: 1253622**

*Handwritten signature*  
**XEN**

**SCHEDULE " B "****S.No:** 37**NAME OF WORK:-****RECONSTRUCTION OF DANGEROUS PRIMARY SCHOOLS  
BUILDINGS OF TALUKA & DISTRICT LARKANO (10-UNITS)  
(2013-14 PROGRAMME) AT GBPS ALI MURAD JATOI TALUKA  
LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).	527.00	Rs 5445/-	% Cft	Rs: 28,895.00
					(Rs: five thous: four hund: forty five only)
2	Removing door with chowkats. (S.I.No.33 (a) P/12).	2.00	@ Rs:142/18	P.No	Rs: 284.00
					(Rs: one hund: fourty two & eighteen only)
3	Remong windows and sky light with chowkats. (S.I.No.33 (b) P/12).	6.00	@ Rs:102/85	P.No	Rs: 617.00
					(Rs: one hund: two & eighty five only)
4	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).	1735.00	@ Rs: 1285/63	% Cft	Rs: 22,305.00
					(Rs: one two hund: eighty five & sixty three only)
5	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	54.00	@ Rs: 3176/25	% 0 Cft	Rs: 171.00
					(Rs: three thous: one hund: seventy six & twenty five only)
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	18.00	@ Rs: 8694/95	% Cft	Rs: 1,565.00
					(Rs: eight thous: six hund: ninty four & ninty five only)
7	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	214.00	@ Rs:11948/36	% Cft	Rs: 25,569.0
					(Rs: eleven thous: nine hund: eighty five & thirty six only)
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	333.00	@ Rs:337/-	P.Cft	Rs: 11,221.00
					(Rs: three hund: thirty seven only)


  
**XEN**



S.No:	Description	Qnty:	Rate	Unit	Amount
-------	-------------	-------	------	------	--------

- 9 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)

15.00 @ Rs:5001/70 P.Cwt Rs: 75,025.00  
(Rs: five thous: one & seventy only)

- 10 Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).

3169.00 @ Rs: 1141/25 %Cft Rs: 36,166.00  
(Rs: one thous: one hund: forty one & twenty five only)

- 11 Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge.  
(S.I.No: 38 P/37).

217.00 @ Rs:10/70 P.Sft Rs: 2,321.0  
(Rs: ten & seventy only)

- 12 Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).

306.00 @ Rs:3327/50 %Cft Rs: 10,182.00  
(Rs: three thous: three hund: twenty seven & fifty only)

- 13 Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).

1793.00 @Rs:12674/36 %Cft Rs: 227,251.00  
(Rs: tweleve thous: six hund: seventy four & thirty six only)

- 14 Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).

50.00 @ Rs:12346/65 %Cft Rs: 6,173.00  
(Rs: tweleve thous: three forty six & sixty five only)

- 15 P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welde and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairir jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P.

67.00 @ Rs:228/90 P.Rft Rs: 15,336.00  
(Rs: two hund: twenty eight & ninty only)

- 16 P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welde and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairir jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).

180.00 @ Rs: 240/50 P.Rft Rs: 43,290.00  
(Rs: two hund: forty & fifty only)

- 17 M.S barred windows squars bars 5/8" dia.

2.00 @ Rs: 3550/- P.Sft Rs: 7,100.00  
(Rs: three thous: five hund: fifty only)

  
XEN

S.No:	Description	Qnty:	Rate	Unit	Amount
18	Cutting and fixing iron bars for barred windows.				
		42.00	@ Rs:28/23	P.Cwt	Rs: 1,186.00
			(Rs: twenty eight & twenty three only)		
19	Suppling of T.Girders at site of Works				
		22.00	@ Rs: 3850/-	P.Cwt	Rs: 84,700.00
			(Rs: three thous: eight hund; fifty only)		
20	Supplying of T-Iron at the site of work				
		19.00	@ Rs: 3575/-	P.Cwt	Rs: 67,925.00
			(Rs: three thous: five hund; seventy five only)		
21	Errection and rolled steel beams or old rails in roof etc errection and fixing in position. (S.I.No. P/ ).				
		41.00	@ Rs: 186/34	P.Cwt	Rs: 7,640.00
			(Rs: one hund; eighty six & thirty four only)		
22	First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc. (S.I.No: 1 P/32).				
		1073.00	@ Rs: 11443/10	% Sft	Rs: 122,784.00
			(Rs: eleven thous: four hund: fourty three & ten only)		
23	Reinforced cement concerte spout i/c fixing in position with top and bottom khuras. (S.I.No: 27 P/18				
		4.00	@ Rs: 524/98	Each	Rs: 2,100.00
			(Rs: five hund; twenty four & ninty eight only)		
25	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		152.00	@ Rs: 902/93	P.Sft	Rs: 137,245.00
			(Rs: nine hund: two & ninty three only)		
26	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		152.00	@ Rs:660/-	% Sft	Rs: 1,003.00
			(Rs: six hund: sixty only)		
27	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		3916.00	@ Rs:2206/60	% Sft	Rs: 86,410.00
			(Rs: two thous: two hund: six & sixty only)		

**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

28 Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).

3852.00 @ Rs:2197/52 % Sft Rs: 84,648.00  
(Rs: two thous: one hund: ninty seven & twenty two only)

29 Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).

856.00 @ Rs:1287/44 % Sft Rs: 11,020.00  
(Rs: one thous: two hund: eighty seven & fourty four only)

30 Notice board made with cement. (S.I.No: 1 P/94).

64.00 @ Rs:58/11 P. Sft Rs: 3,719.00  
(Rs: fifty eight & eleven only)

31 Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

927.00 @ Rs: 4411/82 % Sft Rs: 40,897.00  
(Rs: four thous: four hund: eleven & eighty two only)

(B) 2"Thick

32.00 @ Rs: 3275/50 % S.ft Rs: 1,048.00  
(Rs: three thous: two hund; seventy five & fifty only)

32 Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).

48.00 @ Rs:726/72 P. Sft Rs: 34,883.0  
(Rs: seven hund: twenty six & seventy two only)

33 S/F in position approved grill of 3/4" x 1/4" size flat iron of approved design including painting three coats etc complete (weight not to be less than 3.7 Lbs/ sq. foot of finished grill). (S.I.No: 26 P.97).

66.00 @ Rs: 194/16 P.Sft Rs: 12,815.00  
(Rs: one hund: ninty four & sixteen only)

34 White washing three coats. (S.I.No.26 ( c ) P/53).

887.00 @ Rs:829/95 % Sft Rs: 7,361.00  
(Rs: eight hund: twenty nine & ninty five only)

35 Primary coat of chalk distempering. (S.I.No.23 P/57).

4337.00 @ Rs:442/75 % Sft Rs: 19,202.00  
(Rs: four hund; fourty tow & seventy five only)

36 Distempring three coats

4337.00 @ Rs:1079/65 % Sft Rs: 46,824.00  
(Rs: one thous: seventy nine & sixty five only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 37 Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).

2236.00 @ Rs: 1948/10 % Sft Rs: 43,560.00  
(Rs: one thous: nine hund: fourty eight & ten only)

- 38 Preparing surface and painting of doors and windows any type (including edges)  
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

374.00 @ Rs:2116/41 % Sft Rs: 4,338.00  
(Rs: two thous: one hund: sixteen & fourty one only)

- 39 Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.

955.00 @ Rs:1270/83 % S.ft Rs: 12,136.00  
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 1,346,915.0

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

# **PART-B**

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.  

2.00      @ Rs: 4802/60      P.No:      Rs:      9,605.00  
(Rs: four thous: eight hund; two & sxity only)
- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)  

1.00      @ Rs: 4928/-      P.Each      Rs:      4,928.00  
(Rs: four thous: nine hund; twenty eight only)
- 3 Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed  

1.00      @ Rs: 2533/47      P.No:      Rs:      2,533.00  
(Rs: four thous: five hund; thirty three & fourty seven only)
- 4 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.  

3.00      @ Rs: 447/15      P.No:      Rs:      1,341.00  
(Rs: four hund; fourty seven & fifteen only)
- 5 P/F 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden pleat (a) Standard pattern. (S.I.No.3 (a) P/7).  

1.00      @ Rs:2376/-      P.Each      Rs:      2,376.00  
(Rs: two thous: three hund; seventy six only)
- 6 S/F conceled stop cock of superior quality with C.P head 1/2" dia.  

3.00      @ Rs: 889/46      P.No      Rs:      2,668.00  
(Rs: eight hund; eighty nine fourty six only)
- 7 S/F long bib-cock of superior quality with C.P head 1/2" dia  

5.00      @ Rs: 1384/24      P.No      Rs:      6,921.00  
(Rs: one thous: three hund: eighty four & twenty four only)
- 8 S/F Swan type piller cock of superior quality etc:  

1.00      @ Rs: 877/80      P.Gallan      Rs:      877.00  
(Rs: eight hund; seventy seven & eighty only)
- 9 providing chambers (15"X19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 block set-on 1:6 cement mortar 6" thick C.C.1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) etc fixed in cement concerate 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).  

1.00      @ Rs: 5913/22      Each      Rs:      5,913.00  
(Rs: five thous: nine hund: thirteen & twenty two only)

**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 10 S/F fibre glass tenk of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate iron of cement concrete 1:2:7 and making and connection for inlet-outlet and over flow pipe etc complete .

125.00	@ Rs: 87/95	P.Gallon	Rs:	10,993.00
(Rs: eighty seven & ninety five only)				

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separately recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(a) 1/2" Dia	10.00	@ Rs: 66/81	P.Rft	Rs:	668.00
(Rs: sixty six & eighty one only)					

(b) 3/4" Dia	60.00	@ Rs: 78/01	P.No	Rs:	4,680.00
(Rs: sevnty eight & One only)					

(C) 1" Dia	50.00	@ Rs: 97/91	P.No	Rs:	4,895.00
(Rs: ninety seven & ninety one only)					

(d) 4" Dia	20.00	@ Rs: 397/77	P.No	Rs:	7,955.00
(Rs: three hund: ninty seven & seventy seven only)					

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

(a) 3/4" Dia	20.00	@ Rs: 103/05	P.No	Rs:	2,061.00
(Rs: one hund; three & five only)					

(b) 4" Dia	4.00	@ Rs: 425/45	P.No	Rs:	1,701.00
(Rs: four hund: twenty five & fourty five only)					

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

(a) 3/4" Dia	8.00	@ Rs: 110/40	P.No	Rs:	883.00
(Rs: one hund; ten & fourteen only)					

(f) 4" Dia	2.00	@ Rs:712/75	P.No	Rs:	1,425.00
(Rs: seven hund: twelve & seventy five only)					

- 4 P/F COUPLING / SOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

(a) 3/4" Dia	12.00	@ Rs:98/15	P.No	Rs:	1,177.00
(Rs: ninty eight & fifteen only)					

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 5 P/F UPVC P-Trap W/Elbow (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 2.00 @ Rs:818/04 P.No Rs: 1,636.00  
(Rs: eight hund: eighteen & four only)

- 6 P/F UPVC WYE (Y) (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

3.00 @ Rs:933/13 P.No Rs: 2,799.00  
(Rs: nine hund; thirty three & thirteen only)

- 7 P/F UPVC PLUG ELBOW (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 3.00 @ Rs:677/65 P.No Rs: 2,033.00  
(Rs: six hund; seventy seven & sixty five only)

- 8 P/F UPVC PLUG TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 2.00 @ Rs:847/42 P.No Rs: 1,695.00  
(Rs: eight hund; forty seven & forty two only)

- 9 P/F UPVC VENT COWEL (LOCAL) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 3.00 @ Rs:187/93 P.No Rs: 563.00  
(Rs: one hund: eighty seven & ninty three only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
10	P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete. (R.A)				
	<u>Nyloon Plastic pipe</u>	90.00	@ Rs: 77/- (Rs: seventy seven only)	P.Rft	Rs: 6,930.00
11	Providing & Fixing Hand pump Machine (R.A)				
	<u>Machine</u>	1.00	@ Rs: 4500/- (Rs: four thous: five hund: only)	Each	Rs: 4,500.00
12	Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).				
		1.00	@ Rs:14201/- (Rs: fourteen thous: two hund: one only)	P.No:	Rs: 14,201.00
G.Total:					Rs: 107,957.00

  
**XEN**



**SCHEDULE 'B'**

Name of Work:- Construction of building for existing Shelterless Primary Schools in Taluka Larkano  
(04 Units) (2015-16 Programme) at: GBPS Wazir Phulpoto ( Electric). ADP 354

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	24.00	@ Rs: 910	P.Point	Rs: 21,840.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	160	@ Rs: 171	P.Meter	Rs: 27360.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	66.00	@ Rs: 428	P.Meter	Rs: 28248.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	23.00	@ Rs: 54	P.Each	Rs: 1,242.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	16.00	@ Rs: 70	P.Each	Rs: 1,120.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72	P.Each	Rs: 576.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	5.00	@ Rs: 916	P.No	Rs: 4,580.00

Part "A" TOTAL: Rs: 88,428.0

  
**XEN**

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
------	--------------	------	--	------	------	---------

**Part "B" (Old Schedule 2004)**

- |    |  |       |       |         |          |               |
|----|--|-------|-------|---------|----------|---------------|
| 11 | Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)   | 8.00  | @ Rs: | 91      | Each     | Rs: 728.00    |
| 12 | Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)  | 8.00  | @ Rs: | 141.71  | P.Each   | Rs: 1,133.68  |
| 13 | Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)   | 1.00  | @ Rs: | 1426.34 | P.Sq:ft: | Rs: 1,426.34  |
| 14 | P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27). | 1.00  | @ Rs: | 3341    | P.Set    | Rs: 3,341.00  |
| 15 | P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)   | 16.00 | @ Rs: | 497     | P.Each   | Rs: 7,952.00  |
| 16 | P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).   | 6.00  | @ Rs: | 497     | Each     | Rs: 2,982.00  |
| 17 | Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)   | 8.00  | @ Rs: | 5500    | P.No     | Rs: 44,000.00 |

**Part "B" TOTAL: Rs: 61,563.0**

**Part "A" TOTAL: Rs: 88,428.0**

**G: TOTAL: Rs: 149,991.0**

*Handwritten signature*

**SCHEDULE " B "**

S.No: 39

NAME OF WORK:- **CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING  
ELEMENTARY SCHOOLS (7-UNITS) (2015-16 PROGRAMME)  
AT GBPS DARI MUHALLA LARKANO (2-C/R) TALUKA LARKANO**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 1 Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).

369.00 @ Rs: 3176/25 % 0 Cft Rs: 1,172.00  
(Rs: three thous: one hund: seventy six & twenty five only)

- 2 Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).

65.00 @ Rs: 8694/95 % Cft Rs: 5,652.00  
(Rs: eight thous: six hund: ninty four & ninty five only)

- 3 Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)

116.00 @ Rs:11948/36 % Cft Rs: 13,860.0  
(Rs: eleven thous: nine hund: eighty five & thirty six only)

- 4 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).

123.00 @ Rs:337/- P.Cft Rs: 41,451.0  
(Rs: three hund: thirty seven only)

**(B) F/Floor**

1127.00 @ Rs: 349/10 % Cft Rs: 393,436.00  
(Rs: three hund: forty nine & ten only)

- 5 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)

66.964 @ Rs:5001/70 P.Cwt Rs: 334,934.0  
(Rs: five thous: one & seventy only)

- 6 Extra labour for lifting of steel above first floor for every additional floor (S.I.No: 29 P/18).

60.375 @ Rs: 151/25 P.Cwt Rs: 9,132.00  
(Rs: one hund: fifty one & twenty five only)

- 7 Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).

188.00 @ Rs:12674/36 % Cft Rs: 23,828.00  
(Rs: tweleve thous: six hund: seventy four & thirty six only)

**(B) First Floor.**

175.00 @ Rs:13112/99 %Cft Rs: 126,671.00  
(Rs: thirteen thous: one hund; tweleve & ninty nine only)



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 8 P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 28 P. 92 ).

35.00	@ Rs:228/90	P.Rft	Rs:	8,012.00
-------	-------------	-------	-----	----------

(Rs: two hund: twenty eight & ninty only)

- 9 P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).

180.00	@ Rs: 240/50	P.Rft	Rs:	43,290.00
--------	--------------	-------	-----	-----------

(Rs: two hund: forty & fifty only)

- 10 M.S barred windows squars bars 5/8" dia.

1.71	@ Rs: 3550/-	P.Sft	Rs:	6,071.00
------	--------------	-------	-----	----------

(Rs: three thous: five hund: fifty only)

- 11 Cutting and fixing iron bars for barred windows.

36.00	@ Rs: 28/23	P.Cwt	Rs:	1,016.00
-------	-------------	-------	-----	----------

(Rs: twenty eight & twenty three only)

- 12 S/F in position approved grill of 3/4" x 1/4" size flat iron of approved design including painting three coarts etc complete (weight not to be less than 3.7 Lbs/ sq. foot of finished grill). (S.I.No: 26 P.97).

56.00	@ Rs: 194/16	P.Sft	Rs:	10,873.00
-------	--------------	-------	-----	-----------

(Rs: one hund: ninty four & sixteen only)

- 13 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).

152.00	@ Rs: 902/93	P.Sft	Rs:	137,245.00
--------	--------------	-------	-----	------------

(Rs: nine hud: two & ninty three only)

- 14 Cement plaster (1:6) upto 12' ft: height 1/2" thick. (S.I.No: 13 (b) P.58).

887.00	@ Rs: 2206/60	% Sft	Rs:	19,573.00
--------	---------------	-------	-----	-----------

(Rs: two thous: two hund: six & sixty only)

(B) First Floor.

3484.00	@ Rs:2308/84	%Sft	Rs:	80,440.00
---------	--------------	------	-----	-----------

(Rs: two thous: three hund; eight & eighty four only)

- 15 Cement plaster 1:4 upto 12' ft; height 3/8" thick. (S.I.No: 11 (a) P.58).

887.00	@ Rs: 2197/52	% S.ft	Rs:	19,492.00
--------	---------------	--------	-----	-----------

(Rs: two thous: one hund: ninty seven & twenty two only)

(B) First Floor.

3484.00	@ Rs:2299/76	%Sft	Rs:	80,124.00
---------	--------------	------	-----	-----------

(Rs: two thous: two hund; ninty nine & seventy six only)

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 16 Cement pointing strucking joints on walls (a) Ratio 1:2.

628.00 @ Rs: 1389/68 % S.ft Rs: 8,727.00  
(Rs: one thous: three hund: eighty nine & sixty eighty only)

- 17 Notice board made with cement. (S.I.No: 1 P/94)

64.00 @ Rs: 58/11 P.Sft Rs: 3,719.00  
(Rs: fifty eight & eleven only)

- 18 Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).

46.00 @ Rs: 14429/25 %Cft Rs: 6,637.00  
(Rs: fourteen thous: four hund: twenty nine & twenty five only)

- 19 Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).

356.00 @ Rs:27747/06 %.Sft Rs: 98,780.0  
(Rs: twenty seven thous: seven hund forty seven & six only)

- 20 Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 2" Thick.

646.00 @ Rs:3275/50 % Sft Rs: 21,160.0  
(Rs: three thous: two hund; seventy five & fifty only)

**(B) 2"Thick (FIRST FLOOR)**

1278.00 @ Rs: 3502/38 % S.ft Rs: 44,760.00  
(Rs: three thous: five hund: two & thirty eight only)

- 21 Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).

1278.00 @ Rs:1887/40 %.Sft Rs: 24,121.00  
(Rs: one thous: eight hund; eighty seven & fourteen only)

- 22 Providing and laying 12"x12"x3/4" thick Marble Tiles Floor of approved size, design and quality set in cement sand mortar 1:2 in grey cement 3/4" thick including washing and filling the joints with white cement slurry using colour pigment for matching, including levelling and curing etc, complete as per specification and as directed by the Engineer Incharge. (R.A)

112.00 @ Rs: 310/- P.Sft Rs: 34,720.00  
(Rs: three hun: ten only)

**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
23	Providing & fixing 3/8" thick marble tiles of approved quality and colour and shade size 8"x4"/6"x4" in dado skirting and facing removal / tucking of existing plaster surface etc. Over 1/2" thick base of cement mortar 1:3 setting of tiles in slurry of white cement over mortar base i/c filling the joints and washing the tiles with white cement slurry current finishing cleaning and (i) For new works. (S.I.No: 68 (i) P/48).	69.00	@ Rs: 186/04	P.Sft	Rs: 12,837.00
			(Rs: one hund: eighty six & four only)		
24	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).	64.00	@ Rs:226/02	P.Sft	Rs: 14,465.00
			(Rs: two hund; twenty six & two only)		
25	P/F deodar Almirah 9"x12" depth i/c boxing with back shalves shutters bars fittings complete (Without Box) (S.I.No: 23 P.68).	34.00	@ Rs:1748/-	P.Sft	Rs: 59,432.00
			(Rs: one thous: seven hund; fourty eight only)		
26	Primary coat of chalk under distempring.	3779.00	@ Rs: 442/75	% S.ft	Rs: 16,732.00
			(Rs: four hund; fourty tow & seventy five only)		
27	Distempring three coats	3779.00	@ Rs:1079/65	% Sft	Rs: 40,800.00
			(Rs: one thous: seventy nine & sixty five only)		
(B)	<u>Two coats.</u>				
		1301.00	@ Rs:1043/90	% Sft	Rs: 13,581.00
			(Rs: ten hund; forty three & ninty only)		
28	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	372.00	@ Rs:2116/41	% Sft	Rs: 7,873.0
			(Rs: two thous: one hund: sixteen & fourty one only)		
29	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	1620.00	@ Rs: 1948/10	% Sft	Rs: 31,559.00
			(Rs: one thous: nine hund: fourty eight & ten only)		
			G.Total:		Rs: 1,796,175.0

  
**XEN**

## SCHEDULE " B "

NAME OF WORK:-

40

**CONSTRUCTION /RE-CONSTRUCTION OF DANGEROUS  
PRIMARY SCHOOLS TALUKA LARKANO (8-UNITS) (2015-16  
PROGRAMME) AT GBLSS THARIRI CHUTTO TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		750.00	@ Rs: 1285/63 % Cft	Rs:	9,642.00
			(Rs: one two hund: eighty five & sixty three only)		
2	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		1728.00	@ Rs: 3176/25 % 0 Cft	Rs:	5,489.00
			(Rs: three thous: one hund: seventy six & twenty five only)		
3	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c ) P/ 14).				
		444.00	@ Rs: 8694/95 % Cft	Rs:	38,606.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
(B)	<b><u>Ratio: 1:6:12.</u></b>				
		570.00	@ Rs: 8122/95 % Cft	Rs:	46,300.00
			(Rs: eight thous: one hund: twenty two & ninty five only)		
4	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		1520.00	@ Rs:11948/36 % Cft	Rs:	181,615.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
5	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		332.00	@ Rs:337/- P.Cft	Rs:	111,884.00
			(Rs: three hund: thirty seven only)		
6	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		16.30	@ Rs:5001/70 P.Cwt	Rs:	81,528.00
			(Rs: five thous: one & seventy only)		
7	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		2292.00	@ Rs: 1141/25 % Cft	Rs:	26,157.00
			(Rs: one thous: one hund: forty one & twenty five only)		
8	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1966.00	@ Rs:12674/36 % Cft	Rs:	249,178.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		

S.No:	Description	Qty:	Rate	Unit	Amount
9	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).	35.00	@ Rs:228/90	P.Rft	Rs: 8,012.00
			(Rs: two hund: twenty eight & ninty only)		
10	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand repairing i/c all carriage tools and planst used in making and fixing . ( S.I.No: P/ ).	180.00	@ Rs: 240/50	P.Rft	Rs: 43,290.00
			(Rs: two hund: forty & fifty only)		
11	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).	152.00	@ Rs: 902/93	P.Sft	Rs: 137,245.00
			(Rs: nine hund: two & ninty three only)		
12	M.S barred windows squars bars 5/8" dia.	1.71	@ Rs: 3550/-	P.Sft	Rs: 6,070.00
			(Rs: three thous: five hund: fifty only)		
13	Cutting and fixing iron bars for barred windows.	36.00	@ Rs:28/23	P.Cwt	Rs: 1,016.00
			(Rs: twenty eight & twenty three only)		
14	Notice board made with cement. (S.I.No: 1 P/94).	64.00	@ Rs: 58/11	P.Sft	Rs: 3,719.00
			(Rs: fifty eight & eleven only)		
15	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	3850.00	@ Rs:2206/60	% Sft	Rs: 84,954.00
			(Rs: two thous: two hund: six & sixty only)		
16	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	3786.00	@ Rs:2197/52	% Sft	Rs: 83,198.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		
17	Extra labour rate for making cemet plaster patta/band around straight are couyard oppening and around the edges of roof slabs the wight not less tham 6' with fine finishing as directed by Engineer Incharge. (S.I.NO.35 P/54)	144.00	@ Rs: 19/36	% S.ft	Rs: 2,788.00
			(Rs: ninteen & thirty six only)		



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 18 Cement pointing striking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).

907.00	@ Rs:1287/44	% Sft	Rs:	11,677.00
(Rs: one thous: two hund: eighty seven & fourty four only)				

- 19 Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

1771.00	@ Rs: 4411/82	% Sft	Rs:	78,133.00
(Rs: four thous: four hund: eleven & eighty two only)				

- 20 Supplying of Girders at site of work. (Sch: of Material).

16.89	@ Rs:3850/-	P.Cwt	Rs:	65,026.00
(Rs: three thous: eight hund: fifty only)				

- 21 Supplying of T.Iron at site of work. (Sch: of Material).

19.08	@ Rs:3575/-	P.Cwt	Rs:	68,211.00
(Rs: three thous: five hund: seventy five only)				

- 22 Errection and rolled steel beams or old rails in roof etc errection and fixing in position. (S.I.No. P/ ).

35.97	@ Rs: 186/34	P.Cwt	Rs:	6,703.00
(Rs: one hund; eighty six & thirty four only)				

- 23 First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortor with 1/2" thick sand wiched layer of 1:6 cement mortor including 1:2 cement pointing underside of tiles complete including curing etc. (S.I.No: 1 P/32).

1102.00	@ Rs:11443/10	% Sft	Rs:	126,103.00
(Rs: eleven thous: four hund: fourty three & ten only)				

- 24 Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).

1102.00	@ Rs:10/70	P.Sft	Rs:	11,791.0
(Rs: ten & seventy only)				

- 25 Reinforced cement concerte spout i/c fixing in position with top and bottom khuras. (S.I.No: 27 P/18).

4.00	@ Rs: 524/98	Each	Rs:	2,100.00
(Rs: five hund; twenty four & ninty eight only)				

- 26 Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment. (S.I.No.24P/91).

48.00	@ Rs:726/72	P. Sft	Rs:	34,882.56
(Rs: seven hund: twenty six & seventy two only)				

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
27	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		338.00	@ Rs:12346/65 %Cft	Rs:	41,731.00
			(Rs: twelve thous: three forty six & sixty five only)		
28	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).				
		138.00	@ Rs:180/50 P. Sft	Rs:	24,909.00
			(Rs: one hund: eighty & fifty only)		
29	P/F deodar Almirah 9"x12" depth i/c boxing with back shalves shutters bars fittings complete (Without Box) (S.I.No: 23 P.68).				
		34.00	@ Rs:1748/- P.Sft	Rs:	59,432.00
			(Rs: one thous: seven hund; forty eight only)		
30	White washing three coats. (S.I.No.26 ( c ) P/53).				
		887.00	@ Rs: 829/95 %Sft	Rs:	7,362.00
			(Rs: eight hund: twenty nine & ninty five only)		
31	Primary coat of chalk distempering. (S.I.No.23 P/57).				
		2621.00	@ Rs: 442/75 %Sft	Rs:	11,604.00
			(Rs: four hund; forty tow & seventy five only)		
32	Distempering three coats. (S.I.No.24 (c) P/53).				
		2621.00	@ Rs:1079/65 %Sft	Rs:	28,298.00
			(Rs: one thous: seventy nine & sixty five only)		
33	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		1732.00	@ Rs: 1948/10 %Sft	Rs:	33,741.00
			(Rs: one thous: nine hund: forty eight & ten only)		
34	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).				
		304.00	@ Rs:2116/41 %Sft	Rs:	6,434.00
			(Rs: two thous: one hund: sixteen & forty one only)		
35	Painting guard bars , gates iron bars gratings railings i/c standard barse etc: smiler open works.				
		509.00	@ Rs:1270/83 % S.ft	Rs:	6,469.00
			(Rs: one thous: two hund: seventy & eighty three only)		
<b>G.Total:</b>				<b>Rs:</b>	<b>1,745,297.6</b>

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

**PART-B**

- 1 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond / Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete.

1.00	@ Rs:14201/-	P.No	Rs:	14,201.00
(Rs: fourteen thous: two hund: one only)				

<b>G.Total:</b>	Rs:	<b>14,201.0</b>
-----------------	-----	-----------------

  
**XEN**

## SCHEDULE " B "

41

NAME OF WORK:- CONSTRUCTION /RE-CONSTRUCTION OF DANGEROUS  
PRIMARY SCHOOLS TALUKA LARKANO (8-UNITS) (2015-16  
PROGRAMME) AT GBPS ALIABAD KORKANI TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		239.00	@ Rs: 3327/50	% Cft	Rs: 7,953.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
2	Removing cement or lime plaster. (S.i.No.53 P/13).				
		715.00	@ Rs:121/-	% Sft	Rs: 865.00
			(Rs: one hund: twenty one only)		
3	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		145.00	@ Rs: 1285/63	% Cft	Rs: 1,864.00
			(Rs: one two hund: eighty five & sixty three only)		
4	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).				
		27.00	Rs 5445/-	% Cft	Rs: 1,470.00
			(Rs: five thous: four hund: forty five only)		
5	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		339.00	@ Rs: 3176/25	% 0 Cft	Rs: 1,077.00
			(Rs: three thous: one hund: seventy six & twenty five only)		
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).				
		812.00	@ Rs: 8694/95	% Cft	Rs: 70,603.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
7	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).				
		52.00	@ Rs: 14429/25	%Cft	Rs: 7,503.00
			(Rs: fourteen thous: four hund: twenty nine & twenty five only)		
8	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		615.00	@ Rs:11948/36	% Cft	Rs: 73,482.00
			(Rs. eleven thous: nine hund: eighty five & thirty six only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		368.00	@ Rs:337/- (Rs: three hund: thirty seven only)	P.Cft	Rs: 123,679.00
10	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		16.428	@ Rs:5001/70 (Rs: five thous: one & seventy only)	P.Cwt	Rs: 82,168.00
11	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		35.00	@ Rs:228/90 (Rs: two hund: twenty eight & ninty only)	P.Rft	Rs: 8,012.00
12	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and planst used in making and fixing .( S.I.No: P/ ).				
		180.00	@ Rs: 240/50 (Rs: two hund: forty & fifty only)	P.Rft	Rs: 43,290.00
13	M.S barred windows squars bars 5/8" dia.				
		1.71	@ Rs: 3550/- (Rs: three thous: five hund: fifty only)	P.Sft	Rs: 6,070.00
14	Cutting and fixing iron bars for barred windows.				
		36.00	@ Rs:28/23 (Rs: twenty eight & twenty three only)	P.Cwt	Rs: 1,016.00
15	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		152.00	@ Rs: 902/93 (Rs: nine hund: two & ninty three only)	P.Sft	Rs: 137,245.00
16	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		17.00	@ Rs:12674/36 (Rs: twelve thous: six hund: seventy four & thirty six only)	% Cft	Rs: 2,155.00
17	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		1205.00	@ Rs:12346/65 (Rs: twelve thous: three forty six & sixty five only)	% Cft	Rs: 148,777.00

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 18 Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).

715.00	@ Rs: 660/-	% Sft	Rs:	4,719.00
	(Rs: six hund: sixty only)			

- 19 Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).

3108.00	@ Rs:2206/60	% Sft	Rs:	68,581.0
	(Rs: two thous: two hund: six & sixty only)			

- 20 Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).

3108.00	@ Rs:2197/52	% Sft	Rs:	68,293.0
	(Rs: two thous: one hund: ninty seven & twenty two only)			

- 21 Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).

1983.00	@ Rs:1287/44	% Sft	Rs:	25,530.00
	(Rs: one thous: two hund: eighty seven & fourty four only)			

- 22 Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

3400.00	@ Rs: 4411/82	% Sft	Rs:	150,002.00
	(Rs: four thous: four hund: eleven & eighty two only)			

- (B) 2"Thick

144.00	@ Rs: 3275/50	% S.ft	Rs:	4,717.00
	(Rs: three thous: two hund; seventy five & fifty only)			

- (C) 1-1/2"Thick

1315.00	@ Rs: 2548/29	% S.ft	Rs:	33,510.00
	(Rs: two thous: five hund: forty eight & twenty nine only)			

- 23 Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).

5358.00	@ Rs: 1141/25	% Cft	Rs:	61,148.00
	(Rs: one thous: one hund: forty one & twenty five only)			

- 24 Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment. (S.I.No.24P/91).

54.00	@ Rs:726/72	P. Sft	Rs:	39,243.00
	(Rs: seven hund: twenty six & seventy two only)			

- 25 Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).

52.00	@ Rs:180/50	P. Sft	Rs:	9,386.00
	(Rs: one hund: eighty & fifty only)			

- 26 Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).

1315.00	@ Rs:1887/40	% Sft	Rs:	24,819.00
	(Rs: one thous: eight hund; eighty seven & fourteen only)			

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

27 White washing three coats. (S.I.No.26 ( c ) P/53).

1198.00	@ Rs: 829/95	% Sft	Rs:	9,943.00
(Rs: eight hund: twenty nine & ninty five only)				

28 Primary coat of chalk distempering. (S.I.No.23 P/57).

4131.00	@ Rs: 442/75	% Sft	Rs:	18,290.00
(Rs: four hund; forty tow & seventy five only)				

29 Distempering three coats. (S.I.No.24 (c) P/53).

8931.00	@ Rs:1079/65	% Sft	Rs:	96,424.00
(Rs: one thous: seventy nine & sixty five only)				

30 Preparing surface and painting of doors and windows any type (including edges)  
(ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).

318.00	@ Rs:2116/41	% Sft	Rs:	6,730.00
(Rs: two thous: one hund: sixteen & forty one only)				

31 Painting guard bars , gates iron bars gratings railings i/c standard barsees etc:  
smiler open works.

96.00	@ Rs:1270/83	% S.ft	Rs:	1,220.00
(Rs: one thous: two hund: seventy & eighty three only)				

32 Painting guard bars, gates iron bars gratings, railing including standard braces (etc)  
and simiolar open work (ii) Each subsequent coat (Old Surface). (S.I.No.4(d)(ii) P/68).

194.00	@ Rs:674/60	% Sft	Rs:	1,309.0
(Rs: six hund; seventy four & sixty only)				

G.Total:	Rs:	1,341,093.0
----------	-----	-------------

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 16" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

3.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sixty only)

- 2 S/F conceled stop cock of superior quality with C.P head 1/2" dia.

3.00 @ Rs: 889/46 P.No: Rs: 1,778.00  
(Rs: eight hund; eighty nine fourty six only)

- 3 S/F long bib-cock of superior quality with C.P head 1/2" dia

3.00 @ Rs: 1384/24 P.No: Rs: 2,768.00  
(Rs: one thous: three hund; eighty four & twenty four only)

- 4 Providing fixing 22"x16" Lav: basin in white glazed earthen ware complete with and i/c cost of w.l or C.I cantianer etc:

3.00 @ Rs: 4694/80 P.No: Rs: 9,389.00  
(Rs: four thous: six hund; ninty four & eighty only)

- 5 Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed

3.00 @ Rs: 2533/47 P.No: Rs: 5,066.00  
(Rs: four thous: five hund; thirty three & fourty seven only)

- 6 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts linin joints to nyloon connections.

3.00 @ Rs: 447/15 P.No: Rs: 894.00  
(Rs: four hund: forty seven & fifteen only)

- 7 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concrete 1:2:7 and making and commocion for inlet- outlet and over flow pipe etc complete (250 gallons).

1.00 @ Rs: 21989/61 P.Gallan Rs: 21,990.00  
(Rs: twnty one thous:nine hund; eighty nine & sixty one only)

**G.Total:**

**Rs: 51,490.00**

*Handwritten signature*  
**XEN**



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

**N.S.I**

- 1 P/F UPVC pipe SCH-40 on surface by using clips/saddles ( of approved quality & material), etc. paid separately or recessed in masonry, C.C or RCC upto 60 ft height and making good with C.C i/c c uring, finishing etc complete . 3/4" dia (R.A.,Approved).

<b><u>(A) 3/ 4" Dia</u></b>	150.00	@ Rs: 78/01	P.No	Rs:	11,700.00
(Rs: seventy eight & One only)					

<b><u>(B) 1" Dia</u></b>	80.00	@ Rs: 97/91	P.Rft	Rs:	4,896.00
(Rs: ninty seven & ninty one only)					

<b><u>(C) 4" Dia</u></b>	70.00	@ Rs: 397/77	P.Rft	Rs:	27,844.00
(Rs: three hund: ninty seven & seventy seven only)					

- 2 P/F Bend/ Elbow ( 90 degree) of Sch- 40 PVC of namet or Equivalent make of approved quality and design of various sizes fixed to UPVC pipe/ fittings paid seperately using approved adhesive compound (AGM or WELDON, made USA ).

<b><u>(A) 3/4" Dia</u></b>	20.00	@ Rs: 103/05	P.Rft	Rs:	2,061.00
(Rs: one hund: three & five only)					

<b><u>(B) 1" Dia</u></b>	4.00	@ Rs: 226/-	P.Rft	Rs:	904.00
(Rs: two hund: twenty six only)					

- 3 P/F TEE of Sch-40 PVC of NAMAT or EQUIVALENT make of approved quility and design of various sizes fixed to UPVC pipe/ fitting pade seperately, using approved adhesive compound ( AGM or WELDON, made in USA ).

<b><u>3/4" Dia</u></b>	20.00	@ Rs: 110/40	P.Rft	Rs:	2,208.00
(Rs: one hund; ten & fourteen only)					

- 4 P/F COUPLING/SOCKET of Sch-40 PVC of NAMAT or Equivalent make of approved quility and design of various sizes fixed to UPVC pipe/ fitting pade seperately, using approved adhesive compound ( AGM or WELDON, made in USA ). 3/4" Dia.

<b><u>3/4" Dia</u></b>	20.00	@ Rs: 98/15	P.No	Rs:	1,963.00
(Rs: ninty eight & fifteen only)					

- 5 P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete.(R.A)

<b><u>Nyloon Plastic pij</u></b>	90.00	@ Rs: 77/-	P.Rft	Rs:	6,930.00
(Rs: seventy seven only)					

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 6 Providing & Fixing Hand pump Machine (R.A)

<u>Machine</u>	1.00	@ Rs: 4500/-	Each	Rs:	4,500.00
(Rs: four thous: five hund: only)					

- 7 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).

1.00	@ Rs: 14201/-	P.No:	Rs:	14,201.00
(Rs: fourteen thous: two hund: one only)				

G.Total:	Rs:	77,207.00
----------	-----	-----------

  
XEN

## SCHEDULE " B "

42

NAME OF WORK:-

CONSTRUCTION /RE-CONSTRUCTION OF DANGEROUS  
PRIMARY SCHOOLS TALUKA LARKANO (3-UNITS) (2015-16  
PROGRAMME) AT GBPS SHAHUL UMRANI TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).				
		286.00	Rs 5445/-	% Cft	Rs: 15,572.00
			(Rs: five thous: four hund: forty five only)		
2	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		1241.00	@ Rs: 1285/63	% Cft	Rs: 15,954.00
			(Rs: one two hund: eighty five & sixty three only)		
3	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		67.00	@ Rs: 3176/25	% 0 Cft	Rs: 212.00
			(Rs: three thous: one hund: seventy hund: twenty five only)		
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).				
		24.00	@ Rs: 8694/95	% Cft	Rs: 2,087.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
5	Removing cement or lime plaster (S.I.No: 53 P/13).				
		1098.00	@ Rs: 121/-	% Sft	Rs: 1,329.00
			(Rs: one hund: twenty one only)		
6	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		1098.00	@ Rs:660/-	% Sft	Rs: 7,247.00
			(Rs: six hund: sixty only)		
7	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		405.00	@ Rs:11948/36	% Cft	Rs: 48,489.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		301.00	@ Rs:337/-	P. Cft	Rs: 101,437.00
			(Rs: three hund: thirty seven only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No.8 (b) P/16)				
		16.12	@ Rs:5001/70	P.Cwt	Rs: 80,627.00
			(Rs: five thous: one & seventy only)		
10	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		60.00	@ Rs:12346/65	%Cft	Rs: 7,408.00
			(Rs: twelve thous: three forty six & sixty five only)		
11	Dimantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		19.00	@ Rs: 3327/50	%Cft	Rs: 632.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
12	Supplying and filling sand under floor and plugging in walls. (S.I.No: 29 P/25).				
		1152.00	@ Rs: 1141/25	%Cft	Rs: 13,147.00
			(Rs: one thous: one hund: forty one & twenty five only)		
13	Cement concerate brick or stone ballast 1/2" to 2" guage. (S.I.No: 4 (d) P/ 14).				
		161.00	@ Rs: 8122/95	%Cft	Rs: 13,078.00
			(Rs: eight thous: one hund: twenty two & ninty five only)		
14	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1391.00	@ Rs:12674/36	%Cft	Rs: 176,300.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
15	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 28 P.98 ).				
		50.00	@ Rs:228/90	P.Rft	Rs: 11,445.00
			(Rs: two hund: twenty eight & ninty only)		
16	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		90.00	@ Rs: 240/50	P.Rft	Rs: 21,645.00
			(Rs: two hund: forty & fifty only)		

*[Signature]*  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 17 Providing and laying Halla or pettern tiles glazed 8"x8"x1/4" on floor or wall facing in required pattern of sitile specification jointed in white cement and pigment over a base of 1:2 grey cement motar 3/4" thick including washing and filling joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc. complete including cutting tiles to proper profile (S.I.No: 62 P.47).

88.00 @ Rs: 34520/31 % Sft Rs: 30,378.00  
(Rs: thirty four thous: five hund: twenty & thirty one only)

- 18 First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).

111.00 @ Rs: 902/93 P.Sft Rs: 100,225.00  
(Rs: nine hund: two & ninty three only)

- 19 M.S barred windows squars bars 5/8" dia.

1000.00 @ Rs: 3550/- P.Sft Rs: 3,550.00  
(Rs: three thous: five hund: fifty only)

- 20 Cutting and fixing iron bars for barred windows.

21.00 @ Rs:28/23 P.Cwt Rs: 593.00  
(Rs: twenty eight & twenty three only)

- 21 Notice board made with cement. (S.I.No: 1 P/94)

32.00 @ Rs: 58/11 P.Sft Rs: 1,860.00  
(Rs: fifty eight & eleven only)

- 22 Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).

4626.00 @ Rs:2206/60 % Sft Rs: 102,077.00  
(Rs: two thous: two hund: six & sixty only)

- 23 Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).

4594.00 @ Rs:2197/52 % Sft Rs: 100,954.00  
(Rs: two thous: one hund: ninty seven & twenty two only)

- 24 Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).

965.00 @ Rs:1287/44 % Sft Rs: 12,424.0  
(Rs: one thous: two hund: eighty seven & forty four only)

- 25 Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

515.00 @ Rs: 4411/82 % Sft Rs: 22,721.00  
(Rs: four thous: four hund: eleven & eighty two only)

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

(B) 2"Thick

- |  |  |        |  |     |          |
|--|--|--------|--|-----|----------|
|  |  | 107.00 | @ Rs: 3275/50 % S.ft                                   | Rs: | 3,505.00 |
|  |  |        | (Rs: three thous: two hund; seventy five & fifty only) |     |          |
- 26 Suppling of T.Girders at site of Works
- |  |  |       |   |     |           |
|--|--|-------|---|-----|-----------|
|  |  | 10.76 | @ Rs: 3850/- P.Cwt                        | Rs: | 41,426.00 |
|  |  |       | (Rs: three thous: eight hund; fifty only) |     |           |
- 27 Supplying of T-Iron at the site of work
- |  |  |      |   |     |           |
|--|--|------|---|-----|-----------|
|  |  | 9.78 | @ Rs: 3575/- P.Cwt                              | Rs: | 34,965.00 |
|  |  |      | (Rs: three thous: five hund; seventy five only) |     |           |
- 28 Errection and rolled steel beams or old rails in roof etc errection and fixing in position.  
(S.I.No. P/ ).
- |  |  |       |   |     |          |
|--|--|-------|---|-----|----------|
|  |  | 20.54 | @ Rs: 186/34 P.Cwt                            | Rs: | 3,827.00 |
|  |  |       | (Rs: one hund; eighty six & thirty four only) |     |          |
- 29 First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri  
leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman  
coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in  
1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar  
including 1:2 cement pointing underside of tiles complete including curing  
etc. (S.I.No: 1 P/32).
- |  |  |         |  |     |           |
|--|--|---------|--|-----|-----------|
|  |  | 565.000 | @ Rs: 11443/10 % Sft                                   | Rs: | 64,654.00 |
|  |  |         | (Rs: eleven thous: four hund: fourty three & ten only) |     |           |
- 30 Providing and laying single per layer of polythene sheet 0.13 mm thick for  
water proffing as per specification and instruction of Engineer incharge.  
(S.I.No: 38 P/37).
- |  |  |        |                          |     |         |
|--|--|--------|--------------------------|-----|---------|
|  |  | 565.00 | @ Rs:10/70 P.Sft         | Rs: | 6,045.0 |
|  |  |        | (Rs: ten & seventy only) |     |         |
- 31 Reinforced cement concerte spout i/c fixing in position with top and bottom khuras. (S.I.No: 27 P/18).
- |  |  |      |   |     |          |
|--|--|------|---|-----|----------|
|  |  | 3.00 | @ Rs: 524/98 Each                               | Rs: | 1,575.00 |
|  |  |      | (Rs: five hund; twenty four & ninty eight only) |     |          |
- 32 S/F in position approved grill of 3/4" x 1/4" size flat iron of approved design inluding painting three  
coarts etc complete (weight not to be less than 3.7 Lbs/ sq. foot of finished grill). (S.I.No: 26 P.97).
- |  |  |      |   |     |          |
|--|--|------|---|-----|----------|
|  |  | 6.00 | @ Rs: 194/16 P.Sft                        | Rs: | 1,165.00 |
|  |  |      | (Rs: one hund: ninty four & sixteen only) |     |          |
- 33 Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame  
2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment.  
(S.I.No.24P/91).
- |  |  |       |   |     |          |
|--|--|-------|---|-----|----------|
|  |  | 48.00 | @ Rs:726/72 P. Sft                              | Rs: | 34,882.0 |
|  |  |       | (Rs: seven hund: twenty six & seventy two only) |     |          |

S.No:	Description	Qty:	Rate	Unit	Amount
34	White washing three coats. (S.I.No.26 ( c ) P/53).				
		480.00	@ Rs:829/95	% Sft	Rs: 3,984.00
			(Rs: eight hund: twenty nine & ninty five only)		
35	Primary coat of chalk under distempring.				
		1965.00	@ Rs: 442/75	% S.ft	Rs: 8,700.00
			(Rs: four hund; fourty two & seventy five only)		
36	Distempering three coats. (S.I.No.24 (c) P/53).				
		1965.00	@ Rs:1079/65	% Sft	Rs: 21,215.0
			(Rs: one thos: seventy nine & sixty five only)		
37	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		965.00	@ Rs: 1948/10	% Sft	Rs: 18,799.0
			(Rs: one thous: nine hund: fourty eight & ten only)		
38	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).				
		222.00	@ Rs:2116/41	% Sft	Rs: 4,698.0
			(Rs: two thous: one hund: sixteen & fourty one only)		
39	Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.				
		439.00	@ Rs:1270/83	% S.ft	Rs: 5,579.00
			(Rs: one thous: two hund: seventy & eighty three only)		
<b>G.Total:</b>					<b>Rs: 1,146,410.00</b>

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sxity only)

- 2 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).

1.00 @ Rs:14201/- P.No: Rs: 14,201.00  
(Rs: fourteen thous: two hund: one only)

- 3 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

4" Dia 10.00 @ Rs: 397/77 P.No Rs: 3,977.00  
(Rs: three hund: ninty seven & seventy seven only)

- 4 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

(a) Filter 10.00 @ Rs: 76/05 P.Rft Rs: 760.00  
(Rs: seventy six & five only)

(b) G.I Pipe 80.00 @ Rs: 77/- P.Rft Rs: 6,160.00  
(Rs: seventy seven only)

( C ) Machine 1.00 @ Rs: 4500/- Each Rs: 4,500.00  
(Rs: four thous: five hund: only)

**G.Total:** Rs: 39,203.00

  
**XEN**



## SCHEDULE " B "

43

NAME OF WORK:-

**INTEGRATED REHABILITATION OF PRIMARY SCHOOLS AND  
PROVISION OF MISSING FACILITIES TALUKA LARKANO  
(14-UNITS) (2015-16 PROGRAMME) AT GBPS KHUHRA  
TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Remoning cement or lime plaster. (S.I.No.53 P/13).				
		1667.00	@ Rs:121/-	% Sft	Rs: 2,017.00
			(Rs: one hund: twenty one only)		
2	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		247.00	@ Rs: 1285/63	% Cft	Rs: 3,176.00
			(Rs: one two hund: eighty five & sixty three only)		
3	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		72.00	@ Rs: 3327/50	% Cft	Rs: 2,396.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
4	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		326.00	@ Rs: 3176/25	% 0 Cft	Rs: 1,035.00
			(Rs: three thous: one hund: seventy six & twenty five only)		
5	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c ) P/ 14).				
		163.00	@ Rs: 8694/95	% Cft	Rs: 14,173.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
6	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		428.00	@ Rs:11948/36	% Cft	Rs: 51,139.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
7	Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).				
		378.00	@ Rs:3327/50	% Cft	Rs: 12,578.00
			(Rs: three thous: three hund: twenty seven & fifty only)		
8	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		2208.00	@ Rs: 1141/25	% Cft	Rs: 25,199.00
			(Rs: one thous: one hund: forty one & twenty five only)		
9	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		876.00	@ Rs:12346/65	% Cft	Rs: 108,157.00
			(Rs: twelve thous: three forty six & sixty five only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 10 Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).

1667.00	@ Rs: 660/-	% Sft	Rs:	11,002.00
(Rs: six hund: sixty only)				

- 11 Cement plaster (1:6) upto 12' ft: height 1/2" thick. (S.I.No: 13 (b) P.58).

3161.00	@ Rs: 2206/60	% Sft	Rs:	69,751.00
(Rs: two thous: two hund: six & sixty only)				

- 12 Cement plaster 1:4 upto 12' ft; height 3/8" thick. (S.I.No: 11 (a) P.58).

3161.00	@ Rs: 2197/52	% S.ft	Rs:	69,464.00
(Rs: two thous: one hund: ninty seven & twenty two only)				

- 13 Cement pointing striking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).

1168.00	@ Rs:1287/44	% Sft	Rs:	15,037.00
(Rs: one thous: two hund: eighty seven & fourty four only)				

- 14 Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).

40.00	@ Rs: 14429/25	%Cft	Rs:	5,772.00
(Rs: fourteen thous: four hund: twenty nine & twenty five only)				

- 15 Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).

295.00	@ Rs:27747/06	% Sft	Rs:	81,853.0
(Rs: twenty seven thous: seven hund fourty seven & six only)				

- 16 First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).

12.00	@ Rs: 902/93	P.Sft	Rs:	10,835.00
(Rs: nine hund: two & ninty three only)				

- 17 Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

1355.00	@ Rs: 4411/82	% Sft	Rs:	59,780.00
(Rs: four thous: four hund: eleven & eighty two only)				

(B) 2"Thick

34.00	@ Rs: 3275/50	% S.ft	Rs:	1,114.00
(Rs: three thous: two hund; seventy five & fifty only)				

- 18 Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).

2183.00	@ Rs:1887/40	% Sft	Rs:	41,202.00
(Rs: one thous: eight hund; eighty seven & fourteen only)				

*[Handwritten signature]*  
BEN

S.No:	Description	Qty:	Rate	Unit	Amount
19	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).	48.00	@ Rs:726/72	P. Sft	Rs: 34,883.00
			(Rs: seven hund: twenty six & seventy two only)		
20	White wash two coats.	1848.00	@ Rs:425/84	% Sft	Rs: 7,870.00
			(Rs: four hund: twenty five & eighty four only)		
21	Distempering three coats. (S.I.No.24 (c) P/53).	9999.00	@ Rs:1079/65	% Sft	Rs: 107,954.00
			(Rs: one thos: seventy nine & sixty five only)		
22	Painting doors and windows any type. (ii) Each subsequent coat. (S.I.No.4 ( c ) (ii) P/76).	678.00	@ Rs:1160/06	% Sft	Rs: 7,865.00
			(Rs: one thous: one hund; sixty & six only)		
23	Painting guard bars, gates iron bars gratings, railing including standard braces (etc) and simiolar open work (ii) Each subsequent coat. (S.I.No.4(d)(ii) P/68).	96.00	@ Rs:674/60	% Sft	Rs: 648.00
			(Rs: six hund; seventy four & sixty only)		
<b>G.Total:</b>					<b>Rs: 744,900.0</b>

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sxity only)

- 2 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.00 @ Rs: 1384/24 P.No Rs: 2,768.00  
(Rs: one thous: three hund; eighty four & twenty four only)

- 3 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (250 gallons).(S.S.I.No: 3 P/21

1.00 @ Rs:21989/61 P.No Rs: 21,990.00  
(Rs: Twenty One thous: nine hund: eighty nine & Sixty only)

**Total:** Rs: **34,363.0**

### N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(a) 3/4" Dia 50.00 @ Rs: 78/01 P.No Rs: 3,900.00  
(Rs: sevnty eight & One only)

(b) 4" Dia 20.00 @ Rs: 397/77 P.No Rs: 7,955.00  
(Rs: three hund: ninty seven & seventy seven only)

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fitings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

(a) 3/4" Dia 20.00 @ Rs: 103/05 P.No Rs: 2,061.00  
(Rs: one hund; three & five only)

(b) 4" Dia 2.00 @ Rs: 425/45 P.No Rs: 850.00  
(Rs: four hund: twenty five & fourty five only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>3/4" Dia</u>	10.00	@ Rs: 110/40	P.No	Rs:	1,104.00
(Rs: one hund; ten & fourteen only)					

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

<u>3/4" Dia</u>	18.00	@ Rs:98/15	P.No	Rs:	1,766.00
(Rs: ninty eight & fifteen only)					

- 5 P/F UNION of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>3/4" Dia</u>	2.00	@ Rs: 312/81	P.Rft	Rs:	625.00
(Rs: three hund; tweleve & eighty one only)					

- 6 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond / Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).

1.00	@ Rs:14201/-	P.No:	Rs:	14,201.00
(Rs: fourteen thous: two hund: one only)				

<b>G.Total:</b>	<b>Rs:</b>	<b>32,462.00</b>
-----------------	------------	------------------

  
**XEN**

**SCHEDULE " B "**

S.No: 44

NAME OF WORK:-

**INTEGRATED REHABILITATION OF PRIMARY SCHOOLS & PROVISION OF MISSING FACILITIES TALUKA LARKANO (14-UNITS) (2015-16 PROGRAMME) AT GBPS MALOOK KORAI TALUKA LARKANO.**

S.No.	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).	656.00	Rs 5445/-	% Cft	Rs: 35,719.00
			(Rs: five thous: four hund: forty five only)		
2	Dimantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).	197.00	@ Rs: 3327/50	% Cft	Rs: 6,555.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
3	Removing door with chowkats. (S.I.No.33 (a) P/12).	2.00	@ Rs:142/18	P.No	Rs: 284.00
			(Rs: one hund: fourty two & eighteen only)		
4	Removing windows and sky light with chowkats. (S.I.No.33 (b) P/12).	6.00	@ Rs:102/85	P.No	Rs: 617.00
			(Rs: one hund: two & eighty five only)		
5	Removing cement or lime plaster. (S.i.No.53 P/13).	1055.00	@ Rs:121/-	% Sft	Rs: 1,277.00
			(Rs: one hund: twenty one only)		
6	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).	33.00	@ Rs: 1285/63	% Cft	Rs: 424.00
			(Rs: one two hund: eighty five & sixty three only)		
7	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).	322.00	@ Rs:12674/36	% Cft	Rs: 40,811.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	702.00	@ Rs:337/-	P.Cft	Rs: 236,574.00
			(Rs: three hund: thirty seven only)		
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	37.60	@ Rs:5001/70	P.Cwt	Rs: 188,063.00
			(Rs: five thous: one & seventy only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
10	Supplying and filling sand under floor and plugging in walls. (S.I.No: 29 P/25).				
		400.00	@ Rs: 1141/25	% Cft	Rs: 4,565.00
			(Rs: one thous: one hund: forty one & twenty five only)		
11	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).				
		1055.00	@ Rs: 660/-	% Sft	Rs: 6,963.00
			(Rs: six hund: sixty only)		
12	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).				
		1317.00	@ Rs:1887/40	% Sft	Rs: 24,857.00
			(Rs: one thous: eight hund: eighty seven & fourteen only)		
13	Replacing kaller eaten bricks. (S.I.No: 57(b) P/104).				
		200.00	@ Rs:36/63	Each	Rs: 7,326.00
			(Rs: thirty six & sixty three only)		
14	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hing and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		35.00	@ Rs:228/90	P.Rft	Rs: 7,980.00
			(Rs: two hund: twenty eight & ninty only)		
15	P/F G.I frame chokats of size 7" x2" or 4" x 3" for Windowss using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand repairing i/c all carriage tools and planst used in making and fixing. (S.I.No.29 P/98).				
		180.00	@ Rs: 240/50	P.Rft	Rs: 43,290.00
			(Rs: two hund: fourty & fifty only)		
16	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).				
		16.00	@ Rs: 902/93	P.Sft	Rs: 14,446.00
			(Rs: nine hud: two & ninty three only)		
17	M.S barred windows squars bars 5/8" dia.				
		1.71	@ Rs: 3550/-	P.Sft	Rs: 6,070.00
			(Rs: three thous: five hund: fifty only)		
18	Cutting and fixing iron bars for barred windows.				
		36.00	@ Rs:28/23	P.Cwt	Rs: 1,016.00
			(Rs: twenty eight & twenty three only)		
19	Notice board made with cement. (S.I.No: 1 P/94)				
		64.00	@ Rs: 58/11	P.Sft	Rs: 3,719.00
			(Rs: fifty eight & eleven only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
20	Cement plaster (1:6) upto 12' ft: height 1/2" thick. (S.I.No: 13 (b) P.58).				
		1412.00	@ Rs: 2206/60 % Sft		Rs: 31,157.00
			(Rs: two thous: two hund: six & sixty only)		
21	Cement plaster 1:4 upto 12' ft; height 3/8" thick. (S.I.No: 11 (a) P.58).				
		1412.00	@ Rs: 2197/52 % S.ft		Rs: 31,029.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		
22	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		141.00	@ Rs:1287/44 % Sft		Rs: 1,815.00
			(Rs: one thous: two hund: eighty seven & fourty four only)		
23	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		886.00	@ Rs: 4411/82 % Sft		Rs: 39,089.00
			(Rs: four thous: four hund; eleven & eighty two only)		
(B)	<u>2"Thick</u>				
		1317.00	@ Rs: 3275/50 % S.ft		Rs: 43,138.00
			(Rs: three thous: two hund; seventy five & fifty only)		
24	P/F deodar Almirah 9"x12" depth i/c boxing with back shalves shutters bars fittings complete (Without Box) (S.I.No: 23 P.68).				
		17.00	@ Rs:1748/- P.Sft		Rs: 19,716.00
			(Rs: one thous: seven hund; fourty eight only)		
25	White washing three coats. (S.I.No.26 ( c ) P/53).				
		886.00	@ Rs:829/95 % Sft		Rs: 7,353.00
			(Rs: eight hund: twenty nine & ninty five only)		
26	Primary coat of chalk under distemping.				
		4506.00	@ Rs: 442/75 % S.ft		Rs: 19,950.00
			(Rs: four hund; fourty tow & seventy five only)		
27	Distemping three coats				
		4506.00	@ Rs:1079/65 % Sft		Rs: 48,649.00
			(Rs: one thous: seventy nine & sixty five only)		
28	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).				
		304.00	@ Rs:2116/41 % Sft		Rs: 6,434.00
			(Rs: two thous: one hund sixteen & fourty one only)		
G.Total:					Rs: 878,886.00

  
**XEN**



## SCHEDULE " B "

NAME OF WORK:- INTEGRATED REHABILITATION OF PRIMARY SCHOOLS AND PROVISION OF MISSING FACILITIES TALUKA LARKANO (14-UNITS) (2015-16 PROGRAMME) AT GBPS JOUNGAL KHAN KHAKHRANI TALUKA LARKANO.

S.No:	Description	Qnty:	Rate	Unit	Amount
1	Removing door with chowkats. (S.I.No.33 (a) P/12).				
		2.00	@ Rs:142/18	P.No	Rs: 284.00
			(Rs: one hund: forty two & eighteen only)		
2	Remong windows and sky light with chowkats. (S.I.No.33 (b) P/12).				
		6.00	@ Rs:102/85	P.No	Rs: 617.00
			(Rs: one hund: two & eighty five only)		
3	Remoning cement or lime plaster. (S.I.No.53 P/13).				
		2524.00	@ Rs:121/-	% Sft	Rs: 3,054.00
			(Rs: one hund: twenty one only)		
4	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		192.00	@ Rs: 3327/50	%.Cft	Rs: 6,389.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
5	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		1043.00	@ Rs: 3176/25	% 0 Cft	Rs: 3,313.00
			(Rs: three thous: one hund: seventy six & twenty five only)		
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).				
		276.00	@ Rs: 8694/95	%.Cft	Rs: 23,998.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
7	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		1110.00	@ Rs:11948/36	%.Cft	Rs: 132,627.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		195.00	@ Rs:337/-	P.Cft	Rs: 65,715.00
			(Rs: three hund: thirty seven only)		
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		8.705	@ Rs:5001/70	P.Cwt	Rs: 43,540.00
			(Rs: five thous: one & seventy only)		

S.No:	Description	Qty:	Rate	Unit	Amount
10	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).				
		119.00	@ Rs:10/70 (Rs: ten & seventy only)	P.Sft	Rs: 1,273.0
11	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		328.00	@ Rs:12674/36 (Rs: twelve thous: six hund: seventy four & thirty six only)	% Cft	Rs: 41,572.00
12	Supplying of T.Iron at site of work. (Sch: of Material).				
		0.946	@ Rs:3575/- (Rs: three thous: five hund: seventy five only)	P.Cwt	Rs: 3,382.00
13	Second class tiles roofing consisting of 4" earth and 1" mud plaster with gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs: of hos bitumen coating sand blinded provlided over 2, layer of tiles 12"x6"x11/4" laid in 1:6 cement mortor with 1/2" thick sand wiched layer of 1:6 cement pointing under side of tiles complete including curring etc. (S.I.No. P/ ).				
		67.00	@ Rs: 7607/25 (Rs: seven thous: six hund: seven & twenty five only)	% Sft	Rs: 5,097.00
14	Single layer of tiles 9" x4" 1/2" x2" laid over 4" earth 1" mud plaster without Bhoosa grouted with cement sand 1:3 on top of R: C:C slab provide with 34 Lbs. Bituman coating sand blined. (S.I.No: 5 P/33).				
		55.00	@ Rs: 5310/35 (Rs: five thous: three hund: ten & thrity five only)	% S.ft	Rs: 2,921.00
15	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jams. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P/ ).				
		67.00	@ Rs:228/90 (Rs: two hund: twenty eight & ninty only)	P.Rft	Rs: 15,336.00
16	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and planst used in making and fixing .( S.I.No: P/ ).				
		122.00	@ Rs: 240/50 (Rs: two hund: forty & fifty only)	P.Rft	Rs: 29,341.00
17	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq. foot of finished grill).(S.I.No.26 P/92).				
		6.00	@ Rs:180/50 (Rs: one hund: eighty & fifty only)	P. Sft	Rs: 1,083.00

**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
18	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		713.00	@ Rs:12346/65	% Cft	Rs: 88,032.00
			(Rs: twelve thous: three forty six & sixty five only)		
19	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment. (S.I.No.24P/91).				
		51.00	@ Rs:726/72	P. Sft	Rs: 37,063.00
			(Rs: seven hund: twenty six & seventy two only)		
20	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).				
		2524.00	@ Rs: 660/-	% Sft	Rs: 16,658.00
			(Rs: six hund: sixty only)		
21	Cement plaster (1:6) upto 12' ft: height 1/2" thick. (S.I.No: 13 (b) P.58).				
		4818.00	@ Rs: 2206/60	% Sft	Rs: 106,314.00
			(Rs: two thous: two hund: six & sixty only)		
22	Cement plaster 1:4 upto 12' ft: height 3/8" thick. (S.I.No: 11 (a) P.58).				
		4818.00	@ Rs: 2197/52	% S.ft	Rs: 105,877.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		
23	Notice board made with cement. (S.I.No: 1 P/94).				
		64.00	@ Rs: 58/11	P.Sft	Rs: 3,719.00
			(Rs: fifty eight & eleven only)		
24	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		152.00	@ Rs: 902/93	P.Sft	Rs: 137,248.00
			(Rs: nine hund: two & ninty three only)		
25	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		2400.00	@ Rs: 1141/25	% Cft	Rs: 27,390.00
			(Rs: one thous: one hund: forty one & twenty five only)		
26	Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).				
		264.00	@ Rs:3327/50	% Cft	Rs: 8,785.00
			(Rs: three thous: three hund: twenty seven & fifty only)		
27	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		1642.00	@ Rs: 4411/82	% Sft	Rs: 72,442.00
			(Rs: four thous: four hund: eleven & eighty two only)		

**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

(B) 1-1/2"Thick

1208.00 @ Rs: 2548/29 % S.ft Rs: 30,783.00  
(Rs: two thous: five hund: forty eight & twenty nine only)

- 28 Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).

1208.00 @ Rs:1887/40 % Sft Rs: 22,800.00  
(Rs: one thous: eighty hund; eighty seven & fourteen only)

- 29 Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).

1789.00 @ Rs:1287/44 % Sft Rs: 23,032.00  
(Rs: one thous: two hund: eighty seven & fourty four only)

- 30 Primary coat of chalk distempering. (S.I.No.23 P/57).

4818.00 @ Rs: 442/75 % Sft Rs: 21,332.00  
(Rs: four hund; fourty tow & seventy five only)

- 31 Distempering three coats. (S.I.No.24 (c) P/53).

4818.00 @ Rs:1079/65 % Sft Rs: 52,018.00  
(Rs: one thous: seventy nine & sixty five only)

(B) Two coats

1015.00 @ Rs:1043/90 % Sft Rs: 10,596.00  
(Rs: ten hund; forty three & ninty only)

- 32 Preparing surface and painting of doors and windows any type (including edges)  
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

326.00 @ Rs:2116/41 % Sft Rs: 6,899.00  
(Rs: two thous: one hund: sixteen & fourty one only)

- 33 Painting guard bars , gates iron bars gratings railings i/c standard barse etc:  
smiler open works.

138.00 @ Rs:1270/83 % S.ft Rs: 1,754.00  
(Rs: one thous: two hund: seventy & eighty three only)

**G.Total:** Rs: 1,152,284.0

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 15" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sxity only)

- 2 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.00 @ Rs: 1384/24 P.No: Rs: 2,768.00  
(Rs: one thous: three hund; eighty four & twenty four only)

**Total:** Rs: **12,373.0**

### N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(a) 3/4" Dia 15.00 @ Rs: 78/01 P.No: Rs: 1,170.00  
(Rs: sevnty eight & One only)

(b) 4" Dia 20.00 @ Rs: 397/77 P.No: Rs: 7,955.00  
(Rs: three hund: ninty seven & seventy seven only)

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of verious sizes fixed to UPVC pipe/fitings paid separatly, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

(a) 3/4" Dia 12.00 @ Rs: 103/05 P.No: Rs: 1,236.00  
(Rs: one hund; three & five only)

- 3 P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete.(R.A)

Nyloon Plastic pi 70.00 @ Rs: 77/- P.Rft: Rs: 5,390.00  
(Rs: seventy seven only)

- 4 Providing & Fixing Hand pump Machine (R.A)

Machine 1.00 @ Rs: 4500/- Each: Rs: 4,500.00  
(Rs: four thous: five hund: only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 5 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).

1.00

@ Rs:14201/- P.No:

Rs:

14,201.00

(Rs: fourteen thous: two hund: one only)

G.Total:

Rs:

34,452.00

  
XEN

**SCHEDULE " B "****S.No:****NAME OF WORK:-****INTEGRATED REHABILITATION OF PRIMARY SCHOOLS AND  
PROVISION OF MISSING FACILITIES TALUKA LARKANO  
(14-UNITS) (2015-16 PROGRAMME) AT GGPS PV SINDHI TALUKA  
LARKANO**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Remoning cement or lime plaster. (S.I.No.53 P/13).				
		1672.00	@ Rs:121/-	% Sft	Rs: 2,023.00
2	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).				
		36.00	Rs 5445/-	%.Cft	Rs: 1,960.00
			(Rs: five thous: four hund: forty five only)		
3	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		1032.00	@ Rs: 1285/63	%.Cft	Rs: 13,268.00
			(Rs: one two hund: eighty five & sixty three only)		
4	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		716.00	@ Rs:11948/36	%.Cft	Rs: 85,550.0
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
5	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		329.00	@ Rs:337/-	P.Cft	Rs: 110,873.0
			(Rs: three hund: thirty seven only)		
6	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		16.00	@ Rs:5001/70	P.Cwt	Rs: 80,027.0
			(Rs: five thous: one & seventy only)		
7	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		115.00	@ Rs: 1141/25	%.Cft	Rs: 1,312.0
			(Rs: one thous: one hund: forty one & twenty five only)		
8	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		230.00	@ Rs:12674/36	%.Cft	Rs: 29,151.00
			(Rs: tweleve thous: six hund: seventy four & thirty six only)		
9	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		1650.00	@ Rs:12346/65	%.Cft	Rs: 203,720.00
			(Rs: tweleve thous: three forty six & sixty five only)		


  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
10	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No:28 /P 92).	32.00	@ Rs:228/90	P.Rft	Rs: 7,325.00 (Rs: two hund: twenty eight & ninty only)
11	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	6.00	@ Rs:180/50	P. Sft	Rs: 1,083.0 (Rs: one hund: eighty & fifty only)
12	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	16.00	@ Rs: 8694/95	% Cft	Rs: 1,391.00 (Rs: eight thous: six hund: ninty four & ninty five only)
13	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Surface).	35.00	@ Rs: 902/93	P.Sft	Rs: 31,603.00 (Rs: nine hund: two & ninty three only)
14	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).	1672.00	@ Rs: 660/-	% Sft	Rs: 11,035.00 (Rs: six hund: sixty only)
15	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	3532.00	@ Rs:2206/60	% Sft	Rs: 77,937.0 (Rs: two thous: two hund: six & sixty only)
16	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	3532.00	@ Rs:2197/52	% Sft	Rs: 77,616.0 (Rs: two thous: one hund: ninty seven & twenty two only)
17	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	55.00	@ Rs: 4411/82	% Sft	Rs: 2,426.00 (Rs: four thous: four hund: eleven & eighty two only)
(B) <u>2"Thick</u>		111.00	@ Rs: 3275/50	% S.ft	Rs: 3,635.00 (Rs: three thous: two hund; seventy five & fifty only)
18	Supplying and fixing broken glass on courtyard walls including 1:3:6 cement concrete coping (S.I.No: 61 P/104).	150.00	@ Rs:70/44	P Lft	Rs: 10,566.00 (Rs: seventy & forty four only)



S.No:	Description	Qty:	Rate	Unit	Amount
19	Primary coat of chalk under distempring.				
		3532.00	@ Rs: 442/75	% S.ft	Rs: 15,638.00
			(Rs: four hund; fourty tow & seventy five only)		
20	Distempering two coats. (S.I.No.24 (b) P/53).				
		3532.00	@ Rs:1043/90	% Sft	Rs: 36,871.00
			(Rs: ten hund; forty three & ninty only)		
21	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c) P/69).				
		70.00	@ Rs:2116/41	% Sft	Rs: 1,481.0
			(Rs: two thous: one hund: sixteen & fourty one only)		
22	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment. (S.I.No.24P/91).				
		42.00	@ Rs:726/72	P. Sft	Rs: 30,522.0
			(Rs: seven hund: twenty six & seventy two only)		
23	Painting guard bars , gates iron bars gratings railings i/c standard barsed etc: smiler open works.				
		84.00	@ Rs:1270/83	% S.ft	Rs: 1,067.00
			(Rs: one thous: two hund: seventy & eighty three only)		
<b>G.Total:</b>					<b>Rs: 833,827.0</b>

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.  
2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sixty only)
- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)  
2.00 @ Rs: 4928/- P.Each Rs: 9,856.00  
(Rs: four thous: nine hund; twenty eight only)
- 3 Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed  
2.00 @ Rs: 2533/47 P.No: Rs: 5,066.00  
(Rs: four thous: five hund; thirty three & fourty seven only)
- 4 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.  
4.00 @ Rs: 447/15 P.No: Rs: 1,788.00  
(Rs: four hund: forty seven & fifteen only)
- 5 S/F conceled stop cock of superior quality with C.P head 1/2" dia.  
4.00 @ Rs: 889/46 P.No Rs: 3,557.00  
(Rs: eight hund; eighty nine fourty six only)
- 6 S/F long bib-cock of superior quality with C.P head 1/2" dia  
5.00 @ Rs: 1384/24 P.No Rs: 6,921.00  
(Rs: one thous: three hund; eighty four & twenty four only)
- 7 S/F Swan type pillar cock of superior quality etc:  
2.00 @ Rs: 877/80 P.No Rs: 1,755.00  
(Rs: eight hund; seventy seven & eighty only)
- 8 providing chambers (15"X19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 t set-on 1:6 cement mortor 6" thick C.C. 1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) etc fixied in cement concerate 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).  
1.00 @ Rs: 5913/22 Each Rs: 5,913.00  
(Rs: five thous: nine hund; thirteen & twenty two only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 9 S/F fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate iron of cement concrete 1:2:7 and making and connection for inlet- outlet and over flow pipe etc complete (250 gallons).

1.00	@ Rs: 21989/61	Each	Rs:	21,990.00
(Rs: twenty one thousand nine hundred eighty nine & sixty one only)				

- 10 P/F 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden plate (a) Standard pattern. (S.I.No.3 (a) P/7).

2.00	@ Rs:2376/-	P.Each	Rs:	4,752.00
(Rs: two thousand three hundred seventy six only)				

<b>G.Total:</b>	<b>Rs:</b>	<b>71,203.00</b>
-----------------	------------	------------------

#### N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separately recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

<u>(a) 3/4" Dia</u>	100.00	@ Rs: 78/01	P.Rft	Rs:	7,801.00
(Rs: seventy eight & One only)					

<u>(b) 1" Dia</u>	20.00	@ Rs: 97/91	P.Rft	Rs:	1,958.00
(Rs: ninety seven & ninety one only)					

<u>(c) 4" Dia</u>	30.00	@ Rs: 397/77	P.Rft	Rs:	11,933.00
(Rs: three hundred ninety seven & seventy seven only)					

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>(a) 3/4" Dia</u>	10.00	@ Rs: 103/05	P.No	Rs:	1,030.00
(Rs: one hundred; three & five only)					

<u>(b) 1" Dia</u>	6.00	@ Rs: 125/90	P.No	Rs:	755.00
(Rs: one hundred; twenty five & ninety only)					

<u>(c) 4" Dia</u>	2.00	@ Rs: 425/45	P.No	Rs:	850.00
(Rs: four hundred; twenty five & forty five only)					

*Handwritten signature*

S.No.	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>(a) 3/4" Dia</u>	10.00	@ Rs: 110/40	P.No	Rs:	1,105.00
(Rs: one hund; ten & forty only)					

<u>(b) 1" Dia</u>	5.00	@ Rs: 132/43		Rs:	662.00
(Rs: one hund; thirty two & forty three only)					

<u>(c) 4" Dia</u>	2.00	@ Rs: 712/75	P.No	Rs:	1,425.00
(Rs: seven hund; twelve & seventy five only)					

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

<u>(a) 3/4" Dia</u>	12.00	@ Rs:98/15	P.No	Rs:	1,178.00
(Rs: ninty eight & fifteen only)					

<u>(b) 1" Dia</u>	5.00	@ Rs:110/40	P.No	Rs:	552.00
(Rs: one hund: ten & fourty only)					

- 5 P/F UNION of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>(a) 3/4" Dia</u>	2.00	@ Rs: 312/81	P.Rft	Rs:	626.00
(Rs: three hund; tweleve & eighty one only)					

<u>(b) 1" Dia</u>	2.00	@ Rs:381/37	P.No	Rs:	762.00
(Rs: three hund; eighty one & thirt seven only)					

- 6 P/F UPVC P-Trap W/Elbow (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	2.00	@ Rs:818/04	P.No	Rs:	1,636.00
(Rs: eight hund: eighteen & four only)					

  
**XEN**

S.No.	Description	Qty:	Rate	Unit	Amount
7	P/F UPVC WYE (Y) (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>4" Dia</u>	3.00	@ Rs:933/13	P.No	Rs: 2,799.00
			(Rs: nine hund; thirty three & thirteen only)		
8	P/F UPVC PLUG ELBOW (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>4" Dia</u>	2.00	@ Rs:677/65	P.No	Rs: 1,355.00
			(Rs: six hund; seventy seven & sixty five only)		
9	P/F UPVC PLUG TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>4" Dia</u>	2.00	@ Rs:847/42	P.No	Rs: 1,695.00
			(Rs: eight hund; fourty seven & fourty two only)		
10	P/F UPVC VENT COWEL (LOCAL) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>4" Dia</u>	2.00	@ Rs:187/93	P.No	Rs: 375.00
			(Rs: one hund: eighty seven & ninty three only)		
11	P/F COMPACTE BALL VALVE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>1-1/4" Dia</u>	2.00	@ Rs:652/35	P.No	Rs: 1,304.00
			(Rs: six hund; fifty two & thirty five only)		



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 12 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete.

1.00 @ Rs:14201/- P.No Rs: 14,201.00  
(Rs: fourteen thous: two hund: one only)

- 14 P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete.

105.00 @ Rs:77/- P.Rft Rs: 8,085.00  
(Rs: seventy seven only)

- 15 Providing & Fixing Hand pump Machine i/c fitting and fixing i/c etc complete.

Machine

1.00 @ Rs: 4500/- P.No Rs: 4,500.00  
(Rs: four thous: five hund: only)

N.S.I Rs: 66,587.00

S.I Rs: 71,203.00

G.Total: Rs: 137,790.00

  
XEN

**SCHEDULE " B "****S.No:****NAME OF WORK:-****INTEGRATED REHABILITATION OF PRIMARY  
SCHOOLS & PROVISION OF MISSING FACILITIES  
TALUKA LARKANO (14-UNITS) (2015-16 PROGRAMME)  
AT GBPS ROHAL KHAN BUGTI TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 1 Dimantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).

94.00 @ Rs: 3327/50 % Cft Rs: 3,128.00  
(Rs: three thous: two hund: twenty seven & fifty only)

- 2 Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).

39.00 Rs 5445/- % Cft Rs: 2,124.00  
(Rs: five thous: four hund: forty five only)

- 3 Removing cement or lime plaster. (S.i.No.53 P/13).

342.00 @ Rs:121/- % Sft Rs: 414.00  
(Rs: one hund: twenty one only)

- 4 Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).

183.00 @ Rs: 3176/25 % 0 Cft Rs: 581.00  
(Rs: three thous: one hund: seventy hund: twenty five only)

- 5 Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c ) P/ 14)

61.00 @ Rs: 8694/95 % Cft Rs: 5,304.00  
(Rs: eight thous: six hund: ninety four & ninty five only)

**(b) Ratio 1:6:12**

270.00 @ Rs: 8122/95 % Cft Rs: 21,932.00  
(Rs: eight thous: one hund: twenty two & ninty five only)

- 6 Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)

737.00 @ Rs:11948/36 % Cft Rs: 16,369.00  
(Rs: eleven thous: nine hund: eighty five & thirty six only)

- 6 Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).

115.00 @ Rs:12674/36 % Cft Rs: 14,576.00  
(Rs: twelve thous: six hund: seventy four & thirty six only)

- 7 Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).

7706.00 @ Rs: 1141/25 % Cft Rs: 87,945.00  
(Rs: one thous: one hund: forty one & twenty five only)



S.No.	Description	Qty:	Rate	Unit	Amount
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	54.00	@ Rs:337/- (Rs: three hund: thirty seven only)	P.Cft	Rs: 18,198.00
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	2.65	@ Rs:5001/70 (Rs: five thous: one & seventy only)	P.Cwt	Rs: 13,255.00
10	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).	342.00	@ Rs: 660/- (Rs: six hund: sixty only)	% Sft	Rs: 2,257.00
11	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	342.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 7,547.00
12	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	342.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	Rs: 7,516.00
13	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	1224.00	@ Rs: 4411/82 (Rs: four thous: four hund: eleven & eighty two only)	% Sft	Rs: 71,869.00
(B)	<u>2"Thick</u>	104.00	@ Rs: 3275/50 (Rs: three thous: two hund; seventy five & fifty only)	% S.ft	Rs: 3,407.00
14	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	369.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 4,751.00
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).	8.00	@ Rs: 902/93 (Rs: nine hud: two & ninty three only)	P.Sft	Rs: 7,223.00
16	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	6.00	@ Rs:180/50 (Rs: one hund: eighty & fifty only)	P. Sft	Rs: 1,083.0



S.No:	Description	Qty:	Rate	Unit	Amount
17	Providing and laying Halla or pettern tiles glazed 8"x8"x1/4" on floor or wall facing in required pattern of sitile specification jointed in white cement and pigment over a base of 1:2 grey cement motar 3/4" thick including washing and filling joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc. complete including cutting tiles to proper profile (S.I.No: 62 P.47).	48.00	@ Rs: 34520/31	% Sft	Rs: 16,570.00 (Rs: thirty four thous: five hund: twenty & thirty one only)
18	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	1397.00	@ Rs:1887/40	% Sft	Rs: 26,367.00 (Rs: one thous: eight hund: eighty seven & fourteen only)
19	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).	6.00	@ Rs: 14429/25	%Cft	Rs: 866.00 (Rs: fourteen thous: four hund: twenty nine & twenty five only)
20	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).	148.00	@ Rs:27747/06	% Sft	Rs: 41,065.00 (Rs: twenty seven thous: seven hund fourty seven & six only)
21	White washing three coats. (S.I.No.26 ( c ) P/53).	849.00	@ Rs:829/95	% Sft	Rs: 7,046.00 (Rs: eight hund: twenty nine & ninty five only)
22	Primary coat of chalk under distemping.	2790.00	@ Rs: 442/75	% S.ft	Rs: 12,353.00 (Rs: four hund; fourty tow & seventy five only)
23	Distemping three coats. (S.I.No.24 (c) P/53).	2790.00	@ Rs:1079/65	% Sft	Rs: 30,122.00 (Rs: one thos: seventy nine & sixty five only)
24	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	1624.00	@ Rs: 1948/10	% Sft	Rs: 31,637.00 (Rs: one thous: nine hund: forty eight & ten only)
25	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).	304.00	@ Rs:2116/41	% Sft	Rs: 6,434.00 (Rs: two thous: one hund: sixteen & fourty one only)
26	Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.	1179.00	@ Rs:1270/83	% S.ft	Rs: 14,983.00 (Rs: one thous: two hund: seventy & eighty three only)
G.Total:					Rs: 476,922.0

**SCHEDULE " B "**S.No: *62*

NAME OF WORK:-

**INTEGRATED REHABILITATION OF PRIMARY  
SCHOOLS & PROVISION OF MISSING FACILITIES  
TALUKA LARKANO (14-UNITS) (2015-16 PROGRAMME)  
AT GGMS SACHE BUX JAGIRANI TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Removing cement or lime plaster. (S.I.No.53 P/13).				
		1010.00	@ Rs:121/- (Rs: one hund: twenty one only)	% Sft	Rs: 1,222.00
2	Dimantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		34.00	@ Rs: 3327/50 (Rs: three thous: two hund: twenty seven & fifty only)	% Cft	Rs: 1,131.00
3	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		1010.00	@ Rs:660/- (Rs: six hund: sixty only)	% Sft	Rs: 6,666.00
4	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		1010.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 22,287.00
5	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1010.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	Rs: 22,195.00
6	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		1473.00	@ Rs: 4411/82 (Rs: four thous: four hund; eleven & eighty two only)	% Sft	Rs: 64,986.00
7	Providing and laying Halla or pettern tiles glazed 8"x8"x1/4" on floor or wall facing in required pattern of sitile specification jointed in white cement and pigment over a base of 1:2 grey cement motar 3/4" thick including washing and filling joints with slurry of wihite cement and pigment in desired shape with finishing cleaning and cost of wax polish etc. complete including cutting tiles to proper profile (S.I.No: 62 P.47).				
		50.00	@ Rs: 34520/31 (Rs: thirty four thous: five hund: twenty & thirty one only)	% Sft	Rs: 17,260.00
8	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		93.00	@ Rs: 902/93 (Rs: nine hund: two & ninty three only)	P.Sft	Rs: 83,972.00

*Dr*  
X  
X

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 9 Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).

2508.00 @ Rs:1887/40 %Sft Rs: 47,335.00  
(Rs: one thous: eight hund; eighty seven & fourteen only)

- 10 Distempering three coats. (S.I.No.24 (c) P/53).

5334.000 @ Rs:1079/65 %Sft Rs: 57,588.0  
(Rs: one thos: seventy nine & sixty five only)

**G.Total:** Rs: 324,642.00

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

**PART-B**

- 1 P/f water pumping set 3 HP unonablock single phase 220 volls with 11/2"x11/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of requred size fixing with units + hools E.S.I.No: 23P/33).

1.00 @ Rs:15254/48 P.No: Rs: 15,254.00  
(Rs: fifteen thous: two hund: fifty four & fouty eight only)

- 2 S/F long bib-cock of superior quality with C.P head 1/2" dia

4.00 @ Rs: 1384/24 P.No Rs: 5,537.00  
(Rs: one thous: three hund; eighty four & twenty four only)

**G.Total:**

**Rs: 20,791.00**

**(B) N.S.I**

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(a) 3/4" Dia 75.00 @ Rs: 73/59 P.No Rs: 5,519.00  
(Rs: sevnty three Fifty Nine only)

(b) 1/2" Dia 10.00 @ Rs: 63/03 P.Rft Rs: 630.00  
(Rs: sixty three & Three only)

(C) 1" Dia 10.00 @ Rs: 92/37 P.No Rs: 923.00  
(Rs: ninety two & thirty seven only)

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid separatly, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

(a) 1/2" Dia 5.00 @ Rs:95/65 P.Rft Rs: 478.00  
(Rs: Ninty five & sixty five only)

(b) 3/4" Dia 18.00 @ Rs: 97/22 P.No Rs: 1,750.00  
(Rs: Ninty seven & twenty tow only)

(c) 1" Dia 2.00 @ Rs: 118/78 P.No Rs: 238.00  
(Rs: one hun: eighteen & seventy eight only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

(a) 3/4" Dia	6.00	@ Rs: 104/15	P.No	Rs:	624.00
(Rs: one hundred & fifteen only)					

(b) 4" Dia	2.00	@ Rs:672/41	P.No	Rs:	1,344.00
(Rs: six hundred & seventy two & forty one only)					

G.Total:	Rs:	11,506.00
----------	-----	-----------

  
XEN

**SCHEDULE " B "****S.No:** 49**NAME OF WORK:-****INTEGRATED REHABILITATION OF PRIMARY SCHOOLS AND  
PROVISION OF MISSING FACILITIES TALUKA LARKANO  
(14-UNITS) (2015-16 PROGRAMME) AT GBPS DAE-JI-WANDH  
TALUKA LARKANO**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		212.00	@ Rs: 3327/50	% Cft	Rs: 7,054.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
2	Removing cement or lime plaster. (S.I.No.53 P/13).				
		1514.00	@ Rs:121/-	% Sft	Rs: 1,832.00
3	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		183.00	@ Rs: 3176/25	% 0 Cft	Rs: 581.00
			(Rs: three thous: one hund: seventy six & twenty five only)		
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).				
		41.00	@ Rs: 8694/95	% Cft	Rs: 3,565.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
(b)	<u>Ratio 1:6:12</u>				
		134.00	@ Rs: 8122/95	% Cft	Rs: 10,884.00
			(Rs: eight thous: one hund: twenty two & ninty five only)		
5	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		36.00	@ Rs:11948/36	% Cft	Rs: 4,301.0
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
6	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		41.00	@ Rs:12674/36	% Cft	Rs: 5,196.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
7	Pacca brick work other than building including stricking of joints upto 20ft height in cemen sand mortar. (S.I.No: 7 (i) (e) P.26).				
		675.00	@ Rs: 12346/75	% Cft	Rs: 83,340.00
			(Rs: twelve thous: three hund: fourty six & seventy five only)		
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		65.00	@ Rs:337/-	P.Cft	Rs: 21,905.0
			(Rs: three hund: thirty seven only)		

S.No:	Description	Qty:	Rate	Unit	Amount
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		3.00	@ Rs:5001/70	P.Cwt	Rs: 15,005.0
			(Rs: five thous: one & seventy only)		
10	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		538.00	@ Rs: 1141/25	% Cft	Rs: 6,139.0
			(Rs: one thous: one hund: forty one & twenty five only)		
11	Single layer of tiles 9" x4" 1/2" x2" laid over 4" earth 1" mud plaster without Bhoosa grouted with cement sand 1:3 on top of R: C:C slab provide with 34 Lbs. Bituman coating sand blined. (S.I.No: 5 P/33).				
		1058.00	@ Rs: 5310/35	% S.ft	Rs: 56,183.00
			(Rs: five thous: three hund: ten & thrity five only)		
12	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).				
		1058.00	@ Rs:10/70	P.Sft	Rs: 11,320.0
			(Rs: ten & seventy only)		
13	Reinforced cement concerte spout i/c fixing in position with top and bottom khuras. (S.I.No: 27 P/18)				
		2.00	@ Rs: 524/98	Each	Rs: 1,050.00
			(Rs: five hund; twenty four & ninty eight only)		
14	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).				
		1514.00	@ Rs: 660/-	% Sft	Rs: 9,992.00
			(Rs: six hund: sixty only)		
15	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		1514.00	@ Rs:2206/60	% Sft	Rs: 33,408.0
			(Rs: two thous: two hund: six & sixty only)		
16	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1514.00	@ Rs:2197/52	% Sft	Rs: 33,270.0
			(Rs: two thous: one hund: ninty seven & twenty two only)		
17	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		668.00	@ Rs: 4411/82	% Sft	Rs: 29,470.00
			(Rs: four thous: four hund: eleven & eighty two only)		
18	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		75.00	@ Rs:1287/44	% Sft	Rs: 4,827.0
			(Rs: one thous: two hund: eighty seven & fourty four only)		

S.No:	Description	Qty:	Rate	Unit	Amount
19	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).	18.00	@ Rs:228/90	P.Rft	Rs: 4,120.00 (Rs: two hund: twenty eight & ninty only)
20	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).	20.00	@ Rs: 240/50	P.Rft	Rs: 7,215.00 (Rs: two hund: forty & fifty only)
21	M.S barred windows squars bars 5/8" dia.	0.25	@ Rs: 3550/-	Cwt	Rs: 994.00 (Rs: three thous: five hund: fifty only)
22	Cutting and fixing iron bars for barred windows. (S.I.No: P/ ).	6.00	@ Rs: 28/23	P.No	Rs: 170.00 (Rs: twenty eight & twenty three only)
23	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Surface).	43.00	@ Rs: 902/93	P.Sft	Rs: 39,728.00 (Rs: nine hund: two & ninty three only)
24	White wash three coats. (S.I.No: 26 (c ) P/86).	900.00	@ Rs: 829/95	% Sft	Rs: 7,470.00 (Rs: eight hund: twenty nine & ninty five only)
25	Distemping three Coats (S.I.No: 24 (c) P.No: 60).	5915.00	@ Rs: 1079/65	% Sft	Rs: 63,861.00 (Rs: one thous: seventy nine & sixty five only)
26	Preparing the surface and paointing with weather coat i/c rubbing the surface with rubbing brick sand paper filling the voids with chalk plaster of peris and than painting with weather coat of approved make ( new surface) (S.I.No.38 P/61).	1128.00	@ Rs: 1948/10	% S.ft	Rs: 21,974.0 (Rs: one thous; nine hund: fourty eight & ten only)
27	Prepairng surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c ) P. 76 (ii) ).	304.00	@ Rs: 2116/41	% Sft	Rs: 6,433.00 (Rs: two thous: one hund: sixteen & fourty one only)

  
XEN



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 28 Painting guard bars , gates iron bars gratings railings i/c standard barsees etc:  
smiler open works(S.I.No. (d) P/76(ii).

96.00 @ Rs: 1270/83 % S.ft Rs: 1,220.00  
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 492,507.0



S.No.	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.  
1.00 @ Rs: 4802/60 P.No: Rs: 4,802.00  
(Rs: four thous: eight hund; two & sxity only)
- 2 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.  
1.00 @ Rs: 447/15 P.No: Rs: 447.00  
(Rs: four hund: forty seven & fifteen only)
- 3 S/F long bib-cock of superior quality with C.P head 1/2" dia  
1.00 @ Rs: 1384/24 P.No Rs: 1,384.00  
(Rs: one thous: three hund; eighty four & twenty four only)
- 4 S/F conceled stop cock of superior quality with C.P head 1/2" dia.  
1.00 @ Rs: 889/46 P.No Rs: 898.00  
(Rs: eight hund; eighty nine fourty six only)
- 6 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (100 gallons).(S.S.I.No: 3 P/21  
1.00 @ Rs: 87/95 P.Gallan Rs: 8,795.00  
(Rs: eighty seven & ninty five only)

**G.Total:** Rs: 16,326.00

### N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).  

(a) 3/4" Dia 15.00 @ Rs: 78/01 P.Rft Rs: 1,170.00  
(Rs: sevnty eight & One only)

(b) 4" Dia 5.00 @ Rs: 397/77 P.Rft Rs: 1,988.00  
(Rs: three hund: ninty seven & seventy seven only)

  
XEN

S.No.	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<b>(a) 3/4" Dia</b>	3.00	@ Rs: 103/05	P.No	Rs:	309.00
(Rs: one hund; three & five only)					

- 3 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete.

1.00	@ Rs:14201/-	P.No	Rs:	14,201.00
(Rs: fourteen thous: two hund: one only)				

- 4 P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete.

50.00	@ Rs:77/-	P.Rft	Rs:	3,850.00
(Rs: seventy seven only)				

- 5 Providing & Fixing Hand pump Machine i/c fitting and fixing i/c etc complete.

<b>Machine</b>	1.00	@ Rs: 4500/-	P.No	Rs:	4,500.00
(Rs: four thous: five hund: only)					

<b>N.S.I</b>	<b>Rs:</b>	<b>26,018.00</b>
<b>S.I</b>	<b>Rs:</b>	<b>16,326.00</b>
<b>G.Total:</b>	<b>Rs:</b>	<b>42,344.00</b>



## Schedule-B

Name of  
Work:-

**PROVISION OF MISSING FACILITIES (C/WALL, LAV: BLOCK & ADD: C/R) TO  
EXISTING ELEMENTARY SCHOOLS OF TALUKA RATODERO DISTRICT  
LARKANO (12 UNITS) (2015-16 PROGRAMME) @ GBPS PARIAL JALBANI  
(C/WALL) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	955.00	@ Rs: 3,176.25 % 0Cft (Thirty one Hundred seventy six rup: & twenty five paisa only)	Rs:	3,033
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	233.00	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)	Rs:	20,259
3	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	370.00	@ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)	Rs:	124,690
4	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)	14.866	@ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)	Rs:	74,355
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	509.00	@ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)	Rs:	60,817
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6 (S.I No. 7 'e'	79.00	@ Rs. 12,346.65 % Cft (Twelve thousand Three hundred Forty Six rup: & Sixty Five paisa only)	Rs.	9,754
7	Making & fixing steel gated doors with 1 1/6" thick sheeting i/c angle iron frame 2"x2"x3/4" and square bars 4" centre to cement.	42.00	@ Rs. 726.72 P. Sft (Seven hundred twenty six rupees & seventy two paisa only)	Rs.	30,522
8	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	4050.00	@ Rs. 2,206.60 % Cft (Twenty tow hund: six rup: & sixty paisa only)	Rs.	89,367

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 9 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

4050.00 @ Rs: 2,197.52 % Sft Rs: 89,000  
(Twenty one hundred: ninty seven rup: & fifty two paisa only)

- 10 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

975.00 @ Rs: 1,287.44 % Sft Rs: 12,553  
(Twelve hundred eighty seven rupees & forty for paisa only)

- 11 Primary coat of chalk distemper( S.I No. 23 P/53)

2100.00 @ Rs: 442.75 % Sft Rs: 9,298  
(Four hundred forty two rupees & seventy five paisa only)

- 12 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

2100.00 @ Rs. 1,948.10 % Sft Rs. 40,910  
Twenty on hundred sixteen rupees & forty one paisa only)

- 13 Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.

84.00 @ Rs. 1,270.83 % Sft Rs. 1,067

**Total Rs.**

**565,626**

  
**XEN**

## Schedule-B

Name of  
Work:-

**PROVISION OF MISSING FACILITIES (C/WALL, LAV: BLOCK & ADD: C/R) TO  
EXISTING ELEMENTARY SCHOOLS OF TALUKA RATODERO DISTRICT  
LARKANO (12 UNITS) (2015-16 PROGRAMME) @ GBPS MEHAR BURIRO (02  
C/R) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	1434.00	@ Rs: 3,176.25 % 0Cft (Thirty one Hundred seventy six rup: & twenty five paisa only)	Rs:	4,555
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	972.00	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)	Rs:	84,515
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	131.01	@ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)	Rs:	15,654
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	1008.00	@ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)	Rs:	339,696
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)	45.000	@ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)	Rs:	225,077
6	Supply and fixing sand under floor including plugging in to walls	3230.00	@ Rs: 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)	Rs:	36,862
7	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.	2205.00	@ Rs. 12,674.36 % Cft (Twelve thousand six hundred seventy four rup: & thity six paisa only)	Rs.	279,470
8	P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification	217.00	@ Rs. 10.70 P.Sft (Ten rupees & seventy paisa only)	Rs.	2,322
9	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	3309.00	@ Rs. 2,206.60 % Cft (Twenty tow hund: six rup: & sixty paisa only)	Rs.	73,016

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 10 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

3309.00 @ Rs: 2,197.52 % Sft Rs: 72,716  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

- 11 Making Notice board made with cement.

64.00 @ Rs: 58.11 P. Sft Rs: 3,719  
(Nnety Three rupees & Thirty Seven paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges  
12 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs.  
The cost also i/c all carriage, tools and pla

61.00 @ Rs: 228.90 P. Rft Rs: 13,963  
(Two hundred twenty eight rupees & ninty paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded  
13 hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the  
jambs. The cost also i/c all carriage, tools

270.00 @ Rs: 240.50 P. Rft Rs: 64,935  
(Two hundred forty rupees & fifty paisa only)

- 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts  
14 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25  
P/60)

200.00 @ Rs: 902.93 P. Sft Rs: 180,586  
(Nine hund: two rup: & ninty three paisa only)

- Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved  
15 design including painting 3 coats etc. complee ( weight not to be less than 3.7  
Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

131.00 @ Rs: 180.50 P. Sft Rs: 23,646  
( One hundre ninty four rupees & sixteen paisa only)

- 16 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing  
into panels: (S.I. No. 16 P/41)

927.00 @ Rs: 4,411.82 % Sft Rs: 40,898  
( Forry four hundred eleven rup: & eighty two paisa only)

**(B) 2" Thick.**

1362.00 @ Rs: 3,275.50 Rs: 44,612  
(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

- 17 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

1153.00 @ Rs: 1,287.44 % Sft Rs: 14,844  
(Twelve hundred eighty seven rupees & forty for paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

18 Primary coat of chalk distemper( S.I No. 23 P/53)

3309.00 @ Rs: 442.75 % Sft Rs: 14,651  
(Four hundred forty two rupees & seventy five paisa only)

19 Distemping Three Coats (S.I No. 24 ©P/53)

3309.00 @ Rs: 1,079.65 % Sft Rs: 35,726  
(One thousand Seventy nine rup: & sixty five paisa only)

20 White wash Three Coats (S.I No. 26 © P/53)

1242.00 @ Rs: 829.95 % Sft Rs: 10,308  
(Eight hundred twenty nine rup: & ninty five paisa only)

21 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

1673.00 @ Rs: 1,948.10 % Sft Rs: 32,592  
Twenty on hundred sixteen rupees & forty one paisa only)

22 Prepairng surface and painting of doors and widows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c ) P. 76 (ii) ).

400.00 @ Rs: 2,116.41 % Sft Rs: 8,466  
( Twenty one hundred sixteen rup & forty one paisa only)

23 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)

1362.00 @ Rs: 1,887.40 % Sft Rs: 25,706  
( Eighteen hundred eighty seven rupees & forty paisa only)

24 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

2.468 @ Rs: 3,550.00 P. Sft Rs: 8,761  
(Three Thousand Five hundred Fifty rupees & only)

25 Cutting & Fixing iron bars for barred windows.

52.00 @ Rs: 28.23 P. Sft Rs: 1,468  
( Twenty Eihgt rupees & Twenty Three Paisa only)

**Total Rs. 1,802,140**

  
**XEN**



52

**SCHEDULE 'B'**

Name of Work:- Provision of missing facilities (Compound wall, Lavatory Block & Additional Class Rooms) to existing Elementary Schools of Taluka Ratodero District Larkano (12 Units) (2015-16 Programme) at: GBPS Mehar Buriro (2 C/R) ( Electric). ADP 360

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	22.00	@ Rs:	910	P.Point	Rs: 20,020.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs:	742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68	@ Rs:	171	P.Meter	Rs: 11628.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	66.00	@ Rs:	428	P.Meter	Rs: 28248.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	22.00	@ Rs:	54	P.Each	Rs: 1,188.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs:	83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	16.00	@ Rs:	70	P.Each	Rs: 1,120.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	7.00	@ Rs:	72	P.Each	Rs: 504.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs:	162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	5.00	@ Rs:	916	P.No	Rs: 4,580.00

Part "A" TOTAL: Rs: 69,925.0

  
**XEN**

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
------	--------------	------	--	------	------	---------

**Part "B" (Old Schedule 2004)**

- |    |  |       |       |         |          |               |
|----|--|-------|-------|---------|----------|---------------|
| 11 | Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)   | 6.00  | @ Rs: | 91      | Each     | Rs: 546.00    |
| 12 | Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)  | 6.00  | @ Rs: | 141.71  | P.Each   | Rs: 850.26    |
| 13 | Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)   | 1.00  | @ Rs: | 1426.34 | P.Sq:ft: | Rs: 1,426.34  |
| 14 | P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27). | 1.00  | @ Rs: | 3341    | P.Set    | Rs: 3,341.00  |
| 15 | P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)   | 16.00 | @ Rs: | 497     | P.Each   | Rs: 7,952.00  |
| 16 | P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).   | 6.00  | @ Rs: | 497     | Each     | Rs: 2,982.00  |
| 17 | Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/1.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)   | 6.00  | @ Rs: | 5500    | P.No     | Rs: 33,000.00 |

**Part "B" TOTAL:** Rs: 50,097.6

**Part "A" TOTAL:** Rs: 69,925.0

**G: TOTAL:** Rs: 120,022.6

  
**XEN**

## Schedule-B

53

Name of  
Work:-

**PROVISION OF MISSING FACILITIES (C/WALL, LAV: BLOCK & ADD: C/R) TO  
EXISTING ELEMENTARY SCHOOLS OF TALUKA RATODERO DISTRICT  
LARKANO (12 UNITS) (2015-16 PROGRAMME) @ GBPS WARIS DINO MACHI  
(01 C/R) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		848.00	@ Rs: 3,176.25 % 0Cft		Rs: 2,693
			(Thirty one Hundred seventy six rup: & twenty five paisa only)		
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)				
		308.00	@ Rs: 8,694.95 % Cft		Rs: 26,780
			(Eighty six hund: ninty four rup: & ninty five paisa only)		
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
		669.00	@ Rs: 11,948.36 % Cft		Rs: 79,935
			(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)		
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
		513.24	@ Rs: 337.00 P.Cft		Rs: 172,962
			(Three hundred Thirty seven rup: only)		
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No. 8 (b) P/16)				
		22.913	@ Rs: 5,001.70 P.Cwt		Rs: 114,604
			( Five thousand one rup: & seventy paisa only)		
6	Filling watering and ramming earth in floor with surplus earth from foundation laed upto one chain and lift upto 5 ft. (S.I.No: 2 P/5).				
		565.330	@ Rs: 1,512.50 0.Cft		Rs: 855
			(Fifteen hundred twelve rup: & fifty paisa only)		
7	Supply and fixing sand under floor including plugging in to walls				
		1100.00	@ Rs: 1,141.25 % Cft		Rs: 12,554
			(Eleven hundred forty one rupees & twenty five paisa only)		
9	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.				
		1269.19	@ Rs. 12,674.36 % Cft		Rs. 160,862
			(Twelve thousand six hundred seventy four rup: & thity six paisa only)		
10	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
		1965.00	@ Rs. 2,206.60 % Cft		Rs. 43,360

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(Twenty tow hund: six rup: & sixty paisa only)

- 11 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

1965.00 @ Rs: 2,197.52 % Sft Rs: 43,181  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

- 12 Making Notice board made with cement.

32.00 @ Rs: 58.11 P. Sft Rs: 1,860  
(Nnety Three rupees & Thirty Seven paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

28.00 @ Rs: 228.90 P. Rft Rs: 6,409  
(Two hundred twenty eight rupees & ninty paisa only)

- P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools

96.00 @ Rs: 240.50 P. Rft Rs: 23,088  
(Two hundred forty rupees & fifty paisa only)

- 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

76.00 @ Rs: 902.93 P. Sft Rs: 68,623  
(Nine hund: two rup: & ninty three paisa only)

- 16 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

839.38 @ Rs: 1,287.44 % Sft Rs: 10,807  
(Twelve hundred eighty seven rupees & forty for paisa only)

- Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

98.00 @ Rs: 180.50 P. Sft Rs: 17,689  
( One hundre ninty four rupees & sixteen paisa only)

- 18 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

0.950 @ Rs: 3,550.00 P. Sft Rs: 3,373  
(Three Thousand Five hundred Fifty rupees & only)

- 19 Cutting & Fixing iron bars for barred windows.

20.00 @ Rs. 28.23 P. Sft Rs. 565  
( Twenty Eihgt rupees & Twenty Three Paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 P & Single per layer of polythene sheet 0.13 mm thick for water proging as per specification

125.00 @ Rs. 10.70 P.Sft Rs. 1,338  
(Ten rupees & seventy paia only)

21 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

440.00 @ Rs: 4,411.82 % Sft Rs: 19,412  
( Forry four hundred eleven rup: & eighty two paia only)

**(B) 1-1/2" Thick.**

720.00 @ Rs: 3,275.50 Rs: 23,584  
(Thirty Two hundred Seventy Five rup: & Fifty paia only)

22 Primary coat of chalk distemper( S.I No. 23 P/53)

1965.17 @ Rs: 442.75 % Sft Rs: 8,701  
(Four hundred forty two rupees & seventy five paia only)

23 Distemping Three Coats (S.I No. 24 ©P/53)

1965.17 @ Rs: 1,079.65 % Sft Rs: 21,217  
(One thousand Seventy nine rup: & sixty five paia only)

24 White wash Three Coats (S.I No. 26 © P/53)

440.00 @ Rs: 829.95 % Sft Rs: 3,652  
(Eight hundred twenty nine rup: & ninty five paia only)

25 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

839.38 @ Rs. 1,948.10 % Sft Rs. 16,352  
Twenty on hundred sixteen rupees & forty one paia only)

**Total Rs.**

**879,980**

  
**XEN**

**SCHEDULE 'B'**

54

Name of Work:- Provision of missing facilities (Compound wall, Lavatory Block & Additional Class Rooms) to existing Elementary Schools of Taluka Ratodero District Larkano (12 Units) (2015-16 Programme) at: GBPS Waris Dino Mashi (1 C/R) ( Electric). ADP 360

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	12.00	@ Rs: 910	P.Point	Rs: 10,920.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	36.00	@ Rs: 171	P.Meter	Rs: 6156.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-1.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	32.00	@ Rs: 428	P.Meter	Rs: 13696.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	12.00	@ Rs: 54	P.Each	Rs: 648.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	9.00	@ Rs: 70	P.Each	Rs: 630.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	4.00	@ Rs: 72	P.Each	Rs: 288.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	3.00	@ Rs: 916	P.No	Rs: 2,748.00

Part "A" TOTAL: Rs: 36,898.0

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	3.00	@ Rs: 91	Each	Rs: 273.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	3.00	@ Rs: 141.71	P.Each	Rs: 425.13
13	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs: 1426.34	P.Sq.ft:	Rs: 1,426.00
14	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	9.00	@ Rs: 497	P.Each	Rs: 4,473.00
15	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod. cannopy blade. suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	3.00	@ Rs: 5500	P.No	Rs: 16,500.00

Part "B" TOTAL: Rs: 23,097.1

Part "A" TOTAL: Rs: 36,898.0

G: TOTAL: Rs: 59,995.1



## Schedule-B

**CONSTRUCTION / RECONSTRUCTION OF DANGEROUS PRIMARY SCHOOL**  
**Name of Work:- BUILDINGS OF TALUKA RATODEOR (08 UNITS) (2015-16 PROGRAMME)**  
**@GBPS SUHRAB MACHI TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 1 Removing cement or lime plaster. (S.I No. 53 P/13)

5008 @ Rs: 121.00 % Cft Rs: 6,060  
 ( One hundred & twenty rup: only)

- 2 Dismantling cement concrete plain Ratio 1:2:4

485 @ Rs: 3,327.50 % Cft Rs: 16,138  
 ( Thirty three hundred twenty seven rup:& fifty paisa only)

- 3 Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)

1056 @ Rs: 8,694.95 % Cft Rs: 91,819  
 (Eighty six hund: ninty four rup: & ninty five paisa only)

- 4 Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)

5008 @ Rs. 2,206.60 % Cft Rs. 110,507  
 (Twenty tow hund: six rup: & sixty paisa only)

- 5 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

5008 @ Rs: 2,197.52 % Sft Rs: 110,052  
 (Twenty one hund: ninty seven rup: & fifty two paisa only)

- 6 Removing Doors with Chowkats (S.I.No. 33 (a) P/12)

56 @ Rs: 142.18 P.Sft. Rs: 7,962  
 (One hundred forty two rupees & eighteen paisa only)

- 7 Removing Windows with Chowkats (S.I.No. 33 (a) P/12)

80 @ Rs: 102.85 P.Sft. Rs: 8,228  
 (One hundred two rupees & eighty five paisa only)

- 8 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

5080.00 @ Rs: 4,411.82 % Sft Rs: 224,120  
 ( Forry four hundred eleven rup: & eighty two paisa only)

- (B) 2" Thick.

3776.25 @ Rs: 3,275.50 % Sft Rs: 123,691  
 (Thirty Two hundred Seventy Fine rup: & Fifty paisa only)

- 9 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)

3776.25 @ Rs. 1,887.40 % Sft Rs. 71,273  
 ( Eighteen hundred eighty seven rupees & forty paisa only)

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 10 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.
- 184.48 @ Rs. 14,429.25 % Cft Rs. 26,619
- P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and
- 11 stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)
- 2836.00 @ Rs. 30,509.77 % Sft Rs. 865,257  
(Thirty thousand five hund: nine rupees & seventy seven paisa only)
- 12 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and reparing the jambs. The cost also i/c all carriage, tools and pla
- 56 @ Rs: 228.90 P. Rft Rs: 12,818  
(Two hundred twenty eight rupees & ninty paisa only)
- 13 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and reparing the jambs. The cost also i/c all carriage, tools and pla
- 48.00 @ Rs: 240.50 P. Rft Rs: 11,544  
(Two hundred forty rupees & fifty paisa only)
- 14 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)
- 92 @ Rs: 902.93 P. Sft Rs: 83,070  
(Nine hund: two rup: & ninty three paisa only)
- Supply & Fixing in Position iron/steel grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)
- 20.00 @ Rs: 180.50 P. Sft Rs: 3,610  
( One hundre ninty four rupees & sixteen paisa only)
- 17 Providing and fixing iron steel grill door with angle iron frame of 1 1/2" x 1 1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in charg.(S.I No. 31 P No. 93)
- 51.00 @ Rs. 231.60 P. Sft Rs. 11,812  
( Two hundred thiry one rup: & sixty Paisa only)
- 18 Prepairing surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c ) P. 76 (ii) ).
- 1719 @ Rs: 2,116.41 % Sft Rs: 36,381  
( Twenty one hundred sixteen rup & forty one paisa only)
- 19 Primary coat of chalk distemper( S.I No. 23 P/53)
- 10412 @ Rs: 442.75 % Sft Rs: 46,099  
(Four hundred forty two rupees & seventy five paisa only)



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 Distempering two coats.( S.I No. 24(b) P/54)

8372 @ Rs: 1,043.90 % Sft Rs: 87,395  
( One thousand forty three rup: & ninty paisa only)

21 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)

1964.5 @ Rs: 1,948.10 % Sft Rs: 38,270  
( Ninteen hundred forty eight rupees & ten paisa only)

Total Rs: 1,990,725

  
XEN

## Schedule-B

**CONSTRUCTION OF DANGEROUS PRIMARY SCHOOL BUILDINGS OF  
Name of Work:- TALUKA RATODERO (08 UNITS) (2015-16 PROGRAMME) @GBPS  
NAZAR DETHO TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 20 P/10)				
		574.00	@ Rs. 5,445.00 % Cft		Rs. 31,254
			(Fifty four hundred & forty five rupees only)		
2	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)				
		1372.00	@ Rs: 1,285.63 % Cft		Rs: 17,639
			( Twelve hundred eighty five rup & sixty three paisa only)		
3	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		412.00	@ Rs: 3,176.25 % 0Cft		Rs: 1,309
			(Thirty one Hundred seventy six rup: & twenty five paisa only)		
4	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)				
		225.00	@ Rs: 8,694.95 % Cft		Rs: 19,564
			(Eighty six hund: ninty four rup: & ninty five paisa only)		
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
		643.00	@ Rs: 11,948.36 % Cft		Rs: 76,828
			(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)		
6	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
		412.00	@ Rs: 337.00 P.Cft		Rs: 138,844
			(Three hundred Thirty seven rup: only)		
7	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)				
		18.393	@ Rs: 5,001.70 P.Cwt		Rs: 91,996
			( Five thousand one rup: & seventy paisa only)		
8	Supply and fixing sand under floor including plugging in to walls				
		638.00	@ Rs: 1,141.25 % Cft		Rs: 7,281
			(Eleven hundred forty one rupees & twenty five paisa only)		
9	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.				
		1076.00	@ Rs. 12,674.36 % Cft		Rs. 136,376
			(Twelve thousand six hundred seventy four rup: & thity six paisa only)		
10	Supplying of Girders at Site of Work ( Schedule of Material).				
		16.839	@ Rs. 3,850.00 P.Cwt		Rs. 64,830
			(Thirty Eight Hundred & Fifty Rupees only)		

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

11 Supplying of T-Iron at Site of Work (Schedule of Material).

17.089 @ Rs. 3,575.00 P.Cwt Rs. 61,093  
(Thirty Five Hundred & Seventy five Rupees only)

12 Errection of Rolled Steel Beam etc (S.I No. 6 P/91).

33.929 @ Rs. 186.34 P.Cwt Rs. 6,322  
(One Hundred & Eighty Six Rupees Thirty Four Pessas only)

13 First Class Tile Roofing consiisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layer of tile 12" x6" x1-1/4" laid in 1:6 cement mortar with 1/2" wiched layer of 1:6 cement mortar incliding 1:2 cement pointin underside of tiles complete incliding curing etc (S.I No. 1 P/33).

1100.00 @ Rs: 11,443.10 % Sft Rs: 125,874  
(Eleven Thousand Forty hundred Forty Three rup: & Ten paisa only)

14 Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.

689.00 @ Rs. 12,346.65 % Cft Rs. 85,068  
(Twelve thousand three hund: forty six rup: & sixty five paisa only)

15 Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)

2369.00 @ Rs. 2,206.60 % Cft Rs. 52,274  
(Twenty tow hund: six rup: & sixty paisa only)

16 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

2369.00 @ Rs: 2,197.52 % Sft Rs: 52,059  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

17 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

1659.00 @ Rs: 1,287.44 % Sft Rs: 21,359  
(Twelve hundred eighty seven rupees & forty for paisa only)

18 Providing and laying single per layer of poly then sheet 0.13 mm thick for water proofing as per specification and Instruction of Engineer in charge. (S.I.No: 38 P.44).

1102.00 @ Rs: 10.70 P.Cft Rs: 11,791  
(Ten rupees & seventy paisa only)

19 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

1432.00 @ Rs: 4,411.82 % Sft Rs: 63,177  
( Forry four hundred eleven rup: & eighty two paisa only)

(B) **2" Thick.**

78.00 @ Rs: 3,275.50 % Sft Rs: 2,555  
(Thirty Two hundred Seventy Fine rup: & Fifty paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jams. The cost also i/c all carriage, tools and pla

71.00 @ Rs: 228.90 P. Rft Rs: 16,252  
(Two hundred twenty eight rupees & ninty paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
21	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla	180.00	@ Rs: 240.50	P. Rft	Rs: 43,290
	(Two hundred forty rupees & fifty paisa only)				
22	1 <sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)	88.16	@ Rs: 902.93	P. Sft	Rs: 79,602
	(Nine hund: two rup: & ninty three paisa only)				
23	Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complete ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)	233.00	@ Rs: 180.50	P. Sft	Rs: 42,057
	( One hundre ninty four rupees & sixteen paisa only)				
24	Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.	39	@ Rs. 14,429.25	% Cft	Rs. 5,627
	(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)				
25	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.( S.I No. 23 P/45)	246.00	@ Rs. 27,678.86	% Cft	Rs. 68,090
	( Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)				
26	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	47.00	@ Rs. 28,253.61	% Cft	Rs. 13,279
	(Twenty seven thousand seven hund: forty seve rupp: & six paisa only)				
27	P/F ornamental Cement jali 2" thick (1:2:4) Without steel (S.I No. P/ ).	32.00	@ Rs: 226.02	P. Sft	Rs: 7,233
	(Two hundred Twenty Six rupees & Two paisa only)				
28	Making & fixing steel gated doors with 1 1/6" thick sheeting i/c angle iron frame 2"x2"x3/4" and square bars 4" centre to cement.	48.00	@ Rs. 726.72	P. Sft	Rs. 34,883
	(Seven hundred twenty six rupees & seventy two paisa only)				
29	Making Notice board made with cement.	64.00	@ Rs: 58.11	P. Sft	Rs: 3,719
	(Ninty Three rupees & Thirty Seven paisa only)				
30	White wash Three Coats (S.I No. 26 © P/53).	916.00	@ Rs: 829.95	% Sft	Rs: 7,602
	(Eight hundred twenty nine rup: & ninty five paisa only)				

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

31 Primary coat of chalk distemper( S.I No. 23 P/53)

10069.00 @ Rs: 442.75 % Sft Rs: 44,580  
(Four hundred forty two rupees & seventy five paisa only)

32 Distemping Three Coats (S.I No. 24 ©P/53)

10069.00 @ Rs: 1,079.65 % Sft Rs: 108,710  
(One thousand Seventy nine rup: & sixty five paisa only)

33 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper  
filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)

4110.00 @ Rs: 1,948.10 % Sft Rs: 80,067  
( Nineteen hundred forty eight rupees & ten paisa only)

34 Preparing surface and painting of doors and widows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c ) P. 76 (ii) ).

(a) 184.00 @ Rs: 2,116.41 % Sft Rs: 3,894  
( Twenty one hundred sixteen rup & forty one paisa only)

(b) **Old Surface.**

132.00 @ Rs: 1,212.21 % Sft Rs: 1,600  
(Twelve hundred twelve rup :& twenty one paisa only)

35 Preparing surface & painting Guard bars, gates/ iron bars gating, rakings (i/c standard braces etc) & lar  
open work. (New Surface) (S. I No. 5 (d) P/70)

96.00 @ Rs. 1,270.83 % Sft Rs. 1,220  
(Twelve Hundred seventy rupees & eithty three paisa only)

Total Rs: 1,629,200

  
XEN

## Schedule-B

57

Name of  
Work:-

**REHABILITATION OF EXISTING PRIMARY SCHOOLS IN TALUKA  
RATODERO DISTRICT LARKANO (11 UNITS) (2015-16 PROGRAMME)  
@GBPS BAQOO KHAN KHOSO (REPLACEMENT OF SLAB) (ADP NO. 363)  
TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 1 Dismantling 2nd Class tile roofing (S.I No. 22 (b) P/11)

1066 @ Rs: 378.13 % Cft Rs: 4,031  
(Three Hundred Seventy eight rup & Thirteen paisa only)

- 2 Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 20 P/10)

92.00 @ Rs. 5,445.00 % Cft Rs. 5,009  
(Fifty four hundred & forty five rupees only)

- 3 Dismantling rooled steel (S.I No. 42 P/13).

22.321 @ Rs: 126.04 P.Cwt Rs: 2,813  
(One hundred twenty six rupees & four paisa only)

- 4 Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)

2227.00 @ Rs: 1,285.63 % Cft Rs: 28,631  
(Twelve hundred eighty five rup & sixty three paisa only)

- 5 Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.

13 @ Rs: 3,176.25 % OCft Rs: 41  
(Thirty one Hundred seventy six rup: & twenty five paisa only)

- 6 Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)

289 @ Rs: 8,694.95 % Cft Rs: 25,128  
(Eighty six hund: ninty four rup: & ninty five paisa only)

- 7 Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.

188.00 @ Rs: 11,948.36 % Cft Rs: 22,463  
(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)

- 8 RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)

268.00 @ Rs: 337.00 P.Cft Rs: 90,316  
(Three hundred Thirty seven rup: only)

- Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)

11.964 @ Rs: 5,001.70 P.Cwt Rs: 59,840  
(Five thousand one rup: & seventy paisa only)

XEN

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 10 Supply and fixing sand under floor including plugging in to walls

1696.00 @ Rs. 1,141.25 % Cft Rs. 19,356  
(Eleven hundred forty one rupees & twenty five paisa only)

- 11 Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.

2227 @ Rs. 12,674.36 % Cft Rs. 282,258  
(Twelve thousand six hundred seventy four rup: & thity six paisa only)

- 12 Supplying of Girders at Site of Work ( Schedule of Material).

19.642 @ Rs. 3,850.00 P.Cwt Rs. 75,622  
(Thirty Eight Hundred & Fifty Rupees only)

- 13 Supplying of T-Iron at Site of Work (Schedule of Materral).

17.973 @ Rs. 3,575.00 P.Cwt Rs. 64,253  
(Thirty Five Hundred & Seventy five Rupees only)

- 14 Errection of Rolled Steel Beam etc (S.I No. 6 P/91).

37.615 @ Rs. 186.34 p.Cwt Rs. 7,009  
(Eleven thousand four hund: forty three rup: & ten paisa only)

- 15 P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification

1115 @ Rs. 10.70 P.Sft Rs. 11,931  
(Ten rupees & seventy paisa only)

- 16 First Class Tile Roofing consiisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layer of tile 12" x6" x1-1/4" laid in 1:6 cement mortar with 1/2" wi

1115 @ Rs. 11,443.10 % Cft Rs. 127,591  
(Eleven thousand four hund: forty three rup: & ten paisa only)

- 17 Reinforcement Cement Concrete spout including fixing in position 2 1/2" x6"x5".

4 @ Rs. 261.25 P.No. Rs. 1,045  
(Two hundred sixty one rupees & twenty five paisa only)

- 18 Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)

3650 @ Rs. 2,206.60 % Cft Rs. 80,541  
(Twenty tow hund: six rup: & sixty paisa only)

- 19 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

3594 @ Rs. 2,197.52 % Sft Rs. 78,979  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

  
XEN

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 Making Notice board made with cement.

56 @ Rs: 58.11 P. Sft Rs: 3,254  
(Ninty Three rupees & Thirty Seven paisa only)

21 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

18 @ Rs: 228.90 P. Rft Rs: 4,120  
(Two hundred twenty eight rupees & ninty paisa only)

22 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

87.00 @ Rs: 240.50 P. Rft Rs: 20,924  
(Two hundred forty rupees & fifty paisa only)

23 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

64 @ Rs: 902.93 P. Sft Rs: 57,788  
(Nine hund: two rup: & ninty three paisa only)

24 M.S Barred Windows Squars Bars 5/8" Dia.

1.00 @ Rs: 3,550.00 P. Sft Rs: 3,550  
(Thrity Five hundred & fifty rupees only)

25 Cutting and fixing iron bars for barred windows.

21.00 @ Rs: 28.23 P. Sft Rs: 593  
(Twenty Eight rupees & Twenty Three paisa only)

26 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

848.00 @ Rs: 4,411.82 % Sft Rs: 37,412  
( Forry four hundred eleven rup: & eighty two paisa only)

27 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

880.00 @ Rs: 1,287.44 % Sft Rs: 11,329  
(Twelve hundred eighty seven rupees & forty for paisa only)

28 White wash Threc Coats (S.I No. 26 © P/53)

848 @ Rs: 829.95 % Sft Rs: 7,038  
(Eight hundred twenty nine rup: & ninty five paisa only)

  
**XEN**



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

29 Primary coat of chalk distemper (S.I No. 23 P/53)

4474 @ Rs: 442.75 % Sft Rs: 19,809  
(Four hundred forty two rupees & seventy five paisa only)

30 Distemping Three Coats (S.I No. 24 P/53)

4474 @ Rs: 1,079.65 % Sft Rs: 48,304  
(One thousand Seventy nine rup: & sixty five paisa only)

31 Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.

957 @ Rs. 1,270.83 % Sft Rs. 12,162  
(Twelve Hundred seventy rupees & eighty three paisa only)

32 Preparing surface and painting of doors and windows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).

104 @ Rs: 2,116.41 % Sft Rs: 2,201  
( Twenty one hundred sixteen rup & forty one paisa only)

Total Rs: 1,215,340

  
XEN

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

**PART-B**

P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19' clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605  
(Forty Eight hundred Two rup: & Sixty paisa only)

2 S/F concealed stop cock of superior quality with C.P head 1/2" dia.

2.0 @ Rs: 889/46 P.No Rs: 1,779  
(Eight hundred Eighty Nine rup: & Forty Six paisa only)

3 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.0 @ Rs: 1384/24 P.No Rs: 2,768  
(Thirteen hundred Eighty Four rup: & Twenty Four paisa only)

4 Providing & Fixing Handle valve (China)

2.0 @ Rs: 365.42 P.No Rs: 731  
(Seven hundred Seventy Seven rup: & Eighty paisa only)

**G.Total: Rs: 14,883**

**(B) N.S.I**

1 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

**(a) Filter** 10.0 @ Rs: 76/05 P.Rft Rs: 760  
(Seventy Six rup: & Five Pessa only)

**(b) G.I Pipe** 90.0 @ Rs: 77 P.Rft Rs: 5,390  
(Tharty Eight Six rup: & Ninety Five Pessa only)

**( C ) Machine** 1.0 @ Rs: 4500 Each Rs: 4,500  
(Fourteen Hund: Forty One rup: & Sixty Five Pessa only)

**G.Total: Rs: 10,650**

S.I	Rs.	14,883
N.S.I	Rs.	10,650
<b>G.Total:</b>	<b>Rs.</b>	<b>25,533</b>

**XEN**

## Schedule-B


58

**REHABILITATION OF EXISTING PRIMARY SCHOOLS IN TALUKA**  
**Name of Work:- RATODERO DISTRICT LARKANO (11 UNITS) (2015-16 PROGRAMME)**  
**@GBPS USMAN UNAR TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling 2nd Class tile roofing (S.I No. 22 (b) P/11)				
		1066	@ Rs: 378.13 % Cft		Rs: 4,031
	(Three Hundred Sevent eight rup & Thirteen paisa only)				
2	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 20 P/10)				
		92.00	@ Rs. 5,445.00 % Cft		Rs. 5,009
	(Fifty four hundred & forty five rupees only)				
3	Dismantling rooled steel (S.I No. 42 P/13).				
		22.321	@ Rs: 126.04 P.Cwt		Rs: 2,813
	(One hundred twenty six rupees & four paisa only)				
4	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)				
		2227.00	@ Rs: 1,285.63 % Cft		Rs: 28,631
	( Twelve hundred eighty five rup & sixty three paisa only)				
5	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		13	@ Rs: 3,176.25 % OCft		Rs: 41
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
6	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)				
		289	@ Rs: 8,694.95 % Cft		Rs: 25,128
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
7	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
		188.00	@ Rs: 11,948.36 % Cft		Rs: 22,463
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
8	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
		268.00	@ Rs: 337.00 P.Cft		Rs: 90,316
	(Three hundred Thirty seven rup: only)				
	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)				
9		11.964	@ Rs: 5,001.70 P.Cwt		Rs: 59,840
	( Five thousand one rup: & seventy paisa only)				

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
10	Supply and fixing sand under floor including plugging in to walls				
	1696.00 @ Rs. 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)			Rs.	19,356
11	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.				
	2227 @ Rs. 12,674.36 % Cft (Twelve thousand six hundred seventy four rup: & thirty six paisa only)			Rs.	282,258
12	Supplying of Girders at Site of Work ( Schedule of Material).				
	19.642 @ Rs. 3,850.00 P.Cwt (Thirty Eight Hundred & Fifty Rupees only)			Rs.	75,622
13	Supplying of T-Iron at Site of Work (Schedule of Material).				
	17.973 @ Rs. 3,575.00 P.Cwt (Thirty Five Hundred & Seventy five Rupees only)			Rs.	64,253
14	Errrection of Rolled Steel Beam etc (S.I No. 6 P/91).				
	37.615 @ Rs. 186.34 p.Cwt (Eleven thousand four hund:forty three rup: & ten paisa only)			Rs.	7,009
15	P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification				
	1115 @ Rs. 10.70 P.Sft (Ten rupees & seventy paisa only)			Rs.	11,931
16	First Class Tile Roofing consiisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layer of tile 12" x6" x1-1/4" laid in 1:6 cement mortar with 1/2" wi				
	1115 @ Rs. 11,443.10 % Cft (Eleven thousand four hund:forty three rup: & ten paisa only)			Rs.	127,591
17	Reinforcement Cement Concrete spout including fixing in position 2 1/2" x6"x5".				
	4 @ Rs. 261.25 P.No. (Two hundred sixty one rupees & twenty five paisa only)			Rs.	1,045
18	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
	3650 @ Rs. 2,206.60 % Cft (Twenty tow hund: six rup: & sixty paisa only)			Rs.	80,541
19	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)				
	3594 @ Rs. 2,197.52 % Sft (Twenty one hund: ninty seven rup: & fifty two paisa only)			Rs.	78,979



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 Making Notice board made with cement.

56 @ Rs: 58.11 P. Sft Rs: 3,254  
(Ninty Three rupees & Thirty Seven paisa only)

21 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

18 @ Rs: 228.90 P. Rft Rs: 4,120  
(Two hundred twenty eight rupees & ninty paisa only)

22 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

87.00 @ Rs: 240.50 P. Rft Rs: 20,924  
(Two hundred forty rupees & fifty paisa only)

23 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

64 @ Rs: 902.93 P. Sft Rs: 57,788  
(Nine hund: two rup: & ninty three paisa only)

24 M.S Barred Windows Squars Bars 5/8" Dia.

1.00 @ Rs: 3,550.00 P. Sft Rs: 3,550  
(Thrity Five hundred & fifty rupees only)

25 Cutting and fixing iron bars for barred windows.

21.00 @ Rs: 28.23 P. Sft Rs: 593  
(Twenty Eight rupees & Twenty Three paisa only)

26 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

848.00 @ Rs: 4,411.82 % Sft Rs: 37,412  
( Forry four hundred eleven rup: & eighty two paisa only)

27 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

880.00 @ Rs: 1,287.44 % Sft Rs: 11,329  
(Twelve hundred eighty seven rupees & forty for paisa only)

28 White wash Three Coats (S.I No. 26 © P/53)

848 @ Rs: 829.95 % Sft Rs: 7,038  
(Eight hundred twenty nine rup: & ninty five paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

29 Primary coat of chalk distemper( S.I No. 23 P/53)

4474 @ Rs: 442.75 % Sft Rs: 19,809  
(Four hundred forty two rupees & seventy five paisa only)

30 Distemping Three Coats (S.I No. 24 ©P/53)

4474 @ Rs: 1,079.65 % Sft Rs: 48,304  
(One thousand Seventy nine rup: & sixty five paisa only)

31 Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.

957 @ Rs. 1,270.83 % Sft Rs. 12,162  
(Twelve Hundred seventy rupees & eithy three paisa only)

32 Prepairng surface and painting of doors and widows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).

104 @ Rs: 2,116.41 % Sft Rs: 2,201  
( Twenty one hundred sixteen rup & forty one paisa only)

Total Rs: 1,215,340

  
**XEN**

## Schedule-B

59

**REHABILITATION OF EXISTING PRIMARY SCHOOLS IN TALUKA**  
**Name of Work:-** **RATODERO DISTRICT LARKANO (11 UNITS) (2015-16 PROGRAMME)**  
**@GGPS JEHO BAZIGAR TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling 2nd Class tile roofing (S.I No. 22 (b) P/11)				
	1066 @ Rs: 378.13 % Cft (Three Hundred Sevent eight rup & Thirteen paisa only)			Rs:	4,031
2	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 20 P/10)				
	92.00 @ Rs. 5,445.00 % Cft (Fifty four hundred & forty five rupees only)			Rs.	5,009
3	Dismantling rooled steel (S.I No. 42 P/13).				
	22.321 @ Rs: 126.04 P.Cwt (One hundred twenty six rupees & four paisa only)			Rs:	2,813
4	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)				
	2227.00 @ Rs: 1,285.63 % Cft ( Twelve hunred eighty five rup & sixty three paisa only)			Rs:	28,631
5	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
	13 @ Rs: 3,176.25 % OCft (Thirty one Hundred seventy six rup: & twenty five paisa only)			Rs:	41
6	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)				
	289 @ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)			Rs:	25,128
7	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
	188.00 @ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)			Rs:	22,463
8	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
	268.00 @ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)			Rs:	90,316
9	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)				
	11.964 @ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)			Rs:	59,840

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

10 Supply and fixing sand under floor including plugging in to walls

1696.00 @ Rs. 1,141.25 % Cft Rs. 19,356  
(Eleven hundred forty one rupees & twenty five paisa only)

11 Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.

2227 @ Rs. 12,674.36 % Cft Rs. 282,258  
(Twelve thousand six hundred seventy four rup: & thity six paisa only)

12 Supplying of Girders at Site of Work ( Schedule of Material).

19.642 @ Rs. 3,850.00 P.Cwt Rs. 75,622  
(Thirty Eight Hundred & Fifty Rupees only)

13 Supplying of T-Iron at Site of Work (Schedule of Material).

17.973 @ Rs. 3,575.00 P.Cwt Rs. 64,253  
(Thirty Five Hundred & Seventy five Rupees only)

14 Errection of Rolled Steel Beam etc (S.I No. 6 P/91).

37.615 @ Rs. 186.34 p.Cwt Rs. 7,009  
(Eleven thousand four hund:forty three rup: & ten paisa only)

15 P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification

1115 @ Rs. 10.70 P.Sft Rs. 11,931  
(Ten rupees & seventy paisa only)

16 First Class Tile Roofing consiisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layer of tile 12" x6" x1-1/4" laid in 1:6 cement mortar with 1/2" wi

1115 @ Rs. 11,443.10 % Cft Rs. 127,591  
(Eleven thousand four hund:forty three rup: & ten paisa only)

17 Reinforcement Cement Concrete spout including fixing in position 2 1/2" x6"x5".

4 @ Rs. 261.25 P.No. Rs. 1,045  
(Two hundred sixty one rupees & twenty five paisa only)

18 Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)

3650 @ Rs. 2,206.60 % Cft Rs. 80,541  
(Twenty tow hund: six rup: & sixty paisa only)

19 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

3594 @ Rs. 2,197.52 % Sft Rs. 78,979  
(Twenty one hund: ninty seven rup: & fifty two paisa only)





S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 Making Notice board made with cement.

56 @ Rs: 58.11 P. Sft Rs: 3,254  
(Ninty Three rupees & Thirty Seven paisa only)

21 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

18 @ Rs: 228.90 P. Rft Rs: 4,120  
(Two hundred twenty eight rupees & ninty paisa only)

22 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

87.00 @ Rs: 240.50 P. Rft Rs: 20,924  
(Two hundred forty rupees & fifty paisa only)

23 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

64 @ Rs: 902.93 P. Sft Rs: 57,788  
(Nine hund: two rup: & ninty three paisa only)

24 M.S Barred Windows Squars Bars 5/8" Dia.

1.00 @ Rs: 3,550.00 P. Sft Rs: 3,550  
(Thrity Five hundred & fifty rupees only)

25 Cutting and fixing iron bars for barred windows.

21.00 @ Rs: 28.23 P. Sft Rs: 593  
(Twenty Eight rupees & Twenty Three paisa only)

26 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

848.00 @ Rs: 4,411.82 % Sft Rs: 37,412  
( Forry four hundred eleven rup: & eighty two paisa only)

27 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

880.00 @ Rs: 1,287.44 % Sft Rs: 11,329  
(Twelve hundred eighty seven rupees & forty for paisa only)

28 White wash Three Coats (S.I No. 26 © P/53)

848 @ Rs: 829.95 % Sft Rs: 7,038  
(Eight hundred twenty nine rup: & ninty five paisa only)

  
XEN

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

29 Primary coat of chalk distemper( S.I No. 23 P/53)

4474 @ Rs: 442.75 % Sft Rs: 19,809  
(Four hundred forty two rupees & seventy five paisa only)

30 Distemping Three Coats (S.I No. 24 ©P/53)

4474 @ Rs: 1,079.65 % Sft Rs: 48,304  
(One thousand Seventy nine rup: & sixty five paisa only)

31 Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.

957 @ Rs. 1,270.83 % Sft Rs. 12,162  
(Twelve Hundred seventy rupees & eithty three paisa only)

32 Prepairing surface and painting of doors and widows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c ) P. 76 (ii) ).

104 @ Rs: 2,116.41 % Sft Rs: 2,201  
( Twenty one hundred sixteen rup & forty one paisa only)

Total Rs: 1,215,340



## SCHEDULE "B"

### Name of Work:-

Integrated Rehabilitation of Primary Schools & Provision of  
Missing Facilities Taluka Bakrani (12-Units)(2015-16 Prog)  
At : GGPS Bakrani ( C/Wall ) Taluka Bakrani

S.N	Description	Qty:	Rate		Amount
1	Removing cement or lime plaster. (S.I.No 53 P/14)				
			=	<b>507</b>	
		@ Rs: 121.00	%SFT	Rs: 613.47	
	( One hundred & twenty rup: only)				
2	Excavation in foundation of building bridges and other structure member with excavated le chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).				
			=	<b>1396</b>	
		@ Rs: 3176.25	%0 CFT	Rs: 4,434.0	
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16				
			=	<b>580</b>	
		@ Rs: 8694.95	% CFT	Rs: 50,431	
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
5	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 2				
			=	<b>1066</b>	
		@ Rs: 11948.36	% CFT	Rs: 127370	
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or p laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a) P/18)				
			=	<b>100</b>	
		@ Rs: 337.00	P.CFT	Rs: 33,700	
	(Three hundred Thirty seven rup: only)				
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)				
			=	<b>0.893</b>	
		@ Rs: 5001.70	P.CWT	Rs: 4,467	
	( Five thousand one rup: & seventy paisa only)				
8	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6				
			=	<b>500</b>	
		@ Rs: 12346.65	%SFT	Rs: 61,733	
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
9	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No				
			=	<b>75</b>	
		@ Rs: 12674.36	%SFT	Rs: 9,506	
	(Twelve thousand six hundred seventy four rup: & thity six paisa only)				
10	S/F sand floor and plugging into walls (S.I.No 29 P/31).				
			=	<b>75</b>	
		@ Rs: 1141.25	%SFT	Rs: 856	
	(Eleven hundred forty one rupees & twenty five paisa only)				
9	Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)				

S.No	Description	Qty:	Rate		Amount
------	-------------	------	------	--	--------

10 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)

= **75**

@ Rs: 2197.52 %SFT Rs: 1,648

(Twenty one hund: ninty seven rup: & fifty two paisa only)

11 Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.19 (a) P/53)

= **1108**

@ Rs: 1287.44 %SFT Rs: 14,265

(Twelve hundred eighty seven rupees & forty for paisa only)

12 Cemnet concret plain i/c placing compacting finishing and curring complete i/c screeing and stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)

= **11**

@ Rs: 14429.25 %SFT Rs: 1,587

(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)

13 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls R (S.I No:16 ( C ) P/46)

= **805**

@ Rs: 4411.82 %SFT Rs: 35,515

( Forry four hundred eleven rup: & eighty two paisa only)

(B) Ratio 2" thick,

= **111**

@ Rs: 3275.50 %SFT Rs: 3,636

(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

14 P/L Hala patteren tiles glazed 4"\*4 1/4" of floor of wall cacing in required pattern of cemer of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cemer desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to p ( S.I No: 62 P/53)

= **127**

@ Rs: 34520.31 %CFT Rs: 43,841

(Thirty four thousand five hundred twenty rupees & thirty one paisa only)

15 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c dec panelled and glazed (b) 1-3/4thicks.(Only Shutters)

= **18**

@ Rs: 902.93 P.CFT Rs: 22,928

(Nine hund: two rup: & ninty three paisa only)

16 Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement : i/c finishing complete (Flooring and Facing ) (S.I.No 69 P/55).

= **50**

@ Rs: 21021.11 %CFT Rs: 10,511

( Twenty one thousands twenty one rupes Eleven P.S only)

17 White wash three coats.

= **50**

@ Rs: 829.95 %CFT Rs: 415

(Eight hundred tv y nine rup: & ninty five paisa only)

S.No	Description	Qty:	Rate		Amount
------	-------------	------	------	--	--------

- 19 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat. Make New surface. (S.I.No 39 (a) P/62).

= **3640**

@ Rs: 1948.10 %CFT Rs: 70,911

Twenty on hundred sixteen rupees & forty one paisa only)

- 20 Distempering three coats ( S.I No: 24( B ) P 59)

= **360**

@ Rs: 1079.65 % Sft Rs: 3,758

(One thousand Seventy nine rup: & sixty five paisa only)

- 22 Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2 bars 4" centre to cement .

= **40**

@ Rs: 726.72 P.Sft Rs: 29,069

(Seven hundred twenty six rupees & seventy two paisa only)

- 23 Painting doors & window any type, (S.I.No 05 P/ 76)

= **70**

@Rs: 2116.41 %Cft Rs; 1,481

( Twenty one hundred sixteen rup & forty one paisa only)

**Total 535922**

  
XEN

## SCHEDULE-B

**Name of work:-** Constuction / Reconstruction of Dangerous of Primary Schools  
Taluka Dokri (8-Units ) (2015-16 Prog ) At : GBPS Muhammad Ali  
Burdi Taluka Dokri

S.n	Discription	Qty	Rate	Unit Rs	Amount
1	Dismantling R.C.C Work 1:2:4	767.0	@Rs: 5445.0	%Cft Rs:	41763 (Rs: Five thousand Four Hundred Forty Five on
2	Dismantling Pacca brick work in cement mortor ( s.no (a) P/10)	1154.0	@Rs: 1285.63	%Cft Rs:	14836 (Rs: Twolve thousand Eighty Five & P.S Sixty Thr
3	Excavation in foundation of building bridges and other structure member with excavate chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	35.00	@ Rs: 3176.25	%0 Cft Rs:	111 (Three Thousand One Hund:Seventy Six & P.S Twi
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) I	12.0	@Rs: 8694.95	% Cft Rs:	1043 ( Eight Thousand Six Hund:Ninty Four & P.S Ninty
5	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C	731.0	@ Rs: 11948.36	% S.ft Rs:	87343 ( Eleven Thousand Nine Hund: Fourty Eight & F
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	332.0	@Rs: 337.0	P.Cft Rs:	111884 ( Three Hundred Thirty Seven only)
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and layin i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	14.821	@ Rs: 5001.70	P.CWt Rs:	74130 (Five Thousand One &P.S Seventy ).
8	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S	854.0	@Rs: 12674.36	% Cft Rs:	108239 (Twlove thousand Six Hundred Seventy Four & 7
9	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio	900.0	@Rs: 12346.65	% Cft Rs:	111120 (Tolive Thousand Three Hundred Fourty Six & P.
10	Supplying Girders at site of work(Sch: of Material)	22.10	@ Rs: 3850.0	P.Cwt Rs:	85085 (Three Thousand Eight Hundred Fifty only)
11	Supplying T-iron at site of work (Sch: of Material).	18.92	@ Rs: 3375.0	P.Cwt Rs:	63855 (Three Thousand Three Hundred Seventy Five on
12	First class tiles roofing consisting of 4" earth and 1" plaster wilth Gobri leeping over 1/1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" mortor with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)	1134.00	@ Rs: 11443.10	%Sft Rs:	129765 (Rs:Eleven thousand Four Hundred Fourty Three

**XEN**

S.n	Discription	Qnty	Rate	Unit	Rs	Amount
13	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	3921.0	@Rs; 2206.60	% Sft	Rs:	86521 ( Two hundred Three Hund: Fifty Six & P.S Sever
14	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)	3921.0	@ Rs: 2197.52	%S.ft	Rs:	86165 ( Two Twousand One Hund: Ninty Seven & P.S Fil
15	Notice board made with cement.	64.0	@Rs; 58.11	P.Sft	Rs:	3719 ( Fifty Eight Eleven rupes only)
16	Cement pointing and stricking of joints on walls ratio. 1: 2 ( S.I No.19 (a) P/53)	1574.0	@ Rs: 1287.44	%Cft	Rs:	20264 ( Twolive Thousand Eighty Seven & P.S Fourty Fo
17	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c panelled and glazed (b) 1-3/4thicks.	95.0	@ Rs: 902.93	P.Sft	Rs:	85778 ( Nine Hundrad Two P.S Ninty Three only)
18	S/F iron steel grill 1/4"*3/4" size flate iron of approved made shade in 3 white weight t lbs:/Sq:/Ft: of finished grill.	235.0	@ Rs: 180.50	%C.ft	Rs:	42,418 (Rs:One Hndrad Eighty & P.S Fifty )
19	S/F sand floor and plugging into walls (S.I.No 29 P/31).	3465.0	@Rs: 1141.25	%Cft	Rs:	39544 (Rs:One Thousand One Hund: Fourty One & P.S T
20	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenl	1002.0	@ Rs: 4411.82	% S.ft	Rs:	44206 (Rs: Four Thousand Four Hundred Eleven & P.S Ei
21	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" squar	48.0	@ Rs: 726.72	%Sft	Rs:	34,883 (Rs: Seven Hundred Twenty Six & P.S Seventy Tw
22	White wash three coats (S.I.No 26 ( c ) 59).	948.0	@Rs: 829.95	% Sft	Rs:	7868 (Rs: Eight hundred twenty nine rupes & P.S Nine f
23	Distemping three coats, (S.I.No 24 (b) P/59)	4963.0	@ Rs: 1079.65	% Sft	Rs:	53583 (Rs: One Thousand Seventy Nine & P.S Sixty Five
24	Painting doors & Window any type.	374.0	@ Rs: 2116.41	%Cft	Rs:	7915 (Rs:Two Thousand one Hund: Sixteen & P.S Fourt
25	Preparing surface painting guards bars gates iron grating railing i/c standards brass et (S.I.No 4 d P/76 ii )	96.0	@Rs: 1270.83	%Cft	Rs:	1220 (Rs: One thousand two hundred rupes only)

Total	1343259
-------	---------

  
XEN

**SCHEDULE "B"**

Name of Work:- Construction Reconstruction of Dangerous Primary Schools Taluka Bakrani  
(08-Units)(2015-16 Prog) At : GBPS Ghulam Muhammad Buladi Taluka  
Bakrani

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
------	-------------	----------	------	------	----------	--------

1 Dismantling R.c.c work.

= 1362.00 Cft  
@Rs: 5445.00 % Cft Rs: 74161.00  
(Rs: Three Hundred Seventy Eight & P.S Thirteen only)

2 Dismantlin C.C plain 1:2:4. (S.I.No 19 (c) P/11).

= 121.00 CFT  
@Rs: 3327.50 % Cft Rs: 4026.00  
(Rs: Three thousands three hundred twenty five rupees Fifty P/S only)

3 Removing cementor lime Plaster 1:6. (S.I.No: 53 P 13 ).

= 805.00 Sft  
@Rs: 121.00 % Rs: 974.00  
(Rs: One Hunared Twenty One only)

4 Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 1p1).

= 560.00 CFT  
@Rs: 3176.25 %0 Cft Rs: 1779.00  
(Three Thousand One Hund:Seventy Six & P.S Twenty Five only)

5 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P- 14).

= 301.00 Cft  
@Rs: 8694.95 % Cft Rs: 26171.80  
( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)

6 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) P- 20.)

= 2197.00 Sft  
@Rs: 11948.36 % S.ft Rs: 262505.47  
( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six only)

7 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/16)

= 199.00 Pcft  
@Rs: 337.00 P.CFT Rs: 67063.00  
( Three Hundred Thirty Seven only)

8 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 8 (b) P/16)

= 8.884 Pcwt  
@Rs: 5001.70 P.CWT Rs: 44435.10  
(Five Thousand One &P.S Seventy ).

9 Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P/20)

= 225.00 CFT  
@Rs: 12674.36 %CFT Rs: 28517.31  
(Twlove thousand Six Hundred Seventy Four & Thirty Six only)

  
XEN



S.	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
----	-------------	----------	------	------	----------	--------

10 Supplying filling Sand under floor plugging into walls, (S.I.No 29 P/ 25).

= 322.00 Cft

@Rs: 1141.25 %Sft Rs: 3675.00

(Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)

11 Supplying Girders at site of work (Sch: of Material).

= 16.107 Cft

@Rs: 3850.00 P.CWT Rs: 62012.00

(Three Thousand Eight Hundred Fifty only)

12 Supplying T-iron at site of work (Sch: of Material).

= 19.008 Cft

@Rs: 3575.00 P.CWt Rs: 67954.00

(Three Thousand Three Hundred Seventy Five only)

13 1st class tilesroofing consisting of 4" earth and 1" plaster wilth Gobri leeping over 1/4" thick cement plaster 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in 1:6 cen mortor with 1/4" thick t

= 1100.30 SFT

@Rs: 11443.10 %SFT Rs: 125874.00

(Rs:Eleven thousand Four Hundred Fourty Three & P.S Ten )

14 Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 7 ( E ) P/

= 375.00 Cft

@Rs: 12346.65 %Cft Rs: 46299.94

(Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five only)

15 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.

= 79.00 SFT

@Rs: 902.93 P.SFT Rs: 71331.00

( Nine Hundraed Two P.S Ninty Three only)

16 Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13(b) P/57 )

= 3646.00 SFT

@Rs: 2206.60 %SFT Rs: 80453.00

( Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)

17 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 51)

= 3646.00 SFT

@Rs: 2197.52 %CFT Rs: 80122.00

( Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)

18 Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.11(a) P/51)

= 262.00 CFT

@Rs: 1287.44 %Cft Rs: 3373.09

( Twolive Thousand Eighty Seven & P.S Fourty Four only)

  
XEN

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
------	-------------	----------	------	------	----------	--------

- 19 S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete wi  
not to beless than 3.7 Lbs sq: ft: of finished grill.

= 126.00

@Rs: 194.16 P.SFT Rs: 24464.16  
(Rs: One hundred Ninty Four & P.S Sixteen only)

- 20 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick.  
(S.I No:16 ( C ) P/41)

= 675.00 Cft

@Rs: 4411.82 %Cft Rs: 29780.00  
(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)

- (b) P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2" thick.  
(S.I No:16 ( C ) P/41)

= 721.00 CFT

@Rs: 3275.50 %Cft Rs: 23616.36  
(Rs: Three Thousands two hundred seventy five rupes Fifty P.S only)

- 21 White wash two coats.

= 730.00 Cft

@Rs: 829.95 %Cft Rs: 6059.00  
(Rs: Eight hundred twenty nine rupes ninty five P.S only)

- 22 Primary coat of chalk under distemping ( S.I No: 23 P 59)

= 7215.00

@Rs: 442.75 %Cft Rs: 31944.00  
( Four Hundred Fourty Two & P.S Seventy Five only)

- 23 Distemping three coats ( S.I No: 24 ( B ) P 53)

= 7215.00 Cft

@Rs: 1079.65 %Cft Rs: 77897.00  
(Rs: One Thousand Seventy Nine & P.S Sixty Five only)

- 24 Painting doors & window any type, (S.I.No 05 P/ 76)

= 374.00 Cft

@Rs: 2116.41 %Cft Rs: 7915.00  
(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One only)

- 25 Preparing surface painting guards bars gates iron grating railling i/c standards brass etc similar open work.  
(S.I.No 4 II d P/76)

= 96.00 Cft

@Rs: 1270.83 %Cft Rs: 1220.00  
(Rs: Five Hundred Eighty Five & Fifty Four only)

**Total 1253622**

  
**XEN**

# SCHEDULE "B"

63

## Name of Work:-

Integrated Rehabilitation of Primary Schools & Provision of Missing Facilities Taluka Bakrani (12-Units)(2015-16 Prog)  
At : GBPS Chuttal Abro ( C/Wall & Toilet ) Taluka Dokri

S.N	Description	Qnty:	Rate			Amount	
-----	-------------	-------	------	--	--	--------	--

- 1 Dismantling C.C plain 1:2:4  

= 507

@ Rs: 3327.50      %SFT      Rs: 16870
- 2 Removing cement or lime plaster. (S.I.No 53 P/14)  

= 507

@ Rs: 121.00      %SFT      Rs: 613.47

( One hundred & twenty rup: only)
- 3 Excavation in foundation of building bridges and other structure member with excavated le chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).  

= 1396

@ Rs: 3176.25      %0 CFT      Rs: 4,434.0

(Thirty one Hundred seventy six rup: & twenty five paisa only)
- 4 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16  

= 580

@ Rs: 8694.95      % CFT      Rs: 50,431

(Eighty six hund: ninty four rup: & ninty five paisa only)
- 5 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 2  

= 1066

@ Rs: 11948.36      % CFT      Rs: 127370

(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)
- 6 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or p laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)  

= 100

@ Rs: 337.00      P.CFT      Rs: 33,700

(Three hundred Thirty seven rup: only)
- 7 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying ir i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)  

= 0.893

@ Rs: 5001.70      P.CWT      Rs: 4,467

( Five thousand one rup: & seventy paisa only)
- 8 Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6  

= 500

@ Rs: 12346.65      %SFT      Rs: 61,733

(Twelve thousand three hund: forty six rup: & sixty five paisa only)
- 9 Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No  

= 75

@ Rs: 12674.36      %SFT      Rs: 9,506

(Twelve thousand six hundred seventy four rup: & thity six paisa only)
- 10 S/F sand floor and plugging into walls (S.I No 29 P/31)



S.No	Description	Qty:	Rate		Amount
------	-------------	------	------	--	--------

11 Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)

= **75**

@ Rs: 2206.60 %SFT Rs: 1,655

(Twenty tow hund: six rup: & sixty paisa only)

12 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)

= **75**

@ Rs: 2197.52 %SFT Rs: 1,648

(Twenty one hund: ninty seven rup: & fifty two paisa only)

13 Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.19 (a) P/53)

= **1108**

@ Rs: 1287.44 %SFT Rs: 14,265

(Twelve hundred eighty seven rupees & forty for paisa only)

14 Cemnet concret plain i/c placing compacting finishing and curring complete i/c screeing and stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)

= **11**

@ Rs: 14429.25 %SFT Rs: 1,587

(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)

15 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls R (S.I No:16 ( C ) P/46)

= **1300**

@ Rs: 4411.82 %SFT Rs: 57,354

( Forry four hundred eleven rup: & eighty two paisa only)

(B) Ratio 2" thick,

= **111**

@ Rs: 3275.50 %SFT Rs: 3,636

(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

16 P/L Hala patteren tiles glazed 4" \* 4 1/4" of floor of wall cacing in required pattern of cemer of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cemer desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to ( S.I No: 62 P/53)

= **127**

@ Rs: 34520.31 %CFT Rs: 43,841

(Thirty four thousand five hundred twenty rupees & thirty one paisa only)

17 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c dec panelled and glazed (b) 1-3/4thicks.(Only Shutters)

= **80**

@ Rs: 902.93 P.CFT Rs: 72,234

(Nine hund: two rup: & ninty three paisa only)

18 Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement i/c finishing complete (Flooring and Facing ) (S.I.No 69 P/55).

= **50**

S.No	Description	Qnty:	Rate		Amount
------	-------------	-------	------	--	--------

19 White wash three coats.

= **50**

@ Rs: 829.95 %CFT Rs: 415

(Eight hundred twenty nine rup: & ninty five paisa only)

20 Primary coat of chalk under distempring ( S.I No: 23 P 59)

= **360**

@ Rs: 442.75 %CFT Rs: 1,594

(Four hundred forty two rupees & seventy five paisa only)

21 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbi  
brick /sen paper filling the voilds with chalk plaster of paris and then painting with weathe  
make New surface. (S.I.No 39 (a) P/62).

= **4020**

@ Rs: 1948.10 %CFT Rs: 78,314

Twenty on hundred sixteen rupees & forty one paisa only)

22 Distempering three coats ( S.I No: 24( B ) P 59)

= **360**

@ Rs: 1079.65 % Sft Rs: 3,758

(One thousand Seventy nine rup: & sixty five paisa only)

23 Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2  
bars 4" centre to cement .

= **48**

@ Rs: 726.72 P.Sft Rs: 34,883

(Seven hundred twenty six rupees & seventy two paisa only)

24 Painting doors & window any type, (S.I.No 05 P/ 76)

= **70**

@ Rs: 2116.41 %Cft Rs: 1,481

( Twenty one hundred sixteen rup & forty one paisa only)

**Total 676490**

  
**XEN,**

## SCHEDULE "B"

**Name of Work:-** Integrated Rehabilitation of Primary Schools & Provision of Missing Facilities Taluka Bakrani (12-Units)(2015-16 Prog)  
At : GBPS Imam Bux Sario Taluka Dokri

S.No	Description	Qty:	Rate		Amount
1	Removing cement or lime plaster. (S.I.No 53 P/14)			=	<b>507</b>
		@ Rs: 121.00	%SFT	Rs: 613.47	
				(Rs: One Hunared Twenty One only)	
2	Excavation in foundation of building bridges and other structure member with excavated le chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).			=	<b>1396</b>
		@ Rs: 3176.25	%0 CFT	Rs: 4,434.0	
				(Three Thousand One Hund:Seventy Six & P.S Twenty	
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16			=	<b>580</b>
		@ Rs: 8694.95	% CFT	Rs: 50,431	
				( Eight Thousand Six Hund:Ninty Four & P.S Ninty five	
5	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 2			=	<b>1266</b>
		@ Rs: 11948.36	% CFT	Rs: 151266	
				( Eleven Thousand Nine Hund: Fourty Eight & P.S Th	
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or p laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)			=	<b>175</b>
		@ Rs: 337.00	P.CFT	Rs: 58,975	
				( Three Hundred Thirty Seven only)	
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying ir i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)			=	<b>1.563</b>
		@ Rs: 5001.70	P.CWT	Rs: 7,818	
				(Five Thousand One &P.S Seventy ).	
8	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6			=	<b>700</b>
		@ Rs: 12346.65	%SFT	Rs: 86,427	
				(Tolive Thousand Three Hundred Fourty Six,& P.S Sixt	
9	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No			=	<b>75</b>
		@ Rs: 12674.36	%SFT	Rs: 9,506	
				( Eleven Thousand Nine Hund: Fourty Eight & P.S Th	
10	S/F sand floor and plugging into walls (S.I.No 29 P/31).			=	<b>4000</b>
		@ Rs: 1141.25	%SFT	Rs: 45,650	

S.No	Description	Qty:	Rate		Amount
9	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)			=	75
		@ Rs: 2206.60	%SFT	Rs: 1,655	( Two hundred Three Hund: Fifty Six & P.S Seventy Ei
10	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)			=	75
		@ Rs: 2197.52	%SFT	Rs: 1,648	( Two Twousand One Hund: Ninty Seven & P.S Fifty T
11	Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.19 (a) P/53)			=	1108
		@ Rs: 1287.44	%SFT	Rs: 14,265	( Twolive Thousand Eighty Seven & P.S Fourty Four o
12	Cemnet concret plain i/c placing compacting finishing and curring complete i/c screeing an stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)			=	11
		@ Rs: 14429.25	%SFT	Rs: 1,587	( Fourten thousands four hundred twenty nine Twent
13	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ra (S.I No:16 ( C ) P/46)			=	805
		@ Rs: 4411.82	%SFT	Rs: 35,515	(Rs: Four Thousand Four Hundred Eleven & P.S Eighty
(B)	Ratio 2" thick,			=	111
		@ Rs: 3275.50	%SFT	Rs: 3,636	(Rs: Three Thousands two hundred seventy five rupees
14	P/L Hala patteren tiles glazed 4"*4 1/4" of floor of wall cacing in required pattern of cemer of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cemei desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to p ( S.I No: 62 P/53)			=	127
		@ Rs: 34520.31	%CFT	Rs: 43,841	(Rs: Thirty four thousands five hundred twenty rupes
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c dec panelled and glazed (b) 1-3/4thicks.(Only Shutters)			=	18
		@ Rs: 902.93	P.CFT	Rs: 22,928	( Nine Hundraed Two P.S Ninty Three only)
16	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement :				

S.No	Description	Qnty:	Rate		Amount
17	White wash three coats.			=	<b>50</b>
		@ Rs: 829.95	%CFT	Rs: 415	
				(Rs: Eight hundred twenty nine rupes ninty five P.S o)	
18	Primary coat of chalk under distempring ( S.I No: 23 P 59)			=	<b>360</b>
		@ Rs: 442.75	%CFT	Rs: 1,594	
				( Four Hundred Fourty Two & P.S Seventy Five only)	
19	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbir brick /sen paper filling the voilds with chalk plaster of paris and then painting with weather make New surface. (S.I.No 39 (a) P/62).			=	<b>5000</b>
		@ Rs: 1948.10	%CFT	Rs: 97,405	
				( One thousands nine hundred fouty eight rupes only)	
20	Distempering three coats ( S.I No: 24( B ) P 59)			=	<b>360</b>
		@ Rs: 1079.65	% Sft	Rs: 3,887	
				(Rs: One Thousand Seventy Nine & P.S Sixty Five only)	
22	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2 bars 4" centre to cement .			=	<b>48</b>
		@ Rs: 726.72	P.Sft	Rs: 34,883	
				(Rs: Seven hundred twenty six Seventy two & P.S only)	
23	Painting doors & window any type, (S.I.No 05 P/ 76)			=	<b>70</b>
		@ Rs: 2116.41	%Cft	Rs; 1,481	
				(Rs: One Two Thousand one Hund: Sixteen & P.S Fou	
					<b>Total 690369</b>

  
**XEN**



## SCHEDULE "B"

**Name of Work:-**

Integrated Rehabilitation of Primary Schools & Provision of  
Missing Facilities Taluka Bakrani (12-Units)(2015-16 Prog)  
At : GBPS Gulan Wahan Taluka Dokri

S.No	Description	Qty:	Rate		Amount
1	Removing cement or lime plaster. (S.I.No 53 P/14)			=	<b>1500</b>
		@ Rs: 121.00	%SFT	Rs: 1,815	
				(Rs: One Hunared Twenty One only)	
2	Excavation in foundation of building bridges and other structure member with excavated le chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).			=	<b>1400</b>
		@ Rs: 3176.25	%0 CFT	Rs: 4,446.8	
				(Three Thousand One Hund:Seventy Six & P.S Twenty	
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16			=	<b>1200</b>
		@ Rs: 8694.95	% CFT	Rs: 104339	
				( Eight Thousand Six Hund:Ninty Four & P.S Ninty five	
5	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 2			=	<b>1500</b>
		@ Rs: 11948.36	% CFT	Rs: 179225	
				( Eleven Thousand Nine Hund: Fourty Eight & P.S Th	
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or p laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)			=	<b>350</b>
		@ Rs: 337.00	P.CFT	Rs: 117950.0	
				( Three Hundred Thirty Seven only)	
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)			=	<b>15.63</b>
		@ Rs: 5001.70	P.CWT	Rs: 78,152	
				(Five Thousand One &P.S Seventy ).	
8	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6			=	<b>1000</b>
		@ Rs: 12346.65	%SFT	Rs: 123467	
				(Tolive Thousand Three Hundred Fourty Six & P.S Sixt	
9	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No			=	<b>200</b>
		@ Rs: 12674.36	%SFT	Rs: 25,349	
				( Eleven Thousand Nine Hund: Fourty Eight & P.S Th	
10	S/F sand floor and plugging into walls (S.I.No 29 P/31).			=	<b>10000</b>
		@ Rs: 1141.25	%SFT	Rs: 114125	
				(Rs:One Thousand One Hund: Fourty One & P.S Twent	

S.No	Description	Qty:	Rate		Amount
9	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)			=	<b>9500</b>
		@ Rs: 2206.60	%SFT	Rs: 209627.0	( Two hundred Three Hund: Fifty Six & P.S Seventy Ei
10	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)			=	<b>9500</b>
		@ Rs: 2197.52	%SFT	Rs: 208764.4	( Two Twousand One Hund: Ninty Seven & P.S Fifty T
11	Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.19 (a) P/53)			=	<b>1500</b>
		@ Rs: 1287.44	%SFT	Rs: 19,312	( Twolive Thousand Eighty Seven & P.S Fourty Four o
12	Cemnet concret plain i/c placing compacting finishing and curring complete i/c screeing and stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)			=	<b>200</b>
		@ Rs: 14429.25	%SFT	Rs: 28,859	( Fourten thousands four hundred twenty nine Twent
13	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ra (S.I No:16 ( C ) P/46)			=	<b>1500</b>
		@ Rs: 4411.82	%SFT	Rs: 66,177	(Rs: Four Thousand Four Hundred Eleven & P.S Eighty
(B)	Ratio 2" thick,			=	<b>1500</b>
		@ Rs: 3275.50	%SFT	Rs: 49,133	(Rs: Three Thousands two hundred seventy five rupees
14	P/L Hala patteren tiles glazed 4"*4 1/4" of floor of wall cacing in required pattern of cemer of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cemer desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to 1 ( S.I No: 62 P/53)			=	<b>200</b>
		@ Rs: 34520.31	%CFT	Rs: 69,041	(Rs: Thirty four thousands five hundred twenty rupees
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c dec panelled and glazed (b) 1-3/4thicks.(Only Shutters)			=	<b>50</b>
		@ Rs: 902.93	P.CFT	Rs: 45,147	( Nine Hundraed Two P.S Ninty Three only)
16	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grev cement :				

S.No	Description	Qty:	Rate		Amount
------	-------------	------	------	--	--------

17 White wash three coats.

= **7500**

@ Rs: 829.95 %CFT Rs: 62,246

(Rs: Eight hundred twenty nine rupes ninty five P.S o)

18 Primary coat of chalk under distempring ( S.I No: 23 P 59)

= **25000**

@ Rs: 442.75 %CFT Rs: 110688

( Four Hundred Fourty Two & P.S Seventy Five only)

19 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbin brick /sen paper filling the voids with chalk plaster of paris and then painting with weather make New surface. (S.I.No 39 (a) P/62).

= **10000**

@ Rs: 1948.10 %CFT Rs: 194810

( One thousands nine hundred fouty eight rupes only)

20 Distempering three coats ( S.I No: 24( B ) P 59)

= **25000**

@ Rs: 1079.65 % Sft Rs: 269913

(Rs: One Thousand Seventy Nine & P.S Sixty Five only)

22 Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2 bars 4" centre to cement .

= **48**

@ Rs: 726.72 P.Sft Rs: 34,883

(Rs: Seven hundred twenty six Seventy two & P.S only)

23 Painting doors & window any type, (S.I.No 05 P/ 76)

= **100**

@ Rs: 2116.41 %Cft Rs; 2,116

(Rs: One Two Thousand one Hund: Sixteen & P.S Fou

**Total 2140603**

  
**XEN**

66

**SCHEDULE-B**

**Name of Work:-** Construction Re-Construction of Dangerous Primary Schools Taluka  
Dokri (2015-16 Prog:) ( 08-Units) At: GBPS Allah Yar Sario Taluka Dokri

S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

- 1 Dismenlin 2nd Class tiles roofing.  
@Rs: 378.13 Rs: 4314.00  
1141.00 (Rs: Three Hundred Seventy Eight & P.S Thirteen only)
- 2 Dismenlin Pacca brick work in cement mortor  
1337.00 @Rs: 1285.63 Rs: 17189.00  
(Rs: Twolive thousand Eighty Five & P.S Sixty Three only)
- 3 Excavation in foundation of building bridges and other structure member with excavated lead chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).  
664.00 @Rs: 3176.25 %0 C Rs: 2109.00  
(Three Thousand One Hund:Seventy Six & P.S Twenty Five)
- 4 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).  
456.00 @Rs: 8694.95 % Cft Rs: 39649.00  
( Eight Thousand Six Hund:Ninty Four & P.S Ninty five on)
- 5 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 23.  
726.00 @Rs: 11948.36 % S.ft Rs: 86748.00  
( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty :
- 6 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or pre  
laid in position complete in all respect ratio 1:2:4 (S.I No. 6 { a) P/18)  
300.00 @Rs: 337.00 P.Cft Rs: 101100.00  
( Three Hundred Thirty Seven only)
- 7 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in pc  
i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)  
14.732 @Rs: 5001.70 P.CW Rs: 73686.00  
(Five Thousand One &P.S Seventy ).
- 8 S/F sand floor and plugging into walls (S.I.No 29 P/31).  
9422.00 @Rs: 1141.25 %Cft Rs: 107529.00  
(Rs:One Thousand One Hund: Fourty One & P.S Twenty Fiv
- 9 Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5  
1601.00 @Rs: 12674.36 % Cft Rs: 202917.00  
(Twlove thousand Six Hundred Seventy Four & Thirty Six
- 10 Supplying Girders at site of work(Sch: of Material)  
9.723 @Rs: 3850.00 P.Cw Rs: 37434.00  
(Three Thousand Eight Hundred Fifty only)

  
**XEN**

No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
----	-------------	----------	-------	------	-----	---------

- 11 Supplying T-iron at site of work (Sch: of Material).  
18.143 @Rs: 3375.00 P.Cwt Rs: 64861.00  
(Three Thousand Three Hundred Seventy Five only)
- 12 First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leaping over 1/4" thick 1:6 with 34lbs: of bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" mortar with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)  
1067.00 @Rs: 11443.10 %Sft Rs: 122098.00  
(Rs:Eleven thousand Four Hundred Fourty Three & P.S Ten)
- 13 Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S. 972.00 @Rs: 12346.65 % Cft Rs: 120009.00  
(Twelve Thousand Three Hundred Fourty Six & P.S Sixty Six)
- 14 Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)  
4714.00 @Rs: 2206.60 % Sf Rs: 104019.00  
( Two hundred Three Hund: Fifty Six & P.S Seventy Eight )
- 15 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)  
4714.00 @Rs: 2197.52 %S.ft Rs: 103591.00  
( Two Twousand One Hund: Ninty Seven & P.S Fifty Two c
- 16 Cement pointing and striking of joints on walls ratio. 1: 2 ( S.I No.19 (a) P/53)  
2277.00 @Rs: 1287.44 %Cft Rs: 29315.00  
( Twelve Thousand Eighty Seven & P.S Fourty Four only)
- 17 Notice board made with cement.  
64.00 @Rs: 58.11 % Sf Rs: 3719.00  
( Eighty Eight & P.S Eleven only)
- 18 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deoda panelled and glazed (b) 1-3/4thicks.(Only Shutters)  
60.00 @Rs: 902.93 %Cft Rs: 54176.00  
( Nine Hundraed Two P.S Ninty Three only)
- 19 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ratic  
965.00 @Rs: 3275.50 % S.ft Rs: 31609.00
- 20 White wash three coats (S.I.No 26 ( c ) 59).  
965.00 @Rs: 829.95 P.Sft Rs: 8009.00  
(Rs: Four Hundred Twenty Five & P.S Eighty Four only)
- 21 Primary coat of chalk under distempring ( S.I No: 23 P 59)  
5801.00 @Rs: 442.75 % Sft Rs: 25684.00  
( Four Hundred Fourty Two & P.S Seventy Five only)

  
**XEN**

No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
----	-------------	----------	-------	------	-----	---------

22 Distemping three coats, (S.I.No 24 (b) P/59)

5801.00 @Rs: 1079.65 % Sft Rs: 62631.00

(Rs: One Thousand Seventy Nine & P.S Sixty Five only)

23 Painting doors & Window any type.

374.00 @Rs: 2116.41 %Cft Rs: 7915.00

(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty C

24 Preparing surface painting guards bars gates iron grating railling i/c standards brass etc simila  
(S.I.No 4 d P/76 ii)

96.00 @Rs: 1270.83 %Cft Rs: 1220.00

(Rs: Five Hundred Eighty Five & Fifty Four only)

Total 1411531

  
**XEN**

## SCHEDULE-B

**Name of work:-** Constuction / Reconstruction of Dangerous of Primary Schools  
Taluka Dokri (8-Units ) (2015-16 Prog ) At : GBPS Gulab Junejo  
Taluka Dokri .

S.n	Discription	Qnty	Rate	Unit Rs	Amount
1	Dismantling R.C.C Work 1:2:4	767.0	@Rs: 5445.0	%Cft Rs:	41763 (Rs: Five thousand Four Hundred Fourty Five on
2	Dismantling Pacca brick work in cement mortor ( s.no (a) P/10)	1154.0	@Rs: 1285.63	%Cft Rs:	14836 (Rs: Twolive thousand Eighty Five & P.S Sixty Thr
3	Excavation in foundation of building bridges and other structure member with excavate chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	35.00	@ Rs: 3176.25	%0 Cft Rs:	111 (Three Thousand One Hund:Seventy Six & P.S Twi
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) I	12.0	@Rs: 8694.95	% Cft Rs:	1043 ( Eight Thousand Six Hund:Ninty Four & P.S Ninty
5	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( (	731.0	@ Rs: 11948.36	% S.ft Rs:	87343 ( Eleven Thousand Nine Hund: Fourty Eight & F
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a) P/18)	332.0	@Rs: 337.0	P.Cft Rs:	111884 ( Three Hundred Thirty Seven only)
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and layin i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	14.821	@ Rs: 5001.70	P.CWt Rs:	74130 (Five Thousand One &P.S Seventy ).
8	Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6 (S	854.0	@Rs: 12674.36	% Cft Rs:	108239 (Twlove thousand Six Hundred Seventy Four & 1
9	Pacca brick work in other than building i/c striking of joints cement sand mortor Ratio	900.0	@Rs: 12346.65	% Cft Rs:	111120 (Tolive Thousand Three Hundred Fourty Six & P.
10	Supplying Girders at site of work(Sch: of Material)	22.10	@ Rs: 3850.0	P.Cwt Rs:	85085 (Three Thousand Eight Hundred Fifty only)
11	Supplying T-iron at site of work (Sch: of Material).	18.92	@ Rs: 3375.0	P.Cwt Rs:	63855 (Three Thousand Three Hundred Seventy Five on
12	First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leeping over 1/1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" mortor with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)	1134.00	@ Rs: 11443.10	%Sft Rs:	129765 (Rs:Eleven thousand Four Hundred Fourty Three

  
**XEN**

S.n	Discription	Qnty	Rate	Unit Rs	Amount
13	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	3921.0	@Rs; 2206.60	% Sft Rs:	86521
	( Two hundred Three Hund: Fifty Six & P.S Sever				
14	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)	3921.0	@ Rs: 2197.52	%S.ft Rs:	86165
	( Two Twousand One Hund: Ninty Seven & P.S Fil				
15	Notice board made with cement.	64.0	@Rs; 58.11	P.Sft Rs:	3719
	( Fifty Eight Eleven rupes only)				
16	Cement pointing and stricking of joints on walls ratio. 1: 2 ( S.I No.19 (a) P/53)	1574.0	@ Rs: 1287.44	%Cft Rs:	20264
	( Twolive Thousand Eighty Seven & P.S Fourty Fo				
17	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c panelled and glazed (b) 1-3/4thicks.	95.0	@ Rs: 902.93	P.Sft Rs:	85778
	( Nine Hundraed Two P.S Ninty Three only)				
18	S/F iron steel grill 1/4"*3/4" size flate iron of approved made shade in 3 white weight t lbs:/Sq:/Ft: of finished grill.	235.0	@ Rs: 180.50	%C.ft Rs:	42,418
	(Rs:One Hndrad Eighty & P.S Fifty )				
19	S/F sand floor and plugging into walls (S.I.No 29 P/31).	3465.0	@Rs: 1141.25	%Cft Rs:	39544
	(Rs:One Thousand One Hund: Fourty One & P.S T				
20	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenl	1002.0	@ Rs: 4411.82	% S.ft Rs:	44206
	(Rs: Four Thousand Four Hundred Eleven & P.S Ei				
21	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" squar	48.0	@ Rs: 726.72	%Sft Rs:	34,883
	(Rs: Seven Hundred Twenty Six & P.S Seventy Tw				
22	White wash three coats (S.I.No 26 ( c ) 59).	948.0	@Rs: 829.95	% Sft Rs:	7868
	(Rs: Eight hundred twenty nine rupes & P.S Nine f				
23	Distemping three coats, (S.I.No 24 (b) P/59)	4963.0	@ Rs: 1079.65	% Sft Rs:	53583
	(Rs: One Thousand Seventy Nine & P.S Sixty Five				
24	Painting doors & Window any type.	374.0	@ Rs: 2116.41	%Cft Rs:	7915
	(Rs:Two Thousand one Hund: Sixteen & P.S Fourt				
25	Preparing surface painting guards bars gates iron grating railling i/c standards brass et (S.I.No 4 d P/76 ii )	96.0	@Rs: 1270.83	%Cft Rs:	1220
	(Rs: One thousand two hundred rupes only)				

Total	1343259
-------	---------

  
XEN



**SCHEDULE " B "**

S.No: 62

NAME OF WORK:- **PROVISION OF MISSING FACILITIES IN EXISTING  
ELEMENTARY SCHOOLS (2016-17 PROGRAMME). AT GBPS  
DARYA KHAN KALHORO (1-C/R) TALUKA LARKANO.**

S.No	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	816.00	@ Rs: 3176/25	% Cft	Rs: 2,591.00 (Rs: three thous: one hund: seventy hund: twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/ ).	245.00	@ Rs: 8694/95	% Cft	Rs: 21,302.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	665.00	@ Rs:11948/36	% Cft	Rs: 79,456.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	533.00	@ Rs:337/-	P.Cft	Rs: 179,621.00 (Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	26.00	@ Rs:5001/70	P.Cwt	Rs: 130,044.00 (Rs: five thous: one & seventy only)
6	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	1272.00	@ Rs: 1141/25	% Cft	Rs: 14,516.00 (Rs: one thous: one hund: forty one & twenty five only)
7	Extra lead 3.0 miles	1272.00	@ Rs: 579/41	% Cft	Rs: 7,370.00 (Rs: five hund: sevnty nine & forty one only)
8	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	163.00	@ Rs:10/70	P.Sft	Rs: 1,744.00 (Rs: ten & seventy only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).				
		137.00	@ Rs: 3327/50	% Cft	Rs: 4,558.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
10	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1077.00	@ Rs:12674/36	% Cft	Rs: 136,502.00
			(Rs: tweleve thous: six hund: seventy four & thirty six only)		
11	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		28.00	@ Rs:228/90	P.Rft	Rs: 6,409.00
			(Rs: two hund: twenty eight & ninty only)		
12	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		114.00	@ Rs: 240/50	P.Rft	Rs: 27,417.00
			(Rs: two hund: forty & fifty only)		
13	Suppling M.S square, bar 5/8" dia (Sch: of matrial).				
		1.00	@ Rs: 3350/-	P.Cwt	Rs: 3,550.00
			(Rs: three thous: three hund; fifty only)		
14	Cutting and fixing iron bars for barred windows. (S.I.No.18 P/97).				
		26.00	@ Rs: 28/23	P.Bar	Rs: 733.00
			(Rs: twenty eight & twenty five only)		
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).				
		72.00	@ Rs: 902/93	P.Sft	Rs: 65,010.00
			(Rs: nine hud: two & ninty three only)		
16	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2013.00	@ Rs:2206/60	% Sft	Rs: 44,418.00
			(Rs: two thous: two hund: six & sixty only)		
17	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1981.00	@ Rs:2197/52	% Sft	Rs: 43,532.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
18	Cement pointing striking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		629.00	@ Rs:1287/44 % Sft	Rs:	8,097.00
			(Rs: one thous: two hund: eighty seven & fourty four only)		
19	Notice board made with cement. (S.I.No: 1 P/94)				
		32.00	@ Rs: 58/11 P.Sft	Rs:	1,859.00
			(Rs: fifty eight & eleven only)		
20	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		440.00	@ Rs: 4411/82 % Sft	Rs:	19,412.00
			(Rs: four thous: four hund: eleven & eighty two only)		
(B)	<u>1-1/2"Thick</u>	716.00	@ Rs: 2548/29 % S.ft	Rs:	18,245.00
			(Rs: two thous: five hund: forty eight & twenty nine only)		
21	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).				
		59.00	@ Rs:226/02 P.Sft	Rs:	13,335.00
			(Rs: two hund; twenty six & two only)		
22	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).				
		716.00	@ Rs:1887/40 % Sft	Rs:	13,513.00
			(Rs: one thous: eight hund; eighty seven & fourteen only)		
23	Primary coat of chalk distempering. (S.I.No.23 P/57).				
		2320.00	@ Rs:442/75 % Sft	Rs:	10,271.00
			(Rs: four hund; forty two & seventy five only)		
24	Distempering three coats. (S.I.No.24 (c) P/53).				
		2320.00	@ Rs:1079/65 % Sft	Rs:	25,047.00
			(Rs: one thos: seventy nine & sixty five only)		
(B)	<u>Two coats.</u>	440.00	@ Rs:1043/90 % Sft	Rs:	4,593.00
			(Rs: ten hund; forty three & ninty only)		
25	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		317.00	@ Rs: 1948/10 % Sft	Rs:	6,175.00
			(Rs: one thous: nine hund: forty eight & ten only)		
26	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c) P/69).				
		207.00	@ Rs:2116/41 % Sft	Rs:	4,380.00
			(Rs: two thous: one hund: sixteen & forty one only)		
G.Total:				Rs:	893,700.0

  
XEN

**SCHEDULE " B "**

S.No: 65

NAME OF WORK:-

**PROVISION OF MISSING FACILITIES IN EXISTING  
ELEMENTARY SCHOOLS (2016-17 PROGRAMME). AT GBPS  
HAJI KHAN UMRANI (1-C/R) TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	816.00	@ Rs: 3176/25	% 0 Cft	Rs: 2,591.00 (Rs: three thous: one hund: seventy hund: twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/ ).	245.00	@ Rs: 8694/95	% Cft	Rs: 21,302.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	665.00	@ Rs:11948/36	% Cft	Rs: 79,456.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	533.00	@ Rs:337/-	P.Cft	Rs: 179,621.00 (Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	26.00	@ Rs:5001/70	P.Cwt	Rs: 130,044.00 (Rs: five thous: one & seventy only)
6	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	1272.00	@ Rs: 1141/25	% Cft	Rs: 14,516.00 (Rs: one thous: one hund: forty one & twenty five only)
7	Extra lead 3.0 miles	1272.00	@ Rs: 579/41	% Cft	Rs: 7,370.00 (Rs: five hund: sevnty nine & fourty one only)
8	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	163.00	@ Rs:10/70	P.Sft	Rs: 1,744.00 (Rs: ten & seventy only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).				
		137.00	@ Rs: 3327/50	% Cft	Rs: 4,558.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
10	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(c) P/20).				
		1077.00	@ Rs:12674/36	% Cft	Rs: 136,502.00
			(Rs: tweleve thous: six hund: seventy four & thirty six only)		
11	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		28.00	@ Rs:228/90	P.Rft	Rs: 6,409.00
			(Rs: two hund: twenty eight & ninty only)		
12	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		114.00	@ Rs: 240/50	P.Rft	Rs: 27,417.00
			(Rs: two hund: forty & fifty only)		
13	Suppling M.S square, bar 5/8" dia (Sch: of matrial).				
		1.00	@ Rs: 3350/-	P.Cwt	Rs: 3,550.00
			(Rs: three thous: three hund: fifty only)		
14	Cutting and fixing iron bars for barred windows. (S.I.No.18 P/97).				
		26.00	@ Rs: 28/23	P.Bar	Rs: 733.00
			(Rs: twenty eight & twenty five only)		
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).				
		72.00	@ Rs: 902/93	P.Sft	Rs: 65,010.00
			(Rs: nine hud: two & ninty three only)		
16	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2013.00	@ Rs:2206/60	% Sft	Rs: 44,418.00
			(Rs: two thous: two hund: six & sixty only)		
17	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1981.00	@ Rs:2197/52	% Sft	Rs: 43,532.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		

**AEN**

S.No:	Description	Qty:	Rate	Unit	Amount
18	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		629.00	@ Rs:1287/44 % Sft		Rs: 8,097.00
			(Rs: one thous: two hund: eighty seven & fourty four only)		
19	Notice board made with cement. (S.I.No: 1 P/94)				
		32.00	@ Rs: 58/11 P.Sft		Rs: 1,859.00
			(Rs: fifty eight & eleven only)		
20	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		440.00	@ Rs: 4411/82 % Sft		Rs: 19,412.00
			(Rs: four thous: four hund: eleven & eighty two only)		
(B)	<u>1-1/2"Thick</u>	716.00	@ Rs: 2548/29 % S.ft		Rs: 18,245.00
			(Rs: two thous: five hund: forty eight & twenty nine only)		
21	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).				
		59.00	@ Rs:226/02 P.Sft		Rs: 13,335.00
			(Rs: two hund; twenty six & two only)		
22	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).				
		716.00	@ Rs:1887/40 % Sft		Rs: 13,513.00
			(Rs: one thous: eight hund; eighty seven & fourteen only)		
23	Primary coat of chalk distempering. (S.I.No.23 P/57).				
		2320.00	@ Rs:442/75 % Sft		Rs: 10,271.00
			(Rs: four hund; forty two & seventy five only)		
24	Distempering three coats. (S.I.No.24 (c) P/53).				
		2320.00	@ Rs:1079/65 % Sft		Rs: 25,047.00
			(Rs: one thos: seventy nine & sixty five only)		
(B)	<u>Two coats.</u>	440.00	@ Rs:1043/90 % Sft		Rs: 4,593.00
			(Rs: ten hund; forty three & ninty only)		
25	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		317.00	@ Rs: 1948/10 % Sft		Rs: 6,175.00
			(Rs: one thous: nine hund: forty eight & ten only)		
26	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c) P/69).				
		207.00	@ Rs:2116/41 % Sft		Rs: 4,380.00
			(Rs: two thous: one hund: sixteen & fourty one only)		
G.Total:					Rs: 893,700.0

  
XEN

**Schedule-B**

70

Name of  
Work:-**PROVISION OF MISSING FACILITIES IN EXISTING ELEMENTARY  
SCHOOLS TALUKA RATODERO (2016-17 PROGRAMME) @ GGPS  
FATEHPUR (02 C/R) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		1910.00	@ Rs: 3,176.25 % 0Cft	Rs:	6,067
			(Thirty one Hundred seventy six rup: & twenty five paisa only)		
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:2:4. (S.I. No. 4 © P/14)				
(A)		237.00	@ Rs: 9,416.28 % Cft	Rs:	22,317
			Nine thousand four hundred Sixteen rup: & twenty eight paisa only)		
(B)	<u>Ratio 1:5:10.</u>				
		184.00	@ Rs: 8,694.95 % Cft	Rs:	15,999
			(Eighty six hund: ninty four rup: & ninty five paisa only)		
3	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
(a)	<u>Ground Floor</u>				
		1281.00	@ Rs: 337.00 P.Cft	Rs:	431,697
			(Three hundred Thirty seven rup: only)		
(b)	<u>First Floor</u>				
		608.00	@ Rs: 349.10 P.Cft	Rs:	212,253
			(Three hundred Forty Nine rup: Ten Pessas only)		
4	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)				
		84.330	@ Rs: 5,001.70 P.Cwt	Rs:	421,793
			( Five thousand one rup: & seventy paisa only)		
5	Supply and fixing sand under floor including plugging in to walls				
		1392.00	@ Rs: 1,141.25 % Cft	Rs:	15,886
			(Eleven hundred forty one rupees & twenty five paisa only)		
6	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.				
(a)	<u>Ground Floor</u>				
		604.00	@ Rs: 12,674.36 % Cft	Rs:	76,553
			(Twelve thousand six hundred seventy four rup: & thity six paisa only)		
(b)	<u>First Floor</u>				
		705.00	@ Rs: 13,112.99 % Cft	Rs:	92,447
			(Thirteen thousand One hundred Twelve rup: & Ninety Nine paisa only)		
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
(a)	<u>Ground Floor</u>				
		1718.00	@ Rs: 2,206.60 % Cft	Rs:	37,909
			(Twenty tow hund: six rup: & sixty paisa only)		



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(b) **First Floor**

1380.00 @ Rs. 2,308.84 % Cft Rs. 31,862  
(Twenty Three hund: Eight rup: & Eighty Four paisa only)

8 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

(a) **Ground Floor**

1686.00 @ Rs: 2,197.52 % Sft Rs: 37,050  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

(b) **First Floor**

1348.00 @ Rs: 2,299.76 % Sft Rs: 31,001  
(Twenty Two hund: ninty nine rup: & Seventy six paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges

9 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs.  
The cost also i/c all carriage, tools and pla

59.00 @ Rs: 228.90 P. Rft Rs: 13,505  
(Two hundred twenty eight rupees & ninty paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded

10 hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools

178.00 @ Rs: 240.50 P. Rft Rs: 42,809  
(Two hundred forty rupees & fifty paisa only)

11 Making Notice board made with cement.

64.00 @ Rs: 58.11 P. Sft Rs: 3,719  
(Nnety Three rupees & Thirty Seven paisa only)

1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts

12 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

200.00 @ Rs: 902.93 P. Sft Rs: 180,586  
(Nine hund: two rup: & ninty three paisa only)

13 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

2.464 @ Rs: 3,550.00 P. Sft Rs: 8,747  
(Three Thousand Five hundred Fifty rupees & only)

14 Cutting & Fixing iron bars for barred windows.

36.00 @ Rs. 28.23 P. Sft Rs. 1,016  
( Twenty Eihgt rupees & Twenty Three Paisa only)

15 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.

22.00 @ Rs. 14,429.25 % Cft Rs. 3,174  
(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)

 XE



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 16 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

(a) **Ground Floor**

460.00 @ Rs: 4,411.82 % Sft Rs: 20,294  
( Forry four hundred eleven rup: & eighty two paisa only)

(b) **First Floor**

(B) **2" Thick.**

1012.00 @ Rs: 3,502.38 Rs: 35,444  
(Thirty Five hundred Two rup: & Thirty Eight paisa only)

- 17 P/L Glazed tile 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. 60 P/47)

167.00 @ Rs: 30,509.77 % Sft Rs: 50,951  
(Thirty thousand Five Hund: Nine rup: & Seventy Seven paisa only)

- 18 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)

692.00 @ Rs. 1,887.40 % Sft Rs. 13,061  
( Eighteen hundred eighty seven rupees & forty paisa only)

- 19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel

28.00 @ Rs: 226.02 P. Sft Rs: 6,329  
( Two hundred twenty six rupees & two paisa only)

- 20 Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

165.00 @ Rs: 180.50 P. Sft Rs: 29,783  
( One hundre ninty four rupees & sixteen paisa only)

- 21 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

838.00 @ Rs: 1,287.44 % Sft Rs: 10,789  
(Twelve hundred eighty seven rupees & forty for paisa only)

- 22 White wash Three Coats (S.I No. 26 © P/53)

1048.00 @ Rs: 829.95 % Sft Rs: 8,698  
(Eight hundred twenty nine rup: & ninty five paisa only)

- 23 Primary coat of chalk distemper( S.I No. 23 P/53)

3098.00 @ Rs: 442.75 % Sft Rs: 13,716  
(Four hundred forty two rupees & seventy five paisa only)

- 24 Distemping Three Coats (S.I No. 24 ©P/53)

3098.00 @ Rs: 1,079.65 % Sft Rs: 33,448  
(One thousand Seventy nine rup: & sixty five paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 25 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

1125.00 @ Rs. 1,948.10 % Sft Rs. 21,916  
Twenty on hundred sixteen rupees & forty one paisa only)

- 26 Preparing surface and painting of doors and windows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).

312.00 @ Rs: 2,116.41 % Sft Rs: 6,603  
( Twenty one hundred sixteen rup & forty one paisa only)

**Total Rs. 1,937,422**

  
**XEN**

**SCHEDULE 'B'**

Name of Work:- Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Larkano  
(2011-12 Programme) (7 Units) at: GGHSS Munawarabad ( Electric). ADP 384

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	22.00	@ Rs: 910	P.Point	Rs: 20,020.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68	@ Rs: 171	P.Meter	Rs: 11628.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	66.00	@ Rs: 428	P.Meter	Rs: 28248.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	22.00	@ Rs: 54	P.Each	Rs: 1,188.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	16.00	@ Rs: 70	P.Each	Rs: 1,120.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	7.00	@ Rs: 72	P.Each	Rs: 504.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs: 162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	5.00	@ Rs: 916	P.No	Rs: 4,580.00

Part "A" TOTAL: Rs: 69,925.0

  
**XEN**

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Old Schedule 2004)**

- |    |  |       |               |          |               |
|----|--|-------|---------------|----------|---------------|
| 11 | Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)   | 6.00  | @ Rs: 91      | Each     | Rs: 546.00    |
| 12 | Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)  | 6.00  | @ Rs: 141.71  | P.Each   | Rs: 850.26    |
| 13 | Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)   | 1.00  | @ Rs: 1426.34 | P.Sq:ft. | Rs: 1,426.34  |
| 14 | P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27). | 1.00  | @ Rs: 3341    | P.Set    | Rs: 3,341.00  |
| 15 | P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)   | 16.00 | @ Rs: 497     | P.Each   | Rs: 7,952.00  |
| 16 | P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).   | 6.00  | @ Rs: 497     | Each     | Rs: 2,982.00  |
| 17 | Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)  | 6.00  | @ Rs: 5500    | P.No     | Rs: 33,000.00 |

**Part "B" TOTAL: Rs: 50,097.6**

**Part "A" TOTAL: Rs: 69,925.0**

**G: TOTAL: Rs: 120,022.6**

**XEN**

**SCHEDULE 'B'**

Name of Work:- Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Rarodero  
(2011-12 Programme) (04 Units) (Revised) at: GBHS (S.S) Ratodero ( Electric). ADP 385

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	52.00	@ Rs: 910	P.Point	Rs: 47,320.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	10.00	@ Rs: 742	P.Point	Rs: 7,420.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	150	@ Rs: 171	P.Meter	Rs: 25650.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	55.00	@ Rs: 428	P.Meter	Rs: 23540.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	52.00	@ Rs: 54	P.Each	Rs: 2,808.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	10.00	@ Rs: 83	P.Each	Rs: 830.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	28.00	@ Rs: 70	P.Each	Rs: 1,960.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	25.00	@ Rs: 72	P.Each	Rs: 1,800.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	3.00	@ Rs: 162	P.Each	Rs: 486.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	9.00	@ Rs: 916	P.No	Rs: 8,244.00
11	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).	1.00	@ Rs: 9261	P.Each	Rs: 9,261.00

Part "A" TOTAL: Rs: 129,319.0

  
**XEN**

SNo:	ITEM OF WORK	Qnty:	Rate	Unit	Amount.
------	--------------	-------	------	------	---------

**Part "B" (Old Schedule 2004)**

12	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	24.00	@ Rs: 91	Each	Rs: 2,184.00
13	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	24.00	@ Rs: 141.71	P.Each	Rs: 3,401.04
14	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	2.00	@ Rs: 1426.34	P.Sq:ft	Rs: 2,852.68
15	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	1.00	@ Rs: 3341	P.Set	Rs: 3,341.00
16	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	28.00	@ Rs: 497	P.Each	Rs: 13,916.00
17	P/F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	6.00	@ Rs: 497	Each	Rs: 2,982.00
18	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	24.00	@ Rs: 5500	P.No	Rs: 132,000.00

Part "B" TOTAL: Rs: 160,676.7

Part "A" TOTAL: Rs: 129,319.0

G: TOTAL: Rs: 289,995.7

  
**XEN**

**SCHEDULE " B "**

S.No: 1

NAME OF WORK:-

**PROVISION OF ESSENTIAL FACILITIES IN EXISTING HIGH/  
HIGHER SECONDARY SCHOOLS IN TALUKA LARKANO (5-UNITS)  
(2011-12 PROGRAMME) AT GGHS LITTLE FOLKS (3-C/R) TALUKA  
LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	1819.00	@ Rs: 349/10	% Cft	Rs: 635,013.0
			(Rs: three hund: forty nine & ten only)		
2	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending and laying in position, making joints and fastenings i/c cost of binding wire ( also includes removal of rust from b (B) Using Tor bars. (S.I.No.8(b) P/16).	97.446	@ Rs:5001/70	P.Cwt	Rs: 487,396.0
			(Rs: five thous: one & seventy only)		
3	Extra labour for lifting of steel above first floor for every additional floor (S.I.No: 29 P/18).	97.446	@ Rs: 151/25	P.Cwt	14,739.00
			(Rs: one hund: fifty one & twenty five only)		
4	Pacca brick work in First floor in cement sand mortar Ratio 1:6 (S.I.No: P. ).	1044.00	@ Rs:13112/99	P.Cwt	Rs: 136,900.00
			(Rs: thirteen thous: one hund; tweleve & ninty nine only)		
5	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 28 P.92 ).	53.00	@ Rs:228/90	P.Rft	Rs: 12,132.00
			(Rs: two hund: twenty eight & ninty only)		
6	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosta filling with cement sand repairing i/c all carriage tools and planst used in making and fixing. ( S.I.No: 29 P/ 92).	265.00	@ Rs: 240/50	P.Rft	Rs: 63,733.00
			(Rs: two hund: forty & fifty only)		
7	M.S barred windows squars bars 5/8" dia.	2.565	@ Rs: 3550/-	P.Cwt	Rs: 9,106.00
			(Rs: three thous: five hund: fifty only)		
8	Cutting and fixing iron bars for barred windows.	54.00	@ Rs:28/23	P.No	Rs: 1,524.00
			(Rs: twenty eight & twenty three only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 9 Cement plaster (1:6) upto 12' ft: height 1/2" thick. (First Floor) (S.I.No: 13(b) P/56).

5360.00	@ Rs:2308/84	% S.ft	Rs: 123,754.00
(Rs: two thous: three hund; eight & eighty four only)			

(B) G/Floor

6941.00	@ Rs:2197/52	% Sft	Rs: 152,530.00
(Rs: two thous: one hund: ninty seven & twenty two only)			

- 10 Cement plaster ratio (1:4) upto 12' ft: height 3/4" thick (S.I.No:11 P/56).

5360.00	@ Rs:2299/76	% S.ft	Rs: 123,267.00
(Rs: two thous: two hund; ninty nine & seventy six only)			

- 11 Notice board made with cement. (S.I.No: 1 P/94).

120.00	@ Rs:58/11	P. Sft	Rs: 6,973.00
(Rs: fifty eight & eleven only)			

- 12 First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).

228.00	@ Rs: 902/93	P.Sft	Rs: 205,868.00
(Rs: nine hund: two & ninty three only)			

- 13 Cement pointing strucking joints on walls (a) Ratio 1:2.

867.00	@ Rs: 1389/68	% S.ft	Rs: 12,048.00
(Rs: one thous: three hund: eighty nine & sixty eighty only)			

- 14 Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).

25.00	@ Rs:180/50	P. Sft	Rs: 4,513.00
(Rs: one hund: eighty & fifty only)			

- 15 Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).

40.00	@ Rs:226/02	P.Sft	Rs: 9,041.00
(Rs: two hund: twenty six & two only)			

- 16 Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).

550.00	@ Rs: 14429/25	%Cft	Rs: 79,361.00
(Rs: fourteen thous: four hund: twenty nine & twenty five only)			



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 17 Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).

1617.00	@ Rs:27747/06	%Sft	Rs: 448,670.0
(Rs: twenty seven thous: seven hund forty seven & six only)			

- 18 Providing and laying 2" thick topping cement concrete (1:2:4) including surface finishing and dividing into pannalls (S.I.No.16 ( c ) P/41).

**2"Thick (F/ Floor)**

2194.000	@ Rs: 3502/38	%Sft	Rs: 76,842.00
(Rs: three thous: five hund: two & thirty eight only)			

- 19 Primary coat of chalk distempering. (S.I.No.23 P/57).

4520.00	@ Rs:442/75	%Sft	Rs: 20,012.00
(Rs: four hund; forty two & seventy five only)			

- 20 Distempering three coats. (S.I.No.24 (c) P/53).

4520.00	@ Rs:1079/65	%Sft	Rs: 48,800.00
(Rs: one thous: seventy nine & sixty five only)			

**(B) Two coats**

1617.00	@ Rs:1043/90	%Sft	Rs: 16,880.00
(Rs: ten hund; forty three & ninty only)			

- 21 Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).

1707.00	@ Rs: 1948/10	%Sft	Rs: 33,254.00
(Rs: one thous: nine hund: fourty eight & ten only)			

- 22 Preparing surface and painting of doors and windows any type (including edges)  
(ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).

456.00	@ Rs:2116/41	%Sft	Rs: 9,651.00
(Rs: two thous: one hund: sixteen & fourty one only)			

<b>G.Total:</b>	<b>Rs: 2,732,007.0</b>
-----------------	------------------------

*D*  
**XEN**

## Schedule-B

Name of Work:- Integrated Rehabilitation of Government Boys High Schools Badah (2011-12  
Prog) ( 01- Units) At : GBHS Badah Taluka Dokri ADP No: 392

*Balane Wards*

S.n	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain &				
		1000.00	@ Rs: 3,176.25 % OCft		Rs: 3,176
			(Thirty one Hundred seventy six rup: & twenty five paisa only)		
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)				
		500.00	@ Rs: 8,694.95 % Cft		Rs: 43,475
			(Eighty six hund: ninty four rup: & ninty five paisa only)		
B	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:6:12. (S.I. No. 5 © P/14)				
		200.00	@ Rs: 8,122.95 % Cft		Rs: 16,246
			(Eight Thousands Eight hundred Twenty two rupes ninty nine paisa onl		
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
		1000.00	@ Rs: 11,948.36 % Cft		Rs: 119,484
			(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)		
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in				
		500.00	@ Rs: 337.00 P.Cft		Rs: 168,500
			(Three hundred Thirty seven rup: only)		
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the				
		15.000	@ Rs: 5,001.70 P.Cwt		Rs: 75,026
			( Five thousand one rup: & seventy paisa only)		
6	Supply and fixing sand under floor including plugging in to walls				
		400.00	@ Rs: 1,141.25 % Cft		Rs: 4,565
			(Eleven hundred forty one rupees & twenty five paisa only)		
7	Extra Lead 3.0 Miles				
		400.00	@ Rs: 579.41 % OCft		Rs: 232
			(Five hundred Seventy Nine Four one paisa only)		
8	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No.				
		400.00	@ Rs. 1,887.40 % Sft		Rs. 7,550
			( Eighteen hundred eighty seven rupees & forty paisa only)		

  
**XEN**

S.n	Description	Qty	Rate	Unit	Amount
9	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.				
		600	@ Rs. 12,346.65 % Cft		Rs. 74,080
			(Twelve thousand three hund: forty six rup: & sixty five paisa only)		
10	P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification				
		150.00	@ Rs. 10.70 P.Sft		Rs. 1,605
			(Ten rupees & seventy paisa only)		
11	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges &				
		150.00	@ Rs: 228.90 P. Rft		Rs: 34,335
			(Two hundred twenty eight rupees & ninty paisa only)		
12	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded hinges &				
		80.00	@ Rs: 240.50 P. Rft		Rs: 19,240
			(Two hundred forty rupees & fifty paisa only)		
13	Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved				
		100.00	@ Rs: 180.50 P. Sft		Rs: 18,050
			( One hundre ninty four rupees & sixteen paisa only)		
14	1 <sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts &				
		100.00	@ Rs: 902.93 P. Sft		Rs: 90,293
			(Nine hund: two rup: & ninty three paisa only)		
15	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
		2000.00	@ Rs. 2,206.60 % Cft		Rs. 44,132
			(Twenty tow hund: six rup: & sixty paisa only)		
16	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)				
		2000.00	@ Rs: 2,197.52 % Sft		Rs: 43,950
			(Twenty one hund: ninty seven rup: & fifty two paisa only)		
17	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)				
		2000.00	@ Rs: 1,287.44 % Sft		Rs: 25,749
			(Twelve hundred eighty seven rupees & forty for paisa only)		
(B)	<u>2" Thick.</u>				
		300.00	@ Rs: 3,275.50		Rs: 9,827
			(Thirty Two hundred Seventy Five rup: & Fifty paisa only)		

**XEN**

S.n	Description	Qty	Rate	Unit	Amount
18	Cement concrete plain i/c placing, compacting, finishing & curing complete i/c				
		50.00	@ Rs. 14,429.25	% Cft	Rs. 7,215
			(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)		
19	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4"				
		300.00	@ Rs. 27,678.86	% Cft	Rs. 83,037
			( Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)		
20	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4"				
		400.00	@ Rs. 28,253.61	% Cft	Rs. 113,014
			( Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)		
21	Primary coat of chalk distemper( S.I No. 23 P/53)				
		400.00	@ Rs: 442.75	% Sft	Rs: 1,771
			(Four hundred forty two rupees & seventy five paisa only)		
22	Distemping Three Coats (S.I No. 24 ©P/53)				
		400.00	@ Rs: 1,079.65	% Sft	Rs: 4,319
			(One thousand Seventy nine rup: & sixty five paisa only)		
23	White wash Three Coats (S.I No. 26 © P/53)				
		186.00	@ Rs: 829.95	% Sft	Rs: 1,544
			(Eight hundred twenty nine rup: & ninty five paisa only)		
24	Prepairng surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c ) P. 76 (ii) ).				
		140.00	@ Rs: 2,116.41	% Sft	Rs: 2,963
			( Twenty one hundred sixteen rup & forty one paisa only)		
25	Extra labour rate for making cemet plaster patta/band around straight are couyard oppening and around the edges of roof slabs the wight not less tham 6' with fine finishing as directed by Engineer Incharge. (S.I.NO.35 P/54)				
		106.00	@ Rs: 19.36	% Sft	Rs: 2,052
			[ Nineteen rupes Only )		
26	Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper				
		670.00	@ Rs. 1,948.10	% Sft	Rs. 13,052
			Twenty on hundred sixteen rupees & forty one paisa only)		

1183500

  
**XEN**

**SCHEDULE " B "**

S.No: 75

NAME OF WORK:-

**DEVELOPMENT OF PARK IN EXISTING HIGH/  
HIGHER SECONDARY SCHOOLS IN DISTRICT  
LARKANO (9-UNITSO (2011-12 PROGRAMME) AT  
GGHSS LARKANO TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	1005.00	@ Rs: 3176/25	% 0 Cft	Rs: 3,192.00 (Rs: three thous: one hund: seventy six & twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	744.00	@ Rs: 8694/95	% Cft	Rs: 64,690.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	670.00	@ Rs:11948/36	% Cft	Rs: 80,054.0 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	8955.00	@ Rs: 1141/25	% Cft	Rs: 102,198.0 (Rs: one thous: one hund: forty one & twenty five only)
5	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	1079.00	@ Rs:2206/60	% Sft	Rs: 23,809.0 (Rs: two thous: two hund: six & sixty only)
6	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	1079.00	@ Rs:2197/52	% Sft	Rs: 23,711.0 (Rs: two thous: one hund: ninty seven & twenty two only)
7	Providing and laying marble flooring super / china Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without windings, set in Cement Slurry, laid over 3/4" thick Cement mortor 1:2 & filling the joints with white cement and pigment i/c grinding, rubbing and Chemical polishing as directed by the Engineer Incharge. (R.A)	80.00	@ Rs:307/-	% Sft	Rs: 24,560.00 (Rs: three hund: seven only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
8	Providing & fixing 3/8" thick marble tiles of approved quality and colour and shade size 8"x4"/6"x4" in dado skirting and facing removal / tucking of existing plaster surface etc. Over 1/2" thick base of cement mortar 1:3 setting of tiles in slurry of white cement over mortar base i/c filling the joints and washing the tiles with white cement slurry current finishing cleaning and (i) For new works. (S.I.No: 68 (i) P/48).	80.00	@ Rs: 186/04	P.Sft	Rs: 14,883.00
			(Rs: one hund: eighty six & four only)		
9	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of paris and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	2173.00	@ Rs: 1948/10	% Sft	Rs: 42,332.00
			(Rs: one thous: nine hund: fourty eight & ten only)		
10	Levelling dressing and making lawns (S.I.No.42 P/102)	8137.00	@ Rs:181/50	% Sft	Rs: 14,768.00
			(Rs: one hund: eighty one & fifty only)		
11	Trufing slops of banks or lawn with grass sods including ploughing setting and watering n(Turf got from within a distance of 5 miles and maintenance for 15 days.. (S.I.No.27 P/5)	8137.00	@ Rs:1210/-	% Sft	Rs: 98,457.00
			(Rs: one thous: two hund: ten only)		
12	Supplying Manure. (S.I.No.44 P/103)	49.00	@ Rs:298/12	P.Cort L	Rs: 14,607.00
			(Rs: two hund: ninty eight & tweleve only)		
13	Laying Murum flooring consisting of 1" layer of fine powdery or flakey variety of Murum spread over 9" thick sub-base comprising of hand packes rubble or broken bricks properly watered and rammed provided over well rammed. (S.I.No: 1 P. 39).	1460.00	@ Rs: 3918/20	% Sft	Rs: 20,769.00
			P R: 1422/58		
			(Rs: one thous: four hund: twenty two & twenty only)		
14	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 80 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and laying in specified manner / patter and design etc complete. (S.I.No: 74 P/49).	1460.00	@ Rs:199/77	P.Sft	Rs: 291,664.0
			(Rs:one hund; ninty nine & seventy seven only)		
G.Total:					Rs: 819,694.0

  
XEN

**Schedule-B**

76

**Name of Work:-** **DEVELOPMENT OF PARK IN EXISTING HIGH / HIGHER SECONDARY SCHOOLS IN DISTRICT LARKANO (09 UNITS) (2011-12 PROGRAMME) @ GBHS NAUDERO NO. 02 TALUKO RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	675.00	@ Rs: 3,176.25	% 0Cft	Rs: 2,144
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	185.00	@ Rs: 8,694.25	% Cft	Rs: 16,084
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	970.00	@ Rs: 11,948.36	% Cft	Rs: 115,899
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:4:8.(S.I No. 3(d) P/14)	496.00	@ Rs: 9,416.28	% Cft	Rs: 46,705
	Nine thousand four hundred Sixteen rup: & Twenty eight pisa only)				
5	Laying Murum flooring consisting of 1" layer of fine powdery or flakey variety of Murum laid over 6" good hard layer of Murum spread over 9" thick sub-base comprising of hand paked rubble or broken bricks properly watered and rammed provided over well rammed (S.I No. 1 P/39).	320.00	@ Rs: 3,918.20	% Cft	Rs: 12,538
	(Thirty Nine hundred eighteen rup: & twenty paisa only)				
6	Providing and Fixing Cement paving block flooring having size of 8" x4" x 3" of city / qudda / cobble shape with pigmented having strength b/w 5000 psi over bed filling the joints with hill sand and laying specified manner / pattern and design Envicrete Company etc Complete.(S.I.No.73 P/49)	2230.00	@ Rs: 223.97	P.Sft	Rs: 499,453
	( Two Hundred twenty three rup: & ninety seven paisa only)				
7	Supply and fixing sand under floor including plugging in to walls	15109.00	@ Rs: 1,141.25	% Cft	Rs: 172,431
	(Eleven hundred forty one rupees & twenty five paisa only)				
8	Trufing slops of banks or lawns with grass sods including ploughing laying, setting and watering (Turf got from within a distance of 5 male and maintenance for 15 days.(S.I. No. 27 P/ 5).	13109.00	@ Rs: 1,210.00	% Cft	Rs: 158,619
	(Twelve hundred & ten rupees only)				



S #	Description	Qty	Rate	Unit	Amount
9	Levelling dressing and making lawns. (S.I.No. 42 P/102)				
		13109.00	@ Rs: 181.50 % Cft		Rs: 23,793
	(One hundred eighty one rupees & fifty paisa only)				
10	Supplying Manure.(S.I.No. 44 P/103).				
		91.00	@ Rs: 298.12 P.C.L		Rs: 27,129
	(Two hundred ninety eight rupees & twelve paisa only)				
11	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
		1872.00	@ Rs. 2,206.60 % Cft		Rs. 41,308
	(Twenty tow hund: six rup: & sixty paisa only)				
12	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)				
		1872.00	@ Rs: 2,197.52 % Sft		Rs: 41,138
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
	Providing and laying tiles glazed 6"x6"x1/4" on floor or wall facing in required colour and apttern of				
13	STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filing of joints with slaury of white cement and pigment in desired shape with finishing clearing and cost of wax polish etc. complete including cutting. (S.I No. 60 P/46)				
		690.00	@ Rs. 30,509.77 % Sft		Rs. 210,517
	(Thirty thousand five hund: nine rupees & seventy seven paisa only)				
14	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)				
		9.06	@ Rs: 5,001.70 P.Cwt		Rs: 45,315
	( Five thousand one rup: & seventy paisa only)				
15	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
		203.00	@ Rs: 337.00 P.Cft		Rs: 68,411
	(Three hundred Thirty seven rup: only)				
	Supplying & fixing iron steel grill OF 1/2" X1/2" Dia Sq: Bars 3/8" x3/8" sq: bars in vertical and				
16	horizontal with 3/4" x1/4" angle patti. The rat i/cs all material and labour in three coats of painting. (R.A Attached)				
		465.00	@ Rs: 413.00 P.Cft		Rs: 192,045
	(Four hundred & thirteen rup: only)				

Total Rs: 1,673,530

  
XEN



**SCHEDULE-B****Name of work:**

Development of Park in Existing High/Higer Secondary Schools  
In District Larkana (2011-12 Prog) ( 09-Units) At : GBHS Bakrani  
Taluka Bakrani

SNo:	Discription	Qnty:	Rate	Unit	Rs:	Amount.
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	1896.0	@ Rs: 3176.25	%0 Cft	Rs:	5971.00
						(Three Thousand One Hund:Seventy Six & P.S Twenty Five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	470.00	@Rs: 8694.95	% Cft	Rs:	40866.00
						( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
3	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 23.	1,830.00	@ Rs: 11948.36	% S.ft	Rs:	218654.00
						( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six only)
4	Errection of rolled steel beams or old rails in roof etc crrection and fixing in position.	2820.000	@ Rs: 186.44	P.Cwt	Rs:	88192.00
						(One Hundred Eighty Six & P.S Thirty Four only)
5	C.C plain i/c compacting and curring etc complete I/c screening and washaning of stone aggregate without shuttering Ratio. 1:2:4 ( S.I.No 5 P/18)	1410.00	@Rs: 14429.25	%CFt	Rs:	177589.00
						(Rs: Fourteen thousand Four Hundred Twenty Nine & P.S Twenty Fonly)
6	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	1,852.000	@ Rs: 5001.70	P.CWt	Rs:	80027.00
						(Five Thousand One &P.S Seventy ).
7	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a) P/18)	352.0	@Rs: 337.0	P.Cft	Rs:	118624.00
						( Three Hundred Thirty Seven only)
8	S/F sand floor and plugging into walls (S.I.No 29 P/31).	22862.0	@Rs: 1141.25	%Cft	Rs:	260912.00
						(Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)
9	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:6:12 (S.I.No 4 (C) P/16).	445.0	@Rs: 8122.95	% Cft	Rs:	36147.00
						( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
10	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I.No.13 P/57)	2535.00	@Rs; 2206.60	% Sft	Rs:	55937.00
						( Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
11	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)	2535.00	@ Rs: 2197.52	%S.ft	Rs:	55707.00
						( Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)

  
**XEN**

SNo:	Discription	Qnty:	Rate	Unit	Rs:	Amount.
12	Providing & Fixing envicreate coverup stone tile of required size on wall facing of approved design, shade & pattern set in cement sand mortar ratio 1:2 in grey cement 3/4" thick i/c washing & filling of joints with neat white cement slurry & as per specification & as directed by the engineer incharge(face lifting)(R.A)	676.00	@ Rs: 250.00	P.SFT	Rs:	169000.00
			( Two Hundred fifty rupees only)			
13	S/Fin position iron steel grill of 3/4" X 1/4" flate iron of approved design i/c painting three coats etc complete with weight not to beless than 3.7 Lbs sq: ft: of finished grill.	845.0	@Rs: 194.16	P.Sft	Rs:	348985.00
			(Rs: One hundred Ninty Four & P.S Sixteen only)			
14	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3 " thick. (S.I.No c P/46).	1350.00	@ Rs: 4411.82	% S.ft	Rs:	59560.00
			(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)			
15	Leveling dressing & making lawns (S.I.No.42 P/102)	3739.00	@ Rs: 181.50	% S.ft	Rs:	6786.00
			(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)			
16	Trufing slops of banks or lawn with grass sods including ploughing setting & watering (Turf got from within a distance of 5 miles & maintenance for 15 days.. (S.I.No.27 P/5)	3739.00	@ Rs: 1210.00	% S.ft	Rs:	45241.00
			(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)			
17	Supplying Manure. (S.I.No.44 P/103)	22.43	@ Rs: 298.12	P.Cort L	Rs:	6686.00

Rs: 1774884.00
----------------

  
**XEN**

## Schedule-B

Integrated Rehabilitation of Secondary Schools & Provision of Missing  
Facilities Taluaka Dokri & Bakrani (04-Units) (2015-16 Prog ) At GBHS Mud  
Bahu ( Main GATE Side Wing) Taluka Bakrani

S	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		6760.00	@ Rs: 3,176.25	% OCft	Rs: 21,471
			(Thirty one Hundred seventy six rup: & twenty five paisa only)		
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 @ P/14)				
		1614.00	@ Rs: 8,694.95	% Cft	Rs: 140,336
			(Eighty six hund: ninty four rup: & ninty five paisa only)		
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
		1002.00	@ Rs: 11,948.36	% Cft	Rs: 119,723
			(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)		
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
		3852.00	@ Rs: 337.00	P.Cft	Rs: 1,298,124
			(Three hundred Thirty seven rup: only)		
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)				
		171.964	@ Rs: 5,001.70	P.Cwt	Rs: 860,112
			{ Five thousand one rup: & seventy paisa only)		
6	Filling watering and ramming earth in floor with surplus earth from foundation laed upto one chain and lift upto 5 ft. (S.I.No: 2 P/5).				
		3013.000	@ Rs: 1,512.50	0.Cft	Rs: 4,557
			{Fifteen hundred twelve rup: & fifty paisa only)		
7	Filling Watering and ramming earth Under floor with new earth (Excavated from outside) lead upto one chain and lift upto 5 feet (S.I. No. 22 P/4)				
		2945.00	@ Rs: 3,630.0	%OCft	Rs: 10,690
			(Thirty hundred & Thirty rupees only)		
8	Supply and fixing sand under floor including plugging in to walls				
		1845.00	@ Rs: 1,141.25	% Cft	Rs: 21,056
			(Eleven hundred forty one rupees & twenty five paisa only)		



S	Description	Qty	Rate	Unit	Amount
---	-------------	-----	------	------	--------

- 9 Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.

1649.00 @ Rs. 12,674.36 % Cft Rs. 209,000  
(Twelve thousand six hundred seventy four rup: & thity six paisa only)

- 10 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

112.00 @ Rs: 228.90 P. Rft Rs: 25,637  
(Two hundred twenty eight rupees & ninty paisa only)

- 11 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools

444.00 @ Rs: 240.50 P. Rft Rs: 106,782  
(Two hundred forty rupees & fifty paisa only)

- 12 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

4.946 @ Rs: 3,550.00 P. Sft Rs: 17,558  
(Three Thousand Five hundred Fifty rupees & only)

- 13 Cutting & Fixing iron bars for barred windows.

104.00 @ Rs. 28.23 P. Sft Rs. 2,936  
( Twenty Eihgt rupees & Twenty Three Paisa only)

- 14 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

400.00 @ Rs: 902.93 P. Sft Rs: 361,172  
(Nine hund: two rup: & ninty three paisa only)

- 15 P & Single per layer of polythene sheet 0.13 mm thick for water proggng as per specification

169.00 @ Rs. 10.70 P.Sft Rs. 1,808  
(Ten rupees & seventy paisa only)

- 16 Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

61.00 @ Rs: 180.50 P. Sft Rs: 11,011  
( One hundre ninty four rupees & sixteen paisa only)

  
**XEN**

S	Description	Qty	Rate	Unit	Amount
---	-------------	-----	------	------	--------

- 17 Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" x 4" i/c frame of flat iron patti of 3/4" x 3/4" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3 coats with 1st coat of red oxide paint etc. (S.I No. 30 P No. 93)
- 119.00 @ Rs: 194.16 P. Sft Rs: 23,105  
(One hundre ninty four rupees & sixteen paisa only)
- 18 Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)
- 5430.00 @ Rs. 2,206.60 % Cft Rs. 119,818  
(Twenty tow hund: six rup: & sixty paisa only)
- 19 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)
- 5430.00 @ Rs: 2,197.52 % Sft Rs: 119,325  
(Twenty one hund: ninty seven rup: & fifty two paisa only)
- 20 Making Notice board made with cement.
- 128.00 @ Rs: 58.11 P. Sft Rs: 7,438  
(Nnety Three rupees & Thirty Seven paisa only)
- 21 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)
- 806.00 @ Rs: 1,287.44 % Sft Rs: 10,377  
(Twelve hundred eighty seven rupees & forty for paisa only)
- 22 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.
- 13.00 @ Rs. 14,429.25 % Cft Rs. 1,876  
(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)
- 23 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)
- 1774.00 @ Rs: 4,411.82 % Sft Rs: 78,266  
( Forry four hundred eleven rup: & eighty two paisa only)
- (B) 2" Thick.
- 2364.00 @ Rs: 3,275.50 Rs: 77,433  
(Thirty Two hundred Seventy Five rup: & Fifty paisa only)
- 24 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)
- 2364.00 @ Rs. 1,887.40 % Sft Rs. 44,618  
( Eighteen hundred eighty seven rupees & forty paisa only)

**XET**

S	Description	Qty	Rate	Unit	Amount
25	P/L Glazed tile 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. 60 P/47)				
		80.00	@ Rs: 30,509.77	% Sft	Rs: 24,408
			(Thirty thousand Five Hund: Nine rup: & Seventy Seven paisa only)		
26	P/F Ornamental Cement jali 2" thick (1:2:4) Without steel				
		55.00	@ Rs: 226.02	P. Sft	Rs: 12,431
			( Two hundred twenty six rupees & two paisa only)		
27	White wash Three Coats (S.I No. 26 © P/53)				
		2047.00	@ Rs: 829.95	% Sft	Rs: 16,989
			(Eight hundred twenty nine rup: & ninty five paisa only)		
28	Primary coat of chalk distemper (S.I No. 23 P/53)				
		5302.00	@ Rs: 442.75	% Sft	Rs: 23,475
			(Four hundred forty two rupees & seventy five paisa only)		
24	Distempring Three Coats (S.I No. 24 © P/53)				
		5302.00	@ Rs: 1,079.65	% Sft	Rs: 57,243
			(One thousand Seventy nine rup: & sixty five paisa only)		
25	Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).				
		2685.00	@ Rs: 1,948.10	% Sft	Rs. 52,306
			Twenty on hundred sixteen rupees & forty one paisa only)		
26	Prepairng surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 [c] P. 76 (ii) ).				
		800.00	@ Rs: 2,116.41	% Sft	Rs: 16,931
			( Twenty one hundred sixteen rup & forty one paisa only)		

Total Rs.

3,898,014

**SCHEDULE 'B'**

78

Name of Work:- Integrated Rehabilitation of Secondary Schools & Provision of missing facilities in Taluka District  
Bakrani (04 Units) (2015-16 Programme) at: GBHS Rasheed Waggan ( Electric). ADP 385

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	52.00	@ Rs:	910	P.Point	Rs: 47,320.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	10.00	@ Rs:	742	P.Point	Rs: 7,420.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	208	@ Rs:	171	P.Meter	Rs: 35568.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	55.00	@ Rs:	428	P.Meter	Rs: 23540.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	52.00	@ Rs:	54	P.Each	Rs: 2,808.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	11.00	@ Rs:	83	P.Each	Rs: 913.00
7	Providing & Fixing Brass Batten holder..(S.I.No: 232 P 33)	28.00	@ Rs:	70	P.Each	Rs: 1,960.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	25.00	@ Rs:	72	P.Each	Rs: 1,800.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	3.00	@ Rs:	162	P.Each	Rs: 486.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	9.00	@ Rs:	916	P.No	Rs: 8,244.00
11	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).	1.00	@ Rs:	9261	P.Each	Rs: 9,261.00

Part "A" TOTAL: Rs: 139,320.0

  
**XEN**

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount
------	--------------	------	------	------	--------

**Part "B" (Old Schedule 2004)**

12	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	24.00	@ Rs: 91	Each	Rs: 2,184.00
13	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	24.00	@ Rs: 141.71	P.Each	Rs: 3,401.04
14	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	2.00	@ Rs: 1426.34	P.Sq:ft	Rs: 2,852.68
15	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	1.00	@ Rs: 3341	P.Set	Rs: 3,341.00
16	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	28.00	@ Rs: 497	P.Each	Rs: 13,916.00
17	P/F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	6.00	@ Rs: 497	Each	Rs: 2,982.00
18	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	24.00	@ Rs: 5500	P.No	Rs: 132,000.00

**Part "B" TOTAL: Rs: 160,676.7**

**Part "A" TOTAL: Rs: 139,320.0**

**G: TOTAL: Rs: 299,996.7**

**XEN**



**SCHEDULE 'B'**

Name of Work:- Integrated Rehabilitation of Secondary Schools & Provision of missing facilities in Taluka Dokri / Bakrani (04 Units) (2015-16 Programme) at: GBHS Bakhodero (Office Portion) ( Electric). ADP 385

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	28.00	@ Rs:	910	P.Point	Rs: 25,480.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs:	742	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	162	@ Rs:	171	P.Meter	Rs: 27702.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	32.00	@ Rs:	428	P.Meter	Rs: 13696.0
5	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	28.00	@ Rs:	54	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs:	83	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	18.00	@ Rs:	70	P.Each	Rs: 1,260.00
8	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	10.00	@ Rs:	72	P.Each	Rs: 720.00
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	1.00	@ Rs:	162	P.Each	Rs: 162.0
10	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	6.00	@ Rs:	916	P.No	Rs: 5,496.00

Part "A" TOTAL: Rs: 79,328.0



SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
------	--------------	------	--	------	------	---------

**Part "B" (Old Schedule 2004)**

11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	10.00	@ Rs:	91	Each	Rs: 910.00
12	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	10.00	@ Rs:	141.71	P.Each	Rs: 1,417.10
13	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	1.00	@ Rs:	1426.34	P.Sq:ft:	Rs: 1,426.34
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	18.00	@ Rs:	497	P.Each	Rs: 8,946.00
16	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	6.00	@ Rs:	497	Each	Rs: 2,982.00
17	Suply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, cannopy blade, suitable (Double beering) internal electric connection with 3/.029 PVC (R.A) (Royal Fan, younis Fan,Pak Fan)	10.00	@ Rs:	5500	P.No	Rs: 55,000.00

**Part "B" TOTAL: Rs: 70,681.4**

**Part "A" TOTAL: Rs: 79,328.0**

**G: TOTAL: Rs: 150,009.4**

**XEN**

**SCHEDULE " B "**

S.No: 81

NAME OF WORK:-

**INTEGRATED REHABILITATION OF EXISTING SECONDARY  
AND HIGHER SECONDARY SC HOOLS IN TALUKA  
LARKANO (5-UNITS) (2015-16 PROGRAMME) AT GDHSS.PILOT  
LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement 2nd class tile roofing. (S.I.No: 22 (b) P/11).				
		165.00	@ Rs: 378/13	% Cft	Rs: 624.00
			(Rs: three hund: seventy eight & thirteen only)		
2	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).				
		226.00	Rs 5445/-	% Cft	Rs: 12,305.00
			(Rs: five thous: four hund: forty five only)		
3	Dismantling rolled steel beams, iron rails etc. (S.I.No.42 P/13).				
		3.00	@ Rs:126/04	P.Cft	Rs: 378.00
			(Rs: one hund: twenty six & four only)		
4	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		564.00	@ Rs: 1285/63	% Cft	Rs: 7,250.00
			(Rs: one two hund: eighty five & sixty three only)		
5	Removing door with chowkats. (S.I.No.33 (a) P/12).				
		11.00	@ Rs:142/18	P.No	Rs: 1,563.00
			(Rs: one hund: fourty two & eighteen only)		
6	Remoning cement or lime plaster. (S.i.No.53 P/13).				
		1355.00	@ Rs:121/-	% Sft	Rs: 1,640.00
			(Rs: one hund: twenty one only)		
7	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		1027.00	@ Rs: 3176/25	% 0 Cft	Rs: 3,262.00
			(Rs: three thous: one hund: seventy six & twenty five only)		
8	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).				
		171.00	@ Rs: 8694/95	% Cft	Rs: 14,868.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		885.00	@ Rs:11948/36	%Cft	Rs: 105,742.0
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
10	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		430.00	@ Rs:337/-	P.Cft	Rs: 144,910.0
			(Rs: three hund: thirty seven only)		
11	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		21.000	@ Rs:5001/70	P.Cwt	Rs: 105,035.0
			(Rs: five thous: one & seventy only)		
12	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		1649.00	@ Rs: 1141/25	%Cft	Rs: 18,819.0
			(Rs: one thous: one hund: forty one & twenty five only)		
13	Extra lead 3 miles				
		1649.00	@ Rs: 579/41	%Cft	Rs: 6,711.0
			(Rs: five hund: sevnty nine & fourty one only)		
14	Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).				
		530.00	@ Rs:3327/50	%Cft	Rs: 17,635.00
			(Rs: three thous: three hund: twenty seven & fifty only)		
15	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1039.00	@ Rs:12674/36	%Cft	Rs: 131,687.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
16	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hing and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		307.00	@ Rs:228/90	P.Rft	Rs: 70,272.00
			(Rs: two hund: twenty eight & ninty only)		
17	P/F G.I frame chokats of size 7" x2" or 4" x 3" for Windowss using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and planst used in making and fixing .(S.I.No.29 P/98).				
		120.00	@ Rs: 240/50	P.Rft	Rs: 28,860.00
			(Rs: two hund: fourty & fifty only)		

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 18 P/F iron steel grill door with angle iron frame of 1-1/2" x 1-1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in Charge. (S.I.No.71P/93).

42.00	@ Rs:231/60	P.Sft	Rs:	9,727.00
-------	-------------	-------	-----	----------

(Rs: two hund: thirty one & sixty only)

- 19 Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).

231.00	@ Rs:180/50	P. Sft	Rs:	41,695.0
--------	-------------	--------	-----	----------

(Rs: one hund: eighty & fifty only)

- 20 Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).

4430.00	@ Rs:2206/60	% Sft	Rs:	97,752.0
---------	--------------	-------	-----	----------

(Rs: two thous: two hund: six & sixty only)

- 21 Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).

4430.00	@ Rs:2197/52	% Sft	Rs:	97,350.0
---------	--------------	-------	-----	----------

(Rs: two thous: one hund: ninty seven & twenty two only)

- 22 Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).

429.000	@ Rs:1287/44	% Sft	Rs:	5,523.0
---------	--------------	-------	-----	---------

(Rs: one thous: two hund: eighty seven & fourty four only)

- 23 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).

690.00	@ Rs: 902/93	P.Sft	Rs:	623,022.00
--------	--------------	-------	-----	------------

(Rs: nine hud: two & ninty three only)

- 24 Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

1323.000	@ Rs: 4411/82	% Sft	Rs:	58,368.00
----------	---------------	-------	-----	-----------

(Rs: four thous: four hund: eleven & eighty two only)

**(B) 1-1/2"Thick**

739.00	@ Rs: 2548/29	% S.ft	Rs:	18,832.00
--------	---------------	--------	-----	-----------

(Rs: two thous: five hund: forty eight & twenty nine only)

- 25 Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).

10.00	@ Rs: 14429/25	%Cft	Rs:	1,442.00
-------	----------------	------	-----	----------

(Rs: fourteen thous: four hund: twenty nine & twenty five only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
26	Laying floor of approved with glazed tiles 1/4" thick in white cement 1:2 over 3/4" thick cement mortar ratio 1:2 complete. (S.I.No.24 P/42).	250.00	@ Rs:27678/86	% Sft	Rs: 69,197.00
					(Rs: twenty seven thous: six hund seventy eight & eighty six c
27	White tile dado 1/4" thick laid in pigment over 1:2 cement sand mortor 3/4" thick including finishing. (S.I.No.38 P/44).	1018.00	@ Rs:28299/30	% Sft	Rs: 288,087.0
					(Rs: twenty eight thous: two hund ninety nine & thirtyonly)
28	White washing three coats. (S.I.No.26 ( c ) P/53).	400.00	@ Rs:829/95	% Sft	Rs: 3,320.00
					(Rs: eight hund: twenty nine & ninty five only)
29	Primary coat of chalk under distempring.	9043.00	@ Rs: 442/75	% S.ft	Rs: 40,037.00
					(Rs: four hund; fourty tow & seventy five only)
30	Distempring three coats	9043.00	@ Rs:1079/65	% Sft	Rs: 97,632.00
					(Rs: one thous: seventy nine & sixty five only)
(B)	<u>Two coats</u>	2441.00	@ Rs:1043/90	% Sft	Rs: 25,481.00
					(Rs: ten hund; forty three & ninty only)
31	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).	1933.00	@ Rs:2116/41	% Sft	Rs: 40,910.0
					(Rs: two thous: one hund: sixteen & fourty one only)
32	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	3211.00	@ Rs: 1948/10	% Sft	Rs: 62,553.00
					(Rs: one thous: nine hund: fourty eight & ten only)
33	Laying Murum flooring consisting of 1" layer of fine powdery or flakey variety of Murum spread over 9" thick sub-base comprising of hand packes rubble or broken bricks properly watered and rammed provided over well rammed. (S.I.No: 1 P. 39).	740.00	@ Rs: 3918/20 P R: 1422/58	% Sft	Rs: 10,527.00
					(Rs: one thous: four hund: twenty two & twenty only)

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 34 Providing & fixing cement paving blocks flooring having size of 197 x 97 x 80 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 psi l/c filling the joints with hill sand and laying in specified manner / patter and design etc complete. (S.I.No: 74 P/49).

740.00

@ Rs:199/77

P.Sft

Rs: 147,830.0

(Rs:one hund; ninty nine & seventy seven only)

G.Total:

Rs: 2,410,846.0

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

**PART-B**

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.  

26.00      @ Rs: 4802/60      P.No:      Rs: 124,867.00  
(Rs: four thous: eight hund; two & sixty only)
  
- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and flc for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)  

6.00      @ Rs: 4928/-      P.Each      Rs: 29,568.00  
(Rs: four thous: nine hund; twenty eight only)
  
- 3 Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed  

6.00      @ Rs: 2533/47      P.No:      Rs: 15,200.00  
(Rs: four thous: five hund; thirty three & forty seven only)
  
- 4 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.  

32.00      @ Rs: 447/15      P.No:      Rs: 14,308.00  
(Rs: four hund; forty seven & fifteen only)
  
- 5 P/F 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden pleat (a) Standard pattern. (S.I.No.3 (a) P/7).  

6.00      @ Rs:2376/-      P.Each      Rs: 14,256.00  
(Rs: two thous: three hund; seventy six only)
  
- 6 S/F conceled stop cock of superior quality with C.P head 1/2" dia.  

32.00      @ Rs: 889/46      P.No      Rs: 28,462.00  
(Rs: eight hund; eighty nine forty six only)
  
- 7 S/F long bib-cock of superior quality with C.P head 1/2" dia  

30.00      @ Rs: 1384/24      P.No      Rs: 41,527.00  
(Rs: one thous: three hund: eighty four & twenty four only)
  
- 8 S/F Swan type piller cock of superior quality etc:  

6.00      @ Rs: 877/80      P.Gallan      Rs: 5,266.00  
(Rs: eight hund; seventy seven & eighty only)





S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 9 providing chambers (15"X19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 block set-on 1:6 cement mortar 6" thick C.C.1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4, flooring complete with hinged clear opening (Wt: Qr) etc fixed in cement concrete 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).

10.00	@ Rs: 5913/22	Each	Rs:	59,132.00
-------	---------------	------	-----	-----------

(Rs: five thous: nine hund; thirteen & twenty two only)

- 10 S/F fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate iron of cement concrete 1:2:7 and making and connection for inlet- outlet and over flow pipe etc complete (350 gallons).

3.00	@ Rs: 30773/42	P.Gallan	Rs:	92,320.00
------	----------------	----------	-----	-----------

(Rs: thirty thous; seven hund; seventy four & forty two only)

(B) 250 Gallons.

1.00	@ Rs: 21989/61	P.Gallan	Rs:	21,990.00
------	----------------	----------	-----	-----------

(Rs: Twenty One thous: nine hund: eighty nine & Sixty only)

- 11 Providing and fixing handle valves (china). (S.I.No: 5 P/ 17).

(a) 1" dia

10.00	@ Rs: 365/42	Each	Rs:	3,654.00
-------	--------------	------	-----	----------

(Rs: three hund: sixty five & forty two only)

<b>Total:</b>	<b>Rs:</b>	<b>450,550.0</b>
---------------	------------	------------------

(B) N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separately recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

<u>(a) 3/4" Dia</u>	300.00	@ Rs: 78/01	P.No	Rs:	23,403.00
---------------------	--------	-------------	------	-----	-----------

(Rs: sevnty eight & One only)

<u>(b) 1" Dia</u>	120.00	@ Rs: 97/91	P.No	Rs:	11,749.00
-------------------	--------	-------------	------	-----	-----------

(Rs: ninety seven & ninty one only)

<u>(c) 1-1/2" Dia</u>	100.00	@ Rs: 125/04	P.No	Rs:	12,504.00
-----------------------	--------	--------------	------	-----	-----------

(Rs: one hund; twenty five & four only)

<u>(d) 4" Dia</u>	470.00	@ Rs: 397/77	P.No	Rs:	186,952.00
-------------------	--------	--------------	------	-----	------------

(Rs: three hund: ninty seven & seventy seven only)

<u>(e) 6" Dia</u>	300.00	@ Rs: 757/59	P.No	Rs:	227,277.00
-------------------	--------	--------------	------	-----	------------

(Rs: seven hund: fifty seven & fifty nine only)

<u>(f) 8" Dia</u>	200.00	@ Rs:986/42	P.No	Rs:	197,284.00
-------------------	--------	-------------	------	-----	------------

(Rs: nine hund; eighty six & forty two. only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>(a) 3/4" Dia</u>	35.00	@ Rs: 103/05	P.No	Rs:	3,606.00
(Rs: one hund; three & five only)					

<u>(b) 1" Dia</u>	12.00	@ Rs: 125/90	P.No	Rs:	1,510.00
(Rs: one hund; twenty five & ninty only)					

<u>(c) 4" Dia</u>	38.00	@ Rs: 425/45	P.No	Rs:	16,167.00
(Rs: four hund: twenty five & forty five only)					

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>(a) 3/4" Dia</u>	22.00	@ Rs: 110/40	P.No	Rs:	2,428.00
(Rs: one hund; ten & fourteen only)					

<u>(b) 1" Dia</u>	11.00	@ Rs: 132/43	P.No	Rs:	1,456.00
(Rs: one hund: thirty two & forty three only)					

<u>(c) 4" Dia</u>	8.00	@ Rs:712/75	P.No	Rs:	5,702.00
(Rs: seven hund: twelve & seventy five only)					

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

<u>(a) 3/4" Dia</u>	27.00	@ Rs:98/15	P.No	Rs:	2,650.00
(Rs: ninty eight & fifteen only)					

<u>(b) 1" Dia</u>	16.00	@ Rs:110/40	P.No	Rs:	1,766.00
(Rs: one hund: ten & fourty only)					

<u>(c) 4" Dia</u>	10.00	@ Rs:343/83	P.No	Rs:	3,438.00
(Rs: three hund; forty three & eighty three only)					

- 5 P/F UNION of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>(b) 1" Dia</u>	8.00	@ Rs:381/37	P.No	Rs:	3,050.00
(Rs: three hund; eighty one & thirt seven only)					

S.No:	Description	Qty:	Rate	Unit	Amount
6	P/F UPVC P-Trap W/Elbow (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>4" Dia</u>	8.00	@ Rs:818/04	P.No	Rs: 6,544.00
			(Rs: eight hund: eighteen & four only)		
7	P/F UPVC WYE (Y) (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
		10.00	@ Rs:933/13	P.No	Rs: 9,331.00
			(Rs: nine hund; thirty three & thirteen only)		
8	P/F UPVC PLUG ELBOW (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>4" Dia</u>	25.00	@ Rs:677/65	P.No	Rs: 16,941.00
			(Rs: six hund; seventy seven & sixty five only)		
9	P/F UPVC PLUG TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>4" Dia</u>	25.00	@ Rs:847/42	P.No	Rs: 21,185.00
			(Rs: eight hund; fourty seven & fourty two only)		
10	P/F UPVC VENT COWEL (LOCAL) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).				
	<u>4" Dia</u>	25.00	@ Rs:187/93	P.No	Rs: 4,698.00
			(Rs: one hund: eighty seven & ninty three only)		

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
11	P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete. (R.A)				
	<u>Nyloon Plastic pipe</u>	440.00	@ Rs: 77/- (Rs: seventy seven only)	P.Rft	Rs: 33,880.00
12	Providing & Fixing Hand pump Machine (R.A)				
	<u>Machine</u>	3.00	@ Rs: 4500/- (Rs: four thous: five hund: only)	Each	Rs: 13,500.00
13	Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).				
		4.00	@ Rs:14201/- (Rs: fourteen thous: two hund: one only)	P.No:	Rs: 56,804.00
Total:					Rs: 863,825.0

  
XCN

## SCHEDULE-B

**Name of Work:-** Integrated Rehabilitation of Existing Primary / Middle Building School  
Taluka Bakrani (2017-18 Prog) At : GBPS Yar Muhammad Tharecha  
Taluka Bakrani

S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

- 1 Dismenlin 2nd Class tiles roofing.  
950.00 @Rs: 378.13 Rs: 3592.71  
(Rs: Three Hundred Seventy Eight & P.S Thirteen only)
- 2 Dismenlin Pacca brick work in cement mortor  
950.00 @Rs: 1285.63 Rs: 12213.49  
(Rs: Twolive thousand Eighty Five & P.S Sixty Three only)
- 3 Excavation in foundation of building bridges and other structure member with excavated lead upto or chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).  
400.00 @Rs: 3176.25 %0 C Rs: 1270.50  
(Three Thousand One Hund:Seventy Six & P.S Twenty Five only)
- 4 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).  
300.00 @Rs: 8694.95 % Cft Rs: 26084.85  
( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
- 5 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 23.  
500.00 @Rs: 11948.36 % S.ft Rs: 59741.80  
( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six onl
- 6 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)  
150.00 @Rs: 337.00 P.Cft Rs: 50550.00  
( Three Hundred Thirty Seven only)
- 7 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)  
8.035 @Rs: 5001.70 P.CW Rs: 40188.66  
(Five Thousand One &P.S Seventy ).
- 8 S/F sand floor and plugging into walls (S.I.No 29 P/31).  
9000.00 @Rs: 1141.25 %Cft Rs: 102712.50  
(Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)
- 9 Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P/  
1500.00 @Rs: 12674.36 % Cft Rs: 190115.40  
(Twlove thousand Six Hundred Seventy Four & Thirty Six only)
- 10 Supplying Girders at site of work(Sch: of Material)  
9.723 @Rs: 3850.00 P.Cwt Rs: 37434.00  
(Three Thousand Eight Hundred Fifty only)
- 11 Supplying T-iron at site of work (Sch: of Material).  
18.143 @Rs: 3375.00 P.Cwt Rs: 64861.00  
(Three Thousand Three Hundred Seventy Five only)

  
**XEN**

S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

- 12 First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leaping over 1/4" thick ceme 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in mortar with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)  
950.00 @Rs: 11443.10 %Sft Rs: 108709.45  
(Rs:Eleven thousand Four Hundred Fourty Three & P.S Ten )
- 13 Pacca brick work in other than building i/c stricking of joints cement sand mortar Ratio 1:6 (S.I No 5 )  
800.00 @Rs: 12346.65 % Cft Rs: 98773.20  
(Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five only)
- 14 Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)  
4000.00 @Rs: 2206.60 % Sf Rs: 88264.00  
( Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
- 15 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)  
4000.00 @Rs: 2197.52 %S.ft Rs: 87900.80  
( Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
- 16 Cement pointing and stricking of joints on walls ratio. 1: 2 ( S.I No.19 (a) P/53)  
2000.00 @Rs: 1287.44 %Cft Rs: 25748.80  
( Twolive Thousand Eighty Seven & P.S Fourty Four only)
- 17 Notice board made with cement.  
48.00 @Rs: 58.11 % Sf Rs: 2789.28  
( Eighty Eight & P.S Eleven only)
- 18 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)  
48.00 @Rs: 902.93 %Cft Rs: 43340.64  
( Nine Hundraed Two P.S Ninty Three only)
- 19 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2 " th  
600.00 @Rs: 3275.50 % S.ft Rs: 19653.00
- 20 White wash three coats (S.I.No 26 ( c ) 59).  
700.00 @Rs: 829.95 P.Sft Rs: 5809.65  
(Rs: Four Hundred Twenty Five & P.S Eighty Four only)
- 21 Primary coat of chalk under distemping ( S.I No: 23 P 59)  
5000.00 @Rs: 442.75 % Sft Rs: 22137.50  
( Four Hundred Fourty Two & P.S Seventy Five only)
- 22 Distemping three coats, (S.I.No 24 (b) P/59)  
5000.00 @Rs: 1079.65 % Sft Rs: 53982.50  
(Rs: One Thousand Seventy Nine & P.S Sixty Five only)
- 23 Painting doors & Window any type.  
300.00 @Rs: 2116.41 %Cft Rs: 6349.23  
(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One onl

S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

24 Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open  
(S.I.No 4 d P/76 ii )

56.00 @Rs: 1270.83 %Cft Rs: 711.66

(Rs: Five Hundred Eighty Five & Fifty Four only)

Rs: 1152935

  
XEN

## SCHEDULE-B

**Name of Work:-** Integrated Rehabilitation of Existing Primary / Middle Building School  
Taluka Bakrani (2017-18 Prog) At: GBPS Qadir Bux Khakhrani  
Taluka Bakrani

S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------


- 1 Dismenlin 2nd Class tiles roofing.  
950.00 @Rs: 378.13 Rs: 3592.71  
(Rs: Three Hundred Seventy Eight & P.S Thirteen only)
- 2 Dismenlin Pacca brick work in cement mortor  
950.00 @Rs: 1285.63 Rs: 12213.49  
(Rs: Twolive thousand Eighty Five & P.S Sixty Three only)
- 3 Excavation in foundation of building bridges and other structure member with excavated lead upto or chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).  
400.00 @Rs: 3176.25 %0 C Rs: 1270.50  
(Three Thousand One Hund:Seventy Six & P.S Twenty Five only)
- 4 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).  
300.00 @Rs: 8694.95 % Cft Rs: 26084.85  
( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
- 5 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 23.  
500.00 @Rs: 11948.36 % S.ft Rs: 59741.80  
( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six onl
- 6 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)  
150.00 @Rs: 337.00 P.Cft Rs: 50550.00  
( Three Hundred Thirty Seven only)
- 7 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)  
8.035 @Rs: 5001.70 P.CW Rs: 40188.66  
(Five Thousand One &P.S Seventy ).
- 8 S/F sand floor and plugging into walls (S.I.No 29 P/31).  
9000.00 @Rs: 1141.25 %Cft Rs: 102712.50  
(Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)
- 9 Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P/  
1500.00 @Rs: 12674.36 % Cft Rs: 190115.40  
(Twlove thousand Six Hundred Seventy Four & Thirty Six only)
- 10 Supplying Girders at site of work(Sch: of Material)  
9.723 @Rs: 3850.00 P.Cw Rs: 37434.00  
(Three Thousand Eight Hundred Fifty only)





S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

- 11 Supplying T-iron at site of work (Sch: of Material).  
18.143 @Rs: 3375.00 P.Cw Rs: 64861.00  
(Three Thousand Three Hundred Seventy Five only)
- 12 First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leaping over 1/4" thick ceme  
1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in :  
mortor with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)  
950.00 @Rs: 11443.1 %Sft Rs: 108709.45  
(Rs:Eleven thousand Four Hundred Fourty Three & P.S Ten )
- 13 Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 )  
800.00 @Rs: 12346.7 % Cft Rs: 98773.20  
(Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five only)
- 14 Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)  
4000.00 @Rs: 2206.60 % Sf Rs: 88264.00  
( Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
- 15 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)  
4000.00 @Rs: 2197.52 %S.ft Rs: 87900.80  
( Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
- 16 Cement pointing and stricking of joints on walls ratio. 1: 2 ( S.I No.19 (a) P/53)  
2000.00 @Rs: 1287.44 %Cft Rs: 25748.80  
( Twolive Thousand Eighty Seven & P.S Fourty Four only)
- 17 Notice board made with cement.  
48.00 @Rs: 58.11 % Sft Rs: 2789.28  
( Eighty Eight & P.S Eleven only)
- 18 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar  
panelled and glazed (b) 1-3/4thicks.(Only Shutters)  
48.00 @Rs: 902.93 %Cft Rs: 43340.64  
( Nine Hundraed Two P.S Ninty Three only)
- 19 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2 " th  
600.00 @Rs: 3275.50 % S.ft Rs: 19653.00
- 20 White wash three coats (S.I.No 26 ( c ) 59).  
700.00 @Rs: 829.95 P.Sft Rs: 5809.65  
(Rs: Four Hundred Twenty Five & P.S Eighty Four only)
- 21 Primary coat of chalk under distemping ( S.I No: 23 P 59)  
5000.00 @Rs: 442.75 % Sft Rs: 22137.50  
( Four Hundred Fourty Two & P.S Seventy Five only)
- 22 Distemping three coats, (S.I.No 24 (b) P/59)  
5000.00 @Rs: 1079.65 % Sft Rs: 53982.50  
(Rs: One Thousand Seventy Nine & P.S Sixty Five only)



S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

23 Painting doors & Window any type.

300.00 @Rs: 2116.41 %Cft Rs: 6349.23

(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One onl

24 Preparing surface painting guards bars gates iron grating railling i/c standards brass etc similar open  
(S.I.No 4 d P/76 ii)

56.00 @Rs: 1270.83 %Cft Rs: 711.66

(Rs: Five Hundred Eighty Five & Fifty Four only)

---

Rs: 1152935

---

  
**XEN**

**Schedule "B"**

**Name of Wrok :- Integrated Rehabilitation of Existing Primary Middle School Buildings (2017-18 Prog)**  
**At : GGPS Syed Bachal Shah Taluka Bakrani**

S.No	Description	Qnty:	Rate		Amount
1	Dismantling R.C.C work 1:2:4.				
			=	401.0	Cft
		@Rs: 5445.0	%Cft	Rs:	21880.0
2	Dismantling pacca brick work in cement mortar.				
			=	854.00	Cft
		@Rs: 1285.63	%Cft	Rs:	10979.3
3	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).				
			=	1,080.0	Cft
		@ Rs: 3176.25	%0 Cft	Rs:	3,430.35
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).				
			=	1,218.0	Cft
		@ Rs :8694.95	% Cft	Rs:	105,904.49
5	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) 23.				
			=	280.0	Sft
		@ Rs: 11948.36	% Cft	Rs:	33455.41
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)				
			=	510.00	Pcft
		@ Rs: 337.0	P.Cft	Rs:	171870.00
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)				
			=	29.044	P.Cwt
		@ Rs: 5001.70	P.CWt	Rs:	145,269.37
8	S/F sand floor and plugging into walls (S.I.No 29 P/31).				
			=	3368	P.Cwt
		@Rs: 1141.25	%Cft	Rs:	38437.30
9	Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/24)				
			=	2119.00	
		@Rs: 12674.36	%Cft	Rs:	268,569.69
10	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)				
			=	3,124.0	
		@Rs: 2206.60	% Sft	Rs;	68934.18
11	Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)				
			=	3,124.0	Sft
		@ Rs: 2197.52	% Sft	Rs:	68650.52
12	P/F G.I frame chokats of size 7" x2" or 4" x 3" for Doors using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand reparing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)				
			=	35.00	RFT
		@ Rs: 228.90	P.RFT	Rs:	8,011.50
13	P/F G.I frame chokats Window Of size 7" x2" or 4" x 3" for Windowss using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand reparing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)				
			=	90.0	RFT
		@ Rs: 240.50	P.RFT	Rs:	21,645.00
14	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and square bars 4" centre to cement .				
			=	48.0	SFT
		@ Rs: 726.72	%SFT	Rs:	34,883



S.No	Description	Qty:	Rate		Amount
15	Supplying Girders at site of work(Sch: of Material)				
			=	16.107	
		@Rs: 3850.00	P.cwt	Rs:	62,011.95
16	Supplying T-iron at site of work (Sch: of Material).				
			=	19.008	
		@Rs: 3575.00	P.cwt	Rs:	67,953.60
17	First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leeping over 1/4" thick cement plaster 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in 1:6 cement mortar with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)				
			=	1,100.300	
		@Rs: 11443.10	% Sft	Rs:	125,908.43
18	Errection of rolled steel beams or old rails in roof etc crrection and fixing in position.				
			=	35.115	
		@Rs: 186.04	P.cwt	Rs:	6,532.79
19	Pacca brick work in other than building i/c stricking of joints cement sand mortar Ratio 1:6 (S.I No 5 ( C ) P/24)				
			=	1,050.0	CFT
		@Rs: 12346.65	%CFT	Rs:	129,639.83
20	Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.19 (a) P/53)				
			=	1400.0	SFT
		@ Rs: 1287.44	%SFT	Rs;	18024.16
21	Notice Board mad with cement. (S.I.No 1 P/100).				
			=	64.0	Cft
		@Rs: 58.11	P.Sft	Rs:	3719.0
22	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.				
			=	200.0	P.sft
		@Rs: 902.93	P.Sft	Rs:	180,586.00
23	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick. (S.I No:16 ( C ) P/46)				
			=	3328.0	Cft
		@Rs: 4411.82	% Sft	Rs:	146825.37
(b)	Ratio 2" thick,				
			=	1361.89	Cft
		@Rs: 3275.50	% Sft	Rs:	44608.6
24	White wash three coats.				
			=	928.0	Sft
		@Rs: 829.95	% Sft	Rs:	7,701.9
25	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voilds with chalk plaster of paris and then painting with weather coat of approved make old surface. (S.I.No 39 (a) P/62).				
			=	3455.0	Sft
		@Rs: 1948.10	%Sft	Rs;	67306.86
26	Distempering three coats ( S.I No: 24( B ) P 59)				
			=	2,019.0	Sft
		2,019.0 @ Rs: 1043.90	% Sft	Rs:	21,076.0
27	Painting doors & window any type, (S.I.No 05 P/ 76)				
			=	192.0	Cft
		@Rs: 2116.41	% Sft	Rs;	4046.00

S.No	Description	Qty:	Rate	Amount
------	-------------	------	------	--------

- 28 P/L Hala pattered tiles glazed 4" x 4 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile.  
( S.I No: 62 P/53)

@Rs: 34520.31    %Sft    

1889.00	Sft
Rs:	65160.54

<b>Total</b>	<b>Rs:</b>	<b>1953021</b>
--------------	------------	----------------

  
**XEN**

# SCHEDULE-B

**Name of Work:-** Integrated Rehabilitation of Existing Primary / Middle Building School  
Taluka Bakrani (2017-18 Prog) At : GBLSS New Abad Taluka Bakrani

S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

- 1 Dismantlin 2nd Class tiles roofing.  
950.00 @Rs: 378.13 Rs: 3592.71  
(Rs: Three Hundred Seventy Eight & P.S Thirteen only)
- 2 Dismantlin Pacca brick work in cement mortor  
950.00 @Rs: 1285.63 Rs: 12213.49  
(Rs: Twolive thousand Eighty Five & P.S Sixty Three only)
- 3 Excavation in foundation of building bridges and other structure member with excavated lead upto or chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).  
400.00 @Rs: 3176.25 %0 C Rs: 1270.50  
(Three Thousand One Hund:Seventy Six & P.S Twenty Five only)
- 4 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).  
300.00 @Rs: 8694.95 % Cft Rs: 26084.85  
( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
- 5 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 23.  
500.00 @Rs: 11948.4 % S.ft Rs: 59741.80  
( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six onl
- 6 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)  
150.00 @Rs: 337.00 P.Cft Rs: 50550.00  
( Three Hundred Thirty Seven only)
- 7 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)  
8.035 @Rs: 5001.70 P.CW Rs: 40188.66  
(Five Thousand One &P.S Seventy ).
- 8 S/F sand floor and plugging into walls (S.I.No 29 P/31).  
9000.00 @Rs: 1141.25 %Cft Rs: 102712.50  
(Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)
- 9 Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P/  
1500.00 @Rs: 12674.36 % Cft Rs: 190115.40  
(Twlove thousand Six Hundred Seventy Four & Thirty Six only)
- 10 Supplying Girders at site of work(Sch: of Material)  
9.723 @Rs: 3850.00 P.Cwt Rs: 37434.00  
(Three Thousand Eight Hundred Fifty only)

*[Signature]*  
JEN

S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

- 11 Supplying T-iron at site of work (Sch: of Material).  
18.143 @Rs: 3375.00 P.Cw Rs: 64861.00  
(Three Thousand Three Hundred Seventy Five only)
- 12 First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leeping over 1/4" thick ceme 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in mortor with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)  
950.00 @Rs: 11443.1 %Sft Rs: 108709.45  
(Rs:Eleven thousand Four Hundred Fourty Three & P.S Ten )
- 13 Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 )  
800.00 @Rs: 12346.7 % Cft Rs: 98773.20  
(Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five only)
- 14 Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)  
4000.00 @Rs: 2206.60 % Sft Rs: 88264.00  
( Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
- 15 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)  
4000.00 @Rs: 2197.52 %S.ft Rs: 87900.80  
( Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
- 16 Cement pointing and stricking of joints on walls ratio. 1: 2 ( S.I No.19 (a) P/53)  
2000.00 @Rs: 1287.44 %Cft Rs: 25748.80  
( Twolive Thousand Eighty Seven & P.S Fourty Four only)
- 17 Notice board made with cement.  
48.00 @Rs: 58.11 % Sft Rs: 2789.28  
( Eighty Eight & P.S Eleven only)
- 18 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)  
48.00 @Rs: 902.93 %Cft Rs: 43340.64  
( Nine Hundraed Two P.S Ninty Three only)
- 19 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2 " tl  
600.00 @Rs: 3275.50 % S.ft Rs: 19653.00
- 20 White wash three coats (S.I.No 26 ( c ) 59).  
700.00 @Rs: 829.95 P.Sft Rs: 5809.65  
(Rs: Four Hundred Twenty Five & P.S Eighty Four only)
- 21 Primary coat of chalk under distemping ( S.I No: 23 P 59)  
5000.00 @Rs: 442.75 % Sft Rs: 22137.50  
( Four Hundred Fourty Two & P.S Seventy Five only)
- 22 Distemping three coats, (S.I.No 24 (b) P/59)  
5000.00 @Rs: 1079.65 % Sft Rs: 53982.50  
(Rs: One Thousand Seventy Nine & P.S Sixty Five only)

  
**XEN**

S.No	Discription	Quantity	Ratee	Unit	Rs:	Amount.
------	-------------	----------	-------	------	-----	---------

23 Painting doors & Window any type.

300.00 @Rs: 2116.41 %Cft Rs: 6349.23

(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One onl

24 Preparing surface painting guards bars gates iron grating railling i/c standards brass etc similar open  
(S.I.No 4 d P/76 ii )

56.00 @Rs: 1270.83 %Cft Rs: 711.66

(Rs: Five Hundred Eighty Five & Fifty Four only)

Rs: 1152935





## Schedule - B

**Name of Work :-** Integrated Rehabilitation of Existing Primary School / Middle School Buildings  
Taluka Dokri (2017-18 Prog) At : GBPS Seehar Village Taluka Dokri

S.No	Description	Quantity	Rate	Unit	Quantity	Amount
------	-------------	----------	------	------	----------	--------

- 1 Dismantling R.C.C Work. Separating rainfore cement from concrete cleaning and, Straightning the Same (S.I No: (a) P/10)

= 468

@ Rs: 5445.00      % Cft      Rs: 25483  
(Twenty five thousands four hundred eighty three only )

- 2 Dismantling pacca brick work in cement mortar.( s.i no: (a) P/ 10)

= 136

@ Rs:1285.63      % Cft      Rs: 1748  
(One thousands seven hundred forty eight only )

- 3 Removing cement or lime Plaster 1:6. (S.I.No: 53 P 13 ).

= 1133

@Rs: 121.00      %SFT      Rs: 1371  
(One thousands three hundred seventy one only )

- 4 Dismantlin C.C plain 1:2:4. (S.I.No 19 ( c ) P/11).

= 143

@ Rs: 3327.50      % Cft      Rs: 4758  
(four thousands seven hundred fifty eight only )

- 5 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P- 14).

= 143

@ Rs :8694.95      % Cft      Rs: 12434  
(Twelve thousands four hundred thirty four only )

- 6 Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 ( C ) P- 20.)

= 243

@ Rs:11948.36      % S.ft      Rs: 29035  
(Twenty nine thousands thirty five only )

- 7 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a) P/16)

230

@ Rs: 337.00      P.Cft      Rs: 77510  
(Twenty five thousands nine hundred forty nine only )

- 8 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 8 (b) P/16)

= 11.200

@ Rs: 5001.70      P.CWt      Rs: 56019  
(Eighteen thousands nine hundred thirteen only )

  
**XEN**

S.No	Description	Quantity	Rate	Unit	Quantity	Amount
------	-------------	----------	------	------	----------	--------

- 9 Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P/20)

= 2500

@Rs: 12674.36 %Cft Rs: 316859  
(Fourty thousands eight hundred eleven only )

- 10 Supplying filling Sand under floor pluging into walls, (S.I.No 29 P/ 25).

= 3280

@Rs: 1141.25 %Sft Rs: 37433  
(Thirty seven thousands four hundred thirty three only )

- 11 Supplying Girders at site of work (Sch: of Material) ( S.I 10 (A) P/93)

= 45.00

@ Rs: 3850.00 P.CWt Rs: 161100  
(Eighty thousands eight hundred one rupes only )

- 12 Supplying T-iron at site of work (Sch: of Material). ( S.I 10 (B) P/93)

= 40.25

@ Rs: 3575.00 P.CWt Rs: 143894  
(Sixty three thousands eight hundred fifty only )

- 13 Ist class tilesroofing consisting of 4" earth and 1" plaster with Gobri leeping over 1/4" thick cement plaster 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in 1:6 cement mortor with 1/4" thick .

= 1996

@ Rs: 11443.10 %Cft Rs: 228404  
(One lac seven thousands five hundred seventy two only )

- 14 Errection of rolled steel beams or old rails in roof etc crrrection and fixing in position( S.I No 6 P/90 )

= 85.250

@ Rs: 186.44 P.sft Rs: 15894  
( Seven thousands five hundred thirty eight only )

- 15 P/F G.I frame chokats of size 7" x2" or 4" x 3" for Doors using 20 gauge G.I sheet i/c solded higues and fixing at site with necessary hold fots filling with cement sand repairing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)

= 15.75

@ Rs: 228.90 P.Rft Rs: 4550  
( Four thousands five hundred fifty only )

- 16 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.

= 100

@Rs: 902.93 P.Sft Rs: 90293  
(Sixty thousands two hundred fifty three only )

  
**XEN**

S.No	Description	Quantity	Rate	Unit	Quantity	Amount
------	-------------	----------	------	------	----------	--------

17 Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13(b) P/57)

= 4445

@Rs: 2206.60 % Sft Rs; 98083  
( Fourty nine thousands nine only )

18 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 51)

= 4445

@ Rs: 2197.52 %C.ft Rs: 97680  
( Fourty eight thousands eight hundred seven rupes only )

19 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick.  
(S.I No:16 ( C ) P/41)

= 5800

@Rs: 4411.82 % Sft Rs: 255886  
( Fifty six thousands six hundred four rupes only )

20 S/F in position iron steel grill of 3/4" X 1/4 Size flate iron of approved design i/c painting three coats etc comple  
not to beless than 3.7 Lbs sq: ft: of finished grill. ( S.I No: 26 P. No: 92 )

= 189

@Rs: 194.16 %Sft Rs: 36696  
(Thirty six thousands six hundred ninty six only )

21 White wash three coats.( s.i no: 26 © P/ 53 )

= 2500

@ Rs:829.95 %Cft 20749  
( Seven thousands thirty eight rupes only )

22 Distempering three coats ( S.I No: 24( B ) P 53)

= 4800

@ Rs: 1079.65 %Cft 51823  
(Thrity one thousands three hundred fifty three rupes only )

23 Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open work.  
(S.I.No 4 II d P/76)

= 866

@ Rs: 1270.83 %Sft 11005  
(Eleven thousands five rupes only )

24 Painting doors & window any type, (S.I.No 05 P/ 76)

= 374

@ Rs: 2116.41 % Sft Rs: 7915  
( Seven thousands nine hundred fifteen only )

  
XEN

S.No	Description	Quantity	Rate	Unit	Quantity	Amount
------	-------------	----------	------	------	----------	--------

25 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approved make old surface. (S.I.No 39 (a) P/62).

= 3800

@Rs: 1948.10      % Sft      Rs:      74,028  
(Thrity thousands three hundred ninty rupes only )

**Total Rs: 1860650**



**SCHEDULE " B "**

S.No: 27

NAME OF WORK:- INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL BUILDINGS TALUKA LARKANO (2017-18 PROGRAMME) AT GBPS SHAIKH TAGAR TALUKA LARKANO.

S.No	Description	Qty:	Rate	Unit	Amount
1	Removing cement or lime plaster. (S.I.No.53 P/13).				
		1954.00	@ Rs:121/- (Rs: one hund: twenty one only)	% Sft	Rs: 2,364.00
2	Dismantling cement concrete plain 1:2:4. (S.I.No.19 (c) P/10).				
		22.00	@ Rs: 3327/50 (Rs: three thous: two hund: twenty seven & fifty only)	% Cft	Rs: 732.00
3	Excavation in foundation of building bridges and other structures including dag bellling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		508.00	@ Rs:3176/25 (Rs: three thous: one hund: seventy hund: twenty five only)	%0 Cft	Rs: 1,614.00
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).				
		495.00	@ Rs:8694/95 (Rs: eight thous: six hund: ninty four & ninty five only)	% Cft	Rs: 43,040.00
5	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		372.00	@ Rs:11948/36 (Rs: eleven thous: nine hund: eighty five & thirty six only)	% Cft	Rs: 44,448.00
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		36.00	@ Rs:337/- (Rs: three hund: thirty seven only)	P.Cft	Rs: 12,132.00
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		1.285	@ Rs:5001/70 (Rs: five thous: one & seventy only)	P.Cwt	Rs: 6,427.00
8	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		4472.00	@ Rs: 1141/25 (Rs: one thous: one hund: forty one & twenty five only)	% Cft	Rs: 51,037.00
9	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		31.00	@Rs:12674/36 (Rs: tweleve thous: six hund: seventy four & thirty six only)	% Cft	Rs: 3,929.00



S.No.	Description	Qty:	Rate	Unit	Amount
10	Pacca brick work other than building including striking of joints upto 20' ft. height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		123.00	@ Rs:12346/65 % Cft		Rs: 15,186.00
			(Rs: twelve thous: three forty six & sixty five only)		
11	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		789.00	@ Rs:660/- % Sft		Rs: 12,896.00
			(Rs: six hund: sixty only)		
12	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2832.00	@ Rs:2206/60 % Sft		Rs: 62,490.00
			(Rs: two thous: two hund: six & sixty only)		
13	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		2832.00	@ Rs:2197/52 % Sft		Rs: 62,233.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		
14	Notice board made with cement. (S.I.No: 1 P/94).				
		64.00	@ Rs:58/11 P. Sft		Rs: 3,719.00
			(Rs: fifty eight & eleven only)		
15	First Class deodar wood wrought, joinery in doors and windows etc. fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		35.00	@ Rs: 902/93 P.Sft		Rs: 31,603.00
			(Rs: nine hund: two & ninty three only)		
16	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).				
		217.00	@ Rs:180/50 P. Sft		Rs: 39,169.00
			(Rs: one hund: eighty & fifty only)		
17	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		596.00	@ Rs:1287/44 % Sft		Rs: 7,673.00
			(Rs: one thous: two hund: eighty seven & fourty four only)		
18	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		1177.00	@ Rs: 4411/82 % Sft		Rs: 51,927.00
			(Rs: four thous: four hund: eleven & eighty two only)		

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
19	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).	48.00	@ Rs:726/72	P. Sft	Rs: 34,883.0
					(Rs: seven hund: twenty six & seventy two only)
20	White washing three coats. (S.I.No.26 ( c ) P/53).	1224.00	@ Rs:829/95	% Sft	Rs: 10,159.00
					(Rs: eight hund: twenty nine & ninty five only)
21	Primary coat of chalk distempering. (S.I.No.23 P/57).	4551.00	@ Rs:442/75	% Sft	Rs: 14,739.00
					(Rs: four hund; fourty tow & seventy five only)
22	Distempering two coats. (S.I.No.24 (b) P/53).	4551.00	@ Rs:1043/90	% Sft	Rs: 47,507.00
					(Rs: ten hund; forty three & ninty only)
23	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).	326.00	@ Rs:2116/41	% Sft	Rs: 6,899.00
					(Rs: two thous: one hund: sixteen & fourty one only)
24	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	2911.00	@ Rs: 1948/10	% Sft	Rs: 56,709.00
					(Rs: one thous: nine hund: fourty eight & ten only)
25	Painting guard bars , gates iron bars gratings railings i/c standard barse etc: smiler open works.	96.00	@ Rs:1270/83	% S.ft	Rs: 1,220.00
					(Rs: one thous: two hund: seventy & eighty three only)
G.Total:					Rs: 624,735.0

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern wit internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.  

2.00	@ Rs: 4802/60	Each	Rs:	9,605.00
(Rs: four thous: eight hund; two & sixty only)				
  
- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malloable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)  

2.00	@ Rs: 4928/-	P.Each	Rs:	9,856.00
(Rs: four thous: nine hund; twenty eighty only)				
  
- 3 Add: Extra for labour for providing and fixing of ertthern wire padestal white or coloured glazed  

1.00	@ Rs: 2533/47	P.No:	Rs:	2,533.00
(Rs: four thous: five hund; thirty three & fourty seven only)				
  
- 4 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.  

3.00	@ Rs: 447/15	P.No:	Rs:	1,341.00
(Rs: four hund: forty seven & fifteen only)				
  
- 5 P/F 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden pleat (a) Standard pattern. (S.I.No.3 (a) P/7).  

1.00	@ Rs:2376/-	P.Each	Rs:	2,376.00
(Rs: two thous: three hund; seventy six only)				
  
- 6 S/F conceled stop cock of superior quality with C.P head 1/2" dia.  

3.00	@ Rs: 889/46	P.No	Rs:	2,668.00
(Rs: eight hund; eighty nine forty six only)				
  
- 7 S/F long bib-cock of superior quality with C.P head 1/2" dia  

4.00	@ Rs: 1384/24	P.No	Rs:	5,536.00
(Rs: one thous: three hund: eighty four & twenty four only)				
  
- 8 S/F Swan type piller cock of superior quality etc:  

1.00	@ Rs: 877/80	P.Gallan	Rs:	878.00
(Rs: eight hund; seventy seven & eighty only)				
  
- 9 providing chambers (15"x19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 block set-on 1:6 cement mortor 6" thick C.C.1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) etc fixed in cement concreta 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).  

2.00	@ Rs: 5913/22	Each	Rs:	11,826.00
(Rs: five thous: nine hund; thirteen & twenty two only)				



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 11 S/F fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate iron of cement concrete 1:2:7 and making and commission for inlet- outlet and over flow pipe etc complete (150 gallons).

1.00	@ Rs: 87/95	P.Gallan	Rs:	13,192.00
------	-------------	----------	-----	-----------

(Rs: eighty seven & ninety five only)

**N.S.I**

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separately recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

<u>(a) 1/2" Dia</u>	10.00	@ Rs: 66/81	P.Rft	Rs:	668.00
---------------------	-------	-------------	-------	-----	--------

(Rs: sixty six & eighty one only)

<u>(b) 3/4" Dia</u>	80.00	@ Rs: 78/01	P.No	Rs:	6,240.00
---------------------	-------	-------------	------	-----	----------

(Rs: seventy eight & one only)

<u>(C) 1" Dia</u>	50.00	@ Rs: 97/91	P.No	Rs:	4,895.00
-------------------	-------	-------------	------	-----	----------

(Rs: ninety seven & Ninety one only)

<u>(d) 4" Dia</u>	50.00	@ Rs: 397/77	P.No	Rs:	19,888.00
-------------------	-------	--------------	------	-----	-----------

(Rs: three hundred; ninety seven & seventy seven only)

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B in accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>(A) 3/4" Dia</u>	20.00	@ Rs: 103/05	P.No	Rs:	2,061.00
---------------------	-------	--------------	------	-----	----------

(Rs: one hundred; three & five only)

<u>(B) 4" Dia</u>	4.00	@ Rs: 425/45	P.No	Rs:	1,701.00
-------------------	------	--------------	------	-----	----------

(Rs: four hundred; twenty five & forty five only)

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>(a) 3/4" Dia</u>	8.00	@ Rs: 110/40	P.No	Rs:	883.00
---------------------	------	--------------	------	-----	--------

(Rs: one hundred; ten & forty only)

<u>(B) 4" Dia</u>	2.00	@ Rs: 712/75	P.No	Rs:	1,425.00
-------------------	------	--------------	------	-----	----------

(Rs: seven hundred; twelve & seventy five only)

*[Handwritten signature]*

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

<u>3/4" Dia</u>	12.00	@ Rs: 98/15	P.No	Rs:	1,177.00
(Rs: ninty eight & fifteen only)					

- 5 P/F UPVC P-Trap W/Elbow (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	2.00	@ Rs: 818/04	P.No	Rs:	1,636.00
(Rs: eight hund; eighty & four only)					

- 6 P/F UPVC WYE (Y) (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	1.00	@ Rs:933/13	P.No	Rs:	933.00
(Rs: nine hund; thirty three & thirteen only)					

- 7 P/F UPVC PLUG ELBOW (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	1.00	@ Rs:677/65	P.No	Rs:	678.00
(Rs: six hund; seventy seven & sixty five only)					

- 8 P/F UPVC PLUG TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	2.00	@ Rs:847/42	P.No	Rs:	1,695.00
(Rs: eight hund; fourty seven & fourty two only)					

**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 9 P/F UPVC VENT COWEL (LOCAL) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	2.00	@ Rs:187/93	P.No	Rs:	375.00
---------------	------	-------------	------	-----	--------

(Rs: one hund: eighty seven & ninty three only)

- 10 P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete.(R.A)

<u>Nyloon Plastic pi</u>	90.00	@ Rs: 77/-	P.Rft	Rs:	6,930.00
--------------------------	-------	------------	-------	-----	----------

(Rs: seventy seven only)

- 11 Providing & Fixing Hand pump Machine (R.A)

<u>Machine</u>	1.00	@ Rs: 4500/-	Each	Rs:	4,500.00
----------------	------	--------------	------	-----	----------

(Rs: four thous: five hund: only)

- 12 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).

1.00	@ Rs:14201/-	P.No:	Rs:	14,201.00
------	--------------	-------	-----	-----------

(Rs: fourteen thous: two hund: one only)

<b>G.Total:</b>	<b>Rs:</b>	<b>124,769.00</b>
-----------------	------------	-------------------



**SCHEDULE " B "**

S.No: 88

**NAME OF WORK:-** INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL BUILDINGS TALUKA LARKANO (2017-18 PROGRAMME) AT GBPS IMAM BUX UMRANI TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling 2nd class tile roofing. (S.I.No.22 (b) P/11).				
		1139.00	@ Rs: 378/13	% Cft	Rs: 4,307.00
			(Rs: three hund: seventy eight & thirteen only)		
2	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		538.00	@ Rs: 1285/63	% Cft	Rs: 6,916.00
			(Rs: one two hund: eighty five & sixty three only)		
3	Dismantling rolled steel beams, iron rails etc. (S.I.No.42 P/13).				
		28.00	@ Rs:126/04	P.Cft	Rs: 3,529.00
			(Rs: one hund: twenty six & four only)		
4	Removing cement or lime plaster. (S.i.No.53 P/13).				
		3383.00	@ Rs:121/-	% Sft	Rs: 4,093.00
			(Rs: one hund: twenty one only)		
5	Dismantling cement concrete plain 1:2:4. (S.I.No.19 (c ) P/10).				
		241.00	@ Rs: 3327/50	% Cft	Rs: 8,019.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
6	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		588.00	@ Rs:3176/25	%0 Cft	Rs: 1,867.00
			(Rs: three thous: one hund: seventy hund: twenty five only)		
7	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		546.00	@ Rs:11948/36	% Cft	Rs: 65,238.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
8	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c ) P/ 14).				
		824.00	@ Rs:8694/95	% Cft	Rs: 71,646.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
9	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		266.00	@ Rs:337/-	P.Cft	Rs: 89,642.00
			(Rs: three hund: thirty seven only)		

S.No:	Description	Qty:	Rate	Unit	Amount
10	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	12.00	@ Rs:5001/70	P.Cwt	Rs: 60,020.00
			(Rs: five thous: one & seventy only)		
11	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	2457.00	@ Rs: 1141/25	%Cft	Rs: 28,041.00
			(Rs: one thous: one hund: forty one & twenty five only)		
12	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).	429.00	@Rs:12674/36	%Cft	Rs: 54,373.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
13	Pacca brick work other than building including striking of joints upto 20' ft. height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).	743.00	@ Rs:12346/65	%Cft	Rs: 91,735.00
			(Rs: twelve thous: three forty six & sixty five only)		
14	Supplying of T.Girders at site of work. (Sch: of Material).	5.00	@ Rs:3850/-	P.Cwt	Rs: 19,250.00
			(Rs: three thous: eight hund: fifty only)		
15	Supplying of T.Iron at site of work. (Sch: of Material).	18.00	@ Rs:3575/-	P.Cwt	Rs: 64,350.00
			(Rs: three thous: five hund: seventy five only)		
16	Errrection and rolled steel beams or old rails in roof etc errection and fixing in position. (S.I.No. P/ ).	38.00	@ Rs: 186/34	P.Cwt	Rs: 4,286.00
			(Rs: one hund: eighty six & thirty four only)		
17	First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortor with 1/2" thick sand wiched layer of 1:6 cement mortor including 1:2 cement pointing underside of tiles complete including curing etc. (S.I.No: 1 P/32).	1167.00	@ Rs:11443/10	%Sft	Rs: 133,541.00
			(Rs: eleven thous: four hund: fourty three & ten only)		
18	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	1167.00	@ Rs:10/70	P.Sft	Rs: 12,486.0
			(Rs: ten & seventy only)		
19	Cement Pointing 1:2 flash on floor. (S.I.No: 18 P/52).	1100.00	@ Rs: 939/57	% S.ft	Rs: 10,335.00
			(Rs: nine hund: thirty nine & fifty seven only)		

S.No:	Description	Qty:	Rate	Unit	Amount
20	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		712.00	@ Rs:660/- (Rs: six hund: sixty only)	% Sft	Rs: 4,699.00
21	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2828.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 62,402.00
23	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		2828.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	Rs: 62,146.00
24	Notice board made with cement. (S.I.No: 1 P/94).				
		64.00	@ Rs:58/11 (Rs: fifty eight & eleven only)	P. Sft	Rs: 3,719.00
25	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		1303.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 16,775.00
26	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 28 P.92 ).				
		67.00	@ Rs:228/90 (Rs: two hund: twenty eight & ninty only)	P.Rft	Rs: 15,336.00
27	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand reparing i/c all carriage tools and planst used in making and fixing .( S.I.No: 29 P/ 92).				
		180.00	@ Rs: 240/50 (Rs: two hund: forty & fifty only)	P.Rft	Rs: 43,290.00
28	M.S barred windows squars bars 5/8" dia.				
		1.71	@ Rs: 3550/- (Rs: three thous: five hund: fifty only)	P.Cwt	Rs: 6,070.00
29	Cutting and fixing iron bars for barred windows.				
		36.00	@ Rs:28/25 (Rs: twenty eight & twenty five only)	P.No	Rs: 1,016.00
30	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		187.00	@ Rs: 902/93 (Rs: nine hund: two & ninty three only)	P.Sft	Rs: 168,848.00



S.No:	Description	Qty:	Rate	Unit	Amount
31	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	24.00	@ Rs:180/50 (Rs: one hund: eighty & fifty only)	P. Sft	Rs: 4,332.00
32	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	2489.00	@ Rs: 4411/82 (Rs: four thous: four hund: eleven & eighty two only)	% Sft	Rs: 109,810.00
33	White washing three coats. (S.I.No.26 ( c ) P/53).	1808.00	@ Rs:829/95 (Rs: eight hund: twenty nine & ninty five only)	% Sft	Rs: 7,669.00
34	Primary coat of chalk distempering. (S.I.No.23 P/57).	3210.00	@ Rs:442/75 (Rs: four hund; fourty tow & seventy five only)	% Sft	Rs: 14,212.00
35	Distempering three coats. (S.I.No.24 (c) P/53).	3210.00	@ Rs:1079/65 (Rs: one thous: seventy nine & sixty five only)	% Sft	Rs: 34,567.00
36	Preparing the surface and painting with weather coat of approved make to old weather coat surface. (S.I.No:39 P/55).	2029.00	@ Rs: 1498/48 (Rs: one thous: nine hund: fourty eight & ten only)	% Sft	Rs: 30,398.00
37	Painting guard bars , gates iron bars gratings railings i/c standard barse etc: smiler open works.	463.00	@ Rs:1270/83 (Rs: one thous: two hund: seventy & eighty three only)	% S.ft	Rs: 5,884.00
38	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).	374.00	@ Rs:2116/41 (Rs: two thous: one hund: sixteen & fourty one only)	% Sft	Rs: 7,915.00
<b>G.Total:</b>					<b>Rs: 1,332,762.0</b>

  
**XEN**

**SCHEDULE " B "****S.No:****NAME OF WORK:-**

**INTEGRATED REHABILITATION OF EXISTING PRIMARY /  
MIDDLE SCHOOL BUILDINGS TALUKA LARKANO (2017-18  
PROGRAMME) AT GBPS SACHE BUX JAGIRANI TALUKA  
LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).	41.00	Rs 5445/-	% Cft	Rs: 2,232.00
					(Rs: five thous: four hund: forty five only)
2	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).	97.00	@ Rs: 1285/63	% Cft	Rs: 1,247.00
					(Rs: one two hund: eighty five & sixty three only)
3	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).	74.00	@ Rs: 3327/50	% Cft	Rs: 2,462.00
					(Rs: three thous: two hund: twenty seven & fifty only)
4	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	816.00	@ Rs: 3176/25	% 0 Cft	Rs: 2,591.00
					(Rs: three thous: one hund: seventy hund: twenty five only)
5	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/ ).	245.00	@ Rs: 8694/95	% Cft	Rs: 21,302.00
					(Rs: eight thous: six hund: ninty four & ninty five only)
6	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	665.00	@ Rs:11948/36	% Cft	Rs: 79,456.00
					(Rs: eleven thous: nine hund: eighty five & thirty six only)
7	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	219.00	@ Rs:337/-	P.Cft	Rs: 73,803.00
					(Rs: three hund: thirty seven only)
8	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	9.776	@ Rs:5001/70	P.Cwt	Rs: 48,897.00
					(Rs: five thous: one & seventy only)



**XEN**



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 9 Supplying and filling sand under floor and plugging in walls. (S.I.No: 29 P/25).

1272.00	@ Rs: 1141/25	% Cft	Rs:	14,516.00
(Rs: one thous: one hund: forty one & twenty five only)				

- 10 Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).

891.00	@ Rs:10/70	P.Sft	Rs:	9,533.00
(Rs: ten & seventy only)				

- 11 Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).

137.00	@ Rs: 3327/50	% Cft	Rs:	4,558.00
(Rs: three thous: two hund: twenty seven & fifty only)				

- 12 Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).

1184.00	@ Rs:12674/36	% Cft	Rs:	150,064.00
(Rs: twelve thous: six hund: seventy four & thirty six only)				

- 13 Suppling of T.Girders at site of Works

10.571	@ Rs: 3850/-	P.Cwt	Rs:	40,698.00
(Rs: three thous: eight hund; fifty only)				

- 15 Supplying of T-Iron at the site of work

9.526	@ Rs: 3575/-	P.Cwt	Rs:	34,055.00
(Rs: three thous: five hund; seventy five only)				

- 16 Errection and rolled steel beams or old rails in roof etc errection and fixing in position. (S.I.No. P/ ).

20.097	@ Rs: 186/34	P.Cwt	Rs:	3,745.00
(Rs: one hund; eighty six & thirty four only)				

- 17 First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortor with 1/2" thick sand wiched layer of 1:6 cement mortor including 1:2 cement pointing underside of tiles complete including curing etc. (S.I.No: 1 P/32).

565.00	@ Rs: 11443/10	% Sft	Rs:	64,654.00
(Rs: eleven thous: four hund; forty three & ten only)				

- 18 P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).

18.00	@ Rs:228/90	P.Rft	Rs:	4,120.00
(Rs: two hund: twenty eight & ninty only)				

  
**XEN**

S.No.	Description	Qty:	Rate	Unit	Amount
19	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).	88.00	@ Rs: 240/50 (Rs: two hund: forty & fifty only)	P.Rft	Rs: 21,164.00
20	Suppling M.S square, bar 5/8" dia (Sch: of matrial).	0.857	@ Rs: 3350/- (Rs: three thous: three hund; fifty only)	P.Cwt	Rs: 3,042.00
21	Cutting and fixing iron bars for barred windows. (S.I.No.18 P/97).	18.00	@ Rs: 28/23 (Rs: twenty eight & twenty five only)	P.Bar	Rs: 508.00
22	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).	76.00	@ Rs: 902/93 (Rs: nine hud: two & ninty three only)	P.Sft	Rs: 68,622.00
23	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	2171.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 47,905.00
24	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	2139.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	Rs: 47,005.00
25	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	580.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 7,467.00
26	Notice board made with cement. (S.I.No: 1 P/94)	32.00	@ Rs: 58/11 (Rs: fifty eight & eleven only)	P.Sft	Rs: 1,859.00
27	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).	70.00	@ Rs: 14429/25 (Rs: fourteen thous: four hund: twenty nine & twenty five only)	%Cft	Rs: 10,100.00
28	Providing and laying marble flooring super / china Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without windings, set in Cement Slurry. laid over 3/4" thick Cement mortar 1:2 & filling the joints with white cement and pigment i/c grinding, rubbing and Chemical polishing as directed by the Engineer Incharge. (R.A)	500.00	@ Rs:307/- (Rs: three hund: seven only)	% Sft	Rs: 153,500.00

  
7/10/2020  
P. N. S. S.

S.No:	Description	Qty:	Rate	Unit	Amount
29	Providing & fixing 3/8" thick marble tiles of approved quality and colour and shade size 8"x4"/6"x4" in dado skirting and facing removal / tucking of existing plaster surface etc. Over 1/2" thick base of cement mortar 1:3 setting of tiles in slurry of white cement over mortar base i/c filling the joints and washing the tiles with white cement slurry current finishing cleaning and (i) For new works. (S.I.No: 68 (i) P/48).	62.00	@ Rs: 186/04	P.Sft	Rs: 11,534.00 (Rs: one hund: eighty six & four only)
30	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).	26.00	@ Rs:226/02	P.Sft	Rs: 5,877.00 (Rs: two hund: twenty six & two only)
31	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	530.00	@ Rs:1887/40	%Sft	Rs: 10,003.00 (Rs: one thous: eight hund: eighty seven & fourteen only)
32	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	297.00	@ Rs: 4411/82	%Sft	Rs: 13,103.00 (Rs: four thous: four hund: eleven & eighty two only)
33	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 80 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and laying in specified manner / patter and design etc complete. (S.I.No: 74 P/49).	980.00	@ Rs:199/77	P.Sft	Rs: 179,793.0 (Rs:one hund: ninty nine & seventy seven only)
34	Primary coat of chalk distempering. (S.I.No.23 P/57).	2745.00	@ Rs:442/75	%Sft	Rs: 12,153.00 (Rs: four hund: forty two & seventy five only)
35	Distempering two coats.	3185.00	@ Rs:1043/90	%Sft	Rs: 33,248.00 (Rs: ten hund: forty three & ninty only)
36	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	152.00	@ Rs: 1948/10	%Sft	Rs: 3,217.00 (Rs: one thous: nine hund: forty eight & ten only)
37	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	343.00	@ Rs:2116/41	%Sft	Rs: 4,359.00 (Rs: two thous: one hund: sixteen & fourty one only)
G.Total:					Rs: 1,192,392.0

**SCHEDULE " B "**

S.No: 90

NAME OF WORK:- INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL BUILDINGS TALUKA LARKANO (2017-18 PROGRAMME) AT GBPS SHAH BAIG JAMALI TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Removing door with chowkats. (S.I.No.33 (a) P/12).				
		2.00	@ Rs:142/18	P.No	Rs: 284.00
			(Rs: one hund: forty two & eighteen only)		
2	Removing windows and sky light with chowkats. (S.I.No.33 (b) P/12).				
		6.00	@ Rs:102/85	P.No	Rs: 617.00
			(Rs: one hund: two & eighty five only)		
3	Dismantling cement concrete plain 1:2:4. (S.I.No.19 (c) P/10).				
		461.00	@ Rs: 3327/50	% Cft	Rs: 15,310.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
4	Removing cement or lime plaster. (S.I.No.53 P/13).				
		1541.00	@ Rs:121/-	% Sft	Rs: 1,865.00
			(Rs: one hund: twenty one only)		
5	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).				
		521.00	Rs 5445/-	% Cft	Rs: 28,368.00
			(Rs: five thous: four hund: forty five only)		
6	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		1085.00	@ Rs: 1285/63	% Cft	Rs: 13,949.00
			(Rs: one two hund: eighty five & sixty three only)		
7	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		738.00	@ Rs:3176/25	% Cft	Rs: 2,344.00
			(Rs: three thous: one hund: seventy hund: twenty five only)		
8	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).				
		533.00	@ Rs:8694/95	% Cft	Rs: 46,344.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
9	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		279.00	@ Rs:11948/36	% Cft	Rs: 33,336.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		

S.No:	Description	Qty:	Rate	Unit	Amount
10	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		740.00	@ Rs:337/-	P.Cft	Rs: 249,380.00
			(Rs: three hund: thirty seven only)		
11	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		39.00	@ Rs:5001/70	P.Cwt	Rs: 195,027.00
			(Rs: five thous: one & seventy only)		
12	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).				
		1886.00	@ Rs: 1141/25	% Cft	Rs: 21,524.00
			(Rs: one thous: one hund: forty one & twenty five only)		
13	Extra Lead 3.0 Miles				
		1886.00	@ Rs: 579/41	% 0.Cft	Rs: 1,093.00
			(Rs: five hund: sevnty nine & forty one only)		
14	Pacca brick work in Ground floor in cement sand mortar. Ratio 1:6 (S.I.No.5(e) P/20).				
		977.00	@ Rs:12674/36	% Cft	Rs: 123,828.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
15	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		233.00	@ Rs:12346/65	% Cft	Rs: 28,768.00
			(Rs: twelve thous: three forty six & sixty five only)		
16	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 28 P.92 ).				
		18.00	@ Rs:228/90	P.Rft	Rs: 4,120.00
			(Rs: two hund: twenty eight & ninty only)		
17	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand reparing i/c all carriage tools and planst used in making and fixing .( S.I.No: 29 P/ 92).				
		99.00	@ Rs: 240/50	P.Rft	Rs: 23,809.00
			(Rs: two hund: forty & fifty only)		
18	M.S barred windows squars bars 5/8" dia.				
		1.71	@ Rs: 3550/-	P.Cwt	Rs: 6,070.00
			(Rs: three thous: five hund: fifty only)		
19	Cutting and fixing iron bars for barred windows.				
		36.00	@ Rs:28/25	P.No	Rs: 1,038.00
			(Rs: twenty eight & twenty five only)		

S.No:	Description	Qty:	Rate	Unit	Amount
20	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		1541.00	@ Rs:660/- (Rs: six hund: sixty only)	% Sft	Rs: 10,171.00
21	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		3631.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 80,122.00
22	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		3631.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	Rs: 79,792.00
23	Cement pointing striking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		886.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 11,406.00
24	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		152.00	@ Rs: 902/93 (Rs: nine hund: two & ninty three only)	P.Sft	Rs: 137,245.00
25	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).				
		6.00	@ Rs:180/50 (Rs: one hund: eighty & fifty only)	P. Sft	Rs: 1,083.00
26	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment. (S.I.No.24P/91).				
		48.00	@ Rs:726/72 (Rs: seven hund: twenty six & seventy two only)	P. Sft	Rs: 34,882.00
27	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		2028.00	@ Rs: 4411/82 (Rs: four thous: four hund: eleven & eighty two only)	% Sft	Rs: 89,472.00
(B)	<u>2" thick</u>				
		1362.00	@ Rs: 3275/50 (Rs: three thous: two hund: seventy five & fifty only)	% Sft	Rs: 4,461.00
28	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/15).				
		46.00	@ Rs:14429/25 (Rs: fourteen thous: four hund: twenty nine & twenty five only)	% Cft	Rs: 6,637.00

S.No:	Description	Qty:	Rate	Unit	Amount
29	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).				
		352.00	@ Rs:27747/06	% Sft	Rs: 97,669.00
			(Rs: twenty seven thous: seven hund forty seven & six only)		
30	Notice board made with cement. (S.I.No: 1 P/94).				
		64.00	@ Rs:58/11	P. Sft	Rs: 3,719.00
			(Rs: fifty eight & eleven only)		
31	White washing three coats. (S.I.No.26 ( c ) P/53).				
		1365.00	@ Rs:829/95	% Sft	Rs: 11,329.00
			(Rs: eight hund: twenty nine & ninty five only)		
32	Primary coat of chalk distempering. (S.I.No.23 P/57).				
		4600.00	@ Rs:442/75	% Sft	Rs: 20,366.00
			(Rs: four hund; fourty two & seventy five only)		
33	Distempering three coats. (S.I.No.24 (c) P/53).				
		4600.00	@ Rs:1079/65	% Sft	Rs: 49,663.00
			(Rs: one thous: seventy nine & sixty five only)		
34	Prepareing the surface and painting with weather coat of approved make to old weather coat surface. (S.I.No:39 P/55).				
		3528.00	@ Rs: 1498/48	% Sft	Rs: 52,866.00
			(Rs: one thous: nine hund: fourty eight & ten only)		
35	Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.				
		96.00	@ Rs:1270/83	% S.ft	Rs: 1,220.00
			(Rs: one thous: two hund: seventy & eighty three only)		
36	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).				
		304.00	@ Rs:2116/41	% Sft	Rs: 6,434.00
			(Rs: two thous: one hund: sixteen & fourty one only)		
G.Total:					Rs: 1,495,611.0

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

### PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sxity only)

- 4 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.

2.00 @ Rs: 447/15 P.No: Rs: 894.00  
(Rs: four hund: forty seven & fifteen only)

- 6 S/F conceled stop cock of superior quality with C.P head 1/2" dia.

2.00 @ Rs: 889/46 P.No: Rs: 1,778.00  
(Rs: eight hund; eighty nine fourty six only)

- 7 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.00 @ Rs: 1384/24 P.No: Rs: 2,768.00  
(Rs: one thous: three hund; eighty four & twenty four only)

- 10 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commocion for inlet- outlet and over flow pipe etc complete .(S.S.I.No: 3 P/21

150.00 @ Rs: 87/95 P.G: Rs: 13,192.00  
(Rs: eighty seven & ninty five only)

### N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(a) 3/4" Dia 50.00 @ Rs: 78/01 P.Rft Rs: 3,900.00  
(Rs: sevnty eight & One only)

(b) 1" Dia 10.00 @ Rs: 97/91 P.Rft Rs: 979.00  
(Rs: ninety seven & ninty one only)

(c) 4" Dia 20.00 @ Rs: 397/77 P.Rft Rs: 7,955.00  
(Rs: three hund: ninty seven & seventy seven only)

*[Handwritten signature]*  
XIN



S.No:	Description	Qty:	Rate	Unit	Amount
2	P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)				
	<u>(a) 3/4" Dia</u>	10.00	@ Rs: 103/05	P.No	Rs: 1,030.00
			(Rs: one hund; three & five only)		
	<u>(b) 4" Dia</u>	2.00	@ Rs: 425/45	P.No	Rs: 850.00
			(Rs: four hund: twenty five & fourty five only)		
3	P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.				
	<u>(a) 3/4" Dia</u>	4.00	@ Rs: 110/40	P.No	Rs: 441.00
			(Rs: one hund; ten & fourteen only)		
10	P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete.(R.A)				
	<u>Nyloon Plastic pi</u>	80.00	@ Rs: 77/-	P.Rft	Rs: 6,160.00
			(Rs: seventy seven only)		
11	Providing & Fixing Hand pump Machine (R.A)				
	<u>Machine</u>	1.00	@ Rs: 4500/-	Each	Rs: 4,500.00
			(Rs: four thous: five hund: only)		
12	Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete.				
		1.00	@ Rs:14201/-	P.No	Rs: 14,201.00
			(Rs: fourteen thous: two hund: one only)		
<b>G.Total:</b>					<b>Rs: 68,253.00</b>

*[Handwritten signature]*  
20/01

**SCHEDULE " B "****S.No:**

**NAME OF WORK:-** INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL BUILDINGS TALUKA LARKANO (2017-18 PROGRAMME) AT GBPS KHAIR MUHAMMAD BROHI TALUKA LARKANO.

S.No	Description	Qty	Rate	Unit	Amount
1	Removing cement or lime plaster. (S.I.No.53 P/13).				
		2287.00	@ Rs:121/-	% Sft	Rs: 2,767.00
			(Rs: one hund: twenty one only)		
2	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).				
		50.00	Rs 5445/-	% Cft	Rs: 2,723.00
			(Rs: five thous: four hund: forty five only)		
3	Dismantling cement 2nd class tile roofing. (S.I.No: 22 (b) P/11).				
		1073.00	@ Rs: 378/13	% Cft	Rs: 4,057.00
			(Rs: three hund: seventy eight & thirteen only)		
4	Dismantling rolled steel beams, iron rails etc. (S.I.No.42 P/13).				
		27.27	@ Rs:126/04	P.Cft	Rs: 3,437.00
			(Rs: one hund: twenty six & four only)		
5	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		1119.00	@ Rs: 1285/63	% Cft	Rs: 14,386.00
			(Rs: one two hund: eighty five & sixty three only)		
6	Dismantling cement concrete plain 1:2:4. (S.I.No.19 (c) P/10).				
		243.00	@ Rs: 3327/50	% Cft	Rs: 8,086.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
7	Removing door with chowkats. (S.I.No.33 (a) P/12).				
		4.00	@ Rs:142/18	P.No	Rs: 569.00
			(Rs: one hund: forty two & eighteen only)		
8	Removing windows and sky light with chowkats. (S.I.No.33 (b) P/12).				
		6.00	@ Rs:102/85	P.No	Rs: 617.00
			(Rs: one hund: two & eighty five only)		
9	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		570.00	@ Rs:3176/25	%0 Cft	Rs: 1,810.00
			(Rs: three thous: one hund: seventy hund: twenty five only)		

S.No:	Description	Qty:	Rate	Unit	Amount
10	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).				
		147.00	@ Rs:8694/95 % Cft		Rs: 12,782.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
11	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		635.00	@ Rs:11948/36 % Cft		Rs: 75,872.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
12	Supplying and filling sand under floor and plugging in walls. (S.I.No: 29 P/25).				
		8675.00	@ Rs: 1141/25 % Cft		Rs: 99,003.00
			(Rs: one thous: one hund: forty one & twenty five only)		
13	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:6:12. (S.I.No: 4 (d) P. 17).				
		523.00	@ Rs: 8122/95 % Cft		Rs: 42,483.00
			(Rs: eight thous: one hund: twenty two & ninty five only)		
14	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		1743.00	@ Rs: 4411/82 % Sft		Rs: 76,898.00
			(Rs: four thous: four hund: eleven & eighty two only)		
(B)	<u>2" thick</u>				
		121.00	@ Rs: 3275/50 % Sft		Rs: 3,963.00
			(Rs: three thous: two hund; seventy five & fifty only)		
15	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		127.00	@ Rs:337/- P.Cft		Rs: 42,799.00
			(Rs: three hund: thirty seven only)		
16	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		6.00	@ Rs:5001/70 P.Cwt		Rs: 30,010.00
			(Rs: five thous: one & seventy only)		
17	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		187.00	@ Rs: 902/93 P.Sft		Rs: 168,848.00
			(Rs: nine hund: two & ninty three only)		
18	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 28 P.92 ).				
		67.00	@ Rs:228/90 P.Rft		Rs: 15,336.00
			(Rs: two hund: twenty eight & ninty only)		

S.No:	Description	Qty:	Rate	Unit	Amount
19	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hiques and fixing at site with necessary hold fots filling with cement sand reparing i/c all carriage tools and planst used in making and fixing .( S.I.No: 29 P/ 92).	180.00	@ Rs: 240/50 (Rs: two hund: forty & fifty only)	P.Rft	Rs: 43,290.00
20	M.S barred windows squars bars 5/8" dia.	2.00	@ Rs: 3550/- (Rs: three thous: five hund: fifty only)	P.Cwt	Rs: 7,100.00
21	Cutting and fixing iron bars for barred windows.	42.00	@ Rs:28/23 (Rs: twenty eight & twenty three only)	P.No	Rs: 1,186.00
22	Pacca brick work in Ground floor in cement sand mortar. Ratio 1:6 (S.I.No.5(e) P/20).	337.000	@ Rs:12674/36 (Rs: tweleve thous: six hund: seventy four & thirty six only)	% Cft	Rs: 42,713.00
23	Pacca brick work other than building including stricking of joints upto 20ft height in cemen sand mortar. (S.I.No: 7 (i) (e) P.26).	650.00	@ Rs: 12346/75 (Rs: tweleve thous: three hund: fourty six & seventy five only)	% Cft	Rs: 80,253.00
24	Suppling of T.Girders at site of Works	22.267	@ Rs: 3850/- (Rs: three thous: eight hund; fifty only)	P.Cwt	Rs: 85,728.00
24	Supplying of T-Iron at the site of work	18.58	@ Rs: 3575/- (Rs: three thous: five hund; seventy fiv e only)	P.Cwt	Rs: 66,423.00
25	Errection and rolled steel beams or old rails in roof etc errection and fixing in position. (S.I.No. P/ ).	40.84	@ Rs: 186/34 (Rs: one hund; eighty six & thirty four only)	P.Cwt	Rs: 7,610.00
26	First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortor with 1/2" thick sand wiched layer of 1:6 cement mortor including 1:2 cement pointing underside of tiles complete including curing etc. (S.I.No: 1 P/32).	1073.00	@ Rs: 11443/10 (Rs: eleven thous: four hund; forty three & ten only)	% Sft	Rs: 122,784.00

S.No:	Description	Qty:	Rate	Unit	Amount
27	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	1073.00	@ Rs:10/70 (Rs: ten & seventy only)	P.Sft	Rs: 11,481.00
28	Reinforced cement concerte spout i/c fixing in position with top and bottom khuras. (S.I.No: 27 P/18)	34.00	@ Rs: 524/98 (Rs: five hund; twenty four & ninty eight only)	Each	Rs: 59,432.00
29	S/F in position approved grill of 3/4" x 1/4" size flat iron of approved design inluding painting three coarts etc complete (weight not to be less than 3.7 Lbs/ sq. foot of finished grill). (S.I.No: 26 P.97).	212.00	@ Rs: 194/16 (Rs: one hund: ninty four & sixteen only)	P.Sft	Rs: 41,162.00
30	Extra labour rate for making cemet plaster patta/band around straight are couyard oppening and around the edges of roof slabs the wight not less tham 6' with fine finishing as directed by Engineer Incharge. (S.I.NO.35 P/54)	200.00	@ Rs: 19/36 (Rs: nineteen & thirty six only)	% Sft	Rs: 3,872.00
32	Notice board made with cement. (S.I.No: 1 P/94).	64.00	@ Rs:58/11 (Rs: fifty eight & eleven only)	P. Sft	Rs: 3,719.00
33	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).	2287.00	@ Rs:660/- (Rs: six hund: sixty only)	% Sft	Rs: 15,094.00
34	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	5482.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 120,965.00
35	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	5482.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	Rs: 120,468.00
36	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	1093.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 14,071.00
15	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).	48.00	@ Rs:726/72 (Rs: seven hund: twenty six & seventy two only)	P. Sft	Rs: 34,882.00

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

37 White washing three coats. (S.I.No.26 ( c ) P/53).

935.00 @ Rs:829/95 % Sft Rs: 7,760.00  
(Rs: eight hund: twenty nine & ninty five only)

38 Primary coat of chalk distempering. (S.I.No.23 P/57).

3376.00 @ Rs:442/75 % Sft Rs: 14,947.00  
(Rs: four hund; fourty two & seventy five only)

39 Distempering three coats. (S.I.No.24 (c) P/53).

3976.00 @ Rs:1079/65 % Sft Rs: 42,926.00  
(Rs: one thous: seventy nine & sixty five only)

40 Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).

1600.00 @ Rs: 1948/10 % Sft Rs: 31,170.00  
(Rs: one thous: nine hund: fourty eight & ten only)

41 Preparing surface and painting of doors and windows any type (including edges)  
(ii) Each subsequent coat of paint. (S.I.No.5 ( c ) P/69).

442.00 @ Rs:2116/41 % Sft Rs: 9,355.00  
(Rs: two thous: one hund: sixteen & fourty one only)

42 Painting guard bars , gates iron bars gratings railings i/c standard barsees etc:  
smiler open works.

715.00 @ Rs:1270/83 % S.ft Rs: 9,086.00  
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 1,603,923.0

  
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

# PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.  

2.00      @ Rs: 4802/60      P.No:      Rs: 9,605.00  
(Rs: four thous: eight hund; two & sixty only)
- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)  

1.00      @ Rs: 4928/-      P.Each      Rs: 4,928.00  
(Rs: four thous: nine hund; twenty eight only)
- 3 Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed  

1.00      @ Rs: 2533/47      P.No:      Rs: 2,533.00  
(Rs: four thous: five hund; thirty three & forty seven only)
- 4 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.  

3.00      @ Rs: 447/15      P.No:      Rs: 1,341.00  
(Rs: four hund; forty seven & fifteen only)
- 5 P/F 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden pleat (a) Standard pattern. (S.I.No.3 (a) P/7).  

1.00      @ Rs:2376/-      P.Each      Rs: 2,376.00  
(Rs: two thous: three hund; seventy six only)
- 6 S/F conceled stop cock of superior quality with C.P head 1/2" dia.  

3.00      @ Rs: 889/46      P.No      Rs: 2,668.00  
(Rs: eight hund; eighty nine forty six only)
- 7 S/F long bib-cock of superior quality with C.P head 1/2" dia  

5.00      @ Rs: 1384/24      P.No      Rs: 6,921.00  
(Rs: one thous: three hund: eighty four & twenty four only)
- 8 S/F Swan type piller cock of superior quality etc:  

1.00      @ Rs: 877/80      P.Gallan      Rs: 877.00  
(Rs: eight hund; seventy seven & eighty only)
- 9 providing chambers (15"x19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 block set-on 1:6 cement mortar 6" thick C.C.1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) etc fixied in cement concerate 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).  

1.00      @ Rs: 5913/22      Each      Rs: 5,913.00  
(Rs: five thous: nine hund: thirteen & twenty two only)



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 10 S/F fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate iron of cement concrete 1:2:7 and making and connection for inlet- outlet and over flow pipe etc complete .

125.00	@ Rs: 87/95	P.Gallan	Rs:	10,993.00
(Rs: eighty seven & ninety five only)				

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separately recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(a) 1/2" Dia	10.00	@ Rs: 66/81	P.Rft	Rs:	668.00
(Rs: sixty six & eighty one only)					

(b) 3/4" Dia	60.00	@ Rs: 78/01	P.No	Rs:	4,680.00
(Rs: seventy eight & One only)					

(C) 1" Dia	50.00	@ Rs: 97/91	P.No	Rs:	4,895.00
(Rs: ninety seven & ninety one only)					

(d) 4" Dia	20.00	@ Rs: 397/77	P.No	Rs:	7,955.00
(Rs: three hund: ninty seven & seventy seven only)					

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

(a) 3/4" Dia	20.00	@ Rs: 103/05	P.No	Rs:	2,061.00
(Rs: one hund; three & five only)					

(b) 4" Dia	4.00	@ Rs: 425/45	P.No	Rs:	1,701.00
(Rs: four hund: twenty five & fourty five only)					

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

(a) 3/4" Dia	8.00	@ Rs: 110/40	P.No	Rs:	883.00
(Rs: one hund; ten & fourteen only)					

(f) 4" Dia	2.00	@ Rs: 712/75	P.No	Rs:	1,425.00
(Rs: seven hund: twelve & seventy five only)					

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

(a) 3/4" Dia	12.00	@ Rs: 98/15	P.No	Rs:	1,177.00
(Rs: ninty eight & fifteen only)					

  
XEN



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 5 P/F UPVC P-Trap W/Elbow (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	2.00	@ Rs:818/04	P.No	Rs:	1,636.00
---------------	------	-------------	------	-----	----------

(Rs: eight hund; eighteen & four only)

- 6 P/F UPVC WYE (Y) (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

	3.00	@ Rs:933/13	P.No	Rs:	2,799.00
--	------	-------------	------	-----	----------

(Rs: nine hund; thirty three & thirteen only)

- 7 P/F UPVC PLUG ELBOW (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	3.00	@ Rs:677/65	P.No	Rs:	2,033.00
---------------	------	-------------	------	-----	----------

(Rs: six hund; seventy seven & sixty five only)

- 8 P/F UPVC PLUG TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	2.00	@ Rs:847/42	P.No	Rs:	1,695.00
---------------	------	-------------	------	-----	----------

(Rs: eight hund; forty seven & forty two only)

- 9 P/F UPVC VENT COWEL (LOCAL) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	3.00	@ Rs:187/93	P.No	Rs:	563.00
---------------	------	-------------	------	-----	--------

(Rs: one hund: eighty seven & ninty three only)

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 10 P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete. (R.A)

<u>Nyloon Plastic pipe</u>	90.00	@ Rs: 77/-	P.Rft	Rs:	6,930.00
(Rs: seventy seven only)					

- 11 Providing & Fixing Hand pump Machine (R.A)

<u>Machine</u>	1.00	@ Rs: 4500/-	Each	Rs:	4,500.00
(Rs: four thous: five hund: only)					

- 12 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).

1.00	@ Rs:14201/-	P.No:	Rs:	14,201.00
(Rs: fourteen thous: two hund: one only)				

<b>G.Total:</b>	<b>Rs:</b>	<b>107,957.00</b>
-----------------	------------	-------------------



## Schedule-B

92

**INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL**  
**Name of Work:- BUILDINGS TALUKA RATODERO (2017-18 PROGRAMME) @ GGPS ZANGEJA TALUKA**  
**RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		18	@ Rs: 3,176.25 % OCft		Rs: 57
			(Thirty one Hundred seventy six rup: & twenty five paisa only)		
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)				
		12	@ Rs: 8,694.95 % Cft		Rs: 1,043
			(Eighty six hund: ninty four rup: & ninty five paisa only)		
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.				
		40.00	@ Rs: 11,948.36 % Cft		Rs: 4,779
			(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)		
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
		1405.00	@ Rs: 337.00 P.Cft		Rs: 473,485
			(Three hundred Thirty seven rup: only)		
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)				
		62.723	@ Rs: 5,001.70 P.Cwt		Rs: 313,722
			( Five thousand one rup: & seventy paisa only)		
6	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
		698	@ Rs. 2,206.60 % Cft		Rs. 15,402
			(Twenty tow hund: six rup: & sixty paisa only)		
7	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)				
		698	@ Rs: 2,197.52 % Sft		Rs: 15,339
			(Twenty one hund: ninty seven rup: & fifty two paisa only)		
8	Making Notice board made with cement.				
		96.00	@ Rs: 58.11 P. Sft		Rs: 5,579
			(fifty eight rupees and eleven paisa only)		
9	Providing and Laying 1" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)				
		1216.00	@ Rs: 4,411.82 % Sft		Rs: 53,648
			( Forry four hundred eleven rup: & eighty two paisa only)		

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(B) 2" Thick First Floor

2486.00 @ Rs: 3,275.50 % Sft Rs: 81,429  
(Thirty two hundred seventy five rup: & fifty paisa only)

10 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening &

89 @ Rs. 14,429.25 % Cft Rs. 12,842  
(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)

11 Split Tiles 1/4" thick matt glazed or double glazed jointed inwhite cement and laid over 1:2 grey cement sand mortar 3/4" thick including finishing complete (Flooring and facing.) (S.I No. 69 P/ 48).

442 @ Rs: 21,021.11 % Sft Rs: 92,913  
(Twenty on thousand twenty one rupees & eleven paisa only)

12 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

290.00 @ Rs: 1,273.76 P: Sft Rs: 369,390  
(Twelve hundred seventy three rup: seventy six paisa only)

13 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

1443.00 @ Rs: 1,287.44 % Sft Rs: 18,578  
(Twelve hundred eighty seven rupees & forty for paisa only)

14 White wash Three Coats (S.I No. 26 © P/53)

2360 @ Rs: 829.95 % Sft Rs: 19,587  
(Eight hundred twenty nine rup: & ninty five paisa only)

15 Primary coat of chalk distemper( S.I No. 23 P/53)

8556 @ Rs: 442.75 % Sft Rs: 37,882  
(Four hundred forty two rupees & seventy five paisa only)

16 Distemping Three Coats (S.I No. 24 ©P/53)

8556 @ Rs: 1,079.65 % Sft Rs: 92,375  
(One thousand Seventy nine rup: & sixty five paisa only)

17 Painting doors & Windows any type (New Surface).( S.I No. 4 (c) P/67)

608 @ Rs: 1,212.21 % Sft Rs: 7,370  
(Twelve hundred twelve rup :& twenty one paisa only)

18 Providing and fixing iron steel grill door with angle iron frame of 1 1/2" x 1 1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in charge.(S.I No. 31 P No. 93)

54.00 @ Rs. 231.60 P. Sft Rs. 12,506  
( Two hundred thiry one rup: & sixty Paisa only)

  
XEN

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 19 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)

2486 @ Rs. 1,887.40 % Sft Rs. 46,921  
( Eighteen hundred eighty seven rupees & forty paisa only)

Total Rs: 1,674,847



## Schedule-B

93

Name of Work:- **INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL BUILDINGS TALUKA RTODERO (2017-18 PROGRAMME) @ GBPS PIR BUX SUNANI TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 20 P/10)	639.75	@ Rs. 5,445.00 % Cft (Fifty four hundred & forty five rupees only)		Rs. 34,834
2	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)	1010.25	@ Rs: 1,285.63 % Cft ( Twelve hunred eighty five rup & sixty three paisa only)		Rs: 12,988
3	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 22 P/10)	142	@ Rs: 3,327.50 % Cft ( Thirty three hundred twenty seven rup:& fifty paisa only)		Rs: 4,725
4	Removing cement or lime plaster. (S.I No. 53 P/13)	952	@ Rs: 121.00 % Cft ( One hundred & twenty rup: only)		Rs: 1,152
5	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	24	@ Rs: 3,176.25 % OCft (Thirty one Hundred seventy six rup: & twenty five paisa only)		Rs: 76
6	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	45	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)		Rs: 3,913
7	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	357	@ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa		Rs: 42,656
8	Supply and fixing sand under floor including plugging in to walls	75	@ Rs: 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)		Rs: 856
9	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	777.00	@ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)		Rs: 261,849



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 10 Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No. 8 (b) P/16)

34.688 @ Rs: 5,001.70 P.Cwt Rs: 173,496  
(Five thousand one rup: & seventy paisa only)

- 11 Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.

375 @ Rs. 12,674.36 % Cft Rs. 47,529  
(Twelve thousand six hundred seventy four rup: & thity six paisa only)

- 12 Cement Plaster 1:4 upto 12" height. 3/4" thick ( S.I No. 11 (c) P/51)

952 @ Rs: 3,015.76 % Sft Rs: 28,710  
(Three thousand fifteen rup: & seventy six paisa only)

- 13 Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)

850 @ Rs. 2,206.60 % Cft Rs. 18,756  
(Twenty tow hund: six rup: & sixty paisa only)

- 14 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

850 @ Rs: 2,197.52 % Sft Rs: 18,679  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

- 15 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

450 @ Rs: 1,287.44 % Sft Rs: 5,793  
(Twelve hundred eighty seven rupees & forty for paisa only)

- 16 Providing and Laying 1" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

1886 @ Rs: 4,411.82 % Sft Rs: 83,207  
( Forry four hundred eleven rup: & eighty two paisa only)

(b) 2" Thick

104 @ Rs: 3,275.50 % Sft Rs: 3,407  
(Thirty two hundred seventy five rup: & fifty paisa only)

- Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

36.00 @ Rs. 186.50 P. Sft Rs. 6,498  
( One hundred eighty Six rupees & Fifty rup only)

 XEN

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- Providing & lying HALLA or pattern tiles glazed 8"x8"x1/4" on floor or wall facing in required  
 18 floor & pattern of STILE specification jointed in white cement & pigment over a base of 1:2  
 grey cement mortar 3/4" thick etc i/c the cost of polish & cutting

108 @ Rs: 34,520.31 % Sft Rs: 37,282  
 (Thirty four thousand five hundred twenty rupees & thirty one paisa only)

- 19 White wash three coats. (S.I. No. 26 P No. 54)

886 @ Rs. 425.84 % Sft Rs. 3,772  
 (Four hundred twenty five rup: & eighty four paisa only)

- 20 Distempering two coats. ( S.I No. 24(b) P/54)

1909 @ Rs: 1,043.90 % Sft Rs: 19,928  
 ( One thousand forty three rup: & ninty paisa only)

- 21 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick /  
 sand paper filling the voids with chalk / plaster then painting with weather coat of approved

520 @ Rs: 1,948.10 % Sft Rs: 10,130  
 ( Nineteen hundred forty eight rupees & ten paisa only)

  
 XEN



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

22 Providing and laying single per layer of poly then sheet 0.13 mm thick for water proofing as per specification and Instruction of Engineer in charge. (S.I.No: 38 P.44).

113 @ Rs: 10.70 P.Cft Rs: 1,209  
(Ten rupees & seventy paisa only)

23 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)

106 @ Rs. 1,887.40 % Sft Rs. 2,001  
( Eighteen hundred eighty seven rupees & forty paisa only)

24 Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.

108 @ Rs. 1,270.83 % Sft Rs. 1,372  
(Twelve Hundred seventy rupees & eithy three paisa only)

25 Painting doors & Windows any type (Old surface).( S.I No. 4 (c) P/67)

208 @ Rs: 1,212.21 % Sft Rs: 2,521  
(Twelve hundred twelve rup :& twenty one paisa only)

26 Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.(S.I No. 5 (e) P/20)

619 @ Rs: 12,774.36 % Cft Rs: 79,073

**Total Rs: 906,412**

  
**XEN**

## Schedule-B

94

**INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL  
Name of Work:- BUILDINGS TALUKA RATODEOR (2017-18 PROGRAMME) @GBPS BABAR  
TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Removing cement or lime plaster. (S.I No. 53 P/13)				
		5008	@ Rs: 121.00 % Cft ( One hundred & twenty rup: only)		Rs: 6,060
2	Dismantling cement concrete plain Ratio 1:2:4				
		485	@ Rs: 3,327.50 % Cft ( Thirty three hundred twenty seven rup:& fifty paisa only)		Rs: 16,138
3	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)				
		1056	@ Rs: 8,694.95 % Cft (Eighty six hund: ninety four rup: & ninty five paisa only)		Rs: 91,819
4	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
		5008	@ Rs. 2,206.60 % Cft (Twenty tow hund: six rup: & sixty paisa only)		Rs. 110,507
5	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)				
		5008	@ Rs: 2,197.52 % Sft (Twenty one hund: ninty seven rup: & fifty two paisa only)		Rs: 110,052
6	Removing Doors with Chowkats (S.I.No. 33 (a) P/12)				
		56	@ Rs: 142.18 P.Sft. (One hundred forty two rupees & eighteen paisa only)		Rs: 7,962
7	Removing Windows with Chowkats (S.I.No. 33 (a) P/12)				
		80	@ Rs: 102.85 P.Sft. (One hundred two rupees & eighty five paisa only)		Rs: 8,228
8	Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)				
		5080.00	@ Rs: 4,411.82 % Sft ( Forry four hundred eleven rup: & eighty two paisa only)		Rs: 224,120
(B)	<b><u>2" Thick.</u></b>				
		3776.25	@ Rs: 3,275.50 % Sft (Thirty Two hundred Seventy Fine rup: & Fifty paisa only)		Rs: 123,691
9	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)				
		3776.25	@ Rs. 1,887.40 % Sft ( Eighteen hundred eighty seven rupees & forty paisa only)		Rs. 71,273

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 10 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.

184.48 @ Rs. 14,429.25 % Cft Rs. 26,619

- 11 P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)

2836.00 @ Rs. 30,509.77 % Sft Rs. 865,257  
(Thirty thousand five hund: nine rupees & seventy seven paisa only)

- 12 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio 1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

56 @ Rs: 228.90 P. Rft Rs: 12,818  
(Two hundred twenty eight rupees & ninty paisa only)

- 13 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio 1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla

48.00 @ Rs: 240.50 P. Rft Rs: 11,544  
(Two hundred forty rupees & fifty paisa only)

- 14 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

92 @ Rs: 902.93 P. Sft Rs: 83,070  
(Nine hund: two rup: & ninty three paisa only)

- 16 Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill). (S.I No. 26 P/92)

20.00 @ Rs: 180.50 P. Sft Rs: 3,610  
( One hundre ninty four rupees & sixteen paisa only)

- 17 Providing and fixing iron steel grill door with angle iron frame of 1 1/2" x 1 1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in charg. (S.I No. 31 P No. 93)

51.00 @ Rs. 231.60 P. Sft Rs. 11,812  
( Two hundred thiry one rup: & sixty Paisa only)

- 18 Prepairng surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).

1719 @ Rs: 2,116.41 % Sft Rs: 36,381  
( Twenty one hundred sixteen rup & forty one paisa only)

- 19 Primary coat of chalk distemper( S.I No. 23 P/53)

10412 @ Rs: 442.75 % Sft Rs: 46,099  
(Four hundred forty two rupees & seventy five paisa only)



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 Distempering two coats.( S.I No. 24(b) P/54)

8372 @ Rs: 1,043.90 % Sft Rs: 87,395  
( One thousand forty three rup: & ninty paisa only)

21 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)

1964.5 @ Rs: 1,948.10 % Sft Rs: 38,270  
( Nineteen hundred forty eight rupees & ten paisa only)

Total Rs: 1,990,725

  
**XEN**

## Schedule-B

95

**INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL**  
Name of Work:- **BUILDINGS TALUKA RATODEOR (2017-18 PROGRAMME) @GBPS BHUTTA**  
**VILLAGE-I TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Removing cement or lime plaster. (S.I No. 53 P/13)				
		5008	@ Rs: 121.00 % Cft ( One hundred & twenty rup: only)		Rs: 6,060
2	Dismantling cement concrete plain Ratio 1:2:4				
		485	@ Rs: 3,327.50 % Cft ( Thirty three hundred twenty seven rup:& fifty paisa only)		Rs: 16,138
3	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)				
		1056	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)		Rs: 91,819
4	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
		5008	@ Rs. 2,206.60 % Cft (Twenty tow hund: six rup: & sixty paisa only)		Rs. 110,507
5	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)				
		5008	@ Rs: 2,197.52 % Sft (Twenty one hund: ninty seven rup: & fifty two paisa only)		Rs: 110,052
6	Removing Doors with Chowkats (S.I.No. 33 (a) P/12)				
		56	@ Rs: 142.18 P.Sft. (One hundred forty two rupees & eighteen paisa only)		Rs: 7,962
7	Removing Windows with Chowkats (S.I.No. 33 (a) P/12)				
		80	@ Rs: 102.85 P.Sft. (One hundred two rupees & eighty five paisa only)		Rs: 8,228
8	Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)				
		5080.00	@ Rs: 4,411.82 % Sft ( Forry four hundred eleven rup: & eighty two paisa only)		Rs: 224,120
(B) <u>2" Thick.</u>					
		3776.25	@ Rs: 3,275.50 % Sft (Thirty Two hundred Seventy Fine rup: & Fifty paisa only)		Rs: 123,691
9	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)				
		3776.25	@ Rs. 1,887.40 % Sft ( Eighteen hundred eighty seven rupees & forty paisa only)		Rs. 71,273

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 10 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.
- 184.48 @ Rs. 14,429.25 % Cft Rs. 26,619
- 11 P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)
- 2836.00 @ Rs. 30,509.77 % Sft Rs. 865,257  
(Thirty thousand five hund: nine rupees & seventy seven paisa only)
- 12 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla
- 56 @ Rs: 228.90 P. Rft Rs: 12,818  
(Two hundred twenty eight rupees & ninty paisa only)
- 13 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla
- 48.00 @ Rs: 240.50 P. Rft Rs: 11,544  
(Two hundred forty rupees & fifty paisa only)
- 14 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)
- 92 @ Rs: 902.93 P. Sft Rs: 83,070  
(Nine hund: two rup: & ninty three paisa only)
- 16 Supply & Fixing in Position iron/steel grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)
- 20.00 @ Rs: 180.50 P. Sft Rs: 3,610  
( One hundre ninty four rupees & sixteen paisa only)
- 17 Providing and fixing iron steel grill door with angle iron frame of 1 1/2" x 1 1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in charg.(S.I No. 31 P No. 93)
- 51.00 @ Rs. 231.60 P. Sft Rs. 11,812  
( Two hundred thiry one rup: & sixty Paisa only)
- 18 Prepairng surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).
- 1719 @ Rs: 2,116.41 % Sft Rs: 36,381  
( Twenty one hundred sixteen rup & forty one paisa only)
- 19 Primary coat of chalk distemper( S.I No. 23 P/53)
- 10412 @ Rs: 442.75 % Sft Rs: 46,099  
(Four hundred forty two rupees & seventy five paisa only)

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 Distempering two coats.( S.I No. 24(b) P/54)

8372 @ Rs: 1,043.90 % Sft Rs: 87,395  
( One thousand forty three rup: & ninty paisa only)

21 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)

1964.5 @ Rs: 1,948.10 % Sft Rs: 38,270  
( Nineteen hundred forty eight rupees & ten paisa only)

Total Rs: 1,990,725

  
XEN

Sr. #	Description	Rate	Unit	Amount
-------	-------------	------	------	--------

**PART-B**

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19' clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605  
(Forty Eight hundred Two rup: & Sixty paisa only)

- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)

2.0 @ Rs: 4928/- P.Each Rs: 9,856  
(Forty Nine hundred Twenty Eight rup: & paisa only)

- 3 S/F concealed stop cock of superior quality with C.P head 1/2" dia.

2.0 @ Rs: 889/46 P.No Rs: 1,779  
(Eight hundred Eighty Nine rup: & Forty Six paisa only)

- 4 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.0 @ Rs: 1384/24 P.No Rs: 2,768  
(Thirteen hundred Eighty Four rup: & Twenty Four paisa only)

- 5 Providing & Fixing Handle valve (China)

2.0 @ Rs: 365.42 P.No Rs: 731  
(Seven hundred Seventy Seven rup: & Eighty paisa only)

- 6 S/F fibre glass tenk of approved quality and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commocion for inlet- outlet and over flow pipe etc complete (250 gallons).

250.0 87.95 P.Gallan Rs: 21,988  
(ThartyThousand Seven hundred Seventy Three rup: & Forty Two Pessa only)

**G.Total:**

**Rs: 46,727**

**(B) N.S.I**

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

150.0 @ Rs: 78/01 P.No Rs: 11,702  
(Seventy Eight rup: & One Pessa only)

150.0 @ Rs: 97/91 P.No Rs: 14,687  
(Ninety Seven rup: & Ninety One Pessa only)

50.0 @ Rs: 397/77 P.No Rs: 19,889  
(Three Hund: Ninety Seven rup: & Seventy Seven Pessa only)

  
**XEN**



Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

2.0 @ Rs: 103/05 P.Rft Rs: 206  
(One Hund: Three rup: & Five Pessa only)

2.0 @ Rs: 110/40 P.No Rs: 221  
(One Hund: Ten rup: & Forty Pessa only)

2.0 @ Rs: 132/43 P.No Rs: 265  
(One Hund: Tharty Two rup: & Forty Three Pessa only)

2.0 @ Rs: 712/75 P.No Rs: 1,426  
(seven Hund: Twelve rup: & seventy Five Pessa only)

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

**(b) 3/4" Dia**

2.0 @ Rs: 98/15 P.No Rs: 196  
(Ninty Eight rup: & Fifteen Pessa only)

**(C) 1" Dia**

2.0 @ Rs: 110/40 P.No Rs: 221  
(One Hund: Ten rup: & Forty Pessa only)

- 5 P/F approved quality A.C motor pumping set (Javed Engineering) made 1-1/4" 1" section & delivery with base & complying 1 H.Power single phase motor (Siemens make) 60" ft; head of 2800 KPM i/c the cost of C.I fitting nuts, bolts & the cost of 1:2:4 plate from (RA Approved).

1.0 @ Rs: 18470 P.No Rs: 18,470  
(Eighteen Thousand Four Hund: Seventy rup: & only)

- 6 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

**(a) Filter** 10.0 @ Rs: 76/05 P.Rft Rs: 760  
(Seventy Six rup: & Five Pessa only)

**(b) G.I Pipe** 90.0 @ Rs: 77 P.Rft Rs: 6,930  
(Tharty Eight Six rup: & Ninety Five Pessa only)

**(C) Machine** 1.0 @ Rs: 4500 Each Rs: 4,500  
(Fourteen Hund: Forty One rup: & Sixty Five Pessa only)

**G.Total:** **Rs: 79,471**

**S.I** **Rs. 46,727**

**N.S.I** **Rs. 79,471**

**G.Total:** **Rs. 126,198**

*[Handwritten signature]*

96

**Schedule-B**

**INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE  
SCHOOL BUILDINGS TALUKA RATODERO (2017-18 PROGRAMME)  
@GBPS BADO JALBANI (C/WALL) TALUKA RATODERO  
DISTRICT LARKANO.**

Name of Work:-

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	775.00	@ Rs: 3,176.25 % 0Cft (Thirty one Hundred seventy six rup: & twenty five paisa only)	Rs:	2,462
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	437.00	@ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)	Rs:	37,997
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	915.00	@ Rs: 11,948.36 % Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)	Rs:	109,327
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	794.00	@ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)	Rs:	267,578
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)	16.000	@ Rs: 5,001.70 P.Cwt ( Five thousand one rup: & seventy paisa only)	Rs:	80,027
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	121.00	@ Rs. 12,346.65 % Cft (Twelve thousand three hund: forty six rup: & sixty five paisa only)	Rs.	14,939
7	Making & fixing steel gated doors with 1 1/6" thick sheeting i/c angle iron frame 2"x2"x3/4" and square bars 4" centre to cement.	48.00	@ Rs. 726.72 P. Sft (Seven hundred twenty six rupees & seventy two paisa only)	Rs.	34,883
8	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	2750.00	@ Rs. 2,206.60 % Cft (Twenty tow hund: six rup: & sixty paisa only)	Rs.	60,682
9	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	2750.00	@ Rs: 2,197.52 % Sft (Twenty one hund: ninty seven rup: & fifty two paisa only)	Rs:	60,432

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

10 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

1375.00 @ Rs: 1,287.44 % Sft Rs: 17,702  
(Twelve hundred eighty seven rupees & forty for paisa only)

11 Primary coat of chalk distemper( S.I No. 23 P/53)

4000.00 @ Rs: 442.75 % Sft Rs: 17,710  
(Four hundred forty two rupees & seventy five paisa only)

12 Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.

96.00 @ Rs. 1,270.83 % Sft Rs. 1,220  
(Twelve Hundred seventy rupees & eithy three paisa only)

13 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)

4000 @ Rs: 1,948.10 % Sft Rs: 77,924  
( Ninteen hundred forty eight rupees & ten paisa only)

Total Rs: 782,883

  
XEN

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

**PART-B**

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19' clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605  
(Forty Eight hundred Two rup: & Sixty paisa only)

- 2 S/F concealed stop cock of superior quality with C.P head 1/2" dia.

2.0 @ Rs: 889/46 P.No: Rs: 1,779  
(Eight hundred Eighty Nine rup: & Forty Six paisa only)

- 3 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.0 @ Rs: 1384/24 P.No: Rs: 2,768  
(Thirteen hundred Eighty Four rup: & Twenty Four paisa only)

- 4 Providing & Fixing Handle valve (China)

2.0 @ Rs: 365.42 P.No: Rs: 731  
(Seven hundred Seventy Seven rup: & Eighty paisa only)

**G.Total: Rs: 14,883**

**(B) N.S.I**

- 1 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

**(a) Filter** 10.0 @ Rs: 76/05 P.Rft Rs: 760  
(Seventy Six rup: & Five Pessa only)

**(b) G.I Pipe** 90.0 @ Rs: 77 P.Rft Rs: 5,390  
(Tharty Eight Six rup: & Ninety Five Pessa only)

**(C) Machine** 1.0 @ Rs: 4500 Each Rs: 4,500  
(Fourteen Hund: Forty One rup: & Sixty Five Pessa only)

**G.Total: Rs: 10,650**

S.I	Rs.	14,883
N.S.I	Rs.	10,650
<b>G.Total:</b>	<b>Rs.</b>	<b>25,533</b>

  
**XEN**

## Schedule-B

97

**INTEGRATED REHABILITATION OF EXISTING PRIMARY / MIDDLE SCHOOL**  
Name of Work:- **BUILDINGS TALUKA RATODEOR (2017-18 PROGRAMME) @GBPS HAJI**  
**BOOSAN TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Removing cement or lime plaster. (S.I No. 53 P/13)				
	4090 @ Rs: 121.00 % Cft (One hundred & twenty rup: only)			Rs:	4,949
2	Dismantling cement concrete plain Ratio 1:2:4				
	485 @ Rs: 3,327.50 % Cft (Thirty three hundred twenty seven rup:& fifty paisa only)			Rs:	16,138
3	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10 (S.I No. 3(d) P/14)				
	1056 @ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)			Rs:	91,819
4	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
	4090 @ Rs. 2,206.60 % Cft (Twenty tow hund: six rup: & sixty paisa only)			Rs.	90,250
5	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)				
	4090 @ Rs: 2,197.52 % Sft (Twenty one hund: ninty seven rup: & fifty two paisa only)			Rs:	89,879
6	Removing Doors with Chowkats (S.I.No. 33 (a) P/12)				
	56 @ Rs: 142.18 P.Sft. (One hundred forty two rupees & eighteen paisa only)			Rs:	7,962
7	Removing Windows with Chowkats (S.I.No. 33 (a) P/12)				
	80 @ Rs: 102.85 P.Sft. (One hundred two rupees & eighty five paisa only)			Rs:	8,228
8	Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)				
	5080.00 @ Rs: 4,411.82 % Sft (Forry four hundred eleven rup: & eighty two paisa only)			Rs:	224,120
(B) <u>2" Thick.</u>					
	3776.25 @ Rs: 3,275.50 % Sft (Thirty Two hundred Seventy Fine rup: & Fifty paisa only)			Rs:	123,691
9	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)				
	3776.25 @ Rs. 1,887.40 % Sft (Eighteen hundred eighty seven rupees & forty paisa only)			Rs.	71,273

  
J.  
XEN

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 10 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.
- 184.48 @ Rs. 14,429.25 % Cft Rs. 26,619
- 11 P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)
- 2836.00 @ Rs. 30,509.77 % Sft Rs. 865,257  
(Thirty thousand five hund: nine rupees & seventy seven paisa only)
- 12 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio 1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla
- 56 @ Rs: 228.90 P. Rft Rs: 12,818  
(Two hundred twenty eight rupees & ninty paisa only)
- 13 P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for WINDOWS using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio 1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla
- 48.00 @ Rs: 240.50 P. Rft Rs: 11,544  
(Two hundred forty rupees & fifty paisa only)
- 14 1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)
- 92 @ Rs: 902.93 P. Sft Rs: 83,070  
(Nine hund: two rup: & ninty three paisa only)
- 16 Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)
- 20.00 @ Rs: 180.50 P. Sft Rs: 3,610  
( One hundre ninty four rupees & sixteen paisa only)
- 17 Providing and fixing iron steel grill door with angle iron frame of 1 1/2" x 1 1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in charg.(S.I No. 31 P No. 93)
- 51.00 @ Rs. 231.60 P. Sft Rs. 11,812  
( Two hundred thiry one rup: & sixty Paisa only)
- 18 Prepairng surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).
- 1719 @ Rs: 2,116.41 % Sft Rs: 36,381  
( Twenty one hundred sixteen rup & forty one paisa only)
- 19 Primary coat of chalk distemper( S.I No. 23 P/53)
- 10412 @ Rs: 442.75 % Sft Rs: 46,099  
(Four hundred forty two rupees & seventy five paisa only)

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

20 Distempering two coats.( S.I No. 24(b) P/54)

8372 @ Rs: 1,043.90 % Sft Rs: 87,395  
( One thousand forty three rup: & ninty paisa only)

21 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)

1964.5 @ Rs: 1,948.10 % Sft Rs: 38,270  
( Nineteen hundred forty eight rupees & ten paisa only)

Total Rs: 1,951,185

  
XEN

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

**PART-B**

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19' clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605  
(Forty Eight hundred Two rup: & Sixty paisa only)

- 2 S/F concealed stop cock of superior quality with C.P head 1/2" dia.

2.0 @ Rs: 889/46 P.No Rs: 1,779  
(Eight hundred Eighty Nine rup: & Forty Six paisa only)

- 3 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.0 @ Rs: 1384/24 P.No Rs: 2,768  
(Thirteen hundred Eighty Four rup: & Twenty Four paisa only)

- 4 Providing & Fixing Handle valve (China)

2.0 @ Rs: 365.42 P.No Rs: 731  
(Seven hundred Seventy Seven rup: & Eighty paisa only)

- 5 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (150 gallons).

150.0 87.95 P.Gallan Rs: 13,193  
(ThartyThousand Seven hundred Seventy Three rup: & Forty Two Pessa only)

**G.Total: Rs: 28,076**

**(B) N.S.I**

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

60.0 @ Rs: 78/01 P.No Rs: 4,681  
(Seventy Eight rup: & One Pessa only)

20.0 @ Rs: 97/91 P.No Rs: 1,958  
(Ninety Seven rup: & Ninety One Pessa only)

15.0 @ Rs: 397/77 P.No Rs: 5,967  
(Three Hund: Ninety Seven rup: & Seventy Seven Pessa only)

- 2 P/F approved quality A.C Motor Mono Block Set made 1-1/4"x1" suction and Delivery 1 H Power Single Phase Motor (Diamond / Siemence make or equal) i/c Cost of C.I Fitting Nats Bolts etc complete (R.A)

1.0 @ Rs: 14201.00 P.No Rs: 14,201  
(Forteen Thousand Two Hund: OPne rup: & only)

  
**XEN**



Sr.#	Description	Rate	Unit	Amount
3	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.			
	<u>(a) Filter</u>	10.0 @ Rs: 76/05	P.Rft	Rs: 760
	(Seventy Six rup: & Five Pessa only)			
	<u>(b) G.I Pipe</u>	90.0 @ Rs: 77	P.Rft	Rs: 6,930
	(Tharty Eight Six rup: & Ninety Five Pessa only)			
	<u>(C) Machine</u>	1.0 @ Rs: 4500	Each	Rs: 4,500
	(Fourteen Hund: Forty One rup: & Sixty Five Pessa only)			
	<b>G.Total:</b>			<b>Rs: 38,997</b>
	<b>S.I</b>			<b>Rs. 28,076</b>
	<b>N.S.I</b>			<b>Rs. 38,997</b>
	<b>G.Total:</b>			<b>Rs. 67,073</b>

  
XEN

**SCHEDULE " B "**

S.No: 42

NAME OF WORK:-

**INTEGRATED REHABILITATION OF EXISTING MIDDLE / HIGH SCHOOL BUILDINGS DISTRICT LARKANO (2017-18 PROGRAMME) AT GGHS GAJJANPUR TALUKA LARKANO**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).	36.00	Rs 5445/-	% Cft	Rs: 1,960.00 (Rs: five thous: four hund: forty five only)
2	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).	1032.00	@ Rs: 1285/63	% Cft	Rs: 13,268.00 (Rs: one two hund: eighty five & sixty three only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	716.00	@ Rs:11948/36	% Cft	Rs: 85,550.0 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	329.00	@ Rs:337/-	P.Cft	Rs: 110,873.0 (Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	16.00	@ Rs:5001/70	P.Cwt	Rs: 80,027.0 (Rs: five thous: one & seventy only)
6	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	115.00	@ Rs: 1141/25	% Cft	Rs: 1,312.0 (Rs: one thous: one hund: forty one & twenty five only)
7	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).	230.00	@ Rs:12674/36	% Cft	Rs: 29,151.00 (Rs: twelve thous: six hund: seventy four & thirty six only)
8	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).	1650.00	@ Rs:12346/65	% Cft	Rs: 203,720.00 (Rs: twelve thous: three forty six & sixty five only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
9	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No:28 /P 92).	32.00	@ Rs:228/90	P.Rft	Rs: 7,325.00 (Rs: two hund: twenty eight & ninty only)
10	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete ( weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	6.00	@ Rs:180/50	P. Sft	Rs: 1,083.0 (Rs: one hund: eighty & fifty only)
11	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	16.00	@ Rs: 8694/95	% Cft	Rs: 1,391.00 (Rs: eight thous: six hund: ninty four & ninty five only)
12	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Surface).	35.00	@ Rs: 902/93	P.Sft	Rs: 31,603.00 (Rs: nine hund: two & ninty three only)
13	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	3532.00	@ Rs:2206/60	% Sft	Rs: 77,937.0 (Rs: two thous: two hund: six & sixty only)
14	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	3532.00	@ Rs:2197/52	% Sft	Rs: 77,616.0 (Rs: two thous: one hund: ninty seven & twenty two only)
15	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	55.00	@ Rs: 4411/82	% Sft	Rs: 2,426.00 (Rs: four thous: four hund: eleven & eighty two only)
(B) <u>2"Thick</u>		111.00	@ Rs: 3275/50	% S.ft	Rs: 3,635.00 (Rs: three thous: two hund; seventy five & fifty only)
16	Supplying and fixing broken glass on courtyard walls including 1:3:6 cement concrete coping (S.I.No: 61 P/104).	150.00	@ Rs:70/44	P Lft	Rs: 10,566.00 (Rs: seventy & forty four only)
17	Primary coat of chalk under distemping.	3532.00	@ Rs: 442/75	% S.ft	Rs: 15,638.00 (Rs: four hund; fourty tow & seventy five only)

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

18 Distempering two coats. (S.I.No.24 (b) P/53).

3532.00 @ Rs:1043/90 %Sft Rs: 36,871.00  
(Rs: ten hund; forty three & ninty only)

19 Preparing surface and painting of doors and windows any type (including edges)  
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

70.00 @ Rs:2116/41 %Sft Rs: 1,481.0  
(Rs: two thous: one hund: sixteen & fourty one only)

20 Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame  
2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment.  
(S.I.No.24P/91).

42.00 @ Rs:726/72 P. Sft Rs: 30,522.0  
(Rs: seven hund: twenty six & seventy two only)

21 Painting guard bars , gates iron bars gratings railings i/c standard barsed etc:  
smiler open works.

84.00 @ Rs:1270/83 % S.ft Rs: 1,067.00  
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 825,022.0

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

## PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.  
2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00  
(Rs: four thous: eight hund; two & sixty only)
- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)  
2.00 @ Rs: 4928/- P.Each Rs: 9,856.00  
(Rs: four thous: nine hund; twenty eight only)
- 3 Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed  
2.00 @ Rs: 2533/47 P.No: Rs: 5,066.00  
(Rs: four thous: five hund; thirty three & fourty seven only)
- 4 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.  
4.00 @ Rs: 447/15 P.No: Rs: 1,788.00  
(Rs: four hund: forty seven & fifteen only)
- 5 S/F conceled stop cock of superior quality with C.P head 1/2" dia.  
4.00 @ Rs: 889/46 P.No Rs: 3,557.00  
(Rs: eight hund; eighty nine fourty six only)
- 6 S/F long bib-cock of superior quality with C.P head 1/2" dia  
5.00 @ Rs: 1384/24 P.No Rs: 6,921.00  
(Rs: one thous: three hund; eighty four & twenty four only)
- 7 S/F Swan type pillar cock of superior quality etc:  
2.00 @ Rs: 877/80 P.No Rs: 1,755.00  
(Rs: eight hund; seventy seven & eighty only)
- 8 providing chambers (15"X19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 t set-on 1:6 cement mortar 6" thick C.C.1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) etc fixied in cement concerate 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).  
1.00 @ Rs: 5913/22 Each Rs: 5,913.00  
(Rs: five thous: nine hund; thirteen & twenty two only)

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 9 S/F fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate iron of cement concrete 1:2:7 and making and connection for inlet-outlet and over flow pipe etc complete (250 gallons).

1.00 @ Rs: 21989/61 Each Rs: 21,990.00  
(Rs: twenty one thousand nine hundred; eighty nine & sixty one only)

- 10 P/F 15"x12" beveled edge mirror of Belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden plate (a) Standard pattern. (S.I.No.3 (a) P/7).

2.00 @ Rs:2376/- P.Each Rs: 4,752.00  
(Rs: two thousand three hundred; seventy six only)

**G.Total:** Rs: **71,203.00**

#### N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separately recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(a) 3/4" Dia 100.00 @ Rs: 78/01 P.Rft Rs: 7,801.00  
(Rs: seventy eight & One only)

(b) 1" Dia 20.00 @ Rs: 97/91 P.Rft Rs: 1,958.00  
(Rs: ninety seven & ninety one only)

(c) 4" Dia 30.00 @ Rs: 397/77 P.Rft Rs: 11,933.00  
(Rs: three hundred; ninety seven & seventy seven only)

- 2 P/F Bend/ Elbow ( 90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

(a) 3/4" Dia 10.00 @ Rs: 103/05 P.No Rs: 1,030.00  
(Rs: one hundred; three & five only)

(b) 1" Dia 6.00 @ Rs: 125/90 P.No Rs: 755.00  
(Rs: one hundred; twenty five & ninety only)

(c) 4" Dia 2.00 @ Rs: 425/45 P.No Rs: 850.00  
(Rs: four hundred; twenty five & forty five only)

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D\_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>(a) 3/4" Dia</u>	10.00	@ Rs: 110/40	P.No	Rs:	1,105.00
(Rs: one hund; ten & forty only)					

<u>(b) 1" Dia</u>	5.00	@ Rs: 132/43		Rs:	662.00
(Rs: one hund; thirty two & forty three only)					

<u>(c) 4" Dia</u>	2.00	@ Rs: 712/75	P.No	Rs:	1,425.00
(Rs: seven hund; twelve & seventy five only)					

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

<u>(a) 3/4" Dia</u>	12.00	@ Rs:98/15	P.No	Rs:	1,178.00
(Rs: ninty eight & fifteen only)					

<u>(b) 1" Dia</u>	5.00	@ Rs:110/40	P.No	Rs:	552.00
(Rs: one hund: ten & forty only)					

- 5 P/F UNION of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>(a) 3/4" Dia</u>	2.00	@ Rs: 312/81	P.Rft	Rs:	626.00
(Rs: three hund; tweleve & eighty one only)					

<u>(b) 1" Dia</u>	2.00	@ Rs:381/37	P.No	Rs:	762.00
(Rs: three hund; eighty one & thirt seven only)					

- 6 P/F UPVC P-Trap W/Elbow (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>4" Dia</u>	2.00	@ Rs:818/04	P.No	Rs:	1,636.00
(Rs: eight hund: eighteen & four only)					

  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 7 P/F UPVC WYE (Y) (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 3.00 @ Rs:933/13 P.No Rs: 2,799.00  
(Rs: nine hund; thirty three & thirteen only)

- 8 P/F UPVC PLUG ELBOW (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 2.00 @ Rs:677/65 P.No Rs: 1,355.00  
(Rs: six hund; seventy seven & sixty five only)

- 9 P/F UPVC PLUG TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 2.00 @ Rs:847/42 P.No Rs: 1,695.00  
(Rs: eight hund; fourty seven & fourty two only)

- 10 P/F UPVC VENT COWEL (LOCAL) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 2.00 @ Rs:187/93 P.No Rs: 375.00  
(Rs: one hund: eighty seven & ninty three only)

- 11 P/F COMPACTE BALL VALVE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

1-1/4" Dia 2.00 @ Rs:652/35 P.No Rs: 1,304.00  
(Rs: six hund; fifty two & thirty five only)

  
**XEN**



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 12 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery, 1 H. Power single phase motor (Diamond / Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete.

1.00 @ Rs:14201/- P.No Rs: 14,201.00  
(Rs: fourteen thous: two hund: one only)

- 14 P/F Plastic Pipe of approved quality and Material etc paid separatly I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement rate, i/c all cost of labour, material charges etc complete.

105.00 @ Rs:77/- P.Rft Rs: 8,085.00  
(Rs: seventy seven only)

- 15 Providing & Fixing Hand pump Machine i/c fitting and fixing i/c etc complete.

Machine

1.00 @ Rs: 4500/- P.No Rs: 4,500.00  
(Rs: four thous: five hund: only)

N.S.I Rs: 66,587.00

S.I Rs: 71,203.00

G.Total: Rs: 137,790.00

  
**XEN**

**SCHEDULE " B "**

S.No: 100 -

NAME OF WORK:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING  
PRIMARY SCHOOLS IN TALUKA LARKANO /BAKIRANI/DOKRI  
(2017-18 PROGRAMME AT GBPS DAE-JI-WANDH (1-C/R)  
TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	816.00	@ Rs: 3176/25	% 0 Cft	Rs: 2,591.00 (Rs: three thous: one hund: seventy hund: twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/ ).	245.00	@ Rs: 8694/95	% Cft	Rs: 21,302.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	665.00	@ Rs:11948/36	% Cft	Rs: 79,456.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	533.00	@ Rs:337/-	P.Cft	Rs: 179,621.00 (Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	26.00	@ Rs:5001/70	P.Cwt	Rs: 130,044.00 (Rs: five thous: one & seventy only)
6	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	1272.00	@ Rs: 1141/25	% Cft	Rs: 14,516.00 (Rs: one thous: one hund: forty one & twenty five only)
7	Extra lead 3.0 miles	1272.00	@ Rs: 579/41	% Cft	Rs: 7,370.00 (Rs: five hund: sevnty nine & fourty one only)
8	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	163.00	@ Rs:10/70	P.Sft	Rs: 1,744.00 (Rs: ten & seventy only)

S.No.	Description	Qty:	Rate	Unit	Amount
9	Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).				
		137.00	@ Rs: 3327/50	% Cft	Rs: 4,558.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
10	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1077.00	@ Rs:12674/36	% Cft	Rs: 136,502.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
11	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P. ).				
		28.00	@ Rs:228/90	P.Rft	Rs: 6,409.00
			(Rs: two hund: twenty eight & ninty only)		
12	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		114.00	@ Rs: 240/50	P.Rft	Rs: 27,417.00
			(Rs: two hund: forty & fifty only)		
13	Suppling M.S square, bar 5/8" dia (Sch: of matrial).				
		1.00	@ Rs: 3350/-	P.Cwt	Rs: 3,550.00
			(Rs: three thous: three hund; fifty only)		
14	Cutting and fixing iron bars for barred windows. (S.I.No.18 P/97).				
		26.00	@ Rs: 28/23	P.Bar	Rs: 733.00
			(Rs: twenty eight & twenty five only)		
15	First Class deodar wood wrought joinery in doors and windows etc. fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. ( Only Shutters).				
		72.00	@ Rs: 902/93	P.Sft	Rs: 65,010.00
			(Rs: nine hud: two & ninty three only)		
16	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2013.00	@ Rs:2206/60	% Sft	Rs: 44,418.00
			(Rs: two thous: two hund: six & sixty only)		
17	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1981.00	@ Rs:2197/52	% Sft	Rs: 43,532.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		

*Handwritten signature*  
**XEN**

S.No:	Description	Qty:	Rate	Unit	Amount
18	Cement pointing striking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		629.00	@ Rs:1287/44 % Sft		Rs: 8,097.00
			(Rs: one thous: two hund: eighty seven & forty four only)		
19	Notice board made with cement. (S.I.No: 1 P/94)				
		32.00	@ Rs: 58/11 P.Sft		Rs: 1,859.00
			(Rs: fifty eight & eleven only)		
20	Providing and laying 1" thick topping cement concrate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		440.00	@ Rs: 4411/82 % Sft		Rs: 19,412.00
			(Rs: four thous: four hund: eleven & eighty two only)		
(B)	<u>1-1/2"Thick</u>	716.00	@ Rs: 2548/29 % S.ft		Rs: 18,245.00
			(Rs: two thous: five hund: forty eight & twenty nine only)		
21	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).				
		59.00	@ Rs:226/02 P.Sft		Rs: 13,335.00
			(Rs: two hund; twenty six & two only)		
22	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).				
		716.00	@ Rs:1887/40 % Sft		Rs: 13,513.00
			(Rs: one thous: eight hund; eighty seven & fourteen only)		
23	Primary coat of chalk distempering. (S.I.No.23 P/57).				
		2320.00	@ Rs:442/75 % Sft		Rs: 10,271.00
			(Rs: four hund; forty two & seventy five only)		
24	Distempering three coats. (S.I.No.24 (c) P/53).				
		2320.00	@ Rs:1079/65 % Sft		Rs: 25,047.00
			(Rs: one thos: seventy nine & sixty five only)		
(B)	<u>Two coats.</u>	440.00	@ Rs:1043/90 % Sft		Rs: 4,593.00
			(Rs: ten hund; forty three & ninty only)		
25	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		317.00	@ Rs: 1948/10 % Sft		Rs: 6,175.00
			(Rs: one thous: nine hund: forty eight & ten only)		
26	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 ( c) P/69).				
		207.00	@ Rs:2116/41 % Sft		Rs: 4,380.00
			(Rs: two thous: one hund: sixteen & forty one only)		
G.Total:					Rs: 893,700.0

  
**XEN**

**SCHEDULE "B"**

**Name of Work:-** Construction of Additional Class Rooms in Existing Primary Schools  
in District Larkana ( Bakrani & Dokri ) (2017-18 Prog )

At : GBPS Moriya Khan Burdi Taluka Bakrani

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 1p1).	=	1569.00	Cft	
	@Rs: 3176.25	%0 Cft	Rs: 4984.00		
	(Three Thousand One Hund:Seventy Six & P.S Twenty Five only)				
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P- 14).	=	531.00	Cft	
	@Rs: 8694.95	% Cft	Rs: 46170		
	( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)				
3	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) P- 20.)	=	1799.00	Sft	
	@Rs: 11948.36	% S.ft	Rs: 214951		
	( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six only)				
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/16)	=	1311.00	Pcft	
	@Rs: 337.00	P.CFT	Rs: 441807		
	( Three Hundred Thirty Seven only)				
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 8 (b) P/16)	=	65.313	Pcwt	
	@Rs: 5001.70	P.CWT	Rs: 326676		
	(Five Thousand One &P.S Seventy ).				
6	Supplying filling Sand under floor plugging into walls, (S.I.No 29 P/ 25).	=	4041.00	Cft	
	@Rs: 1141.25	%Sft	Rs: 46118		
	(Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)				
7	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 ( C ) P/20)	=	2664.00	CFT	
	@Rs: 12674.36	%CFT	Rs: 337645		
	(Twlove thousand Six Hundred Seventy Four & Thirty Six only)				
8	Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13(b) P/57 )	=	3938.00	Sft	
	@Rs: 2206.60	% Sft	Rs; 86896		
	( Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)				
9	Cement plaster 1;4 upto 20' ft; height 3/8" thick. (S.I No.13(b) P/57 )	=	3938.00	SFT	
	@Rs: 2197.52	% Sft	Rs; 86538		
	( Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)				
10	Notice Board mad with cement. (S.I.No 1 P/100).	=	64.00	SFT	
	@Rs: 58.11	% Sft	Rs; 3719		
	( Fifty Eight P.S Eleven only)				
11	P/F G.I frame chokats Door of size 7" x2" or 4" x 3" for Door using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand repairing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)	=	48.00	P.Rft	
	@Rs: 228.90	P.Rft	Rs: 10987		
	(Two hundred twenty eight rupees & ninty paisa only)				
12	P/F G.I frame chokats of size 7" x2" or 4" x 3" for Windowss using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand repairing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)	=	264.00	P.Rft	
	@Rs: 240.50	P.Rft	Rs: 63492		

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
------	-------------	----------	------	------	--------

- 14 S/F in position iron steel grill of 3/4" X flat iron of approved design i/c painting three coats etc complete with not to be less than 3.7 Lbs sq: ft: of finished grill.

=	132.00	P.SFT
@Rs: 180.50	P.SFT	Rs: 23826
(One hundred ninety four rupees & sixteen paisa only)		

- 15 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ratio 3" thick. (S.I No:16 (C) P/41)

=	792.00	Cft
@Rs: 4411.82	%Cft	Rs: 34942

(Forty four hundred eleven rup: & eighty two paisa only)

- (b) P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ratio 2" thick. (S.I No:16 (C) P/41)

=	1630.00	CFT
@Rs: 3275.50	%Cft	Rs: 53391

(Thirty Two hundred Seventy Five rup: & Fifty paisa only)

- 16 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)

=	58.00	SFT
@Rs: 14429.25	% Sft	Rs: 8369

(Fourteen thousand four hundred: twenty nine rup: & twenty paisa only)

- 17 Laying & Flooring of Approved coloured with Glazed tiles 1/4 " thick laid in white cement

=	421.00	SFT
@Rs: 27678.86	% Sft	Rs: 116528

(Twenty seven thousands six hundred seventy eight only)

- 18 Cement pointing and striking of joints on walls ratio 1: 2 (S.I No.11(a) P/51)

=	1230.00	CFT
@Rs: 1287.44	%Cft	Rs: 15836

(Twelve hundred eighty seven rupees & forty for paisa only)

- 19 Primary coat of chalk under distempering (S.I No: 23 P 59)

=	3763.00	CFT
@Rs: 442.75	%Cft	Rs: 16661

(Four hundred forty two rupees & seventy five paisa only)

- 20 White wash three coats.

=	1522.00	Cft
@Rs: 829.95	%Cft	Rs: 12632

(Eight hundred twenty nine rup: & ninty five paisa only)

- 21 Distempering three coats (S.I No: 24 (B) P 53)

=	3763.00	Cft
@Rs: 1079.65	%Cft	Rs: 40627

(One thousand Seventy nine rup: & sixty five paisa only)

- 22 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approved make old surface. (S.I.No 39 (a) P/62).

=	1842.00	Cft
@Rs: 1948.10	% Sft	Rs: 35884

Twenty on hundred sixteen rupees & forty one paisa only)

- 23 Painting doors & window any type, (S.I.No 05 P/ 76)

=	400.00	Cft
@Rs: 2116.41	%Cft	Rs: 8466

(Twenty one hundred sixteen rup & forty one paisa only)

- 24 Two coat of bitumen laid not using 34 lbs for over foot and blinded with stand at Cft per (S.I No: 13 P/40)

=	1630.00	Cft
@Rs: 1887.40	%Cft	Rs: 30765

(Eighteen hundred eighty seven rupees & forty paisa only)

- 25 P/L Hala pattern tiles glazed 4" X 1 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile.

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
------	-------------	----------	------	------	--------

27 Cutting and Fixing iron Bars for Barried Windows (S.I No.18 P/97)

= 48.00 P.SFT

@Rs: 28.23

P.SFT

Rs: 1355

( Twenty Eihgt rupees & Twenty Three Paisa only)

28 Polly thin Sheed ,

= 240.0 P.SFT

@Rs: 10.70

P.SFT

Rs: 2568

( Ten Seventy P.S only)

**Total 2315713**

## Schedule-B

101

Name of  
Work:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING PRIMARY SCHOOLS  
TALUKA RATODERO (2017-18 PROGRAMME) @ GBPS WANDH JOGI NAUDERO (02  
C/R) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		1910.00	@ Rs: 3,176.25 % 0Cft		Rs: 6,067
			(Thirty one Hundred seventy six rup: & twenty five paisa only)		
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:2:4. (S.I. No. 4 © P/14)				
(A)		237.00	@ Rs: 9,416.28 % Cft		Rs: 22,317
			Nine thousand four hundred Sixteen rup: & twenty eight paisa only)		
(B) <u>Ratio 1:5:10.</u>					
		184.00	@ Rs: 8,694.95 % Cft		Rs: 15,999
			(Eighty six hund: ninty four rup: & ninty five paisa only)		
3	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
(a) <u>Ground Floor</u>		1281.00	@ Rs: 337.00 P.Cft		Rs: 431,697
			(Three hundred Thirty seven rup: only)		
(b) <u>First Floor</u>		608.00	@ Rs: 349.10 P.Cft		Rs: 212,253
			(Three hundred Forty Nine rup: Ten Pessas only)		
4	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)				
		84.330	@ Rs: 5,001.70 P.Cwt		Rs: 421,793
			( Five thousand one rup: & seventy paisa only)		
5	Supply and fixing sand under floor including plugging in to walls				
		1392.00	@ Rs: 1,141.25 % Cft		Rs: 15,886
			(Eleven hundred forty one rupees & twenty five paisa only)		
6	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.				
(a) <u>Ground Floor</u>		604.00	@ Rs. 12,674.36 % Cft		Rs. 76,553
			(Twelve thousand six hundred seventy four rup: & thity six paisa only)		
(b) <u>First Floor</u>		705.00	@ Rs. 13,112.99 % Cft		Rs. 92,447
			(Thirteen thousand One hundred Twelve rup: & Ninety Nine paisa only)		
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
(a) <u>Ground Floor</u>		1718.00	@ Rs. 2,206.60 % Cft		Rs. 37,909
			(Twenty tow hund: six rup: & sixty paisa only)		

  
**XEN**



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(b) **First Floor**

1380.00 @ Rs. 2,308.84 % Cft Rs. 31,862  
(Twenty Three hund: Eight rup: & Eighty Four paisa only)

8 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

(a) **Ground Floor**

1686.00 @ Rs: 2,197.52 % Sft Rs: 37,050  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

(b) **First Floor**

1348.00 @ Rs: 2,299.76 % Sft Rs: 31,001  
(Twenty Two hund: ninty nine rup: & Seventy six paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges

9 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs.

The cost also i/c all carriage, tools and pla

59.00 @ Rs: 228.90 P. Rft Rs: 13,505  
(Two hundred twenty eight rupees & ninty paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded

10 hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools

178.00 @ Rs: 240.50 P. Rft Rs: 42,809  
(Two hundred forty rupees & fifty paisa only)

11 Making Notice board made with cement.

64.00 @ Rs: 58.11 P. Sft Rs: 3,719  
(Nnety Three rupees & Thirty Seven paisa only)

1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts

12 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

200.00 @ Rs: 902.93 P. Sft Rs: 180,586  
(Nine hund: two rup: & ninty three paisa only)

13 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

2.464 @ Rs: 3,550.00 P. Sft Rs: 8,747  
(Three Thousand Five hundred Fifty rupees & only)

14 Cutting & Fixing iron bars for barred windows.

36.00 @ Rs. 28.23 P. Sft Rs. 1,016  
( Twenty Eihgt rupees & Twenty Three Paisa only)

15 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.

22.00 @ Rs. 14,429.25 % Cft Rs. 3,174  
(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 16 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

(a) **Ground Floor**

460.00 @ Rs: 4,411.82 % Sft Rs: 20,294  
(Forry four hundred eleven rup: & eighty two paisa only)

(b) **First Floor**

(B) **2" Thick.**

1012.00 @ Rs: 3,502.38 Rs: 35,444  
(Thirty Five hundred Two rup: & Thirty Eight paisa only)

- 17 P/L Glazed tile 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. 60 P/47)

167.00 @ Rs: 30,509.77 % Sft Rs: 50,951  
(Thirty thousand Five Hund: Nine rup: & Seventy Seven paisa only)

- 18 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)

692.00 @ Rs. 1,887.40 % Sft Rs. 13,061  
(Eighteen hundred eighty seven rupees & forty paisa only)

- 19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel

28.00 @ Rs: 226.02 P. Sft Rs: 6,329  
(Two hundred twenty six rupees & two paisa only)

- 20 Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complete ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

165.00 @ Rs: 180.50 P. Sft Rs: 29,783  
(One hundre ninty four rupees & sixteen paisa only)

- 21 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

838.00 @ Rs: 1,287.44 % Sft Rs: 10,789  
(Twelve hundred eighty seven rupees & forty for paisa only)

- 22 White wash Three Coats (S.I No. 26 © P/53)

1048.00 @ Rs: 829.95 % Sft Rs: 8,698  
(Eight hundred twenty nine rup: & ninty five paisa only)

- 23 Primary coat of chalk distemper( S.I No. 23 P/53)

3098.00 @ Rs: 442.75 % Sft Rs: 13,716  
(Four hundred forty two rupees & seventy five paisa only)

- 24 Distemping Three Coats (S.I No. 24 ©P/53)

3098.00 @ Rs: 1,079.65 % Sft Rs: 33,448  
(One thousand Seventy nine rup: & sixty five paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 25 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

1125.00 @ Rs. 1,948.10 % Sft Rs. 21,916  
Twenty on hundred sixteen rupees & forty one paisa only)

- 26 Preparing surface and painting of doors and windows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).

312.00 @ Rs: 2,116.41 % Sft Rs: 6,603  
( Twenty one hundred sixteen rup & forty one paisa only)

**Total Rs. 1,937,422**

  
**XEN**

## Schedule-B

Name of  
Work:-

**CONSTRUCTION OF ADDITIONAL CLASS ROOMS IN EXISTING PRIMARY  
SCHOOLS TALUKA RATODERO (2017-18 PROGRAMME) @ GBPS SAVO  
LABANO (02 C/R) TALUKA RATODERO DISTRICT LARKANO.**

102

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.				
		1910.00	@ Rs: 3,176.25 % 0Cft		Rs: 6,067
			(Thirty one Hundred seventy six rup: & twenty five paisa only)		
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:2:4. (S.I. No. 4 © P/14)				
(A)		237.00	@ Rs: 9,416.28 % Cft		Rs: 22,317
			Nine thousand four hundred Sixteen rup: & twenty eight paisa only)		
(B)	<u>Ratio 1:5:10.</u>				
		184.00	@ Rs: 8,694.95 % Cft		Rs: 15,999
			(Eighty six hund: ninty four rup: & ninty five paisa only)		
3	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
(a)	<u>Ground Floor</u>				
		1281.00	@ Rs: 337.00 P.Cft		Rs: 431,697
			(Three hundred Thirty seven rup: only)		
(b)	<u>First Floor</u>				
		608.00	@ Rs: 349.10 P.Cft		Rs: 212,253
			(Three hundred Forty Nine rup: Ten Pessas only)		
4	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No. 8 (b) P/16)				
		84.330	@ Rs: 5,001.70 P.Cwt		Rs: 421,793
			( Five thousand one rup: & seventy paisa only)		
5	Supply and fixing sand under floor including plugging in to walls				
		1392.00	@ Rs: 1,141.25 % Cft		Rs: 15,886
			(Eleven hundred forty one rupees & twenty five paisa only)		
6	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.				
(a)	<u>Ground Floor</u>				
		604.00	@ Rs. 12,674.36 % Cft		Rs. 76,553
			(Twelve thousand six hundred seventy four rup: & thity six paisa only)		
(b)	<u>First Floor</u>				
		705.00	@ Rs. 13,112.99 % Cft		Rs. 92,447
			(Thirteen thousand One hundred Twelve rup: & Ninety Nine paisa only)		
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)				
(a)	<u>Ground Floor</u>	1718.00	@ Rs. 2,206.60 % Cft		Rs. 37,909
			(Twenty tow hund: six rup: & sixty paisa only)		

  
22/09/2018

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(b) **First Floor**

1380.00 @ Rs. 2,308.84 % Cft Rs. 31,862  
(Twenty Three hund: Eight rup: & Eighty Four paisa only)

8 Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)

(a) **Ground Floor**

1686.00 @ Rs: 2,197.52 % Sft Rs: 37,050  
(Twenty one hund: ninty seven rup: & fifty two paisa only)

(b) **First Floor**

1348.00 @ Rs: 2,299.76 % Sft Rs: 31,001  
(Twenty Two hund: ninty nine rup: & Seventy six paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges

9 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs.  
The cost also i/c all carriage, tools and pla

59.00 @ Rs: 228.90 P. Rft Rs: 13,505  
(Two hundred twenty eight rupees & ninty paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for Windows using 20 gauge G.I sheet i/c Velded

10 hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools

178.00 @ Rs: 240.50 P. Rft Rs: 42,809  
(Two hundred forty rupees & fifty paisa only)

11 Making Notice board made with cement.

64.00 @ Rs: 58.11 P. Sft Rs: 3,719  
(Nnety Three rupees & Thirty Seven paisa only)

1<sup>st</sup> class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts

12 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

200.00 @ Rs: 902.93 P. Sft Rs: 180,586  
(Nine hund: two rup: & ninty three paisa only)

13 M.S barred windows squars bars 5/8" dia S.I No. 146 P/72).

2.464 @ Rs: 3,550.00 P. Sft Rs: 8,747  
(Three Thousand Five hundred Fifty rupees & only)

14 Cutting & Fixing iron bars for barred windows.

36.00 @ Rs. 28.23 P. Sft Rs. 1,016  
( Twenty Eihgt rupees & Twenty Three Paisa only)

15 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.

22.00 @ Rs. 14,429.25 % Cft Rs. 3,174  
(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)

  
**XEN**

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 16 Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

(a) **Ground Floor**

460.00 @ Rs: 4,411.82 % Sft Rs: 20,294  
( Forry four hundred eleven rup: & eighty two paisa only)

(b) **First Floor**

(B) **2" Thick.**

1012.00 @ Rs: 3,502.38 Rs: 35,444  
(Thirty Five hundred Two rup: & Thirty Eight paisa only)

- 17 P/L Glazed tile 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. 60 P/47)

167.00 @ Rs: 30,509.77 % Sft Rs: 50,951  
(Thirty thousand Five Hund: Nine rup: & Seventy Seven paisa only)

- 18 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)

692.00 @ Rs. 1,887.40 % Sft Rs. 13,061  
( Eighteen hundred eighty seven rupees & forty paisa only)

- 19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel

28.00 @ Rs: 226.02 P. Sft Rs: 6,329  
( Two hundred twenty six rupees & two paisa only)

- 20 Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee ( weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)

165.00 @ Rs: 180.50 P. Sft Rs: 29,783  
( One hundre ninty four rupees & sixteen paisa only)

- 21 Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)

838.00 @ Rs: 1,287.44 % Sft Rs: 10,789  
(Twelve hundred eighty seven rupees & forty for paisa only)

- 22 White wash Three Coats (S.I No. 26 © P/53)


1048.00 @ Rs: 829.95 % Sft Rs: 8,698  
(Eight hundred twenty nine rup: & ninty five paisa only)

- 23 Primary coat of chalk distemper( S.I No. 23 P/53)

3098.00 @ Rs: 442.75 % Sft Rs: 13,716  
(Four hundred forty two rupees & seventy five paisa only)

- 24 Distemping Three Coats (S.I No. 24 ©P/53)

3098.00 @ Rs: 1,079.65 % Sft Rs: 33,448  
(One thousand Seventy nine rup: & sixty five paisa only)

  
JUN 11

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 25 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).

1125.00 @ Rs. 1,948.10 % Sft Rs. 21,916  
Twenty on hundred sixteen rupees & forty one paisa only)

- 26 Preparing surface and painting of doors and windows any type, (including edges)  
(3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii) ).

312.00 @ Rs: 2,116.41 % Sft Rs: 6,603  
( Twenty one hundred sixteen rup & forty one paisa only)

**Total Rs. 1,937,422**

  
**XEN**

# **SCHEDULE "B"**

**Name of Work:-**

Construction of Building For Shelterless Primary Schools District  
Larkana(2017-18 Prog) At: GBPS Jumo Kalhoro Taluka Bakrani

S.N	Description	Qty:	Rate			Amount
-----	-------------	------	------	--	--	--------

- 1 Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).

= 5,490

@ Rs: 3176.25      %0 CFT      Rs: **17,438**

(Three Thousand One Hund:Seventy Six & P.S Twenty Five onl

- 2 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:4:8 (S.I.No 4 (C) P/16).

= 428

@ Rs: 9416.18      % CFT      Rs: **40,301**

[ Nine thousands four hundred sixteen Eighteen & P.S only)

- 3 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).

= 435

@ Rs: 8694.95      % CFT      Rs: **37,823**

( Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)

- 4 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C ) 23.

= 2,260

@ Rs: 11948.36      % CFT      Rs: **270,033**

(Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six c

- 5 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a ) P/18)

= 2,560

@ Rs: 337.00      P.CFT      Rs: **862,720**

( Three Hundred Thirty Seven only)

- 6 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)

= 125

@ Rs: 5001.70      P.CWT      Rs: **625,213**

(Five Thousand One &P.S Seventy ).

- 7 S/F sand floor and plugging into walls (S.I.No 29 P/31).

= 3,387

@ Rs: 1141.25      %SFT      Rs: **38,654**

(Rs:One Thousand One Hund: Fourty One & P.S Twenty Five on

- 8 Extra Lead 3 Miles

= 3,387

@ Rs: 579.41      %SFT      Rs: **19,625**

(Rs:Five thousands seventy nine fourty one P.S only)

- 9 Providing and laying single per layer of polythen sheet 0.13 mm thick for water proffing as per specification instruments of Engineer Incharge.

= 321

@ Rs: 10.70      P.sft      Rs: **3,435**

(Rs: Ten Rupes Seventy P.S only)

  
**XEN**



S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

10 Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 ( C ) P/24)

= 1,754

@ Rs: 12674.36 %SFT Rs: 222,308

( Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six only)

11 Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 ( C ) P

= 750

@ Rs: 12346.65 %SFT Rs: 92,600

(Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five only)

12 Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and s bars 4" centre to cement .

= 48

@ Rs: 726.72 P.Sft Rs: 34,883

( Seven hundred twenty six rupes )

13 P/F G.I frame chokats of size 7" x2" or 4" x 3" for Doors using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand reparing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)

= 77

@ Rs: 228.90 P.Sft Rs: 17,625

(Two hundred twenty eight rupes nintyP.S only)

14 P/F G.I frame chokats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand reparing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)

= 190

@ Rs: 240.50 P.Sft Rs: 45,695

(Two Hundred fourty rupes Fifty P.S only)

15 Supplying M.S Sqaure bar 5/8 dia ( Sch: of material)

= 1,429

@ Rs: 3350.00 P.Sft Rs: 4,787

(Three thousands three hundred fifty rupes only)

16 Cutting & Fixing iron bar for barrid windows

= 52.00

@ Rs: 28.23 P.Sft Rs: 1,468

(Twenty Eight Twenty three only)

17 S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with not to beless than 3.7 Lbs sq: ft: of finished grill.

= 203

@ Rs: 194.16 %Cft Rs; 39,414

(Rs: One hundred Ninety Four & P.S Sixteen only)

18 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)

= 180

@ Rs: 902.93 P.CFT Rs: 162,527

( Nine Hundraed Two P.S Ninty Three only)

19 Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)

= 3,477

@ Rs: 2206.60 %Cft Rs; 76,723

( Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)



S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

20 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)

= 3,477

@ Rs: 2197.52 %SFT Rs: 76,408

( Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)

21 Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.19 (a) P/53)

= 2,470

@ Rs: 1287.44 %SFT Rs: 31,800

( Twolive Thousand Eighty Seven & P.S Fourty Four only)

22 Notice Board mad with cement. (S.I.No 1 P/100).

= 64

@ Rs: 58.11 %SFT Rs: 3,719

( Fifty Eight Eleven P.S only)

23 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick.  
(S.I No:16 ( C ) P/46)

= 995

@ Rs: 4411.82 %SFT Rs: 43,898

(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)

(B) Ratio 2" thick,

= 459

@ Rs: 3275.50 %SFT Rs: 15,035

(Rs: Three Thousands two hundred seventy five rupes Fifty P.S only)

24 Two coat of bitumen laid not using 34 lbs for over foof and blinded with stand at Cft per ( S.I No: 13 P/40)

= 1,465

@ Rs: 1887.40 %SFT Rs: 27,650

(Rs: One thousands Eight hundred eighty seven P.S Fourty four )

25 Providing and Fixing ornamental cement jalli 2" thick (1:2:4) with out steel (s.i.no:11p/17)

= 100

@ Rs: 226.04 %SFT Rs: 22,604

(Rs: Two hundred twenty sex rupes )

26 Primary coat of chalk under distemping ( S.I No: 23 P 59)

= 6,110

@ Rs: 442.75 %CFT Rs: 27,052

( Four Hundred Fourty Two & P.S Seventy Five only)

27 Distemping three coats ( S.I No: 24( B ) P 59)

= 6,555

@ Rs: 1079.65 %CFT Rs: 70,771

(Rs: One Thousand Seventy Nine & P.S Sixty Five only)

28 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface w  
brick /sen paper filling the voilds with chalk plaster of paris and then painting with weather coat of approv  
make New surface. (S.I.No 39 (a) P/62).

= 1,166

@ Rs: 1948.10 %CFT Rs: 22,715

(Rs: One thousands nine hundred fourty eight only)

  
XEN

S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

29 Painting doors & window any type, (S.I.No 05 P/ 76)

= 470

@ Rs: 2116.41

%Cft

Rs;

9,947

(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One only)

30 Painting guards bars , gates iron bars gratings railings i/c standard bares etc smiller open works

= 96

@ Rs: 1270.83

%Cft

Rs;

1,220

(Rs: One thousands two hundred seventy rupes eighty three only)

**Total Rs: 2,966,091**

**SCHEDULE "B"****Name of Work:-**

Construction of Building For Shelterless Primary Schools District  
Larkana(2017-18 Prog) At: GBPS Muhammad Khan Chandio  
Taluka Dokri

S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

- 1 Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).

= **5,490**

@ Rs: 3176.25 %0 CFT Rs: **17,438**

(Thirty one Hundred seventy six rup: & twenty five paisa only)

- 2 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:4:8 (S.I.No 4 (C) P/16).

= **428**

@ Rs: 9416.18 % CFT Rs: **40,301**

(Nine thousands four hundred sixteen Eighteen P.S only)

- 3 Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).

= **435**

(Eighty six hund: ninty four rup: & ninty five paisa only)

@ Rs: 8694.95 % CFT Rs: **37,823**

- 4 Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 ( C) 23.

= **2,260**

@ Rs: 11948.36 % CFT Rs: **270,033**

(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)

- 5 RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 ( a) P/18)

= **2,560**

@ Rs: 337.00 P.CFT Rs: **862,720**

(Thiree hundred Thirtty seven rup: only)

- 6 Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)

= **125**

@ Rs: 5001.70 P.CWT Rs: **625,213**

( Five thousand one rup: & seventy paisa only)

- 7 S/F sand floor and plugging into walls (S.I.No 29 P/31).

= **3,387**

@ Rs: 1141.25 %SFT Rs: **38,654**

(Eleven hundred forty one rupees & twenty five paisa only)

- 8 Extra Lead 3 Miles

= **3,387**

@ Rs: 579.41 %SFT Rs: **19,625**

(Five hundred seventy nine fourty one P.S only)

- 9 Providing and laying single per layer of polythen sheet 0.13 mm thick for water proffing as per specification instruments of Engineer Incharge.

= **321**

@ Rs: 10.70 P.sft Rs: **3,435**

(Ten rupees & seventy paisa only)

*[Signature]*

S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

10 Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 ( C ) P/24)

= 1,754

@ Rs: 12674.36 %SFT Rs: 222,308

(Twelve thousand six hundred seventy four rup: & thity six paisa only)

11 Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 ( C ) P

= 750

@ Rs: 12346.65 %SFT Rs: 92,600

(Twelve thousand three hund: forty six rup: & sixty five paisa only)

12 Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and s bars 4" centre to cement .

= 48

@ Rs: 726.72 P.Sft Rs: 34,883

(Seven hundred twenty six rupees & seventy two paisa only)

13 P/F G.I frame chokats of size 7" x2" or 4" x 3" for Doors using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand reparing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)

= 77

@ Rs: 228.90 P.Sft Rs: 17,625

(Two hundred twenty eight rupees & ninty paisa only)

14 P/F G.I frame chokats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fots filling with cement sand reparing i/c all carriage tools and planst used in making and fixing . (S.I.No 28 P/98)

= 190

@ Rs: 240.50 P.Sft Rs: 45,695

(Two hundred forty rupees & fifty paisa only)

15 Supplying M.S Sqaure bar 5/8 dia ( Sch: of material)

= 1,429

@ Rs: 3350.00 P.Sft Rs: 4,787

(Three Thousand Five hundred Fifty rupees & only)

16 Cutting & Fixing iron bar for barrid windows

= 52.00

@ Rs: 28.23 P.Sft Rs: 1,468

( Twenty Eihgt rupees & Twenty Three Paisa only)

17 S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with not to beless than 3.7 Lbs sq: ft: of finished grill.

= 203

@ Rs: 194.16 %Cft Rs: 39,414

( One hundre ninty four rupees & sixteen paisa only)

18 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)

= 180

@ Rs: 902.93 P.CFT Rs: 162,527

(Nine hund: two rup: & ninty three paisa only)

19 Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)

= 3,477

@ Rs: 2206.60 %Cft Rs: 76,723

(Twenty tow hund: six rup: & sixty paisa only)

  
XEN

S.N	Description	Qty:	Rate		Amount
-----	-------------	------	------	--	--------

- 20 Cement plaster 1:4 upto 20' ft; height 3/8" thick. ( S.I No: 11(a) P 57)  
 = 3,477  
 @ Rs: 2197.52 %SFT Rs: 76,408  
 (Twenty one hund: ninty seven rup: & fifty two paisa only)
- 21 Cement pointing and stricking of joints on walls ratid. 1: 2 ( S.I No.19 (a) P/53)  
 = 2,470  
 @ Rs: 1287.44 %SFT Rs: 31,800  
 (Twelve hundred eighty seven rupees & forty for paisa only)
- 22 Notice Board mad with cement. (S.I.No 1 P/100).  
 = 64  
 @ Rs: 58.11 %SFT Rs: 3,719  
 ( Fifty Eight Eleven P.S only)
- 23 P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick.  
 (S.I No:16 ( C ) P/46)  
 = 995  
 @ Rs: 4411.82 %SFT Rs: 43,898  
 ( Forry four hundred eleven rup: & eighty two paisa only)
- (B) Ratio 2" thick,  
 = 459  
 @ Rs: 3275.50 %SFT Rs: 15,035  
 (Thirty Two hundred Seventy Five rup: & Fifty paisa only)
- 24 Two coat of bitumen laid not using 34 lbs for over foof and blinded with stand at Cft per ( S.I No: 13 P/40)  
 = 1,465  
 @ Rs: 1887.40 %SFT Rs: 27,650  
 ( Eighteen hundred eighty seven rupees & forty paisa only)
- 25 Providing and Fixing ornamental cement jalli 2" thick (1:2:4) with out steel (s.i.no:11p/17)  
 = 100  
 @ Rs: 226.00 %SFT Rs: 226  
 ( Two hundred twenty six only)
- 26 Primary coat of chalk under distemping ( S.I No: 23 P 59)  
 = 6,110  
 @ Rs: 442.75 %CFT Rs: 27,052  
 (Four hundred forty two rupees & seventy five paisa only)
- 27 Distemping three coats ( S.I No: 24( B ) P 59)  
 = 6,555  
 @ Rs: 1079.65 %CFT Rs: 70,771
- 28 Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface w  
 brick /sen paper filling the voilds with chalk plaster of paris and then painting with weather coat of approv  
 make New surface. (S.I.No 39 (a) P/62).  
 = 1,166  
 @ Rs: 1948.10 %CFT Rs: 22,715  
 Twenty on hundred sixteen rupees & forty one paisa only)
- 29 Painting doors & window any type, (S.I.No 05 P/ 76)  
 = 470  
 @ Rs: 2116.41 %Cft Rs: 9,947  
 ( Twenty one hundred sixteen rup & forty one paisa only)

  
**XEN**

S.N	Description	Qty:	Rate			Amount
-----	-------------	------	------	--	--	--------

30 Painting guards bars , gates iron bars gratings railings i/c standard bares etc smiller open works

= 96

@ Rs: 1270.83

%Cft

Rs;

1,220

(Twelve Hundred seventy rupees & eithy three paisa only)

Total Rs: 2,943,713

 XEN

**SCHEDULE "B"**

105

Name of Work:- Construction of Bilawal Bhutto Zardari Peoples Parks at Larkano ( Electric).

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part A Schedule Item**

- 1 Providing & Fixing of MS hexagonal pole as per following specification to be fixed on pre-cost foundation with help of hydraulic crane & manual labour. 40ft long with dia of pole at the top 4" & bottom 12" wall thickness 6mm base plate 24"x24"x1" Stiffener 12"x6"x1/2" 8 nos. Holes 6 nos. Making window in the pole required size with LN key provision Two coats red oxide as rust preventive Two coats oil paint as per site requirement & instruction of EI. (S.I.No: 135 P 17).  
3.00 @ Rs: 109843 P.Point Rs: 329,529.00
  - 2 Providing & Fixing of MS tabular pole as following specification to be fixed on pre-cost foundation with the help of hydraulic crane & manual labour. 6Mtr-(6"dia) x 3Mtr (5"dia) x 3Mtr (4"dia) = 40ft wall thickness 8 SWG Base plate 18"x18"x3/4 Hole 4 no's stiffeners 4 nos. 9 1/2"x41/2"x1/2 Making window in the pole required size with LN key provision Two coats red oxide (2 coat) as rust preventive & of required oil paint (2 coat) as Par site requirement & instruction of EI. (S.I.No: 133 P 16).  
10.00 @ Rs: 37797 P.Point Rs: 377,970.00
  - 3 Construction of RCC foundation as per following specification & instruction of EI for 40/50ft long hexagonal pole 18"x6 Excavation of soft/hard soil 4'x4'x9' Stone soiling 4'x4'x6 making lean in the ratio of 1:4:8 length of MS bolts 9 1/2 (1 1/4" dia) 8 no's & Making thread on MS rod Template 22"x22"x1/4 Rings 1/4" dia round bar to the welded with MS rod RCC foundation ratio 1:2:4 with appropriation size 2.5'x2.5'x8.5 (S.I.No: 141 P 19).  
3.00 @ Rs: 31580 P.Point Rs: 94,740.00
  - 4 Construction of RCC foundation as per following specification & instruction of EI for 31ft/40ft long tubular pole Excavation of soft/hard soil 3'x3'x5.5' Stone soiling 3'x3'x6 making lean in the ratio of 1:4:8 length of MS bolts 6 1/2 (3/4" dia) 4 no's & Making thread on MS rod Template 16"x16"x1/4 Rings 1/4" dia round bar 4 no's to the welded with MS rod RCC foundation ratio 1:2:4 with appropriation size 2'x2'x6.5 (S.I.No: 139 P 19).  
10.00 @ Rs: 15168 P.Point Rs: 151,680.00
  - 5 Manufacturing Providing & Fixing GI double Arm with help of hydraulic crane & manual labour as per site requirement instruction of EI with following specification GI pipe 2"dia 10 SWG 7'long MS canopy 5"dia long with nuts & bolts.(S.I.No: 152 P 22).  
15.00 @ Rs: 4571 P.Point Rs: 68,565.00
  - 6 Providing & Fixing of street light 250 watts (SON-T) having IP66 classification with 250w lamp,choke capacitor & Internal wiring complete in all respect at the height with the help of hydraulic crane as per site requirement and instruction of EI. (S.I.No: 163 P 25).  
18.00 @ Rs: 24790 P.Point Rs: 446,220.00
- 2 Core Wires**
- 7 Providing & Laying (MAIN or SUB MAIN) PVC insulated & PVC sheathed with two core copper conductor 300/500 volts size 2.5mm<sup>2</sup> (S.I.No: 60 P 8).  
400.00 @ Rs: 118 P.Mater Rs: 47,200.00
  - 8 Providing & Laying (MAIN or SUB MAIN) PVC insulated & PVC sheathed with two core conductor 300/500 volts size 4mm<sup>2</sup> (S.I.No: 61 P 8).  
150.00 @ Rs: 170 P.Mater Rs: 25,500.00
- 4 Core Wires**
- 9 Providing & Laying (MAIN or SUB MAIN) PVC insulated & PVC sheathed with 4core copper conductor 300/500 volts size 10mm<sup>2</sup> (S.I.No: 101 P 12).  
250.00 @ Rs: 742 P.Mater Rs: 185,500.00



SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
10	Providing & Laying (MAIN or SUB MAIN) PVC insulated & PVC sheathed with 4core copper conductor 600/1000 volts size 16mm <sup>2</sup> (S.I.No: 102 P 12).	70.00	@ Rs:	1300	P.Mater	Rs: 91,000.00
11	Providing & Laying (MAIN or SUB MAIN) PVC insulated & PVC sheathed with 4core Armoured copper conductor 600/1000 volts size 10mm <sup>2</sup> (S.I.No: 112 P 13).	75.00	@ Rs:	1230	P.Mater	Rs: 92,250.00
12	Providing & Laying (MAIN or SUB MAIN) PVC insulated & PVC sheathed with 4core Armoured copper conductor 600/1000 volts size 16mm <sup>2</sup> (S.I.No: 113 P 13).	85.00	@ Rs:	1679	P.Mater	Rs: 142,715.00
13	Providing & Fixing of street light 250 watts (SON-T) having IP65 classification with 250w lamp,choke, capacitor & Internal wiring complete in all respect at the height with the help of hydraulic crane as per site requirement. (S.I.No: 162 P 25).	4.00	@ Rs:	16100	P.Each	Rs: 64,400.00
14	Providing & Fixing of flood light 400 watts (SON-T) having IP65 classification with 400w lamp,choke, capacitor & Internal wiring complete in all respect at the height up to 40ft with the help of hydraulic crane as per site requirement. (S.I.No: 166 P 26).	2.00	@ Rs:	17585	P.Each	Rs: 35,170.00
15	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	51.00	@ Rs:	916	P.Each	Rs: 46,716.00
16	Providing & Fixing circuit breaker 6,10,15,20,30,40,50 & 63amp DP (TB-5S) on prepared board as required. (S.I.No: 204 P 31)	10.00	@ Rs:	2456	P.Each	Rs: 24,560.00
17	Providing & Fixing circuit breaker 3,5,10,15,20,&30Amp TP (XS-30NS[NB])on prepared board as required (S.I.No: 205 P 31)	2.00	@ Rs:	5301	P.Each	Rs: 10,602.00
18	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).	4.00	@ Rs:	9261	P.Each	Rs: 37,044.00
19	Providing & Fixing Circuit breaker 125,150,200,& 225 Amp TP (XS-225NS) on a prepared board as required (S.I.No: 208 P 31).	2.00	@ Rs:	25541	P.No	Rs: 51,082.00
20	Providing & Fixing Circuit breaker 250Amp TP Setting 160-250amp (XS-250NJ) on a prepared board as required (S.I.No: 209 P 31).	1.00	@ Rs:	27411	P.No	Rs: 27,411.00
<b>AMPERE METER</b>						
21	Providing & Fixing ammeters size 96/96mm Direct 15A, 30A, 60A, & 100A as required & as per instruction of EI (S.I.No: 284 P 41).	10.00	@ Rs:	1054	P.No	Rs: 10,540.00
<b>VOLT METER</b>						
22	Providing & Fixing voltmeter size 96/96mm 500volt as required & as per instruction of EI (S.I.No: 285 P 41).	10.00	@ Rs:	999	P.No	Rs: 9,990.00
23	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") PVC conduit recessed in the wall or column as required (S.I.No: 124 P 15).	133.00	@ Rs:	1130	P.Point	Rs: 150,290.00

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
------	--------------	------	--	------	------	---------

24	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") PVC conduit recessed in the wall or column as required (S.I.No: 126 P 15)	30.00	@ Rs:	985	P.Point	Rs: 29,550.00
25	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029) Copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (S.I.No: 10 P 2)	102.00	@ Rs:	222	P.Meter	Rs: 22644.0
26	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/044)(6mm2) Copper conductor in 1" dia PVC conduit recessed in the wall or column as required (S.I.No: 11 P 2).	102.00	@ Rs:	341	P.Meter	Rs: 34,782.00
27	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	30.00	@ Rs:	162	P.Each	Rs: 4860.0
28	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	80.00	@ Rs:	70	P.Each	Rs: 5,600.00
29	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	20.00	@ Rs:	72	P.Each	Rs: 1,440.00

**Non Schedule Item**

30	Providing & Fixing Low Light pole 6ft hexagonal type Metal Colour with foundation and Wiring i/c Labour charges etc	15.00	@ Rs:	14500	P.Each	Rs: 217,500.00
31	Providing & Fixing Bultet Light 2.75 37ft long in 4" Black pipe style i/c top of light with glass shade frame i/c i/c holder wiring saver and foundation i/c Labour charges etc	20.00	@ Rs:	7910	P.Each	Rs: 158,200.00
32	Providing & Fixing gate Light with 45 watt saver metal shape mach with pole style i/c Labour charges etc	15.00	@ Rs:	5100	P.Each	Rs: 76,500.00
33	Providing & Fixing LED Light 8" square / circle shop (09) watt in plastic cover fancy type (Chaina made) (R.A)	33.00	@ Rs:	2450	P.Each	Rs: 80,850.00
34	Supply and fixing A.C electric ceiling fan 56" sweep (pure copper winding) i/c down rod, canopy blade, suitable (Double bearing) internal electric connection with 3/029 PVC (R.A) (Royal Fan, younis Fan, Pak Fan)	20.00	@ Rs:	5500	P.No	Rs: 110,000.00
35	P/F Flush type fancy type switch 10 amps i/c plastic board imported made etc complete (R.A).	150.00	@ Rs:	130	P.Each	Rs: 19,500.00
36	P/F 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary connection (R.A).	40.00	@ Rs:	195	P.Each	Rs: 7,800.00
37	P/F flush type 3 pin 1 plug socket 15 amps with fancy type board and sheet i/c necessary connection (R.A).	20.00	@ Rs:	350	P.Each	Rs: 7,000.00
38	P/F distribution board double shutter for accommodate circuit breaker and busbar i/c painting with enamel paint.(R.A)	6.00	@ Rs:	1950	P.Sq.ft:	Rs: 11,700.00
39	Providing & Fixing main panel board double shutter to accommodate heavy duty circuit breaker bus bar in painting.(R.A)	6.00	@ Rs:	2900	P.Sq.ft:	Rs: 17,400.00

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
40	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(R.A)	3.00	@ Rs:	15000	P.Set	Rs: 45,000.00
41	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (R.A)	35.00	@ Rs:	600	Each	Rs: 21,000.00
42	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(R.A)	100.00	@ Rs:	600	P.Each	Rs: 60,000.00
43	P/F 2-40 watts tube light complete with 40 watts 4-0 long rod chock starter and metal base with lover plastic shade as approved with philip components including necessary electric connection..(R.A)	15.00	@ Rs:	3200	P.Each	Rs: 48000.0

**TOTAL:** Rs: 3,500,000.0



Name of Work:- Rehabilitation & Expansion of High Priority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at: GBPS Ali Goharabad (Rehab:), GBPS Rehmatpur (Rehab:), 2 Add C.R. GBPS Khair Shah Bukhari (Rehab:), GBPS Shah Muhammad Sindhi (Rehab:), GBPS Lahori (Rehab:) Taluka Larkano ( Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	178.00	@ Rs:	910	P.Point	Rs: 161,980.00
	(B)	141.00	@ Rs:	1130	P.Point	Rs: 159,330.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	55.00	@ Rs:	742	P.Point	Rs: 40,810.00
	(B)	28.00	@ Rs:	985	P.Point	Rs: 27,580.00
3	Wiring for Call bell with (3/.029) PVC insulated wire in 20mm(3/4") PVC conduit recessed in the wall or column as required (S.I.No: 128 P 15)					
		2.00	@ Rs:	1764	P.Point	Rs: 3528.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	1069	@ Rs:	171	P.Meter	Rs: 182799.00
	(B)	680	@ Rs:	222	P.Meter	Rs: 150960.00
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/044}(6mm <sup>2</sup> ) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	525.00	@ Rs:	305	P.Meter	Rs: 160,125.00
	(B)	329.00	@ Rs:	341	P.Meter	Rs: 112,189.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm <sup>2</sup> ) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		610.00	@ Rs:	428	P.Meter	Rs: 261080.00
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	178.00	@ Rs:	54	P.Each	Rs: 9,612.00
	(B)	141.00	@ Rs:	58	P.Each	Rs: 8,178.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		83.00	@ Rs:	83	P.Each	Rs: 6,889.00
9	Providing & Fixing Brass Battern holder.(S.I.No: 232 P 33)					
		206.00	@ Rs:	70	P.Each	Rs: 14,420.00
10	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)					
		126.00	@ Rs:	72	P.Each	Rs: 9,072.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		25.00	@ Rs:	162	P.Each	Rs: 4050.00
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		120.00	@ Rs:	3185	P.No	Rs: 382,200.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		91.00	@ Rs:	916	P.No	Rs: 83,356.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS) on a prepared board as required (S.I.No: 207 P 31).					
		4.00	@ Rs:	9261	P.Each	Rs: 37,044.00
15	Providing & Fixing Circuit breaker 125,150,200,& 225 Amp TP (XS-225NS) on a prepared board as required (S.I.No: 208 P 31).					
		2.00	@ Rs:	25541	P.No	Rs: 51,082.00

Part "A" TOTAL: Rs: 1,866,284.00

  
XEN

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount
------	--------------	------	------	------	--------

**Part "B" (Non Schedule Item)**

16	Providing & Fixing A.C or D.C Electric bell 200/250 Volts 70 MM.(S.I.No: 19 P 12).	2.00	@ Rs: 149.48	P.Each	Rs: 299.0
17	Providing & Fixing flush type electric bell push button.(S.I.No: 21 P 12)	2.00	@ Rs: 25.17	P.Each	Rs: 50.3
13	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	124.00	@ Rs: 91	Each	Rs: 11,284.00
14	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	124.00	@ Rs: 141.71	P.Each	Rs: 17,572.04
17	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	9.00	@ Rs: 3341	P.Set	Rs: 30,069.00
15	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	11.00	@ Rs: 1426.34	P.Sq:ft:	Rs: 15,689.74
16	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	213.00	@ Rs: 497	P.Each	Rs: 105,861.00
18	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	16.00	@ Rs: 497	Each	Rs: 7,952.00

**Part "B" TOTAL: Rs: 188,777.1**

**Part "A" TOTAL: Rs: 1,866,284.0**

**G: TOTAL: Rs: 2,055,061.1**

**Say Rs: 2,055,000.0**

**XEN**

Name of Work:- Rehabilitation & Expansion of High Priority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at:GGPS P.V Primary (Rehab.),GBPS Railway (Rehab.), GBPS Chandka (Rehab.), GBPS Behram Khan Luhar(Rehab.,2addl: C.R),GBPS Rohal Khan Bugti (Rehab.), GBPS Dhamrah-II (Rehab.), GBPS Vikya Sangi (Rehab.), GBPS Dhoon (Rehab.), GBPS Ratokot (Rehab., 5addl: C.R), Taluka Larkano ( Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	194.00	@ Rs:	910	P.Point	Rs: 176,540.00
	(B)	184.00	@ Rs:	1130	P.Point	Rs: 207,920.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	40.00	@ Rs:	742	P.Point	Rs: 29,680.00
	(B)	44.00	@ Rs:	985	P.Point	Rs: 43,340.00
3	Wiring for Call bell with (3/.029) PVC insulated wire in 20mm(3/4") PVC conduit recessed in the wall or column as required (S.I.No: 128 P 15)					
		2.00	@ Rs:	1764	P.Point	Rs: 3528.0
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	1129	@ Rs:	171	P.Meter	Rs: 193059.0
	(B)	1126	@ Rs:	222	P.Meter	Rs: 249972.0
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-/044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	488.00	@ Rs:	305	P.Meter	Rs: 148,840.00
	(B)	556.00	@ Rs:	341	P.Meter	Rs: 189,596.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		802.00	@ Rs:	428	P.Meter	Rs: 343256.0
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	194.00	@ Rs:	54	P.Each	Rs: 10,476.00
	(B)	183.00	@ Rs:	58	P.Each	Rs: 10,614.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		95.00	@ Rs:	83	P.Each	Rs: 7,885.00
9	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)					
		212.00	@ Rs:	70	P.Each	Rs: 14,840.00
10	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)					
		148.00	@ Rs:	72	P.Each	Rs: 10,656.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		24.00	@ Rs:	162	P.Each	Rs: 3888.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		135.00	@ Rs:	3185	P.No	Rs: 429,975.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		118.00	@ Rs:	916	P.No	Rs: 108,088.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS) on a prepared board as required (S.I.No: 207 P 31).					
		4.00	@ Rs:	9261	P.Each	Rs: 37,044.00
15	Providing & Fixing Circuit breaker 125,150,200,& 225 Amp TP (XS-225NS) on a prepared board as required (S.I.No: 208 P 31).					
		1.00	@ Rs:	25541	P.No	Rs: 25,541.00

Part "A" TOTAL: Rs: 2,244,738.0

**XEN**

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Non Schedule Item)**

16	Providing & Fixing A.C or D.C Electric bell 200/250 Volts 70 MM.(S.I.No: 19 P 12).	2.00	@ Rs: 149.48	P.Each	Rs: 299.0
17	Providing & Fixing flush type electric bell push button.(S.I.No: 21 P 12)	2.00	@ Rs: 25.17	P.Each	Rs: 50.3
13	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	146.00	@ Rs: 91	Each	Rs: 13,286.00
14	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	146.00	@ Rs: 141.71	P.Each	Rs: 20,689.66
17	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	10.00	@ Rs: 3341	P.Set	Rs: 33,410.00
15	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	13.00	@ Rs: 1426.34	P.Sq.ft:	Rs: 18,542.42
16	P/F Energy saver superior quality i/c fixing on extg: holder etc complete (S.I.No: 6 P 33)	238.00	@ Rs: 497	P.Each	Rs: 118,286.00
18	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	34.00	@ Rs: 497	Each	Rs: 16,898.00

Part 'B' TOTAL: Rs: 221,461.4

Part "A" TOTAL: Rs: 2,244,738.0

G: TOTAL: Rs: 2,466,199.4

Say Rs: 2,466,000.0

  
**XEN**

Name of Work:- Rehabilitation & Expansion of High Priority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at:GGPS Shaikh Zaid-II (Rehab.:3addl C.R),GGPS Shaheed Abdul Qasir Laghari (Rehab:),GBPS Mitodero (Rehab.:3addl: C.R), GBPS Akil (Rehab.:3addl: C.R), GBPS Shahoo Boraho (Rehab:), GBPS Sacha Bux Jagirani (Rehab:), GGPS Kehar (Rehab:), GBLSS Sher Muhammad Jamali (Rehab:), GBPS Jurio Chandio (Rehab:2addl: C.R), GBPS Wapda Colony-II (Rehab:), GBPS Gul Muhammad Khoso (Rehab:), Taluka Larkano ( Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	248.00	@ Rs:	910	P.Point	Rs: 225,680.00
	(B)	192.00	@ Rs:	1130	P.Point	Rs: 216,960.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	55.00	@ Rs:	742	P.Point	Rs: 40,810.00
	(B)	39.00	@ Rs:	985	P.Point	Rs: 38,415.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	1280	@ Rs:	171	P.Meter	Rs: 218880.0
	(B)	1114	@ Rs:	222	P.Meter	Rs: 247308.0
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/044}{6mm2} Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	436.00	@ Rs:	305	P.Meter	Rs: 132,980.00
	(B)	341.00	@ Rs:	341	P.Meter	Rs: 116,281.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}{10mm2} Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		1038.00	@ Rs:	428	P.Meter	Rs: 444264.0
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	260.00	@ Rs:	54	P.Each	Rs: 14,040.00
	(B)	192.00	@ Rs:	58	P.Each	Rs: 11,136.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		111.00	@ Rs:	83	P.Each	Rs: 9,213.00
9	Providing & Fixing Brass Battern holder.(S.I.No: 232 P 33)					
		244.00	@ Rs:	70	P.Each	Rs: 17,080.00
10	Providing & Fixing Baklite Ceiling rose with two terminals.(S.I.No: 228 P 33)					
		168.00	@ Rs:	72	P.Each	Rs: 12,096.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		25.00	@ Rs:	162	P.Each	Rs: 4050.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		152.00	@ Rs:	3185	P.No	Rs: 484,120.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		138.00	@ Rs:	916	P.No	Rs: 126,408.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).					
		6.00	@ Rs:	9261	P.Each	Rs: 55,566.00

Part "A" TOTAL: Rs: 2,415,287.0

  
XEN



SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
------	--------------	------	--	------	------	---------

**Part "B" (Non Schedule Item)**

- |    |   |        |       |         |         |                |
|----|---|--------|-------|---------|---------|----------------|
| 13 | Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)  | 162.00 | @ Rs: | 91      | Each    | Rs: 14,742.00  |
| 14 | Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)   | 162.00 | @ Rs: | 141.71  | P.Each  | Rs: 22,957.02  |
| 17 | P/F Earthing set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27). | 8.00   | @ Rs: | 3341    | P Set   | Rs: 26,728.00  |
| 15 | Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)  | 17.00  | @ Rs: | 1426.34 | P.Sq:ft | Rs: 24,247.78  |
| 16 | P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)  | 274.00 | @ Rs: | 497     | P.Each  | Rs: 136,178.00 |
| 18 | P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).  | 36.00  | @ Rs: | 497     | Each    | Rs: 17,892.00  |

---

**Part "B" TOTAL: Rs: 242,744.8**

**Part "A" TOTAL: Rs: 2,415,287.0**

---

**G: TOTAL: Rs: 2,658,031.8**

**Say Rs: 2,658,000.0**

  
**XEN**

Name of Work:- Rehabilitation & Expansion of High Periority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at:GBPS Ratodero-II (Rehab:,6addl C.R),GGPS Madsersatul Ghurba-II (3addl: C.R),GBPS Mubarak Shah (Rehab:), GBPS Wandh Bhutta (Rehab:), GBPS Fatehpur (Rehab:,2addl: C.R), GBPS Waris Dino Machi (Rehab:,3addl: C.R), Taluka Ratodero ( Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	175.00	@ Rs:	910	P.Point	Rs: 159,250.00
	(B)	187.00	@ Rs:	1130	P.Point	Rs: 211,310.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	41.00	@ Rs:	742	P.Point	Rs: 30,422.00
	(B)	34.00	@ Rs:	985	P.Point	Rs: 33,490.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	923	@ Rs:	171	P.Meter	Rs: 157833.0
	(B)	1009	@ Rs:	222	P.Meter	Rs: 223998.0
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	363.00	@ Rs:	305	P.Meter	Rs: 110,715.00
	(B)	368.00	@ Rs:	341	P.Meter	Rs: 125,488.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		679.00	@ Rs:	428	P.Meter	Rs: 290612.0
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	171.00	@ Rs:	54	P.Each	Rs: 9,234.00
	(B)	189.00	@ Rs:	58	P.Each	Rs: 10,962.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		77.00	@ Rs:	83	P.Each	Rs: 6,391.00
9	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)					
		205.00	@ Rs:	70	P.Each	Rs: 14,350.00
10	Providing & Fixing Bakelite Ceiling rose with two terminals .(S.I.No: 228 P 33)					
		132.00	@ Rs:	72	P.Each	Rs: 9,504.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		22.00	@ Rs:	162	P.Each	Rs: 3564.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		119.00	@ Rs:	3185	P.No	Rs: 379,015.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		102.00	@ Rs:	916	P.No	Rs: 93,432.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).					
		4.00	@ Rs:	9261	P.Each	Rs: 37,044.00

Part "A" TOTAL: Rs: 1,906,614.0

  
XEN

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Non Schedule Item)**

- |    |   |        |               |          |                |
|----|---|--------|---------------|----------|----------------|
| 13 | Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)  | 130.00 | @ Rs: 91      | Each     | Rs: 11,830.00  |
| 14 | Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)   | 128.00 | @ Rs: 141.71  | P.Each   | Rs: 18,138.88  |
| 17 | P/F Earthing set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i,c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27). | 7.00   | @ Rs: 3341    | P.Set    | Rs: 23,387.00  |
| 15 | Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)   | 10.00  | @ Rs: 1426.34 | P.Sq:ft: | Rs: 14,263.40  |
| 16 | P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)  | 227.00 | @ Rs: 497     | P.Each   | Rs: 112,819.00 |
| 18 | P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).  | 16.00  | @ Rs: 497     | Each     | Rs: 7,952.00   |

---

**Part "B" TOTAL:** Rs: 188,390.3

**Part "A" TOTAL:** Rs: 1,906,614.0

---

**G: TOTAL:** Rs: 2,095,004.3

**Say** Rs: 2,095,000.0

  
**XEN**

Name of Work:- Rehabilitation & Expansion of High Periority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at:GBPS Naudero-I (Rehab:),GBPS Naudero-II (Rehab:), GBPS Over Crowd Naudero (Rehab:, 3 Add:C.R), GBPS Khuda Bux Phulpoto (Rehab:), GBPS Naudero-3 (Rehab:, 3 Add C.R), GBPS Moria Faqeer (Rehab:, 2 Add: C.R), Taluka Ratodero ( Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/ 029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	175.00	@ Rs:	910	P.Point	Rs: 159,250.00
	(B)	150.00	@ Rs:	1130	P.Point	Rs: 169,500.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	26.00	@ Rs:	742	P.Point	Rs: 19,292.00
	(B)	31.00	@ Rs:	985	P.Point	Rs: 30,535.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	556	@ Rs:	171	P.Meter	Rs: 95076.0
	(B)	874	@ Rs:	222	P.Meter	Rs: 194028.0
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	153.00	@ Rs:	305	P.Meter	Rs: 46,665.00
	(B)	203.00	@ Rs:	341	P.Meter	Rs: 69,223.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		633.00	@ Rs:	428	P.Meter	Rs: 270924.0
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	175.00	@ Rs:	54	P.Each	Rs: 9,450.00
	(B)	154.00	@ Rs:	58	P.Each	Rs: 8,932.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		57.00	@ Rs:	83	P.Each	Rs: 4,731.00
9	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)					
		178.00	@ Rs:	70	P.Each	Rs: 12,460.00
10	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)					
		121.00	@ Rs:	72	P.Each	Rs: 8,712.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		18.00	@ Rs:	162	P.Each	Rs: 2916.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		113.00	@ Rs:	3185	P.No	Rs: 359,905.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40.50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		77.00	@ Rs:	916	P.No	Rs: 70,532.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).					
		4.00	@ Rs:	9261	P.Each	Rs: 37,044.00

Part "A" TOTAL: Rs: 1,569,175.0

  
XEN

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
------	--------------	------	--	------	------	---------

**Part "B" (Non Schedule Item)**

13	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	127.00	@ Rs:	91	Each	Rs: 11,557.00
14	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	128.00	@ Rs:	141.71	P.Each	Rs: 18,138.88
17	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	4.00	@ Rs:	3341	P.Set	Rs: 13,364.00
15	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	10.00	@ Rs:	1426.34	P.Sq.ft:	Rs: 14,263.40
16	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	188.00	@ Rs:	497	P.Each	Rs: 93,436.00
18	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	26.00	@ Rs:	497	Each	Rs: 12,922.00

**Part 'B' TOTAL: Rs: 163,681.3**

**Part "A" TOTAL: Rs: 1,569,175.0**

**G: TOTAL: Rs: 1,732,856.3**

**Say Rs: 1,733,000.0**

  
**XEN**

Name of Work:- Rehabilitation & Expansion of High Periority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at:GBPS Cajra (Rehab.; 2 Add: C.R),GBPS Banguldero (Main) (Rehab.); GBPS Banguldero (Rehab.); GBPS Bhai Khan Ghanrho (1 Add: C.R), GBPS Agham-1 (Rehab.); GBPS Walidad Gabar (Rehab.); GBPS Khan Wah (Rehab.; 1 Add: C.R), GBPS Sohrab Machi (Rehab.) Taluka Ratodero ( Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	342.00	@ Rs:	910	P.Point	Rs: 311,220.00
	(B)	26.00	@ Rs:	1130	P.Point	Rs: 29,380.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	76.00	@ Rs:	742	P.Point	Rs: 56,392.00
	(B)	3.00	@ Rs:	985	P.Point	Rs: 2,955.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	1560	@ Rs:	171	P.Meter	Rs: 266760.0
	(B)	110	@ Rs:	222	P.Meter	Rs: 24420.0
5	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	529.00	@ Rs:	305	P.Meter	Rs: 161,345.00
	(B)	30.00	@ Rs:	341	P.Meter	Rs: 10,230.00
6	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		647.00	@ Rs:	428	P.Meter	Rs: 276916.0
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	345.00	@ Rs:	54	P.Each	Rs: 18,630.00
	(B)	26.00	@ Rs:	58	P.Each	Rs: 1 508.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		79.00	@ Rs:	83	P.Each	Rs: 6,557.00
9	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)					
		231.00	@ Rs:	70	P.Each	Rs: 16,170.00
10	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)					
		132.00	@ Rs:	72	P.Each	Rs: 9,504.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		26.00	@ Rs:	162	P.Each	Rs: 4212.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		120.00	@ Rs:	3185	P.No	Rs: 382,200.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		95.00	@ Rs:	916	P.No	Rs: 87,020.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).					
		4.00	@ Rs:	9261	P.Each	Rs: 37,044.00

Part "A" TOTAL: Rs: 1,702,463.0

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Non Schedule Item)**

13	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	119.00	@ Rs: 91	Each	Rs: 10,829.00
14	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	119.00	@ Rs: 141.71	P.Each	Rs: 16,863.49
17	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No 8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	7.00	@ Rs: 3341	P.Set	Rs: 23,387.00
15	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)	10.00	@ Rs: 1426.34	P.Sq:ft	Rs: 14,263.40
16	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	220.00	@ Rs: 497	P.Each	Rs: 109,340.00
18	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	6.00	@ Rs: 497	Each	Rs: 2,982.00

**Part 'B' TOTAL: Rs: 177,664.9**

**Part "A" TOTAL: Rs: 1,702,463.0**

**G: TOTAL: Rs: 1,880,127.9**

**Say Rs: 1,880,000.0**

  
**XEN**

Name of Work:- Rehabilitation & Expansion of High Priority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at: GBPS Hyder Brohi (4 Add: C.R), GBPS Haji Altaf Hussain Unar (3 Add: C.R), GBPS Ganja Tunia (Rehab: 1 Add: C.R), GBPS Mahi Bhutto (Rehab:), GBPS Ramzan Shaikh (Rehab: 2 Add:), GBPS ali Jatoi (Rehab: 4 Add: C.R), Taluka Bakrani ( Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	157.00	@ Rs:	910	P.Point	Rs: 142,870.00
	(B)	168.00	@ Rs:	1130	P.Point	Rs: 189,840.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	39.00	@ Rs:	742	P.Point	Rs: 28,938.00
	(B)	31.00	@ Rs:	985	P.Point	Rs: 30,535.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	879	@ Rs:	171	P.Meter	Rs: 150309.0
	(B)	932	@ Rs:	222	P.Meter	Rs: 206904.0
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-/.044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	229.00	@ Rs:	305	P.Meter	Rs: 69,845.00
	(B)	375.00	@ Rs:	341	P.Meter	Rs: 127,875.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		855.00	@ Rs:	428	P.Meter	Rs: 365940.0
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	159.00	@ Rs:	54	P.Each	Rs: 8,586.00
	(B)	171.00	@ Rs:	58	P.Each	Rs: 9,918.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		69.00	@ Rs:	83	P.Each	Rs: 5,727.00
9	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)					
		180.00	@ Rs:	70	P.Each	Rs: 12,600.00
10	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)					
		122.00	@ Rs:	72	P.Each	Rs: 8,784.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		23.00	@ Rs:	162	P.Each	Rs: 3726.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		115.00	@ Rs:	3185	P.No	Rs: 366,275.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		83.00	@ Rs:	916	P.No	Rs: 76,028.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).					
		5.00	@ Rs:	9261	P.Each	Rs: 46,305.00

Part "A" TOTAL: Rs: 1,851,005.0

  
XEN



SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Non Schedule Item)**

13	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	116.00	@ Rs: 91	Each	Rs: 10,556.00
14	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	117.00	@ Rs: 141.71	P.Each	Rs: 16,580.07
17	P/F Earthing set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	6.00	@ Rs: 3341	P Set	Rs: 20,046.00
15	Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting (S.I.No: 8 P 13)	12.00	@ Rs: 1426.34	P.Sq.ft:	Rs: 17,116.08
16	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	199.00	@ Rs: 497	P.Each	Rs: 98,903.00
18	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	42.00	@ Rs: 497	Each	Rs: 20,874.00

Part 'B' TOTAL: Rs: 184,075.2

Part "A" TOTAL: Rs: 1,851,005.0

G: TOTAL: Rs: 2,035,080.2

Say Rs: 2,035,000.0

  
**XEN**

Name of Work:- Rehabilitation & Expansion of High Periority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at:GBPS Bakrani station (Rehab:),GBPS Mehrabpur (1 Add: C.R) GBPS Gerelo-II (Rehab:, 1 Add: C.R), GBPS Muhammad Khan Mashori (Rehab:), GBPS Abdul; Samad Tunio (Rehab:, 3 Add:), GBPS Kuli (Rehab:), GGPS Ghulam Ali Zuhriani (Rehab:, 6 Add:), GBPS Garhi Takht Ram (Rehab:), GBPS Mahar Wada (Rehab:, 2 Add:), Taluka Bakrani ( Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	280.00	@ Rs:	910	P.Point	Rs: 254,800.00
	(B)	190.00	@ Rs:	1130	P.Point	Rs: 214,700.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	67.00	@ Rs:	742	P.Point	Rs: 49,714.00
	(B)	40.00	@ Rs:	985	P.Point	Rs: 39,400.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	1494	@ Rs:	171	P.Meter	Rs: 255,474.0
	(B)	1096	@ Rs:	222	P.Meter	Rs: 243,312.0
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	590.00	@ Rs:	305	P.Meter	Rs: 179,950.00
	(B)	412.00	@ Rs:	341	P.Meter	Rs: 140,492.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		1005.00	@ Rs:	428	P.Meter	Rs: 430,140.0
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	283.00	@ Rs:	54	P.Each	Rs: 15,282.00
	(B)	185.00	@ Rs:	58	P.Each	Rs: 10,730.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		110.00	@ Rs:	83	P.Each	Rs: 9,130.00
9	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)					
		285.00	@ Rs:	70	P.Each	Rs: 19,950.00
10	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)					
		205.00	@ Rs:	72	P.Each	Rs: 14,760.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		32.00	@ Rs:	162	P.Each	Rs: 5,184.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		177.00	@ Rs:	3185	P.No	Rs: 563,745.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		122.00	@ Rs:	916	P.No	Rs: 111,752.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).					
		6.00	@ Rs:	9261	P.Each	Rs: 55,566.00
15	Providing & Fixing Circuit breaker 125,150,200,& 225 Amp TP (XS-225NS) on a prepared board as required (S.I.No: 208 P 31).					
		1.00	@ Rs:	25541	P.No	Rs: 25,541.00

Part "A" TOTAL: Rs: 2,639,622.0

  
XEN

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Non Schedule Item)**

13	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)	180.00	@ Rs: 91	Each	Rs: 16,380.00
14	Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)	180.00	@ Rs: 141.71	P.Each	Rs: 25,507.80
17	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27).	9.00	@ Rs: 3341	P.Set	Rs: 30,069.00
15	Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting (S.I.No: 8 P 13)	15.00	@ Rs: 1426.34	P.Sq.ft.	Rs: 21,395.10
16	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	302.00	@ Rs: 497	P.Each	Rs: 150,094.00
18	P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).	32.00	@ Rs: 497	Each	Rs: 15,904.00

**Part 'B' TOTAL: Rs: 259,349.9**

**Part "A" TOTAL: Rs: 2,639,622.0**

**G: TOTAL: Rs: 2,898,971.9**

**Say Rs: 2,899,000.0**

*[Handwritten Signature]*

Name of Work:- Rehabilitation & Expansion of High Priority 4560 Schools (Primary / Elementary) Distt: Larkana (115 Units) (NON-ADP) at: GBPS Dokri (Main) (Rehab:), GGPS Dokri (Main) (Rehab:), GBPS Almani (1 Add: C.R), GBPS Wakro (Rehab:), GBLSS Hatri Ghulam Shah (Rehab:), GBPS Mandhra (Rehab: 2 Add:), GBPS Muhammad Ismail Chandio (2 Add: C.R), GGPS Haji Lal Bux Shaikh (Rehab: 3 Add:), GBPS Usman Kalhoro (4 Add: C.R), GBLSS Sono Jatoi (Rehab:), Taluka Dokri (Electric).

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).					
	(A)	426.00	@ Rs:	910	P.Point	Rs: 387,660.00
	(B)	126.00	@ Rs:	1130	P.Point	Rs: 142,380.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)					
	(A)	104.00	@ Rs:	742	P.Point	Rs: 77,168.00
	(B)	22.00	@ Rs:	985	P.Point	Rs: 21,670.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)					
	(A)	2963	@ Rs:	171	P.Meter	Rs: 506673.0
	(B)	555	@ Rs:	222	P.Meter	Rs: 123210.0
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
	(A)	1077.00	@ Rs:	305	P.Meter	Rs: 328,485.00
	(B)	151.00	@ Rs:	341	P.Meter	Rs: 51,491.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).					
		1157.00	@ Rs:	428	P.Meter	Rs: 495196.0
7	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)					
	(A)	426.00	@ Rs:	54	P.Each	Rs: 23,004.00
	(B)	125.00	@ Rs:	58	P.Each	Rs: 7,250.00
8	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).					
		128.00	@ Rs:	83	P.Each	Rs: 10,624.00
9	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)					
		338.00	@ Rs:	70	P.Each	Rs: 23,660.00
10	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)					
		191.00	@ Rs:	72	P.Each	Rs: 13,752.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).					
		41.00	@ Rs:	162	P.Each	Rs: 6642.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)					
		189.00	@ Rs:	3185	P.No	Rs: 601,965.00
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)					
		143.00	@ Rs:	916	P.No	Rs: 130,988.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).					
		9.00	@ Rs:	9261	P.Each	Rs: 83,349.00
15	Providing & Fixing Circuit breaker 125,150,200,& 225 Amp TP (XS-225NS) on a prepared board as required (S.I.No: 208 P 31).					
		1.00	@ Rs:	25541	P.No	Rs: 25,541.00

Part "A" TOTAL: Rs: 3,060,708.0

SNo:	ITEM OF WORK	Qty:		Rate	Unit	Amount.
------	--------------	------	--	------	------	---------

**Part "B" (Non Schedule Item)**

- |    |   |        |       |         |          |                |
|----|---|--------|-------|---------|----------|----------------|
| 13 | Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)  | 190.00 | @ Rs: | 91      | Each     | Rs: 17,290.00  |
| 14 | Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)   | 190.00 | @ Rs: | 141.71  | P.Each   | Rs: 26,924.90  |
| 17 | P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27). | 12.00  | @ Rs: | 3341    | P.Set    | Rs: 40,092.00  |
| 15 | Providing & Fixing main pannel board double shutter to accommodate heavey duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)  | 17.00  | @ Rs: | 1426.34 | P.Sq.ft: | Rs: 24,247.78  |
| 16 | P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)  | 366.00 | @ Rs: | 497     | P.Each   | Rs: 181,902.00 |
| 18 | P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).  | 38.00  | @ Rs: | 497     | Each     | Rs: 18,886.00  |

Part 'B' TOTAL: Rs: 309,342.7

Part "A" TOTAL: Rs: 3,060,708.0

G: TOTAL: Rs: 3,370,050.7

Say Rs: 3,370,000.0

  
XEN

Name of Work:- Rehabilitation & Expansion of High Priority 4560 Schools (secondary) District Larkana  
(16 Units) (NON-ADP) at: GBHS Model School (EM) Tal: Larkano (Rehab.); GGHS Mahota (Rehab.);  
GBHS Arija Phero (Rehab.); GBHS Lashari Tal: R'Dero (Rehab.; 4 Add.); GBHS Phulpota-I  
(Rehab.); GBHS Masoodero (Rehab.; 1 Add.); GGHS Panjoodero (Rehab.); GBHS Pathan (Rehab.);  
GBHS Khair Muhammad Arija (2 Add: C.R) Taluka Bakrani, ( Electric).

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with (3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	278.00	@ Rs: 910	P.Point	Rs: 252,980.00
	(A)				
	(B)	190.00	@ Rs: 1130	P.Point	Rs: 214,700.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	53.00	@ Rs: 742	P.Point	Rs: 39,326.00
	(A)				
	(B)	37.00	@ Rs: 985	P.Point	Rs: 36,445.00
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	1172	@ Rs: 171	P.Meter	Rs: 200,412.0
	(A)				
	(B)	954	@ Rs: 222	P.Meter	Rs: 211,788.0
5	Providing and laying (Main or sub-Main) PVC insulated with size 2-1.044}(6mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	346.00	@ Rs: 305	P.Meter	Rs: 105,530.00
	(A)				
	(B)	498.00	@ Rs: 341	P.Meter	Rs: 169,818.00
6	Providing and laying (Main or sub-Main) PVC insulated with size 2-1.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	731.00	@ Rs: 428	P.Meter	Rs: 312,868.0
	(A)				
	(B)	108.00	@ Rs: 1300	P.Meter	Rs: 140,400.00
7	Providing and laying (Main or sub-Main) PVC insulated & PVC Sheeted with 4 core Copper conductor in 600/1000 Volts size 16mm2" (S.I.No: 102 P 12).				
8	Providing & Fixing one way S.P 10/15 amps switch surface type (S.I.No: 218 P 33)	279.00	@ Rs: 54	P.Each	Rs: 15,066.00
	(A)				
	(B)	188.00	@ Rs: 58	P.Each	Rs: 10,904.00
9	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33)	90.00	@ Rs: 83	P.Each	Rs: 7,470.00
	(A)				
	(B)	297.00	@ Rs: 70	P.Each	Rs: 20,790.00
9	Providing & Fixing Brass Battern holder. (S.I.No: 232 P 33)				
10	Providing & Fixing Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	156.00	@ Rs: 72	P.Each	Rs: 11,232.00
	(A)				
	(B)	29.00	@ Rs: 162	P.Each	Rs: 4,698.00
11	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33)				
12	Providing and fixing brass ceiling fan 56" (good quality) (S.I.No: 235 P 34)	147.00	@ Rs: 3185	P.No	Rs: 468,195.00
	(A)				
13	Providing & Fixing Circuit breaker 6,10,15,20,30,40,50 & 63 Amps S.P (T B-5S) on prepared board as required. (S.I.No: 203 P 31)	86.00	@ Rs: 916	P.No	Rs: 78,776.00
	(A)				
	(B)	5.00	@ Rs: 9261	P.Each	Rs: 46,305.00
14	Providing & Fixing Circuit breaker 15,20,30,40,50,60,75 & 100 Amp (T P (XS-100 NS) on a prepared board as required (S.I.No: 207 P 31).				
	(A)				
	(B)	1.00	@ Rs: 25541	P.No	Rs: 25,541.00
15	Providing & Fixing Circuit breaker 125,150,200,& 225 Amp TP (XS-225NS) on a prepared board as required (S.I.No: 208 P 31).				

Part "A" TOTAL: Rs: 2,073,244.0

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
------	--------------	------	------	------	---------

**Part "B" (Non Schedule Item)**

- |    |   |        |               |          |                |
|----|---|--------|---------------|----------|----------------|
| 13 | Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 P 14)  | 155.00 | @ Rs: 91      | Each     | Rs: 14,105.00  |
| 14 | Providing and Fixing mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 6 P 14)   | 156.00 | @ Rs: 141.71  | P.Each   | Rs: 22,106.76  |
| 17 | P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth plat,(S.I.No: 1 P 27). | 6.00   | @ Rs: 3341    | P.Set    | Rs: 20,046.00  |
| 15 | Providing & Fixing main pannel board double shutter to accommodate heavy duty circuit breaker bus bar ine painting.(S.I.No: 8 P 13)   | 15.00  | @ Rs: 1426.34 | P.Sq:ft: | Rs: 21,395.10  |
| 16 | P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)  | 312.00 | @ Rs: 497     | P.Each   | Rs: 155,064.00 |
| 18 | P/ F ceiling mounted light fancy type superior quality i/c necessary electric connection an with holder without energy saver etc (S.I.No: 5 P 33).  | 34.00  | @ Rs: 497     | Each     | Rs: 16,898.00  |

**Part "B" TOTAL: Rs: 249,614.9**

**Part "A" TOTAL: Rs: 2,373,244.0**

**G: TOTAL: Rs: 2,622,858.9**

**Say Rs: 2,623,000.0**

