


## BILL OF QUANTITIES / SCHEDULE-B

1- Construction of 2nd Story Hall at Prayer Hall Christian Community K.M.C Compound, Glass Tower Teen Talwar Clifton Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items</b>					
1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structure with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	1237.50	Cft Rs.	3176.25	%0Cft Rs. 3,930.61
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	187.50	Cft Rs.	9416.28	%Cft Rs. 17,655.53
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4"	783.31	Cft Rs.	337.00	P.Cft Rs. 263,976.31
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	41.963	Cwt Rs.	5001.70	P.Cwt Rs. 209,887.19
5	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	397.13	Cft Rs.	11948.36	%Cft Rs. 47,449.92
6	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	825.00	Cft Rs.	1512.50	%0Cft Rs. 1,247.81
7	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	1154.25	Cft Rs.	3630.00	%0Cft Rs. 4,189.93
8	Extra lead 10 miles	1154.25	Cft Rs.	902.20	% Cft Rs. 10,413.64
9	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	192.38	Cft Rs.	8694.25	%Cft Rs. 16,725.56
10	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	495.00	Cft Rs.	12674.36	%Cft Rs. 62,738.08
11	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2373.00	Sft Rs.	2206.06	%Sft Rs. 52,349.80
12	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2373.00	Sft Rs.	2197.52	%Sft Rs. 52,147.15
13	First class deodar wood wrought joinery in doors and windos etcified inosition 1/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4" (C.S.I No:7 (b) P.58).	73.00	Sft. Rs.	1273.76	P. Sft. Rs. 92,984.48
14	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shuttring Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	215.44	Cft Rs.	14429.25	%Cft Rs. 31,086.02
15	Laying Floor of aproved coloured glazed tile 1/4" thick laid in white cement and pigment on a bed of 3/4 thick cement moratr 1:2(S. I No: 60 P-47 )	834.75	Sft Rs.	27747.06	%Sft Rs. 231,618.58

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42) .	544.00	Sft Rs. 3275.50	%Sft Rs.	17,818.72
17	Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	544.00	Sft Rs. 1887.40	%Sft Rs.	10,267.46
18	White wash three coats (C.S.I No:26 (c) P-54).	564.75	Sft Rs. 829.95	%Sft Rs.	4,687.14
19	Paerpairing the Surface and painting with matt finish i/c rubbing the surface with arhy (Slicion Carbide) rubbing brick filling the voids with zink / chalk / plaster of pairs mixture applying first coat premix making the surface smooth an then painting 3	2268.00	Sft Rs. 3444.38	%Sft Rs.	78,118.54
20	French Polishing Complete.(a) One New Work (S.I.No.7 p-71)	146.00	Sft Rs. 3841.75	%Sft Rs.	5,608.96
21	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	4.00	Nos Rs. 261.25	Each Rs.	1,045.00
<b>Total:-</b>					<b>Rs. 1,216,019</b>

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------

## General Abstract

### Composite Schedule Items.

#### (a) Civil Works

(i) Schedule Items Rs. 1,216,019

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Civil Work** Rs.

#### (b) Water Supply & Sanitary Fittings

(i) Schedule Items Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Civil Work** Rs.

### Non-Schedule Item / Item Based Item.


Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Non-Schedule Item** Rs.

**Total Bid Amount** Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

# BILL OF QUANTITIES / SCHEDULE-B

2- Construction of Church Building Gali No. 23/24 Zia Colony Korangi Karachi

S. No.:-	Description.	Quantity.	Rate.	Unit.	Amount.
----------	--------------	-----------	-------	-------	---------

## (a) Civil Works.

### (i) Schedule Items

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structure with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	1237.50	Cft	Rs.	3176.25	%0Cft	Rs.	3,930.61
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	187.50	Cft	Rs.	9416.28	%Cft	Rs.	17,655.53
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4"	783.31	Cft	Rs.	337.00	P.Cft	Rs.	263,976.31
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	41.963	Cwt	Rs.	5001.70	P.Cwt	Rs.	209,887.19
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	397.13	Cft	Rs.	11948.36	%Cft	Rs.	47,449.92
6	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	825.00	Cft	Rs.	1512.50	%0Cft	Rs.	1,247.81
7	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	1154.25	Cft	Rs.	3630.00	%0Cft	Rs.	4,189.93
8	Extra lead 10 miles	1154.25	Cft	Rs.	902.20	% Cft	Rs.	10,413.64
9	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	192.38	Cft	Rs.	8694.25	%Cft	Rs.	16,725.56
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	495.00	Cft	Rs.	12674.36	%Cft	Rs.	62,738.08
11	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2373.00	Sft	Rs.	2206.06	%Sft	Rs.	52,349.80
12	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2373.00	Sft	Rs.	2197.52	%Sft	Rs.	52,147.15
13	First class deodar wood wrought joinery in doors and windos etefied inosition I/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4" (C.S.I No:7 (b) P.58).	73.00	Sft.	Rs.	1273.76	P. Sft.	Rs.	92,984.48
14	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreeegate without shuttring Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	215.44	Cft	Rs.	14429.25	%Cft	Rs.	31,086.02
15	Laying Floor of aproved coloured glazed tile 1/4" thick laid in white cement and pigment on a bed of 3/4 thick cement moratr 1:2(S. I No: 60 P-47 )	834.75	Sft	Rs.	27747.06	%Sft	Rs.	231,618.58



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42) .	544.00 Sft	Rs. 3275.50	%Sft	Rs. 17,818.72
17	Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	544.00 Sft	Rs. 1887.40	%Sft	Rs. 10,267.46
18	White wash three coats (C.S.I No:26 (c) P-54).	564.75 Sft	Rs. 829.95	%Sft	Rs. 4,687.14
19	Paerpairing the Surface and painting with matt finish i/c rubbing the surface with arhy (Slicion Carbide) rubbing brick filling the voids with zink / chalk / plaster of pairs mixture applying first coat premix making the surface smooth an then painting 3	2268.00 Sft	Rs. 3444.38	%Sft	Rs. 78,118.54
20	French Polishing Complete.(a) One New Work (S.I.No.7 p-71)	146.00 Sft	Rs. 3841.75	%Sft	Rs. 5,608.96
21	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	4.00 Nos	Rs. 261.25	Each	Rs. 1,045.00
<b>Total:-</b>					<b>Rs. 1,216,019</b>

Signature of Contractor / Bidder



Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items		Rs.	1,216,019
Add: / Deducted .....	% Above / Below Premium	Rs.	.....
	Total Civil Work	Rs.	

#### (b) Water Supply & Sanitary Fittings


(i) Schdule Items		Rs.	
Add: / Deducted .....	% Above / Below Premium	Rs.	.....
	Total Civil Work	Rs.	

#### Non-Schedule Item / Item Based Item.

		Rs.	
Add: / Deducted .....	% Above / Below Premium	Rs.	.....
	Total Non-Schedule Item	Rs.	

Total Bid Amount	Rs.
------------------	-----

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

3- Construction of Christian Community Center Malir Burf Khana Punjab Para Near Catholic Church  
Malir Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b><u>(a) Civil Works.</u></b>					
<b><u>(i) Schedule Items</u></b>					
1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structure with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	1237.50	Cft Rs. 3176.25	%0Cft Rs.	3,930.61
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	187.50	Cft Rs. 9416.28	%Cft Rs.	17,655.53
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" (C.S.I No: 6 (a) (b) P-17).	783.31	Cft Rs. 337.00	P.Cft Rs.	263,976.31
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	41.963	Cwt Rs. 5001.70	P.Cwt Rs.	209,887.19
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	397.13	Cft Rs. 11948.36	%Cft Rs.	47,449.92
6	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	825.00	Cft Rs. 1512.50	%0Cft Rs.	1,247.81
7	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	1154.25	Cft Rs. 3630.00	%0Cft Rs.	4,189.93
8	Extra lead 10 miles	1154.25	Cft Rs. 902.20	% Cft Rs.	10,413.64
9	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	192.38	Cft Rs. 8694.25	%Cft Rs.	16,725.56
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	495.00	Cft Rs. 12674.36	%Cft Rs.	62,738.08
11	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2373.00	Sft Rs. 2206.06	%Sft Rs.	52,349.80
12	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2373.00	Sft Rs. 2197.52	%Sft Rs.	52,147.15
13	First class deodar wood wrought joinery in doors and windos etcified inosition 1/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4" (C.S.I No:7 (b) P.58).	73.00	Sft. Rs. 1273.76	P. Sft. Rs.	92,984.48
14	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shutting Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	215.44	Cft Rs. 14429.25	%Cft Rs.	31,086.02
15	Laying Floor of aproved coloured glazed tile 1/4" thick laid in white cement and pigment on a bed of 3/4 thick cement moratr 1:2(S. I No: 60 P-47 )	834.75	Sft Rs. 27747.06	%Sft Rs.	231,618.58

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42) .	544.00 Sft	Rs. 3275.50	%Sft	Rs. 17,818.72
17	Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	544.00 Sft	Rs. 1887.40	%Sft	Rs. 10,267.46
18	White wash three coats (C.S.I No:26 (c) P-54).	564.75 Sft	Rs. 829.95	%Sft	Rs. 4,687.14
19	Paerpairing the Surface and painting with matt finish i/c rubbing the surface with arhy (Slicion Carbide) rubbing brick filling the voids with zink / chalk / plaster of pairs mixture applying first coat premix making the surface smooth an then painting 3	2268.00 Sft	Rs. 3444.38	%Sft	Rs. 78,118.54
20	French Polishing Complete.(a) One New Work (S.I.No.7 p-71)	146.00 Sft	Rs. 3841.75	%Sft	Rs. 5,608.96
21	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	4.00 Nos	Rs. 261.25	Each	Rs. 1,045.00
<b>Total:-</b>					<b>Rs. 1,216,019</b>

Signature of Contractor / Bidder



Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------

## General Abstract

### Composite Schedule Items.

#### (a) Civil Works

(i) Schedule Items Rs. 1,216,019

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Civil Work** **Rs.**

#### (b) Water Supply & Sanitary Fittings

(i) Schedule Items Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Civil Work** **Rs.**

### Non-Schedule Item / Item Based Item.


Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Non-Schedule Item** **Rs.**

**Total Bid Amount** **Rs.**

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

# BILL OF QUANTITIES / SCHEDULE-B

4- Construction of Church Building Gali No.07 Essa Nagri Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------


**(a) Civil Works.**

**(i) Schedule Items**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structure with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	1237.50	Cft	Rs.	3176.25	%0Cft	Rs.	3,930.61
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	187.50	Cft	Rs.	9416.28	%Cft	Rs.	17,655.53
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" (C.S.I No: 6 (a) (b) P-17).	783.31	Cft	Rs.	337.00	P.Cft	Rs.	263,976.31
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	41.963	Cwt	Rs.	5001.70	P.Cwt	Rs.	209,887.19
5	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	397.13	Cft	Rs.	11948.36	%Cft	Rs.	47,449.92
6	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	825.00	Cft	Rs.	1512.50	%0Cft	Rs.	1,247.81
7	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	1154.25	Cft	Rs.	3630.00	%0Cft	Rs.	4,189.93
8	Extra lead 10 miles	1154.25	Cft	Rs.	902.20	% Cft	Rs.	10,413.64
9	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	192.38	Cft	Rs.	8694.25	%Cft	Rs.	16,725.56
10	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	495.00	Cft	Rs.	12674.36	%Cft	Rs.	62,738.08
11	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2373.00	Sft	Rs.	2206.06	%Sft	Rs.	52,349.80
12	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2373.00	Sft	Rs.	2197.52	%Sft	Rs.	52,147.15
13	First class deodar wood wrought joinery in doors and windos etcified inosition I/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4" (C.S.I No:7 (b) P.58).	73.00	Sft.	Rs.	1273.76	P. Sft.	Rs.	92,984.48
14	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shuttring Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	215.44	Cft	Rs.	14429.25	%Cft	Rs.	31,086.02
15	Laying Floor of aproved coloured glazed tile 1/4" thick laid in white cement and pigment on a bed of 3/4 thick cement moratr 1:2(S. I No: 60 P-47 )	834.75	Sft	Rs.	27747.06	%Sft	Rs.	231,618.58

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42) .	544.00	Sft Rs. 3275.50	%Sft Rs.	17,818.72
17	Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	544.00	Sft Rs. 1887.40	%Sft Rs.	10,267.46
18	White wash three coats (C.S.I No:26 (c) P-54).	564.75	Sft Rs. 829.95	%Sft Rs.	4,687.14
19	Paerpairing the Surface and painting with matt finish i/c rubbing the surface with arhy (Slicion Carbide) rubbing brick filling the voids with zink / chalk / plaster of pairs mixture applying first coat premix making the surface smooth an then painting 3	2268.00	Sft Rs. 3444.38	%Sft Rs.	78,118.54
20	French Polishing Complete.(a) One New Work (S.I.No.7 p-71)	146.00	Sft Rs. 3841.75	%Sft Rs.	5,608.96
21	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	4.00	Nos Rs. 261.25	Each Rs.	1,045.00
<b>Total:-</b>					<b>Rs. 1,216,019</b>

Signature of Contractor / Bidder

  
**Executive Engineer**  
**Minorities Affairs, Sindh**  
**Hyderabad @ Karachi**



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------

## General Abstract

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,216,019

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Civil Work** **Rs.**

#### (b) Water Supply & Sanitary Fittings

(i) Schdule Items Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Civil Work** **Rs.**

### Non-Schedule Item / Item Based Item.


Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

**Total Non-Schedule Item** **Rs.**

**Total Bid Amount** **Rs.**

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi


# BILL OF QUANTITIES / SCHEDULE-B

5- Construction of Gosphe Church No.12 Azam Basti Karachi

S. No.	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items</b>					
1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structure with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	1237.50	Cft Rs. 3176.25	%0Cft Rs.	3,930.61
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	187.50	Cft Rs. 9416.28	%Cft Rs.	17,655.53
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" (C.S.I No: 6 (a) (b) P-17).	783.31	Cft Rs. 337.00	P.Cft Rs.	263,976.31
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	41.963	Cwt Rs. 5001.70	P.Cwt Rs.	209,887.19
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	397.13	Cft Rs. 11948.36	%Cft Rs.	47,449.92
6	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	825.00	Cft Rs. 1512.50	%0Cft Rs.	1,247.81
7	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	1154.25	Cft Rs. 3630.00	%0Cft Rs.	4,189.93
8	Extra lead 10 miles	1154.25	Cft Rs. 902.20	% Cft Rs.	10,413.64
9	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	192.38	Cft Rs. 8694.25	%Cft Rs.	16,725.56
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	495.00	Cft Rs. 12674.36	%Cft Rs.	62,738.08
11	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2373.00	Sft Rs. 2206.06	%Sft Rs.	52,349.80
12	Cement plaster upto 20' height 3/8" thick ratio 1:4 (C.S.I No: 11 (a) Page No: 52).	2373.00	Sft Rs. 2197.52	%Sft Rs.	52,147.15
13	First class deodar wood wrought joinery in doors and windos etcified inosition l/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4" (C.S.I No:7 (b) P.58).	73.00	Sft. Rs. 1273.76	P. Sft. Rs.	92,984.48
14	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreeegate without shuttering Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	215.44	Cft Rs. 14429.25	%Cft Rs.	31,086.02
15	Laying Floor of aproved coloured glazed tile 1/4" thick laid in white cement and pigment on a bed of 3/4 thick cement moratr 1:2(S. I No: 60 P-47 )	834.75	Sft Rs. 27747.06	%Sft Rs.	231,618.58

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42) .	544.00	Sft Rs. 3275.50	%Sft Rs.	17,818.72
17	Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	544.00	Sft Rs. 1887.40	%Sft Rs.	10,267.46
18	White wash three coats (C.S.I No:26 (c) P-54).	564.75	Sft Rs. 829.95	%Sft Rs.	4,687.14
19	Paerpairing the Surface and painting with matt finish i/c rubbing the surface with arhy (Slicion Carbide) rubbing brick filling the voids with zink / chalk / plaster of pairs mixture applying first coat premix making the surface smooth an then painting 3	2268.00	Sft Rs. 3444.38	%Sft Rs.	78,118.54
20	French Polishing Complete.(a) One New Work (S.I.No.7 p-71)	146.00	Sft Rs. 3841.75	%Sft Rs.	5,608.96
21	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	4.00	Nos Rs. 261.25	Each Rs.	1,045.00
<b>Total:-</b>					<b>Rs. 1,216,019</b>

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items		Rs.	1,216,019
Add: / Deducted .....	% Above / Below Premium	Rs.	.....
	Total Civil Work	Rs.	


#### (b) Water Supply & Sanitary Fittings

(i) Schdule Items		Rs.	
Add: / Deducted .....	% Above / Below Premium	Rs.	.....
	Total Civil Work	Rs.	

#### Non-Schedule Item / Item Based Item.

		Rs.	
Add: / Deducted .....	% Above / Below Premium	Rs.	.....
	Total Non-Schedule Item	Rs.	
	Total Bid Amount	Rs.	

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

# HP LaserJet Pro MFP M127fn

## Web Services

### Enable HP Web Services

NOTE: HP Web Services requires the printer to be connected to a network.

1. Once the printer is connected to a network, enter the printer's network IP address into a Web browser. To find the printer's IP address, refer to the printer's user guide, or reprint this page after the printer is connected to the network.
2. On the Web page that appears, click on the HP Web Services tab.
3. Review and accept the terms of use, and then click the Enable button.

### HP ePrint

#### Print from Anywhere

HP's free ePrint service provides an easy way to print from e-mail, anywhere and anytime. Simply attach a file to an e-mail, and send it to this printer's e-mail address. The attachment will print automatically on this printer. Supported attachment file types include .pdf, .jpg, .tif, and Microsoft Office(R) documents.

NOTE: Attachments may print differently than they appear in the software program which created them depending on the original fonts and layout options used.

#### Your Printer is Protected

To help prevent unauthorized e-mail, HP assigns a random e-mail address to your printer, never publicizes this address, and by default does not respond to any sender. ePrint also provides industry-standard spam filtering and transforms e-mail and attachments to a print-only format to reduce the threat of a virus or other harmful content.

NOTE: The ePrint service does not filter e-mails based on content, so it cannot prevent objectionable or copyrighted material from being printed.

### HP Connected

#### Use the HP Connected Web Site

Use HP's free HP Connected Web site to set up increased security for ePrint, specify the e-mail addresses that are allowed to send e-mail to your printer, get Print Apps (if available for your product), and access other free services.

Go to the HP Connected Web site for more information and specific terms and conditions:  
<http://www.hpconnected.com>

## BILL OF QUANTITIES / SCHEDULE-B


6- Repair of Christian Graveyard Gulshan Colony Ring Road Near Jarwari Taluka & District Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	3125.00	Cft Rs.	3176.25 %0Cft Rs.	9,925.78
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	731.25	Cft Rs.	9416.28 %Cft Rs.	68,856.55
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	903.88	Cft Rs.	337.00 P.Cft Rs.	304,607.56
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	53.264	Cwt Rs.	5001.70 P.Cwt Rs.	266,410.55
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (e) P.21).	1246.88	Cft Rs.	11948.36 %Cft Rs.	148,981.71
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	2083.33	Cft Rs.	1512.50 %0Cft Rs.	3,151.04
7	Pacca brick work other than building in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	1312.50	Cft Rs.	12346.65 %Cft Rs.	162,049.78
8	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	4200.00	Sft Rs.	2206.60 %Sft Rs.	92,677.20
9	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3500.00	Sft Rs.	2197.52 %Sft Rs.	76,913.20
10	P/L Halla pattern tiles glazed 6" x 6" x 1/4" of floor of walls facing required pattern stile specification jointed in white cement and pigment over a bases 1:2 grey cement mortar 3/4" thick i/c washing & filling of joints with slurry of white cement & pigment in desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tiles to proper profile. (C.S.I No: 61 P-48 )	670.00	Sft Rs.	47651.56 %Sft Rs.	319,265.45
11	Making & Fixing Steel Grated Door Complete with locking arrangements angle iron frame 2"x2" 3/8" and 3/4" sq bars 4" center to center (C.S.I No:23 P-92).	128.00	Sft Rs.	726.72 P. Sft. Rs.	93,020.16
12	Primary coat of chalk under duster (C.S.I No:23 P-54).	3500.00	Sft Rs.	442.75 %Sft Rs.	15,496.25
13	Distemper. Three coat (CSI No. 24 (c) Page No. 54)	3500.00	Sft. Rs.	1079.65 %Sft Rs.	37,787.75

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
14	Painting new surfaces (c) Preparing surfaces and painting of doors and windows any type (including edges). (S.I.No.5-c P-70).	256.00	Sft Rs. 2116.41	%Sft Rs.	5,418.01

**Total:- Rs. 1604536**

**Signature of Contractor / Bidder**



**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,604,536

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

7- Construction of Temple Bheel Para, Gul Hassan Taluka Shujaabad District Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	1220.00	Cft Rs. 3176.25	%0Cft Rs.	3,875.03
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	152.50	Cft Rs. 9416.28	%Cft Rs.	14,359.83
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	614.25	Cft Rs. 11948.36	%Cft Rs.	73,392.80
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	329.06	Cft Rs. 337.00	P.Cft Rs.	110,893.22
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	23.504	Cwt Rs. 5001.70	P.Cwt Rs.	117,559.96
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	813.33	Cft Rs. 1512.50	%0Cft Rs.	1,230.16
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	2849.00	Cft Rs. 3630.00	%0Cft Rs.	10,341.87
8	Extra Lead 10 miles	2849.00	Sft Rs. 902.20	%Sft Rs.	25,703.68
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	581.13	Cft Rs. 8694.95	%Cft Rs.	50,528.96
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	939.00	Cft Rs. 12674.36	%Cft Rs.	119,012.24
11	S/F Girder at Site of Work	17.500	Cwt Rs. 3850.00	P.Cwt Rs.	67,375.00
12	S/F T-Iron at Site of Work	11.250	Cwt Rs. 3575.00	P.Cwt Rs.	40,218.75
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	1600.00	Sft Rs. 7607.25	%Sft Rs.	121,716.00
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1600.00	Sft Rs. 10.70	P. Sft Rs.	17,120.00
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	3276.00	Sft Rs. 2206.60	%Sft Rs.	72,288.22

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3276.00	Sft Rs. 2197.52	%Sft Rs.	71,990.76
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs. 240.50	P.Rft Rs.	23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (h) / P-58).	130.95	Sft. Rs. 902.93	P. Sft. Rs.	118,238.68
20	Primary coat of chalk under destember (C.S.I No:23 P.	3276.00	Sft Rs. 442.75	%Sft Rs.	14,504.49
21	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3276.00	Sft. Rs. 1079.65	%Sft Rs.	35,369.33
22	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	712.25	Sft Rs. 829.95	%Sft Rs.	5,911.32
23	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	304.00	Sft. Rs. 2116.41	%Sft Rs.	6,433.89
24	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	630.00	Sft Rs. 1270.83	%Sft Rs.	8,006.23
<b>Total:-</b>					<b>Rs. 1137398</b>


**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

1162.25 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:- Rs.**

**Signature of Contractor / Bidder**

  
**Executive Engineer**  
**Minorities Affairs, Sindh**  
**Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>General Abstract</b>					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,137,398

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

**Total Civil Work** Rs.

#### Non-Schedule Item / Item Based Item.

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


**Total Non-Schedule Item** Rs.

---

**Total Bid Amount** Rs.

---

Signature of Contractor / Bidder

  
**Executive Engineer**  
**Minorities Affairs, Sindh**  
**Hyderabad @ Karachi**

## BILL OF QUANTITIES / SCHEDULE-B

8- Construction of Hanuman Temple Jamanshah Para Bhagat Valuram Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	1220.00	Cft Rs.	3176.25 %0Cft Rs.	3,875.03
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	152.50	Cft Rs.	9416.28 %Cft Rs.	14,359.83
3	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	614.25	Cft Rs.	11948.36 %Cft Rs.	73,392.80
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	329.06	Cft Rs.	337.00 P.Cft Rs.	110,893.22
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	23.504	Cwt Rs.	5001.70 P.Cwt Rs.	117,559.96
6	Filling Watering & Ramming Earth in Floor with Surplus Eartch from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	813.33	Cft Rs.	1512.50 %0Cft Rs.	1,230.16
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	2849.00	Cft Rs.	3630.00 %0Cft Rs.	10,341.87
8	Extra Lead 10 miles	2849.00	Sft Rs.	902.20 %Sft Rs.	25,703.68
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	581.13	Cft Rs.	8694.95 %Cft Rs.	50,528.96
10	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	939.00	Cft Rs.	12674.36 %Cft Rs.	119,012.24
11	S/F Girder at Site of Work	17.500	Cwt Rs.	3850.00 P.Cwt Rs.	67,375.00
12	S/F T-Iron at Site of Work	11.250	Cwt Rs.	3575.00 P.Cwt Rs.	40,218.75
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortor including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	1600.00	Sft Rs.	7607.25 %Sft Rs.	121,716.00
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1600.00	Sft Rs.	10.70 P. Sft Rs.	17,120.00
15	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	3276.00	Sft Rs.	2206.60 %Sft Rs.	72,288.22

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3276.00	Sft Rs. 2197.52	%Sft Rs.	71,990.76
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs. 240.50	P.Rft Rs.	23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	130.95	Sft. Rs. 902.93	P. Sft. Rs.	118,238.68
20	Primary coat of chalk under destember (C.S.I No:23 P.	3276.00	Sft Rs. 442.75	%Sft Rs.	14,504.49
21	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3276.00	Sft. Rs. 1079.65	%Sft Rs.	35,369.33
22	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	712.25	Sft Rs. 829.95	%Sft Rs.	5,911.32
23	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	304.00	Sft. Rs. 2116.41	%Sft Rs.	6,433.89
24	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	630.00	Sft Rs. 1270.83	%Sft Rs.	8,006.23
<b>Total:-</b>					<b>Rs. 1137398</b>

**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

1162.25 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:- Rs.**

**Signature of Contractor / Bidder**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,137,398

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi



## BILL OF QUANTITIES / SCHEDULE-B

9- Construction of Boundary Wall of Masihi Qabristan Near Children Shamshanghat Colony UC-2  
Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	5000.00	Cft Rs.	3176.25	%0Cft Rs. 15,881.25
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	1200.00	Cft Rs.	9416.28	%Cft Rs. 112,995.36
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	1325.75	Cft Rs.	337.00	P.Cft Rs. 446,777.75
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	71.022	Cwt Rs.	5001.70	P.Cwt Rs. 355,230.74
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	2137.50	Cft Rs.	11948.36	%Cft Rs. 255,396.20
6	Filling Watering & Ramming Earth in Floor with Surplus Eartch from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	3333.33	Cft Rs.	1512.50	%0Cft Rs. 5,041.66
7	Pacca brick work other than building in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	2250.00	Cft Rs.	12346.65	%Cft Rs. 277,799.63
8	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	7200.00	Sft Rs.	2206.60	%Sft Rs. 158,875.20
9	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	6000.00	Sft Rs.	2197.52	%Sft Rs. 131,851.20
10	P/L Halla pattern tiles glazed 6" x 6" x 1/4" of floor of walls facing required pattern stile specification jointed in white cement and pigment over a bazes 1:2 gra y cement mortar 3/4" thick I/c washing & filling of joints with sullury of white cement & pigment in desire shape with finishing cleaning and cost of wax polish etc complete i/c cutting tiles to proper profile. (C.S.I No: 61 P-48 )	920.00	Sft Rs.	47651.56	%Sft Rs. 438,394.35
11	Making & Fixing Steel Grated Door Complete with locking arrangments angel iron frame 2"x2" 3/8" and 3/4" sq bars 4" center to center (C.S.I No:23 P-92).	128.00	Sft Rs.	726.72	P. Sft. Rs. 93,020.16
12	Primary coat of chalk under destember (C.S.I No:23 P. 54).	6000.00	Sft Rs.	442.75	%Sft Rs. 26,565.00
13	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	6000.00	Sft. Rs.	1079.65	%Sft Rs. 64,779.00

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
14	Painting new surfaces (c) Preparing surfaces and painting of doors and windows any type (including edges). (S.I.No.5-c P-70).	256.00	Sft Rs. 2116.41	%Sft Rs.	5,418.01

**Total:-**

**Rs. 2387988**

**Signature of Contractor / Bidder**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>General Abstract</b>					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 2,387,988

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

**Total Civil Work** Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


**Total Non-Schedule Item** Rs.

---

**Total Bid Amount** Rs.

---

Signature of Contractor / Bidder

  
**Executive Engineer**  
**Minorities Affairs, Sindh**  
**Hyderabad @ Karachi**

# BILL OF QUANTITIES / SCHEDULE-B

10- Construction of Temple Village Kachi Paro Dhamon Kolhi Deh Phadro UC Dalutpur Taluka Shujaabad  
Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:-	1730.00	Cft Rs.	3176.25	%0Cft Rs. 5,494.91
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	216.25	Cft Rs.	9416.28	%Cft Rs. 20,362.71
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	858.38	Cft Rs.	11948.36	%Cft Rs. 102,562.33
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4)	490.50	Cft Rs.	337.00	P.Cft Rs. 165,298.50
5	90 Lbs Cement 2 Cft Sand 4 Cft Shingle 1/8" to 1/4" Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	35.036	Cwt Rs.	5001.70	P.Cwt Rs. 175,239.56
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	1153.33	Cft Rs.	1512.50	%0Cft Rs. 1,744.41
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	3137.00	Cft Rs.	3630.00	%0Cft Rs. 11,387.31
8	Extra Lead 10 miles	3137.00	Sft Rs.	902.20	%Sft Rs. 28,302.01
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	1092.13	Cft Rs.	8694.95	%Cft Rs. 94,960.16
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	1086.00	Cft Rs.	12674.36	%Cft Rs. 137,643.55
11	S/F Girder at Site of Work	17.500	Cwt Rs.	3850.00	P.Cwt Rs. 67,375.00
12	S/F T-Iron at Site of Work	13.254	Cwt Rs.	3575.00	P.Cwt Rs. 47,383.05
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing	1771.00	Sft Rs.	7607.25	%Sft Rs. 134,724.40
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1771.00	Sft Rs.	10.70	P. Sft. Rs. 18,949.70
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	3906.00	Sft Rs.	2206.60	%Sft Rs. 86,189.80
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3631.50	Sft Rs.	2197.52	%Sft Rs. 79,802.94

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	69.00	Rft Rs.	228.90	P.Rft Rs. 15,794.10
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs.	240.50	P.Rft Rs. 23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick	160.59	Sft. Rs.	902.93	P. Sft. Rs. 145,001.53
20	Laying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I.No. 24 P-43)	72.00	Sft Rs.	27678.86	%Sft Rs. 19,928.78
21	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick including finishing (S.I.No. 37 P-45)	301.00	Sft. Rs.	28253.61	%Sft Rs. 85,043.37
22	Primary coat of chalk under destember (C.S.I No:23 P-	3631.50	Sft Rs.	442.75	%Sft Rs. 16,078.47
23	Distemper. Three coat (CSI No. 24 (c) Page No. 54)	3631.50	Sft. Rs.	1079.65	%Sft Rs. 39,207.49
24	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	784.25	Sft Rs.	829.95	%Sft Rs. 6,508.88
25	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	374.00	Sft. Rs.	2116.41	%Sft Rs. 7,915.37
26	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	679.88	Sft Rs.	1270.83	%Sft Rs. 8,640.12

**Total:-**

**Rs. 1544622**

**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

2112.25 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:-**

**Rs.**

**Signature of Contractor / Bidder**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------

**(b) Water Supply & Sanitary Fittings.**

**(i) Schedule Items.**

1	Providing & fixing squatting type white glazed of flush cistern with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumb. (S.I No:1 (b) i P-No:1)	2.00	Nos.	Rs.	4802.60	Each	Rs.	9,605.20
2	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & l/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or c.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	2.00	Nos.	Rs.	4253.70	Each	Rs.	8,507.40
3	Add: extra labour for providing and fixing of earthen wire pedestal white or colored glass standard pattern (S.I No:9 P-No:3).	2.00	Nos.	Rs.	938.47	Each	Rs.	1,876.94
4	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	2.00	Nos.	Rs.	447.15	Each	Rs.	894.30
5	P/F 6" x 4" c.c gully trap with 4" dia out let complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb c.I casing 6" x 6" and c.I cover and frame 12" x 12" in side etc complete. (S.I No:1(a-i) P-No:21).	2.00	Nos.	Rs.	1193.17	Each	Rs.	2,386.34
6	RCC pipe with collar class "B" and bedding the tranches to the required depth and fixing in position l/c cutting fitting and jointing with max phalt composition and cement mortar 1:1 and testing with water pressure to head of 4 Ft above the top of the height	20.00	Rft	Rs.	146.57	P.Rft	Rs.	2,931.40
	4" dia	20.00	Rft	Rs.	199.25	P.Rft	Rs.	3,985.00
7	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & l/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	2.00	Nos.	Rs.	2042.43	Each	Rs.	4,084.86
8	Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking through walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zinc paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (S.I No. 1 Page No.12)							

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
i	1/2" dia	20.00 Rft	Rs. 73.21	P.Rft	Rs. 1,464.20
ii	3/4" dia	20.00 Rft	Rs. 95.79	P.Rft	Rs. 1,915.80
iii	1" dia	20.00 Rft	Rs. 128.55	P.Rft	Rs. 2,571.00
vi	1-1/4" dia	20.00 Rft	Rs. 153.19	P.Rft	Rs. 3,063.80
9	Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement motor etc Complete				
	1/2" dia	20.00 Rft	Rs. 7.82	P.Rft	Rs. 156.40
	3/4" dia	20.00 Rft	Rs. 8.45	P.Rft	Rs. 169.00
10	Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standard pattern (Note standard Manufacture by M/S Anwar Mechanical works. (S.I No:4 (b) P-No:17).				
	1/2" dia	2.00 Nos.	Rs. 161.92	Each	Rs. 323.84
	3/4 dia	2.00 Nos.	Rs. 227.92	Each	Rs. 455.84
11	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	2.00 Nos.	Rs. 478.28	Each	Rs. 956.56
12	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	2.00 Nos.	Rs. 1109.46	Each	Rs. 2,218.92
13	S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2.00 Nos.	Rs. 2882.00	Each	Rs. 5,764.00
14	S/F Swan type Pillars Cock of supreior quality with arvstal Head.	2.00 Nos.	Rs. 795.30	Each	Rs. 1,590.60
15	Supplying & fixing Bath room accessories set (7 pieces l/c towel rod, brush hloder, soap tray, shelf of approved quality and design etc complete. (Si No: 22 P-No:19)	2.00 Nos.	Rs. 8122.40	Each	Rs. 16,244.80
16	P/F handle values (China) (S.I No:7 P-No:14).				
i	1/2" dia	2.00 Nos.	Rs. 271.92	Each	Rs. 543.84
ii	3/4" dia	2.00 Nos.	Rs. 365.42	Each	Rs. 730.84
17	Supplying & fixing fibre glass tank of approved quality and design and wall thicness as specified l/c cost of nutes, bolts and fixing in plateform of cement concreete 1: 3: 6 and makin connections for in -let ,& ou-let & over flow pipes etc. complete.				
A	250 Gallons	1.00 Nos.	Rs. 21989.61	Each	Rs. 21,989.61

**Total:- Rs. 94430**

**Contractor**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,544,622

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### (b) Water Supply & Sanitary Fittings

(i) Schdule Items Rs. 94,430

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

### Non-Schedule Item / Item Based Item.

Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

11- Construction of Temple Village Krishan Bhagat Taluka & District Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:-	1730.00	Cft Rs.	3176.25	%0Cft Rs. 5,494.91
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	216.25	Cft Rs.	9416.28	%Cft Rs. 20,362.71
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	858.38	Cft Rs.	11948.36	%Cft Rs. 102,562.33
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4)	490.50	Cft Rs.	337.00	P.Cft Rs. 165,298.50
5	90 lbs Cement 2 Cft Sand 4 Cft Shingle 1/8" to 1/4" Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	35.036	Cwt Rs.	5001.70	P.Cwt Rs. 175,239.56
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	1153.33	Cft Rs.	1512.50	%0Cft Rs. 1,744.41
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	3137.00	Cft Rs.	3630.00	%0Cft Rs. 11,387.31
8	Extra Lead 10 miles	3137.00	Sft Rs.	902.20	%Sft Rs. 28,302.01
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	1092.13	Cft Rs.	8694.95	%Cft Rs. 94,960.16
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	1086.00	Cft Rs.	12674.36	%Cft Rs. 137,643.55
11	S/F Girder at Site of Work	17.500	Cwt Rs.	3850.00	P.Cwt Rs. 67,375.00
12	S/F T-Iron at Site of Work	13.254	Cwt Rs.	3575.00	P.Cwt Rs. 47,383.05
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing	1771.00	Sft Rs.	7607.25	%Sft Rs. 134,724.40
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1771.00	Sft Rs.	10.70	P. Sft. Rs. 18,949.70
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	3906.00	Sft Rs.	2206.60	%Sft Rs. 86,189.80
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3631.50	Sft Rs.	2197.52	%Sft Rs. 79,802.94

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	69.00	Rft Rs.	228.90	P.Rft Rs. 15,794.10
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs.	240.50	P.Rft Rs. 23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick	160.59	Sft. Rs.	902.93	P. Sft. Rs. 145,001.53
20	Laying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I.No. 24 P-43)	72.00	Sft Rs.	27678.86	%Sft Rs. 19,928.78
21	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick including finishing (S.I.No. 37 P-45)	301.00	Sft. Rs.	28253.61	%Sft Rs. 85,043.37
22	Primary coat of chalk under destember (C.S.I No:23 P.	3631.50	Sft Rs.	442.75	%Sft Rs. 16,078.47
23	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3631.50	Sft. Rs.	1079.65	%Sft Rs. 39,207.49
24	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	784.25	Sft Rs.	829.95	%Sft Rs. 6,508.88
25	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	374.00	Sft. Rs.	2116.41	%Sft Rs. 7,915.37
26	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	679.88	Sft Rs.	1270.83	%Sft Rs. 8,640.12

**Total:-**

**Rs. 1544622**

**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

2112.25 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:-**

**Rs.**

**Signature of Contractor / Bidder**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------

**(b) Water Supply & Sanitary Fittings.**

**(i) Schedule Items.**

1	Providing & fixing squatting type white glazed of flush cistern with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumb. (S.I No:1 (b) i P-No:1)	2.00	Nos.	Rs.	4802.60	Each	Rs.	9,605.20
2	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & I/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or c.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	2.00	Nos.	Rs.	4253.70	Each	Rs.	8,507.40
3	Add: extra labour for providing and fixing of earthen wire pedestal white or colored glass standard pattern (S.I No:9 P-No:3).	2.00	Nos.	Rs.	938.47	Each	Rs.	1,876.94
4	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	2.00	Nos.	Rs.	447.15	Each	Rs.	894.30
5	P/F 6" x 4" c.c gully trap with 4" dia outlet complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb c.I casing 6" x 6" and c.I cover and frame 12" x 12" in side etc complete. (S.I No:1(a-i) P-No:21).	2.00	Nos.	Rs.	1193.17	Each	Rs.	2,386.34
6	RCC pipe with collar class "B" and dipping the tranches to the required depth and fixing in position I/c cutting fitting and jointing with max phalt composition and cement mortar 1:1 and testing with water pressure to head of 4 Ft above the top of the height	20.00	Rft	Rs.	146.57	P.Rft	Rs.	2,931.40
	4" dia	20.00	Rft	Rs.	199.25	P.Rft	Rs.	3,985.00
	6" dia							
7	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & I/c making requisite number of holes in walls, plinth & floor for pipe connections & making good cement concrete 1:2:4. (S.I No. 20 Page No.3).	2.00	Nos.	Rs.	2042.43	Each	Rs.	4,084.86
8	Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and I/c the cost of breaking through walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zinc paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)							

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
i	1/2" dia	20.00 Rft	Rs. 73.21	P.Rft	Rs. 1,464.20
ii	3/4" dia	20.00 Rft	Rs. 95.79	P.Rft	Rs. 1,915.80
iii	1" dia	20.00 Rft	Rs. 128.55	P.Rft	Rs. 2,571.00
vi	1-1/4" dia	20.00 Rft	Rs. 153.19	P.Rft	Rs. 3,063.80
9	Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement motor etc Complete				
	1/2" dia	20.00 Rft	Rs. 7.82	P.Rft	Rs. 156.40
	3/4" dia	20.00 Rft	Rs. 8.45	P.Rft	Rs. 169.00
10	Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standard pattern (Note standard Manufacture by M/S Anwar Mechanical works. (S.I No:4 (b) P-No:17).				
	1/2" dia	2.00 Nos.	Rs. 161.92	Each	Rs. 323.84
	3/4 dia	2.00 Nos.	Rs. 227.92	Each	Rs. 455.84
11	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	2.00 Nos.	Rs. 478.28	Each	Rs. 956.56
12	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	2.00 Nos.	Rs. 1109.46	Each	Rs. 2,218.92
13	S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2.00 Nos.	Rs. 2882.00	Each	Rs. 5,764.00
14	S/F Swan type Pillars Cock of supreior quality with arvstal Head.	2.00 Nos.	Rs. 795.30	Each	Rs. 1,590.60
15	Supplying & fixing Bath room accessories set (7 pieces i/c towel rod, brush hloder, soap tray, shelf of approved quality and design etc complete. (Si No: 22 P-No:19)	2.00 Nos.	Rs. 8122.40	Each	Rs. 16,244.80
16	P/F handle valves (China) (S.I No:7 P-No:14).				
i	1/2" dia	2.00 Nos.	Rs. 271.92	Each	Rs. 543.84
ii	3/4" dia	2.00 Nos.	Rs. 365.42	Each	Rs. 730.84
17	Supplying & fixing fibre glass tank of approved quality and design and wall thickness as specified i/c cost of nutes, bolts and fixing in plateform of cement concrete 1: 3: 6 and makin connections for in -let ,& ou-let & over flow pipes etc. complete.				
A	250 Gallons	1.00 Nos.	Rs. 21989.61	Each	Rs. 21,989.61

**Total:-**

**Rs. 94430**

**Contractor**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,544,622

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### (b) Water Supply & Sanitary Fittings

(i) Schdule Items Rs. 94,430

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

12- Construction of Boundary Wall Children Shamshanghat Majhar Colony UC-II Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	3125.00	Cft Rs.	3176.25 %0Cft Rs.	9,925.78
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	731.25	Cft Rs.	9416.28 %Cft Rs.	68,856.55
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	903.88	Cft Rs.	337.00 P.Cft Rs.	304,607.56
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	53.264	Cwt Rs.	5001.70 P.Cwt Rs.	266,410.55
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	1246.88	Cft Rs.	11948.36 %Cft Rs.	148,981.71
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	2083.33	Cft Rs.	1512.50 %0Cft Rs.	3,151.04
7	Pacca brick work other than building in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	1312.50	Cft Rs.	12346.65 %Cft Rs.	162,049.78
8	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	4200.00	Sft Rs.	2206.60 %Sft Rs.	92,677.20
9	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3500.00	Sft Rs.	2197.52 %Sft Rs.	76,913.20
10	P/L Halla pattern tiles glazed 6" x 6" x 1/4" of floor of walls facing required pattern stile specification jointed in white cement and pigment over a bases 1:2 gra y cement mortar 3/4" thick I/c washing & filling of joints with sullury of white cement & pigment in desire shape with finishing cleaning and cost of wax polish etc complete i/c cutting tiles to proper profile. (C.S.I No: 61 P-48 )	670.00	Sft Rs.	47651.56 %Sft Rs.	319,265.45
11	Making & Fixing Steel Grated Door Complete with locking arrangements angel iron frame 2"x2" 3/8" and 3/4" sq bars 4" center to center (C.S.I No:23 P-92).	128.00	Sft Rs.	726.72 P. Sft Rs.	93,020.16
12	Primary coat of chalk under destember (C.S.I No:23 P-54).	3500.00	Sft Rs.	442.75 %Sft Rs.	15,496.25
13	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3500.00	Sft Rs.	1079.65 %Sft Rs.	37,787.75



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
14	Painting new surfaces (c) Preparing surfaces and painting of doors and windows any type (including edges). (S.I.No.5-c P-70).	256.00	Sft Rs. 2116.41	%Sft Rs.	5,418.01

**Total:-**

**Rs. 1604536**

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>General Abstract</b>					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,604,536

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
**Executive Engineer**  
**Minorities Affairs, Sindh**  
**Hyderabad @ Karachi**

## BILL OF QUANTITIES / SCHEDULE-B

13- Construction of Prayer Hall/ Community Center Christian Colony Sheet Form Road Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:-	1730.00	Cft Rs.	3176.25	%0Cft Rs. 5,494.91
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	216.25	Cft Rs.	9416.28	%Cft Rs. 20,362.71
3	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	858.38	Cft Rs.	11948.36	%Cft Rs. 102,562.33
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4)	490.50	Cft Rs.	337.00	P.Cft Rs. 165,298.50
5	901 lb Cement 2 Cft Sand 4 Cft Shingle 1/8" to 1/4" Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	31.094	Cwt Rs.	5001.70	P.Cwt Rs. 155,522.86
6	Filling Watering & Ramming Earth in Floor with Surplus Eartch from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	1153.33	Cft Rs.	1512.50	%0Cft Rs. 1,744.41
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	3137.00	Cft Rs.	3630.00	%0Cft Rs. 11,387.31
8	Extra Lead 10 miles	3137.00	Sft Rs.	902.20	%Sft Rs. 28,302.01
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	692.13	Cft Rs.	8694.95	%Cft Rs. 60,180.36
10	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	1086.00	Cft Rs.	12674.36	%Cft Rs. 137,643.55
11	S/F Girder at Site of Work	17.500	Cwt Rs.	3850.00	P.Cwt Rs. 67,375.00
12	S/F T-Iron at Site of Work	13.254	Cwt Rs.	3575.00	P.Cwt Rs. 47,383.05
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortor including 1:2 cement pointing	1771.00	Sft Rs.	7607.25	%Sft Rs. 134,724.40
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1771.00	Sft Rs.	10.70	P. Sft. Rs. 18,949.70
15	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	3906.00	Sft Rs.	2206.60	%Sft Rs. 86,189.80
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3631.50	Sft Rs.	2197.52	%Sft Rs. 79,802.94

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	69.00	Rft Rs.	228.90	P.Rft Rs. 15,794.10
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs.	240.50	P.Rft Rs. 23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	160.59	Sft. Rs.	902.93	P. Sft. Rs. 145,001.53
20	Laying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I.No. 24 P-43)	72.00	Sft Rs.	27678.86	%Sft Rs. 19,928.78
21	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick including finishing (S.I.No. 37 P-45)	301.00	Sft. Rs.	28253.61	%Sft Rs. 85,043.37
22	Primary coat of chalk under destember (C.S.I No:23 P.	3631.50	Sft Rs.	442.75	%Sft Rs. 16,078.47
23	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3631.50	Sft. Rs.	1079.65	%Sft Rs. 39,207.49
24	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	784.25	Sft Rs.	829.95	%Sft Rs. 6,508.88
25	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	374.00	Sft. Rs.	2116.41	%Sft Rs. 7,915.37
26	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	679.88	Sft Rs.	1270.83	%Sft Rs. 8,640.12

**Total:-**

**Rs. 1490128**

**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

1312.25 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:-**

**Rs.**

**Signature of Contractor / Bidder**

**Executive Engineer**  
**Minorities Affairs, Sindh**  
**Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,490,128

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

14- Repair / Renovation of 7th Day Church Near Lachan Bagh Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	1220.00	Cft Rs.	3176.25	%0Cft Rs. 3,875.03
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	152.50	Cft Rs.	9416.28	%Cft Rs. 14,359.83
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (e) P.21).	614.25	Cft Rs.	11948.36	%Cft Rs. 73,392.80
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	329.06	Cft Rs.	337.00	P.Cft Rs. 110,893.22
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	23.504	Cwt Rs.	5001.70	P.Cwt Rs. 117,559.96
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	813.33	Cft Rs.	1512.50	%0Cft Rs. 1,230.16
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	2849.00	Cft Rs.	3630.00	%0Cft Rs. 10,341.87
8	Extra Lead 10 miles	2849.00	Sft Rs.	902.20	%Sft Rs. 25,703.68
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	581.13	Cft Rs.	8694.95	%Cft Rs. 50,528.96
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	939.00	Cft Rs.	12674.36	%Cft Rs. 119,012.24
11	S/F Girder at Site of Work	17.500	Cwt Rs.	3850.00	P.Cwt Rs. 67,375.00
12	S/F T-Iron at Site of Work	11.250	Cwt Rs.	3575.00	P.Cwt Rs. 40,218.75
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	1600.00	Sft Rs.	7607.25	%Sft Rs. 121,716.00
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1600.00	Sft Rs.	10.70	P. Sft. Rs. 17,120.00
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	3276.00	Sft Rs.	2206.60	%Sft Rs. 72,288.22

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3276.00	Sft Rs. 2197.52	%Sft Rs.	71,990.76
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs. 240.50	P.Rft Rs.	23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	130.95	Sft. Rs. 902.93	P. Sft. Rs.	118,238.68
20	Primary coat of chalk under destember (C.S.I No:23 P.	3276.00	Sft Rs. 442.75	%Sft Rs.	14,504.49
21	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3276.00	Sft. Rs. 1079.65	%Sft Rs.	35,369.33
22	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	712.25	Sft Rs. 829.95	%Sft Rs.	5,911.32
23	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	304.00	Sft. Rs. 2116.41	%Sft Rs.	6,433.89
24	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	630.00	Sft Rs. 1270.83	%Sft Rs.	8,006.23
<b>Total:-</b>					<b>Rs. 1137398</b>

**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

1162.25 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:- Rs.**

**Signature of Contractor / Bidder**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,137,398

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi



## BILL OF QUANTITIES / SCHEDULE-B

15- Construction of Krishan Koli Mandir Mali Colony Deh 110 Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	1220.00	Cft Rs.	3176.25 %0Cft Rs.	3,875.03
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	152.50	Cft Rs.	9416.28 %Cft Rs.	14,359.83
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (e) P.21).	614.25	Cft Rs.	11948.36 %Cft Rs.	73,392.80
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	329.06	Cft Rs.	337.00 P.Cft Rs.	110,893.22
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	23.504	Cwt Rs.	5001.70 P.Cwt Rs.	117,559.96
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	813.33	Cft Rs.	1512.50 %0Cft Rs.	1,230.16
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	2849.00	Cft Rs.	3630.00 %0Cft Rs.	10,341.87
8	Extra Lead 10 miles	2849.00	Sft Rs.	902.20 %Sft Rs.	25,703.68
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	581.13	Cft Rs.	8694.95 %Cft Rs.	50,528.96
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	939.00	Cft Rs.	12674.36 %Cft Rs.	119,012.24
11	S/F Girder at Site of Work	17.500	Cwt Rs.	3850.00 P.Cwt Rs.	67,375.00
12	S/F T-Iron at Site of Work	11.250	Cwt Rs.	3575.00 P.Cwt Rs.	40,218.75
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	1600.00	Sft Rs.	7607.25 %Sft Rs.	121,716.00
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1600.00	Sft Rs.	10.70 P. Sft Rs.	17,120.00
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	3276.00	Sft Rs.	2206.60 %Sft Rs.	72,288.22



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3276.00	Sft Rs. 2197.52	%Sft Rs.	71,990.76
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs. 240.50	P.Rft Rs.	23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	130.95	Sft. Rs. 902.93	P. Sft. Rs.	118,238.68
20	Primary coat of chalk under destember (C.S.I No:23 P.	3276.00	Sft Rs. 442.75	%Sft Rs.	14,504.49
21	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3276.00	Sft. Rs. 1079.65	%Sft Rs.	35,369.33
22	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	712.25	Sft Rs. 829.95	%Sft Rs.	5,911.32
23	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	304.00	Sft. Rs. 2116.41	%Sft Rs.	6,433.89
24	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	630.00	Sft Rs. 1270.83	%Sft Rs.	8,006.23
<b>Total:-</b>					<b>Rs. 1137398</b>

**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

1162.25 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:- Rs.**

**Signature of Contractor / Bidder**



**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,137,398

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

16- Construction of Bagho Koli Mandir Bhago Paro Deh 110 Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	1220.00	Cft Rs.	3176.25 %0Cft Rs.	3,875.03
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	152.50	Cft Rs.	9416.28 %Cft Rs.	14,359.83
3	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	614.25	Cft Rs.	11948.36 %Cft Rs.	73,392.80
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	329.06	Cft Rs.	337.00 P.Cft Rs.	110,893.22
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	23.504	Cwt Rs.	5001.70 P.Cwt Rs.	117,559.96
6	Filling Watering & Ramming Earth in Floor with Surplus Earch from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	813.33	Cft Rs.	1512.50 %0Cft Rs.	1,230.16
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	2849.00	Cft Rs.	3630.00 %0Cft Rs.	10,341.87
8	Extra Lead 10 miles	2849.00	Sft Rs.	902.20 %Sft Rs.	25,703.68
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	581.13	Cft Rs.	8694.95 %Cft Rs.	50,528.96
10	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	939.00	Cft Rs.	12674.36 %Cft Rs.	119,012.24
11	S/F Girder at Site of Work	17.500	Cwt Rs.	3850.00 P.Cwt Rs.	67,375.00
12	S/F T-Iron at Site of Work	11.250	Cwt Rs.	3575.00 P.Cwt Rs.	40,218.75
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortor including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	1600.00	Sft Rs.	7607.25 %Sft Rs.	121,716.00
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1600.00	Sft Rs.	10.70 P. Sft Rs.	17,120.00
15	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	3276.00	Sft Rs.	2206.60 %Sft Rs.	72,288.22

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3276.00 Sft	Rs. 2197.52	%Sft	Rs. 71,990.76
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00 Rft	Rs. 228.90	P.Rft	Rs. 8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00 Rft	Rs. 240.50	P.Rft	Rs. 23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	130.95 Sft	Rs. 902.93	P. Sft	Rs. 118,238.68
20	Primary coat of chalk under destember (C.S.I No:23 P.	3276.00 Sft	Rs. 442.75	%Sft	Rs. 14,504.49
21	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3276.00 Sft	Rs. 1079.65	%Sft	Rs. 35,369.33
22	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	712.25 Sft	Rs. 829.95	%Sft	Rs. 5,911.32
23	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	304.00 Sft	Rs. 2116.41	%Sft	Rs. 6,433.89
24	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	630.00 Sft	Rs. 1270.83	%Sft	Rs. 8,006.23
<b>Total:-</b>					<b>Rs. 1137398</b>


**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

1162.25 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:- Rs.**

**Signature of Contractor / Bidder**

  
**Executive Engineer**  
**Minorities Affairs, Sindh**  
**Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,137,398

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

17- Reconstruction of Church Building Saint Paul Church Situated at Shahbaz Colony Tando Allahyar

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:-	1730.00	Cft Rs. 3176.25	%0Cft Rs.	5,494.91
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	216.25	Cft Rs. 9416.28	%Cft Rs.	20,362.71
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	858.38	Cft Rs. 11948.36	%Cft Rs.	102,562.33
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 1 lb Cement 2 Cft Sand 4 Cft Shingle 1/8" to 1/4"	367.88	Cft Rs. 337.00	P.Cft Rs.	123,975.56
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	19.708	Cwt Rs. 5001.70	P.Cwt Rs.	98,573.50
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	1153.33	Cft Rs. 1512.50	%0Cft Rs.	1,744.41
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	3137.00	Cft Rs. 3630.00	%0Cft Rs.	11,387.31
8	Extra Lead 10 miles	3137.00	Sft Rs. 902.20	%Sft Rs.	28,302.01
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	392.13	Cft Rs. 8694.95	%Cft Rs.	34,095.51
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	1086.00	Cft Rs. 12674.36	%Cft Rs.	137,643.55
11	S/F Girder at Site of Work	17.500	Cwt Rs. 3850.00	P.Cwt Rs.	67,375.00
12	S/F T-Iron at Site of Work	13.254	Cwt Rs. 3575.00	P.Cwt Rs.	47,383.05
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing	1771.00	Sft Rs. 7607.25	%Sft Rs.	134,724.40
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	1771.00	Sft Rs. 10.70	P. Sft. Rs.	18,949.70
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	3906.00	Sft Rs. 2206.60	%Sft Rs.	86,189.80
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	3631.50	Sft Rs. 2197.52	%Sft Rs.	79,802.94

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	69.00	Rft Rs.	228.90	P.Rft Rs. 15,794.10
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs.	240.50	P.Rft Rs. 23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick	160.59	Sft. Rs.	902.93	P. Sft. Rs. 145,001.53
20	Laying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I.No. 24 P-43)	72.00	Sft Rs.	27678.86	%Sft Rs. 19,928.78
21	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick including finishing (S.I.No. 37 P-45)	301.00	Sft. Rs.	28253.61	%Sft Rs. 85,043.37
22	Primary coat of chalk under destember (C.S.I No:23 P.	3631.50	Sft Rs.	442.75	%Sft Rs. 16,078.47
23	Distemper. Three coat (CSI No. 24 ( c) Page No. 54)	3631.50	Sft. Rs.	1079.65	%Sft Rs. 39,207.49
24	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	784.25	Sft Rs.	829.95	%Sft Rs. 6,508.88
25	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	374.00	Sft. Rs.	2116.41	%Sft Rs. 7,915.37
26	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	679.88	Sft Rs.	1270.83	%Sft Rs. 8,640.12

**Total:-**

**Rs. 1365766**

**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

712.25

Sft

Rs.

P.Sft

Rs.

**Total:-**

**Rs.**

**Signature of Contractor / Bidder**



**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b><u>(b) Water Supply &amp; Sanitary Fittings.</u></b>					
<b><u>(i) Schedule Items.</u></b>					
1	Providing & fixing squatting type white glazed of flush cistern with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumb. (S.I No:1 (b) i P-No:1)	2.00	Nos. Rs. 4802.60	Each Rs.	9,605.20
2	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & l/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or c.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	2.00	Nos. Rs. 4253.70	Each Rs.	8,507.40
3	Add: extra labour for providing and fixing of earthen wire padstle white or colored glass standard pattern (S.I No:9 P-No:3).	2.00	Nos. Rs. 938.47	Each Rs.	1,876.94
4	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	2.00	Nos. Rs. 447.15	Each Rs.	894.30
5	P/F 6" x 4" c.c gully trap with 4" dia out let complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb c.I casing 6" x 6" and c.I cover and frame 12" x 12" in side etc complete. (S.I No:1(a-i) P-No:21).	2.00	Nos. Rs. 1193.17	Each Rs.	2,386.34
6	RCC pipe with collar class "B" and bedding the traches to the required depth and fixing in position l/c cutting fitting and jointing with max phalt composition and cement mortar 1:1 and testing with water pressure to head of 4 Ft above the top of the height	20.00	Rft Rs. 146.57	P.Rft Rs.	2,931.40
	4" dia	20.00	Rft Rs. 199.25	P.Rft Rs.	3,985.00
	6" dia				
7	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & l/c making requisite number of holes in walls, plinth & floor for pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	2.00	Nos. Rs. 2042.43	Each Rs.	4,084.86
8	Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking through walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zinc paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)				



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
i	1/2" dia	20.00 Rft	Rs. 73.21	P.Rft	Rs. 1,464.20
ii	3/4" dia	20.00 Rft	Rs. 95.79	P.Rft	Rs. 1,915.80
iii	1" dia	20.00 Rft	Rs. 128.55	P.Rft	Rs. 2,571.00
vi	1-1/4" dia	20.00 Rft	Rs. 153.19	P.Rft	Rs. 3,063.80
9	Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement motor etc Complete				
	1/2" dia	20.00 Rft	Rs. 7.82	P.Rft	Rs. 156.40
	3/4" dia	20.00 Rft	Rs. 8.45	P.Rft	Rs. 169.00
10	Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standard pattern (Note standard Manufacture by M/S Anwar Mechanical works. (S.I No:4 (b) P-No:17).				
	1/2" dia	2.00 Nos.	Rs. 161.92	Each	Rs. 323.84
	3/4 dia	2.00 Nos.	Rs. 227.92	Each	Rs. 455.84
11	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	2.00 Nos.	Rs. 478.28	Each	Rs. 956.56
12	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	2.00 Nos.	Rs. 1109.46	Each	Rs. 2,218.92
13	S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2.00 Nos.	Rs. 2882.00	Each	Rs. 5,764.00
14	S/F Swan type Pillars Cock of supreior quality with arvstal Head.	2.00 Nos.	Rs. 795.30	Each	Rs. 1,590.60
15	Supplying & fixing Bath room accessories set (7 pieces I/c towel rod, brush hloder, soap tray, shelf of approved quality and design etc complete. (Si No: 22 P-No:19)	2.00 Nos.	Rs. 8122.40	Each	Rs. 16,244.80
16	P/F handle valves (China) (S.I No:7 P-No:14).				
i	1/2" dia	2.00 Nos.	Rs. 271.92	Each	Rs. 543.84
ii	3/4" dia	2.00 Nos.	Rs. 365.42	Each	Rs. 730.84
17	Supplying & fixing fibre glass tank of approved quality and design and wall thicness as specified I/c cost of nutes, bolts and fixing in plateform of cement concreete 1: 3: 6 and makin connections for in -let ,& ou-let & over flow pipes etc. complete.				
A	250 Gallons	1.00 Nos.	Rs. 21989.61	Each	Rs. 21,989.61

**Total:- Rs. 94430**

**Contractor**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schedule Items Rs. 1,365,766

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### (b) Water Supply & Sanitary Fittings

(i) Schedule Items Rs. 94,430

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

# BILL OF QUANTITIES / SCHEDULE-B

18- Construction of Prayer Hall Lavatory Block and Kitchen at Parsi Colony Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items</b>					
1	Excavtion in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structrue with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	2836.13	Cft Rs. 3176.25	%0Cft Rs.	9,008.24
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	428.25	Cft Rs. 9416.28	%Cft Rs.	40,325.22
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	2233.29	Cft Rs. 337.00	P.Cft Rs.	752,619.15
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	125.623	Cwt Rs. 5001.70	P.Cwt Rs.	628,326.72
5	Erection and removal of centering for R.C.C or plain cement concrete works of Deodar wood (2nd-Class) (ii) Vertical (S.I.No. 18-b(ii)P-18)	870.00	Sft Rs. 3127.41	%Sft Rs.	27,208.47
6	Cement concrete plain including placing compacting, finishing and curing, comlete (including screening and washing at stone aggregate without shuttering. for partial wood (h) Ratio. 1:3 :6 (S.I.No.5(h)p-16)	489.38	Cft Rs. 12595.00	%Cft Rs.	61,636.78
7	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	217.00	Cft Rs. 11948.36	%Cft Rs.	25,927.94
8	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	1890.75	Cft Rs. 1512.50	%0Cft Rs.	2,859.76
9	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	2786.75	Cft Rs. 3630.00	%0Cft Rs.	10,115.90
10	Extra lead 10 miles	2786.75	Cft Rs. 902.20	%Cft Rs.	25,142.06
11	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	448.63	Cft Rs. 8694.25	%Cft Rs.	39,004.58
12	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	883.50	Cft Rs. 12674.36	%Cft Rs.	111,977.97
13	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	3950.50	Sft Rs. 2206.06	%Sft Rs.	87,150.40
14	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2033.00	Sft Rs. 2197.52	%Sft Rs.	44,675.58
15	P/F clolour create to wall surface to provide durable crust and aestheics having thickness upto 3/4" with specified colour having water, fire and temite resistance (upto 2' -0 height). (C.S>I No. 44 P-56).	1892.50	Sft Rs. 6319.50	%Sft Rs.	119,596.54

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone aggregate without shuttering Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	164.01	Cft Rs.	14429.25	%Cft Rs. 23,665.05
17	P/L Halla pattern tiles glazed 6" x 6" x 1/4" of floor of walls facing required pattern stile specification jointed in white cement and pigment over a bases 1:2 gra y cement mortar 3/4" thick I/c washing & filling of joints with sullury of white cement & pigment in desire shape with finishing cleaning and cost of wax polish etc complete i/c cutting tiles to proper profile. (C.S.I No: 61 P-48 )	140.00	Sft Rs.	47651.56	%Sft Rs. 66,712.18
18	Supplying and fixing in position Aluminium channels framing for doors alco made with 5 mm thick tinted glass glazing (Belgium) & Aluminium glass Glazing (Blgium) & Aluminium fly screen I/c handles stoppers locking arrangement etc complete Deluxe model (Blonze) (C.S.I No:83 (b) P-108).	28.00	Sft. Rs.	1507.66	P. Sft. Rs. 42,214.48
19	Supplying and fixing in position Aluminium channels framing for sliding windows and ventilators of alco made with 5 mm thick tinted glass glazing (Belgium) & Aluminium glass Glazing (Blgium) & Aluminium fly screen I/c handles stoppers locking arrangement etc complete Deluxe model (Blonze) (C.S.I No:84 (b) P-108).	128.00	Sft. Rs.	1647.69	P. Sft. Rs. 210,904.32
20	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	33.00	Rft Rs.	228.90	P.Rft Rs. 7,553.70
21	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	10.00	Rft Rs.	240.50	P.Rft Rs. 2,405.00
22	First class deodar wood wrought joinery in doors and windos etcified inosition I/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4"only shutter (C.S.I No:7 (b) P.58).	31.21	Sft. Rs.	902.93	P. Sft. Rs. 28,180.45
23	First class deodar wood wrought joinery in doors and windos etcified inosition I/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4" (C.S.I No:7 (b) P.58).	28.00	Sft. Rs.	1273.76	P. Sft. Rs. 35,665.28
24	Laying white marble flooring fine dressed in the surface without winging sate in lie mortor 1:2 including rubbing and polishing of the joints(C.S.I No:28 (a) P-43) .	897.25	Sft. Rs.	567.48	P. Sft. Rs. 509,171.43
25	Laying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I.No. 24 P-43)	38.25	Sft Rs.	27678.86	%Sft Rs. 10,587.16
26	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick including finishing (S.I.No. 37 P-45)	135.00	Sft Rs.	28253.61	%Sft Rs. 38,142.37

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
27	Providing & Fixing plaster paris ceiling border of 8" - 10" with of specified design and thickness including fixing besides ceiling with nails / screws with gatties (C.S.I No:44 P.39).	67.00	Rft Rs.	104.22	P.Rft Rs. 6,982.74
28	Supplying & Fixing false ceiling of plaster paris, in panels including making frame work of deodar wood including painting with soligia paint (C.S.I No: 52 P-64).	897.25	Sft Rs.	25293.42	%Sft Rs. 226,945.21
29	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42).	1352.25	Sft Rs.	3275.50	%Sft Rs. 44,292.95
30	Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	1352.25	Sft Rs.	1887.40	%Sft Rs. 25,522.37
31	White wash three coats (C.S.I No:26 (c) P-54).	1225.50	Sft Rs.	829.95	%Sft Rs. 10,171.04
32	Making & Fixing Steel Grated Door Complete with locking arrangements angel iron frame 2"x2" 3/8" and 3/4" sq bars 4" center to center (C.S.I No:23 P-92).	24.50	Sft Rs.	726.72	P.Sft Rs. 17,804.64
33	Paerpairing the Surface and painting with matt finish i/c rubbing the surface with arhy (Slicion Carbide) rubbing brick filling the voids with zink / chalk / plaster of pairs mixture applying first coat premix making the surface smooth an then painting 3	2033.00	Sft Rs.	3444.38	%Sft Rs. 70,024.25
34	French Polishing Complete.(a) One New Work (S.I.No.7 p-71)	167.42	Sft Rs.	3841.75	%Sft Rs. 6,431.86
35	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	10.00	Nos Rs.	261.25	Each Rs. 2,612.50

**Total:- Rs. 3,371,586**

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------

**(b) Water Supply & Sanitary Fittings.**

**(i) Schedule Items**

1	Providing & fixing squatting type white glazed of flush cistern with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear	2.00	Nos	Rs.	4802.60	Each	Rs.	9,605.20
2	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & I/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia rubber	2.00	Nos	Rs.	4253.70	Each	Rs.	8,507.40
3	Add: extra labour for providing and fixing of earthen wire pedestal white or colored glass standard pattern (S.I No:9 P-No:3).	2.00	Nos	Rs.	938.47	Each	Rs.	1,876.94
4	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	2.00	Nos	Rs.	447.15	Each	Rs.	894.30
5	P/F 6" x 4" c.c gully trap with 4" dia out let complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb c.I casing 6" x 6" and c.I cover and frame 12" x 12" in side etc complete (S.I No:1(a-i) P-No:21).	2.00	Nos	Rs.	1193.17	Each	Rs.	2,386.34
6	RCC pipe with collar class "B" and bedding the traches to the required depth and fixing in position I/c cutting fitting and jointing with max phalt composition and cement mortar 1:1 and testing with water pressure to head of 4 Ft above the top of the height							
	4" dia	30.00	Rft	Rs.	146.57	P.Rft	Rs.	4,397.10
	6" dia	30.00	Rft	Rs.	199.25	P.Rft	Rs.	5,977.50
7	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & I/c making requisite number of holes in walls, plinth & floor for pipe connections &	2.00	Nos	Rs.	2042.43	Each	Rs.	4,084.86
8	Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and I/c the cost of breaking thorough walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zinc paint with pigment to match							
I	1/2" dia	20.00	Rft	Rs.	73.21	P.Rft	Rs.	1,464.20
ii	3/4" dia	20.00	Rft	Rs.	95.79	P.Rft	Rs.	1,915.80
iii	1" dia	20.00	Rft	Rs.	128.55	P.Rft	Rs.	2,571.00
vi	1-1/4" dia	20.00	Rft	Rs.	153.19	P.Rft	Rs.	3,063.80
9	Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement mortar etc Complete							
	1/2" dia	20.00	Nos	Rs.	7.82	Each	Rs.	156.40
	3/4" dia	20.00	Nos	Rs.	8.45	Each	Rs.	169.00
10	Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standard pattern (Note standard Manufacture by M/S Anwar Mechanical works (S.I No:4 (b) P-No:17).							
	1" dia	2.00	Nos	Rs.	161.92	Each	Rs.	323.84

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
	1-1/2" dia	2.00 Nos	Rs. 227.92	Each	Rs. 455.84
11	S/F cancelled stop cock of superior quality with crystal head 1/2" dia (S.I No:11 (b) P-No:18).	2.00 Nos	Rs. 478.28	Each	Rs. 956.56
12	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	2.00 Nos	Rs. 1109.46	Each	Rs. 2,218.92
13	S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2.00 Nos	Rs. 2882.00	Each	Rs. 5,764.00
14	S/F Swan type Pillars Cock of supreior quality with arvstal Head.	2.00 Nos	Rs. 795.30	Each	Rs. 1,590.60
15	Supplying & fixing Bath room accessories set (7 pieces l/c towel rod, brush hloder, soap tray, shelf of approved quality and design etc complete. (Si No: 22 P-No:19)	1.00 Nos	Rs. 8122.40	Each	Rs. 8,122.40
16	P/F handle values (China) (S.I No:7 P-No:14).	2.00 Nos	Rs. 271.92	Each	Rs. 543.84
ii	3/4" Dia	2.00 Nos	Rs. 365.42	Each	Rs. 730.84
iii	1" Dia	2.00 Nos	Rs. 365.42	Each	Rs. 730.84
17	Supplying & fixing fibre glass tank of approved quality and design and wall thicness as specified l/c cost of nutes, bolts and fixing in plateform of cement concrete 1: 3: 6 and makin connections for in -let ,& ou-let & over flow pipes etc. complete.250	1.00 Nos	Rs. 21989.61	Each	Rs. 21,989.61

**Total:- Rs. 89,766**

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schedule Items Rs. 3,371,586

Add: / Deducted ..... % Above / Below Premium Rs. ....

Total Civil Work Rs.

#### (b) Water Supply & Sanitary Fittings

(i) Schedule Items Rs. 89,766

Add: / Deducted ..... % Above / Below Premium Rs. ....

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.


Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder



Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi



## BILL OF QUANTITIES / SCHEDULE-B

19- Construction of Satsang Hall at Deh 390 Kot Ghualm Muhammad District Mirpurkhas

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	1012.50	Cft Rs. 3176.25	%0Cft Rs.	3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs. 9416.28	%Cft Rs.	10,593.32
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (e) P.21).	456.77	Cft Rs. 11948.36	%Cft Rs.	54,576.52
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (1) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (1) / P-17).	244.69	Cft Rs. 337.00	P.Cft Rs.	82,460.53
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	14.201	Cwt Rs. 5001.70	P.Cwt Rs.	71,029.14
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs. 1512.50	%0Cft Rs.	1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs. 3630.00	%0Cft Rs.	5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs. 902.20	%Sft Rs.	13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	372.38	Cft Rs. 8694.95	%Cft Rs.	32,378.25
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	669.00	Cft Rs. 12674.36	%Cft Rs.	84,791.47
11	S/F Girder at Site of Work	13.125	Cwt Rs. 3850.00	P.Cwt Rs.	50,531.25
12	S/F T-Iron at Site of Work	8.438	Cwt Rs. 3575.00	P.Cwt Rs.	30,165.85
13	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	900.00	Sft Rs. 7607.25	%Sft Rs.	68,465.25
14	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	900.00	Sft Rs. 10.70	P. Sft. Rs.	9,630.00
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2436.00	Sft Rs. 2206.60	%Sft Rs.	53,752.78

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2436.00	Sft Rs. 2197.52	%Sft Rs.	53,531.59
17	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	96.00	Rft Rs. 240.50	P.Rft Rs.	23,088.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	130.95	Sft. Rs. 902.93	P. Sft. Rs.	118,238.68
20	Primary coat of chalk under destember (C.S.I No:23 P.	2436.00	Sft Rs. 442.75	%Sft Rs.	10,785.39
21	Distemper. Three coat (CSI No. 24 (c) Page No. 54)	2436.00	Sft. Rs. 1079.65	%Sft Rs.	26,300.27
22	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75	Sft Rs. 829.95	%Sft Rs.	3,193.23
23	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	152.00	Sft. Rs. 2116.41	%Sft Rs.	3,216.94
24	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	472.50	Sft Rs. 1270.83	%Sft Rs.	6,004.67
<b>Total:-</b>					<b>Rs. 824673</b>

**(ii) Non Schedule Items.**

- 1 Providing & Laying marble flooring super / China Verona / Teravera or equivalent having size 24"x12"x3/4" or 12"x12"x3/4" fine dressed on the surface without winding set in lime putty laid over 3/4 thick lime mortar 1:2 & Filling the joints with white cement and pigment i/c grinding rubbing and chemical polishing as directed by the Engineer Incharge

984.75 Sft Rs. \_\_\_\_\_ P.Sft Rs. \_\_\_\_\_

**Total:- Rs.**

**Signature of Contractor / Bidder**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 824,673

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
**Executive Engineer**  
**Minorities Affairs, Sindh**  
**Hyderabad @ Karachi**

## BILL OF QUANTITIES / SCHEDULE-B

20- Repair / Renovation & Construction of Stage & Compound Wall of Shankar Annand Temple Shikarpur.

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------

### (a) Civil Works.

#### (i) Schedule Items

1	Excavtion in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structrure with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	2124.00 Cft	Rs. 3176.25	%0Cft	Rs. 6,746.36
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	321.00 Cft	Rs. 9416.28	%Cft	Rs. 30,226.26
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	1782.50 Cft	Rs. 337.00	P.Cft	Rs. 600,702.50
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	95.491 Cwt	Rs. 5001.70	P.Cwt	Rs. 477,617.69
5	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	1309.63 Cft	Rs. 11948.36	%Cft	Rs. 156,478.71
6	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	1416.00 Cft	Rs. 1512.50	%0Cft	Rs. 2,141.70
7	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	3936.25 Cft	Rs. 3630.00	%0Cft	Rs. 14,288.59
8	Extra lead 10 miles	3936.25 Cft	Rs. 902.20	%Cft	Rs. 35,512.85
9	Cement concrete brick or stone ballast 11/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	3936.25 Cft	Rs. 8694.25	%Cft	Rs. 342,227.42
10	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	507.00 Cft	Rs. 12674.36	%Cft	Rs. 64,259.01
11	Pacca brick work other than building including skriting of joints upto 20 feet height in 1:6 (C.S.I No: 7 (e) Page No: 22)	337.50 Cft	Rs. 12346.65	%Cft	Rs. 41,669.94
12	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	6179.00 Sft	Rs. 2206.06	%Sft	Rs. 136,312.45
13	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	5595.00 Sft	Rs. 2197.52	%Sft	Rs. 122,951.24
14	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shutting Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	133.83 Cft	Rs. 14429.25	%Cft	Rs. 19,311.03

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
15	Laying white marble flooring fine dressed in the surface without winging sate in lie mortor 1:2 including rubbing and polishing of the joints(C.S.I No:28 (a) P-43) .	1162.25 Sft.	Rs. 567.48	P. Sft.	Rs. 659,553.63
16	Providing and fixing 3/8" thick marble tiles of approved quality and colour and shade size 8" x 4" /6" x 4" in dado skirting anf facing removal /tucking of existing plaster surface etc. Over 1/2" thick base of cement mortar 1:3 setting of tiles in slurry	40.25 Sft.	Rs. 201.00	P. Sft.	Rs. 8,090.25
17	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick including finishing (S.I.No. 37 P-45)	584.00 Sft	Rs. 28253.61	%Sft	Rs. 165,001.08
18	P/L Halla pattern tiles glazed 6" x 6" x 1/4" of floor of walls facing required pattern stile specification jointed in white cement and pigment over a bazes 1:2 gra y cement mortor 3/4" thick i/c washing & filling of joints with sullury of white cement & pigment in desire shape with finishing cleaning and cost of wax polish etc complete i/c cutting tiles to proper profile. (C.S.I No: 61 P-48 )	198.00 Sft	Rs. 47651.56	%Sft	Rs. 94,350.09
19	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42) .	875.00 Sft	Rs. 3275.50	%Sft	Rs. 28,660.63
20	Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	875.00 Sft	Rs. 1887.40	%Sft	Rs. 16,514.75
21	White wash three coats (C.S.I No:26 (c) P-54).	787.25 Sft	Rs. 829.95	%Sft	Rs. 6,533.78
22	Providing and fixing iron steel girll door with angle iron frame of 1-1/2" x 1-1/2" x 1/4" and flate iron of 3/4" x 1/4" with approved design and locking arrangments embeded in masonary as per instruction of engineer enchange(S.I.NO.31,P-94	70.00 Sft.	Rs. 231.60	P. Sft.	Rs. 16,212.00
23	Paerpairing the Surface and painting with matt finish i/c rubbing the surface with arhy (Slicion Carbide) rubbing brick filling the voids with zink / chalk / plaster of pairs mixture applying first coat premix making the surface smooth an then painting 3	5595.00 Sft	Rs. 3444.38	%Sft	Rs. 192,713.06
24	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	4.00 Nos	Rs. 261.25	Each	Rs. 1,045.00

Total:-

Rs.

3,222,941

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schedule Items Rs. -

---

Add: / Deducted ..... % Above / Below Premium Rs. ....

---

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.

---


Total Non-Schedule Item Rs.

---

Total Bid Amount Rs.

---

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

2/- Repair / Renovation & Remaining Work of Lajni Graveyard Compound Wall U.C Kaloi Taluka Diplo Tharparkar


S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	2375.00	Cft Rs.	3176.25	%0Cft Rs. 7,543.59
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	543.75	Cft Rs.	9416.28	%Cft Rs. 51,201.02
3	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	735.13	Cft Rs.	337.00	P.Cft Rs. 247,738.81
4	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	39.644	Cwt Rs.	5001.70	P.Cwt Rs. 198,287.39
5	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (e) P.21).	890.63	Cft Rs.	11948.36	%Cft Rs. 106,415.68
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	1583.33	Cft Rs.	1512.50	%0Cft Rs. 2,394.79
7	Pacca brick work other than building in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	937.50	Cft Rs.	12346.65	%Cft Rs. 115,749.84
8	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b) Page No: 52).	3000.00	Sft Rs.	2206.60	%Sft Rs. 66,198.00
9	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2500.00	Sft Rs.	2197.52	%Sft Rs. 54,938.00
10	P/L. Halla pattern tiles glazed 6" x 6" x 1/4" of floor of walls facing required pattern stile specification jointed in white cement and pigment over a bases 1:2 gray cement mortar 3/4" thick i/c washing & filling of joints with sullury of white cement & pigment in desire shape with finishing cleaning and cost of wax polish etc. complete i/c cutting tiles to proper profile. (C.S.I No: 61 P-48)	445.00	Sft Rs.	47651.56	%Sft Rs. 212,049.44
11	Making & Fixing Steel Grated Door Complete with locking arrangements angel iron frame 2"x2" 3/8" and 3/4" sq bars 4" center to center (C.S.I No:23 P-92).	128.00	Sft Rs.	726.72	P. Sft. Rs. 93,020.16
12	Primary coat of chalk under destember (C.S.I No:23 P-54).	2500.00	Sft Rs.	442.75	%Sft Rs. 11,068.75
13	Distemper. Three coat (CSI No. 24 (c) Page No. 54)	2500.00	Sft. Rs.	1079.65	%Sft Rs. 26,991.25

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
14	Painting new surfaces (c) Preparing surfaces and painting of doors and windows any type (including edges). (S.I.No.5-c P-70).	256.00	Sft Rs. 2116.41	%Sft Rs.	5,418.01

Total:-

Rs. 1198997

Signature of Contractor / Bidder



Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 1,198,997


Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

22- Construction of Satsang Hall at Sami Jo Dado Village Maharaj Malji Ram Ji Dhani (Sattar) Taluka Mithi District Tharparkar

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No: 18 (b) / P-4).	1012.50	Cft Rs.	3176.25	%0Cft Rs. 3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs.	9416.28	%Cft Rs. 10,593.32
3	Pucca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P,21).	456.77	Cft Rs.	11948.36	%Cft Rs. 54,576.82
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds. Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) / P-17).	261.00	Cft Rs.	337.00	P.Cft Rs. 87,957.00
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	13.982	Cwt Rs.	5001.70	P.Cwt Rs. 69,934.48
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs.	1512.50	%0Cft Rs. 1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs.	3630.00	%0Cft Rs. 5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs.	902.20	%Sft Rs. 13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	192.38	Cft Rs.	8694.95	%Cft Rs. 16,726.91
10	Pucca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	562.50	Cft Rs.	12674.36	%Cft Rs. 71,293.28
11	S/F Girder at Site of Work	11.250	Cwt Rs.	3850.00	P.Cwt Rs. 43,312.50
12	S/F T-Iron at Site of Work	8.438	Cwt Rs.	3575.00	P.Cwt Rs. 30,164.06
13	1st class tiles roofing consisting of 4"earth and 1" mud plaster with gobi leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over two layer of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc (C.S.I No:1 P,33)	450.00	Sft Rs.	11443.10	%Sft Rs. 51,493.95

S. No:-	Description.	Quantity.		Rate.		Unit.		Amount.
14	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge(C.S.I No:38	450.00	Sft	Rs.	10.70	P. Sft.	Rs.	4,815.00
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2164.00	Sft	Rs.	2206.60	%Sft	Rs.	47,750.82
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2164.00	Sft	Rs.	2197.52	%Sft	Rs.	47,554.33
17	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:29	36.00	Rft	Rs.	228.90	P.Rft	Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:28	64.00	Rft	Rs.	240.50	P.Rft	Rs.	15,392.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	104.01	Sft.	Rs.	902.93	P. Sft.	Rs.	93,911.76
20	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42)	450.00	Sft	Rs.	3275.50	%Sft	Rs.	14,739.75
21	Primary coat of chalk under destemper (C.S.I No:23	2164.00	Sft	Rs.	442.75	%Sft	Rs.	9,581.11
22	Distemper Three coat (C.S.I No. 24 (c) Page No.	2164.00	Sft.	Rs.	1079.65	%Sft	Rs.	23,363.63
23	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75	Sft	Rs.	829.95	%Sft	Rs.	3,193.23
24	Painting new surface & perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	240.00	Sft.	Rs.	2116.41	%Sft	Rs.	5,079.38
25	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	435.00	Sft	Rs.	1270.83	%Sft	Rs.	5,528.11

Total:- Rs. 738910

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
------------	--------------	-----------	-------	-------	---------

## General Abstract

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 738,910

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.


### Non-Schedule Item / Item Based Item.

Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder



Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

23- Construction of Satsang Hall Dharmani Paro Mithi Tharparkar

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure i.e Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No: 18 (b) / P-4).	1012.50	Cft Rs.	3176.25	%Cft Rs. 3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs.	9416.28	%Cft Rs. 10,593.32
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (c) P.21).	456.77	Cft Rs.	11948.36	%Cft Rs. 54,576.82
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	261.00	Cft Rs.	337.00	P.Cft Rs. 87,957.00
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	13.982	Cwt Rs.	5001.70	P.Cwt Rs. 69,934.48
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs.	1512.50	%Cft Rs. 1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs.	3630.00	%Cft Rs. 5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs.	902.20	%Sft Rs. 13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	192.38	Cft Rs.	8694.95	%Cft Rs. 16,726.91
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	562.50	Cft Rs.	12674.36	%Cft Rs. 71,293.28
11	S/F Girder at Site of Work	11.250	Cwt Rs.	3850.00	P.Cwt Rs. 43,312.50
12	S/F T-Iron at Site of Work	8.438	Cwt Rs.	3575.00	P.Cwt Rs. 30,164.06
13	1st class tiles roofing consisting of 4"earth and 1" mud plaster with gobri leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over two layer of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc (C.S.I No:1 P.33)	450.00	Sft Rs.	11443.10	%Sft Rs. 51,493.95
14	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	450.00	Sft Rs.	10.70	P. Sft. Rs. 4,815.00

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2164.00	Sft Rs. 2206.60	%Sft Rs.	47,750.82
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2164.00	Sft Rs. 2197.52	%Sft Rs.	47,554.33
17	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:28 P.93).	64.00	Rft Rs. 240.50	P.Rft Rs.	15,392.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	104.01	Sft. Rs. 902.93	P. Sft. Rs.	93,911.76
20	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42)	450.00	Sft Rs. 3275.50	%Sft Rs.	14,739.75
21	Primary coat of chalk under destemper (C.S.I No:23	2164.00	Sft Rs. 442.75	%Sft Rs.	9,581.11
22	Distemper, Three coat (CSI No. 24 ( c) Page No. 54)	2164.00	Sft. Rs. 1079.65	%Sft Rs.	23,363.63
23	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75	Sft Rs. 829.95	%Sft Rs.	3,193.23
24	Painting new surface @ perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	240.00	Sft. Rs. 2116.41	%Sft Rs.	5,079.38
25	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	435.00	Sft Rs. 1270.83	%Sft Rs.	5,528.11

Total:- Rs. 738910

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 738,910

Add: / Deducted ..... % Above / Below Premium Rs. ....

Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.


Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....

Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

24- Construction of Satsang Hall Shewala Mandir Chachro Tharparkar

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure i/e Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No: 18 (b) / P-4).	1012.50	Cft Rs.	3176.25	%0Cft Rs. 3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs.	9416.28	%Cft Rs. 10,593.32
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (c) P.21).	456.77	Cft Rs.	11948.36	%Cft Rs. 54,576.82
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	261.00	Cft Rs.	337.00	P.Cft Rs. 87,957.00
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	13.982	Cwt Rs.	5001.70	P.Cwt Rs. 69,934.48
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs.	1512.50	%0Cft Rs. 1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs.	3630.00	%0Cft Rs. 5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs.	902.20	%Sft Rs. 13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	192.38	Cft Rs.	8694.95	%Cft Rs. 16,726.91
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (c) Page No: 21)	562.50	Cft Rs.	12674.36	%Cft Rs. 71,293.28
11	S/F Girder at Site of Work	11.250	Cwt Rs.	3850.00	P.Cwt Rs. 43,312.50
12	S/F T-Iron at Site of Work	8.438	Cwt Rs.	3575.00	P.Cwt Rs. 30,164.06
13	1st class tiles roofing consisting of 4" earth and 1" mud plaster with gobri leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over two layer of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc (C.S.I No:1 P.33)	450.00	Sft Rs.	11443.10	%Sft Rs. 51,493.95
14	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge (C.S.I No:38 P.38).	450.00	Sft Rs.	10.70	P. Sft. Rs. 4,815.00



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b) Page No: 52).	2164.00 Sft	Rs. 2206.60	%Sft	Rs. 47,750.82
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2164.00 Sft	Rs. 2197.52	%Sft	Rs. 47,554.33
17	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00 Rft	Rs. 228.90	P.Rft	Rs. 8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	64.00 Rft	Rs. 240.50	P.Rft	Rs. 15,392.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	104.01 Sft.	Rs. 902.93	P. Sft.	Rs. 93,911.76
20	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels (C.S.I No:16 (c) P-42)	450.00 Sft	Rs. 3275.50	%Sft	Rs. 14,739.75
21	Primary coat of chalk under destember (C.S.I No:23	2164.00 Sft	Rs. 442.75	%Sft	Rs. 9,581.11
22	Distemper, Three coat (C.S.I No. 24 (c) Page No. 54)	2164.00 Sft.	Rs. 1079.65	%Sft	Rs. 23,363.63
23	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75 Sft	Rs. 829.95	%Sft	Rs. 3,193.23
24	Painting new surface (i) preparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	240.00 Sft.	Rs. 2116.41	%Sft	Rs. 5,079.38
25	Painting guard bars gats iron bars grating railing including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	435.00 Sft	Rs. 1270.83	%Sft	Rs. 5,528.11

Total:- Rs. 738910

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 738,910

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.


#### Non-Schedule Item / Item Based Item.

Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

25- Repair / Renovation / Construction of Omkar Mandir Nabisar Thar Umerkot

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure 1/2 Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No: 18 (b) / P-4).	1012.50	Cft Rs.	3176.25	%0Cft Rs. 3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs.	9416.28	%Cft Rs. 10,593.32
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (c) P.21).	456.77	Cft Rs.	11948.36	%Cft Rs. 54,576.82
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	261.00	Cft Rs.	337.00	P.Cft Rs. 87,957.00
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	13.982	Cwt Rs.	5001.70	P.Cwt Rs. 69,934.48
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs.	1512.50	%0Cft Rs. 1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs.	3630.00	%0Cft Rs. 5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs.	902.20	%Sft Rs. 13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	192.38	Cft Rs.	8694.95	%Cft Rs. 16,726.91
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (c) Page No: 21)	562.50	Cft Rs.	12674.36	%Cft Rs. 71,293.28
11	S/F Girder at Site of Work	11.250	Cwt Rs.	3850.00	P.Cwt Rs. 43,312.50
12	S/F T-Iron at Site of Work	8.438	Cwt Rs.	3575.00	P.Cwt Rs. 30,164.06
13	1st class tiles roofing consisting of 4"earth and 1" mud plaster with gobri leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over two layer of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc (C.S.I No:1 P.33)	450.00	Sft Rs.	11443.10	%Sft Rs. 51,493.95
14	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	450.00	Sft Rs.	10.70	P. Sft. Rs. 4,815.00

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2164.00	Sft Rs. 2206.60	%Sft Rs.	47,750.82
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2164.00	Sft Rs. 2197.52	%Sft Rs.	47,554.33
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:28 P.93).	64.00	Rft Rs. 240.50	P.Rft Rs.	15,392.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	104.01	Sft. Rs. 902.93	P. Sft. Rs.	93,911.76
20	Providing and fixing 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42)	450.00	Sft Rs. 3275.50	%Sft Rs.	14,739.75
21	Primary coat of chalk under distemper (C.S.I No:23	2164.00	Sft Rs. 442.75	%Sft Rs.	9,581.11
22	Distemper, Three coat (CSI No. 24 (c) Page No. 54)	2164.00	Sft. Rs. 1079.65	%Sft Rs.	23,363.63
23	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75	Sft Rs. 829.95	%Sft Rs.	3,193.23
24	Painting new surface & perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	240.00	Sft. Rs. 2116.41	%Sft Rs.	5,079.38
25	Painting guard bars gats iron bars grating raling including standard braces etc and sniller open work three coat (C.S.I No:4 (d) (ii) P-70).	435.00	Sft Rs. 1270.83	%Sft Rs.	5,528.11

Total:- Rs. 738910

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 738,910


Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.  
 Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

26- Repair / Renovation of Mirwah Heera Lal Paro Mirpurkhas

S. No.:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	1012.50	Cft Rs.	3176.25	%0Cft Rs. 3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs.	9416.28	%Cft Rs. 10,593.32
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (c) P.21).	456.77	Cft Rs.	11948.36	%Cft Rs. 54,576.82
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	261.00	Cft Rs.	337.00	P.Cft Rs. 87,957.00
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	13.982	Cwt Rs.	5001.70	P.Cwt Rs. 69,934.48
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs.	1512.50	%0Cft Rs. 1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs.	3630.00	%0Cft Rs. 5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs.	902.20	%Sft Rs. 13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	192.38	Cft Rs.	8694.95	%Cft Rs. 16,726.91
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (c) Page No: 21)	562.50	Cft Rs.	12674.36	%Cft Rs. 71,293.28
11	S/F Girder at Site of Work	11.250	Cwt Rs.	3850.00	P.Cwt Rs. 43,312.50
12	S/F T-Iron at Site of Work	8.438	Cwt Rs.	3575.00	P.Cwt Rs. 30,164.06
13	1st class tiles roofing consisting of 4"earth and 1" mud plaster with gobri leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over two layer of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc (C.S.I No:1 P.33)	450.00	Sft Rs.	11443.10	%Sft Rs. 51,493.95
14	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge (C.S.I No:38 P.38).	450.00	Sft Rs.	10.70	P. Sft. Rs. 4,815.00

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b) Page No: 52).	2164.00	Sft Rs. 2206.60	%Sft Rs.	47,750.82
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2164.00	Sft Rs. 2197.52	%Sft Rs.	47,554.33
17	Providing and fixing G.I frames (Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/e welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/e all carriage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames (Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/e welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/e all carriage tools and plants used in making and fixing (C.S.I No:28 P.93).	64.00	Rft Rs. 240.50	P.Rft Rs.	15,392.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No, 7 (b) / P-58).	104.01	Sft Rs. 902.93	P. Sft Rs.	93,911.76
20	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels (C.S.I No:16 (c) P-42)	450.00	Sft Rs. 3275.50	%Sft Rs.	14,739.75
21	Primary coat of chalk under destemper (C.S.I No:23	2164.00	Sft Rs. 442.75	%Sft Rs.	9,581.11
22	Distemper, Three coat (CSI No. 24 (c) Page No. 54)	2164.00	Sft Rs. 1079.65	%Sft Rs.	23,363.63
23	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75	Sft Rs. 829.95	%Sft Rs.	3,193.23
24	Painting new surface (i) perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	240.00	Sft Rs. 2116.41	%Sft Rs.	5,079.38
25	Painting guard bars gats iron bars grating raling including standard braces etc and smaller open work three coat (C.S.I No:4 (d) (ii) P-70).	435.00	Sft Rs. 1270.83	%Sft Rs.	5,528.11

Total:- Rs. 738910

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 738,910


Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.

#### Non-Schedule Item / Item Based Item.

Rs.  
 Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi



## BILL OF QUANTITIES / SCHEDULE-B

27- Repair / Renovation of Darbar Aarth Prakash Jeelani Mohalla Khairpur Mir's

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure w/ Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No: 18 (b) / P-4).	1012.50	Cft Rs.	3176.25	%Cft Rs. 3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs.	9416.28	%Cft Rs. 10,593.32
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (c) P.21).	456.77	Cft Rs.	11948.36	%Cft Rs. 54,576.82
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	261.00	Cft Rs.	337.00	P.Cft Rs. 87,957.00
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	13.982	Cwt Rs.	5001.70	P.Cwt Rs. 69,934.48
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs.	1512.50	%Cft Rs. 1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs.	3630.00	%Cft Rs. 5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs.	902.20	%Sft Rs. 13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	192.38	Cft Rs.	8694.95	%Cft Rs. 16,726.91
10	Pacca brick work in ground floor in cement sand mortar ratio (C.S.I No: 5 (c) Page No: 21)	562.50	Cft Rs.	12674.36	%Cft Rs. 71,293.28
11	S/E Girder at Site of Work	11.250	Cwt Rs.	3850.00	P.Cwt Rs. 43,312.50
12	S/E T-Iron at Site of Work	8.438	Cwt Rs.	3575.00	P.Cwt Rs. 30,164.06
13	1st class tiles roofing consisting of 4" earth and 1" mud plaster with gobri leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over two layer of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc (C.S.I No:1 P.33)	450.00	Sft Rs.	11443.10	%Sft Rs. 51,493.95
14	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge (C.S.I No:38 P.38).	450.00	Sft Rs.	10.70	P.Sft Rs. 4,815.00

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2164.00	Sft Rs. 2206.60	%Sft Rs.	47,750.82
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2164.00	Sft Rs. 2197.52	%Sft Rs.	47,554.33
17	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:28 P.93).	64.00	Rft Rs. 240.50	P.Rft Rs.	15,392.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc, Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	104.01	Sft. Rs. 902.93	P. Sft. Rs.	93,911.76
20	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-12)	450.00	Sft Rs. 3275.50	%Sft Rs.	14,739.75
21	Primary coat of chalk under destempler (C.S.I No:23	2164.00	Sft Rs. 442.75	%Sft Rs.	9,581.11
22	Distemper Three coat (CSI No. 24 (c) Page No. 54)	2164.00	Sft. Rs. 1079.65	%Sft Rs.	23,363.63
23	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75	Sft Rs. 829.95	%Sft Rs.	3,193.23
24	Painting new surface & perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	240.00	Sft. Rs. 2116.41	%Sft Rs.	5,079.38
25	Painting guard bars gats iron bars grating railing including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	435.00	Sft Rs. 1270.83	%Sft Rs.	5,528.11
Total:-					Rs. 738910

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schedule Items Rs. 738,910

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.


#### Non-Schedule Item / Item Based Item.

Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

# BILL OF QUANTITIES / SCHEDULE-B

28- Repair / Renovation of Shivalo Shewak Ram Munshi Mohalla Khairpur Mir's

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No: 18 (b) / P-4).	1012.50	Cft Rs.	3176.25	%0Cft Rs. 3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs.	9416.28	%Cft Rs. 10,593.32
3	Pucca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (c) P.21).	456.77	Cft Rs.	11948.36	%Cft Rs. 54,576.82
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 Lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	261.00	Cft Rs.	337.00	P.Cft Rs. 87,957.00
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	13.982	Cwt Rs.	5061.70	P.Cwt Rs. 69,934.48
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs.	1512.50	%0Cft Rs. 1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs.	3630.00	%0Cft Rs. 5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs.	902.20	%Sft Rs. 13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	192.38	Cft Rs.	8694.95	%Cft Rs. 16,726.91
10	Pucca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (c) Page No: 21)	562.50	Cft Rs.	12674.36	%Cft Rs. 71,293.28
11	S/F Girder at Site of Work	11.250	Cwt Rs.	3850.00	P.Cwt Rs. 43,312.50
12	S/F T-Iron at Site of Work	8.438	Cwt Rs.	3575.00	P.Cwt Rs. 30,164.06
13	1st class tiles roofing consisting of 4"earth and 1" mud plaster with gobri leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over two layer of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc (C.S.I No:1 P.33)	450.00	Sft Rs.	11443.10	%Sft Rs. 51,493.95
14	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	450.00	Sft Rs.	10.70	P. Sft. Rs. 4,815.00

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2164.00 Sft	Rs. 2206.60	%Sft	Rs. 47,750.82
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2164.00 Sft	Rs. 2197.52	%Sft	Rs. 47,554.33
17	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00 Rft	Rs. 228.90	P.Rft	Rs. 8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:28 P.93).	64.00 Rft	Rs. 240.50	P.Rft	Rs. 15,392.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	104.01 Sft.	Rs. 902.93	P. Sft.	Rs. 93,911.76
20	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42)	450.00 Sft	Rs. 3275.50	%Sft	Rs. 14,739.75
21	Primary coat of chalk under destember (C.S.I No:23	2164.00 Sft	Rs. 442.75	%Sft	Rs. 9,581.11
22	Distemper, Three coat (CSI No. 24 (c) Page No. 54)	2164.00 Sft.	Rs. 1079.65	%Sft	Rs. 23,363.63
23	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75 Sft	Rs. 829.95	%Sft	Rs. 3,193.23
24	Painting new surface & perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	240.00 Sft.	Rs. 2116.41	%Sft	Rs. 5,079.38
25	Painting guard bars gats iron bars grating raling including standard braces etc and sniller open work three coat (C.S.I No:4 (d)(ii) P-70).	435.00 Sft	Rs. 1270.83	%Sft	Rs. 5,528.11
Total:-					Rs. 738910

Signature of Contractor / Bidder

Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

### Composite Schedule Items.

#### (a) Civil Works

(i) Schdule Items Rs. 738,910

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.


#### Non-Schedule Item / Item Based Item.

Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi


## BILL OF QUANTITIES / SCHEDULE-B

29- Construction of Satsang Hall at Village Raryaro Taluak Chacharo Tharparkar

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<u>(a) Civil Works.</u>					
<u>(i) Schedule Items.</u>					
1	Excavation in Foundation of Building Bridges & Other Structure i/e Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No: 18 (b) / P-4).	1012.50	Cft Rs.	3176.25	%0Cft Rs. 3,215.95
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	112.50	Cft Rs.	9416.28	%Cft Rs. 10,593.32
3	Pucca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (c) P.21).	456.77	Cft Rs.	11948.36	%Cft Rs. 54,576.82
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 lbs Cement, 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" Gauge (S.I.No:- 6 (a) (I) / P-17).	261.00	Cft Rs.	337.00	P.Cft Rs. 87,957.00
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	13.982	Cwt Rs.	5001.70	P.Cwt Rs. 69,934.48
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	675.00	Cft Rs.	1512.50	%0Cft Rs. 1,020.94
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	1539.00	Cft Rs.	3630.00	%0Cft Rs. 5,586.57
8	Extra Lead 10 miles	1539.00	Sft Rs.	902.20	%Sft Rs. 13,884.86
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4 (c) / P-17).	192.38	Cft Rs.	8694.95	%Cft Rs. 16,726.91
10	Pucca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (c) Page No: 21)	562.50	Cft Rs.	12674.36	%Cft Rs. 71,293.28
11	S/F Girder at Site of Work	11.250	Cwt Rs.	3850.00	P.Cwt Rs. 43,312.50
12	S/F T-Iron at Site of Work	8.438	Cwt Rs.	3575.00	P.Cwt Rs. 30,164.06
13	1st class tiles roofing consisting of 4"earth and 1" mud plaster with gobri leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over two layer of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiched layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including eafing etc (C.S.I No:1 P.33)	450.00	Sft Rs.	11443.10	%Sft Rs. 51,493.95
14	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge (C.S.I No:38 P.38).	450.00	Sft Rs.	10.70	P. Sft. Rs. 4,815.00

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
15	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2164.00	Sft Rs. 2206.60	%Sft Rs.	47,750.82
16	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	2164.00	Sft Rs. 2197.52	%Sft Rs.	47,554.33
17	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:29 P.93).	36.00	Rft Rs. 228.90	P.Rft Rs.	8,240.40
18	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the jambs. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:28 P.93).	64.00	Rft Rs. 240.50	P.Rft Rs.	15,392.00
19	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	104.01	Sft Rs. 902.93	P. Sft Rs.	93,911.76
20	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42)	450.00	Sft Rs. 3275.50	%Sft Rs.	14,739.75
21	Primary coat of chalk under destemper (C.S.I No:23	2164.00	Sft Rs. 442.75	%Sft Rs.	9,581.11
22	Distemper, Three coat (CSI No. 24 (c) Page No. 54)	2164.00	Sft Rs. 1079.65	%Sft Rs.	23,363.63
23	White Wash (c) Three Coats (S.I.No:- 26 (c) / P-60).	384.75	Sft Rs. 829.95	%Sft Rs.	3,193.23
24	Painting new surface & perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c) p-	240.00	Sft Rs. 2116.41	%Sft Rs.	5,079.38
25	Painting guard bars gats iron bars grating railing including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	435.00	Sft Rs. 1270.83	%Sft Rs.	5,528.11
<b>Total:-</b>					<b>Rs. 738910</b>

Signature of Contractor / Bidder

  
Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi



S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
General Abstract					

## Composite Schedule Items.

### (a) Civil Works

(i) Schdule Items Rs. 738,910

Add: / Deducted ..... % Above / Below Premium Rs. ....

Total Civil Work Rs.


### Non-Schedule Item / Item Based Item.

Add: / Deducted ..... % Above / Below Premium Rs. ....

Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
 Executive Engineer  
 Minorities Affairs, Sindh  
 Hyderabad @ Karachi

## BILL OF QUANTITIES / SCHEDULE-B

30- Construction of Lavatory Blocks @ Church of Kotri & Shiv Mandir Hyderabad

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
<b>(a) Civil Works.</b>					
<b>(i) Schedule Items.</b>					
1	Excavation in Foundation of Building Bridges & Other Structure i/c Dagbelling Dressing Refilling around Structure with Excavated Earth Watering & Ramming Lead up to 5' (b) In Ordinary Soil (S.I. No:- 18 (b) / P-4).	1273.13	Cft Rs.	3176.25	%0Cft Rs. 4,043.76
2	Cement Concrete Brick or Stone Ballast 1-1/2" to 2" Gauge (b) Ratio 1:4:8 (S.I.No:- 4 (b) / P-15).	181.88	Cft Rs.	9416.28	%Cft Rs. 17,125.86
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e)	509.22	Cft Rs.	11948.36	%Cft Rs. 60,843.71
4	Reinforced Cement Concrete Work including All Labour & Material Except The Cost of Steel Reinforcement & its Labour for Bending & Binding which will be Paid Separately. This Rate also includes All Kind of Forms Moulds, Lifting, Shuttering, Curing, Rendering & Finishing the Exposed Surface (Including Screening & Washing of Shingle) (a) R.C. Work in Roof Slab, Beams, Columns Rafts, Lintels & Other Structural Members Laid in Situ or Precast Laid in Position Complete in All Respects (I) Ratio (1:2:4) 90 lbs Cement. 2 Cft Sand. 4 Cft Shingle	214.59	Cft Rs.	337.00	P.Cft Rs. 72,318.09
5	Fabrication of Mild Steel Reinforcement for Cement Concrete including Cutting, Bending, Laying in Position, Making Joints & Fastenings including Cost of Binding Wire (Also Includes Removal of Rust from Bars) (b) TOR Steel Bar (S.I.No:- 8 (b) / P-17).	9.388	Cwt Rs.	5001.70	P.Cwt Rs. 46,958.34
6	Filling Watering & Ramming Earth in Floor with Surplus Earth from Foundation Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 21 / P-5).	848.75	Cft Rs.	1512.50	%0Cft Rs. 1,283.73
7	Filling Watering & Ramming Earth under Floor with New Earth Excavated from Outside Lead up to One Chain & Lift up to 5' Feet (S.I. No:- 22 / P-5).	425.25	Cft Rs.	3630.00	%0Cft Rs. 1,543.66
8	Extra Lead 10 miles	425.25	Sft Rs.	902.20	%Sft Rs. 3,836.61
9	Cement Concrete Brick or Stone Ballast 1-1/2" Thick to 2" Gauge (c) Ratio 1:5:10 (S.I. No:- 4	60.75	Cft Rs.	8694.25	%Cft Rs. 5,281.76
10	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	668.25	Cft Rs.	12674.36	%Cft Rs. 84,696.41
11	S/F T-Iron at Site of Work	8.984	Cwt Rs.	3575.00	P.Cwt Rs. 32,117.54
12	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	216.00	Sft Rs.	7607.25	%Sft Rs. 16,431.66
13	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	216.00	Sft Rs.	10.70	P. Sft. Rs. 2,311.20
14	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2151.00	Sft Rs.	2206.60	%Sft Rs. 47,463.97
15	Cement Plaster 1:4 Upto 20' Height 3/8" Thick (S.I.No:- 11 (a) / P-52).	815.00	Sft Rs.	2197.52	%Sft Rs. 17,909.79

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
16	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone aggregate without shuttering Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	20.66	Cft Rs.	14429.25	%Cft Rs. 2,980.36
17	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	99.00	Rft Rs.	228.90	P.Rft Rs. 22,661.10
18	First Class Deodar Wood Wrought Joinery in Doors & Windows etc Fixed in Position including Chowkhats, Hold Fast Hinges, Iron Tower Bolts, Chocks Cleats, Handles & Cords with Hooks etc. Deodar Panelled or Panelled & Glazed or Fully Glazed (b) 1-3/4" Thick (S.I.No. 7 (b) / P-58).	105.00	Sft. Rs.	902.93	P. Sft. Rs. 94,807.65
19	Laying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I.No. 24 P-43)	121.50	Sft Rs.	27678.86	%Sft Rs. 33,629.81
20	White Glazed Tile 1/4" Thick Dado Jointed in White Cement & Laid over 1:2 Cement Sand Mortar 3/4" Thick including Finsihing (S.I. No:-	279.00	Sft Rs.	28253.61	%Sft Rs. 78,827.57
21	White wash three coats (C.S.I No:26 (c) P-54)	121.50	Sft Rs.	829.95	%Cft Rs. 1,008.39
22	Painting new surface © perparing new surface & painting of doors & window any types (including edges) (ii) each subsequent of paint (S.I.No.5 (c)	210.00	Sft. Rs.	2116.41	%Sft Rs. 4,444.46
23	Paerpairing the Surface and painting with matt finish i/c rubbing the surface with arhy (Slicion Carbide) rubbing brick filling the voids with zink / chalk / plaster of pairs mixture applying first coat premix making the surface smooth an then painting 3 cotas with matt finish approved make etc complete (new surface ) (C.S.I No:36 P-55).	815.00	Sft. Rs.	3444.38	%Sft Rs. 28,071.70
24	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	1053.00	Sft Rs.	1270.83	%Sft Rs. 13,381.84

**Total:- Rs. 693979**

**Signature of Contractor / Bidder**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
---------	--------------	-----------	-------	-------	---------

**(b) Water Supply & Sanitary Fittings.**

**(i) Schedule Items.**

1	Providing & fixing squatting type white glazed of flush cistern with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumble. (S.I No:1 (h) i P-No:1)	6.00	Nos.	Rs. 4802.60	Each	Rs. 28,815.60
2	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & l/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or c.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	3.00	Nos.	Rs. 4253.70	Each	Rs. 12,761.10
3	Add: extra labour for providing and fixing of earthen wire pedestal white or colored glass standard pattern (S.I No:9 P-No:3).	3.00	Nos.	Rs. 938.47	Each	Rs. 2,815.41
4	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	6.00	Nos.	Rs. 447.15	Each	Rs. 2,682.90
5	P/F 6" x 4" c.c gully trap with 4" dia out let complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb c.I caning 6" x 6" and c.I cover and frame 12" x 12" in side etc complete. (S.I No:1(a-i) P-No:21).	3.00	Nos.	Rs. 1193.17	Each	Rs. 3,579.51
6	RCC pipe with collar class "B" and bedding the tranches to the required depth and fixing in position l/c cutting fitting and jointing with max phalt composition and cement mortar 1:1 and testing with water pressure to head of 4 Ft above the top of the height	100.00	Rft	Rs. 146.57	P.Rft	Rs. 14,657.00
	4" dia	100.00	Rft	Rs. 199.25	P.Rft	Rs. 19,925.00
	6" dia					
7	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & l/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	3.00	Nos.	Rs. 2042.43	Each	Rs. 6,127.29
8	Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking through walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zinc paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No 12)					

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
i	1/2" dia	100.00 Rft	Rs. 73.21	P.Rft	Rs. 7,321.00
ii	3/4" dia	100.00 Rft	Rs. 95.79	P.Rft	Rs. 9,579.00
iii	1" dia	100.00 Rft	Rs. 128.55	P.Rft	Rs. 12,855.00
vi	1-1/4" dia	100.00 Rft	Rs. 153.19	P.Rft	Rs. 15,319.00
9	Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement motor etc Complete				
	1/2" dia	100.00 Rft	Rs. 7.82	P.Rft	Rs. 782.00
	3/4" dia	100.00 Rft	Rs. 8.45	P.Rft	Rs. 845.00
10	Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standard pattern (Note standard Manufacture by M/S Anwar Mechanical works. (S.I No:4 (b) P-No:17).				
	1/2" dia	6.00 Nos.	Rs. 161.92	Each	Rs. 971.52
	3/4" dia	6.00 Nos.	Rs. 227.92	Each	Rs. 1,367.52
11	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	6.00 Nos.	Rs. 478.28	Each	Rs. 2,869.68
12	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	3.00 Nos.	Rs. 1109.46	Each	Rs. 3,328.38
13	S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	3.00 Nos.	Rs. 2882.00	Each	Rs. 8,646.00
14	S/F Swan type Pillars Cock of supreior quality with arvstal Head.	3.00 Nos.	Rs. 795.30	Each	Rs. 2,385.90
15	Supplying & fixing Bath room accessories set (7 pieces I/c towel rod, brush hloder, soap tray, shelf of approved quality and design etc complete. (Si No: 22 P-No:19)	3.00 Nos.	Rs. 8122.40	Each	Rs. 24,367.20
16	P/F handle values (China) (S.I No:7 P-No:14).				
i	1/2" dia	6.00 Nos.	Rs. 271.92	Each	Rs. 1,631.52
ii	3/4" dia	6.00 Nos.	Rs. 365.42	Each	Rs. 2,192.52
17	Supplying & fixing fibre glass tank of approved quality and design and wall thickness as specified I/c cost of nutes, bolts and fixing in plateform of cement concreete 1: 3: 6 and makin connections for in -let ,& ou-let & over flow pipes etc. complete.				
A	250 Gallons	1.00 Nos.	Rs. 21989.61	Each	Rs. 21,989.61

**Total:-**

**Rs. 207815**

**Contractor**

**Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi**

S. No:-	Description.	Quantity.	Rate.	Unit.	Amount.
------------	--------------	-----------	-------	-------	---------

## General Abstract

### Composite Schedule Items.

#### (a) Civil Works

(i) Schedule Items Rs. 693,979

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.

#### (b) Water Supply & Sanitary Fittings

(i) Schedule Items Rs. 207,815

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Civil Work Rs.


### Non-Schedule Item / Item Based Item.

Rs.

Add: / Deducted ..... % Above / Below Premium Rs. ....  
Total Non-Schedule Item Rs.

Total Bid Amount Rs.

Signature of Contractor / Bidder

  
Executive Engineer  
Minorities Affairs, Sindh  
Hyderabad @ Karachi