

OFFICE OF THE  
EXECUTIVE ENGINEER EDUCATION WORKS DIVISION, KASHMORE-KANDHKOT

Govt. Boys High School, Boys College, College Road, Jacobabad- email: ew.jacobabad@gmail.com

No. XEN(EWD)/TC/G-55/1096

Kandhkot, Dated

19.04.2018

To,

The Director (information),  
Advertisement  
Government of Sindh,  
Karachi.

Subject: - **PUBLICATION OF CORRIGENDUM.**

Kindly find enclosed herewith a copy of Corrigendum with a request to please get it published in 3-leading Newspapers viz: Sindh, Urdu and English, as required under SPPRA Rules 2010.

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE-KANDHKOT

cc to:

✓

The Managing Director, Sindh Public Procurement Regulatory Authority, Planning and Development Department Government of Sindh, Karachi with a request to kindly hoist the Corrigendum on authority's website (copy enclosed).

The Secretary (Focal Person), Information Technology Department, Government of Sindh, New Sindh Secretariat 1<sup>st</sup> Floor, Karachi with a request kindly to float the Corrigendum on website of Sindh Government, please (copy enclosed).

EXECUTIVE ENGINEER

8324  
20.04.2018

OFFICE OF THE  
EXECUTIVE ENGINEER EDUCATION WORKS DIVISION, KASHMORE-KANDHKOT

(Near Nadra Office Kandhkot, email: [ewd.kashmore@gmail.com](mailto:ewd.kashmore@gmail.com))

No. XEN(EWD)/TC/G-55/1096

Kandhkot, Dated

19/04/2018

**CORRIGENDUM**

Due to posting of Executive Engineer, Education Works (Elect:) Division, Larkano, the tenders/bid documents for the **only electrical works** mentioned at Package-1 to 19 of this office NIT No. XEN(EWD)/TC/G-55/1047 dated 30-03-2018, published in the newspaper "Daily Awami Awaz " Sukkur dated 11-04-2018 and others, will be now issued by the Executive Engineer, Education Works (Elect:) Division, Larkano and the same will be opened in his office as per schedule given as under:

- i. **Issuance:** Documents will be issued from date of 1<sup>st</sup> publication in the newspapers & from date of hoisting on SPPRA Website up to **08-05-2018**
- ii. **Submission:** Last date will be **09-05-2018 up to 1:00 pm.**
- iii. **Opening:** will be opened on **09-05-2018 at 2:00 pm.**
- iv. **Un-responded tenders** will be again issued / submitted/opened on following dates.  
**2<sup>nd</sup> Attempt:** Issue date from: **10-05-2018** to **24-05-2018**  
Submission date: **25-05-2018** at 1:00 p.m  
Opening date: **25-05-2018** at 2:00 p.m

Other terms and conditions will remain the same as un-changed except following.

1. The works mentioned at Package No.1 to 19 may be treated for electrical works.
2. Valid registration with Inspectorate of Electrical License Larkana Region.

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE-KANDHKOT

*CFWCs to:*

1. The Chief Engineer, Education Works, Sukkur for favour of his kind information.
2. The Superintending Engineer, Education Works Circle, Larkano for favour of information and approval please.  
The Deputy Commissioner, Jacobabad for information.
3. The Director (Information), Advertisement Government of Sindh, Karachi along-with 03 extra copies for publication in the leading newspapers.
4. The Director (C.B) SPPRA, Planning and Development Department, GoS Karachi for posting NIT on website.
5. The Secretary (Focal Person), Information Technology Department, Govt. of Sindh, New Sindh Secretariat, 1<sup>st</sup> Floor, Karachi for floating tenders on website.
6. The Executive Engineer, Roads Division / Buildings Division, Jacobabad.
7. The Assistant Engineer, Education Works Sub-Division, Kashmore/Kandhkot Electrical Sub-Division Larkano for vide publicity.
8. The Member of Procurement Committee for information.
9. Copy to Divisional Accounts Officer/Draftsman/Establishment Branch/Notice Board (local)

  
**EXECUTIVE ENGINEER**



**OFFICE OF THE**  
**EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION KASHMORE KANDHKOT**  
**No. EE/EWD/SAC/1048 of 2018**  
**K'KOT, Dated: 30-3-2018**

To,


The Director (A&F),  
Sindh Public Regulatory Authority,  
**KARACHI.**

**SUBJECT: SUBMISSION OF THE NIT ALONG WITH RELEVANT DOCUMENTS FOR LOADING ON SPPRA WEBSITE.**

It is submitted that the required / relevant documents of this office NIT No. EE/EWD/TC/1047 dated 30.3.2018, (along with Softcopy) are submitted herewith for favour of your kind information and loading for hoisted on your official website.

Sr No.	Particular	Remarks
1.	Notice Inviting Tenders	Attached
2.	Bidding Documents / Bidding Data & Bill of Quantities	Attached
3.	Notification of Procurement Committee	Attached
4.	Notification of Compliant Redressal Committee	Attached
5.	Procurement Plan 2016-17	Attached

D/As.....Above

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

# PROCUREMENT PLAN 2017-18

## IN RESPECT OF EDUCATION WORKS DIVISION KASHMORE @ KANDHKOT

S.No	ADP No.	Name of Scheme	Estimated Cost	Source of Funds ADP / Non ADP	Proposed procurement method	Cost of New works	Funds for New works	Nature of procurement	Timing of procurement			
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr
1	2	3	4	5	6	7	8	9	10	11	12	13

**Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools).**


<b>Package No.1</b>		<b>1.815</b>	Provincial ADP	NCB	1.815	1.815
1	426010291	GBPS ADRESH				
2	426010242	GBPS SHAHBAZ KHAN NOONARI				
3	426010170	GBPS MEHAR DIL QAMBRANI				
4	426010064	GBPS NAWAB KHAN MANGRIO				
5	426010141	GGPS GHULAM HUSSAIN CHACHAR				
6	426030345	GBPS MIANI SOHRAB				
<b>Package No.2.</b>		<b>2.355</b>	Provincial ADP	NCB	2.355	2.355
7	426030346	GBPS KHAMISO KHAN OGAHI				
8	426010232	GBPS MUMTAZ ABAD				
9	426010158	GBPS MARKH KHAN BHAYO				
10	426010246	GBPS JAHAN KHAN BHANGWAR				
11	426030077	GBPS WAHID BIJARANI				
<b>Package No.3</b>		<b>2.915</b>	Provincial ADP	NCB	2.915	2.915
12	426010189	GBPS MIANI QAISER KHAN				
13	426010188	GBPS WAHID BUX BHAYO				
14	426030454	GBPS RISAL DAR				
15	426010129	GGPS AWAN MOHALLA KANDHKOT				
16	426010250	GBPS AHMEDAN BHANGWAR				
17	426010294	GBPS RAIS ALLAH BUX CHACHAR				
18	426010047	GBPS BASHIR ABAD				
<b>Package No.4</b>		<b>2.620</b>	Provincial ADP	NCB	2.620	2.620
19	426010219	GBPS MOHSIN SHAH				
20	426010216	GBPS ARBAB OGAHI				
21	426010231	GBPS WORK SHOP				
22	426010279	GBPS ABDUL KHALIQUE BANGWAR				
23	426010274	GBPS SYED MEHAR SHAH				
24	426030336	GBPS ALLAH WARAYO KHAN BAHALKANI				
<b>Package No.5</b>		<b>1.200</b>	Provincial ADP	NCB	1.200	1.200
25	426010219	GBPS MEER MUHAMMAD SUBZOI				
26	426010004	GBPS Mirzapur (Old)				
27	426010032	GBLSS MIRZAPUR NEW				
28	426010007	GBPS MAQBOOL AHMED SOOMRO				
29	426010295	GBPS GHULAM HUSSAIN CHACHAR				
<b>Package No.6</b>		<b>1.500</b>	Provincial ADP	NCB	1.500	1.500
30	426030229	GBPS HAJI KHAIR MUHAMMAD				
31	426030286	GBPS HAMZO KHAN OGAHI				
32	426030263	GBPS MUHAMMAD IBRAHIM KHAN BAJKANI				
33	426010270	GBPS LAL BUX LASHARI				
34	426010272	GBPS DODO KHAN NASIRANI @ MIR AHMED NASEERANI				
<b>Package No.7</b>		<b>2.000</b>	Provincial ADP	NCB	2.000	2.000
35	426030391	GBPS GUL MUHAMMAD BIJARANI				

**Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools).**

<b>Package No.1</b>		0.454	0.454	0.454	0.454
1	426010291	GBPS ADRESH			
2	426010242	GBPS SHAHBAZ KHAN NOONARI			
3	426010170	GBPS MEHAR DIL QAMBRANI			
4	426010064	GBPS NAWAB KHAN MANGRIO			
5	426010141	GGPS GHULAM HUSSAIN CHACHAR			
6	426030345	GBPS MIANI SOHRAB			
<b>Package No.2.</b>		0.589	0.589	0.589	0.589
7	426030346	GBPS KHAMISO KHAN OGAHI			
8	426010232	GBPS MUMTAZ ABAD			
9	426010158	GBPS MARKH KHAN BHAYO			
10	426010246	GBPS JAHAN KHAN BHANGWAR			
11	426030077	GBPS WAHID BIJARANI			
<b>Package No.3</b>		0.729	0.729	0.729	0.729
12	426010189	GBPS MIANI QAISER KHAN			
13	426010188	GBPS WAHID BUX BHAYO			
14	426030454	GBPS RISAL DAR			
15	426010129	GGPS AWAN MOHALLA KANDHKOT			
16	426010250	GBPS AHMEDAN BHANGWAR			
17	426010294	GBPS RAIS ALLAH BUX CHACHAR			
18	426010047	GBPS BASHIR ABAD			
<b>Package No.4</b>		0.655	0.655	0.655	0.655
19	426010219	GBPS MOHSIN SHAH			
20	426010216	GBPS ARBAB OGAHI			
21	426010231	GBPS WORK SHOP			
22	426010279	GBPS ABDUL KHALIQUE BANGWAR			
23	426010274	GBPS SYED MEHAR SHAH			
24	426030336	GBPS ALLAH WARAYO KHAN BAHALKANI			
<b>Package No.5</b>		0.300	0.300	0.300	0.300
25	426010219	GBPS MEER MUHAMMAD SUBZOI			
26	426010004	GBPS Mirzapur (Old)			
27	426010032	GBLSS MIRZAPUR NEW			
28	426010007	GBPS MAQBOOL AHMED SOOMRO			
29	426010295	GBPS GHULAM HUSSAIN CHACHAR			
<b>Package No.6</b>		0.375	0.375	0.375	0.375
30	426030229	GBPS HAJI KHAIR MUHAMMAD			
31	426030286	GBPS HAMZO KHAN OGAHI			
32	426030263	GBPS MUHAMMAD IBRAHIM KHAN BAJKANI			
33	426010270	GBPS LAL BUX LASHARI			
34	426010272	GBPS DODO KHAN NASIRANI @ MIR AHMED NASEERANI			
<b>Package No.7</b>		0.500	0.500	0.500	0.500
35	426030391	GBPS GUL MUHAMMAD BIJARANI			

S.No	ADP No.	Name of Scheme	Estimated Cost	Source of Funds ADP / Non ADP	Proposed procurement method	Cost of New works	Funds for New works	Nature of procurement	Timing of procurement			
									1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.
1	2	3	4	5	6	7	8	9	10	11	12	13
36	426030261	GBPS JHANDO KHAN JAFFERI						36 426030261 GBPS JHANDO KHAN JAFFERI				
37	426030354	GBPS MAHMOOD KHAN BIJARANI						37 426030354 GBPS MAHMOOD KHAN BIJARANI				
38	412030461	GBPS MIR HAZAAR KHAN BIJARANI						38 412030461 GBPS MIR HAZAAR KHAN BIJARANI				
39	426030348	GBPS KARIM KHAN BIJARANI						39 426030348 GBPS KARIM KHAN BIJARANI				
40	426030472	GBPS PIR JAN						40 426030472 GBPS PIR JAN				
41	426030516	GBPS MOLVI MUHAMMAD SALEH MALIK (BR)						41 426030516 GBPS MOLVI MUHAMMAD SALEH MALIK (BR)				
42	426030523	GBPS HAJI SHERAL MALIK						42 426030523 GBPS HAJI SHERAL MALIK				
	<b>Package No.8</b>		<b>0.680</b>	Provincial ADP	NCB	0.680	0.680	<b>Package No.8</b>	0.170	0.170	0.170	0.170
43	426030302	GBPS AIT BAR BROHI						43 426030302 GBPS AIT BAR BROHI				
44	426030297	GBPS PARTO MALIK						44 426030297 GBPS PARTO MALIK				
45	426030499	GBPS WAHID BUX JAFFERY						45 426030499 GBPS WAHID BUX JAFFERY				
46	426010256	GBPS HAZOOR BUX OGAHI						46 426010256 GBPS HAZOOR BUX OGAHI				
47	426020177	GGPS ABDUL BARI KHOSO						47 426020177 GGPS ABDUL BARI KHOSO				
48	426030056	GBPS MIR MEHRAN KHAN						48 426030056 GBPS MIR MEHRAN KHAN				
	<b>Package No.9</b>		<b>1.800</b>	Provincial ADP	NCB	1.800	1.800	<b>Package No.9</b>	0.450	0.450	0.450	0.450
49	426030102	GBPS MEHBOOB OGAHI						49 426030102 GBPS MEHBOOB OGAHI				
50	426030435	GBPS JANIB LASHARI						50 426030435 GBPS JANIB LASHARI				
51	426030576	GBLSS NOOR MUHAMMAD JAMALI						51 426030576 GBLSS NOOR MUHAMMAD JAMALI				
52	426020140	GBPS FIDA HUSSAIN SOOMRO						52 426020140 GBPS FIDA HUSSAIN SOOMRO				
	<b>Package No.10</b>		<b>1.335</b>	Provincial ADP	NCB	1.335	1.335	<b>Package No.10</b>	0.334	0.334	0.334	0.334
53	426020277	GBPS DIN MUHAMMAD DASTI						53 426020277 GBPS DIN MUHAMMAD DASTI				
54	426020023	GBPS ZANGI JAKHRANI						54 426020023 GBPS ZANGI JAKHRANI				
55	426020455	GBPS MUHAMMAD MOOSA NAICH						55 426020455 GBPS MUHAMMAD MOOSA NAICH				
56	426020426	GBPS BADANI NO: II						56 426020426 GBPS BADANI NO: II				
57	426020402	GBPS LASHKAR KHAN						57 426020402 GBPS LASHKAR KHAN				
	<b>Package No.11</b>		<b>1.313</b>	Provincial ADP	NCB	1.313	1.313	<b>Package No.11</b>	0.328	0.328	0.328	0.328
58	426020109	GBPS ABDUL HAMEED KHOSO						58 426020109 GBPS ABDUL HAMEED KHOSO				
59	426020099	GBPS RAIS MUHAMMAD UMER BHUTTO						59 426020099 GBPS RAIS MUHAMMAD UMER BHUTTO				
60	426030505	GBPS ABDUL WAHID KHOSO						60 426030505 GBPS ABDUL WAHID KHOSO				
61	426020414	GBPS DILSHAD JAKHRANI						61 426020414 GBPS DILSHAD JAKHRANI				
62	426020495	GBPS ALAW UD DIN KHOSO						62 426020495 GBPS ALAW UD DIN KHOSO				
63	426020255	GBPS FATEH MUHAMMAD MACHI COLONY						63 426020255 GBPS FATEH MUHAMMAD MACHI COLONY				
64	426020299	GBPS ALTAF HUSSAIN NO.II						64 426020299 GBPS ALTAF HUSSAIN NO.II				
	<b>Package No.12</b>		<b>1.158</b>	Provincial ADP	NCB	1.158	1.158	<b>Package No.12</b>	0.290	0.290	0.290	0.290
65	426020047	GBPS MOLI JO DARO						65 426020047 GBPS MOLI JO DARO				
66	426020442	GBPS NASSAR UD DIN KHOSO						66 426020442 GBPS NASSAR UD DIN KHOSO				
67	426020307	GBPS LAL BUX CHACHAR						67 426020307 GBPS LAL BUX CHACHAR				
68	426020074	GBPS HAZOOR BUX LANJWANI						68 426020074 GBPS HAZOOR BUX LANJWANI				
69	426020254	GBPS ABDULLAH BHATTI						69 426020254 GBPS ABDULLAH BHATTI				
	<b>Package No.13</b>		<b>1.402</b>	Provincial ADP	NCB	1.402	1.402	<b>Package No.13</b>	0.351	0.351	0.351	0.351
70	426020187	GGPS COLONY NO 1 KASHMORE						70 426020187 GGPS COLONY NO 1 KASHMORE				
71	426020368	GBPS COLONY NO 1 KASHMORE						71 426020368 GBPS COLONY NO 1 KASHMORE				
72	426020500	GBPS SYED ZULFIQAR ALI SHAH						72 426020500 GBPS SYED ZULFIQAR ALI SHAH				
	<b>Package No.14</b>		<b>2.200</b>	Provincial ADP	NCB	2.200	2.200	<b>Package No.14</b>	0.550	0.550	0.550	0.550
73	426020529	GBPS GHULAM HYDER KHAN JAKHRANI						73 426020529 GBPS GHULAM HYDER KHAN JAKHRANI				
74	426020365	GBLSS BANHON LASHARI						74 426020365 GBLSS BANHON LASHARI				
75	426020160	GBPS MOLVI SHAH MURAD GOLO						75 426020160 GBPS MOLVI SHAH MURAD GOLO				

S.No	ADP No.	Name of Scheme	Estimated Cost	Source of Funds ADP / Non ADP	Proposed procurement method	Cost of New works	Funds for New works	Nature of procurement	Timing of procurement			
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr
1	2	3	4	5	6	7	8	9	10	11	12	13
76	426010306	GBPS MADARSAH MUHAMMADI						76 426010306 GBPS MADARSAH MUHAMMADI				
77	426010263	GBPS GBPS Dilijan @ Siddique Noonari						77 426010263 GBPS GBPS Dilijan @ Siddique Noonari				
78	426010405	GBPS GBPS Bebak @ Baloch Golato						78 426010405 GBPS GBPS Bebak @ Baloch Golato				
79	426020425	GBPS BADANI (MAIN)						79 426020425 GBPS BADANI (MAIN)				
<b>Package No.15</b>			<b>4.593</b>	Provincial ADP	NCB	4.593	4.593	<b>Package No.15</b>	1.148	1.148	1.148	1.148
80	426010223	GBPS JATOI CHACHAR						80 426010223 GBPS JATOI CHACHAR				
81	426010217	GBPS GHULAM RASOOL OGAHI						81 426010217 GBPS GHULAM RASOOL OGAHI				
82	426010282	GBPS TAHAFIZUL QURAN						82 426010282 GBPS TAHAFIZUL QURAN				
83	426010040	GBPS GHULAM MUHAMMAD KHOSO						83 426010040 GBPS GHULAM MUHAMMAD KHOSO				
84	426010048	GBPS GAMAN KHAN						84 426010048 GBPS GAMAN KHAN				
85	426010151	GBPS DOST ALI SUHRIYANI						85 426010151 GBPS DOST ALI SUHRIYANI				
86	426010142	GBPS MUHAMMAD SULEMAN CHIJAN						86 426010142 GBPS MUHAMMAD SULEMAN CHIJAN				
<b>Package No.16</b>			<b>2.478</b>	Provincial ADP	NCB	2.478	2.478	<b>Package No.16</b>	0.620	0.620	0.620	0.620
87	426020213	GGPS PANDHI KALWAR						87 426020213 GGPS PANDHI KALWAR				
88	426020367	GBPS PANDHI KALWAR						88 426020367 GBPS PANDHI KALWAR				
89	426020364	GBPS MADARSAH AHYA UL ULOOM						89 426020364 GBPS MADARSAH AHYA UL ULOOM				
90	426020162	GBPS SHER MUHAMAMD NAICH						90 426020162 GBPS SHER MUHAMAMD NAICH				
<b>Package No.17</b>			<b>1.303</b>	Provincial ADP	NCB	1.303	1.303	<b>Package No.17</b>	0.326	0.326	0.326	0.326
91	426020372	GBPS GUDDU						91 426020372 GBPS GUDDU				
92	426020191	GBPS GGPS Kashmore						92 426020191 GBPS GGPS Kashmore				
93	426020248	GBPS PIR ABDUL SATTAR SHAH						93 426020248 GBPS PIR ABDUL SATTAR SHAH				
94	426020251	GBPS ALI BUX SOLANGI						94 426020251 GBPS ALI BUX SOLANGI				
<b>SECONDARY / HIGHER SECONDARY SCHOOLS</b>								<b>SECONDARY / HIGHER SECONDARY SCHOOLS</b>				
<b>Package No.18</b>				Provincial ADP	NCB	0.000	0.000	<b>Package No.18</b>	0.000	0.000	0.000	0.000
95	426010348	GGHS - GHOU PUR	<b>2.875</b>					95 426010348 GGHS - GHOU PUR				
96	426030568	GGHS TANGWANI (CAMPUS)						96 426030568 GGHS TANGWANI (CAMPUS)				
<b>Package No.19</b>				Provincial ADP	NCB	0.000	0.000	<b>Package No.19</b>	0.000	0.000	0.000	0.000
97	426030586	GBHS - BALACH KHAN DAHANI	<b>3.650</b>					97 426030586 GBHS - BALACH KHAN DAHANI				
98	426030563	GBHS - SHERAN BHAYO (Campus)						98 426030563 GBHS - SHERAN BHAYO (Campus)				
99	426020547	GGHS - KASHMORE						99 426020547 GGHS - KASHMORE				
<b>COMMUNITY DEVELOPMENT PROGRAMME UNDER SUSTAINABLE GOALS 2017-18</b>								<b>COMMUNITY DEVELOPMENT PROGRAMME UNDER SUSTAINABLE GOALS 2017-18</b>				
		Construction of Shelterless Building for Village Jan Muhammad Khan Sabzoi U/C Doulatpur Taluka Kandhkot	2.000	CDP	NCB	2.000	2.000	Construction of Shelterless Building for Village Jan Muhammad Khan Sabzoi U/C Doulatpur Taluka Kandhkot	0.500	0.500	0.500	0.500
		Construction of Shelterless Building for Village Najamdin Khan Sabzoi U/C Wakro Taluka Kandhkot	2.000	CDP	NCB	2.000	2.000	Construction of Shelterless Building for Village Najamdin Khan Sabzoi U/C Wakro Taluka Kandhkot	0.500	0.500	0.500	0.500

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS  
DIVISION, KASHMORÉ @ KANDHKOT**

NO: XEN/EWD/TC/- 1047


OF 2018 Kashmore @K,kot

DATED: 30 / 3 /2018.

**NOTICE INVITING TENDERS**

Sealed tenders are invited on Standard Bidding Documents from interested contractors/firms for the following works as per SPPRA Rules 2010.

2. **Eligibility:** Valid Registration with Income Tax, Sales Tax, Sindh Revenue Board, Pakistan Engineering Council in relevant category and Inspectorate of Electrical License for electric works.
3. Method of Procurement (Single Stage Single Envelope).
4. **The Bid Security 5%** (five percent) of bid amount shall be submitted in the shape of call deposit / pay order issued from any scheduled Bank of Pakistan in favour of undersigned at the time of submission of bidding documents containing full name, complete address, telephone number, fax number & e-mail of the organization.
5. Bidder should submit Bank Statement showing salaries of the technical staff.
6. Undertaking on stamp paper of Rs. 200/- that firm is not involved in any litigation, abandonment of any work in the Department or previously black listed by the Government, Semi Government and Autonomous Bodies.
6. Undertaking regarding list of Partners/Partnership Deed with Director / Proprietor etc with complete information along with Power of Attorney / Sole Proprietor.
7. Only one firm/bidder will be allowed to participate for maximum 3 Nos. of Packages.
8. Undertaking on stamp paper that information submitted by Bidder / Firm is correct and if found misleading at any stage, the work awarded will be cancelled.
9. Bidding/Tender Documents:
  - 1) **Issuance:** Documents will be issued from date of 1st publication in the newspapers & from date of hoisting on SPPRA Website up to ~~19.04.2018~~ **19-4-18**
  - 2) **Submission:** Last date will be ~~19.04.2018~~ **19.04.2018 up to 01:00 am.**
  - 3) **Opening:** will be opened on ~~19.04.2018~~ **at 02:00 pm. 20-4-2018**
  - 4) **Un-responded tenders** will be again issued / submitted/opened on following dates. **26.5.2018 07.5.2018**
10. **Terms & Conditions:**
  - a. Under following conditions bid will be rejected:-
    - i. Conditional, In-complete and telegraphic bids/tenders.
    - ii. Bids not accompanied by bid security and form.
    - iii. Bids received after specified date and time.
    - iv. Bids of black listed firms.
    - v. Bids received without information of technical staff working with firm.
    - vi. Bids received without list of Machinery & Equipment available with documentary evidence of its ownership & certificate of Bank showing the credit worthiness along with Bank Statement.
  - b. If the undersigned or any member of the Procurement Committee remains out of head quarter on date of opening of tenders, the same will be opened on the next working day at the same time as mentioned above.
  - c. The bidder must submit Bank Certificate showing the actual name of Bidder/Firm maintaining his/their account therein.
  - d. Procuring Agency reserves the right to reject all or any bids subject to the relevant provisions of Sindh Public Procurement Rules 2010.

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORÉ @ KANDHKOT

## LIST OF WORKS

SN O.	SIMIS CODE		NAME OF SCHEMES / LOCATION	TALUKA	ESTIMATED IN MILLION COST	EARNEST MONY IN MILLION	TENDER FEE IN RUPEES	TIME ALLOWED
<b>Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary &amp; Elementary Schools).</b>								
<b>Package No.1</b>					<b>1.815</b>	<b>0.091</b>	<b>3000</b>	<b>4 Months</b>
1	426010291	GBPS	ADRESH	K'Kot				
2	426010242	GBPS	SHAHBAZ KHAN NOONARI	do				
3	426010170	GBPS	MEHAR DIL QAMBRANI	do				
4	426010064	GBPS	NAWAB KHAN MANGRIO	do				
5	426010141	GGPS	GHULAM HUSSAIN CHACHAR	do				
6	426030345	GBPS	MIANI SOHRAB	do				
<b>Package No.2.</b>					<b>2.355</b>	<b>0.118</b>	<b>3000</b>	<b>4 Months</b>
7	426030346	GBPS	KHAMISO KHAN OGAHI	K'Kot				
8	426010232	GBPS	MUMTAZ ABAD	do				
9	426010158	GBPS	MARKH KHAN BHAYO	do				
10	426010246	GBPS	JAHAN KHAN BHANGWAR	do				
11	426030077	GBPS	WAHID BIJARANI	do				
<b>Package No.3</b>					<b>2.915</b>	<b>0.146</b>	<b>3000</b>	<b>4 Months</b>
12	426010189	GBPS	MIANI QAISER KHAN	K'Kot				
13	426010188	GBPS	WAHID BUX BHAYO	do				
14	426030454	GBPS	RISAL DAR	do				
15	426010129	GGPS	AWAN MOHALLA KANDHKOT	do				
16	426010250	GBPS	AHMEDAN BHANGWAR	do				
17	426010294	GBPS	RAIS ALLAH BUX CHACHAR	do				
18	426010047	GBPS	BASHIR ABAD	do				
<b>Package No.4</b>					<b>2.620</b>	<b>0.131</b>	<b>3000</b>	<b>4 Months</b>
19	426010219	GBPS	MOHSIN SHAH	K'Kot				
20	426010216	GBPS	ARBAB OGAHI	do				
21	426010231	GBPS	WORK SHOP	do				
22	426010279	GBPS	ABDUL KHALIQUE BANGWAR	do				
23	426010274	GBPS	SYED MEHAR SHAH	do				
24	426030336	GBPS	ALLAH WARAYO KHAN BAHALKANI	do				
<b>Package No.5</b>					<b>1.200</b>	<b>0.060</b>	<b>3000</b>	<b>4 Months</b>
25	426010219	GBPS	MEER MUHAMMAD SUBZOI	K'Kot				
26	426010004	GBPS	Mirzapur (Old)	do				
27	426010032	GBLSS	MIRZAPUR NEW	do				
28	426010007	GBPS	MAQBOOL AHMED SOOMRO	do				
29	426010295	GBPS	GHULAM HUSSAIN CHACHAR	do				
<b>Package No.6</b>					<b>1.500</b>	<b>0.075</b>	<b>3000</b>	<b>4 Months</b>
30	426030229	GBPS	HAJI KHAIR MUHAMMAD	T'gwani				
31	426030286	GBPS	HAMZO KHAN OGAHI	do				
32	426030263	GBPS	MUHAMMAD IBRAHIM KHAN BAJKANI	do				
33	426010270	GBPS	LAL BUX LASHARI	do				



34	426010272	GBPS	DODO KHAN NASIRANI @ MIR AHMED NASEERANI	K.Kot				
			<b>Package No.7</b>		<b>2.000</b>	<b>0.100</b>	<b>3000</b>	<b>4 Months</b>
35	426030391	GBPS	GUL MUHAMMAD BIJARANI	T'gwani				
36	426030251	GBPS	JHANDO KHAN JAFFERI	do				
37	426030354	GBPS	MAHMOOD KHAN BIJARANI	do				
38	412030461	GBPS	MIR HAZAAR KHAN BIJARANI	do				
39	426030348	GBPS	KARIM KHAN BIJARANI	do				
40	426030472	GBPS	PIR JAN	do				
41	426030516	GBPS	MOLVI MUHAMMAD SALEH MALIK (BR)	do				
42	426030523	GBPS	HAJI SHERAL MALIK	do				
			<b>Package No.8</b>		<b>0.680</b>	<b>0.034</b>	<b>3000</b>	<b>4 Months</b>
43	426030302	GBPS	AIT BAR BROHI	T'gwani				
44	426030297	GBPS	PARTO MALIK	do				
45	426030499	GBPS	WAHID BUX JAFFERY	do				
46	426010256	GBPS	HAZOOR BUX OGAHI	do				
47	426020177	GGPS	ABDUL BARI KHOSO	do				
48	426030056	GBPS	MIR MEHRAN KHAN	do				
			<b>Package No.9</b>		<b>1.800</b>	<b>0.090</b>	<b>3000</b>	<b>4 Months</b>
49	426030102	GBPS	MEHBOOB OGAHI	T'gwani				
50	426030435	GBPS	JANIB LASHARI	do				
51	426030576	GBLSS	NOOR MUHAMMAD JAMALI	do				
52	426020140	GBPS	FIDA HUSSAIN SOOMRO	do				
			<b>Package No.10</b>		<b>1.335</b>	<b>0.067</b>	<b>3000</b>	<b>4 Months</b>
53	426020277	GBPS	DIN MUHAMMAD DASTI	K'More				
54	426020023	GBPS	ZANGI JAKHRANI	do				
55	426020455	GBPS	MUHAMMAD MOOSA NAICH	do				
56	426020426	GBPS	BADANI NO: II	do				
57	426020402	GBPS	LASHKAR KHAN	do				
			<b>Package No.11</b>		<b>1.313</b>	<b>0.066</b>	<b>3000</b>	<b>4 Months</b>
58	426020109	GBPS	ABDUL HAMEED KHOSO	K'More				
59	426020099	GBPS	RAIS MUHAMMAD UMER BHUTTO	do				
60	426030505	GBPS	ABDUL WAHID KHOSO	do				
61	426020414	GBPS	DILSHAD JAKHRANI	do				
62	426020495	GBPS	ALAW UD DIN KHOSO	do				
63	426020255	GBPS	FATEH MUHAMMAD MACHI COLONY	do				
64	426020299	GBPS	ALTAF HUSSAIN NO.II	do				
			<b>Package No.12</b>		<b>1.158</b>	<b>0.058</b>	<b>3000</b>	<b>4 Months</b>
65	426020047	GBPS	MOLI JO DARO	K'More				
66	426020442	GBPS	NASSAR UD DIN KHOSO	K'More				
67	426020307	GBPS	LAL BUX CHACHAR	do				
68	426020074	GBPS	HAZOOR BUX LANJWANI	do				
69	426020254	GBPS	ABDULLAH BHATTI	do				
			<b>Package No.13</b>		<b>1.402</b>	<b>0.070</b>	<b>3000</b>	<b>4 Months</b>
70	426020187	GGPS	COLONY NO 1 KASHMORE	K'More				
71	426020368	GBPS	COLONY NO 1 KASHMORE	do				
72	426020500	GBPS	SYED ZULFIQAR ALI SHAH	do				
			<b>Package No.14</b>		<b>2.200</b>	<b>0.110</b>	<b>3000</b>	<b>4 Months</b>

73	426020529	GBPS	GHULAM HYDER KHAN JAKHRANI	K'More				
74	426020365	GBLSS	BANHON LASHARI	do				
75	426020160	GBPS	MOLVI SHAH MURAD GOLO	do				
76	426010306	GBPS	MADARSAH MUHAMMADI	do				
77	426010263	GBPS	GBPS Dilijan @ Siddique Noonari	do				
78	426010405	GBPS	GBPS Bebarak @ Baloch Golato	do				
79	426020425	GBPS	BADANI (MAIN)	do				
			<b>Package No.15</b>		<b>4.593</b>	<b>0.230</b>	<b>3000</b>	<b>4 Months</b>
80	426010223	GBPS	JATOI CHACHAR	K.Kot				
81	426010217	GBPS	GHULAM RASOOL OGAHI	do				
82	426010282	GBPS	TAHAFIZUL QURAN	do				
83	426010040	GBPS	GHULAM MUHAMMAD KHOSO	do				
84	426010048	GBPS	GAMAN KHAN	do				
85	426010151	GBPS	DOST ALI SUHRIYANI	do				
86	426010142	GBPS	MUHAMMAD SULEMAN CHIJAN	do				
			<b>Package No.16</b>		<b>2.478</b>	<b>0.124</b>	<b>3000</b>	<b>4 Months</b>
87	426020213	GGPS	PANDHI KALWAR	K'More				
88	426020367	GBPS	PANDHI KALWAR	do				
89	426020364	GBPS	MADARSAH AHYA UL ULOOM	do				
90	426020162	GBPS	SHER MUHAMAMD NAICH	do				
			<b>Package No.17</b>		<b>1.303</b>	<b>0.065</b>	<b>3000</b>	<b>4 Months</b>
91	426020372	GBPS	GUDDU	K'More				
92	426020191	GBPS	GGPS Kashmore	do				
93	426020248	GBPS	PIR ABDUL SATTAR SHAH	do				
94	426020251	GBPS	ALI BUX SOLANGI	do				

### SECONDARY / HIGHER SECONDARY SCHOOLS

			<b>Package No.18</b>		<b>2.875</b>	<b>0.144</b>	<b>3000</b>	<b>4 Months</b>
95	426010348	GGHS -	GHOUS PUR	K'Kot				
96	426030568	GGHS	TANGWANI (CAMPUS)	T'gwani				
			<b>Package No.19</b>		<b>3.650</b>	<b>0.183</b>	<b>3000</b>	<b>4 Months</b>
97	426030586	GBHS -	BALACH KHAN DAHANI	T'gwani				
98	426030563	GBHS -	SHERAN BHAYO (Campus)	do				
99	426020547	GGHS -	KASHMORE	K'More				

### COMMUNITY DEVELOPMENT PROGRAMME UNDER SUSTAINABLE

1			Construction of Shelterless Building for Village Jan Muhammad Khan Sabzoi U/C Doulatpur Taluka Kandhkot	K'Kot	2.000	0.100	3000	6 Months
2			Construction of Shelterless Building for Village Najamdin Khan Sabzoi U/C Wakro Taluka Kandhkot	K'Kot	2.000	0.100	3000	6 Months

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT



GOVERNMENT OF SINDH  
EDUCATION & LITERACY DEPARTMENT  
Karachi, date the 28-04-2015

## NOTIFICATION

NO.SO(G) EDU/E&A/PRO-EW/14-15: In pursuance of Rule – 7 of the Sindh Public Procurement Rules, 2010, a Departmental Procurement Committee comprising of following Officers for procurement of works for various Educational Institutes / Offices / Line Departments working under Administrative Control of Education & Literacy Department to be procured under ADP / Regular Budget / SNE of Education Department is constituted as under:-

- |   |          |
|---|----------|
| 1. Executive Engineer (Education Works)<br>Concerned Education Works Division<br>Education & Literacy Department                    | Chairman |
| 2. Assistant Engineer<br>Local Government Public Health Engineering Department  | Member   |
| 3. Assistant Engineer (Education Works) of Headquarter<br>Concerned Education Works sub Division<br>Education & Literacy Department | Member   |

### ToRs

- Preparing bidding documents;
- Carrying out technical as well as financial evaluation of the bids;
- Preparing evaluation report as provided in Rule 45 of SPPRA 2010;
- Making recommendations for the award of contract to the competent authority; and
- Perform any other function ancillary and incidental to the above.


- DR. FAZLULLAH PECHUHO -  
SECRETARY TO GOVT. OF SINDH

NO.SO(G) EDU/E&A/PRO-EW/14-15:

Karachi, date the 28<sup>th</sup> May, 2015

A copy is forwarded for information & necessary action to:-

1. All Members of the Committee;
2. The P.S. to Senior Minister, Education & Literacy Department, Govt. of Sindh, Karachi.
3. The P.S to Secretary, Education & Literacy Department.
4. The P.S to Secretary, Local Government Public Health Engineering Department.
5. Office Order File



DEPUTY SECRETARY (GA)

## NOTIFICATION

GOVT(G) EDU/EA/PRO-EW(CRC)/14-15: In pursuance of Rule - 31 of the Sindh Public Procurement Rules, 2010 a Departmental Complaint Redressal Committee comprising of following Officers is constituted as under to resolve complaints of aggrieved bidders:-

- |  |          |
|--|----------|
| 1. Superintendent Engineer (Education Works) of concerned Education Works Circle Education & Literacy Department | Chairman |
| 2. Representative of District Account Officer / Accountant General, Sindh  | Member   |
| Representative of Head of procuring Agency (Professional from relevant field concerning)                         | Member   |

### ToRs

- To perform according to Rule - 31 of SPPRA, 2010;
- Perform any other function ancillary and incidental to the above.

SECRETARY EDUCATION  
TO GOVT. OF SINDH  
Karachi, date the 28<sup>th</sup> May, 2015


GOVT(G) EDU/EA/PRO-EW(CRC)/14-15:

A copy is forwarded for information & necessary action to:-

All Members of the Committee.

The P.S to Secretary, Education & Literacy Department.

Office Order File



DEPUTY SECRETARY (GA)


# **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS ADRESH, GBPS SHAHBAZ KHAN NOONARI, GBPS MEHAR DIL QAMBRANI, GBPS NAWAB KHAN MANGRIO, GBPS GHULAM HUSSAIN CHACHAR, MIANI SOHRAB, TALUKA KANDHKOT (PACKAGE NO. 1) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 1815000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS ADRESH, GBPS SHAHBAZ KHAN NOONARI, GBPS MEHAR DIL QAMBRANI, GBPS NAWAB KHAN MANGRIO, GBPS GHULAM HUSSAIN CHACHAR, MIANI SOHRAB, TALUKA KANDHKOT (PACKAGE NO. 1) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	234	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 129 P-15).	910	per point	212940
2	24	Wiring for plug point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 130 P-15).	742	per point	17808
3	1190	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. CSI No. 3 Page No. 1)	171	per Meter	203490
4	865	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:11 P- No:2)	252	per Meter	217980
5	675	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 (6mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:12 P- No:2)	341	per Meter	230175
6	46	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	Each	42136
7	7	207. Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required.	9261	P.No	64827
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	5760
9	70	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	4900
10	80	Providing & fixing junction box as per following specification Size of box 8"×6"×4"MS plate size 16 SWG thick Clamp with nuts & bolts Cover plate with screw Painting two coats of rust preventive red oxide & two coats of ICI oil paint as per site requirement & instruction of EI (SI No. 158 P-24)	800	P.No	64000
<b>TOTAL :-</b>					<b>1064016</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
 Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	234	P/F Flush Fancy type switch 10 amps i/c plastic board imported made etc complete. R.A Sanctioned By Chief Engineer		Each	
2	24	P/F Flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
3	11	P/F Flush type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
4	80	S/F A.C Ceiling fan 56" sweep pure copper winding i/c down rod canopy blade suitable double bearing inter electric connection with 3/0.29 PVC. R.A Sanctioned By Chief Engineer		Each	
5	80	S/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete. R.A Sanctioned By Chief Engineer		Each	
6	16	P/F distribution board double shutter to accommodate circuit breaker & bushar i/c painting with enamelled paint. R.A Sanctioned By Chief Engineer		Each	
7	7	P/F earthing set set (1x1) copper pate i/c excavation of rock earth 12" depth or if water comes out i/c salt/choracle mixed with G.I Rod with butts, blots testing topping etc complete. R.A Sanctioned By Chief Engineer		Each	
8	24	P/F wall / ceiling mounted light, fancy type, superior quality i/c necessary electric connection and with holder, without energy saver etc. R.A Sanctioned By Chief Engineer		Each	
9	154	P/F energy saver superior quality i/c fixing on existing holder etc complete. R.A Sanctioned By Chief Engineer		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
10	32	P/F L.E.D light 8" square/circle shop (09) watt in plastic cover fancy type (China make). R.A Sanctioned By Chief Engineer		Each	
<b>TOTAL :-</b>					

**Cost of Bid**


**Amount      Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS KHAMISO KHAN OGAHI, GBPS MUMTAZ ABAD, GBPS MARKH KHAN BHAYO, GBPS JAHAN KHAN BHANGWAR, GBPS WAHID BIJARANI TALUKA KANDHKOT (PACKAGE NO. 2) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2355000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT



**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS KHAMISO KHAN OGAHI, GBPS MUMTAZ ABAD, GBPS MARKH KHAN BHAYO, GBPS JAHAN KHAN BHANGWAR, GBPS WAHID BIJARANI TALUKA KANDHKOT (PACKAGE NO. 2) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	328	Wiring for light or fan point with 3/029 PVCinsulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	298480
2	58	Wiring for plug point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	43036
3	5	Wiring for call bell point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	7950
4	1237	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	211527
5	767	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/036 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	193284
6	395	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 copper conductor in 3/4" dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	120475
7	250	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/064 (16mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	151250
8	114	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	8208
9	216	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	15120
10	58	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	53128
11	9	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	49689
12	4	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	37044
13	579	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	217125
14	7	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	59185
<b>TOTAL :-</b>					<b>1465501</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	338	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	58	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	34	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	9	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	90	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	99	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	20.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	4	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	59	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	232	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	80	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	5	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	5	P/F flush type electric bell bush button		Each	
14		P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	3	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**


**Amount Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS MIANI QAISER KHAN, GBPS WAHID BUX BHAYO, GBPS RISAL DAR, GGPS AWAN MOHALLA KANDHKOT, GBPS AHMEDAN BHANGWAR, GBPS RAIS ALLAH BUX CHACHAR, GBPS BASHIR ABAD TALUKA KANDHKOT (PACKAGE NO. 3) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2915000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :-** Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS MIANI QAISER KHAN, GBPS WAHID BUX BHAYO, GBPS RISAL DAR, GGPS AWAN MOHALLA KANDHKOT, GBPS AHMEDAN BHANGWAR, GBPS RAIS ALLAH BUX CHACHAR, GBPS BASHIR ABAD TALUKA KANDHKOT (PACKAGE NO. 3) (Electrification)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	469	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4'') channel patti on surface as required (S.No. 129 P-15).	910	per point	426790
2	87	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	64554
3	10	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	15900
4	1742	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	297882
5	1235	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	311220
6	565	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	172325
7	114	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	68970
8	165	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	11880
9	318	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	22260
10	92	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	84272
11	18	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	99378
12	6	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	55566
13	566	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	212250
14	6	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of El. Make of the above light is as follow	8455	P.No	50730
<b>TOTAL :-</b>					<b>1893977</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	483	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	48	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	48	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4		P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	13	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	107	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	153	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	10	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	111	P/F- wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	338	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	94	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	9	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	9	P/F flush type electric bell bush button		Each	
14		P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	2	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS MOHSIN SHAH, GBPS ARBAB OGAHI, GBPS WORK SHOP, GBPS ABDUL KHALIQUE BANGWAR, GBPS SYED MEHAR SHAH, GBPS ALLAH WARAYO KHAN BAHALKANI TALUKA KANDHKOT (PACKAGE NO. 4) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2620000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS MOHSIN SHAH, GBPS ARBAB OGAHI, GBPS WORK SHOP, GBPS ABDUL KHALIQUE BANGWAR, GBPS SYED MEHAR SHAH, GBPS ALLAH WARAYO KHAN BAHALKANI TALUKA KANDHKOT (PACKAGE NO. 4) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	316	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 129 P-15).	910	per point	287560
2	23	Wiring for plug point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 130 P-15).	742	per point	17066
3	1650	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. CSI No. 3 Page No. 1)	171	per Meter	282150
4	1440	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:11 P- No:2)	252	per Meter	362880
5	1252	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 (6mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:12 P- No:2)	341	per Meter	426932
6	54	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	Each	49464
7	6	207. Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required.	9261	P.No	55566
8	115	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	8280
9	201	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	14070
10	115	Providing & fixing junction box as per following specification Size of box 8"×6"×4"MS plate size 16 SWG thick Clamp with nuts & bolts Cover plate with screw Painting two coats of rust preventive red oxide & two coats of ICI oil paint as per site requirement & instruction of EI (SI No. 158 P-24)	800	P.No	92000
<b>TOTAL :-</b>					<b>1595968</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
 Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	316	P/F Flush Fancy type switch 10 amps i/c plastic board imported made etc complete. R.A Sanctioned By Chief Engineer		Each	
2	23	P/F Flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
3	10	P/F Flush type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
4	115	S/F A.C Ceiling fan 56" sweep pure copper winding i/c down rod canopy blade suitable double bearing inter electric connection with 3/0.29 PVC. R.A Sanctioned By Chief Engineer		Each	
5	115	S/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete. R.A Sanctioned By Chief Engineer		Each	
6	13	P/F distribution board double shutter to accommodate circuit breaker & bushar i/c painting with enamelled paint. R.A Sanctioned By Chief Engineer		Each	
7	6	P/F earthing set set (1x1) copper pate i/c excavation of rock earth 12" depth or if water comes out i/c salt/choracle mixed with G.I Rod with butts, blots testing topping etc complete. R.A Sanctioned By Chief Engineer		Each	
8	20	P/F wall / ceiling mounted light, fancy type, superior quality i/c necessary electric connection and with holder, without energy saver etc. R.A Sanctioned By Chief Engineer		Each	
9	201	P/F energy saver superior quality i/c fixing on existing holder etc complete. R.A Sanctioned By Chief Engineer		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
10	42	P/F L.E.D light 8" square/circle shop (09) watt in plastic cover fancy type (China make). R.A Sanctioned By Chief Engineer		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT



## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS MEER MUHAMMAD SUBZOI, GBPS Mirzapur (Old), GBPS MIRZAPUR NEW, GBPS MAQBOOL AHMED SOOMRO, GBPS GHULAM HUSSAIN CHACHAR TALUKA KANDHKOT (PACKAGE NO. 5) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 1200000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS MEER MUHAMMAD SUBZOI, GBPS Mirzapur (Old), GBPS MIRZAPUR NEW, GBPS MAQBOOL AHMED SOOMRO, GBPS GHULAM HUSSAIN CHACHAR TALUKA KANDHKOT (PACKAGE NO. 5) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	224	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4'') channel patti on surface as required (S.No. 129 P-15).	910	per point	203840
2	42	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	31164
3	3	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	4770
4	478	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	81738
5	387	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	97524
6	220	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	67100
7	150	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	90750
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	5760
9	147	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	10290
10	38	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	34808
11	6	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	33126
12	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9261
13	436	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	163500
14	2	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	16910
<b>TOTAL :-</b>					<b>850541</b>

Amount Total (CSR)

Part "A"

% Above / Below \_\_\_\_\_

Total Amount \_\_\_\_\_

Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	224	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	46	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	19	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	4	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	47	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	86	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	12.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	1	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	40	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	171	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	62	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	3	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	3	P/F flush type electric bell bush button		Each	
14	2	P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	1	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.3.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS HAJI KHAIR MUHAMMAD, GBPS GHULAM HUSSAIN CHACHAR, HAMZO KHAN OGAHI, GBPS MUHAMMAD IBRAHIM KHAN BAJKANI, LAL BUX LASHARI, DODO KHAN NASIRANI @ MIR AHMED NASEERANI TALUKA TANGWANI (PACKAGE NO. 6) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 1500000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitation / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS HAJI KHAIR MUHAMMAD, GBPS GHULAM HUSSAIN CHACHAR, HAMZO KHAN OGAHI, GBPS MUHAMMAD IBRAHIM KHAN BAJKANI, LAL BUX LASHARI, DODO KHAN NASIRANI @ MIR AHMED NASEERANI TALUKA TANGWANI (PACKAGE NO. 6) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	150	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 129 P-15).	910	per point	136500
2	24	Wiring for plug point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 130 P-15).	742	per point	17808
3	800	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. CSI No. 3 Page No. 1)	171	per Meter	136800
4	600	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:11 P- No:2)	252	per Meter	151200
5	300	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 (6mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:12 P- No:2)	341	per Meter	102300
6	46	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	Each	42136
7	7	207. Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required.	9261	P.No	64827
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P-No:33)	72	P.No	5760
9	70	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	4900
10	80	Providing & fixing junction box as per following specification Size of box 8"x6"x4" MS plate size 16 SWG thick Clamp with nuts & bolts Cover plate with screw Painting two coats of rust preventive red oxide & two coats of ICI oil paint as per site requirement & instruction of EI (SI No. 158 P-24)	800	P.No	64000
<b>TOTAL :-</b>					<b>726231</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	234	P/F Flush Fancy type switch 10 amps i/c plastic board imported made etc complete. R.A Sanctioned By Chief Engineer		Each	
2	24	P/F Flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
3	11	P/F Flush type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
4	60	S/F A.C Ceiling fan 56" sweep pure copper winding i/c down rod canopy blade suitable double bearing inter electric connection with 3/0.29 PVC. R.A Sanctioned By Chief Engineer		Each	
5	60	S/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete. R.A Sanctioned By Chief Engineer		Each	
6	16	P/F distribution board double shutter to accommodate circuit breaker & bushar i/c painting with enemelled paint. R.A Sanctioned By Chief Engineer		Each	
7	7	P/F earthing set set (1x1) copper pate i/c excavation of rock earth 12" depth or if water comes out i/c salt/choracle mixed with G.I Rod with butts, blots testing topping etc complete. R.A Sanctioned By Chief Engineer		Each	
8	24	P/F wall / ceiling mounted light, fancy type, superior quality i/c necessary electric connection and with holder, without energy saver etc. R.A Sanctioned By Chief Engineer		Each	
9	154	P/F energy saver superior quality i/c fixing on existing holder etc complete. R.A Sanctioned By Chief Engineer		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
10	32	P/F L.E.D light 8" square/circle shop (09) watt in plastic cover fancy type (China make). R.A Sanctioned By Chief Engineer		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS GUL MUHAMMAD BIJARANI, GBPS JHANDO KHAN JAFFERI, GBPS MAHMOOD KHAN BIJARANI, GBPS MIR HAZAAR KHAN BIJARANI, KARIM KHAN BIJARANI, PIR JAN, MOLVI MUHAMMAD SALEH MALIK (BR), HAJI SHERAL MALIK, TALUKA TANGWANI (PACKAGE NO. EE/EWD/TC/1047)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2000000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

## BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :-** Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS GUL MUHAMMAD BIJARANİ, GBPS JHANDO KHAN JAFFERI, GBPS MAHMOOD KHAN BIJARANİ, GBPS MIR HAZAAR KHAN BIJARANİ, KARİM KHAN BIJARANİ, PIR JAN, MOLVI MUHAMMAD SALEH MALİK (BR), HAJI SHERAL MALİK, TALUKA TANGWANI (PACKAGE NO. 7) (Electrification)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	224	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4'') channel patti on surface as required (S.No. 129 P-15).	910	per point	203840
2	42	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	31164
3	3	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	4770
4	478	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	81738
5	387	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	97524
6	220	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	67100
7	150	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	90750
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	5760
9	147	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	10290
10	38	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	34808
11	6	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	33126
12	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9261
13	200	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	75000
14	2	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	16910
				<b>TOTAL :-</b>	<b>762041</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

### NON SCHEDULE ITEMS

1	224	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complete		Each	
2	46	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	19	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	4	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	40	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	86	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	



Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	12.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	1	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	40	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	171	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	62	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	3	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	3	P/F flush type electric bell bush button		Each	
14	2	P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	1	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS AIT BAR BROHI, GBPS PARTO MALIK, GBPS WAHID BUX JAFFERY, GBPS HAZOOR BUX OGAHI, GBPS ABDUL BARI KHOSO, GBPS MIR MEHRAN KHAN TALUKA TANGWANI (PACKAGE NO. 8) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 680000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS AIT BAR BROHI, GBPS PARTO MALIK, GBPS WAHID BUX JAFFERY, GBPS HAZOOR BUX OGAHI, GBPS ABDUL BARI KHOSO, GBPS MIR MEHRAN KHAN TALUKA TANGWANI (PACKAGE NO. 8) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	150	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4'') channel patti on surface as required (S.No. 129 P-15).	910	per point	136500
2	42	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	31164
3	3	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	4770
4	200	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	34200
5	150	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	37800
6	100	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	30500
7	50	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	30250
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	5760
9	147	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	10290
10	38	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	34808
11	6	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	33126
12	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9261
13	100	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	37500
14	2	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	16910
<b>TOTAL :-</b>					<b>452839</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	224	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	46	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	19	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	4	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	47	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	86	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	12.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	1	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	40	P/F- wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	171	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	62	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	3	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	3	P/F flush type electric bell bush button		Each	
14		P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15		P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS MEHBOOB OGAHI, GBPS JANIB LASHARI, GBLSS NOOR MUHAMMAD JAMALI, GBPS FIDA HUSSAIN SOOMRO TALUKA TANGWANI (PACKAGE NO. 9) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 1800000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

## BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :-** Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS MEHBOOB OGAHI, GBPS JANIB LASHARI, GBLSS NOOR MUHAMMAD JAMALI, GBPS FIDA HUSSAIN SOOMRO TALUKA TANGWANI (PACKAGE NO. 9) (Electrification)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	234	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 129 P-15).	910	per point	212940
2	24	Wiring for plug point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 130 P-15).	742	per point	17808
3	1190	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.No. 3 Page No. 1)	171	per Meter	203490
4	865	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:11 P- No:2)	252	per Meter	217980
5	675	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:12 P- No:2)	341	per Meter	230175
6	46	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	Each	42136
7	7	207. Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required.	9261	P.No	64827
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P-No:33)	72	P.No	5760
9	70	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	4900
10	80	Providing & fixing junction box as per following specification Size of box 8"x6"x4"MS plate size 16 SWG thick Clamp with nuts & bolts Cover plate with screw Painting two coats of rust preventive red oxide & two coats of ICI oil paint as per site requirement & instruction of EI (SI No. 158 P-24)	800	P.No	64000
<b>TOTAL :-</b>					<b>1064016</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

### **NON SCHEDULE ITEMS**

1	234	P/F Flush Fancy type switch 10 amps i/c plastic board imported made etc complete. R.A Sanctioned By Chief Engineer		Each	
2	24	P/F Flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
3	11	P/F Flush type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
4	80	S/F A.C Ceiling fan 56" sweep pure copper winding i/c down rod canopy blade suitable double bearing inter electric connection with 3/0.29 PVC. R.A Sanctioned By Chief Engineer		Each	
5	80	S/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete. R.A Sanctioned By Chief Engineer		Each	
6	16	P/F distribution board double shutter to accommodate circuit breaker & bushar i/c painting with enamelled paint. R.A Sanctioned By Chief Engineer		Each	
7	7	P/F earthing set set (1x1) copper pate i/c excavation of rock earth 12" depth or if water comes out i/c salt/choracle mixed with G.I Rod with butts, blots testing topping etc complete. R.A Sanctioned By Chief Engineer		Each	
8	24	P/F wall / ceiling mounted light, fancy type, superior quality i/c necessary electric connection and with holder, without energy saver etc. R.A Sanctioned By Chief Engineer		Each	
9	154	P/F energy saver superior quality i/c fixing on existing holder etc complete. R.A Sanctioned By Chief Engineer		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
10	32	P/F L.E.D light 8" square/circle shop (09) watt in plastic cover fancy type (China make). R.A Sanctioned By Chief Engineer		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**

**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS DIN MUHAMMAD DASTI, GBPS ZANGI JAKHRANI, GBPS MUHAMMAD MOOSA NAICH, GBPS BADANI NO: II, GBPS LASHKAR KHAN TALUKA KASHMORE (PACKAGE NO. 10) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 1335000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT



**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :-** Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS DIN MUHAMMAD DASTI, GBPS ZANGI JAKHRANI, GBPS MUHAMMAD MOOSA NAICH, GBPS BADANI NO: II, GBPS LASHKAR KHAN TALUKA KASHMORE (PACKAGE NO. 10) (Electrification)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	224	Wiring for light or fan point with 3/029 PVCinsulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	203840
2	42	Wiring for plug point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	31164
3	3	Wiring for call bell point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	4770
4	478	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	81738
5	387	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/036 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	97524
6	220	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 copper conductor in 3/4" dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	67100
7	150	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/064 (16mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	90750
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	5760
9	147	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	10290
10	38	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	34808
11	6	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	33126
12	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9261
13	436	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	163500
14	2	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of El. Make of the above light is as follow	8455	P.No	16910
<b>TOTAL :-</b>					<b>850541</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_

Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	224	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	46	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	19	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	4	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	47	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	86	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	12.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	1	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	40	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	171	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	62	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	3	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	3	P/F flush type electric bell bush button		Each	
14	2	P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	1	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS ABDUL HAMEED KHOSO, GBPS RAIS MUHAMMAD UMER BHUTTO, GBPS ABDUL WAHID KHOSO, GBPS DILSHAD JAKHRANI, GBPS ALAW UD DIN KHOSO, GBPS FATEH MUHAMMAD MACHI COLONY, GBPS ALTAF HUSSAIN NO.II TALUKA KASHMORE (PACKAGE NO. 11) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 1313000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS ABDUL HAMEED KHOSO, GBPS RAIS MUHAMMAD UMER BHUTTO, GBPS ABDUL WAHID KHOSO, GBPS DILSHAD JAKHRANI, GBPS ALAW UD DIN KHOSO, GBPS FATEH MUHAMMAD MACHI COLONY, GBPS ALTAF HUSSAIN NO.II TALUKA KASHMORE (PACKAGE NO. 11) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	224	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4'') channel patti on surface as required (S.No. 129 P-15).	910	per point	203840
2	42	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	31164
3	3	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	4770
4	478	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	81738
5	387	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	97524
6	220	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	67100
7	150	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	90750
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	5760
9	147	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	10290
10	38	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	34808
11	6	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	33126
12	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9261
13	436	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	163500
14	2	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	16910
<b>TOTAL :-</b>					<b>850541</b>

Amount Total (CSR)

Part "A"

% Above / Below \_\_\_\_\_

Total Amount \_\_\_\_\_

Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	224	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	46	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	19	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	4	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	47	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	86	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	12.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	1	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	40	P/F- wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	171	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	62	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	3	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	3	P/F flush type electric bell bush button		Each	
14	2	P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	1	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS MOLLI JO DARO, GBPS NASSAR UD DIN KHOSO, GBPS LAL BUX CHACHAR, GBPS HAZOOR BUX LANJWANI, GBPS ABDULLAH BHATTI TALUKA TANGWANI (PACKAGE NO. 12) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 1158000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT



Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	12.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	1	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	40	P/F- wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	150	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	62	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	3	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	3	P/F flush type electric bell bush button		Each	
14	2	P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	1	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT



## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GGPS COLONY NO 1 KASHMORE, GBPS COLONY NO 1 KASHMORE, GBPS SYED ZULFIQAR ALI SHAH TALUKA KASHMORE (PACKAGE NO. 13) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 1402000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK:- Rehabilitation / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GGPS COLONY NO 1 KASHMORE, GBPS COLONY NO 1 KASHMORE, GBPS SYED ZULFIQAR ALI SHAH TALUKA KASHMORE (PACKAGE NO. 13) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	238	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	216580
2	35	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	25970
3	3	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	4770
4	478	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	81738
5	300	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	75600
6	150	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4" dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	45750
7	100	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	60500
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	5760
9	147	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	10290
10	38	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	34808
11	6	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	33126
12	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9261
13	350	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I.No. 63 Page No. 8)	375	P.Meter	131250
14	2	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of El. Make of the above light is as follow	8455	P.No	16910
<b>TOTAL :-</b>					<b>752313</b>

Amount Total (CSR)

Part "A"

% Above / Below \_\_\_\_\_

Total Amount \_\_\_\_\_

Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	238	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	46	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	19	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	4	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	50	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	50	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	12.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	1	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	40	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	150	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	62	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	3	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	3	P/F flush type electric bell bush button		Each	
14	2	P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	1	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**


**Amount Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

**TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)**

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GBPS GHULAM HYDER KHAN JAKHRANI, GBLSS BANHON LASHARI, GBPS MOLVI SHAH MURAD GOLO, GBPS Dilijan @ Siddique Noonari, GBPS Bebarak @ Baloch Golato, GBPS BADANI (MAIN) TALUKA KASHMORE (PACKAGE NO. 14) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2200000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK:-** Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS GHULAM HYDER KHAN JAKHRANI, GBLSS BANHON LASHARI, GBPS MOLVI SHAH MURAD GOLO, GBPS Dilijan @ Siddique Noonari, GBPS Bebarak @ Baloch Golato, GBPS BADANI (MAIN) TALUKA KASHMIRE (PACKAGE NO. 14) (Electrification)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	280	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	254800
2	58	Wiring for plug point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	43036
3	5	Wiring for call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	7950
4	1100	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	188100
5	500	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	126000
6	395	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 copper conductor in 3/4" dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	120475
7	250	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/0.64 (16mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	151250
8	114	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	8208
9	216	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	15120
10	58	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	53128
11	9	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	49689
12	4	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	37044
13	579	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	217125
14	7	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of E.I. Make of the above light is as follow	8455	P.No	59185
<b>TOTAL :-</b>					<b>1331110</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_

Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	338	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complete		Each	
2	58	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	34	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	9	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	90	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	99	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	20.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	4	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	59	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	232	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	80	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	5	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	5	P/F flush type electric bell bush button		Each	
14		P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	3	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmir @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS JATOI CHACHAR, GBPS GHULAM RASOOL OGAHI, GBPS TAHAFIZUL QURAN, GBPS GHULAM MUHAMMAD KHOSO, GBPS GAMAN KHAN, GBPS DOST ALI SUHRIYANI, GBPS MUHAMMAD SULEMAN CHIJAN TALUKA KASHMORE (PACKAGE NO. 15)
- (c) Procuring Agency Address Near NADRA Office Kashmir @ Kandhkot
- (d) Estimated Cost 4593000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK:-** Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS JATOI CHACHAR, GBPS GHULAM RASOOL OGAHI, GBPS TAHAFIZUL QURAN, GBPS GHULAM MUHAMMAD KHOSO, GBPS GAMAN KHAN, GBPS DOST ALI SUHRIYANI, GBPS MUHAMMAD SULEMAN CHIJAN TALUKA KASHMORE (PACKAGE NO. 15)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	599	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 129 P-15).	910	per point	545090
2	50	Wiring for plug point with 3/0.29 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.No. 130 P-15).	742	per point	37100
3	3095	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. CSI No. 3 Page No. 1)	171	per Meter	529245
4	2509	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:11 P- No:2)	252	per Meter	632268
5	2221	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 (6mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:12 P- No:2)	341	per Meter	757361
6	103	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	Each	94348
7	13	207. Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required.	9261	P.No	120393
8	185	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	13320
9	414	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	28980
10	185	Providing & fixing junction box as per following specification Size of box 8"×6"×4"MS plate size 16 SWG thick Clamp with nuts & bolts Cover plate with screw Painting two coats of rust preventive red oxide & two coats of ICI oil paint as per site requirement & instruction of EI (SI No. 158 P-24)	800	P.No	148000
<b>TOTAL :-</b>					<b>2906105</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	599	P/F Flush Fancy type switch 10 amps i/c plastic board imported made etc complete. R.A Sanctioned By Chief Engineer		Each	
2	50	P/F Flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
3	27	P/F Flush type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection. R.A Sanctioned By Chief Engineer		Each	
4	185	S/F A.C Ceiling fan 56" sweep pure copper winding i/c down rod canopy blade suitable double bearing inter electric connection with 3/0.29 PVC. R.A Sanctioned By Chief Engineer		Each	
5	185	S/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete. R.A Sanctioned By Chief Engineer		Each	
6	29	P/F distribution board double shutter to accommodate circuit breaker & bushar i/c painting with enamelled paint. R.A Sanctioned By Chief Engineer		Each	
7	13	P/F earthing set set (1x1) copper pate i/c excavation of rock earth 12" depth or if water comes out i/c salt/choracle mixed with G.I Rod with butts, blots testing topping etc complete. R.A Sanctioned By Chief Engineer		Each	
8	50	P/F wall / ceiling mounted light, fancy type, superior quality i/c necessary electric connection and with holder, without energy saver etc. R.A Sanctioned By Chief Engineer		Each	
9	414	P/F energy saver superior quality i/c fixing on existing holder etc complete. R.A Sanctioned By Chief Engineer		Each	



Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
10	59	P/F L.E.D light 8" square/circle shop (09) watt in plastic cover fancy type (China make). R.A Sanctioned By Chief Engineer		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary & Elementary Schools) at GGPS PANDHI KALWAR, GBPS PANDHI KALWAR, GBPS MADARSAH AHYA UL ULOOM, GBPS SHER MUHAMAMD NAICH TALUKA KASHMORE (PACKAGE NO. 16) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2478000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK:- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GGPS PANDHI KALWAR, GBPS PANDHI KALWAR, GBPS MADARSAH AHYA UL ULOOM, GBPS SHER MUHAMAMD NAICH TALUKA KASHMORE (PACKAGE NO. 16) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	328	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4'') channel patti on surface as required (S.No. 129 P-15).	910	per point	298480
2	58	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	43036
3	5	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	7950
4	1237	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	211527
5	767	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	193284
6	395	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	120475
7	250	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	151250
8	114	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	8208
9	216	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	15120
10	58	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	53128
11	9	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	49689
12	4	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	37044
13	579	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	217125
14	7	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	59185
<b>TOTAL :-</b>					<b>1465501</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_

Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	338	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	58	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	34	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	9	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	90	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	99	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	20.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	4	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	59	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	232	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	80	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	5	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	5	P/F flush type electric bell bush button		Each	
14		P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	3	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount**


**Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- |   |  |
|---|--|
| (a) Name of Procuring Agency                            | <u>Executive Engineer, Education Works Division K'Kot</u>  |
| (b) Brief Discription of Works                          | <u>Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (Primary &amp; Elementary Schools) at GBPS GUDDU, GGPS Kashmore, GBPS PIR ABDUL SATTAR SHAH, GBPS ALI BUX SOLANGI TALUKA KASHMORE (PACKAGE NO. 17) (Electrification)</u> |
| (c) Procuring Agency Address                            | <u>Near NADRA Office Kashmore @ Kandhkot</u>   |
| (d) Estimated Cost                                      | <u>1303000</u>   |
| (e) Amount of Bid Security                              | <u>5% on Bid</u>   |
| (f) Period of Bid Validity (Days)                       | <u>90 Days</u>   |
| (g) Security Deposit (i/c bid Security)                 | <u>8%</u>  |
| (h) Percentage, if any, to be deducted from bills       | <u>(7.50% Income Tax) &amp; (3% Security Deposit)</u>  |
| (i) Deadline for submission of bids along with time     | <u>19.04.2018 at 12:00 PM</u>  |
| (j) Venue, Time and Date of Bid Opening                 | <u>20.04.2018 at 01:00 PM</u>  |
| (k) Time for completion from written order of commences | <u>04 Months</u>   |
| (L) Liquidity Demages                                   | <u>-</u>   |
| (m) Deposit Receipt _____ Date _____ Amount _____       |  |
| (n) D.R No. _____ Date _____ Amount <b>Rs. 3000/-</b>   |  |
| (o) Tender Issued to (Mr. / M/S)                        | _____  |

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORKS :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmir @ Kandhkot (Primary & Elementary Schools) at GBPS GUDDU, GGPS Kashmir, GBPS PIR ABDUL SATTAR SHAH, GBPS ALI BUX SOLANGI TALUKA KASHMIRE (PACKAGE NO. 17) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	224	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	203840
2	42	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	31164
3	3	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	4770
4	478	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	81738
5	387	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	97524
6	220	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4" dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	67100
7	150	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	90750
8	80	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	5760
9	147	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	10290
10	38	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	34808
11	6	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	33126
12	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9261
13	436	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	163500
14	2	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	16910
<b>TOTAL :-</b>					<b>850541</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	224	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	46	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	19	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	4	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	47	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	86	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	12.5	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	1	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	40	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	171	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	62	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	3	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	3	P/F flush type electric bell bush button		Each	
14	2	P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	1	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**


**Amount Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (SECONDARY & HIGH SECONDARY Schools) at GGHS - GHOUS PUR, GGHS TANGWANI (CAMPUS), TALUKA KANDHKOT & TANGWANI (PACKAGE NO. 18) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2875000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT



**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (SECONDARY & HIGH SECONDARY Schools) at GGHS - GHOU PUR, GGHS TANGWANI (CAMPUS), TALUKA KANDHKOT & TANGWANI (PACKAGE NO. 18) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	469	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4'') channel patti on surface as required (S.No. 129 P-15).	910	per point	426790
2	87	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	64554
3	10	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4'') channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	15900
4	1742	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	297882
5	1235	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4'' dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	311220
6	565	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	172325
7	114	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4'' dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	68970
8	165	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	11880
9	318	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	22260
10	92	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	84272
11	18	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	99378
12	6	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	55566
13	566	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I.No. 63 Page No. 8)	375	P.Meter	212250
14	6	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	50730
<b>TOTAL :-</b>					<b>1893977</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_

Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	483	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	48	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	48	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4		P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	13	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	107	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	153	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	10	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	111	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	338	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	94	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	9	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	9	P/F flush type electric bell bush button		Each	
14		P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	2	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**


**Amount      Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (SECONDARY & HIGH SECONDARY Schools) at GBHS - BALACH KHAN DAHANI, GBHS - SHERAN BHAYO (Campus), GGHS - KASHMORE TALUKA TANGWANI & KASHMORE (PACKAGE NO. 19) (Electrification)
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 3650000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

**BILL OF QUANTITIES**

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Rehabilitaion / Expansion of High Priority 4560-Schools @ District Kashmore @ Kandhkot (SECONDARY & HIGH SECONDARY Schools) at GBHS - BALACH KHAN DAHANI, GBHS - SHERAN BHAYO (Campus), GGHS - KASHMORE TALUKA TANGWANI & KASHMORE (PACKAGE NO. 19) (Electrification)**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	505	Wiring for light or fan point with 3/.029 PVCinsulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	459550
2	95	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	70490
3	6	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") channel patti on surface as required.(S.I.No:131 P- No:15)	1590	per point	9540
4	1769	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	per Meter	302499
5	1241	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.036 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	252	per Meter	312732
6	1075	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 copper conductor in 3/4" dia PVC conduit as required. (S.I.No:11 P- No:2)	305	per Meter	327875
7	520	Providing & laying (MAIN or SUB MAIN) PVC insulated size 2-7/.064 (16mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduit as required. (S.I.No:14 P- No:2)	605	per Meter	314600
8	187	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	13464
9	329	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	23030
10	86	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	78776
11	14	206. Providing & fixing circuit breaker 15,20, 30,40,50 & 60amp TP (XE-100CS[CB]) on prepared board as required. (S.I.No:206 P- No:31)	5521	P.No	77294
12	8	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	74088
13	657	Providing & laying (MAIN or SUB MAIN) PVC insulated & PVC Sheeted with two core copper conductor 300/500 volts size 10mm <sup>2</sup> (S.I No. 63 Page No. 8)	375	P.Meter	246375
14	11	160. Providing & Fixing of street light 250 watts (HPMV) having IP54 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height up to 31ft as per site requirement and instruction of EI. Make of the above light is as follow	8455	P.No	93005
<b>TOTAL :-</b>					<b>2403318</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_  
Total A \_\_\_\_\_

**NON SCHEDULE ITEMS**

1	288	P/F flush type fancy switch 10 amps i/c plastic board imported made etc complece		Each	
2	75	P/F flush type 2 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
3	24	P/F flush type 3 pin plug socket 10 amps with fancy type board and sheet i/c necessary		Each	
4	9	P/F fit.sh type 3 pin plug socket 15 amps with fancy type board and sheet i/c necessary connection		Each	
5	86	S/F A.C electric ceiling fans 56" sweep (Pure copper winding) i/c down rod, canopy blade,		Each	
6	117	P/F fan dimmer 220/240 volts fancy type imported make with necessary connection etc complete		Each	

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	24	P/F distribution board double shutter for accommodate circuit breaker and buslor i/c painting With enameled paint		P.Sft	
8	4	P/F on a prepared board iron clad bus bar with 4 copper strips of 200 amps in 24.4 mm x 5.50 mm Rs. 18000.00 Each lc/ necessary electric connection		Each	
9	55	P/F-. wall / Ceiling mounted light fancy type, superior quality i/c necessary electric connection Rs. 600.00 Each an with holder , without energy Saver etc		Each	
10	287	P/F Energy saver superior quality i/c fixing on existing holder etc complete etc		Each	
11	76	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof		Each	
12	5	P/F AC or DC electric bell 200/250 volt 70MM.		Each	
13	5	P/F flush type electric bell bush button		Each	
14	4	P/F Exhaust Fan 10" to 12" plastic body complete in all respect (GEC) made/Pak good quality (RA)		Each	
15	1	P/F earthing set size (1x1) copper plate i/c excavation of rock earth 12/ depth or if water comes out i/c Salt choracale mixed with '3.I. Road with nuts, bolts testing topping etc complete		Each	
<b>TOTAL :-</b>					

**Cost of Bid**


**Amount Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Construction of Shelterless Building for Village Jan Muhammad Khan Sabzoi U/C Doulatpur Taluka Kandhkot
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2000000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

# BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Construction of Shelterless Building for Village Jan Muhammad Khan Sabzoi U/C Doulatpur Taluka Kandhkot**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
1	1919	Excavtion in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structruere with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	3176.25	%0Cft	6095
2	1107	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	8694.95	%Cft	96253
3	1841	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	11948.36	%Cft	219969
4	446	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepretely this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (I)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft . shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.17).	337.00	P.Cft	150302
5	19.910	Fabrication of Tor steel reinforcecement for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:8 B P.17).	5001.70	P.Cwt	99584
6	1279	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	1512.50	%0Cft	1934
7	2238	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	3630.00	%0Cft	8124
8	1014	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	12674.36	%Cft	128518
9	24.107	S/F Girder at Site of Work	3850.00	P.Cwt	92812
10	17.178	S/F T.Iron at Site of Work	3575.00	P.Cwt	61411
11	41.285	Errection rooled steel beam or old rails in roof etc errection and fixing in position (C.SI No:6 P-91).	186.34	P.Cwt	7693
12	580	1st class tiles roofing consisting of 4"earth and 1" mud plaster with leeping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x1"1/4 tiles laid in 1"6 cement mortor icluding 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.38).	7607.25	%Sft	44122
13	580	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.44).	10.70	P.Sft	6206
14	3099	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2206.06	%Sft	68366
15	3099	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2197.52	%Sft	68101
16	1338	Cement pointing strucking of joints of walls ratio 1:2 (C.S.I No: 19 (a) Page. 53)	1287.44	%Sft	17226
17	83	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	228.90	P.Rft	18999
18	217	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	240.50	P.Rft	52189
19	2.456	Febrication of heavy steel	4928.49	P.Cwt	12104

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
20	188	Suppling and fixing in position iron steel grill of 3/4"x 1/4" size flate iron of approved design l/c painting three coats etccomplete weightg not less than 3.7 lbs of finished grill (C.S.I No:26 P.97).	180.50	P.Sft	33934
21	195	First class deodar wood wrought joinery in doors and windos etcfied inosition l/c in chwoakts holds fasts hings iron tower bolts chowkts cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4"only shutter (C.S.I No:7 (b) P.58).	902.93	P.Sft	176071
22	707	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42) .	3275.50	%Sft	23158
23	175	Cement concrete plain including placing compacting, finishing curing, complete including screening and washing of stone aggregate without shuttering. (CSI No.5(a) P-18)	14429.25	%Cft	25251
24	87	Providing and lying tiles glazed 5" x 5" x1/2" on floor on wall facing in required floor and pattern of STILE spcification jointed in white cement and pigment over a base of1:2 grey cement mortar 3/4" thick including washing and filling of white joints with slurry of white cement and pigment in desired shape with finshing cleaning and cost of wax polish etc . complete including cutting tiles to proper profile (C.S.I No:61 P-54) .	30509.77	%Sft	26543
25	248	White glazed tile 14" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4 " thick including finishing (C.S.I No:37 P-45) .	28253.51	%Sft	70069
26	4	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	261.45	Each	1046
27	64	Notice board made with cement (C.S.I No:1 P.95).	58.11	P.Sft	3719
28	965	White wash three coats (C.S.I No:26 (c) P-54).	829.95	%Sft	8009
29	3099	Primary coat of chalk under destember (C.S.I No:23 P-54).	442.75	%Sft	13721
30	3099	Destember three coats (C.S.I No:24 (c) P-54).	1079.65	%Sft	33458
31	1338	Preparing the surface and painting with weather coat of approved make to new weather coat surface (CSI No. 41 (a) P. No. 62)	2567.95	%Sft	34359
32	446	Painting new surface, and paiting of doors and windows any type (i/c edges) 2 coats (C.S.I No:4 (c) P-76).	2116.41	%Sft	9439
33	1195	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	1270.83	%Sft	15186
<b>TOTAL :-</b>					<b>1633973</b>

**PART "B"**

1	2	Providing & fixing squatting type white glazed of flushe cisten with internal fitting&flush pippe with bend and making requesite numbers of holes in wall plinth & floor for pipe conection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with4" dia C.I trap with C.I thumble. (S.I No:1 (b) i P-No:1)	4802.60	Each	9605
2	2	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & l/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	4253.70	Each	8507
3	2	Add: extra labour for providing and fixing of earthen wire padestle whiute or colored glass standared pattern (S.I No:9 P-No:3).	938.47	Each	1877
4	4	P/F in position nyloon connections complete with 1/2"dia brass stop cock with pair of brass nuts and lining joints to nyloon connection (S.I No:23 P-No:6).	447.15	Each	1789
5	2	P/F 6" x 4" c.c gully trap with 4" dia out let complte with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the karb c.I caning 6" x 6" and c.I cover and frame 12" x 12" in side etc complete (S.I No:1(a-i) P-No:21).	1193.17	Each	2386
6		RCC pipe with colar class "B" and didding the traches to the required depth an fixing in positin l/c cutting fitting and jointing with max phalt composition and cemen mortar 1:1 and testing with water presure to head of 4 Ft aboe the top of the heigh			
	100	4"dia	146.57	P.Rft	14657
	100	6"dia	199.25	P.Rft	19925



Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount	
7	2	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & l/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	2042.43	P.Rft	4085	
8		Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking thorough walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zink paint with pigment to match the colour5 of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)				
i	100	1/2" dia	73.21	P.Rft	7321	
ii	150	3/4" dia	95.79	P.Rft	14369	
iii	100	1" dia	128.55	P.Rft	12855	
vi	50	1-1/4" dia	153.19	P.Rft	7660	
9		Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement motor etc Complete				
	100	1/2" dia	7.82	P.Rft	782	
	50	3/4" dia	8.45	P.Rft	423	
10		Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standared pattern (Note standared Manufacture by M/S Anwar Mechanical works (S.I No:4 (b) P-No:17).				
	2	1/2" dia	161.92	Each	324	
	2	3/4 dia	227.92	Each	456	
11	4	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	478.28	Each	1913	
12	2	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	1109.46	Each	2219	
13	1	S./F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2882.00	Each	2882	
14	1	S/F Swan type Pillars Cock of supreior quality with arvstal Head.	795.30	Each	795	
15		P/F handle valves (China) (S.I No:7 P-No:14).				
	ii	2	3/4" dia	271.92	Each	544
	iii	2	1" dia	365.42	Each	731
16		Supplying & fixing fibre glass tank of approved quality and design and wall thicness as specified l/c cost of nutes, bolts and fixing in plateform of cement concreete 1: 3: 6 and makin connections for in -let ,& ou-let & over flow pipes etc. complete.				
A	1	250 Gallons	21989.61	Each	21990	
				<b>TOTAL :-</b>	<b>138095</b>	

**PART "C"**

1		Providing PVC Pipes of class D equalvalent make) fixing in trench i/c cutting fitting and jointing with "Z" joint with one rubber Ring i/c testing with water to head of 122 metere or 400ft. (S.I.No:3 Page No:23)			
	100	3" dia	137.00	R.FT	13700
	100	4" dia	226.00	R.FT	22600
2	2	Constructiong manhole or inspectionchamb er for the required dia of circular sewer and 3'-6" (1067 mm) dpth with walls of BB in cement motor 1:3 cement plaster 1:3, 1/2' thick inside of walls and 1" (25 mm) thick over benchingh and channel i/c fixing CI manhole cover with fram of clear opening 1-1/2' x 1., 1/2' (457x457 mm) of 1.75 Cwt. (88.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps 6' (150 mm) waide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per spacification and drawing (SI No. P Page No. 46). (PHE)	14748	Each	29496
				<b>TOTAL :-</b>	<b>65796</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_

Part "B" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
Part "C"		% Above / Below _____			Total Amount _____
					Total "A+B+C" _____

**NON SCHEDULE ITEMS**

1	352	Providing & laying floor of Verona marble tiles of size 12" x 12" x 3/4" fine dressed on the surface without winding set in white cement laid over 3 / 4" thick bed of 1:2 grey cement mortar setting the tiles with grey cement slurry, jointing and washing the tiles with slurry of white cement and pigment to match the colour of titles, including curring, grinding, rubbing and chemical polishing etc. complete i/c cutting tiles to proper profile.		P.Sft	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount      Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT

## **BIDDING DATA**

This Section should be filled in by the Executive Engineer Education Works Division Kashmore @ Kandhkot, before issuance of the Bidding Documents.

**NIT No. EE/EWD/TC/ 1047**

**Dated: 30.0.2018**

- (a) Name of Procuring Agency Executive Engineer, Education Works Division K'Kot
- (b) Brief Discription of Works Construction of Shelterless Building for Village Najamdin Khan Sabzoi U/C Wakro Taluka Kandhkot
- (c) Procuring Agency Address Near NADRA Office Kashmore @ Kandhkot
- (d) Estimated Cost 2000000
- (e) Amount of Bid Security 5% on Bid
- (f) Period of Bid Validity (Days) 90 Days
- (g) Security Deposit (i/c bid Security) 8%
- (h) Percentage, if any, to be deducted from bills (7.50% Income Tax) & (3% Security Deposit)
- (i) Deadline for submission of bids along with time 19.04.2018 at 12:00 PM
- (j) Venue, Time and Date of Bid Opening 20.04.2018 at 01:00 PM
- (k) Time for completion from written order of commences 04 Months
- (L) Liquidity Demages -
- (m) Deposit Receipt \_\_\_\_\_ Date \_\_\_\_\_ Amount \_\_\_\_\_
- (n) D.R No. \_\_\_\_\_ Date \_\_\_\_\_ Amount **Rs. 3000/-**
- (o) Tender Issued to (Mr. / M/S) \_\_\_\_\_

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
KASHMORE @ KANDHKOT

# BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

**NAME OF WORK :- Construction of Shelterless Building for Village Najamdin Khan Sabzoi U/C Wakro Taluka Kandhkot**

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
<b>PART "A" SCHEDULE ITEMS</b>					
1	1919	Excavtion in foundation of Building Bridges and other structures including dagbelling dressing,refilling around structrure with excavated earth Watering and ramming lead upto 5 ft (b) in ordinary soil (C.S.I No:18 (b)P.4)	3176.25	%0Cft	6095
2	1107	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:5:10 (C.S.I No: 4 (c) Page No:15)	8694.95	%Cft	96253
3	1841	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	11948.36	%Cft	219969
4	446	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepretely this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (I)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft . shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.17).	337.00	P.Cft	150302
5	19.910	Fabrication of Tor steel reinforcecment for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:8 B P.17).	5001.70	P.Cwt	99584
6	1279	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	1512.50	%0Cft	1934
7	2238	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	3630.00	%0Cft	8124
8	1014	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	12674.36	%Cft	128518
9	24.107	S/F Girder at Site of Work	3850.00	P.Cwt	92812
10	17.178	S/F T.Iron at Site of Work	3575.00	P.Cwt	61411
11	41.285	Errection rooled steel beam or old rails in roof etc errection and fixing in position (C.SI No:6 P-91).	186.34	P.Cwt	7693
12	580	1st class tiles roofing consisting of 4"earth and 1" mud plaster with leeping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x1"1/4 tiles laid in 1"6 cement mortor icluding 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.38).	7607.25	%Sft	44122
13	580	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.44).	10.70	P.Sft	6206
14	3099	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2206.06	%Sft	68366
15	3099	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2197.52	%Sft	68101
16	1338	Cement pointing strucking of joints of walls ratio 1:2 (C.S.I No: 19 (a) Page. 53)	1287.44	%Sft	17226
17	83	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	228.90	P.Rft	18999
18	217	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:28 P.93).	240.50	P.Rft	52189
19	2.456	Febrication of heavy steel	4928.49	P.Cwt	12104

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
20	188	Suppling and fixing in position iron steel grill of 3/4"x 1/4" size flate iron of approved design l/c painting three coats etccomplete weightg not less than 3.7 lbs of finished grill (C.S.I No:26 P.97).	180.50	P.Sft	33934
21	195	First class deodar wood wrought joinery in doors and windos etcfied inosition l/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4"only shutter (C.S.I No:7 (b) P.58).	902.93	P.Sft	176071
22	707	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42) .	3275.50	%Sft	23158
23	175	Cement concrete plain including placing compacting, finishing curing, complete including screening and washing of stone aggregate without shuttering. (CSI No.5(a) P-18)	14429.25	%Cft	25251
24	87	Providing and lying tiles glazed 5" x 5" x1/2" on floor on wall facing in required floor and pattern of STILE spcification jointed in white cement and pigment over a base of1:2 grey cement mortar 3/4" thick including washing and filling of white joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc . complete including cutting tiles to proper profile (C.S.I No:61 P-54) .	30509.77	%Sft	26543
25	248	White glazed tile 14" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4 " thick including finishing (C.S.I No:37 P-45) .	28253.51	%Sft	70069
26	4	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	261.45	Each	1046
27	64	Notice board made with cement (C.S.I No:1 P.95).	58.11	P.Sft	3719
28	965	White wash three coats (C.S.I No:26 (c) P-54).	829.95	%Sft	8009
29	3099	Primary coat of chalk under destember (C.S.I No:23 P-54).	442.75	%Sft	13721
30	3099	Destember three coats (C.S.I No:24 (c) P-54).	1079.65	%Sft	33458
31	1338	Preparing the surface and painting with weather coat of approved make to new weather coat surface (CSI No. 41 (a) P. No. 62)	2567.95	%Sft	34359
32	446	Painting new surface, and paiting of doors and windows any type (i/c edges) 2 coats (C.S.I No:4 (c) P-76).	2116.41	%Sft	9439
33	1195	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	1270.83	%Sft	15186
			<b>TOTAL :-</b>		<b>1633973</b>

**PART "B"**

1	2	Providing & fixing squating type white glazed of flushe cisten with internal fitting&flush pippe with bend and making requesite numbers of holes in wall plinth & floor for pipe conection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with4" dia C.I trap with C.I thumble. (S.I No:1 (b) i P-No:1)	4802.60	Each	9605
2	2	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & l/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or c.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	4253.70	Each	8507
3	2	Add: extra labour for providing and fixing of earthen wire padestle whiute or colored glass standared pattern (S.I No:9 P-No:3) .	938.47	Each	1877
4	4	P/F in position nyloon connections complete with 1/2"dia brass stop cock with pair of brass nuts and lining joints to nyloon connection (S.I No:23 P-No:6).	447.15	Each	1789
5	2	P/F 6" x 4" c.c gully trap with 4" dia out let complt with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the karb c.I caning 6" x 6" and c.I cover and frame 12" x 12" in side etc complete (S.I No:1(a-i) P-No:21).	1193.17	Each	2386
6		RCC pipe with colar class "B" and didding the traches to the required depth an fixing in positin l/c cutting fitting and jointing with max phalt composition and cemen mortar 1:1 and testing with water presure to head of 4 Ft aboe the top of the heigh			
	100	4"dia	146.57	P.Rft	14657
	100	6"dia	199.25	P.Rft	19925

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
7	2	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & l/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	2042.43	P.Rft	4085
8		Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking thorough walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zink paint with pigment to match the colour5 of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)			
i	100	1/2" dia	73.21	P.Rft	7321
ii	150	3/4" dia	95.79	P.Rft	14369
iii	100	1" dia	128.55	P.Rft	12855
vi	50	1-1/4" dia	153.19	P.Rft	7660
9		Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement motor etc Complete			
	100	1/2" dia	7.82	P.Rft	782
	50	3/4" dia	8.45	P.Rft	423
10		Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standared pattern (Note standared Manufacture by M/S Anwar Mechanical works (S.I No:4 (b) P-No:17).			
	2	1/2" dia	161.92	Each	324
	2	3/4 dia	227.92	Each	456
11	4	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	478.28	Each	1913
12	2	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	1109.46	Each	2219
13	1	S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2882.00	Each	2882
14	1	S/F Swan type Pillars Cock of supreior quality with arvstal Head.	795.30	Each	795
15		P/F handle values (China) (S.I No:7 P-No:14).			
ii	2	3/4" dia	271.92	Each	544
iii	2	1" dia	365.42	Each	731
16		Supplying & fixing fibre glass tank of approved quality and design and wall thicness as specified l/c cost of nutes, bolts and fixing in plateform of cement concreete 1: 3: 6 and makin connections for in -let ,& ou-let & over flow pipes etc. complete.			
A	1	250 Gallons	21989.61	Each	21990
<b>TOTAL :-</b>					<b>138095</b>

**PART "C"**

1		Providing PVC Pipes of class D equalvalent make) fixing in trench i/c cutting fitting and jointing with "Z" joint with one rubber Ring i/c testing with water to head of 122 metere or 400ft. (S.I.No:3 Page No:23)			
	100	3" dia	137.00	R.FT	13700
	100	4" dia	226.00	R.FT	22600
2	2	Constructiong manhole or inspectionchamb er for the required dia of circular sewer and 3'-6" (1067 mm) dpth with walls of BB in cement motor 1:3 cement plaster 1:3, 1/2' thick inside of walls and 1" (25 mm) thick over benchingh and channel i/c fixing CI manhole cover with fram of clear opening 1-1/2' x 1., 1/2' (457x457 mm) of 1.75 Cwt. (88.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps 6' (150 mm) waide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per spacification and drawing (SI No. P Page No. 46). (PHE)	14748	Each	29496
<b>TOTAL :-</b>					<b>65796</b>

Amount Total (CSR)

Part "A" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_

Part "B" % Above / Below \_\_\_\_\_ Total Amount \_\_\_\_\_

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
Part "C"		% Above / Below _____			Total Amount _____
					Total "A+B+C" _____

**NON SCHEDULE ITEMS**

1	352	Providing & laying floor of Verona marble tiles of size 12" x 12" x 3/4" fine dressed on the surface without winding set in white cement laid over 3 / 4" thick bed of 1:2 grey cement mortar setting the tiles with grey cement slurry, jointing and washing the tiles with slurry of white cement and pigment to match the colour of titles, including curring, grinding, rubbing and chemical polishing etc. complete i/c cutting tiles to proper profile.		P.Sft	
<b>TOTAL :-</b>					

**Cost of Bid**

**Amount      Position**

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)

CONTRACTOR

  
 EXECUTIVE ENGINEER  
 EDUCATION WORKS DIVISION  
 KASHMORE @ KANDHKOT