



**OFFICE OF THE  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT**

NO. GB/ /2018  
K'more @ K.kot dated. .2018

To,

The Director Information,  
Public Relation, Department (Advertisement),  
Government of Sindh,  
Block 96 Sindh Secretariat,  
**KARACHI.**

**SUBJECT: PUBLICATION OF NOTICE INVITING TENDERS.**

Kindly find enclosed herewith copies of order Notice Inviting Tender for publication in leading news papers, preferably Dailies Dwan, Jang, Kawish for wide publicity.

**(BASHIR AHMED BROHI), PSP  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT**

No.GB /

7924-27 /2018 /

K'more @ Kandhkot

Dated

25/4.2018

1. Copy Submitted to the Deputy Inspector General of Police Larkana Range for favour of kind information.
- ✓ 2. Copy submitted to the Manager Assessment Sindh Public Procurement Regularity Authority, Barrack No.08 Sindh Secretariat No.4-A Court, Road Karachi, along with draft of Rs.2000/- No. \_\_\_\_\_ dated \_\_\_\_\_ of branch \_\_\_\_\_ bid documents procurement plane PC, CRC, Committee and CD w/r to publish advertisement on SPPRA website.
3. Copy Submitted to the Deputy Inspector General of Police I.T CPO Sindh Karachi for favour of kind information

**(BASHIR AHMED BROHI), PSP  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT**

SPPRA INWARD DIARY

NO: RS 32

DATED 26-04-2018

**OFFICE OF THE SUPERINTENDENT OF POLICE KASHMORE @ KANDHKOT**

NO. OB/ 1446

/2018 K'more @ Kandhkot

Dated. 25-4-2018

**NOTICE INVITING TENDER**

Senior Superintendent of Police Kashmore @ Kandhkot invited sealed Tender/Bids on SPPRA Rules from interested firms/person having appropriate experience for procurement of the work on single Envelope method.

2/- A Complete set of bidding documents can be obtain from the office of undersigned at the address given below on tender fee as per list attached.

3/- Bids must accompanied with earnest money / Bid security in form of call deposit in the name of undersigned from Bank.

Address: Superintendent of Police Kashmore @ Kandhkot.

Phone No. 07225-70905 / 07225-70913

Date of issue from publication	Date of time of submission & opening	
16-05-2018	Bid submission	Date 16-05-2018 Time 01:00 PM
	Bid Opening	Date 16-05-2018 Time 02:00 PM

(BASHIR AHMED BROHI), PSP  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

No.GB /

7928-25

/2018 /

K'more @ Kandhkot

Dated 25.4.2018

**Copy submitted for information to:-**

1. The Secretary, Information Technology, Government of Sindh Secretariat No.06 at Karachi alongwith copies of NITS for information and placing the same on the website of Sindh Government.
2. The Director Information Public Relation Department (Advertisement) Block No.96 Sindh Secretariat Karachi for Publication in News Paper specially in Dawn (ENGLISH), Jung (URDU) and Kawish (SINDHI).
3. ✓ Copy submitted to the Manager Assessment Sindh Public Procurement Regularity Authority, Barrack No.08 Sindh Secretariat No.04-A Court Road Karachi alongwith copy of NIT for placing the same on website.
4. The Deputy Inspector General of Police Finance CPO Sindh Karachi.
5. The Deputy Inspector General of Police Larkana Range.
6. The Deputy Inspector General of Police I.T CPO Sindh Karachi.
7. The Assistant Inspector General of Police Logistics CPO Sindh Karachi.
8. The Assistant Engineer, Police Works, Larkana.

(BASHIR AHMED BROHI), PSP  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

## LIST OF WORK

S/#	NAME OF WORK	ESTIMATE COST	BID SECURITY / EANEEST MONEY 5%	PERIOD	TENDER FEE
1	Repair/ Renovation work of CRO Branch DSP CIA Kashmore @ Kandhkot	1.0 (M)	Rs.50,000/-	One Month	Rs.2,000/-
2	Repair/ Renovation work of I.T Section at SSP Office Kashmore @ Kandhkot	1.0 (M)	Rs.50,000/-	One Month	Rs.2,000/-



**(BASHIR AHMED BROHI), PSP**  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

# SPPRA BIDDING DOCUMENTS



OFFICE OF THE  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

Tel: 0722-570913  
Fax: 07225-70912  
spkashmore@yahoo.com

## STANDARD BIDDING DOCUMENTS PROCUREMENT OF WORKS

*(For Contracts Costing 1.0 Million)*

### REPAIR/ RENOVATION WORK OF IT LAB AT SSP OFFICE KASHMORE @ KANDHKOT

- . Instructions to Bidders (ITB)
- . General Conditions of Contract (GCC)

Name of Contractor/ firm:

---

D.R No. & Date.

---


**(BASHIR AHMED BROHI), PSP**  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT



## BIDDING DATA

(This section should be filled in the Engineer/Procuring Agency Before Issuance of the Bidding Documents).

- |   |   |
|---|---|
| (p) Name of Procuring Agency:-  | <b>SP Kashmore @ Kandhkot</b>             |
| (q) Brief Description of works:-  | <b>Repair / Renovation work of IT Lab</b> |
| (r) Procuring Agency's Address:-  | <b>SSP Office Kashmore @ Kandhkot</b>     |
| (s) Estimated Cost:-  | 1.0 (M)                                   |
| (t) Amount of Bid Security.<br>(Fill in lump sum amount in % age Of bid amount/estimated cost, but Not exceeding 5%). | 0.050(M)                                  |
| (u) Period of Bid validity (days)<br>(Not more than Ninety days)  | 1 Month                                   |
| (v) Security Deposit (including bid Security) (in % age of bid amount/ Estimated cost equal to 10 %)                  | 2%  |
| (w) Percentage, if any, to be deducted Form bills.  | 7.5%+5%=12.5%                             |
| (x) Deadline for submission of Bids<br>Date along with time   | 10-05-2018<br>01:00 PM                    |
| (y) Venue ,time and Date of Bid Opening<br>Date along with time   | 10-05-2018<br>02:00 PM                    |
| (z) Time for completion from written order<br>Of commence.  | _____                                     |
| (aa) Liquidity damages<br>(0.05 of Estimated cost or Bid cost Per day of delay, but total not Exceeding 10%).         | _____                                     |
| (bb) Deposit Receipt No:  | _____                                     |
| (cc) Dr.No:&Date  | _____                                     |
| (dd) Rate quoted by contractor above/<br>Below schedule items & Non-<br>Schedule items/Total tender cost.             | _____                                     |

  
**(BASHIR AHMED BROHI), PSP**  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

# SPPRA BIDDING DOCUMENTS



OFFICE OF THE  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

Tel: 0722-570913  
Fax:07225-70912  
spkashmore@yahoo.com

## STANDARD BIDDING DOCUMENTS PROCUREMENT OF WORKS

*(For Contracts Costing 1.0 Million)*

### REPAIR/ RENOVATION WORK OF CRO BRANCH DSP CIA KASHMORE @ KANDHKOT


- . Instructions to Bidders (ITB)
- . General Conditions of Contract (GCC)

Name of Contractor/ firm:

---

D.R No. & Date.


---

  
(BASHIR AHMED BROHI), PSP  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

## BIDDING DATA

(This section should be filled in the Engineer/Procuring Agency Before Issuance of the Bidding Documents).

- |   |  |
|---|--|
| (a) Name of Procuring Agency:-  | <b>SP Kashmore @ Kandhkot</b>                                  |
| (b) Brief Description of works:-  | <b>Repair / Renovation work of CRO Branch DSP CIA Kandhkot</b> |
| (c) Procuring Agency's Address:-  | <b>Main Highway Road Kandhkot</b>                              |
| (d) Estimated Cost:-  | 1.0 (M)  |
| (e) Amount of Bid Security.<br>(Fill in lump sum amount in % age Of bid amount/estimated cost, but Not exceeding 5%). | 0.050(M)   |
| (f) Period of Bid validity (days)<br>(Not more than Ninety days)  | 1 Month  |
| (g) Security Deposit (including bid Security) (in % age of bid amount/ Estimated cost equal to 10 %)                  | 2%   |
| (h) Percentage, if any, to be deducted Form bills.  | 7.5%+5%=12.5%  |
| (i) Deadline for submission of Bids<br>Date along with time   | 10-05-2018<br>01:00 PM   |
| (j) Venue ,time and Date of Bid Opening<br>Date along with time   | 10-05-2018<br>02:00 PM   |
| (k) Time for completion from written order<br>Of commence.  | _____  |
| (l) Liquidity damages<br>(0.05 of Estimated cost or Bid cost Per day of delay, but total not Exceeding 10%).          | _____  |
| (m) Deposit Receipt No:   | _____  |
| (n) Dr.No:&Date   | _____  |
| (o) Rate quoted by contractor above/<br>Below schedule items & Non-<br>Schedule items/Total tender cost.              | _____  |

  
**(BASHIR AHMED BROHI), PSP**  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT



**OFFICE OF THE  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT**

NO. GB/ /2018  
K'more @ K.kot dated. .2018

To,

The Deputy Inspector General of Police,  
Larkana Range.

**SUBJECT: CONSTITUTION OF COMMITTEE FOR REPAIR / RENOVATION WORK OF CRO ROOM AT DSP CIA OFFICE & IT LAB AT SSP OFFICE KASHMORE @ KANDHKOT FOR THE YEAR 2017-2018.**

It is submitted that, funds amounting to Rs. 2,000,000/- have been allocated to this district under the head of A13301 Office Building (KK-0013) SSP Kashmore @ Kandhkot) for repair / renovation work of CRO Room and IT Lab at SSP Office Kashmore@Kandh Kot. Following committees consisting of officers mentioned below may kindly be constituted for repair / Renovation work of CRO Room and IT Lab for the year 2017-2018.

1. **Procurement Committee**

- |      |  |             |
|------|--|-------------|
| i.   | SSP Kashmore @ Kandhkot                          | (Chairman)  |
| ii.  | DSP Head Quarter Kashmore @ Kandhkot             | (Secretary) |
| iii. | DSP/SDPO Kashmore                                | (Member)    |
| iv.  | OS DC Office Kashmore @ Kandhkot                 | (Member)    |
| v.   | Assistant Engineer (Prov: Building Div. Larkana) | (Member)    |

2. **Redressal of Grievance & Settlement of Disputes Committee**

- |      |  |             |
|------|--|-------------|
| i.   | DIGP Larkana Range                             | (Chairman)  |
| ii.  | DSP/SDPO Buxapur                               | (Secretary) |
| iii. | DSP/SDPO Durani Mahar                          | (Member)    |
| iv.  | District Accounts Officer Kashmore @ Kandhkot  | (Member)    |
| v.   | Assistant Engineer EDU Works Sub Div: Kashmore | (Member)    |

3. **Physical Inspection & Technical Committee**

- |      |                                      |             |
|------|--------------------------------------|-------------|
| i.   | ADIGP Larkana                        | (Chairman)  |
| ii.  | DSP Head Quarter Kashmore @ Kandhkot | (Secretary) |
| iii. | Assistant Engineer Highways Kandhkot | (Member)    |

It is therefore, requested that, an order in this regard may kindly be issued from office of the AIGP Logistics in the best interest of Govt: work.

**(BASHIR AHMED BROHI), PSP**  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

No.GB / 7817-23 /2018 /

K'more @ Kandhkot

Dated 25.4.2018

**Copy submitted for information to:-**

1. The ADIGP Larkana Range.
2. The District Accounts Officer Kashmore @ Kandhkot.
3. The Assistant Engineer Prov: Building, Div: Larkana.
4. The Assistant Engineer EDU Works Sub Div: Kashmore @KandhKot.
5. The Assistant Engineer Highways Sub Div: KandhKot.
6. DSP, Head Quarter Kashmore @ KandhKot / DSP/SDPO Kashmore / Tangwani Buxapur/ OS DC Office / SP Office Kashmore @ Kandhkot.

**(BASHIR AHMED BROHI), PSP**  
SUPERINTENDENT OF POLICE  
KASHMORE @ KANDHKOT

FACE SHEET

BY HEAD :- PROVINCIAL GOVERNMENT.

FOR HEAD :-

BY HEAD :-

BY HEAD :- ESTIMATE FOR REPAIR / RENOVATION OF  
BRANCH DSP CIA OFFICE KANDH KOT

AMOUNT :- Rs:1000,000

This estimate has been framed in the office of Superintending Engineer  
Works Department for the probable expenditure that will be incurred the above  
amount.


ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH  
D.S.P C.I.A OFFICE KANDH KOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 299522
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 614,648

Total Rs:1000,854

SAY RS :1000,000

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHAR  
Schedule "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (A)</u>					
Removing door with chowkats (SINO:33(a)P-12).	01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
Removing window and sky light with chowkats (SINO:33(b)P-12).	02	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	206
Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	21	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	31,661
Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc.complete (Deluxe modle (Bornze)(SINO:84(a)P-108).	24	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	39,545
Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	250	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	22,875
Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	64	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	6,670



ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	36	Sft 2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	85,127
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	30	Sft 443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	13,311
Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specification jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	280	Sft 30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only.	% Sft (hundred)	85,427
Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate without shuttering ratio (1:2:4) (SINO:5(f)P-18).	48	Cft 14429/25 Rs:Fourteen thousand Four hundred Twenty nine & Ps Twenty five only.	% Cft (hundred)	6,926
RCC work i/c all labour and material except the cost of reinforcement and its labour for bending and blinding which will be paid separately. This rate also i/c all kinds of forms lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) (a) RCC work in roof slab beams columns rafts lintels and other str: members laid in situ or precast laid in position completed in all respects ration ( 1:2:4 ) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge (SINO:6(i)P-16).	13	Cft 337/00 Rs: Three hundred Thirty seven only.	P.Cft (single)	4,381

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------

Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position, making joints and fastening including using Tor Bars (SINO:7-P-20).

0.65	Cwt	5001/70 Rs: Five thousand One & Ps Seventy only.	P.Cwt (single)	3,251
------	-----	--	-------------------	-------

Total 299522

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

QUOTE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDI

Volume: "13"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (A)</u>	
Removing door with chowkats (SINO:33(a)P-12). 1x1.0 =	01 No
Removing window and sky light with chowkats (SINO:33(b)P-12). 1x2.0 =	02 Nos
Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha 1x3.0x7.0 =	21 Sft
Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass 2x3.0x4.0 =	24 Sft
Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire 1x19.0x13.16 =	250 Sft
Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties 1x2(19.0+13.16) =	64 Sft
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking 3x4.0x3.0 =	36 Sft
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61). 3x4.0x2.50 =	30 Sft
Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate 1x20.0x14.0x0.17 =	48 Cft

PAGE NO: 2

ITEM OF WORK NO.L.B.D	QUANTITY
APPLYING CAMICAL POLISHIING ON MARBLE FLOORING QTY SAME AS ITEM NO; 5	= 250 SFT

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

STATEMENT FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDI KOT  
 Part B

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>				
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos 1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos 985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos 1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr 222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr 341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos 162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos 150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (7S 100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or Less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire run in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
P/F Energy sever superior quality including fixing on existing holder complete (SINO:6-P-33).	04	Nos	497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No	1054/00 Rs:One thousand Fifty four only.	Each (single)	1,004
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	01	No	999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total					87,191

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO



ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI

Module "B"

	ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (B) ELECTRIC WORK.</u>		
	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	1x15.0 = 15 Nos
	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	1x5.0 = 05 Nos
	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	1x2.0 = 02 Nos
	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:10-P-2).	1x50.0 = 50 Mtr
	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	1x54.0 = 54 Mtr
	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	1x10.0 = 10 Nos
	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	1x2.0 = 02 Nos
	Providing and fixing flush type electric bell push button (SINO:23-P-12).	1x2.0 = 02 Nos
	Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1x1.50 = 1.50 Sft
	Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	1x4.0 = 4 Nos
	Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	1x12.0 = 12 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (75-100NS) on prepared board as required (SINO:207-P-31).	1x1.0 = 01 No
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making	1x1.0 = 01 No
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	1x2.0 = 02 Nos
P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	1x4.0 = 04 Nos
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	1x1.0 = 01 No
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	1x1.0 = 01 No

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDIVITA  
 File "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>					
Providing and fixing A.C 6-10 Amp china type switch & socket of superior quality as approved by Engineer incharge.					
(a) 4-gang	08	Nos	700/00	Each	5,600
(b) 10 gang	04	Nos	1050/00	Each	4,200
(c) Bell Push	02	Nos	425/00	Each	850
(d) Telephone socket	04	Nos	550/00	Each	2,200
(e) Net Jack	04	Nos	550/00	Each	2,200
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
	10	Sft	600/00	P.Sft	6,000
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
	02	Nos	15000/00	Each	30,000
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
	05	Nos	7000/00	Each	35,000
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
	01	Job	7000/00	P-Job	7,000
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
	18	Meters	1111/00	P-Meters	19,998
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in all respect.					
	500	ft	60/00	P.Rft	30,000
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
	18	Nos	1250/00	Each	22,500

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
1/1" wall bracket fan 121 to 18" etc complete in all respect	04		4300/00	Each	8,600
Supplying and fixing DVR 04 channels H 264 or as required High definition HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
Commutation Rack 124 for DVR and other system with calling fan etc complete in all respect,	01	No	16250/00	Each	16,250
2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
Supplying and fixing 12 LED superior quality approved by Engineer incharge.	01	No	9000/00	Each	9,000
Supplying and fixing fancy type fibre glass wall paneling of approved design shape.	643	Sft	150/00	P.Sft	96,450
Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi or and other equivalent quality as approved by Engineer incharge.	02	Nos	94000/00	Each	188,000
AVF Stabilizer 7000-10000 watts as required approved by Engineer incharge.	02	Nos	22500/00	Each	45,000
				Total	614,140

  
 ASSISTANT ENGINEER  
 POLICE WORKS

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHAKA  
 Schedule "B"

ITEM OF WORK NO:L.B.D		QUANTITY
<u>PART (C) NON-SCHEDULE ITEM.</u>		
Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.		
(a) 4- gang	1x8.0	= 08 Nos
(b) 10 gang	1x4.0	= 04 Nos
(c) Bell Push	1x2.0	= 02 Nos
(d) Telephone socket	1x4.0	= 04 Nos
(e) Net Jack	1x4.0	= 04 Nos
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving		
	1x10.0	= 10 Sft
Providing and fixing shish am wood Almira 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking		
	1x2.0	= 02 Nos
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.		
	1x3.0	= 03 Nos
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing		
	1x1.0	= 01 Job
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all		
	1x18.0	= 18 Meters
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.		
	1x500.0	= 500 ft
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.		
	1x16.0	= 16 Nos
P/F wall breaket fan 12 to 18" etc complete in all respect.		
	1x2.0	= 02 Nos

Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.

1x1.0

=

01 No

PAGE NO: 2

ITEM OF WORK NO:L.B.D

QUANTITY

Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.

1x1.0

=

01 No

Accessories Power supply and BNC connector Both side etc complete in all respect.

1x4.0

=

04 Nos

Commutation Rack 124 for DVR and other system with calling line etc complete in all respect,

1x1.0

=

01 No

IP FB 3.5 sea gate surveillance (Design for video recording) etc complete in all respect

1x1.0

=

01 No

Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.

1x4.0

=

04 Nos

Supplying and fixing 12 LED superior quality approved by Engineer incharge.

1x1.0

=

01 No

Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.

1x2(19.0+13.16)x10.0

=

643 Sft

Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi or other equivalent quality as approved by Engineer incharge.

1X2.0

=

02 Nos

P/F Stabilizer 7000-10000 watts as required approved by Engineer incharge.

1X2.0

=

02 Nos

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH  
D.S.P C.I.A OFFICE KANDH KOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 299522
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 614,648

Total Rs:1000,854

SAY RS :1000,000



Superintendent Of Police  
Kashmore @ Kandhkot



ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI  
Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (A)</u>					
01	Removing door with chowkats (SINO:33(a)P-12).				
		01 No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).				
		02 Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	206
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).				
		21 Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	31,661
04	Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe model (Bronze)(SINO:84(a)P-108).				
		24 Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	39,545
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).				
		250 Sft	91/50 Rs:Ninety one & Ps Fifty only.	P Sft (single)	22,875
06	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).				
		64 Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	6,670

NO.	ITEM OF WORK.	QTY.	RATE	UNIT	AMOUNT
07	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	36	Sft 2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	85,127
08	Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	30	Sft 443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	13,311
09	Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specification jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	280	Sft 30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only.	% Sft (hundred)	85,427
10	Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate without shuttering ratio (1:2:4) (SINO:5(f)P-18).	48	Cft 14429/25 Rs:Fourteen thousand Four hundred Twenty nine & Ps Twenty five only.	% Cft (hundred)	6,926
11	RCC work i/c all labour and material except the cost of reinforcement and its labour for bending and blinding which will be paid separately. This rate also i/c all kinds of forms lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) (a) RCC work in roof slab beams columns rafts lintels and other str: members laid in situ or precast laid in position completed in all respects ration ( 1:2:4 ) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge (SINO:6(i)P-16).	13	Cft 337/00 Rs: Three hundred Thirty seven only.	P.Cft (single)	4,381

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------

Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position, making joints and fastening including using Tor Bars (SINO:7-P-20).

0.65	Cwt	5001/70	P.Cwt	3,251
		Rs: Five thousand	(single)	
		One & Ps Seventy only.		

Total 299522

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDH KOT  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
01	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15 Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
02	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05 Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
03	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02 Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
04	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50 Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
05	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54 Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
06	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33)	10 Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
07	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02 Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

SR	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
08	Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos 25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
09	P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft 1354/83 Rs: One thousand three hundred Fifty four & Ps Eighty three only	P.Sft	2,032
10	Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos 53/69 Rs: Fifty three & Ps Sixty nine only.	Each (single)	215
11	Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos 916/00 Rs: Nine hundred Sixteen only.	Each (single)	10,992
12	Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No 9261/00 Rs: Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
13	P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire run in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No 3610/04 Rs: Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
14	Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos 72/00 Rs: Seventy two only	Each (single)	144

Sl. No.	ITEM OF WORK.	QTY.	RATE	UNIT	AMOUNT
16	P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
16	Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs: One thousand Fifty four only.	Each (single)	1,054
17	Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total					37,184


  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHIKOT  
Schedule "B"

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>						
01	Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
	(a) 4- gang	08	Nos	700/00	Each	5,600
	(b) 10 gang	04	Nos	1050/00	Each	4,200
	(c) Bell Push	02	Nos	425/00	Each	850
	(d) Telephone socket	04	Nos	550/00	Each	2,200
	(e) Net Jack	04	Nos	550/00	Each	2,200
02	Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
		10	Sft	600/00	P.Sft	6,000
03	Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
		02	Nos	15000/00	Each	30,000
04	Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
		05	Nos	7000/00	Each	35,000
05	Providing and fixing in position name Plate form, made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
		01	Job	7000/00	P-Job	7,000
06	Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
		18	Meters	1111/00	P-Meters	19,998
07	P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
		500	ft	60/00	P.Rft	30,000
08	P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
		18	Nos	1250/00	Each	22,500



ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
P/F wall breaket fan 121 to 18" etc complete in all respect Nos 4300/00	Each		8,600		
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01	No	16250/00	Each	16,250
2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01	No	9000/00	Each	9,000
Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	643	Sft	150/00	P.Sft	96,450
Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi Or and other equivalent quality as approved by Engineer incharge.	02	Nos	94000/00	Each	188,000
P/F Stabilizer 7000-10000 watts as required approved by Engineer incharge.	02	Nos	22500/00	Each	45,000
Total					614,148

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

FACE SHEET

FOUNDRY HEAD :- PROVINCIAL GOVERNMENT.

WORKS HEAD :-

ESTIMATE HEAD :-

ESTIMATE HEAD :- ESTIMATE FOR REPAIR /RENOVATION OF LT SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

ESTIMATE :- Rs:1000,000

This estimate has been framed in the office of Superintending Engineer,  
Works Department for the probable expenditure that will be incurred the above  
estimate.

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT


---

GENERAL ABSTRACT

01.	PART (A)	Rs: 503,739
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 410,198

Total Rs:1,001,121

Say **Rs.1,000,000**

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRE @ KANDHAR  
Module "B"

NO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
<u>PART (A)</u>						
01	Removing door with chowkats (SINO:33(a)P-12).	01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
03	Removing window and sky light with chowkats (SINO:33(b)P-12).	03	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	310
36	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	36	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	54,277
380	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe model (Bornze)(SINO:84(a)P-108).	380	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	34,770
361	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	361	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	33,032
80	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	80	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	8,338

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------

Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).

84	Sft	2364/63	P.Sft	198,629
		Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	(single)	

Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).

70	Sft	443/71	P.Sft	31,060
		Rs: Four hundred Forty three & Ps Seventy one Only.	(single)	

Total 503,739

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRE @ KANPUR  
 Schedule "B"

Sl. No.	ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (A)</u>		
1	Removing door with chowkats (SINO:33(a)P-12). 1x1.0 =	01 No
2	Removing window and sky light with chowkats (SINO:33(b)P-12). 1x3.0 =	03 Nos
3	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha 1x4.0x9.0 =	36 Sft
4	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass 3x6.0x6.0 =	108 Sft
5	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire 1x19.0x19.0 =	361 Sft
6	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties 1x2(19.0+19.0) =	76 Rft
7	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking 7x4.0x3.0 =	84 Sft
8	Making and fixing deodar wood shelves including brackets 1"thick 7x4.0x2.50 =	70 Sft

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRE  
Module "B"

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>				
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos 1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos 985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos 1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr 222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr 341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos 162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos 150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	300

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred Fifty four & Ps Eighty three only	P.Sft	2,032
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
P/F earthling Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making the pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire run in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144



ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
177 Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1908
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total				87,164

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORE @ KAMPUR  
Module "B"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (B) ELECTRIC WORK.</u>	
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	1x15.0 = 15 Nos
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	1x5.0 = 05 Nos
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	1x2.0 = 02 Nos
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:10-P-2).	1x50.0 = 50 Mtr
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	1x54.0 = 54 Mtr
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-35).	1x10.0 = 10 Nos
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	1x2.0 = 02 Nos
Providing and fixing flush type electric bell push button (SINO:23-P-12).	1x2.0 = 02 Nos
P/fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1x1.50 = 1.50 Sft
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	1x4.0 = 4 Nos
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	1x12.0 = 12 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Providing and fixing circuit breaker <b>15,20,30,40,50,60,75 &amp; 100 Amp TP</b> (ZS-100NS) on prepared board as required (SINO:207-P-31).	1x1.0 = 01 No
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making	1x1.0 = 01 No
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	1x2.0 = 02 Nos
P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	1x4.0 = 04 Nos
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	1x1.0 = 01 No
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	1x1.0 = 01 No

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORI @ "A" -  
 Part "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>					
Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
(a) 4- gang	08	Nos	700/00	Each	5,600
(b) 10 gang	04	Nos	1050/00	Each	4,200
(c) Bell Push	02	Nos	425/00	Each	850
(d) Telephone socket	04	Nos	550/00	Each	2,200
(e) Net Jack	04	Nos	550/00	Each	2,200
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
	10	Sft	600/00	P.Sft	6,000
Providing and fixing shish am wood Almira 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
	02	Nos	15000/00	Each	30,000
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
	07	Nos	7000/00	Each	49,000
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
	01	Job	7000/00	P-Job	7,000
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
	18	Meters	1111/00	P-Meters	19,998
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
	500	ft	60/00	P.Rft	30,000
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
	16	Nos	1250/00	Each	20,000

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
IVT wall breaket fan 121 to 18" etc complete in all respect.	02	Nos	4300/00	Each	8,600
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01	No	16250/00	Each	16,250
2 1B 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01	No	9000/00	Each	9,000
Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	760	Sft	150/00	P.Sft	114,000
				Total	410,198

QUOTE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDHPOLE  
 Schedule "B"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (C) NON-SCHEDULE ITEM.</u>	
Providing and fixing A,C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.	
(a) 4- gang 1x8.0 =	08 Nos
(b) 10 gang 1x4.0 =	04 Nos
(c) Bell Push 1x2.0 =	02 Nos
(d) Telephone socket 1x4.0 =	04 Nos
(e) Net Jack 1x4.0 =	04 Nos
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving	
1x10.0 =	10 Sft
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking	
1x2.0 =	02 Nos
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.	
1x7.0 =	07 Nos
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing	
1x1.0 =	01 Job
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all	
1x18.0 =	18 Meters
P/W Internet wire cat-6 i/c fixing on ¾" channel putty etc complete in All respect.	
1x500.0 =	500 ft
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.	
1x16.0 =	16 Nos
P/W wall breaket fan 121 to 18" etc complete in all respect.	
1x2.0 =	02 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	1x1.0 = 01 No
Accessories Power supply and BNC connector Both side etc complete in all respect.	1x4.0 = 04 Nos
Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	1x1.0 = 01 No
2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	1x1.0 = 01 No
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	1x4.0 = 04 Nos
Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	1x1.0 = 01 No
Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	1x2(19.0+19.0)x10.0 = 760 Sft

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO


ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 503,739
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 410,198

Total Rs:1,001,121

Say Rs.1,000,000


  
Superintendent Of Police  
Kashmore @ Kandhkot



ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRE @ KANUR  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
<u>PART (A)</u>						
01	Removing door with chowkats (SINO:33(a)P-12).	01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).	03	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	310
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	36	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	54,277
04	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe modle (Bornze)(SINO:84(a)P-108).	380	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	34,770
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	361	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	33,032
06	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	80	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	8,338

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
07	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	84	2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	198,620
08	Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	70	443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	31,060
Total					503,739

  
**Superintendent Of Police**  
**Kashmore @ Kandhkot**

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRE @ KANDHAR  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
01	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single) 16,950
02	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single) 4,925
03	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single) 3,528
04	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single) 11,100
05	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single) 18,414
06	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single) 1,620
07	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single) 301

ITEM NO.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
08	Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos 25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
09	P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft 1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
10	Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos 53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
11	Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos 916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
12	Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No 9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
13	P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire ruynb in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No 3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
14	Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos 72/00 Rs:Seventy two only	Each (single)	144

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
15 P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos	497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
16 Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No	1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
17 Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No	999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999

Total 37,164


  
 Superintendent Of Police  
 Kashmore @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDI IFC  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>						
01	Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
	(a) 4-gang	08	Nos	700/00	Each	5,600
	(b) 10 gang	04	Nos	1050/00	Each	4,200
	(c) Bell Push	02	Nos	425/00	Each	850
	(d) Telephone socket	04	Nos	550/00	Each	2,200
	(e) Net Jack	04	Nos	550/00	Each	2,200
02	Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
		10	Sft	600/00	P.Sft	6,000
03	Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
		02	Nos	15000/00	Each	30,000
04	Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
		07	Nos	7000/00	Each	49,000
05	Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
		01	Job	7000/00	P-Job	7,000
06	Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
		18	Meters	1111/00	P-Meters	19,998
06	P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
		500	ft	60/00	P.Rft	30,000
07	P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
		16	Nos	1250/00	Each	20,000

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
09	P/F wall breaket fan 121 to 18" etc complete in all respect.	02	Nos	4300/00	Each	8,600
10	Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
11	Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
12	Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01	No	16250/00	Each	16,250
13	2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
14	Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
15	Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01	No	9000/00	Each	9,000
16	Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	760	Sft	150/00	P.Sft	114,000

Total 410,198

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

FACE SHEET

PROVIDER HEAD :- PROVINCIAL GOVERNMENT.

WORK HEAD :-

WORK HEAD :-

WORK HEAD :- ESTIMATE FOR REPAIR / RENOVATION OF OFFICE  
BRANCH DSP CIA OFFICE KANDH KOT

ESTIMATE :- Rs:1000,000

This estimate has been framed in the office of Superintending Engineer  
Public Works Department for the probable expenditure that will be incurred the above  
estimate.




ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH  
D.S.P C.I.A OFFICE KANDH KOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 299522
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 614,648

Total Rs:1000,854

SAY RS :1000,000

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHAR  
 File "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (A)</u>					
Removing door with chowkats (SINO:33(a)P-12).	01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
Removing window and sky light with chowkats (SINO:33(b)P-12).	02	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	206
Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	21	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	31,661
Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc.complete (Deluxe modle (Bornze)(SINO:84(a)P-108).	24	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	39,545
Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	250	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	22,875
Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	64	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	6,670

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	36	Sft	2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single) 85,12
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	30	Sft	443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single) 13,311
Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specification jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	280	Sft	30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only.	% Sft (hundred) 85,42
Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate without shuttering ratio (1:2:4) (SINO:5(f)P-18).	48	Cft	14429/25 Rs:Fourteen thousand Four hundred Twenty nine & Ps Twenty five only.	% Cft (hundred) 6,92
RCC work i/c all labour and material except the cost of reinforcement and its labour for bending and blinding which will be paid separately. This rate also i/c all kinds of forms lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) (a) RCC work in roof slab beams columns rafts lintels and other str: members laid in situ or precast laid in position completed in all respects ration ( 1:2:4 ) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge (SINO:6(i)P-16).	13	Cft	337/00 Rs: Three hundred Thirty seven only.	P.Cft (single) 4,381

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------

Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position, making joints and fastening including using Tor Bars (SINO:7-P-20).

0.65	Cwt	5001/70	P.Cwt	3,251
		Rs: Five thousand One & Ps Seventy only.	(single)	

Total 299522

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

QUOTE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDI

Module "B"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (A)</u>	
Removing door with chowkats (SINO:33(a)P-12). 1x1.0 =	01 No
Removing window and sky light with chowkats (SINO:33(b)P-12). 1x2.0 =	02 Nos
Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha 1x3.0x7.0 =	21 Sft
Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass 2x3.0x4.0 =	24 Sft
Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire 1x19.0x13.16 =	250 Sft
Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties 1x2(19.0+13.16) =	64 Sft
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking 3x4.0x3.0 =	36 Sft
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61). 3x4.0x2.50 =	30 Sft
Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate 1x20.0x14.0x0.17 =	48 Cft

PAGE NO: 2

ITEM OF WORK NO: L.B.D

QUANTITY

APPLYING CAMICAL POLISHIING ON MARBLE FLOORING

QTY SAME AS ITEM NO; 5

= 250 SFT

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDI KOT  
Module "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	50
P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	216
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (TS 100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire run in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,614
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144



ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
P/F Energy sever superior quality including fixing on existing holder complete (SINO:6-P-33).	04	Nos	497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No	1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No	999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total					87,187

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI

Module "B"

	ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (B) ELECTRIC WORK.</u>		
100	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	1x15.0 = 15 Nos
101	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	1x5.0 = 05 Nos
102	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	1x2.0 = 02 Nos
103	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	1x50.0 = 50 Mtr
104	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	1x54.0 = 54 Mtr
105	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	1x10.0 = 10 Nos
106	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	1x2.0 = 02 Nos
107	Providing and fixing flush type electric bell push button (SINO:23-P-12).	1x2.0 = 02 Nos
108	P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1x1.50 = 1.50 Sft
109	Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	1x4.0 = 4 Nos
110	Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	1x12.0 = 12 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (75-100NS) on prepared board as required (SINO:207-P-31).	1x1.0 = 01 No
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making	1x1.0 = 01 No
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	1x2.0 = 02 Nos
P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	1x4.0 = 04 Nos
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	1x1.0 = 01 No
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	1x1.0 = 01 No

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

QUOTE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDIVATI  
 Part "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>					
Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
(a) 4- gang	08	Nos	700/00	Each	5,600
(b) 10 gang	04	Nos	1050/00	Each	4,200
(c) Bell Push	02	Nos	425/00	Each	850
(d) Telephone socket	04	Nos	550/00	Each	2,200
(e) Net Jack	04	Nos	550/00	Each	2,200
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
	10	Sft	600/00	P.Sft	6,000
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
	02	Nos	15000/00	Each	30,000
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
	05	Nos	7000/00	Each	35,000
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
	01	Job	7000/00	P-Job	7,000
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
	18	Meters	1111/00	P-Meters	19,998
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in all respect.					
	500	ft	60/00	P.Rft	30,000
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
	18	Nos	1250/00	Each	22,500

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
1/1 wall breaket fan 121 to 18" etc complete in all respect Nos 4300/00	Each		8,600		02
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
Commutation Rack 124 for DVR and other system with calling fan etc complete in all respect,	01	No	16250/00	Each	16,250
2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
Supplying and fixing 12 LED superior quality approved by Engineer incharge.	01	No	9000/00	Each	9,000
Supplying and fixing fancy type fibre glass wall paneling of approved design shape.	643	Sft	150/00	P.Sft	96,450
Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi or and other equivalent quality as approved by Engineer incharge.	02	Nos	94000/00	Each	188,000
1/1 Stabilizer 7000-10000 watts as required approved by Engineer incharge.	02	Nos	22500/00	Each	45,000
Total					614,140

  
 ASSISTANT ENGINEER  
 POLICE WORKS

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHROU  
 Schedule "B"

ITEM OF WORK	NO:L.B.D		QUANTITY	
<u>PART (C) NON-SCHEDULE ITEM.</u>				
Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.				
(a) 4- gang	1x8.0	=	08	Nos
(b) 10 gang	1x4.0	=	04	Nos
(c) Bell Push	1x2.0	=	02	Nos
(d) Telephone socket	1x4.0	=	04	Nos
(e) Net Jack	1x4.0	=	04	Nos
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving				
	1x10.0	=	10	Sft
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking				
	1x2.0	=	02	Nos
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.				
	1x3.0	=	03	Nos
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing				
	1x1.0	=	01	Job
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all				
	1x18.0	=	18	Meters
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.				
	1x500.0	=	500	ft
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.				
	1x16.0	=	16	Nos
P/F wall breaket fan 12 to 18" etc complete in all respect.				
	1x2.0	=	02	Nos

Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.

1x1.0 = 01 No

PAGE NO: 2

ITEM OF WORK NO:L.B.D	QUANTITY
-----------------------	----------

Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.

1x1.0 = 01 No

Accessories Power supply and BNC connector Both side etc complete in all respect.

1x4.0 = 04 Nos

Commutation Rack 124 for DVR and other system with calling Bin etc complete in all respect,

1x1.0 = 01 No

2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect

1x1.0 = 01 No

Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.

1x4.0 = 04 Nos

Supplying and fixing 12 LED superior quality approved by Engineer incharge.

1x1.0 = 01 No

Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.

1x2(19.0+13.16)x10.0 = 643 Sft

Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi Or and other equivalent quality as approved by Engineer incharge.

1X2.0 = 02 Nos

P/F Stabilizer 7000-10000 watts as required approved by Engineer incharge.

1X2.0 = 02 Nos

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

FACE SHEET

OWNER HEAD :- PROVINCIAL GOVERNMENT.

WORK HEAD :-

ITEM HEAD :-

NAME HEAD :- ESTIMATE FOR REPAIR / RENOVATION OF  
BRANCH DSP CIA OFFICE KANDH KOT

AMOUNTING :- Rs:1000,000

This estimate has been framed in the office of Superintending Engineer  
Works Department for the probable expenditure that will be incurred the above




ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH  
D.S.P C.I.A OFFICE KANDH KOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 299522
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 614,648

Total Rs:1000,854

SAY RS :1000,000

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI  
 Schedule "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (A)</u>					
Removing door with chowkats (SINO:33(a)P-12).					
	01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
Removing window and sky light with chowkats (SINO:33(b)P-12).					
	02	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	206
Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).					
	21	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	31,661
Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc.complete (Deluxe modle (Bornze)(SINO:84(a)P-108).					
	24	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	39,545
Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).					
	250	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	22,875
Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).					
	64	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	6,670

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	36	Sft 2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	85,127
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	30	Sft 443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	13,311
Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specification jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	280	Sft 30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only.	% Sft (hundred)	85,427
Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate without shuttering ratio (1:2:4) (SINO:5(f)P-18).	48	Cft 14429/25 Rs:Fourteen thousand Four hundred Twenty nine & Ps Twenty five only.	% Cft (hundred)	6,925
RCC work i/c all labour and material except the cost of reinforcement and its labour for bending and blinding which will be paid separately. This rate also i/c all kinds of forms lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) (a) RCC work in roof slab beams columns rafts lintels and other str: members laid in situ or precast laid in position completed in all respects ration ( 1:2:4 ) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge (SINO:6(i)P-16).	13	Cft 337/00 Rs: Three hundred Thirty seven only.	P.Cft (single)	4,381

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------

Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position, making joints and fastening including using Tor Bars (SINO:7-P-20).

0.65	Cwt	5001/70 Rs: Five thousand One & Ps Seventy only.	P.Cwt	3,251
			(single)	

Total 299522

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

QUOTE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDI

Volume "13"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (A)</u>	
Removing door with chowkats (SINO:33(a)P-12). 1x1.0	= 01 No
Removing window and sky light with chowkats (SINO:33(b)P-12). 1x2.0	= 02 Nos
Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha 1x3.0x7.0	= 21 Sft
Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass 2x3.0x4.0	= 24 Sft
Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire 1x19.0x13.16	= 250 Sft
Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties 1x2(19.0+13.16)	= 64 Sft
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking 3x4.0x3.0	= 36 Sft
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61). 3x4.0x2.50	= 30 Sft
Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate 1x20.0x14.0x0.17	= 48 Cft

PAGE NO: 2

ITEM OF WORK NO: L.B.D	QUANTITY
APPLYING CAMICAL POLISHIING ON MARBLE FLOORING QTY SAME AS ITEM NO; 5	= 250 SFT

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

BILL OF MATERIALS FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDH KOT  
Module 'B'

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (TS 100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire run in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,614
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144




ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
17/ Energy sever superior quality including fixing on existing holder complete (SINO:6-P-33).	04	Nos	497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No	1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No	999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total					37,194

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI  
Module "B"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (B) ELECTRIC WORK.</u>	
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	1x15.0 = 15 Nos
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	1x5.0 = 05 Nos
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	1x2.0 = 02 Nos
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:10-P-2).	1x50.0 = 50 Mtr
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	1x54.0 = 54 Mtr
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	1x10.0 = 10 Nos
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	1x2.0 = 02 Nos
Providing and fixing flush type electric bell push button (SINO:23-P-12).	1x2.0 = 02 Nos
Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1x1.50 = 1.50 Sft
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	1x4.0 = 4 Nos
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	1x12.0 = 12 Nos

ITEM OF WORK NO:L.B.D		QUANTITY	
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	1x1.0 =	01	No
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making	1x1.0 =	01	No
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	1x2.0 =	02	Nos
P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	1x4.0 =	04	Nos
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	1x1.0 =	01	No
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	1x1.0 =	01	No

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

QUOTE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDIVAR  
 Part "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>					
Providing and fixing A.C 6-10 Amp china type switch & socket of superior quality as approved by Engineer incharge.					
(a) 4- gang	08	Nos	700/00	Each	5,600
(b) 10 gang	04	Nos	1050/00	Each	4,200
(c) Bell Push	02	Nos	425/00	Each	850
(d) Telephone socket	04	Nos	550/00	Each	2,200
(e) Net Jack	04	Nos	550/00	Each	2,200
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
	10	Sft	600/00	P.Sft	6,000
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
	02	Nos	15000/00	Each	30,000
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
	05	Nos	7000/00	Each	35,000
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
	01	Job	7000/00	P-Job	7,000
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
	18	Meters	1111/00	P-Meters	19,998
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in all respect.					
	500	ft	60/00	P.Rft	30,000
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
	18	Nos	1250/00	Each	22,500

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
1/6" wall bracket fan 121 to 18" etc complete in all respect IPBs	4300/00	Each	8,600		02
Supplying and fixing DVR 04 channels H 264 or as required High definition HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
Commutation Rack 124 for DVR and other system with calling fan etc complete in all respect,	01	No	16250/00	Each	16,250
2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
Supplying and fixing 12 LED superior quality approved by Engineer incharge.	01	No	9000/00	Each	9,000
Supplying and fixing fancy type fibre glass wall paneling of approved design shape.	643	Sft	150/00	P.Sft	96,450
Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi or and other equivalent quality as approved by Engineer incharge.	02	Nos	94000/00	Each	188,000
1/6" Stabilizer 7000-10000 watts as required approved by Engineer incharge.	02	Nos	22500/00	Each	45,000
				Total	614,140

  
 ASSISTANT ENGINEER  
 POLICE WORKS



Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.

1x1.0

=

01

No

PAGE NO: 2

ITEM OF WORK NO:L.B.D	QUANTITY
-----------------------	----------

Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.

1x1.0

=

01

No

Accessories Power supply and BNC connector Both side etc complete in all respect.

1x4.0

=

04

Nos

Commutation Rack 124 for DVR and other system with calling fan etc complete in all respect,

1x1.0

=

01

No

2 TB 3.5 sea gate surveillance (Design for video recording) etc complete in all respect

1x1.0

=

01

No

Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.

1x4.0

=

04

Nos

Supplying and fixing 12 LED superior quality approved by Engineer incharge.

1x1.0

=

01

No

Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.

1x2(19.0+13.16)x10.0

=

643

Sft

Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi or other equivalent quality as approved by Engineer incharge.

1X2.0

=

02

Nos

PVF Stabilizer 7000-10000 watts as required approved by Engineer incharge.

1X2.0

=

02

Nos

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

FACE SHEET

PROVIDER HEAD :- PROVINCIAL GOVERNMENT.

FOR HEAD :-

FOR HEAD :-

ESTIMATE HEAD :- ESTIMATE FOR REPAIR / RENOVATION OF CIVIL  
BRANCH DSP CIA OFFICE KANDH KOT

AMOUNT :- Rs:1000,000

This estimate has been framed in the office of Superintending Engineer  
Works Department for the probable expenditure that will be incurred the above




ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH  
D.S.P C.I.A OFFICE KANDH KOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 299522
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 614,648

Total Rs:1000,854

SAY RS :1000,000

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHAR  
Module "B"

NO.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
<u>PART (A)</u>						
01	Removing door with chowkats (SINO:33(a)P-12).	01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).	02	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	206
21	Supplying & fixing in position Aluminum channels framing for hinged doors (Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	21	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	31,661
24	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc.complete (Deluxe modle (Bornze)(SINO:84(a)P-108).	24	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	39,545
250	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	250	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	22,875
64	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	64	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	6,670

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	36	Sft 2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	85,127
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	30	Sft 443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	13,311
Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specification jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	280	Sft 30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only.	% Sft (hundred)	85,427
Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate without shuttering ratio (1:2:4) (SINO:5(f)P-18).	48	Cft 14429/25 Rs:Fourteen thousand Four hundred Twenty nine & Ps Twenty five only.	% Cft (hundred)	6,925
RCC work i/c all labour and material except the cost of reinforcement and its labour for bending and blinding which will be paid separately. This rate also i/c all kinds of forms lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) (a) RCC work in roof slab beams columns rafts lintels and other str: members laid in situ or precast laid in position completed in all respects ration ( 1:2:4 ) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge (SINO:6(i)P-16).	13	Cft 337/00 Rs: Three hundred Thirty seven only.	P.Cft (single)	4,381

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------

Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position, making joints and fastening including using Tor Bars (SINO:7-P-20).

0.65	Cwt	5001/70	P.Cwt	3,251
		Rs: Five thousand	(single)	
		One & Ps Seventy only.		

Total 299522

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

QUOTE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDI

Volume: "13"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (A)</u>	
Removing door with chowkats (SINO:33(a)P-12). 1x1.0 =	01 No
Removing window and sky light with chowkats (SINO:33(b)P-12). 1x2.0 =	02 Nos
Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha 1x3.0x7.0 =	21 Sft
Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass 2x3.0x4.0 =	24 Sft
Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire 1x19.0x13.16 =	250 Sft
Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties 1x2(19.0+13.16) =	64 Sft
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking 3x4.0x3.0 =	36 Sft
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61). 3x4.0x2.50 =	30 Sft
Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate 1x20.0x14.0x0.17 =	48 Cft

PAGE NO: 2

ITEM OF WORK NO: L.B.D

QUANTITY

APPLYING CAMICAL POLISHIING ON MARBLE FLOORING

QTY SAME AS ITEM NO; 5

= 250 SFT

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

BUDGET FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDI KOP  
Part B

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	1015
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (7S 100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or Less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12"deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire run in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144



ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
17/ Energy sever superior quality including fixing on existing holder w. complete (SINO:6-P-33).	04	Nos	497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No	1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No	999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total					87,197

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI

Module "B"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (B) ELECTRIC WORK.</u>	
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	1x15.0 = 15 Nos
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	1x5.0 = 05 Nos
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	1x2.0 = 02 Nos
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	1x50.0 = 50 Mtr
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	1x54.0 = 54 Mtr
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	1x10.0 = 10 Nos
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	1x2.0 = 02 Nos
Providing and fixing flush type electric bell push button (SINO:23-P-12).	1x2.0 = 02 Nos
P/fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1x1.50 = 1.50 Sft
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	1x4.0 = 4 Nos
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	1x12.0 = 12 Nos

ITEM OF WORK NO:L.B.D		QUANTITY	
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (7S-100NS) on prepared board as required (SINO:207-P-31).	1x1.0 =	01	No
I/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making	1x1.0 =	01	No
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	1x2.0 =	02	Nos
I/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	1x4.0 =	04	Nos
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	1x1.0 =	01	No
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	1x1.0 =	01	No

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDIVATI  
Part "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>					
Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
(a) 4- gang	08	Nos	700/00	Each	5,600
(b) 10 gang	04	Nos	1050/00	Each	4,200
(c) Bell Push	02	Nos	425/00	Each	850
(d) Telephone socket	04	Nos	550/00	Each	2,200
(e) Net Jack	04	Nos	550/00	Each	2,200
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
	10	Sft	600/00	P.Sft	6,000
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
	02	Nos	15000/00	Each	30,000
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
	05	Nos	7000/00	Each	35,000
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
	01	Job	7000/00	P-Job	7,000
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
	18	Meters	1111/00	P-Meters	19,998
P/W Internet wire cat-6 i/c fixing on ¾" channel putty etc complete in All respect.					
	500	ft	60/00	P.Rft	30,000
P/W LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
	18	Nos	1250/00	Each	22,500

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
1/1 wall breaket fan 121 to 18" etc complete in all respect Nos	4300/00	Each	8,600		02
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
Commutation Rack 124 for DVR and other system with calling fan etc complete in all respect,	01	No	16250/00	Each	16,250
1 IB 3.5 sea gate surveillane (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
Supplying and fixing 12 LED superior quality approved by Engineer incharge.	01	No	9000/00	Each	9,000
Supplying and fixing fancy type fibre glass wall paneling of approved design in shape.	643	Sft	150/00	P.Sft	96,450
Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi or and other equivalent quality as approved by Engineer incharge.	02	Nos	94000/00	Each	188,000
1/1 Stabilizer 7000-10000 watts as required approved by Engineer incharge.	02	Nos	22500/00	Each	45,000
				Total	614,140

  
 ASSISTANT ENGINEER  
 POLICE WORKS

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHAKU  
 Schedule "B"

ITEM OF WORK	NO:L.B.D		QUANTITY	
<u>PART (C) NON-SCHEDULE ITEM.</u>				
Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.				
(a) 4- gang	1x8.0	=	08	Nos
(b) 10 gang	1x4.0	=	04	Nos
(c) Bell Push	1x2.0	=	02	Nos
(d) Telephone socket	1x4.0	=	04	Nos
(e) Net Jack	1x4.0	=	04	Nos
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving				
	1x10.0	=	10	Sft
Providing and fixing shish am wood Almira h 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking				
	1x2.0	=	02	Nos
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.				
	1x3.0	=	03	Nos
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing				
	1x1.0	=	01	Job
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all				
	1x18.0	=	18	Meters
P/F- Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.				
	1x500.0	=	500	ft
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.				
	1x16.0	=	16	Nos
P/F wall breaket fan 121 to 18" etc complete in all respect.				
	1x2.0	=	02	Nos

Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.

1x1.0 = 01 No

PAGE NO: 2

ITEM OF WORK NO:L.B.D	QUANTITY
-----------------------	----------

Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.

1x1.0 = 01 No

Accessories Power supply and BNC connector Both side etc complete in all respect.

1x4.0 = 04 Nos

Commutation Rack 124 for DVR and other system with calling etc complete in all respect,

1x1.0 = 01 No

IP 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect

1x1.0 = 01 No

Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.

1x4.0 = 04 Nos

Supplying and fixing 12 LED superior quality approved by Engineer incharge.

1x1.0 = 01 No

Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.

1x2(19.0+13.16)x10.0 = 643 Sft

Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi or and other equivalent quality as approved by Engineer incharge.

1X2.0 = 02 Nos

P/F Stabilizer 7000-10000 watts as required approved by Engineer incharge.

1X2.0 = 02 Nos

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH  
D.S.P C.I.A OFFICE KANDH KOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 299522
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 614,648

---

Total Rs:1000,854

SAY RS :1000,000



Superintendent Of Police  
Kashmore @ Kandhkot



ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHUKOT  
Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (A)</u>					
01	Removing door with chowkats (SINO:33(a)P-12).				
		01	No 142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).				
		02	Nos 102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	206
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).				
		21	Sft 1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	31,661
04	Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe modle (Bornze)(SINO:84(a)P-108).				
		24	Sft 1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	39,545
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).				
		250	Sft 91/50 Rs:Ninety one & Ps Fifty only.	P Sft (single)	22,875
06	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).				
		64	Rft 104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	6,670

Sl. No.	ITEM OF WORK.	QTY.	RATE	UNIT	AMOUNT	
07	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	36	Sft	2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	85,127
08	Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	30	Sft	443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	13,311
09	Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specification jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	280	Sft	30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only.	% Sft (hundred)	85,427
10	Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate without shuttering ratio (1:2:4) (SINO:5(f)P-18).	48	Cft	14429/25 Rs:Fourteen thousand Four hundred Twenty nine & Ps Twenty five only.	% Cft (hundred)	6,926
11	RCC work i/c all labour and material except the cost of reinforcement and its labour for bending and blinding which will be paid separately. This rate also i/c all kinds of forms lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) (a) RCC work in roof slab beams columns rafts lintels and other str. members laid in situ or precast laid in position completed in all respects ration ( 1:2:4 ) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge (SINO:6(i)P-16).	13	Cft	337/00 Rs: Three hundred Thirty seven only.	P.Cft (single)	4,361

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------

12 Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position, making joints and fastening including using Tor Bars (SINO:7-P-20).

0.65	Cwt	5001/70 Rs: Five thousand One & Ps Seventy only.	P.Cwt (single)	3,251
------	-----	--	-------------------	-------

Total 299522

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDH KOT  
Schedule "B"

NO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
01	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15 Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
02	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05 Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
03	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02 Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
04	Providing and laying (main or Sub-Main)PVC insulated with size 7/.029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50 Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
05	Providing and laying (main or sub-main )PVC insulated wire size 2-7/.044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54 Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
06	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33)	10 Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
07	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02 Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
08) Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
09) P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
10) Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
11) Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
12) Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
13) P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire ruynb in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
14) Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
15. P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos	497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
16. Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No	1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
17. Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No	999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999


Total 37,041

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDIHKOT  
Schedule "B"

NO	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
	<u>PART (C) NON-SCHEDULE ITEM.</u>					
01	Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
	(a) 4- gang	08	Nos	700/00	Each	5,600
	(b) 10 gang	04	Nos	1050/00	Each	4,200
	(c) Bell Push	02	Nos	425/00	Each	850
	(d) Telephone socket	04	Nos	550/00	Each	2,200
	(e) Net Jack	04	Nos	550/00	Each	2,200
02	Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
		10	Sft	600/00	P.Sft	6,000
03	Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
		02	Nos	15000/00	Each	30,000
04	Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
		05	Nos	7000/00	Each	35,000
05	Providing and fixing in position name Plate form, made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
		01	Job	7000/00	P-Job	7,000
06	Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
		18	Meters	1111/00	P-Meters	19,998
06	P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
		500	ft	60/00	P.Rft	30,000
07	P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
		18	Nos	1250/00	Each	22,500

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
08 P/F wall breaket fan 121 to 18" etc complete in all respect Nos 4300/00	Each		8,600		0.7
09 Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
10 Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
11 Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01	No	16250/00	Each	16,250
12 2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
13 Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
14 Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01	No	9000/00	Each	9,000
15 Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	643	Sft	150/00	P.Sft	96,450
16 Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi Or and other equivalent quality as approved by Engineer incharge.	02	Nos	94000/00	Each	188,000
17 P/F Stabilizer 7000-10000 watts as required approved by Engineer incharge.	02	Nos	22500/00	Each	45,000
Total					614,148

  
 Superintendent Of Police  
 Kashmir @ Kandhkot



ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH  
D.S.P C.I.A OFFICE KANDH KOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 299522
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 614,648

Total Rs:1000,854

SAY RS :1000,000



Superintendent Of Police  
Kashmore @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI  
Module "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (A)</u>					
01	Removing door with chowkats (SINO:33(a)P-12).				
		01	No 142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).				
		02	Nos 102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	206
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).				
		21	Sft 1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	31,661
04	Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe modle (Bornze)(SINO:84(a)P-108).				
		24	Sft 1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	39,545
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).				
		250	Sft 91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	22,875
06	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).				
		64	Rft 104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	6,670

NO.	ITEM OF WORK.	QTY.	RATE	UNIT	AMOUNT	
07	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	36	Sft	2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	85,127
08	Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	30	Sft	443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	13,311
09	Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specification jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	280	Sft	30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only.	% Sft (hundred)	85,427
10	Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate without shuttering ratio (1:2:4) (SINO:5(f)P-18).	48	Cft	14429/25 Rs:Fourteen thousand Four hundred Twenty nine & Ps Twenty five only.	% Cft (hundred)	6,926
11	RCC work i/c all labour and material except the cost of reinforcement and its labour for bending and blinding which will be paid separately. This rate also i/c all kinds of forms lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) (a) RCC work in roof slab beams columns rafts lintels and other str: members laid in situ or precast laid in position completed in all respects ration ( 1:2:4 ) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge (SINO:6(i)P-16).	13	Cft	337/00 Rs: Three hundred Thirty seven only.	P.Cft (single)	4,381

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------

12 Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position, making joints and fastening including using Tor Bars (SINO:7-P-20).

0.65	Cwt	5001/70 Rs: Five thousand One & Ps Seventy only.	P.Cwt (single)	3,251
------	-----	--	-------------------	-------

Total 299522

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDH KOI  
Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
01	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos 1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	15,980
02	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos 985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
03	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos 1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
04	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr 222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
05	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr 341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
06	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33)	10	Nos 162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
07	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos 150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
08) Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
09) P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs: One thousand three hundred Fifty four & Ps Eighty three only	P.Sft	2,032
10) Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs: Fifty three & Ps Sixty nine only.	Each (single)	215
11) Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs: Nine hundred Sixteen only.	Each (single)	10,992
12) Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs: Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
13) P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or Less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire ruynb in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs: Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
14) Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs: Seventy two only	Each (single)	144

Sl. No.	ITEM OF WORK.	QTY.	RATE	UNIT	AMOUNT
15	P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
16	Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
17	Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total					37,144


  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHUKOT  
Schedule "B"

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>						
01	Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
	(a) 4- gang	08	Nos	700/00	Each	5,600
	(b) 10 gang	04	Nos	1050/00	Each	4,200
	(c) Bell Push	02	Nos	425/00	Each	850
	(d) Telephone socket	04	Nos	550/00	Each	2,200
	(e) Net Jack	04	Nos	550/00	Each	2,200
02	Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
		10	Sft	600/00	P.Sft	6,000
03	Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
		02	Nos	15000/00	Each	30,000
04	Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
		05	Nos	7000/00	Each	35,000
05	Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing Monogram of Affidavit branch on Glass door etc complete.					
		01	Job	7000/00	P-Job	7,000
06	Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
		18	Meters	1111/00	P-Meters	19,998
06	P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
		500	ft	60/00	P.Rft	30,000
07	P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
		18	Nos	1250/00	Each	22,500



ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
P/F wall breaket fan 121 to 18" etc complete in all respect Nos 4300/00	Each		8,600		02
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01	No	16250/00	Each	16,250
2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01	No	9000/00	Each	9,000
Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	643	Sft	150/00	P.Sft	96,450
Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi Or and other equivalent quality as approved by Engineer incharge.	02	Nos	94000/00	Each	188,000
P/F Stabilizer 7000-10000 watts as required approved by Engineer incharge.	02	Nos	22500/00	Each	45,000
Total					614,148

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH  
D.S.P C.I.A OFFICE KANDH KOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 299522
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 614,648

Total Rs:1000,854

SAY RS :1000,000



Superintendent Of Police  
Kashmore @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI  
Schedule "B"

NO.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (A)</u>					
01	Removing door with chowkats (SINO:33(a)P-12).				
		01 No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).				
		02 Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	206
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).				
		21 Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	31,661
04	Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe model (Bronze))(SINO:84(a)P-108).				
		24 Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	39,546
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).				
		250 Sft	91/50 Rs:Ninety one & Ps Fifty only.	P Sft (single)	22,875
06	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).				
		64 Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	6,670

Sl. No.	ITEM OF WORK.	QTY.	RATE	UNIT	AMOUNT	
07	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	36	Sft	2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	85,127
08	Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	30	Sft	443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	13,311
09	Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specification jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	280	Sft	30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only.	% Sft (hundred)	85,427
10	Cement concrete plain including placing compacting finishing and curing complete(including screening and washing of stone aggregate without shuttering ratio (1:2:4) (SINO:5(f)P-18).	48	Cft	14429/25 Rs:Fourteen thousand Four hundred Twenty nine & Ps Twenty five only.	% Cft (hundred)	6,926
11	RCC work i/c all labour and material except the cost of reinforcement and its labour for bending and blinding which will be paid separately. This rate also i/c all kinds of forms lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) (a) RCC work in roof slab beams columns rafts lintels and other str: members laid in situ or precast laid in position completed in all respects ration ( 1:2:4 ) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge (SINO:6(i)P-16).	13	Cft	337/00 Rs: Three hundred Thirty seven only.	P.Cft (single)	4,381

NO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
----	---------------	-----	------	------	--------

17 Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position, making joints and fastening including using Tor Bars (SINO:7-P-20).

0.65	Cwt	5001/70	P.Cwt	3,251
		Rs: Five thousand	(single)	
		One & Ps Seventy only.		

Total 299522

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDH KOT  
Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
01	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single) 15,980
02	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single) 4,925
03	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single) 3,528
04	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single) 11,100
05	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single) 18,414
06	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33)	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single) 1,620
07	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single) 301

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
08 Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
09 P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs: One thousand three hundred Fifty four & Ps Eighty three only	P.Sft	2,032
10 Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs: Fifty three & Ps Sixty nine only.	Each (single)	215
11 Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs: Nine hundred Sixteen only.	Each (single)	10,992
12 Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs: Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
13 P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or Less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire ruynb in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs: Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
14 Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs: Seventy two only	Each (single)	144

ITEM OF WORK.	QTY.		RATE	UNIT	AMOUNT
15 P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos	497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
16 Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No	1054/00 Rs: One thousand Fifty four only.	Each (single)	1,054
17 Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No	999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total					37,134

  
 Superintendent Of Police  
 Kashmir @ Kandhkot




## ESTIMATE FOR REPAIR / RENOVATION OF CRO BRANCH DSP CIA OFFICE KANDHKOI

## Schedule "B"

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
	<u>PART (C) NON-SCHEDULE ITEM.</u>					
01	Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
	(a) 4- gang	08	Nos	700/00	Each	5,600
	(b) 10 gang	04	Nos	1050/00	Each	4,200
	(c) Bell Push	02	Nos	425/00	Each	850
	(d) Telephone socket	04	Nos	550/00	Each	2,200
	(e) Net Jack	04	Nos	550/00	Each	2,200
02	Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
		10	Sft	600/00	P.Sft	6,000
03	Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
		02	Nos	15000/00	Each	30,000
04	Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
		05	Nos	7000/00	Each	35,000
05	Providing and fixing in position name Plate form, made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
		01	Job	7000/00	P-Job	7,000
06	Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
		18	Meters	1111/00	P-Meters	19,998
06	P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
		500	ft	60/00	P.Rft	30,000
07	P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
		18	Nos	1250/00	Each	22,500

Sl No	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
09	P/F wall breaket fan 121 to 18" etc complete in all respect Nos 4300/00 Each 8,600				
10	Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01 No	35000/00	Each	35,000
11	Accessories Power supply and BNC connector Both side etc complete in all respect.	04 Nos	1500/00	Each	6,000
12	Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01 No	16250/00	Each	16,250
13	2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01 No	14300/00	Each	14,300
14	Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04 Nos	7500/00	Each	30,000
15	Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01 No	9000/00	Each	9,000
16	Supplying and fixing fency type fibre glass wall paneling of approved design & shape.	643 Sft	150/00	P.Sft	96,450
17	Providing and fixing split type air condition 1.5 Ton capacity Mitsubishi Or and other equivalent quality as approved by Engineer incharge.	02 Nos	94000/00	Each	188,000
18	P/F Stabilizer 7000-10000 watts as required approved by Engineer incharge.	02 Nos	22500/00	Each	45,000
Total					614,148

  
**Superintendent Of Police**  
**Kashmore @ Kandhkot**


ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 503,739
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 410,198

Total Rs:1,001,121


Say Rs.1,000,000

  
Superintendent Of Police  
Kashmore @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF LT SECTION S.S.P OFFICE KASHIMORE @ KASHIMORE  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
<u>PART (A)</u>						
01	Removing door with chowkats (SINO:33(a)P-12).	01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).	03	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	310
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	36	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	54,277
04	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe modle (Bornze)(SINO:84(a)P-108).	380	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	34,770
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	361	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	33,032
06	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	80	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	8,338

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	84	Sft 2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	198,620
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	70	Sft 443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	31,060
Total				503,730

  
 Superintendent Of Police  
 Kashmore @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORE @ KANJIKHUR  
Module "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
01	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single) 16,950
02	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single) 4,925
03	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single) 3,528
04	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single) 11,100
05	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single) 18,414
06	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single) 1,620
07	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single) 301

NO	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
08	Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
09	P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,037
10	Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
11	Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
12	Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
13	P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12"deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire ruynb in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
14	Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
15.	P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
16.	Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
17.	Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999

Total 37,164

  
 Superintendent Of Police  
 Kashmir @ Kandhkot




ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANJHUC  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>						
91	Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
	(a) 4- gang	08	Nos	700/00	Each	5,600
	(b) 10 gang	04	Nos	1050/00	Each	4,200
	(c) Bell Push	02	Nos	425/00	Each	850
	(d) Telephone socket	04	Nos	550/00	Each	2,200
	(e) Net Jack	04	Nos	550/00	Each	2,200
92	Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
		10	Sft	600/00	P.Sft	6,000
93	Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
		02	Nos	15000/00	Each	30,000
94	Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
		07	Nos	7000/00	Each	49,000
95	Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
		01	Job	7000/00	P-Job	7,000
96	Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
		18	Meters	1111/00	P-Meters	19,998
96	P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
		500	ft	60/00	P.Rft	30,000
97	P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
		16	Nos	1250/00	Each	20,000

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
01	P/F wall breaket fan 121 to 18" etc complete in all respect.	02	Nos	4300/00	Each	8,600
02	Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
03	Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
04	Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01	No	16250/00	Each	16,250
05	2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
06	Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
07	Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01	No	9000/00	Each	9,000
08	Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	760	Sft	150/00	P.Sft	114,000

Total 410,198

  
 Superintendent Of Police  
 Kashmir @ Kandhkot


ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 503,739
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 410,198

Total Rs:1,001,121


Say Rs.1,000,000

  
Superintendent Of Police  
Kashmore @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRE @ KASHMIRE  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (A)</u>					
01	Removing door with chowkats (SINO:33(a)P-12).	01	No 142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).	03	Nos 102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	310
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	36	Sft 1507/66 Rs: One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	54,277
04	Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and locking arrangement etc complete (Deluxe model (Bronze))(SINO:84(a)P-108).	380	Sft 1647/69 Rs: One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	34,770
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	361	Sft 91/50 Rs: Ninety one & Ps Fifty only.	P.Sft (single)	33,032
06	Providing and fixing plaster of Paris ceiling border of 8" - 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	80	Rft 104/22 Rs: One hundred Four & Ps Twenty two only.	P.Rft (single)	8,338

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<p>07 Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).</p>	84 Sft	2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	198,620
<p>08 Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).</p>	70 Sft	443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	31,060
Total				503,739

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANJHRI  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
<u>PART (B) ELECTRIC WORK.</u>						
01	Wiring for light or fan point with 1/1.13(3/.029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
02	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
03	Wiring for Call Bell point with (3/.029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
04	Providing and laying (main or Sub-Main)PVC insulated with size 7/.029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
05	Providing and laying (main or sub-main )PVC insulated wire size 2-7/.044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
06	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
07	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
08	Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
09	P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
10	Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
11	Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
1	Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
1	P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12"deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire ruynb in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
11	Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
15	P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,388
16	Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
17	Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999

Total 37,164

  
 Superintendent Of Police  
 Kashmore @ Kandhkot




ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDHKO  
Schedule "B"

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>						
01	Providing and fixing A:C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
	(a) 4- gang	08	Nos	700/00	Each	5,600
	(b) 10 gang	04	Nos	1050/00	Each	4,200
	(c) Bell Push	02	Nos	425/00	Each	850
	(d) Telephone socket	04	Nos	550/00	Each	2,200
	(e) Net Jack	04	Nos	550/00	Each	2,200
02	Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
		10	Sft	600/00	P.Sft	6,000
03	Providing and fixing shish am wood Almira 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
		02	Nos	15000/00	Each	30,000
04	Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
		07	Nos	7000/00	Each	49,000
05	Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
		01	Job	7000/00	P-Job	7,000
06	Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
		18	Meters	1111/00	P-Meters	19,998
07	P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
		500	ft	60/00	P.Rft	30,000
08	P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
		16	Nos	1250/00	Each	20,000

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
06	P/F wall breaket fan 121 to 18" etc complete in all respect.	02	Nos	4300/00	Each	8,600
07	Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
08	Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
09	Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01	No	16250/00	Each	16,250
10	2 TB 3.5 sea gate surveillane (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
11	Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
12	Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01	No	9000/00	Each	9,000
13	Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	760	Sft	150/00	P.Sft	114,000

Total 410,198

  
 Superintendent Of Police  
 Kashmir @ Kandhkot


ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 503,739
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 410,198

Total Rs:1,001,121


Say Rs.1,000,000

  
Superintendent Of Police  
Kashmore @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANUNJ  
 Schedule "B"

#	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (A)</u>					
01	Removing door with chowkats (SINO:33(a)P-12).				
		01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single) 142
02	Removing window and sky light with chowkats (SINO:33(b)P-12).				
		03	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single) 310
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).				
		36	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single) 54,277
04	Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe modle (Bornze)(SINO:84(a)P-108).				
		380	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single) 34,770
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).				
		361	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single) 33,032
06	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).				
		80	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single) 8,338

NO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
07	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	84	2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	198,620
08	Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	70	443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	31,060
Total					503,730

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORE @ KAFI JEL  
Module "B"

NO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
<u>PART (B) ELECTRIC WORK.</u>						
01	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
02	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
03	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
04	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
05	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
06	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
07	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	301

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
08 Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
09 P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO.6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
10 Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
11 Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
12 Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
13 P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12"deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire ruynb in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
14 Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144

Sl. No.	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
15	P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
16	Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
17	Providing and fixing voltmeter size 96/96mm 500volt as required & as per Instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999

Total 37,184

  
 Superintendent Of Police  
 Kashmir @ Kandhkot




ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDHIK  
 Schedule "B"

Sl. No.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>						
01	Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
	(a) 4- gang	08	Nos	700/00	Each	5,600
	(b) 10 gang	04	Nos	1050/00	Each	4,200
	(c) Bell Push	02	Nos	425/00	Each	850
	(d) Telephone socket	04	Nos	550/00	Each	2,200
	(e) Net Jack	04	Nos	550/00	Each	2,200
02	Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
		10	Sft	600/00	P.Sft	6,000
03	Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
		02	Nos	15000/00	Each	30,000
04	Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
		07	Nos	7000/00	Each	49,000
05	Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
		01	Job	7000/00	P-Job	7,000
06	Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
		18	Meters	1111/00	P-Meters	19,998
07	P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
		500	ft	60/00	P.Rft	30,000
08	P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
		16	Nos	1250/00	Each	20,000

Sl No	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
06	P/F wall breaket fan 121 to 18" etc complete in all respect.	02	Nos	4300/00	Each	8,600
09	Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01	No	35000/00	Each	35,000
10	Accessories Power supply and BNC connector Both side etc complete in all respect.	04	Nos	1500/00	Each	6,000
11	Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01	No	16250/00	Each	16,250
12	2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01	No	14300/00	Each	14,300
13	Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04	Nos	7500/00	Each	30,000
14	Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01	No	9000/00	Each	9,000
15	Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	760	Sft	150/00	P.Sft	114,000

Total 410,198

  
 Superintendent Of Police  
 Kashmir @ Kandhkot

FACE SHEET

1. FUND HEAD :- PROVINCIAL GOVERNMENT.

2. WORK HEAD :-

3. PART HEAD :-

4. PROJECT HEAD :- ESTIMATE FOR REPAIR /RENOVATION OF LT SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

5. AMOUNT :- Rs:1000,000

This estimate has been framed in the office of Superintending Engineer,  
Works Department for the probable expenditure that will be incurred the above  
work.

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

GENERAL ABSTRACT

01.	PART (A)	Rs: 503,739
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 410,198

Total Rs:1,001,121

Say Rs.1,000,000

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDHAR  
Module "B"

NO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
<u>PART (A)</u>						
1	Removing door with chowkats (SINO:33(a)P-12).	01	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
2	Removing window and sky light with chowkats (SINO:33(b)P-12).	03	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	310
3	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	36	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	54,277
4	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe modle (Bornze)(SINO:84(a)P-108).	380	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	34,770
5	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	361	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	33,032
6	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	80	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	8,338

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
---------------	-----	------	------	--------


Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).

84	Sft	2364/63 Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	P.Sft (single)	198,629
----	-----	---	-------------------	---------

Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).

70	Sft	443/71 Rs: Four hundred Forty three & Ps Seventy one Only.	P.Sft (single)	31,060
----	-----	---	-------------------	--------

Total 503,739

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANPUR

Sl. No.	ITEM OF WORK NO: L.B.D	QUANTITY
<u>PART (A)</u>		
01	Removing door with chowkats (SINO:33(a)P-12). 1x1.0 =	01 No
02	Removing window and sky light with chowkats (SINO:33(b)P-12). 1x3.0 =	03 Nos
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha 1x4.0x9.0 =	36 Sft
04	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass 3x6.0x6.0 =	108 Sft
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire 1x19.0x19.0 =	361 Sft
06	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties 1x2(19.0+19.0) =	76 Rft
07	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking 7x4.0x3.0 =	84 Sft
08	Making and fixing deodar wood shelves including brackets 1"thick 7x4.0x2.50 =	70 Sft

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORE. @ KASHIMORE  
Module "B"

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>				
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos 1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos 985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos 1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr 222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr 341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos 162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos 150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	300



ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred Fifty four & Ps Eighty three only	P.Sft	2,032
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
P/F earthling Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or Less if water comes out from the ground level with salt and charcoal etc i/c making The pit 12"deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire ruynb in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
177 Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1 988
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs: One thousand Fifty four only.	Each (single)	1,054
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total				87,184

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF IT SECTION S.S.P OFFICE KASHMORI @ KANL  
Module "B"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (B) ELECTRIC WORIK.</u>	
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	1x15.0 = 15 Nos
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	1x5.0 = 05 Nos
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	1x2.0 = 02 Nos
Providing and laying (main or Sub-Main)PVC insulated with size 7/.029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	1x50.0 = 50 Mtr
Providing and laying (main or sub-main )PVC insulated wire size 2-7/.044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	1x54.0 = 54 Mtr
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-35).	1x10.0 = 10 Nos
Providing and fixing A.C or D.C Electric bell 200/250 volts 75 MM (SINO:21-P-11).	1x2.0 = 02 Nos
Providing and fixing flush type electric bell push button (SINO:23-P-12).	1x2.0 = 02 Nos
P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1x1.50 = 1.50 Sft
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	1x4.0 = 4 Nos
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	1x12.0 = 12 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (7S-100NS) on prepared board as required (SINO:207-P-31).	1x1.0 = 01 No
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making	1x1.0 = 01 No
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	1x2.0 = 02 Nos
P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	1x4.0 = 04 Nos
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	1x1.0 = 01 No
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	1x1.0 = 01 No

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORI  
Job "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>					
Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
(a) 4- gang	08	Nos	700/00	Each	5,600
(b) 10 gang	04	Nos	1050/00	Each	4,200
(c) Bell Push	02	Nos	425/00	Each	850
(d) Telephone socket	04	Nos	550/00	Each	2,200
(e) Net Jack	04	Nos	550/00	Each	2,200
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
	10	Sft	600/00	P.Sft	6,000
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
	02	Nos	15000/00	Each	30,000
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
	07	Nos	7000/00	Each	49,000
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
	01	Job	7000/00	P-Job	7,000
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
	18	Meters	1111/00	P-Meters	19,998
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
	500	ft	60/00	P.Rft	30,000
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
	16	Nos	1250/00	Each	20,000

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
177	P/F wall breaket fan 121 to 18" etc complete in all respect.				
	02	Nos	4300/00	Each	8,600
178	Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.				
	01	No	35000/00	Each	35,000
179	Accessories Power supply and BNC connector Both side etc complete in all respect.				
	04	Nos	1500/00	Each	6,000
180	Commutation Rack 124 for DVR and other system with calling fan etc complete in all respect,				
	01	No	16250/00	Each	16,250
181	2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect				
	01	No	14300/00	Each	14,300
182	Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.				
	04	Nos	7500/00	Each	30,000
183	Supplying and fixing 12 LED superior quality approved by Engineer incharge.				
	01	No	9000/00	Each	9,000
184	Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.				
	760	Sft	150/00	P.Sft	114,000
				Total	410,198

	ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (C) NON-SCHEDULE ITEM.</u>		
Providing and fixing A,C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.		
(a)	4-gang 1x8.0 =	08 Nos
(b)	10 gang 1x4.0 =	04 Nos
(c)	Bell Push 1x2.0 =	02 Nos
(d)	Telephone socket 1x4.0 =	04 Nos
(e)	Net Jack 1x4.0 =	04 Nos
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving		
	1x10.0 =	10 Sft
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking		
	1x2.0 =	02 Nos
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.		
	1x7.0 =	07 Nos
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing		
	1x1.0 =	01 Job
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all		
	1x18.0 =	18 Meters
P/W Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.		
	1x500.0 =	500 ft
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.		
	1x16.0 =	16 Nos
P/W wall breaket fan 12 to 18" etc complete in all respect.		
	1x2.0 =	02 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01 No
1x1.0 =	01 No
Accessories Power supply and BNC connector Both side etc complete in all respect.	04 Nos
1x4.0 =	04 Nos
Comrnutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01 No
1x1.0 =	01 No
2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01 No
1x1.0 =	01 No
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04 Nos
1x4.0 =	04 Nos
Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01 No
1x1.0 =	01 No
Supplying and fixing fency type fibre glass wall paneling of approved design & shape.	760 Sft
1x2(19.0+19.0)x10.0 =	760 Sft

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO



FACE SHEET

FOUNDER HEAD :- PROVINCIAL GOVERNMENT.

WORKS HEAD :-

ARTICLE HEAD :-

DESCRIPTION HEAD :- ESTIMATE FOR REPAIR /RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

AMOUNT :- Rs:1000,000

This estimate has been framed in the office of Superintending Engineer,  
Works Department for the probable expenditure that will be incurred the above  
year.

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

---

GENERAL ABSTRACT

01.	PART (A)	Rs: 503,739
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 410,198

Total Rs:1,001,121

Say **Rs.1,000,000**

  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDHAR  
Module "B"

NO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (A)</u>					
01	Removing door with chowkats (SINO:33(a)P-12).	01 No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
03	Removing window and sky light with chowkats (SINO:33(b)P-12).	03 Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	310
04	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	36 Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	54,277
05	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe modle (Bornze)(SINO:84(a)P-108).	380 Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	34,770
06	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	361 Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	33,032
07	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	80 Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	8,338

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	84	Sft	2364/63	P.Sft	198,629
			Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	(single)	
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	70	Sft	443/71	P.Sft	31,060
			Rs: Four hundred Forty three & Ps Seventy one Only.	(single)	
					Total 503,739

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDI  
Module "B"

NO	ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (A)</u>		
	Removing door with chowkats (SINO:33(a)P-12).	
	1x1.0 =	01 No
	Removing window and sky light with chowkats (SINO:33(b)P-12).	
	1x3.0 =	03 Nos
	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha	
	1x4.0x9.0 =	36 Sft
	Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass	
	3x6.0x6.0 =	108 Sft
	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire	
	1x19.0x19.0 =	361 Sft
	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties	
	1x2(19.0+19.0) =	76 Rft
	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking	
	7x4.0x3.0 =	84 Sft
	Making and fixing deodar wood shelves including brackets 1"thick	
	7x4.0x2.50 =	70 Sft

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRE @ SATHI  
Module "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
Providing and fixing A.C or D.C Electric bell 200/250 volts 75 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	300

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred (single) Fifty four & Ps Eighty three only	P.Sft	2,032
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	53/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (XS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
P/F earthling Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making the pit 12" deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire run in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
M/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,968
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs:One thousand Fifty four only.	Each (single)	1,054
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total				87,184


  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO



ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORE @ KAPU 19  
Module "B"

ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (B) ELECTRIC WORIK.</u>	
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 25 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	1x15.0 = 15 Nos
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	1x5.0 = 05 Nos
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	1x2.0 = 02 Nos
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	1x50.0 = 50 Mtr
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	1x54.0 = 54 Mtr
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-35).	1x10.0 = 10 Nos
Providing and fixing A.C or D.C Electric bell 200/250 volts 75 MM (SINO:21-P-11).	1x2.0 = 02 Nos
Providing and fixing flush type electric bell push button (SINO:23-P-12).	1x2.0 = 02 Nos
P/fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1x1.50 = 1.50 Sft
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	1x4.0 = 4 Nos
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	1x12.0 = 12 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (ZS-100NS) on prepared board as required (SINO:207-P-31).	1x1.0 = 01 No
P/W earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making	1x1.0 = 01 No
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	1x2.0 = 02 Nos
P/W Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	1x4.0 = 04 Nos
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	1x1.0 = 01 No
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	1x1.0 = 01 No

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRI  
 Part "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>					
Providing and fixing A.C 6-10 Amp china type switch & socket of superior quality as approved by Engineer incharge.					
(a) 4- gang	08	Nos	700/00	Each	5,600
(b) 10 gang	04	Nos	1050/00	Each	4,200
(c) Bell Push	02	Nos	425/00	Each	850
(d) Telephone socket	04	Nos	550/00	Each	2,200
(e) Net Jack	04	Nos	550/00	Each	2,200
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
	10	Sft	600/00	P.Sft	6,000
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
	02	Nos	15000/00	Each	30,000
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
	07	Nos	7000/00	Each	49,000
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
	01	Job	7000/00	P-Job	7,000
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
	18	Meters	1111/00	P-Meters	19,998
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
	500	ft	60/00	P.Rft	30,000
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
	16	Nos	1250/00	Each	20,000

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
177	177" wall breaket fan 121 to 18" etc complete in all respect.				
	02	Nos	4300/00	Each	8,600
178	Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.				
	01	No	35000/00	Each	35,000
179	Accessories Power supply and BNC connector Both side etc complete in all respect.				
	04	Nos	1500/00	Each	6,000
180	Commutation Rack 124 for DVR and other system with calling fan etc complete in all respect,				
	01	No	16250/00	Each	16,250
181	2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect				
	01	No	14300/00	Each	14,300
182	Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.				
	04	Nos	7500/00	Each	30,000
183	Supplying and fixing 12 LED superior quality approved by Engineer incharge.				
	01	No	9000/00	Each	9,000
184	Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.				
	760	Sft	150/00	P.Sft	114,000
				Total	410,198

FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDHAR  
 Module "B"

ITEM OF WORK	NO:L.B.D		QUANTITY	
<u>PART (C) NON-SCHEDULE ITEM.</u>				
Providing and fixing A,C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.				
(a) 4-gang	1x8.0	=	08	Nos
(b) 10 gang	1x4.0	=	04	Nos
(c) Bell Push	1x2.0	=	02	Nos
(d) Telephone socket	1x4.0	=	04	Nos
(e) Net Jack	1x4.0	=	04	Nos
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving				
	1x10.0	=	10	Sft
Providing and fixing shish am wood Almiraah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking				
	1x2.0	=	02	Nos
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.				
	1x7.0	=	07	Nos
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing				
	1x1.0	=	01	Job
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all				
	1x18.0	=	18	Meters
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.				
	1x500.0	=	500	ft
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.				
	1x16.0	=	16	Nos
P/F wall breaket fan 121 to 18" etc complete in all respect.				
	1x2.0	=	02	Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	01 No
1x1.0 =	01 No
Accessories Power supply and BNC connector Both side etc complete in all respect.	04 Nos
1x4.0 =	04 Nos
Comrnutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	01 No
1x1.0 =	01 No
2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect	01 No
1x1.0 =	01 No
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	04 Nos
1x4.0 =	04 Nos
Supplying and fixing 12 LED superior quality approved by Engineer Incharge.	01 No
1x1.0 =	01 No
Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	760 Sft
1x2(19.0+19.0)x10.0 =	760 Sft

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

FACE SHEET

OWNER HEAD :- PROVINCIAL GOVERNMENT.

WORK HEAD :-

ITEM HEAD :-

WORK HEAD :- ESTIMATE FOR REPAIR /RENOVATION OF LT SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

AMOUNT :- Rs:1000,000

This estimate has been framed in the office of Superintending Engineer,  
Works Department for the probable expenditure that will be incurred the above  
estimate.

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION  
S.S.P OFFICE KASHMORE @ KANDHKOT

---

GENERAL ABSTRACT

01.	PART (A)	Rs: 503,739
02.	PART (B)	Rs: 87,184
03.	PART (C)	Rs: 410,198

---

Total Rs:1,001,121

Say **Rs.1,000,000**


  
ASSISTANT ENGINEER  
POLICE WORKS  
LARKANO



ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMIRE @ KANDHAR  
Module "B"

NO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
<u>PART (A)</u>					
01	Removing door with chowkats (SINO:33(a)P-12).	No	142/18 Rs: One hundred Forty two & Ps Eighteen only.	Each (single)	142
03	Removing window and sky light with chowkats (SINO:33(b)P-12).	Nos	102/85 Rs: One hundred Two & Ps Eight five only.	Each (single)	310
36	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan ) locks i/c handles stoppers etc (b) Deluxe model (Bronze) (SINO:83(b)P-108).	Sft	1507/66 Rs:One thousand Five hundred seven & Ps Sixty six only.	P.Sft (single)	54,277
380	Supplying and fixing in position Aluminum channels framing for slidding Windows & ventilators of Alcops made with 5 mm thick tinted glass Glazing (Belgium) & Aluminum fly screen i/c handles stoppers and Locking arrangement etc complete (Deluxe modle (Bornze)(SINO:84(a)P-108).	Sft	1647/69 Rs:One thousand Six hundred forty seven & Ps Sixty nine only.	P.Sft (single)	34,770
361	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	Sft	91/50 Rs:Ninety one & Ps Fifty only.	P.Sft (single)	33,032
80	Providing and fixing plaster of Paris ceiling border of 8" – 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	8,338

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design(SINO: 24-P-61).	84	Sft	2364/63	P.Sft	198,629
			Rs: Two thousand Three hundred sixty four & Ps Sixty three only.	(single)	
Making and fixing deodar wood shelves including brackets 1"thick (SINO:27(a)P-61).	70	Sft	443/71	P.Sft	31,060
			Rs: Four hundred Forty three & Ps Seventy one Only.	(single)	
					Total 503,739

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF T SECTION S.S.P OFFICE KASHMIRE @ KANDI  
 Module "B"

	ITEM OF WORK NO: L.B.D	QUANTITY
<u>PART (A)</u>		
01	Removing door with chowkats (SINO:33(a)P-12).	
	1x1.0 =	01 No
02	Removing window and sky light with chowkats (SINO:33(b)P-12).	
	1x3.0 =	03 Nos
03	Supplying & fixing in position Aluminum channels framing for hinged doors Or alcops made with 5 mm thick tinted glass glazing (Belgium) and Alpha	
	1x4.0x9.0 =	36 Sft
04	Supplying and fixing in position Aluminum channels framing for sliding Windows & ventilators of Alcops made with 5 mm thick tinted glass	
	3x6.0x6.0 =	108 Sft
05	Providing and fixing false of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire	
	1x19.0x19.0 =	361 Sft
06	Providing and fixing plaster of Paris ceiling border of 8" - 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties	
	1x2(19.0+19.0) =	76 Rft
07	Providing and fixing deodar wooden wardrobe including boxing with back shelves, shutters drawers and brass fittings such as handles locking	
	7x4.0x3.0 =	84 Sft
08	Making and fixing deodar wood shelves including brackets 1" thick	
	7x4.0x2.50 =	70 Sft


  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORE (U.S.A.)  
Module "B"

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (B) ELECTRIC WORK.</u>					
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	15	Nos	1130/00 Rs:One thousand One hundred thirty only.	P.Point (single)	16,950
Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	05	Nos	985/00 Rs:Nine hundred Eighty five only.	P.Point (single)	4,925
Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	02	Nos	1764/00 Rs:One thousand Sevev hundred Sixty four Only.	Each (single)	3,528
Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recerred in the wall or columns as required (SINO:10-P-2).	50	Mtr	222/00 Rs:Two hundred Twenty two only.	P.Mtr (single)	11,100
Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	54	Mtr	341/00 Rs:Three hundred Forty one only.	P.Mtr (single)	18,414
Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33).	10	Nos	162/00 Rs:One hundred Sixty two only.	Each (single)	1,620
Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	02	Nos	150/70 Rs: One hundred Fifty & Ps Seventy only.	Each (single)	300

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
Providing and fixing flush type electric bell push button (SINO:23-P-12).	02	Nos	25/19 Rs: Twenty five & Ps Nineteen only.	Each (single)	51
P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1.50	Sft	1354/83 Rs:One thousand three hundred Fifty four & Ps Eighty three only	P.Sft	2,032
Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	4	Nos	58/69 Rs:Fifty three & Ps Sixty nine only.	Each (single)	215
Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	12	Nos	916/00 Rs:Nine hundred Sixteen only.	Each (single)	10,992
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (TS-100NS) on prepared board as required (SINO:207-P-31).	01	No	9261/00 Rs:Nine thousand Two hundred sixty one only.	Per Nos (single)	9,261
P/F earthling Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making the pit 12"deep by excavation of all type of soil. Earth plate to be connected with No:8 SWG bare copper wire run in 1/2" G.L pipe straight from the earth plate upto the metallic Electrical accessory i-e providing necessary Tee(SINO:1(A)P-26).	01	No	3610/04 Rs:Three thousand Six hundred Ten & Ps Four only.	Each (single)	3,610
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	02	Nos	72/00 Rs:Seventy two only	Each (single)	144

ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
1/11 Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	04	Nos 497/00 Rs: Four hundred Ninety seven hundred Only.	Each (single)	1,988
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	01	No 1054/00 Rs: One thousand Fifty four only.	Each (single)	1,054
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	01	No 999/00 Rs: Nine hundred Ninety nine only.	Each (single)	999
Total				37,184

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO

ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORE (S. KANTH 14)

Module "B"

	ITEM OF WORK NO:L.B.D	QUANTITY
<u>PART (B) ELECTRIC WORK.</u>		
	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20 mm (3/4")PVC conduit recessed required in the wall or columns as (SINO:124-P-15).	1x15.0 = 15 Nos
	Wiring for plug point with 1/1.13 (3/039)PVC insulated wire in 20 mm (3/4")PVC Conduit recessed in the wall or columns as required (SINO:126-P-15).	1x5.0 = 05 Nos
	Wiring for Call Bell point with (3/029)PVC insulated wire in 25 mm (1")PVC conduit recessed required in the wall or columns as (SINO:128-P-15).	1x2.0 = 02 Nos
	Providing and laying (main or Sub-Main)PVC insulated with size 7/029 copper Conductor in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:10-P-2).	1x50.0 = 50 Mtr
	Providing and laying (main or sub-main )PVC insulated wire size 2-7/044 (6mm2) Copper conductor or in 3/4"dia PVC conduit recessed in the wall or columns as required (SINO:12-P-2).	1x54.0 = 54 Mtr
	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-35).	1x10.0 = 10 Nos
	Providing and fixing A.C or D.C Electric bell 200/250 volts 70 MM (SINO:21-P-11).	1x2.0 = 02 Nos
	Providing and fixing flush type electric bell push button (SINO:23-P-12).	1x2.0 = 02 Nos
	P/Fixing panel board double shutter to accommodate heavy duty circuit breaker Bus bars i/c painting with enameled paint and for other similar jobs on surface (SINO:6-P-13).	1x1.50 = 1.50 Sft
	Providing and fixing B.C. Bakelite angular type batten holder (SNo. 1P-14)	1x4.0 = 4 Nos
	Providing & fixing circuit breaker 6,10,15,20,30,40,50 & 63 amp SP (TB-5S) on prepared Board as required ( SINO:203-P-31).	1x12.0 = 12 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Providing and fixing circuit breaker 15,20,30,40,50,60,75 & 100 Amp TP (7S-100NS) on prepared board as required (SINO:207-P-31).	1x1.0 = 01 No
P/F earthing Set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc i/c making	1x1.0 = 01 No
Providing and fixing Backlite ceiling Rose with two terminals (SINO:228-P-33)	1x2.0 = 02 Nos
P/F Energy sever superior quality including fixing on existing holder etc complete (SINO:6-P-33).	1x4.0 = 04 Nos
Providing and fixing ammeters size 96/96 mm Direct 15A, 30A,50A,60A & 100A as required & as per instruction of E.I (SINO:284-P-41).	1x1.0 = 01 No
Providing and fixing voltmeter size 96/96mm 500volt as required & as per instruction of E.I (SINO:285-P-41).	1x1.0 = 01 No

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
LARKANO



ESTIMATE FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHIMORE

Jul '13

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
<u>PART (C) NON-SCHEDULE ITEM.</u>					
Providing and fixing A.C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.					
(a) 4- gang	08	Nos	700/00	Each	5,600
(b) 10 gang	04	Nos	1050/00	Each	4,200
(c) Bell Push	02	Nos	425/00	Each	850
(d) Telephone socket	04	Nos	550/00	Each	2,200
(e) Net Jack	04	Nos	550/00	Each	2,200
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving mechanism i/c locking arrangement and necessary fitting complete in all respect.					
	10	Sft	600/00	P.Sft	6,000
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking arrangement complete					
	02	Nos	15000/00	Each	30,000
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.					
	07	Nos	7000/00	Each	49,000
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing monogram of Affidavit branch on Glass door etc complete.					
	01	Job	7000/00	P-Job	7,000
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all respect.					
	18	Meters	1111/00	P-Meters	19,998
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.					
	500	ft	60/00	P.Rft	30,000
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.					
	16	Nos	1250/00	Each	20,000

ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
177	177" wall breaket fan 121 to 18" etc complete in all respect.				
	02	Nos	4300/00	Each	8,600
178	178 Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.				
	01	No	35000/00	Each	35,000
179	179 Accessories Power supply and BNC connector Both side etc complete in all respect.				
	04	Nos	1500/00	Each	6,000
180	180 Commutation Rack 124 for DVR and other system with calling fan etc complete in all respect,				
	01	No	16250/00	Each	16,250
181	181 2 TB 3.5 sea gate surveillance (Design for vide recording) etc complete in all respect				
	01	No	14300/00	Each	14,300
182	182 Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.				
	04	Nos	7500/00	Each	30,000
183	183 Supplying and fixing 12 LED superior quality approved by Engineer Incharge.				
	01	No	9000/00	Each	9,000
184	184 Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.				
	760	Sft	150/00	P.Sft	114,000
				Total	410,198

PLAN FOR REPAIR / RENOVATION OF I.T SECTION S.S.P OFFICE KASHMORE @ KANDHAR  
Module "B"

ITEM OF WORK NO:L.B.D		QUANTITY
<u>PART (C) NON-SCHEDULE ITEM.</u>		
Providing and fixing A,C 6-10 Amp china type switch & socket of Superior quality as approved by Engineer incharge.		
(a) 4- gang	1x8.0	= 08 Nos
(b) 10 gang	1x4.0	= 04 Nos
(c) Bell Push	1x2.0	= 02 Nos
(d) Telephone socket	1x4.0	= 04 Nos
(e) Net Jack	1x4.0	= 04 Nos
Providing ( 12mm thick ) glass including cutting, making and fixing glass doors, counter partitions etc with door stopper and moving		
	1x10.0	= 10 Sft
Providing and fixing shish am wood Almirah 12" to 18" depth including shutters drawers, boxing with back shelves with brass fittings together with locking		
	1x2.0	= 02 Nos
Supplying wooden office chairs made of First class shisham wood including polishing etc complete.		
	1x7.0	= 07 Nos
Providing and fixing in position name Plate form , made of fibre glass sheet including necessary fittings etc complete along with in scribing		
	1x1.0	= 01 Job
Supplying and erecting curtains of approved colour and design including railing, and other necessary fitting complete in all		
	1x18.0	= 18 Meters
P/F Internet wire cat-6 i/c fixing on 3/4" channel putty etc complete in All respect.		
	1x500.0	= 500 ft
P/F LED 6"x8" for ceiling type 12 to 16 watts etc complete in all respect.		
	1x16.0	= 16 Nos
P/F wall breaket fan 121 to 18" etc complete in all respect.		
	1x2.0	= 02 Nos

ITEM OF WORK NO:L.B.D	QUANTITY
Supplying and fixing DVR 04 channels H 264 or as required High destination HD Auto on line version with fixing etc complete in all respect.	1x1.0 = 01 No
Accessories Power supply and BNC connector Both side etc complete in all respect.	1x4.0 = 04 Nos
Commutation Rack 124 for DVR and other system with calling Fan etc complete in all respect,	1x1.0 = 01 No
2 TB 3.5 sea gate surveillance (Design for wide recording) etc complete in all respect	1x1.0 = 01 No
Supplying and fixing (High definition) Sony 2.0 MP High Resolution Day / Night vision Camera with Housing water proof coverage area upto 40 yards recommended for main Gate, main entrance gate corridor court Room and other office Section with one year warranty.	1x4.0 = 04 Nos
Supplying and fixing 12 LED superior quality approved by Engineer In-charge.	1x1.0 = 01 No
Supplying and fixing fancy type fibre glass wall paneling of approved design & shape.	1x2(19.0+19.0)x10.0 = 760 Sft

  
 ASSISTANT ENGINEER  
 POLICE WORKS  
 LARKANO