

# OFFICE OF THE RESIDENT ENGINEER, SPECIAL PROJECT, SINDH HOUSE ISLAMABAD SECTOR, F-5/2, ISLAMABAD,

Tele-051-9211411 (PABX), Fax: 051-9203407, E-Mail:- reshibd@yahoo.com

NO.RE/SHI/P-13/\_446\_/2018

DATED: \_15\_/ 5 /2018

# **NOTICE INVITING TENDERS**

Procuring Agency invites sealed bids in "single stage – one envelope procedure" from all the interested bidders fulfilling terms & conditions under SPPRA rules 2010 (Amended 2013) for the following work.

Sr.	Name of work	Estimated cost	Earnest Money (2%)	Cost of bidding documents	Time allowed for completion
١.	M/R to double room flat / lounge of Staff Colony at Sindh House Islamabad. (Block A-1,2,3,4,5 & 6).	1,000,000/-	20,000/-	1,000/-	2 Months.
2.	M/R to double room flat / lounge of Staff Colony at Sindh House Islamabad. (Block B-1,2,3,4,5 & 6).	1,000,000/-	20,000/-	1,000/-	2 Months.
3.	M/R to double room flat / lounge of Staff Colony at Sindh House Islamabad. (Block C-1,2,3,4,5 & 6).	1,000,000/-	20,000/-	1,000/-	2 Months.
4.	M/R to double room flat / lounge of Staff Colony at Sindh House Islamabad. (Block D-1,2,3,4,5 & 6).	1,000,000/-	20,000/-	1,000/-	2 Months.
5.	M/R to Sindh House Islamabad (Block A,B,C & D (Electrical Works).	1,000,000/-	20,000/-	1,000/-	2 Months.
ó.	M/R to Old Colony / lounge of Staff Colony at Sindh House Islamabad. (Single Room Qtrs 1,2,3,4,5,6,7,8 & 9).	900,000/-	18,000/-	500/-	2 Months.
7	M/R to Old Colony / lounge of Staff Colony at Sindh House Islamabad. (Single Room Qtrs 10,11,12,13,14,15,16,17 & 18).	900,000/-	18,000/-	500/-	2 Months.
8.	M/R to Old Colony / lounge of Staff Colony at Sindh House Islamabad. (Single Room Qtrs 19,20,21,22,23,24,25 & 26).	800,000/-	16,000/-	500/-	2 Months.
9.	M/R to Old Colony / lounge of Staff Colony at Sindh House Islamabad. (Single Room Qtrs 27,28,29,30,31,32,33 & 34).	800,000/-	16,000/-	500/-	2 Months.
10.	M/R to Sindh House Islamabad (Old Colony (Electrical Works).)	1,000,000/-	20,000/-	1,000/-	2 Months.
11.	M/R to Sindh House Islamabad (Single Room Qtrs. 1.2,3,4,5,6 at staff Colony under Police Barrack Sindh House Islamabad).	1,000,000/-	20,000/-	1,000/-	2 Months.
12.	M/R to Sindh House Islamabad (Masjid Bab ul Islam).	500,000/-	10,000/-	500/-	2 Months.
13.	M/R to Sindh House Islamabad (Old Police Barrack Rooms 1.2,3,4,5,6).	500,000/-	10,000/-	500/-	2 Months.
14.	M/R to Sindh House Islamabad (Colony stair case).	700,000/-	14,000/-	500/-	2 Months.
15.	M/R to Sindh House Islamabad (M/R dhobi ghatt).	500,000/-	10,000/-	500/-	2 Months.
16.	M/R to Sindh House Islamabad (M/R to R.E. House)	1,000,000/-	20,000/-	1,000/-	2 Months.
17.	M/R to Sindh House Islamabad (M/R to C-1. C-2).	1,000,000/-	20,000/-	1,000/-	2 Months.
18.	M/R to Sindh House Islamabad (Colony Street Lights (Category VI Flats).	900,000/-	18,000/-	500/-	2 Months.
19.	M/R to Sindh House Islamabad (Colony drainage system (Category VI Flats).	1,000,000/-	20,000/-	1,000/-	2 Months.
20.	M/R to Sindh House Murree (Lawn light).	1,000,000/-	20,000/-	1,000/-	2 Months.
21.	M/R to Sindh House Islamabad (Colony Street Lights (Single room quarter side).	900,000/-	18,000/-	500/-	2 Months.
22.	M/R to Sindh House Islamabad (Colony drainage system (Single room quarter side).	1,000,000/-	20,000/-	1.000/-	2 Months.

2. The intending participants can submit their applications along with the below listed documents / requirements for the purpose of issuance of bidding documents of work during office hours with immediate effect No bidding documents will be provided without the payment of cost shown above (Not refundable) of bidding documents which shall be in shape of pay order / deposit receipt or cash payment.

SPPRA INWARD DIARY
NO: 2191
DATED LO 2012

Conti..... P-2

#### PAGE-2

- 3. The tender documents downloaded from Sindh PPRA website, shall only be entertained if exclusively accompanied with pay order / deposit receipt as the cost of bidding documents in favour of "Resident Engineer Special Project Sindh House Islamabad".
- 4. The bids will be received back on 04-6-2018 up to 10:00 A.M. and will be opened on the same day @ 11:00 AM in presence of Procurement Committee and participating bidders or their authorized representatives who wish to be present on the occasion. In case of tender(s) remains un-responded, the schedule for 2<sup>nd</sup> attempt will be as under:-

#### Date of issue

Tenders shall be sold from 05-6-2018 to 19-6-2018

Date of receiving and opening
Sealed envelop of tenders shall be received on
20-6-2018 up to 10:00 A.M.
and opened on same day at 11:00 AM

#### Eligibility / Conditions:-

- Valid Registration with Pakistan Engineering Council in the relevant category or above discipline keeping in view the bid costs for items shown above.
- For electrical work valid license issued from inspectorate of Electrical License Sindh or similar region with respect to works, shown above.
- Documentary evidence of work of equivalent cost or above executed in last 3 years and Certificate of satisfactory completion showing date of start and completion.
- List of work is progress along with copy of letter of award.
- List of machinery and equipment available with status of its ownership.
- Registration with Income Tax Department (NTN copy) and Sindh Revenue Board (Sales Tax Registration) and copy of CNIC.
- Undertaking on stamp paper that firm is not involved in any litigation, Departmental rift, abandoned or unnecessary delay in completion of any work in the Government Departments.
- The 2% Earnest money shall be submitted in favour of undersigned, in shape of call deposit issued from scheduled bank, accompanied with bidding documents. Cheques shall not be entertained for this purpose.
- · Certificate of bank showing credit worthiness along-with current bank statement.
- Affidavit to the effect that firm has not been black listed.
- Affidavit to the effect that all documents, particulars and information furnished is true and correct.
- ❖ In case the applicant not fulfills SPPRA Rules-2010 (Amended 2013) or aforesaid conditions the application for issuance of bidding document will not be entertained.
- The Competent Authority reserves the right to reject any or all the tenders in accordance with SPPRA Rules 10 (Amended 2013).
- . Conditional Tenders will not be entertained.
- \* Advertisement can be seen on Sindh Government website (w.w.w.Sindh.gov.pk) and SPPRA web site.

The bids shall be evaluated as per criterion annexed to the bidding documents.

(MUZAEEAR ALI SEELRO) RESIDENT ENGINEER SPECIAL PROJECT SINDH HOUSE ISLAMABAD

- Copy forwarded to the Manager (CB) Sindh PPRA, Barrack No.8, Sindh Secretariat No.4-A, Karachi along with <u>CD</u>, <u>Standard Bidding Documents</u>, copy of Notification of <u>Procurement Committee</u>. <u>Procurement Plan</u> and <u>Notifications of CRC</u> for hoisting.
- 2. Copy F.W.Cs. the Chief Engineer (Buildings) Govt. of Sindh, Hyderabad.
- 3. Copy F.W.Cs. to the Superintending Engineer, Provincial Buildings Circle Karachi, with reference to approval of N.I.T. vide his letter No. PBC/B&A/, dated -2018 for favour of information.
- 4. Copy to the Section Officer (Tech.), Information Technology Department, Govt: of Sindh, Sindh Secretariat No.6 (old State Bank Building) Karachi for hoisting on Sindh Portal (w.w.w.Sindh.gov.pk).
- 5. Copy to the President of Contractor Union Barrack No.3 Sindh Secretariat Block 4-A, Karachi.
- 6. Copy to the Assistant Engineer, Sindh House Islamabad for information & necessary action.
- 7. Copy for Notice Board.

# Instructions to Bidders/ Procuring Agencies.

### General Rules and Directions for the Guidance of Contractors.

This section of the bidding documents should provide the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring Agency. It should also give information on bid submission, opening and evaluation, and on the award of contract.

Matters governing the performance of the Contract or payments under the Contract, or matters affecting the risks, rights, and obligations of the parties under the Contract are included as Conditions of Contract and Contract Data.

The Instructions to Bidders will not be part of the Contract and will cease to have effect once the contract is signed.

1. All work proposed to be executed by contract shall be notified in a form of Notice Inviting Tender (NIT)/Invitation for Bid (IFB) hoisted on website of Authority and Procuring Agency and also in printed media where ever required as per rules.

NIT must state the description of the work, dates, time and place of issuing, submission, opening of bids, completion time, cost of bidding document and bid security either in lump sum or percentage of Estimated Cost/Bid Cost. The interested bidder must have valid NTN also.

- 2. Content of Bidding Documents must include but not limited to: Conditions of contract, Contract Data, specifications or its reference, Bill of Quantities containing description of items with scheduled/item rates with premium to be filled in form of percentage above/ below or on item rates to be quoted, Form of Agreement and drawings.
- 3. Fixed Price Contracts: The Bid prices and rates are fixed during currency of contract and under no circumstance shall any contractor be entitled to claim enhanced rates for any item in this contract.
- **4.** The Procuring Agency shall have right of rejecting all or any of the tenders as per provisions of SPP Rules 2010.
- 5. Conditional Offer: Any person who submits a tender shall fill up the usual printed form stating at what percentage above or below on the rates specified in Bill of Quantities for items of work to be carried out: he is willing to undertake the work and also quote the rates for those items which are based on market rates. Only one rate of such percentage, on all the Scheduled Rates shall be framed. Tenders, which propose any alternative in the works specified in the said form of invitation to tender or in the time allowed for carrying out the work, or which contain any other conditions, will be liable to rejection. No printed form of tender shall include a tender for more than one work, but if contractor wish to tender for two or more works, they shall submit a separate tender for each.

The envelope containing the tender documents shall refer the name and number of the work.

- 6. All works shall be measured by standard instruments according to the rules.
- 7. Bidders shall provide evidence of their eligibility as and when requested by the Procuring Agency.
- **8.** Any bid received by the Agency after the deadline for submission of bids shall be rejected and returned unopened to the bidder.
- 9. Prior to the detailed evaluation of bids, the Procuring Agency will determine whether the bidder fulfills all codal requirements of eligibility criteria given in the tender notice such as registration with tax authorities, registration with PEC (where applicable), turnover statement, experience statement, and any other condition mentioned in the NIT and bidding document. If the bidder does not fulfill any of these conditions, it shall not be evaluated further.
- 10. Bid without bid security of required amount and prescribed form shall be rejected.
- 11. Bids determined to be substantially responsive shall be checked for any arithmetic errors. Arithmetical errors shall be rectified on the following basis;
- (A) In case of schedule rates, the amount of percentage quoted above or below will be checked and added or subtracted from amount of bill of quantities to arrive the final bid cost.
- (B) In case of item rates, .If there is a discrepancy between the unit rate and the total cost that is obtained by multiplying the unit rate and quantity, the unit rate shall prevail and the total cost will be corrected unless in the opinion of the Agency there is an obvious misplacement of the decimal point in the unit rate, in which case the total cost as quoted will govern and the unit rate corrected. If there is a discrepancy between the total bid amount and the sum of total costs, the sum of the total costs shall prevail and the total bid amount shall be corrected.
- (C) Where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.

# **Conditions of Contract**

Clause – 1: Commencement & Completion Dates of work. The contractor shall not enter upon or commence any portion or work except with the written authority and instructions of the Engineer-in-charge or of in subordinate-in-charge of the work. Failing such authority the contractor shall have no claim to ask for measurements of or payment for work.

The contractor shall proceed with the works with due expedition and without delay and complete the works in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckoned from the date on which the order to commence work is given to the contractor. And further to ensure good progress during the execution of the wok, contractor shall be bound, in all in which the time allowed for completion of any work exceeds one month, to achieve progress on the prorate basis.

Clause – 2: Liquidated Damages. The contractor shall pay liquidated damages to the Agency at the rate per day stated in the bidding data for each day that the completion date is later than the Intended completion date; the amount of liquidated damage paid by the contractor to the Agency shall not exceed 10 per cent of the contract price. Agency may deduct liquidated damages from payments due to the contractor. Payment of liquidated damages does not affect the contractor's liabilities.

Clause - 3: Termination of the Contract.

- (A) Procuring Agency/Executive Engineer may terminate the contract if either of the following conditions exits:-
- (i) Contractor causes a breach of any clause of the Contract;
- (ii) the progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired;
- (iii) In the case of abandonment of the work owing to the serious illness or death of the contractor or any other cause.
- (iv) Contractor can also request for termination of contract if a payment certified by the Engineer is not paid to the contractor within 60 days of the date of the submission of the bill;
- (B) The Executive Engineer/Procuring Agency has power to adopt any of the following courses as may deem fit:-
- (i) to forfeit the security deposit available except conditions mentioned at A (iii) and (iv) above;
- (ii) to finalize the work by measuring the work done by the contractor.
- (C) In the event of any of the above courses being adopted by the Executive Engineer/Procuring Agency, the contractor shall have:
  - no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work or the performance of the contract,

(ii) However, the contractor can claim for the work done at site duly certified by the executive engineer in writing regarding the performance of such work and has not been paid.

Procuring Agency/Engineer may invite fresh bids for remaining work.

Clause 4: Possession of the site and claims for compensation for delay. The Engineer shall give possession of all parts of the site to the contractor. If possession of site is not given by the date stated in the contract data, no compensation shall be allowed for any delay caused in starting of the work on account of any acquisition of land, water standing in borrow pits/ compartments or in according sanction to estimates. In such case, either date of commencement will be changed or period of completion is to be extended accordingly.

Clause -5: Extension of Intended Completion Date. The Procuring Agency either at its own initiatives before the date of completion or on desire of the contractor may extend the intended completion date, if an event (which hinders the execution of contract) occurs or a variation order is issued which makes it impossible to complete the work by the intended completion date for such period as he may think necessary or proper. The decision of the Executive Engineer in this matter shall be final; where time has been extended under this or any other clause of this agreement, the date for completion of the work shall be the date fixed by the order giving the extension or by the aggregate of all such orders, made under this agreement. When time has been extended as aforesaid, it shall continue to be the essence of the contract and all clauses of the contract shall continue to be operative during the extended period.

Clause -6: Specifications. The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards materials and all other matters in strict accordance with the specifications lodged in the office of the Executive Engineer and initialed by the parties, the said specification being a part of the contract. The contractor shall also confirm exactly, fully and faithfully to the designs, drawing, and instructions in writing relating to the work signed by the Engineer-in-charge and lodge in his office and to which the contractor shall be entitled to have access at such office or on the site of work for the purpose of inspection during office hours and the contractor shall, if he so requires, be entitled at his own expense to make or cause to be made copies of the specifications, and of all such designs, drawings, and instructions as aforesaid.

### Clause - 7: Payments.

(A) Interim/Running Bill. A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill at least once in a month and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as for as admissible, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose countersignature to the measurement list will be sufficient to warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

The Engineer /Procuring Agency shall pass/certify the amount to be paid to the contractor, which he considers due and payable in respect thereof, subject to deduction of security deposit, advance payment if any made to him and taxes.

All such intermediate payment shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the Engineer-in-charge from recoveries from final bill and rectification of defects and unsatisfactory items of works pointed out to him during defect liability period.

- **(B)** The Final Bill. A bill shall be submitted by the contractor within one month of the date fixed for the completion of the work otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.
- Clause 8: Reduced Rates. In cases where the items of work are not accepted as so completed, the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

## Clause - 9: Issuance of Variation and Repeat Orders.

- (A) Agency may issue a Variation Order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plans, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.
- (B) Contractor shall not perform a variation until the Procuring Agency has authorized the variation in writing subject to the limit not exceeding the contract cost by of 15% on the same conditions in all respects on which he agreed to do them in the work, and at the same rates, as are specified in the tender for the main work. The contractor has no right to claim for compensation by reason of alterations or curtailment of the work.
- **(C)** In case the nature of the work in the variation does not correspond with items in the Bill of Quantities, the quotation by the contractor is to be in the form of new rates for the relevant items of work, and if the Engineer-in-charge is satisfied that the rate quoted is within the rate worked out by him on detailed rate analysis, and then only he shall allow him that rate after approval from higher authority.
- (D) The time for the completion of the work shall be extended in the proportion that the additional work bear to the original contact work.
- **(E)** In case of quantities of work executed result the Initial Contract Price to be exceeded by more than 15%, and then Engineer can adjust the rates for those quantities causing excess the cost of contract beyond 15% after approval of Superintending Engineer.

- (F) Repeat Order: Any cumulative variation, beyond the 15% of initial contract amount, shall be subject of another contract to be tendered out if the works are separable from the original contract.

  Clause-10: Quality Control.
  - (A) Identifying Defects: If at any time before the security deposit is refunded to the contractor/during defect liability period mentioned in bid data, the Engineer-incharge or his subordinate-in-charge of the work may instruct the contractor to uncover and test any part of the works which he considers may have a defect due to use of unsound materials or unskillful workmanship and the contractor has to carry out a test at his own cost irrespective of work already approved or paid.
  - **(B) Correction of Defects:** The contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require. The contractor shall correct the notified defect within the Defects Correction Period mentioned in notice.

### (C) Uncorrected Defects:

- (i) In the case of any such failure, the Engineer-in-charge shall give the contractor at least 14 days notice of his intention to use a third party to correct a defect. He may rectify or remove, and re-execute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor.
- (ii) If the Engineer considers that rectification/correction of a defect is not essential and it may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fix therefore.

#### Clause - 11:

- (A) Inspection of Operations. The Engineer and his subordinates, shall at all reasonable times have access to the site for supervision and inspection of works under or in course of execution in pursuance of the contract and the contractor shall afford every facility for and every assistance in obtaining the right to such access.
- (B) Dates for Inspection and Testing. The Engineer shall give the contractor reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, then he either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, orders given to the contractor's duly authorized agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

### Clause - 12: Examination of work before covering up.

(A) No part of the works shall be covered up or put out of view/beyond the reach without giving notice of not less than five days to the Engineer whenever any such part of the works or foundations is or are ready or about to be ready for

examination and the Engineer shall, without delay, unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations;

(B) If any work is covered up or placed beyond the reach of measurement without such notice having been given, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed.

Clause - 13: Risks. The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or related services at the premises and of personal injury and death which arise during and in consequence of its performance of the contract. if any damage is caused while the work is in progress or become apparent within three months of the grant of the certificate of completion, final or otherwise, the contractor shall make good the same at his own expense, or in default the Engineer may cause the same to be made good by other workmen, and deduct the expenses from retention money lying with the Engineer.

Clause-14: Measures for prevention of fire and safety measures. The contractor shall not set fire to any standing jungle, trees, bush-wood or grass without a written permit from the Executive Engineer. When such permit is given, and also in all cases when destroying, cutting or uprooting trees, bush-wood, grass, etc by fire, the contractor shall take necessary measures to prevent such fire spreading to or otherwise damaging surrounding property. The contractor is responsible for the safety of all its activities including protection of the environment on and off the site. Compensation of all damage done intentionally or unintentionally on or off the site by the contractor's labour shall bepaid by him.

Clause-15:Sub-contracting. The contractor shall not subcontract the whole of the works, except where otherwise provided by the contract. The contractor shall not subcontract any part of the works without the prior consent of the Engineer. Any such consent shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts, defaults and neglects of any subcontractor, his agents, servants or workmen as if these acts, defaults or neglects were those of the contractor, his agents' servants or workmen. The provisions of this contract shall apply to such subcontractor or his employees as if he or it were employees of the contractor.

Clause - 16: Disputes. All disputes arising in connection with the present contract, and which cannot be amicably settled between the parties, , the decision of the Superintending Engineer of the circle/officer/one grade higher to awarding authority shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions, hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other questions, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, of failure to execute the same, whether arising, during the progress of the work, or after the completion or abandonment thereof.

Clause -17: Site Clearance. On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (hereinafter called the Engineer in charge) of such completion, but neither such certificate shall be given nor shall the work be considered to be complete until the contractor shall have removed all temporary structures and materials brought at site either for use or for operation facilities including cleaning debris and dirt at the site. If the contractor fails to comply with the requirements of this clause then Engineer-in-charge, may at the expense of the contractor remove and dispose of the same as he thinks fit and shall deduct the amount of all expenses so incurred from the contractor's retention money. The contractor shall have no claim in respect of any surplus materials as aforesaid except for any sum actually realized by the sale thereof.

### Clause -18: Financial Assistance / Advance Payment.

- (A) Mobilization advance is not allowed.
- (B) Secured Advance against materials brought at site.
  - (i) Advance may be permitted only against materials/quantities anticipated to be consumed/utilized on the work within a period of three months from the date of issue of secured advance and quantities of not for full materials for work/contract. The sum payable for such materials on site shall not exceed 75% of the market price of materials;
  - (ii) Recovery of Secured Advance paid to the contractor under the above provisions shall be affected from the monthly payments on actual consumption basis, but not later than period more than three months (even if unutilized).

Clause -19: Recovery as arrears of Land Revenue. Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

Clause -20: Refund of Security Deposit/Retention Money. On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurements are checked by a competent authority, if such check is necessary otherwise from the last date of recording the final measurements), the defects notice period has also passed and the Engineer has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor (in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

Divisional Accountant

Resident Engineer

Special Project, Sindh House

Islamabad

Contractor

# EVALUATION CRITERION

- \* Registration with PEC.
- \* NTN Certificate.
- Affidavit for no black listing / litigation.
- Payment of Tender Fee.
- Call Deposit / Pay Order of Earnest money.

# NAME OF WORK =>

# M/R TO SINDH HOUSE ISLAMABAD (COLONY STREET LIGHTS (Category VI Flats)

		HEDULE B			
S.no	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
	Providing and fixing distribution board double shutter to accommodate circuit breakers including painting with enamel paint and for other similar jobs on surface, the cost is also i/c the cost of all labour, cartage, material etc complete as approved by the engineer in-				
	-	9.00 Sft.		P. Sft.	
2	P/F on a prepared board iron clad bus bar with 4 copper strips of 300 Amps in 31.7mmx6.3mm(1-1/4"x1/4") section with chamber of overall size 1828x419mm (72"x16.50") or as approved by the	1 Nos			
2	Description & Scriptor and all bound to accompany to	1 1105		Each	
3	Providing & fixing metal board to accommodate mains or sub-mains control switches recessed in the wall i/c the cost of all labour, cartage, material etc complete as approved by the engineer in-charge.				
d .		15.00 Sft.		P. Sft.	
	Providing circuit breaker 300Amps to 400 Amps (imported or equivalent) T.P. including fixing on a prepared board and necessary connection, the cost is also i/c the cost of all labour, cartage, material etc complete as approved by the engineer in-charge.			s V	4
		1 Nos		Each	
5	Providing circuit breaker 100 Amps (imported or equivalent) T.P. including fixing on a prepared board and necessary connection, the cost is also i/c the cost of all labour, cartage, material etc complete as approved by the engineer in-charge.	5 5 6 K b	- =	- Z - 4	
		2 Nos		Each	
6	Providing circuit breaker 6 amps. To 63 amps. (imported or equivalent) D.P. i/c fixing on a prepared board and necessary connection , the cost is also i/c the cost of all labour, cartage, material etc complete as approved by the engineer in-charge.				
		25 Nos		Each	
7	Wiring with Main 4-7/0.64 in 1-1/4" dia PVC pipe of best quality Galco or Equivalent quality with earth wire of approved quality with all necessary PVC fitting recessed in the wall / on surface. This also includes the cost of all labour, material etc complete as approved by the Engineer In-charge.				
	and the second s	227.00 Rft.		P.Rft.	
8	Wiring with Main 4-7/0.44 in 1" dia PVC pipe of best quality Galco or Equivalent quality with earth wire of approved quality with all necessary PVC fitting recessed in the wall / on surface. This also includes the cost of all labour, material etc complete as approved by the Engineer In-charge.				
		896.0 Rft.		P. Rft.	

9	Wiring with Main 3-7/0.44 in 1" dia PVC pipe of best
	quality Galco or Equivalent quality with earth wire of
	approved quality with all necessary PVC fitting
	recessed in the wall / on surface. This also includes
	the cost of all labour, material etc complete as
	approved by the Engineer In-charge.

10	Wiring with Main 2-7/0.44 in 3/4" dia PVC pipe of best
	quality Galco or Equivalent quality with earth wire of
	approved quality with all necessary PVC fitting
	recessed in the wall / on surface. This also includes
	the cost of all labour, material etc complete as
	approved by the Engineer In-charge.

	Wiring with Main 2-7/0.44 in 3/4" dia PVC pipe of best quality Galco or Equivalent quality with earth wire of approved quality with all necessary PVC fitting recessed in the wall / on surface. This also includes the cost of all labour, material etc complete as approved by the Engineer In-charge.	10
0 Rft. P. Rft.	1400.	

1400.0 Rft.

11 Wiring with Main 2-7/0.29 in 3/4" dia PVC pipe of best quality Galco or Equivalent quality with earth wire of approved quality with all necessary PVC fitting recessed in the wall / on surface. This also includes the cost of all labour, material etc complete as approved by the Engineer In-charge.

		237.50 Rft.	P.Rft.	
12	Providing and fixing search light 85 watts or in required power (Energy Saver), water proof of approved quality (Imported or equivelent) with reflector i/c the cost of fixing at required height with nut, bolts in/c the cost of making connection in PVC flexible pipe in/c testing as approved by the Engineer	1		
		25 Nos	Each	
			Total	

#### TERMS & CONDITIONS.

The work will be carried out as per PWD specification.

No Premium shall be allowed on Non-Schedule Items.

No cartage shall be allowed on Non-Schedule Items.

Any Typographical error will referred to the composite Schedule of Rates enforced.

The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

RESIDENTENGINEER SPECIAL PROJECT SINDH HOUSE ISLAMABAD

P. Rft.

# NAME OF WORK => M/R TO SINDH HOUSE ISLAMABAD (COLONY DRAINAGE SYSTEM (CATEGORY VI

	SCHEDULE B			
S. No.	DESCRIPTION OF ITEMS QUANTITY R.	ATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)			
1	Cutting of Hard rock such as granite ballast line stone are sand stone etc with chsels a hammers for small foundations.i/c the cost of all labour,cartage,material etc complete directed by the Engineer In-charge.	nd as		
2	TOTAL QUANTITY: 3,538.00 Cft 286 Excavation in shingle or gravel formation and rock ' not requiring blasting undressed , le upto 100 ft. (b) Wet (S.I.N.4-b/P-1)		%0Cft	101,442 / 00
3	TOTAL QUANTITY: 5,307.00 Cft. 66 Cement concrete brick or stone ballast 1½" to 2" gauge 1:4:8 etc complete,the cost is a i/c the cost of all labour, cartage, material etc complete as directed by the Engineer	so	%0Cft	35,318 / 00
4			3 % Cft	47,081 / 00
5	A CONTRACTOR OF THE PROPERTY O	ne	2 % Sft	187,502 / 00
6	Providing and laying brick masonry in ratio 1:4 with pacca brick work at any floor cur finishing etc complete. The cost is also i/c all carriage, tools and plants used in mak and fixing the cost is also i/c the cost of all labour,cartage,material etc complete as direct	ng ng	) %o Cf	11,614 / 00
7	by the Engineer  TOTAL QUANTITY: 937.50 Cft 125  Applying cement plaster 1:4 upto any height /floor 3/4" thick at the hilly site the cost is a i/c the cost of all labour,cartage,material etc complete as directed by the Engineer		1 % Cft	117,201 / 00
	TOTAL QUANTITY: 2,500.00 Sft 30 SUB TOTAL		6 % Sft . work :	75,394 / 00 <b>575,552</b> / 00
(B)	WATER SUPPLY AND SANITARY FITTINGS (Schedule Items)  Providing RCC pipe & collor of Class "C" & fixing in trench i/c cutting, fitting and joint with maxphalt composition and cement mortor i/c testing with a water head of 45 meter 150 ft .The cost is also i/c the cost of all labour, cartage, material etc complete as directly the Engineer In-Charge.6" dia	or		
2	TOTAL QUANTITY: 200.00 Rft  Providing RCC pipe & collor of Class "C" & fixing in trench i/c cutting, fitting and joint with maxphalt composition and cement mortor i/c testing with a water head of 45 meter 150 ft .The cost is also i/c the cost of all labour, cartage, material etc complete as directly the Engineer In-Charge.9" dia	or	P.Rft	37,800 / 00
3	TOTAL QUANTITY: 100.00 Rft  Providing RCC pipe & collor of Class "C" & fixing in trench i/c cutting, fitting and joint with maxphalt composition and cement mortor i/c testing with a water head of 45 meter 150 ft. The cost is also i/c the cost of all labour, cartage, material etc complete as directly the Engineer In-Charge.12" dia	or	P.Rft	19,400 / 00
	TOTAL QUANTITY: 200.00 Rft	30	P.Rft	66,000 / 00

# NAME OF WORK => $\frac{M/R}{FLATS}$ $\frac{TO}{FLATS}$ $\frac{SINDH}{FLATS}$ $\frac{HOUSE}{FLATS}$ $\frac{ISLAMABAD}{FLATS}$ $\frac{(COLONY)}{FLATS}$ $\frac{DRAINAGE}{FLATS}$ $\frac{SYSTEM}{FLATS}$ $\frac{(CATEGORY)}{FLATS}$

# SCHEDULE 'B'

S. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
4	Concenteration Manhole for the required dia of drainage of B.B in cement sand mortor 1:3 cement plastered 1:3 (25mm) over benching and channel i/c fixing manhole of 2'x2' (610x610mm) of 4.5 Cwt. embeded in plain C.C 1:2 cost is also i/c the cost of all labour, cartage, material Engineer In-Charge. (a) 4" to 9" dia 4' x 3' x 7'-6"	1/2" thick inside of wal over with frame of clea 4 and two way reinforce	Is and 1" r opening ed 6",The		
	TOTAL QUANTITY Concenteration Manhole for the required dia of drainage of B.B in cement sand mortor 1:3 cement plastered 1:3	sewer and 3'-6" depth		Each	213,725 / 00
5	(25mm) over benching and channel i/c fixing manhole of 2'x2' (610x610mm) of 4.5 Cwt. embeded in plain C.C 1:2 cost is also i/c the cost of all labour, cartage, material Engineer In-Charge. (a) 4" to 9" dia 2' x 2' x 3'-6"	over with frame of clea 4 and two way reinforce	r opening ed 6",The		
	TOTAL QUANTITY	7: 4.00 Each	14748	Each _	58,992 / 00
	TOTAL AMO	OUNT OF PLUMBING WO	RK (SCHEDUL	E ITEMS):	395.917 / 00

# **GRAND TOTAL OF BIDE (A+B):**

## TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

# SCHEDULE 'B'

S.No	DESCRIPTION OF ITEMS	QUANTITY	RATE UNIT	AMOUNT
1	Supplying and spreading cow dung manuer including breaking clods and free from bushes, the cost includes loading and unloading, the cost is also i/c all labour, cartage, material etc complete as directed by the Engineer In-charge.	1 Truck	P.Truck	
2	Supplying and spreading sweet earth including breaking clods and free from bushes, the cost includes loading and unloading the cost is also i/c all labour, cartage, material etc complete as directed by the Engineer In-charge.	1 Truck	P.Truck	
3	Supplying of flower all season in different approved verities & colours specially for climate of Murree, the cost is also i/c all labour, cartage, material etc complete as directed by the Engineer In-charge.	120 Packets	P.Pk	
4	Supplying of Nyloon pipe 1" dia of special quality i/c cartage for garden the cost is also i/c all cartage, material etc complete as directed by the Engineer In-charge.	300 feet	P.Rf	
5	Making & fixing Fancy type 3 seated "Garden benches" made with 1-1/2" diameter 16 gauge M.S pipe frame with providing 1"x3/4"x3/16 & 1"x3/4"x3/16 angle iron strips duly welded with pipe frame also painted 2 or more coats upto required finish with imported anti rust paint after first coat of red oxide also fixing in position on C.C. plat form or providing extra ptties for stand for making moveable type etc complete with all cost for labour, material & cartage or as directed by the Engineer in	10 Nos.	Each	
6	Wiring with Main 2-7/0.44 in 3/4" dia PVC pipe of best quality Galco or Equivalent quality with earth wire of approved quality with all necessary PVC fitting recessed in the wall / on surface. This also includes the cost of all labour, material etc complete as approved by the Engineer In-charge.	587 Rft	P. Rf	
7	Providing and fixing search light 85 watts or in required power (Energy Saver), water proof of approved quality (Imported or equivelent) with reflector i/c the cost of fixing at required height with nut, bolts in/c the cost of making connection in PVC flexible pipe in/c testing as approved by the Engineer In-	37 Nos.	Each	
8	Making & fixing 2" dia G.I pipe pole for security light of security purpose using 2" dia G.I pipe of heavy guage 12'-0" long also using 15"x15" M.S plat 1/8" thick welded horizantly at top side of pipe for fixing of security lights also supported by extra patties dully welded in approved design i/c fixing on C.C.1:2:4, painting 3 coat etc complete or as approved by the Engineer	37 Nos.	Eacl	
	In-charge	07 1103.	Total:	

### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rul

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE SUB DIVISION ISLAMABAD

# NAME OF WORK => M/R TO SINDH HOUSE ISLAMABAD (OLD COLONY (ELECTRICAL WORKS

# SCHEDULE 'B'

	COTIL	DOLL D			
S. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
1	ELECTRICAL WORKS (NonSchedul Items) Wiring of light of fan point with 1/1.13mm (3/0.029) PV equilant in 20mm (3/4") PVC conduit recessed in wall or co the cost of all labour cartage material etc complete as appr	olumn as required, the o	cost is also i/c		
2	Providing and fixing A.C one way S.P 5AMP switch fuse to board recessed in wall or column and covered with fiber stabour cartage material etc complete as approved by the E.	heet, the cost is also i/c	nt) on a metal the cost of all	P.Point	
3	Providing and fixing Ceiling fan regulator (imported or eq wall or column and covered with, the cost is also i/c the complete as approved by the Engineer In-Charge.	68.00 No uilant) on a metal board cost of all labour cartage	d recessed in e material etc	Each	
4	Providing and fixing 1-40 watts tube light complete with 40 putty with Philips componenta including necessary electric also i/c the cost of all labour cartage material etc complete.	connection and fixing of	on, the cost is	Each	
5	TOTAL QUANTITY: Wiring for mains with 2-7/.029 wire (Pakistan cable or equi surface as required, the cost is also i/c the cost of all lab approved by the Engineer In-Charge.			Each	
6	TOTAL QUANTITY: Supplying of A.C ceiling fan 56" sweep (Pak or Millat), the cartage material etc complete as approved by the Engineer		t of all labour	P.Rft	, - 1
7	Providing and fixing A.C two 3-pin 15 Amp S.P plug sock equilant) on metal board recessed in wall or column and also i/c the cost of all labour cartage material etc complete.	34.00 No et switch and shoe unit covered with plastic she	et,the cost is	Each	
8	TOTAL QUANTITY: Providing and fixing wall bracket light fancy type superio connection and fixing on wall or ceiling etc complete, the cartage material etc complete as approved by the Engineer	cost is also i/c the cost		Each	
9	TOTAL QUANTITY: Providing and fixing exhaust fan 12" size (Pak or Millat) me causing and making necessary electric connection, the cartage material etc complete as approved by the Engineer	cost is also i/c the cost		Each	
	TOTAL QUANTITY:	68.00 No		Each	
				TOTAL:-	

### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.

5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

SPECIAL PROJECT SINDH HOUSE ISLAMABAD

# NAME OF WORK => $\frac{M/R}{QUARTER SIDE).}$ ISLAMABAD (COLONY DRAINAGE SYSTEM (SINGLE ROOM)

	SCHEDULE B			
S. No.	DESCRIPTION OF ITEMS QUANTITY	RATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)			
1	Cutting of Hard rock such as granite ballast line stone are sand stone etc with chammers for small foundations.i/c the cost of all labour,cartage,material etc codirected by the Engineer In-charge.	chsels and emplete as		
2	TOTAL QUANTITY: 3,538.00 Cft Excavation in shingle or gravel formation and rock 'not requiring blasting undres upto 100 ft. (b) Wet (S.I.N.4-b/P-1)		5 %0Cft	101,442 / 00
3	TOTAL QUANTITY: 5,307.00 Cft.  Cement concrete brick or stone ballast 1½" to 2" gauge 1:4:8 etc complete,the ci/c the cost of all labour, cartage, material etc complete as directed by the En		%0Cft	35,318 / 00
4	TOTAL QUANTITY: 500.00 Cft Providing and laying 3" thick topping cement concrete (1:2:4) including Surface and dividing into panels: (d.) 3" thick (S.I.N. 16- d/P-42)	9416 / 26 e finishing	8 % Cft	47,081 / 00
5	TOTAL QUANTITY: 4,250.00 Cft Filling, watering and ramming earth in floor with surpls earth from foundation lead chain and lift upro 5 feet the cost is also i/c the cost of all labour, cartage, me complete as directed by the Engineer		2 % Sft	187,502 / 00
6	TOTAL QUANTITY: 7,679.00 Cft Providing and laying brick masonry in ratio 1:4 with pacca brick work at any fle finishing etc complete. The cost is also i/c all carriage, tools and plants used and fixing the cost is also i/c the cost of all labour,cartage,material etc cod directed by the Engineer	oor curing in making	0 %o Cf	11,614 / 00
7	TOTAL QUANTITY: 937.50 Cft Applying cement plaster 1:4 upto any height /floor 3/4" thick at the hilly site the ci/c the cost of all labour,cartage,material etc complete as directed by the Engineer		1 % Cft.	117,201 / 00
	TOTAL QUANTITY: 2,500.00 Sft SUB	3015 / 7 TOTAL OF CIVIL		75,394 / 00 <b>575,552</b> / 00
(B)	WATER SUPPLY AND SANITARY FITTINGS (Schedule Items)  Providing RCC pipe & collor of Class "C" & fixing in trench i/c cutting, fitting an with maxphalt composition and cement mortor i/c testing with a water head of 4:150 ft .The cost is also i/c the cost of all labour, cartage, material etc complete a by the Engineer In-Charge.6" dia	5 meter or		
2	Providing RCC pipe & collor of Class "C" & fixing in trench i/c cutting, fitting as with maxphalt composition and cement mortor i/c testing with a water head of 4 150 ft .The cost is also i/c the cost of all labour, cartage, material etc complete a by the Engineer In-Charge 9" dia	5 meter or	P.Rft	37,800 / 00
3	Providing RCC pipe & collor of Class "C" & fixing in trench i/c cutting, fitting as with maxphalt composition and cement mortor i/c testing with a water head of 4 150 ft .The cost is also i/c the cost of all labour, cartage, material etc complete a by the Engineer In-Charge.12" dia	5 meter or	P.Rft	19,400 / 00
	TOTAL QUANTITY: 200.00 Rft	330	P.Rft	66,000 / 00

# NAME OF WORK => M/R TO SINDH HOUSE ISLAMABAD (COLONY DRAINAGE SYSTEM (SINGLE ROOM QUARTER SIDE).)

# SCHEDULE 'B'

S. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
4	Concenteration Manhole for the required dia of drainage of B.B in cement sand mortor 1:3 cement plastered 1:3 (25mm) over benching and channel i/c fixing manhole c 2'x2' (610x610mm) of 4.5 Cwt. embeded in plain C.C 1:2 cost is also i/c the cost of all labour, cartage, material Engineer In-Charge. (a) 4" to 9" dia 4' x 3' x 7'-6"	1/2" thick inside of wa over with frame of clea :4 and two way reinforce	lls and 1" r opening ed 6",The		
5	Concenteration Manhole for the required dia of drainage of B.B in cement sand mortor 1:3 cement plastered 1:3 (25mm) over benching and channel i/c fixing manhole c 2'x2' (610x610mm) of 4.5 Cwt. embeded in plain C.C 1:2 cost is also i/c the cost of all labour, cartage, material Engineer In-Charge. (a) 4" to 9" dia 2' x 2' x 3'-6"	sewer and 3'-6" depth 1/2" thick inside of wa over with frame of clea :4 and two way reinforce	lls and 1" r opening ed 6",The	Each	213,725 / 00
	TOTAL QUANTIT	Y: 4.00 Each	14748	Each _	58,992 / 00
	TOTAL AMO	OUNT OF PLUMBING WO	RK (SCHEDUL	FITEMS):	395.917 / 00

# GRAND TOTAL OF BIDE (A+B):

### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

#### M/R TO DOUBLE ROOM FLAT ! LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. NAME OF WORK => (BLOCK A-1,2,3,4,5 & 6).

#### SCHEDULE 'B'

S.		TOOLL D					
No.	DESCRIPTION OF ITEMS	QUANTITY	<b>′</b>	RATE	UNIT	AMOUNT	
(A)	CIVIL WORKS (Schedule Items)						
1	Providing and laying brick masonry in ratio 1:4 with pacca b complete. The cost is also i/c all carriage, tools and plants used cost of all labour, cartage, material etc complete as directed by the	I in making and fixing th	curing fini e cost is a	shing etc so i/c the			
	TOTAL QUAN	TITY: 357.38	Cft	240 / 10	P. Cft.	85,806	/ 00
2	Applying cement plaster 1:4 upto any height /floor 3/4" thick at the labour, cartage, material etc complete as directed by the Engineer		lso i/c the	cost of all			
	TOTAL QUAN	TITY: 1,429.50	Sft	3015 / 76	% Sft	43,110	/ 00
3	Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 l/c welded hinges and fixing at site with necessary hold fasts, fill repairing the jambs. The cost also i/c all carriage, tools and pla 93)	ing with cement sand sl	urry of rati	o 1:6 and			
	TOTAL QUAN	TITY: 170.00	Cft	228 / 90	P. Cft.	38,913	/ 00
4	Providing and fixing in position, Doors, Windows and Ventilato 1½" thick commercial, ply veneer shutters of first class deod wood (3 ply) on both sides.(With out frame)(S.I.N.58/P-65)-(S.I.N	ar skeleton (H ollow )	and comm	ercial ply			
	TOTAL QUAN	TITY: 210.00	Sft	706 / 23	P.Sft.	148,308	/ 00
			SUB T	OTAL OF CIVIL	WORK:	316,137	/ 00
(B)	CIVIL WORKS (Non Schedule Items) Preparing the surface and painting with mat finish paint of appro	oved quality and ,make i	/c scrappir	ng the old			
1	surface, applying sandpaper filling with loppy and ICI or equilan		101525 Environment Designation	•			

applying sandpaper filling with loppy and ICI or equilant than applying matt finish paint 2 coats as directed by Engineer Incharge.

TOTAL QUANTITY:

12,474.00 Sft

P.Sft.

Preparing the surface and painting with enmal paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying enamal paint 2 coats as directed by Engineer Incharge.

TOTAL QUANTITY:

P.Sft.

Providing & Fixing wooden cabinet with shutter of "Lasani sheet" 3/4" thick and frame work of 1" class partal wood 2"x1" pasted with classic "Formica" 18" deep in/c necessary hinges, catchers, handles, sliding wheels in doors, nails, screws etc with approved design and shape. The cost also in/c necessary tools and plants to

be used in making etc complete as directed by the Engineer Incharge.

333.00 Sft

P.Sft.

TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS):

**GRAND TOTAL OF BID (A+B):** 

## TERMS & CONDITIONS.

- The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- Any Typographical error will referred to the composite Schedule of Rates enforced.
- The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

SPECIAL PROJECT SINDH HOUSE ISLAMABAD

# NAME OF WORK => M/R TO DOUBLE ROOM FLAT / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (BLOCK B-1,2,3,4,5 & 6).

#### SCHEDULE 'B'

1 C	CIVIL WORKS (Schedule Items)			UNIT	AMOUNT
1 C					
1 0					
	roviding and laying brick masonry in ratio 1:4 with pacca brick wo omplete. The cost is also i/c all carriage, tools and plants used in ma ost of all labour,cartage,material etc complete as directed by the Engir	king and fixing the o			
	TOTAL QUANTITY:	357.38	Cft 240 / 1	0 P. Cft.	85.806 / 00
	pplying cement plaster 1:4 upto any height /floor 3/4" thick at the hilly abour,cartage,material etc complete as directed by the Engineer	site the cost is also	i/c the cost of all		
	TOTAL QUANTITY:	1,429.50	Sft 3015 / 7	6 % Sft	43,110 / 00
3 1/c	roviding and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x c welded hinges and fixing at site with necessary hold fasts, filling wit epairing the jambs. The cost also i/c all carriage, tools and plants us 3)	h cement sand slurr	y of ratio 1:6 and		
	TOTAL QUANTITY:	170.00	Cft 228 / 9	0 P. Cft.	38,913 / 00
4 1	roviding and fixing in position, Doors, Windows and Ventilators of $\frac{1}{2}$ " thick commercial , ply veneer shutters of first class deodar ske rood (3 ply ) on both sides. (With out frame) (S.I.N.58/P-65)-(S.I.N.25-b.	leton (H ollow ) and	d commercial ply		
	TOTAL QUANTITY:	210.00	Sft 706 / 2	3 P.Sft.	148,308 / 00
			SUB TOTAL OF CIV	L WORK :	316,137 / 00

#### (B) CIVIL WORKS (Non Schedule Items)

Preparing the surface and painting with mat finish paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying matt finish paint 2 coats as directed by Engineer Incharge.

TOTAL QUANTITY: 12,474.00 Sft

Preparing the surface and painting with enmal paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying enamal paint 2 coats as directed by Engineer Incharge.

TOTAL QUANTITY:

2,028.00 Sft

P.Sft.

P.Sft.

Providing & Fixing wooden cabinet with shutter of "Lasani sheet" 3/4" thick and frame work of 1" class partal wood 2"x1" pasted with classic "Formica" 18" deep in/c necessary hinges, catchers, handles, sliding wheels in doors, nails, screws etc with approved design and shape. The cost also in/c necessary tools and plants to

be used in making etc complete as directed by the Engineer Incharge.

TOTAL QUANTITY:

333.00 Sft

P.Sft.

TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS):

**GRAND TOTAL OF BID (A+B):** 

#### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

# NAME OF WORK => $\frac{M/R}{(BLOCK C-1,2,3,4,5 \& 6)}$ . FLAT ! LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD.

SCHEDULE 'B'

No.	DESCRIPTION OF ITEMS		QUANTITY		RATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)						
1	Providing and laying brick masonry in ratio 1: complete. The cost is also i/c all carriage, tools cost of all labour, cartage, material etc complete a	and plants used in making	g and fixing the	uring finishi cost is also	ng etc i/c the		
		TOTAL QUANTITY:	357.38	Cft	240 / 10	P. Cft.	85,806 / (
2	Applying cement plaster 1:4 upto any height /floolabour,cartage,material etc complete as directed	or 3/4" thick at the hilly site by the Engineer	e the cost is als	so i/c the cos	st of all		
		TOTAL QUANTITY:	1,429.50	Sft	3015 / 76	% Sft	43,110 / (
3	Providing and fixing G.I frames /Choukhats of s I/c welded hinges and fixing at site with necessarepairing the jambs. The cost also i/c all carriag 93)	ary hold fasts, filling with co	ement sand slu	rry of ratio 1	:6 and		
		TOTAL QUANTITY:	170.00	Cft	228 / 90	P. Cft.	38,913 / (
4	Providing and fixing in position, Doors, Window $1\frac{1}{2}$ " thick commercial , ply veneer shutters of wood (3 ply ) on both sides.(With out frame)(S.I.	first class deodar skeleto	on (H ollow ) ar	nd commer	cial ply		
		TOTAL QUANTITY:	210.00	Sft	706 / 23	P.Sft.	148,308 / (
					AL OF CIVIL	WORK:	316,137 /
(B)	CIVIL WORKS (Non Schedule Items)						
1	Preparing the surface and painting with mat finis surface, applying sandpaper filling with loppy ardirected by Engineer Incharge.						
1	Preparing the surface and painting with mat finis surface, applying sandpaper filling with loppy ar		plying matt finis	sh paint 2 co		P.Sft.	
1	Preparing the surface and painting with mat finis surface, applying sandpaper filling with loppy ardirected by Engineer Incharge.  Preparing the surface and painting with enmal	TOTAL QUANTITY: paint of approved quality	12,474.00 and ,make i/c	Sft scrapping	the old	P.Sft.	
2	Preparing the surface and painting with mat finis surface, applying sandpaper filling with loppy ardirected by Engineer Incharge.	TOTAL QUANTITY: paint of approved quality	12,474.00 and ,make i/c	Sft scrapping	the old	P.Sft.	
	Preparing the surface and painting with mat finis surface, applying sandpaper filling with loppy ardirected by Engineer Incharge.  Preparing the surface and painting with enmal surface, applying sandpaper filling with loppy a directed by Engineer Incharge.	TOTAL QUANTITY: paint of approved quality and ICI or equilant than a	12,474.00 _ r and ,make i/c pplying enama 2,028.00 _	Sft scrapping all paint 2 co	the old	P.Sft.	
	Preparing the surface and painting with mat finis surface, applying sandpaper filling with loppy ardirected by Engineer Incharge.  Preparing the surface and painting with enmal surface, applying sandpaper filling with loppy as	TOTAL QUANTITY: paint of approved quality and ICI or equilant than a  TOTAL QUANTITY: of "Lasani sheet" 3/4" thick eep in/c necessary hinges, and shape. The cost also	12,474.00 _r and ,make i/c pplying enama 2,028.00 _s and frame wor, catchers, hand	Sft scrapping al paint 2 co	the old pats as		
2	Preparing the surface and painting with mat finis surface, applying sandpaper filling with loppy ardirected by Engineer Incharge.  Preparing the surface and painting with enmal surface, applying sandpaper filling with loppy addrected by Engineer Incharge.  Providing & Fixing wooden cabinet with shutter wood 2"x1" pasted with classic "Formica" 18" de in doors, nails, screws etc with approved design	TOTAL QUANTITY: paint of approved quality and ICI or equilant than a  TOTAL QUANTITY: of "Lasani sheet" 3/4" thick eep in/c necessary hinges, and shape. The cost also	12,474.00 _r and ,make i/c pplying enama 2,028.00 _s and frame wor, catchers, hand	Sft scrapping al paint 2 co	the old pats as		

TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS):

## **GRAND TOTAL OF BID (A+B):**

#### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

148,308 / 00

316,137 / 00

# $\mathsf{NAME}\;\mathsf{OF}\;\mathsf{WORK}\;\mathsf{=>}\;\;\frac{\mathsf{M/R}\;\;\mathsf{TO}\;\;\mathsf{DOUBLE}\;\;\mathsf{ROOM}}{(\mathsf{BLOCK}\;\;\mathsf{D-1},2,3,4,5\;\&\;6).}\;\;\mathsf{FLAT}\;\;\mathit{\mathit{I}}\;\;\mathsf{LOUNGE}\;\;\mathsf{OF}\;\;\mathsf{STAFF}\;\;\mathsf{COLONY}\;\;\mathsf{AT}\;\;\mathsf{SINDH}\;\;\mathsf{HOUSE}\;\;\mathsf{ISLAMABAD}.$

SCHEDIN E ID

	SCHEDU	LE .B.				
S. No.	DESCRIPTION OF ITEMS	QUANTITY		RATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)					
1	Providing and laying brick masonry in ratio 1:4 with pacca brick was complete. The cost is also i/c all carriage, tools and plants used in m cost of all labour, cartage, material etc complete as directed by the Eng	aking and fixing the				
	TOTAL QUANTITY:	357.38	Cft	240 / 10	P. Cft.	85,806 / 00
2	Applying cement plaster 1:4 upto any height /floor 3/4" thick at the hill labour,cartage,material etc complete as directed by the Engineer	y site the cost is als	so i/c the	cost of all		
	TOTAL QUANTITY:	1,429.50	Sft	3015 / 76	% Sft	43,110 / 00
3	Providing and fixing G.I frames /Choukhats of size 7" $\times$ 2" or 4 1/2" $\times$ 1/c welded hinges and fixing at site with necessary hold fasts, filling w repairing the jambs. The cost also i/c all carriage, tools and plants (93)	ith cement sand slu	rry of ratio	1:6 and		
	TOTAL QUANTITY:	170.00	Cft	228 / 90	P. Cft.	38,913 / 00
4	Providing and fixing in position, Doors, Windows and Ventilators of $1\frac{1}{2}$ " thick commercial , ply veneer shutters of first class deodar sk wood (3 ply ) on both sides.(With out frame)(S.I.N.58/P-65)-(S.I.N.25-	eleton (H ollow) a	nd comm	ercial ply		

#### (B) CIVIL WORKS (Non Schedule Items)

Preparing the surface and painting with mat finish paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying matt finish paint 2 coats as directed by Engineer Incharge.

TOTAL QUANTITY:

TOTAL QUANTITY: 12,474.00 Sft

Preparing the surface and painting with enmal paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying enamal paint 2 coats as directed by Engineer Incharge.

TOTAL QUANTITY: 2,028.00 Sft P.Sft.

210.00

Sft

Providing & Fixing wooden cabinet with shutter of "Lasani sheet" 3/4" thick and frame work of 1" class partal wood 2"x1" pasted with classic "Formica" 18" deep in/c necessary hinges, catchers, handles, sliding wheels in doors, pails, screws atc with approved design and shape. The cost also in/c necessary tools and plants to

in doors, nails, screws etc with approved design and shape. The cost also in/c necessary tools and plants to be used in making etc complete as directed by the Engineer Incharge.

TOTAL QUANTITY: 333.00 Sft

P.Sft.

P.Sft.

706 / 23 P.Sft.

SUB TOTAL OF CIVIL WORK :

TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS):

### **GRAND TOTAL OF BID (A+B):**

#### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

# NAME OF WORK => M/R TO DOUBLE ROOM FLAT / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (BLOCK A,B,C & D (ELECTRICAL WORKS)

	SCHEDULE 'B'		
S. No.	DESCRIPTION OF ITEMS QUANTITY RAT	re unit	AMOUNT
1	ELECTRICAL WORKS (NonSchedul Items) Wiring of light of fan point with 1/1.13mm (3/0.029) PVC insulated wire Pakistan cable or equilant in 20mm (3/4") PVC conduit recessed in wall or column as required, the cost is also i/c the cost of all labour cartage material etc complete as approved by the Engineer In-Charge.	m ge	
2	Providing and fixing A.C one way S.P 5AMP switch fuse type (imported or equilant) on a metal boar recessed in wall or column and covered with fiber sheet, the cost is also i/c the cost of all labour cartages.		1
3	TOTAL QUANTITY: 48.00 No  Providing and fixing Ceiling fan regulator (imported or equilant) on a metal board recessed in wall or column and covered with, the cost is also i/c the cost of all labour cartage material etc complete as approved by the Engineer In-Charge.	Each in ne	
4	TOTAL QUANTITY: 48.00 No  Providing and fixing 1-40 watts tube light complete with 40 watts 4'-0" long rod,chock,starter and putty will  Philips componenta including necessary electric connection and fixing on, the cost is also i/c the cost of a labour cartage material etc complete as approved by the Engineer In-Charge.		
5	TOTAL QUANTITY: 96.00 Rft  Wiring for mains with 2-7/.029 wire (Pakistan cable or equilant)660 volts grade, in 1" conduit on surface a required, the cost is also i/c the cost of all labour cartage material etc complete as approved by the Engineer In-Charge.		
6	TOTAL QUANTITY: 1,200.00 No  Supplying of A.C ceiling fan 56" sweep (Pak or Millat), the cost is also i/c the cost of all labour cartage materi etc complete as approved by the Engineer In-Charge.	P.Rft al	
7	TOTAL QUANTITY: 48.00 No  Providing and fixing A.C two 3-pin 15 Amp S.P plug socket switch and shoe unit ((imported or equilant) of metal board recessed in wall or column and covered with plastic sheet, the cost is also i/c the cost of all labor cartage material etc complete as approved by the Engineer In-Charge.		
8	Providing and fixing wall bracket light fancy type superior quality including necessary electric connection are fixing on wall or ceiling etc complete, the cost is also i/c the cost of all labour cartage material etc complete approved by the Engineer In-Charge.		
9	TOTAL QUANTITY: 120.00 No  Providing and fixing exhaust fan 12" size (Pak or Millat) metal body cutting hole in wall plastering causing ar making necessary electric connection, the cost is also i/c the cost of all labour cartage material etc comple as approved by the Engineer In-Charge.		

**GRAND TOTAL OF BID** 

52.00 No

#### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

TOTAL QUANTITY:

RESIDENT ENGINEER
SPECIAL PROJECT
SINDH HOUSE ISLAMABAD

Each SUB TOTAL:-

### NAME OF WORK =>

# M/R TO OLD COLONY / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (SINGLE ROOM QTRS 1,2,3,4,5,6,7,8 & 9).

	OUTIEDO	,				
S. No.	DESCRIPTION OF ITEMS	QUANTI	ΓY	RATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)				-	
1	Cement concrete brick or stone ballast 1½" to 2" gauge 1:4: i/c the cost of all labour, cartage, material etc complete as charge					
	TOTAL QUANTITY:	237.60	Cft	9416 / 28	% Cft	22,373 / 00
2	Re-inforcement concrete work at any floor work including all cost of steel reinfotcement and its labour for bending an separately this rate also includes all kinds of forms, moulds I finishing the exposed surface (including screening and was the cost is also i/c the cost of all labour, cartage, material et Engineer In-charge.	nd binding v lifting shutter hing of shin	vhich will ring rende gle) (i) Ra	be paid ering and atio 1:2:4		
	TOTAL QUANTITY:	180.00	Cft	337 / 0	P. Cft.	60,660 / 00
3	Providing and laying brick masonry in ratio 1:4 with pacca finishing etc complete. The cost is also i/c all carriage, tools a fixing the cost is also i/c the cost of all labour,cartage,materithe Engineer	and plants u	sed in ma	king and ected by		
	TOTAL QUANTITY:	360.00	Cft	240 / 10	P. Cft.	86,436 / 00
4	Applying cement plaster 1:4 upto any height /floor 3/4" thick i/c the cost of all labour,cartage,material etc complete as dire-			st is also		
	TOTAL QUANTITY:	1,440.00	Sft	3015 / 76	% Sft	43,427 / 00
5	Providing and fixing G.I frames /Choukhats of size 7" x 2" of gauge G.I sheet I/c welded hinges and fixing at site with necement sand slurry of ratio 1:6 and repairing the jambs. The and plants used in making and fixing.(S.I.N.29/P-93)	ecessary hol	ld fasts, fi	lling with		
	TOTAL QUANTITY:	153.00	Cft	228 / 90	P. Cft.	35,022 / 00
6	Providing and fixing in position, Doors, Windows and Ventila frames, and 1½" thick commercial, ply veneer shutters of ollow) and commercial ply wood (3 ply) on both sides.(V (S.I.N.25-b/P-61).(1077/06-370/83=706/23)	first class d	eodar ske	eleton (H		
	TOTAL QUANTITY:	189.00	Sft	706 / 23	P.Sft.	133,477 / 00
			SUB TO	OTAL OF CIVIL	WORK :	381,395 / 00
(B)	CIVIL WORKS (Non Schedule Items)  Preparing the surface and painting with mat finish paint of a scrapping the old surface, applying sandpaper filling with applying matt finish paint 2 coats as directed by Engineer Inc.	loppy and IC				
	TOTAL QUANTITY:	7.985.25	Sft		P.Sft.	
2	Preparing the surface and painting with enmal paint of a scrapping the old surface, applying sandpaper filling with applying enamal paint 2 coats as directed by Engineer Incha	pproved qualoppy and IC	ality and	make i/c lant than		
	TOTAL QUANTITY:	1,296.00	Sft		P.Sft.	
		.,,_,	0			

S. **DESCRIPTION OF ITEMS** QUANTITY RATE UNIT **AMOUNT** No. Providing & Fixing wooden cabinet with shutter of "Lasani sheet" 3/4" thick and frame work of 1" class partal wood 2"x1" pasted with classic "Formica" 18" deep in/c necessary hinges, catchers, handles, sliding wheels in doors, nails, screws etc with approved design and shape. The cost also in/c necessary tools and plants to be used in making etc complete as directed by the Engineer Incharge. TOTAL QUANTITY: P.Sft. 173.25 Sft TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS): (C) WATER SUPPLY AND SANITARY FITTINGS (Schedule Items) Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & I/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Foreign or Equivalent).(S.I.N. 10/P-3) TOTAL QUANTITY: 4928 / 70 Each 11.00 Nos 54,216 / 00 Supplying / Fixing wash basen mixture of superir quality with C.P., head 1/2" dia. (SIN 14/a)/P-19 TOTAL QUANTITY: 11.00 Nos 3179 / 0 34,969 / 00 Each TOTAL AMOUNT OF PLUMBING WORK (SCHEDULE ITEMS): 89,185 / 00

# GRAND TOTAL OF ESTIMATE (A+B+C):

#### TERMS & CONDITIONS.

- The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER
SINDH HOUSE ISLAMABAD

# NAME OF WORK =>

# 

S. No.	DESCRIPTION OF ITEMS	QUANTIT	Υ	RATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)					
1	Cement concrete brick or stone ballast 1½" to 2" gauge 1:4 the cost of all labour, cartage, material etc complete as direct					
•	the cost of all labour, cartage, material etc complete as direc	sted by the Eng	ineer in-c	narge.		
	TOTAL QUANTITY:	237.60	Cft	9416 / 28	% Cft	22,373 / 00
2	Re-inforcement concrete work at any floor work including a cost of steel reinfotcement and its labour for bending separately this rate also includes all kinds of forms, mould finishing the exposed surface (including screening and was cost is also i/c the cost of all labour, cartage, material engineer In-charge.	and binding w Is lifting shutter hing of shingle	hich will ring rend (i) Ratio	be paid ering and 1:2:4 the		
	TOTAL QUANTITY:	180.00	Cft	337 / 0	P. Cft.	60,660 / 00
3	Providing and laying brick masonry in ratio 1:4 with pace finishing etc complete. The cost is also i/c all carriage, tool fixing the cost is also i/c the cost of all labour, cartage, materi Engineer	s and plants u	sed in ma	aking and		
	TOTAL QUANTITY:	360.00	Cft	240 / 10	P. Cft.	86,436 / 00
4	Applying cement plaster 1:4 upto any height /floor 3/4" thick the cost of all labour,cartage,material etc complete as direct			is also i/c		
	TOTAL QUANTITY:	1,440.00	Sft	3015 / 76	% Sft	43,427 / 00
5	Providing and fixing G.I frames /Choukhats of size 7" x 2' gauge G.I sheet I/c welded hinges and fixing at site with cement sand slurry of ratio 1:6 and repairing the jambs. The and plants used in making and fixing.(S.I.N.29/P-93)	necessary hol	d fasts, f	illing with		
	TOTAL QUANTITY:	153.00	Cft	228 / 90	P. Cft.	35,022 / 00
6	Providing and fixing in position, Doors, Windows and Vent frames, and $1\frac{1}{2}$ " thick commercial , ply veneer shutters of fi ) and commercial ply wood (3 ply ) on both sides.(With oub/P-61).(1077/06-370/83=706/23)	rst class deoda	r skeletor	n (H ollow		
	TOTAL QUANTITY:	189.00	Sft	706 / 23	P.Sft.	133,477 / 00
			SUB T	OTAL OF CIVIL	WORK:	<b>381,395</b> / 00
(B)	CIVIL WORKS (Non Schedule Items)					
1	Preparing the surface and painting with mat finish paint of scrapping the old surface, applying sandpaper filling with applying matt finish paint 2 coats as directed by Engineer In	n loppy and IC				
	TOTAL QUANTITY:	7,985.25	Sft		P.Sft.	
2	Preparing the surface and painting with enmal paint of scrapping the old surface, applying sandpaper filling with applying enamal paint 2 coats as directed by Engineer Inch	approved qua	lity and			

# **GRAND TOTAL OF ESTIMATE (A+B+C):**

#### TERMS & CONDITIONS.

- I The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.

5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

# $\text{AME OF WORK} \Rightarrow \frac{\text{M/R}}{\text{(SINGLE ROOM QTRS 19,20,21,22,23,24,25 \& 26).}} \underbrace{\text{COLONY AT SINDH HOUSE ISLAMABAD.}}_{\text{(SINGLE ROOM QTRS 19,20,21,22,23,24,25 \& 26).}}$

	SCHEDO	JLL D				
S. No.	DESCRIPTION OF ITEMS	QUANTI	TY	RATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)  Cement concrete brick or stone ballast 1½" to 2" gauge 1:4: i/c the cost of all labour, cartage, material etc complete a					
	charge	s directed by	y the Engl	neer m-		
2	Re-inforcement concrete work at any floor work including the cost of steel reinfotcement and its labour for bending a separately this rate also includes all kinds of forms, moulds finishing the exposed surface (including screening and was the cost is also i/c the cost of all labour, cartage, material engineer In-charge	and binding lifting shutte shing of shin	which will ring rende gle) (i) Ra	be paid ring and tio 1:2:4	% Cft	19,887 / 00
	TOTAL QUANTITY:	160.00	Cft	337 / 0	P. Cft.	53,920 / 00
3	Providing and laying brick masonry in ratio 1:4 with pacca finishing etc complete. The cost is also i/c all carriage, too and fixing the cost is also i/c the cost of all labour, cart directed by the Engineer	ols and plant	at any floc s used in	making		
	TOTAL QUANTITY:	320.00	Cft	240 / 10	P. Cft.	76,832 / 00
4	Applying cement plaster 1:4 upto any height /floor 3/4" thick i/c the cost of all labour,cartage,material etc complete as dir			st is also		
	TOTAL QUANTITY:	1,280.00	Sft	3015 / 76	% Sft	38,602 / 00
5	Providing and fixing G.I frames /Choukhats of size 7" x 2" of gauge G.I sheet I/c welded hinges and fixing at site with no cement sand slurry of ratio 1:6 and repairing the jambs. tools and plants used in making and fixing.(S.I.N.29/P-93)	ecessary ho	' for door uld fasts, fil	ling with		
	TOTAL QUANTITY:	136.00	Cft	228 / 90	P. Cft.	31,130 / 00
6	Providing and fixing in position, Doors, Windows and Vewood frames, and 1½" thick commercial, ply veneer skeleton (H ollow) and commercial ply wood (3 ply frame)(S.I.N.58/P-65)-(S.I.N.25-b/P-61).(1077/06-370/83=7	shutters of	first class	deodar		
	TOTAL QUANTITY:	168.00	Sft	706 / 23	P Sft	118,647 / 00
	TOTAL WOARTITT.	100.00	11301713	TAL OF CIVIL		339,018 / 00
(B)	CIVIL WORKS (Non Schedule Items)					
1	Preparing the surface and painting with mat finish paint of scrapping the old surface, applying sandpaper filling with applying matt finish paint 2 coats as directed by Engineer In	loppy and IC				
	TOTAL QUANTITY:	7,098.00	Sft		P.Sft.	
2	Preparing the surface and painting with enmal paint of a scrapping the old surface, applying sandpaper filling with applying enamal paint 2 coats as directed by Engineer Inch	pproved qualiformal loppy and lo	ality and ,			
	TOTAL QUANTITY:	1,152.00	Sft		P.Sft.	

S. **AMOUNT DESCRIPTION OF ITEMS** RATE UNIT QUANTITY No. Providing & Fixing wooden cabinet with shutter of "Lasani sheet" 3/4" thick and frame work of 1" class partal wood 2"x1" pasted with classic "Formica" 18" deep in/c necessary hinges, catchers, handles, sliding wheels in doors, nails, screws etc with approved design and shape. The cost also in/c necessary tools and plants to be used in making etc complete as directed by the Engineer Incharge. TOTAL QUANTITY: 154.00 Sft P.Sft. TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS): (C) WATER SUPPLY AND SANITARY FITTINGS (Schedule Items) Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & I/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Foreign or Equivalent).(S.I.N. 10/P-3) TOTAL QUANTITY: 10.00 Nos 4928 / 70 Each 49.287 / 00 Supplying / Fixing wash basen mixture of superir quality with C.P, head 1/2" dia. (S.I.N.14(a)/P-19 TOTAL QUANTITY: 10.00 Nos 3179 / 0 Each 31,790 / 00 TOTAL AMOUNT OF PLUMBING WORK (SCHEDULE ITEMS): 81,077 / 00

# GRAND TOTAL OF BID(A+B+C):

#### TERMS & CONDITIONS.

- The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER
SINDH HOUSE ISLAMABAD

# AME OF WORK =: $\frac{M/R}{SINGLE} = \frac{OLD}{SINGLE} = \frac{OLD}{SINGLE} = \frac{OLDNY}{SINGLE} = \frac{$

	COTILEDO				
S. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)				
1	Cement concrete brick or stone ballast 1½" to 2" gauge 1:4:8 i/c the cost of all labour, cartage, material etc complete as				
2	TOTAL QUANTITY:  Re-inforcement concrete work at any floor work including al the cost of steel reinfotcement and its labour for bending ar separately this rate also includes all kinds of forms, moulds lif finishing the exposed surface (including screening and wash the cost is also i/c the cost of all labour, cartage, material etc.	II labour and nd binding whating shuttering shuttering of shingle	nich will be paid g rendering and e) (i) Ratio 1:2:4	% Cft	19,887 / 00
	Engineer In-charge	complete as	directed by the		
3	TOTAL QUANTITY: Providing and laying brick masonry in ratio 1:4 with pacca be finishing etc complete. The cost is also i/c all carriage, tools and fixing the cost is also i/c the cost of all labour, cartage directed by the Engineer	orick work at a	used in making	P. Cft.	53,920 / 00
4	TOTAL QUANTITY: Applying cement plaster 1:4 upto any height /floor 3/4" thick a i/c the cost of all labour,cartage,material etc complete as direct	at the hilly site		P. Cft.	76,832 / 00
5	Providing and fixing G.I frames /Choukhats of size 7" x 2" or gauge G.I sheet I/c welded hinges and fixing at site with necement sand slurry of ratio 1:6 and repairing the jambs. The tools and plants used in making and fixing.(S.I.N.29/P-93)	4 1/2" x 3" fo	fasts, filling with	% Sft	38,602 / 00
6	Providing and fixing in position, Doors, Windows and Ven wood frames, and 1½" thick commercial , ply veneer sh skeleton (H ollow ) and commercial ply wood (3 ply frame)(S.I.N.58/P-65)-(S.I.N.25-b/P-61).(1077/06-370/83=706	tilators of firs nutters of firs ) on both	t class deodar	P. Cft.	31,130 / 00
	TOTAL QUANTITY:		Sft 706 / 23 SUB TOTAL OF CIVIL V		118,647 / 00 339,018 / 00
(B)	CIVIL WORKS (Non Schedule Items) Preparing the surface and painting with mat finish paint of apscrapping the old surface, applying sandpaper filling with lo	ppy and ICI			
	applying matt finish paint 2 coats as directed by Engineer Incl	harge.			
	TOTAL QUANTITY:	7,098.00	Sft	P.Sft.	
2	Preparing the surface and painting with enmal paint of app scrapping the old surface, applying sandpaper filling with lo applying enamal paint 2 coats as directed by Engineer Incha	ppy and ICI			
	TOTAL QUANTITY:	1,152.00	Sft	P.Sft.	

S. **AMOUNT DESCRIPTION OF ITEMS** QUANTITY RATE UNIT No Providing & Fixing wooden cabinet with shutter of "Lasani sheet" 3/4" thick and frame work of 1" class partal wood 2"x1" pasted with classic "Formica" 18" deep in/c necessary hinges, catchers, handles, sliding wheels in doors, nails, screws etc with approved design and shape. The cost also in/c necessary tools and plants to be used in making etc complete as directed by the Engineer Incharge. TOTAL QUANTITY: 154.00 Sft P.Sft. TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS): (C) WATER SUPPLY AND SANITARY FITTINGS (Schedule Items) Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & I/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Foreign or Equivalent).(S.I.N. 10/P-3) TOTAL QUANTITY: 10.00 Nos 4928 / 70 Each 49.287 / 00 Supplying / Fixing wash basen mixture of superir quality with C.P, head 1/2" dia. (S.I.N.14(a)/P-19 TOTAL QUANTITY: 31,790 / 00 10.00 Nos 3179 / 0 Each TOTAL AMOUNT OF PLUMBING WORK (SCHEDULE ITEMS): 81.077 / 00

# GRAND TOTAL OF BID(A+B+C):

#### TERMS & CONDITIONS.

- The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER
SINDH HOUSE ISLAMABAD

# NAME OF WORK => M/R TO SINDH HOUSE ISLAMABAD (OLD COLONY (ELECTRICAL WORKS

# SCHEDULE 'B'

S. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
	ELECTRICAL WORKS (NonSchedul Items)				
1	Wiring of light of fan point with 1/1.13mm (3/0.029) PVC ins 20mm (3/4") PVC conduit recessed in wall or column as reclabour cartage material etc complete as approved by the Engi	quired, the cost is also			
	TOTAL QUANTIT	Y: 340.00	No	P.Point	
2	Providing and fixing A.C one way S.P 5AMP switch fuse type recessed in wall or column and covered with fiber sheet, the cartage material etc complete as approved by the Engineer In	he cost is also i/c the			
	TOTAL QUANTIT	Y: 68.00	No	Each	
3	Providing and fixing Ceiling fan regulator (imported or equila column and covered with, the cost is also i/c the cost of all approved by the Engineer In-Charge.			2	
	TOTAL QUANTIT	Y: 34.00	No	Each	
4	Providing and fixing 1-40 watts tube light complete with 40 was with Philips componenta including necessary electric connect cost of all labour cartage material etc complete as approved by	tion and fixing on, the	cost is also i/c the		1
	TOTAL QUANTIT	Y: 68.00	Rft	Each	
5	Wiring for mains with 2-7/.029 wire (Pakistan cable or equal surface as required, the cost is also i/c the cost of all labour caby the Engineer In-Charge.				
	TOTAL QUANTIT	Y: 816.00	No	P.Rft	
6	Supplying of A.C ceiling fan 56" sweep (Pak or Millat), the comaterial etc complete as approved by the Engineer In-Charge		f all labour cartage		
	TOTAL QUANTIT	Y: 34.00	No	Each	
7	Providing and fixing A.C two 3-pin 15 Amp S.P plug socket sw on metal board recessed in wall or column and covered with p all labour cartage material etc complete as approved by the E	plastic sheet, the cost is			
	TOTAL QUANTIT	Y: 68.00	No	Each	
	Providing and fixing wall bracket light fancy type superior				
8	connection and fixing on wall or ceiling etc complete,the cos material etc complete as approved by the Engineer In-Charge		f all labour cartage		
	TOTAL QUANTIT	Y: 102.00	No	Each	
9	Providing and fixing exhaust fan 12" size (Pak or Millat) m causing and making necessary electric connection,the cost material etc complete as approved by the Engineer In-Charge	is also i/c the cost of			
	TOTAL QUANTIT	ry: 68.00	No	Each	
		_		TOTAL:-	

## TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

# NAME OF WORK => SINGLE ROOM QTRS. 1,2,3,4,5,6 AT STAFF COLONY UNDER POLICE BARRACK SINDH HOUSE ISLAMABAD.

S. No.	DESCRIPTION OF ITEMS QUANTITY RATE UNIT AMOUN	Т
(A)		
	Applying cement plaster 1:4 upto any height /floor 3/4" thick at the hilly site the cost is also i/c the	
1	cost of all labour,cartage,material etc complete as directed by the Engineer	
	TOTAL QUANTITY: 576.00 Sft 3015 / 76 % Sft 17,371	/ 00
2	Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry	
	TOTAL QUANTITY: 102.00 Cft 228 / 90 P. Cft. 23,348	/ 00
3	Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage, tools and plants used in making and fixing.(S.I.N.29/P-93)	
	TOTAL QUANTITY: 126.00 Sft 706 / 23 P.Sft. 88,985	/ 00
	SUB TOTAL OF CIVIL WORK : 129,704	
B)	CIVIL WORKS (Non Schedule Items)	
2	Providing and laying above 6" thick C. C. 1:3:6 solid Block masorany set in 1:6 cement mortar in any floor including raking out joints & curing etc complete with all labour, material scaffolding if	
1	neccassory or as directed by Engineer In charge.(N.S.I)	
	P/L bath room tiles glazed or matt, make having size 12"x18"/12"x12"/8"x12"/8"x12"/8"x8"	
2	Master/Shabbir/Sonex/Karam or equilent jointed with white cement and laid over 1:2 gray cement sand mortor 3/4" thick finishing and filling of joints with sullary of white cement or tile grouted in desired shapes i/c cutting of tile to proper profile.	
	TOTAL QUANTITY: 375.00 Sft P.Sft.	
3	Preparing the surface and painting with enmal paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying enamal paint 2 coats as directed by Engineer Incharge.	
	TOTAL QUANTITY: 756.00 Sft P.Sft.	
	Providing and fixing best quality granite tile 24"x24"/ 20"x20"/16"x16" or in required size, best	
4	quality (Imported) or equivalent quality of approved shade, design & pattern fixing in proper grads, level & alignment with dry bond and cement mortar i/c grouting and finishing etc complete i/c the cost of all material, wastage, labour & cartage as directed by the engineer In-charge.	
	TOTAL QUANTITY: 804.00 Sft P.Sft.	
	TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS):	
(C)	WATER SUPPLY AND SANITARY FITTINGS (Schedule Items)	
,	Providing and fixing English commode couple set i/c all necessary fittings (imported	
1	brand/equilant), the cost is also i/c the cost of all labour, cartage, material etc complete as directed by the Engineer In-Charge.	
	TOTAL QUANTITY: 3.00 Nos 15000 / 0 Each 45,000	/ 00
	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & I/c the cost	
	of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia	
2	malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of	
2	malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4	
2	malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Foreign or Equivalent).(S.I.N. 10/P-3)  TOTAL QUANTITY: 3.00 Nos 4928 / 0 Each 14,784	

S. No.	DESCRIPTION OF ITEI	MS	QUANTITY	RATE	UNIT	AMOUNT
3	Providing & fixing steel sinks stainless to 6 inches built in wall, 1-1/2" c.p bubber with 1-1/2" P.V.C. waste pipe & making connection & making good in cement co make (Standard Pattern.)(S.I.N. 19-a/P-6	plug chrome plated bras requisite number of hole ncrete 1 : 2: 4.(a) Steel si	ss chain, 1-1/2" s in wall & plin	c.p brass waste, th & floor for pipe		
4	Supplying / Fixing wash basen mixture of	TOTAL QUANTITY: f superir quality with C.P,	3.00 head 1/2" dia. (		/ 30 Each	15,157 / 00
5	(b) S/F long bib-cock of C.P head with 1/	<b>TOTAL QUANTITY:</b> 2" dia. (S.I.N. 13-a/P-19)	3.00	No 3179	/ 0 Each	9,537 / 00
6	Supplying & fixing sink mixture cock of S	TOTAL QUANTITY: uperior quality with c.p he	3.00 ad etc complete		/ 46 Each	3,328 / 00
		TOTAL QUANTITY:	3.00		/ 60 Each	8,237 / 00
		TOTAL AMOU	JNT OF PLUMB	ING WORK (SCHEE	DULE ITEMS):	96,043 / 00
(D)	WATER SUPPLY AND SANITARY F	ITTINGS. (Non Sched	lule Items)			
1	Providing & fixing "PAK ARAB" UPVC pi the cost of all labour, cartage, material					
		TOTAL QUANTITY:	102.00	Rft	P.Rft	
2	Providing & fixing "PAK ARAB" UPVC pithe cost of all labour, cartage, material					-1
		TOTAL QUANTITY:	60.00	Rft	P.Rft	
3	Providing and fixing fancy shower mixer Nos. stop cocks, shower rod and showe cartage, material etc complete as direct	r etc complete , the cost	is also i/c the			
		TOTAL QUANTITY:	3.00_		Each	
		TOTA	L FOR ESTIMA	TE (D). (Non Sch	edule Items)	
(E)	ELECTRICAL WORKS (NonSch	edul Items)				
1	Wiring of light of fan point with 1/1.13mi in 20mm (3/4") PVC conduit recessed in all labour cartage material etc complete	m (3/0.029) PVC insulate wall or column as require	ed, the cost is	and comment of the solution of the contract of		
		TOTAL QUANTITY:	48.00_	No	P.point	
2	Providing and fixing A.C one way S.P.s board recessed in wall or column and clabour cartage material etc complete as	covered with fiber sheet,	the cost is also			
		TOTAL QUANTITY:	12.00_	No	Each	
3	Providing and fixing Ceiling fan regulato or column and covered with, the cost is as approved by the Engineer In-Charge.	also i/c the cost of all labo				
		TOTAL QUANTITY:	6.00_	No	Each	
4	Providing and fixing 1-40 watts tube light putty with Philips componenta including also i/c the cost of all labour cartage Charge.	necessary electric conn	ection and fixing	ng on, the cost is		
		TOTAL QUANTITY:	12.00_	No	Each	
5	Wiring for mains with 2-7/.029 wire (Pa surface as required, the cost is also i/o approved by the Engineer In-Charge.					
		TOTAL QUANTITY:	240.00	No	P.Rft	
6	Supplying of A.C ceiling fan 56" sweep cartage material etc complete as approv			cost of all labour		
		TOTAL QUANTITY:	6.00	No	Each	

S. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
7	Providing and fixing mild steel bar fan clamp 15.8mm (5/8"dia) suitable for R.C.C roof, the cost is also i/c the cost of all labour cartage material etc complete as approved by the Engineer In-Charge.				
	TOTAL QUANTITY	': 6.00 <sub>_</sub>	No	Each	
. 8	Providing and fixing wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete, the cost is also i/c the cost of all labour cartage material etc complete as approved by the Engineer In-Charge.				
	TOTAL QUANTITY	r: 18.00_	No	Each	
9	Providing and fixing exhaust fan 12" size (Pak or Millat) metal body cutting hole in wall plastering causing and making necessary electric connection, the cost is also i/c the cost of all labour cartage material etc complete as approved by the Engineer In-Charge.				
	TOTAL QUANTITY	r: 9.00	No	Each	
	TOTAL FOR ESTIMATE (E). (Non Schedule Items)				

# GRAND TOTAL OF BID (A+B+C+D+E):

### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

### NAME OF WORK => M/R TO SINDH HOUSE ISLAMABAD (REPAIR WORK OF MASJID BAB UL ISLAM)

#### SCHEDULE 'B'

S. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
1	Providing and laying prayer mates woolen make, approve i/c the cost of material, labour and cartage etc complete.	ed quality, standar	d size, the rate		
	TOTAL QUANTITY:	150.00 N	0	Each	
2	Providing & fixing double bibcock with necessary fitting complete.	g, approved design	gn & color etc		
	TOTAL QUANTITY:	15.00 N	0	Each	
3	Providing and fixing gas geysers 55 gallon approved ma dia gate valve 1" dia G.I. pie 1" dia 20.0 Rft. Making conne				
	TOTAL QUANTITY:	1.00 N	0	Each	
4	Distempering tow coats i/c scraping & painting with app material, labour & cartage etc complete.				
	TOTAL QUANTITY:	2,100.00 S	ft	P.Sft	
	_			Total:-	

#### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

RESIDENT ENGINEER
SPECIAL PROJECT
SINDH HOUSE ISLAMABAD

### NAME OF WORK => M&R TO SINDH HOUSE ISLAMABAD.(OLD POLICE BARRACK ROOMS 1,2,3,4,5,6)

### SCHEDULE 'B'

	SCHEDOLL D				
S. No.	DESCRIPTION OF ITEMS QU	JANTITY	RATE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)				
	Applying cement plaster 1:4 upto any height /floor 3/4" thick at the hilly s	site the cost is	s also i/c		
1	the cost of all labour, cartage, material etc complete as directed by the E	ngineer			
	TOTAL QUANTITY: 33	0.00 Sft	3015 / 76	% Sft	9,952 / 00
	Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x			70 011	0,002 7 00
	gauge G.I sheet I/c welded hinges and fixing at site with necessary				
2	cement sand slurry of ratio 1:6 and repairing the jambs. The cost also				
	and plants used in making and fixing.(S.I.N.29/P-93)				
		9.00 Rft.	228 / 90	P.Rft.	22,661 / 00
	Providing and fixing in position, Doors, Windows and Ventilators of fir				
3	frames, and 1½" thick commercial, ply veneer shutters of first class				
0	ollow ) and commercial ply wood (3 ply ) on both sides.(With out f (S.I.N.25-b/P-61).(1077/06-370/83=706/23)	rame)(S.i.iv.S	00/F-05)-		
	The Management of the Transferred				
		5.00 Sft	706 / 23	P. Sft.	74,154 / 00
	First class deodar wood wrought, joinery in doors and windows a including chowkats hold fasts hinges, iron tower bolts, chocks cleats, ha				
4	hooks, etc.Deodar panelled or panelled and glazed, or fully glazed.(b)				
	frame)(S.I.N.7-b/P-58)-(S.I.N.25-b/P-61)				
	TOTAL QUANTITY: 1	4.00 Sft	902 / 93	P.Sft.	12,641 / 00
5	(a) Fixing door including chowkhats (S.I No: 44-a Page-63)				
	TOTAL QUANTITY: 1	0.00 Each	279 / 51	Each	2,795 / 00
6	(a) Fixing windows including chowkhats (S.I No: 44-b Page-63)				
	TOTAL QUANTITY:	4.00 Each	139 / 76	Each	559 / 00
		SUB TO	TAL OF CIVIL	WORK :	122,762 / 00
(B)	CIVIL WORKS (Non Schedule Items)				
(6)	Providing and laying brick masonry in ratio 1:4 with pacca brick wor	rk at any floo	or curing		
1	finishing etc complete. The cost is also i/c all carriage, tools and plants				
	fixing the cost is also i/c the cost of all labour, cartage, material etc cor	mplete as dir	ected by		
	the Engineer TOTAL QUANTITY: 1	E 7E C#		P. Cft.	
	P/L bath room tiles glazed or matt, make having size 12"x18"	<b>5.75 Cft</b>  //12"x12"/8"x1	12"/8"x8"	r. Cit.	
	Master/Shabbir/Sonex/Karam or equilent jointed with white cement a				
2	cement sand mortor 3/4" thick finishing and filling of joints with sullary of	of white ceme	ent or tile		
	grouted in desired shapes i/c cutting of tile to proper profile.				
	TOTAL QUANTITY: 69	6.63 Sft		P.Sft.	
	TOTAL AMOUNT OF CIV		ON SCHEDULE		
			JA GOTTEDULE	, LIVIO).	
(C)	WATER SUPPLY AND SANITARY FITTINGS (Schedule It		- la		
	Providing and fixing squating type white glazed earthen were w.e pan v				
	of flushing cistern with internal fitting and flush Pipe with bend & makin holes in walls plinth & floor for pipe connections & making good in cen				
1	W.C of not less than 19" clear opening between flushing rims and 3 g				
	with 4" dia C.I trap and C.I thumble. (ii) with 4" dia earthen				
	thumble.(S.I.N.1-a-ii/P-1)				
	TOTAL QUANTITY:	2 Nos	5088 / 20	Each	10,176 / 00

S. No.	DESCRIPTION OF ITEMS	3	QUANT	ITY	RATE	UNIT	AMOUNT
2	Providing & fixing 24" x 18" lavatory basin in the cost of W.I or C.I cantilever brackets 6 in after a primary coat of red lead paint, a pair chain 1-1/4" dia malloable iron or c.P brass to requisite number of holes in walls, plinth & cement concrete 1: 2: 4 (Foreign or Equivalent)	nches built into wall, p of 1/2" dia rubber p aps malloable iron or floor for pipe connec	painted who ug & chro brass uni	nite in to ome pla ons an	wo coast ate brass d making		
3	Add extra for labour for providing & fixing of e (Foreign or Equivalent) (S.I.N. 9/P-3)	TOTAL QUANTITY: earthen ware pedesta		Nos coloure	4928 / 7 ed glazed	0 Each	9,857 / 00
4	Providing & fixing 6" x 2" or 6" x 3" C.I floor tra C.I scrrewed down gratting with or without a number of holes in walls, plinth & floor for Pipe 1: 2:4 (S.I.N. 20/P-6)	vent arm complete w	elf cleaning	naking	gn with a requisite	7 Each	1,877 / 00
5	Providing & fixing steel sinks stainless local brackets 6 inches built in wall, 1-1/2" c.p bub brass waste, with 1-1/2" P.V.C. waste pipe plinth & floor for pipe connection & making g stainless sized 40" x 20" local make (Standard	ber plug chrome plate & making requisite n good in cement concr	cast iron ed brass oumber of ete 1 : 2:	chain, 1 holes	1-1/2" c.p in wall &	3 Each	12,255 / 00
6	Supplying / Fixing wash basen mixture of (S.I.N.14(a)/P-19	TOTAL QUANTITY: of superir quality w		<b>No</b> head	5052 / 3 1/2" dia.	0 Each	20,209 / 00
7	Concealed C.P. fittings of superior quality for of superir quality with C.P. head 1/2" dia.(S.I.N	TOTAL QUANTITY: tiles Bath Rooms. (b) N. 11-b/P-18)		No ealed	3179 / 0 stop cock	Each	6,358 / 00
8	(b) S/F long bib-cock of C.P head with 1/2" dia	TOTAL QUANTITY: a. (S.I.N. 13-a/P-19)	10	No	509 / 7	4 Each	5,097 / 00
9	Providing and fixing in position nyloon conne with pair of brass nuts and lining joints to nyloon		1/2" dia,	No brass s	1109 / 4 stop cock	6 Each	6,657 / 00
10	Providing and fixing C.P brass shower rose (superior quality) (S.I.N. 3-ii-b/P-16)	TOTAL QUANTITY: e with or 3/3" inlet (v		Nos. hable	447 / 1 lid)6" dia	5 Each	2,683 / 00
11	Supplying & fixing sink mixture cock of Supe	TOTAL QUANTITY: rior quality with c.p h		Nos omplet		8 Each	342 / 00
		TOTAL QUANTITY: TOTAL AMOUNT OF		No IG WOR	2745 / 6 RK (SCHEDUL		5,491 / 00 <b>81,002</b> / 00
(D) 1	WATER SUPPLY AND SANITARY FITTII Providing & fixing "PAK ARAB" P.P.R. Pipe tea, elbow, socket, clamp, union, etc as rec proof cutting of well up to 1" thick deep fillin curing etc, this rate i/c all charges of labor Engineer in charge.	of approved quality quired jointed with so ng / cement plasterin	/c all rela lution / pe g as requ	ted fitti est to m ired &	nake leak finishing		
(a)	1/2" dia	TOTAL QUANTITY:	30.00	Rft		P.Rft	
(b)	3/4" dia	TOTAL QUANTITY:	30.00	Rft		P.Rft	
(c)	1" dia	TOTAL QUANTITY:	18.00	Rft		P.Rft	
2	Providing & fixing gate valve suitable for "PA make approved quality & design the cost is a etc complete as directed by the engineer in-ch	also i/c the cost of al	best qual	ity or e			

S. No.	DESCRIPTION OF IT	rems	QUANT	ITY	RATE	UNIT	AMOUNT
(a)	1/2" dia	TOTAL QUANTITY:	3	Nos		Each	
(b)	3/4" dia	TOTAL QUANTITY:	2	Nos	***************************************	Each	
(c)	1" dia	TOTAL QUANTITY:	2	Nos		Each	
3	Providing & fixing "PAK ARAB" UPVC palso i/c the cost of all labour, cartage, n charge.	naterial etc complete as c	directed by	the eng			
	Providing & fixing "PAK ARAB" UPVC	TOTAL QUANTITY:	25.00	Rft	cost is	P.rft	
4	also i/c the cost of all labour, cartage, r charge.						
		TOTAL QUANTITY:	30.00	Rft		P.rft	100 IC 10 IC
5	Providing & fixing "PAK ARAB" UPVC fit all labour, cartage, material etc complete				cost of		
(a)	4" dia	Elbow	4	Nos.	- 2-9	Each	
(b)		Tee	4	Nos.		Each	
(c)		Plug Elbow	6	Nos.		Each	
(d)		Plug Tee	6	Nos.		Each	
(e)	3" dia	Elbow	4	Nos.		Each	
(f)		Tee	4	Nos.		Each	
(g)		Plug Elbow	6	Nos.		Each	
(h)		Plug Tee	6	Nos.		Each	
6	Providing and fixing fancy shower m consisting of 2 Nos. stop cocks, showe the cost of all labour, cartage, material	r rod and shower etc com	uivalent) plete , the	(plastic e cost is	also i/c		
		TOTAL QUANTITY:		Nos.		Each	
		TOTAL FOR	ESTIMAT	E (D). (N	on Schedu	le Items)	
		GRAND TO	TAL OF	<b>ESTIM</b>	ATE (A+B	+C+D):	

#### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.

5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

RESIDENT ENGINEER SPECIAL PROJECT SINDH HOUSE ISLAMABAD

#### \* NAME OF WORK => M/R TO SINDH HOUSE COLONY (M/R DHOBI GHATT)

#### SCHEDULE 'B'

S. No.	DESCRIPTION OF ITEMS		QUANTIT	Y RA	TE	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items)						
1	Applying cement plaster 1:4 upto any height /floor of all labour,cartage,material etc complete as direct				ost		
		TOTAL QUANTITY:	576.00	Sft 30	15 / 76	% Sft	17,371 / 00
2	Providing and fixing G.I frames /Choukhats of siz sheet I/c welded hinges and fixing at site with ne ratio 1:6 and repairing the jambs. The cost also in fixing.(S.I.N.29/P-93)	cessary hold fasts, filling	with cemer	nt sand slurry	of		
		TOTAL QUANTITY:	102.00	Rft. 2	28 / 90	P.Rft.	23,348 / 00
3	Providing and fixing in position, Doors, Windows and 1½" thick commercial, ply veneer shutters of ply wood (3 ply) on both sides.(With our ply wood)	first class deodar skeleto	n (H ollow )	and commerc	ial		
	370/83=706/23)		(0				
	- 1 1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	TOTAL QUANTITY:	126.00	V 1		P. Sft.	88,985 / 00

#### (B) CIVIL WORKS (Non Schedule Items)

Providing and laying above 6" thick C. C. 1:3:6 solid Block masorany set in 1:6 cement mortar in any floor including raking out joints & curing etc complete with all labour, material scaffolding if neccassory or as directed by Engineer In charge.(N.S.I)

P/L bath room tiles glazed or matt, make having size 12"x18"/12"x12"/8"x12"/8"x8"

Master/Shabbir/Sonex/Karam or equilent jointed with white cement and laid over 1:2 gray cement sand mortor 3/4" thick finishing and filling of joints with sullary of white cement or tile grouted in desired shapes i/c cutting of tile to proper profile.

TOTAL QUANTITY: 375.00 Sft P.Sft.

Preparing the surface and painting with weather coat I/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved

TOTAL QUANTITY: 1,689.00 Sft P.Sft.

Providing and fixing best quality granite tile 24"x24"/ 20"x20"/16"x16" or in required size, best quality (Imported) or equivalent quality of approved shade, design & pattern fixing in proper grads, level & alignment with dry bond and cement mortar i/c grouting and finishing etc complete i/c the cost of all material, wastage, labour & cartage as directed by the engineer In-charge.

TOTAL QUANTITY:

440.00 Sft

%Sft

TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE ITEMS):

### GRAND TOTAL OF BID (A+B):

#### TERMS & CONDITIONS.

- The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER
SINDH HOUSE ISLAMABAD

RESIDENT ENGINEER
SPECIAL PROJECT
SINDH HOUSE ISLAMABAD

### NAME OF WORK => MR TO SINDH HOUSE ISLAMABAD (R. E. HOUSE)

### SCHEDULE 'B'

S. No.	DESCRIPTION OF ITEMS QUANTITY RATE	UNIT	AMOUNT
	CIVIL WORKS (Schedule Items)		
1	Applying cement plaster 1:4 upto any height /floor 3/4" thick at the hilly site the cost is also i/c the cost of all labour,cartage,material etc complete as directed by the Engineer		
	TOTAL QUANTITY: 453.00 Sft 3015 / 76	% Sft	13,661 / 00
	TOTAL AMOUNT OF CIVIL WORK (SCHEDULE	ITEMS):	<b>13,661</b> / 00
(B)	CIVIL WORKS (Non Schedule Items)  Providing and fixing best quality granite tile 24"x24"/ 20"x20"/16"x16" or in required size, best quality (Imported) or equivalent quality of approved shade, design & pattern fixing in		
1	proper grads, level & alignment with dry bond and cement mortar i/c grouting and finishing etc complete i/c the cost of all material, wastage, labour & cartage as directed by the engineer In-charge.		
	TOTAL QUANTITY: 1357.55 Sft.	% Sft.	
2	Preparing the surface and painting with plastic emulsion paint of approved make I/c rubbing the surface with sand Paper, filling the voids with chalk / plaster of paris and then painting etc. complete. (Three coats)		
	TOTAL QUANTITY: 403.50 Sft	P.Sft.	
3	Preparing the surface and painting with enmal paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying enamal paint 2 coats as directed by Engineer Incharge.		
	TOTAL QUANTITY: 73.00 Sft	P.Sft.	
4	Preparing the surface and painting with weather coat I/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make.(Three coats)		
	TOTAL QUANTITY: 3,308.00 Sft	P.Sft.	
	Providing & Fixing wooden cabinet with only shutter of "Lasai sheet" 3/4" thick and frame		
5	work of 1" class partal wood 2"x1" pasted with classic "Formica" in/c necessary hinges, catchers, handles, sliding wheels in doors, nails, screws etc with approved design and shape. The cost also in/c necessary tools and plants to be used in making etc complete as		
	directed by the Engineer Incharge.  TOTAL QUANTITY: 168.00 Sft	P.Sft.	
	TOTAL AMOUNT OF CIVIL WORK (NON SCHEDULE		
(B)	WATER SUPPLY AND SANITARY FITTINGS (Schedule Items)		
	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & I/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass		
1	chain 1-1/4" dia malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Foreign or Equivalent).(S.I.N. 10/P-3)		
	TOTAL QUANTITY: 2 No. 4928 / 70	Each	9,857 / 00
2	Add extra for labour for providing & fixing of earthen ware pedestal white or coloured glazed (Foreign or Equivalent) (S.I.N. 9/P-3)		
3	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I scrrewed down gratting with or without a vent arm complete with & I/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement	Each	1,877 / 00
4	Supplying / Fixing wash basen mixture of superir quality with C.P., head 1/2" dia.	Each	4,085 / 00
	(S.I.N.14(a)/P-19 TOTAL QUANTITY: 2 No 3179 / 0	Each	6,358 / 00

S. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE	UNIT	AMOUNT
5	Concealed C.P. fittings of superior quality for tiles Bath Rooms. cock of superir quality with C.P. head 1/2" dia.(S.I.N. 11-b/P-18)	(b) S/ F canceale	ed stop		
6	TOTAL QUANTITY: (b) S/F long bib-cock of C.P head with 1/2" dia. (S.I.N. 13-a/P-19)	2 Nos.	509 / 74	Each	1,019 / 00
7	TOTAL QUANTITY: Providing and fixing in position nyloon connections complete with with pair of brass nuts and lining joints to nyloon connection. (S.I.N.		1109 / 46 p cock	Each	2,219 / 00
	TOTAL QUANTITY: TOTAL AMOUNT OF	2 Nos.	447 / 15 (SCHEDULE)	Each	894 / 00 26,309 / 00

#### (C) WATER SUPPLY AND SANITARY FITTINGS. (Non Schedule Items)

Providing & fixing "PAK ARAB" P.P.R. Pipe of approved quality i/c all related fittings i-e tea, elbow, socket, clamp, union, etc as required jointed with solution / pest to make leak proof cutting of well up to 1" thick deep filling / cement plastering as required & finishing

	curing etc , this rate i/c all charges	s of labour, material, cartage	, etc as directed by th	ne	
(a)	1/2" dia	TOTAL QUANTITY:	80.00 Rft	P.Rft	
(b)	3/4" dia	TOTAL QUANTITY:	80.00 Rft	P.Rft	
(C)	1" dia	TOTAL QUANTITY:	80.00 Rft	P.Rft	
2	Providing & fixing "PAK ARAB" UP also i/c the cost of all labour, cartage charge				
		TOTAL QUANTITY:	100.00 Rft	P.rft	
3	Providing & fixing "PAK ARAB" UPV also i/c the cost of all labour, cartage charge.				

TOTAL QUANTITY:

88.00 Rft TOTAL FOR ESTIMATE (C). (Non Schedule Items)

#### **GRAND TOTAL OF ESTIMATE (A+B+C):**

#### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD

SPECIAL PROJECT SINDH HOUSE ISLAMABAD

### NAME OF WORK =>

# M&R TO SINDH HOUSE ISLAMABD (REPAIRING WORK OF C-I & C-II STAFF QUARTER)

### SCHEDULE 'B'

	SCHEDULE B			
S. No.	DESCRIPTION OF ITEMS QUANTITY RAT	E	UNIT	AMOUNT
(A)	CIVIL WORKS (Schedule Items) Re-inforcement concrete work at any floor work including all labour and material except the cost of steel reinfotcement and its labour for bending and binding which will be paid separately this rate also includes all kinds of forms, moulds lifting shuttering rendering and finishing the exposed surface (including screening and washing of shingle) (i) Ratio 1:2:4 the cost is also i/c the cost of all labour, cartage, material etc complete as directed by the			
2	Fabrication of Mild Steel reinforcement at any floor for cement concrete(cost of cement concrete shall be paid saperately) Including cutting bending ,Binding and laying position making joints and fatening including cost of binding wire also including removal of rust from bars.(b) Using Tor bars, etc complete the cost is also i/c the cost of all labour, cartage,material etc complete as directed by the Engineer In-charge.	/ 0	P. Cft.	109,241 / 00
3	TOTAL QUANTITY: 24.51 Cwt 5001  Providing and laying brick masonry in ratio 1:4 with pacca brick work at any floor curing finishing etc complete. The cost is also i/c all carriage, tools and plants used in making and fixing the cost is also i/c the cost of all labour,cartage,material etc complete as directed by the Engineer	/ 70	P.Cwt	122,592 / 00
4		/ 10	P. Cft.	71,208 / 00
5	TOTAL QUANTITY: 1,062.38 Sft 3015 Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage , tools and plants used in making and fixing.(S.I.N.29/P-93)	/ 76	% Sft	32,039 / 00
6	TOTAL QUANTITY: 16.50 Rft. 228 Providing and fixing in position, Doors, Windows and Ventilators of first class deodar wood frames, and 1½" thick commercial , ply veneer shutters of first class deodar skeleton (H ollow ) and commercial ply wood (3 ply ) on both sides.(With out frame)(S.I.N.58/P-65)-(S.I.N.25-b/P-61).(1077/06-370/83=706/23)	/ 90	P.Rft.	3,777 / 00
7	TOTAL QUANTITY: 17.50 Sft 706 (a) Fixing door including chowkhats (S.I No: 44-a Page-63)	/ 23	P. Sft.	12,359 / 00
8	Providing and fixing Aluminum sheet on doors pasted with glue as per requirement.(S.I.N.61/P-66)	/ 51	Each	280 / 00
9	TOTAL QUANTITY: 60.00 Sft 63 Priming coat of chalk distemper.(S.I.N.23/P-54)		P.Sft.	3,826 / 00
10	TOTAL QUANTITY: 2,074.00 Sft 442 Distempering.(b) Two coats (S.I.N.24-b/P-54)	/ 75	% Sft	9,183 / 00
			% Sft	22,360 / 00
	TOTAL AMOUNT OF CIVIL WORK (SCHEI	DULE	ITEMS):	<b>386,865</b> / 00

S. No.	DESCRIPTION OF ITEMS QUANTITY RATE	UNIT	AMOUNT
(B)	CIVIL WORKS (Non Schedule Items)		
1	P/L bath room tiles glazed or matt, make having size 12"x18"/12"x12"/8"x12"/8"x8" Master/Shabbir/Sonex/Karam or equilent jointed with white cement and laid over 1:2 gray cement sand mortor 3/4" thick finishing and filling of joints with sullary of white cement or tile grouted in desired shapes i/c cutting of tile to proper profile.		
	TOTAL QUANTITY: 891.00 Sft	P.Sft.	
2	Preparing the surface and painting with mat finish paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying matt finish paint 2 coats as directed by Engineer Incharge.		
	TOTAL QUANTITY: 3,118.00 Sft	P.Sft.	
3	Preparing the surface and painting with enmal paint of approved quality and ,make i/c scrapping the old surface, applying sandpaper filling with loppy and ICI or equilant than applying enamal paint 2 coats as directed by Engineer Incharge.		± =
	TOTAL QUANTITY: 1,413.00 Sft	P.Sft.	
4	Preparing the surface and painting with weather coat I/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make.(Three coats)		
	TOTAL QUANTITY: 5,176.75 Sft	P.Sft.	
	TOTAL AMOUNT OF CIVIL WORK (NON SCHEDUL	E ITEMS):	

#### **GRAND TOTAL OF BID (A+B):**

#### TERMS & CONDITIONS.

- 1 The work will be carried out as per PWD specification.
- 2 No Premium shall be allowed on Non-Schedule Items.
- 3 No cartage shall be allowed on Non-Schedule Items.
- 4 Any Typographical error will referred to the composite Schedule of Rates enforced.
- 5 The deduction of Income Tax from the Contractor's Bill will be made as admissible under the rules.

CONTRACTOR

ASSISTANT ENGINEER SINDH HOUSE ISLAMABAD RESIDENT ENGINEER
SPECIAL PROJECT
SINDH HOUSE ISLAMABAD

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO DOUBLE ROOM FLAT / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (BLOCK A-1,2,3,4,5 & 6).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO DOUBLE ROOM FLAT / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (BLOCK B-1,2,3,4,5 & 6).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO DOUBLE ROOM FLAT / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (BLOCK C-1,2,3,4,5 & 6).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No.	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO DOUBLE ROOM FLAT / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (BLOCK D-1,2,3,4,5 & 6).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO SINDH HOUSE ISLAMABAD (BLOCK A,B,C & D (ELECTRICAL WORKS).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO OLD COLONY / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (SINGLE ROOM QTRS 1,2,3,4,5,6,7,8 & 9).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No.	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO OLD COLONY / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (SINGLE ROOM QTRS

10,11,12,13,14,15,16,17 & 18).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO OLD COLONY / LOUNGE OF STAFF COLONY AT SINDH

HOUSE ISLAMABAD. (SINGLE ROOM QTRS

19,20,21,22,23,24,25 & 26).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO OLD COLONY / LOUNGE OF STAFF COLONY AT SINDH

HOUSE ISLAMABAD. (SINGLE ROOM QTRS .

27,28,29,30,31,32,33 & 34).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

(ELECTRICAL WORKS).)	
Bidding Documents issued to: M/s	
Vide Pay Order/ Deposit Receipt /D.R. No	Dated
Amounting To Rs.	

Name of Work: M/R TO SINDH HOUSE ISLAMABAD (OLD COLONY

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work: M/R TO SINDH HOUSE ISLAMABAD (SINGLE ROOM QTRS. 1,2,3,4,5,6 AT STAFF COLONY UNDER POLICE BARRACK SINDH HOUSE ISLAMABAD).

Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work:	M/R TO SINDH HOUSE ISLAMABAD (MA	ASJID BAB UL ISLAM).
Bidding Documents is	ssued to: M/s	
Vide	Pay Order/ Deposit Receipt /D.R. No.	Dated
Amounting To Rs.		

### STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

M/R TO SINDH HOUSE ISLAMABAD (OLD POLICE BARRACK ROOMS 1,2,3,4,5,6). Bidding Documents issued to: M/s Vide Pay Order/ Deposit Receipt /D.R. No. Dated Amounting To Rs.

Name of Work:

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work:	M/R TO SI	NDH HOUSE ISLAMABAD (COL	ONY STAIR CASE).
Bidding Documents is	sued to :	M/s	
Vide	Pay Order/	Deposit Receipt /D.R. No.	Dated
Amounting To Rs.			

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work:	M/R TO SII	NDH HOUSE ISLAMABAD (M/R	DHOBI GHATT).
Bidding Documents is	sued to:	M/s	
Vide	Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.			

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of work:	M/R TO SIN	NDH HOUSE ISLAMABAD (M/R	R TO R.E. HOUSE)	
Bidding Documents is	sued to:	M/s		
Vide	Pay Order/	Deposit Receipt /D.R. No	Dated	
Amounting To Rs.				

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

Name of Work:	M/R TO SINDH HOUSE ISLAMABAD (M	/R TO C-1. C-2).
Bidding Documents is	ssued to: M/s	
Vide	Pay Order/ Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

(CATEGOR	RY VI FLATS).	
Bidding Documents issued to:	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

Name of Work: M/R TO SINDH HOUSE ISLAMABAD (COLONY STREET LIGHTS

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

SISIEM (C	CATEGORY VIFLAIS).	
Bidding Documents issued to :	M/s	
Vide Pay Order/	Deposit Receipt /D.R. No	Dated
Amounting To Rs.		

Name of Work: M/R TO SINDH HOUSE ISLAMABAD (COLONY DRAINAGE

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

Name of work: M/R TO SINDH HOUSE MURREE (LAWN LIV	GH1).	
Bidding Documents issued to: M/s		
Vide Pay Order/ Deposit Receipt /D.R. No.	Dated	
Amounting To Rs.		

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS (For Contracts Costing up to Rs 4.00 MILLION)

(SINGLE R	OOM QUARTER SIDE).		
Bidding Documents issued to:	M/s		
Vide Pay Order/	Deposit Receipt /D.R. No	Dated	
Amounting To Rs.			

Name of Work: M/R TO SINDH HOUSE ISLAMABAD (COLONY STREET LIGHTS

# STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 4.00 MILLION)

Name of Work:	M/R	TO	<b>SINDH</b>	HOUSE	<b>ISLAMABAD</b>	(COLONY	DRAINAGE
	SYST	EM	(SINGLE	ROOM (	QUARTER SIDE	E).	
Bidding Documents is	sued t	: o	M/s			Mestoes and a second	
Vide	Pay O	rder	/ Depos	it Recei	pt /D.R. No	Date	d
Amounting To Rs.							



ľ

### GOVERNMENT OF SINDH WORKS & SERVICES DEPARTMENT

Karnehi, dated the \$/4/2017

### CORRINGENDUM

No.F&A(W&S)3.0/91-2015: In partial modification of this department's Notification duted 18 ps 2015. With the approval of Competent Authority a Re-Constitution of Procurement committee with the following composition, in terms of Rule-07 of Sindh Public Procurement Rules-2010 (Amended 2013) in the Office of Resident Engineer, Special Project, Sindh House Islamabad, with the following composition:-

### Progurement Committees

1. Superintending Engineer, Provincial Buildings Circle, Karachi

Chairman

 Deputy Director (Tech.) PPP Unit, Finance Department.

Member

 Resident Engineer, Special Project. Islamabad.

Member

The Functions & Responsibilities of the Committee will be same as specified in Rules-7&8 of Sindh Public Procurement Rules-2010 (Amended 2013)

SECRETARY TO GOVT, OF SINDH

No. E&A(W&S)3-9/91-2015

Karachi, dated the 5/4/ 2017

A copy is forwarded for information to:-

01. The Accountant General, Sindh, Karachi.

02 The Managing Director, SPPRA, Karachi.

03. The Chief Engineer (Buildings), Hyderabad.

04. The Chairman / Members of the Committee.

05 The Deputy Director (Monitoring), PM&E Cell, W&SD.

06. P.S to Secretary, W&S Department.

07. Notification file.

SECTION OFFICER (GENERAL) FOR SECRETARY TO GOVT. OF SINDH

ulfleation like

### GORDANIAT OF SINDR WORKS & SELVICES DEPARTMENT

Kararia dana dan

### NOTIFICATION

No. 14 ANY 6-3 B-1971 CHAS With the approval of Competent Authorities and the the territory of the position in borns of Rule-31 of South Public Procuss and Police 2016 ment of the led in the Warts & Services Department for redressed in price was new securities of durantes, if any, arises between producing agency and building security presentation works, goods and services in the jurisdiction of Super. While give years remains the large Circle, Katachi and Hyderabad to

> CALL Engineer (Duttelings) Hyderabad

Choleman

Mr. Tarlouse Hassan 1475 The Architectoff mich Monther

Representative of Agricultury, General Modb.

Marchael

a process and preparabilities of the Committee Land in the policy and (6) Sindh Public Procurement holes 1010.

> AIJAZ AHMED MEMON SPORT WITH TO GOVE OF SIND

Karachi doted the November, 2.10

topy is increased and information to

The Accountant Ceneral, Elndh, Karaphil The Landing Olders, SPIRA, KNOWL The Over Tagines (Bullillings), Hyderabad.

The Secretary Secretary (1981) to Chief Secretary Shoot, Kitching

the Contract of the Committee

The Englanding Lagineer, Previncial Buildings Circle, Karley The Living Director (Monitoring), Physic Coll, W&S Department

The Forestee Engineer, Provincial Bolleings Divisional Lie He Control Crataries Special Project Stock Heise Managhed and Course one Swell Perform

in unappage The Committee, White Services Department, Consentration

They are Secount Officer, Shall British Blams and

SECTION OFFICER GENERAL

### **BIDDING DATA**

(a). Name of Procuring Agency :	RESIDENT ENGINEER, SPECIAL
(This section should be filled in by the Enthe Bidding Documents).	gineer/Procuring Agency before issuance of

(b). Brief Description of Works

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

M/R TO DOUBLE ROOM FLAT / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (BLOCK A-1,2,3,4,5 & 6).

(c). Procuring Agency's address

Sindh House, F-5/2, Islamabad

(d). Estimated Cost

Rs. 1,000,000/-

(e). Amount of Bid Security

2% (Rs.20,000/-)

(f).Period of Bid Validity (days)

90 days

(g).Security Deposit

10 (Ten) %

(h). Percentage, if any, to be deducted from bills:

8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

:

(j). Venue, Time, and Date of Bid Opening:

Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order of commence:

(2)Months

(1). Liquidity damages

10 (Ten) % of estimate

(m). Call Deposit Receipt No: (Rupees

Dated:

Amount: Rs.

RESIDENT ENGINEER SPECIAL PROJECT SINDH HOUSE ISLAMABAD

### **BIDDING DATA**

(This section should be filled in by the Bidding Documents).	the Engineer,	Procuring Agency before issuance of	of
(a). Name of Procuring Agency	•	RESIDENT ENGINEER, SPECIAL PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.	
(b). Brief Description of Works	•	M/R TO DOUBLE ROOM FLAT / LOUNG OF STAFF COLONY AT SINDH HO ISLAMABAD. (BLOCK B-1,2,3,4,5 & 6).	
(c).Procuring Agency's address		Sindh House, F-5/2, Islamabad	
(d). Estimated Cost	:	Rs. 1,000,000/-	
(e). Amount of Bid Security	:	2% (Rs.20,000/-)	
(f).Period of Bid Validity (days)	:	90 days	
(g).Security Deposit	:	10 (Ten) %	
(h). Percentage, if any, to be dec from bills:	lucted	8 (Eight) %	
(i). Deadline for Submission of E	ids along wit	h time: 04-6-2018 up to 10:00 A	M
(j). Venue, Time, and Date of Bio	d Opening:	Sindh House Islamabad 04-6-2018 11:00 A	AM.
(k). Time for Completion from w of commence:	ritten order	(2)Months	
(1). Liquidity damages	:	10 (Ten) % of estimate	

RESIDENT-ENGINEER SPECIAL PROJECT SINDH HOUSE ISLAMABAD

Amount: Rs.

### **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO DOUBLE ROOM FLAT / LOUNGE

OF STAFF COLONY AT SINDH HOUSE

ISLAMABAD. (BLOCK C-1,2,3,4,5 & 6).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 1,000,000/-

(e). Amount of Bid Security : 2% (Rs.20,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills:

from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order

of commence:

(2)Months

(1). Liquidity damages :

10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

RESIDENT ENGINEER
SPECIAL PROJECT
SINDH HOUSE ISLAMABAD

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO DOUBLE ROOM FLAT / LOUNGE

OF STAFF COLONY AT SINDH HOUSE

ISLAMABAD. (BLOCK D-1,2,3,4,5 & 6).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 1,000,000/-

(e). Amount of Bid Security : 2% (Rs.20,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad 04-6-2018 11:00 AM.

Dated:

(k). Time for Completion from written order of commence: (2)Months

:

(Rupees

(1). Liquidity damages

(m). Call Deposit Receipt No:

RESIDENT ENGINEER SPECIAL PROJECT SINDH HOUSE ISLAMABAD

Amount: Rs.

10 (Ten) % of estimate

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE ISLAMABAD

(BLOCK A,B,C& D (ELECTRICAL WORKS).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 1,000,000/-

(e). Amount of Bid Security : 2% (Rs.20,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018 11:00 AM.

(k). Time for Completion from written order of commence: (2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: \_\_\_\_\_ Dated: \_\_\_\_ Amount : Rs.\_\_\_\_ (Rupees

RESIDENT ENGINEER
SPECIAL PROJECT

SINDH HOUSE ISLAMABAD

(This section should be filled in by the Engineer/Procuring Agency before issuance of

the Bidding Documents).		
(a). Name of Procuring Agency	:	RESIDENT ENGINEER, SPECIAL PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.
(b). Brief Description of Works	:	M/R TO OLD COLONY / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (SINGLE ROOM QTRS 1,2,3,4,5,6,7,8 & 9).
(c).Procuring Agency's address	:	Sindh House, F-5/2, Islamabad
(d). Estimated Cost	:	Rs. 900,000/-
(e). Amount of Bid Security	:	2% (Rs.18,000/-)

(h). Percentage, if any, to be deducted from bills:

(f).Period of Bid Validity (days) :

8 (Eight) %

10 (Ten) %

90 days

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening:

Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order of commence:

(2)Months

(l). Liquidity damages

(g).Security Deposit

10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated: (Rupees

Amount: Rs.

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO OLD COLONY / LOUNGE OF

STAFF COLONY AT SINDH HOUSE ISLAMABAD. (SINGLE ROOM QTRS

10,11,12,13,14,15,16,17 & 18).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 900,000/-

(e). Amount of Bid Security : 2% (Rs. 18,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018 11:00 AM.

(k). Time for Completion from written order of commence: (2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO OLD COLONY / LOUNGE OF

STAFF COLONY AT SINDH HOUSE ISLAMABAD. (SINGLE ROOM QTRS

19,20,21,22,23,24,25 & 26).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 800,000/-

(e). Amount of Bid Security : 2% (Rs. 16,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted

from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018 11:00 AM.

(k). Time for Completion from written order of commence: (2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: \_\_\_\_\_\_Dated: \_\_\_\_\_ Amount : Rs.\_\_\_\_\_(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency :

RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works

M/R TO OLD COLONY / LOUNGE OF STAFF COLONY AT SINDH HOUSE ISLAMABAD. (SINGLE ROOM QTRS

27,28,29,30,31,32,33 & 34).

(c).Procuring Agency's address

Sindh House, F-5/2, Islamabad

(d). Estimated Cost

•

:

Rs. 800,000/-

(e). Amount of Bid Security

2% (Rs.16,000/-)

(f).Period of Bid Validity (days)

90 days

(g). Security Deposit

10 (Ten) %

(h). Percentage, if any, to be deducted

from bills:

8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

:

(j). Venue, Time, and Date of Bid Opening:

Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order

of commence:

(2)Months

(l). Liquidity damages

10 (Ten) % of estimate

(m). Call Deposit Receipt No:

Dated:

Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE ISLAMABAD

(OLD COLONY (ELECTRICAL WORKS)

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 1,000,000/-

(e). Amount of Bid Security : 2% (Rs.20,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order of commence: (2)

or commence.

(2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE ISLAMABAD

(SINGLE ROOM QTRS. 1,2,3,4,5,6 AT STAFF COLONY UNDER POLICE

BARRACK SINDH HOUSE

ISLAMABAD).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 1,000,000/-

(e). Amount of Bid Security : 2% (Rs.20,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted

from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018 11:00 AM.

(k). Time for Completion from written order

of commence: (2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE ISLAMABAD

(MASJID BAB UL ISLAM).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 500,000/-

(e). Amount of Bid Security : 2% (Rs.10,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills:

rom bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order of commence:

CHARLES AND CHARLES CHARLES AND CHARLES AN

(2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency RESIDENT ENGINEER, SPECIAL

> PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works M/R TO SINDH HOUSE ISLAMABAD

(OLD POLICE BARRACK ROOMS

1,2,3,4,5,6).

(c). Procuring Agency's address Sindh House, F-5/2, Islamabad

(d). Estimated Cost Rs. 500,000/-

(e). Amount of Bid Security 2% (Rs.10,000/-)

(f).Period of Bid Validity (days) 90 days

(g). Security Deposit 10 (Ten) %

(h). Percentage, if any, to be deducted from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order of commence: (2)Months

10 (Ten) % of estimate

(1). Liquidity damages

(m). Call Deposit Receipt No: (Rupees

Dated:

Amount: Rs.

RESIDENT ENGINEER SPECIAL PROJECT

SINDH HOUSE ISLAMABAD

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency RESIDENT ENGINEER, SPECIAL

> PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works M/R TO SINDH HOUSE ISLAMABAD

(COLONY STAIR CASE).

(c). Procuring Agency's address Sindh House, F-5/2, Islamabad

(d). Estimated Cost Rs. 700,000/-

(e). Amount of Bid Security 2% (Rs.14,000/-)

(f).Period of Bid Validity (days) 90 days

(g).Security Deposit 10 (Ten) %

(h). Percentage, if any, to be deducted from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

> 04-6-2018 11:00 AM.

(k). Time for Completion from written order of commence:

(2)Months

10 (Ten) % of estimate (1). Liquidity damages

Dated: (m). Call Deposit Receipt No: Amount: Rs.

(Rupees

RESIDENT ENGINEER SPECIAL PROJECT

SINDH HOUSE ISLAMABAD

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency RESIDENT ENGINEER, SPECIAL

> PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works M/R TO SINDH HOUSE ISLAMABAD

(M/R DHOBI GHATT).

(c). Procuring Agency's address Sindh House, F-5/2, Islamabad

(d). Estimated Cost Rs. 500,000/-

(e). Amount of Bid Security 2% (Rs.10,000/-) :

(f).Period of Bid Validity (days) 90 days

(g).Security Deposit 10 (Ten) %

(h). Percentage, if any, to be deducted from bills:

8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

> 04-6-2018 11:00 AM.

(k). Time for Completion from written order

of commence: (2)Months

10 (Ten) % of estimate (1). Liquidity damages :

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE ISLAMABAD

(M/R TO R.E. HOUSE).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 1,000,000/-

(e). Amount of Bid Security : 2% (Rs.20,000/-)

(f). Period of Bid Validity (days) : 90 days

(g).Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills:

rom bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018 11:00 AM.

(k). Time for Completion from written order of commence: (2)Months

of commence. (2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE ISLAMABAD

(M/R TO C-1. C-2).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 1,000,000/-

(e). Amount of Bid Security : 2% (Rs.20,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills:

from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018 11:00 AM.

(k). Time for Completion from written order of commence: (2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE ISLAMABAD

(COLONY STREET LIGHTS (CATEGORY VI FLATS).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 900,000/-

(e). Amount of Bid Security : 2% (Rs.18,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted

from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018 11:00 AM.

(k). Time for Completion from written order

of commence: (2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: \_\_\_\_\_Dated: \_\_\_\_ Amount : Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency RESIDENT ENGINEER, SPECIAL

> PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works M/R TO SINDH HOUSE ISLAMABAD

(COLONY DRAINAGE SYSTEM

(CATEGORY VI FLATS).

(c). Procuring Agency's address Sindh House, F-5/2, Islamabad

(d). Estimated Cost Rs. 1,000,000/-

(e). Amount of Bid Security 2% (Rs.20,000/-) :

(f).Period of Bid Validity (days) 90 days

(g).Security Deposit 10 (Ten) %

(h). Percentage, if any, to be deducted from bills:

8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order of commence:

(2)Months

10 (Ten) % of estimate (1). Liquidity damages

(m). Call Deposit Receipt No: Dated: Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE MURREE

(LAWN LIGHT).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 1,000,000/-

(e). Amount of Bid Security : 2% (Rs.20,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted from bills:

from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018 11:00 AM.

(k). Time for Completion from written order of commence: (2)Months

(1). Liquidity damages : 10 (Ten) % of estimate

(m). Call Deposit Receipt No: \_\_\_\_\_ Dated: \_\_\_\_ Amount : Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency : RESIDENT ENGINEER, SPECIAL

PROJECT, SINDH HOUSE ISLAMABAD/ MURREE.

(b). Brief Description of Works : M/R TO SINDH HOUSE ISLAMABAD

(COLONY STREET LIGHTS

(SINGLE ROOM QUARTER SIDE).

(c).Procuring Agency's address : Sindh House, F-5/2, Islamabad

(d). Estimated Cost : Rs. 900,000/-

(e). Amount of Bid Security : 2% (Rs.18,000/-)

(f).Period of Bid Validity (days) : 90 days

(g). Security Deposit : 10 (Ten) %

(h). Percentage, if any, to be deducted

from bills: 8 (Eight) %

(i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening:

Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order

of commence:

(2)Months

(l). Liquidity damages

10 (Ten) % of estimate

(m). Call Deposit Receipt No: Dated:

Amount: Rs.

(Rupees

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents). (a). Name of Procuring Agency RESIDENT ENGINEER, SPECIAL PROJECT, SINDH HOUSE ISLAMABAD/ MURREE. (b). Brief Description of Works M/R TO SINDH HOUSE ISLAMABAD (COLONY DRAINAGE SYSTEM (SINGLE ROOM QUARTER SIDE). (c).Procuring Agency's address Sindh House, F-5/2, Islamabad (d). Estimated Cost Rs. 1,000,000/-(e). Amount of Bid Security 2% (Rs.20,000/-) (f).Period of Bid Validity (days) 90 days (g). Security Deposit 10 (Ten) % (h). Percentage, if any, to be deducted From bills: 8 (Eight) % (i). Deadline for Submission of Bids along with time: 04-6-2018 up to 10:00 AM

(j). Venue, Time, and Date of Bid Opening: Sindh House Islamabad

04-6-2018

11:00 AM.

(k). Time for Completion from written order of commence: (2

or commence:

(2)Months

(1). Liquidity damages

10 (Ten) % of estimate

(m). Call Deposit Receipt No:

Dated:

Amount: Rs.

(Rupees