

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE MADEJI DISTRICT SHIKARPUR**

No: TC/ 215 /2018,

Madeji

Dated: 25/5 /2018

To,

The Assistant Director (Assessment)  
Sindh Public Procurement Regulatory Authority,  
Karachi

**SUBJECT: NIT NO.TC/208/2018 DATED 15.15.2018**

With Reference Letter No. A.D(A)/SPPRA/(TC Madeji)/2017-18/4096  
Karachi dated 22th May,2018, the para-wise comments/reply is mentioned as under.

- i. The Procuring Agency (PA) has clearly mentioned allocation of schemes are under OZT funds 2017-18.
- ii. The District Account Officer or his representative is not related to this CRC.
- iii. The procurement Committee and CRC are approved by the competent authority.
- iv. The Phone Number & Fax Number has mentioned in Bidding Data.
- v. The Date of Submission & Opening of Bid has been corrected.
- vi. Schedule-B alongwith NIT & Bidding Data are attached herewith.
- vii. Validity date of Bids as required Rule 38 has been mentioned.

Now you are requested to please host NIT on SPPRA website.



*[Signature]*  
**CHAIRMAN  
TOWN COMMITTEE  
MADEJI**

SPPRA INWARD DIARY  
NO : 944  
DATED : 29-5-2018  
C. P. O.

The Secretary Local Government Department Sindh Karachi.  
The Staff Officer to MD, SPPRA

*[Signature]*  
**CHAIRMAN  
TOWN COMMITTEE  
MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE MADEJI DISTRICT SHIKARPUR**

No: TC/ 214 /2018,

Madeji

Dated: 25 / 05 /2018

To,

The Director,  
Sindh Public Procurement Regulatory Authority,  
Karachi.

**SUBJECT: PUBLICATION OF NOTICE FOR INVITING TENDERS.**

Enclosed herewith a Hard copy & Soft Copy of NIT bearing No. TC/213/2018, dated: 25/ 05 /2018 duly signed alongwith following documents for hosting on SPPRA website.

- (a) Notice inviting Tender
- (b) Notification of Procurement Committee
- (c) Notification of Complaint Redressal Committee
- (d) Bidding Documents 01 Set
- (e) Annual Procurement Plan
- (f) Cheque No.23564100 Dated 25-05-2018 amounting Rs.2000/- in words (Two Thousand)



*[Handwritten Signature]*  
**CHAIRMAN  
TOWN COMMITTEE  
MADEJI**

**C.C to,**

- 1. The Director Local Government Department Larkana (Division)
- 2. The Assistant Director Local Fund Audit Shikarpur
- 3. P.S to Secretary LGD Karachi

*[Handwritten Signature]*  
**CHAIRMAN  
TOWN COMMITTEE  
MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE MADEJI DISTRICT SHIKARPUR**

No: TC/ 213 /2018,


Madeji,

dated: 25/5 /2018

**NOTICE FOR INVITING TENDER.**

Tenders in sealed covers are invited on Schedule Rate/Offer Rate Basis (Estimated Cost less then and within Rs: 10,00,000/-) for the following works/jobs from the interested Firm/Bidders, according to the SPPRA Rules-2010. Details given below:-

S. NO:	NAME OF WORK	ESTIMATED COST(Rs:)	Earnest Money 2%	Tender Fee Non refundable	TIME ALLOWED
1.	Construction of Paver Block New Shaikh Mohalla Madeji Alam Chowk to Haji Eiden House TC Madeji (Ward 1)	671993	2%	1000	06 Months
2.	Construction of Paver Block New Shaikh Mohalla Madeji From Aijaz Ali Shaikh House to Otaq Chowk TC Madeji (Ward 1)	996371	2%	1000	06 Months
3.	Construction of Paver Block New Shaikh Mohalla Madeji Masjid to Arbab Shaikh House & Haji Bashir Shaikh House to Sikandar House TC Madeji (Ward 1)	991686	2%	1000	06 Months
4.	Construction of Paver Block New Shaikh Mohalla Madeji From House of Sikandar Shaikh to House of Lal Bux & Miskeen Shaikh TC Madeji (Ward 1)	999276	2%	1000	06 Months
5.	Construction of Paver Block New Shaikh Mohalla Madeji From Otaq Chowk to Masjid TC Madeji (Ward 1)	988295	2%	1000	06 Months
6.	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Abbasi Mohalla Amanullah Channa House to Shaman Abbasi House T/C Madeji (Ward-2)	993654	2%	1000	06 Months
7.	Construction of Paver Block from Ali Murad Brohi Shop to Geo Hussani House & Gul Hassan House TC Madeji (Ward-2)	998550	2%	1000	06 Months
8.	Construction of Paver Block from Atif Panhwar Shop to Lashari House TC Madeji (Ward-2)	986449	2%	1000	06 Months
9.	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Gareebabad Mohalla Sadaruddin shop to Manzoor Marfani T/C Madeji (Ward-2)	983204	2%	1000	06 Months
10.	Construction of Paver Block from Ghulam Rasool House to Loung Shop TC Madeji (Ward-2)	669863	2%	1000	06 Months
11.	Construction Of Drains Type-I & I/C RCC Slabs, Ghulam Shabir Otaq to Mohammad Hashim Dayo House T/C Madeji (Ward-2)	867857	2%	1000	06 Months
12.	Construction of Paver Block from Shaman Abbasi House to Shakoore Mangi House TC Madeji (Ward-2)	989002	2%	1000	06 Months
13.	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Shaikh Mohalla to Ali Bux Mast from Khalid Soomro House to Gul Mir Otaq T/C Madeji (Ward-2)	992577	2%	1000	06 Months
14.	Construction of Paver Block Qamar Din Vegetable Shop to Riaz Qazi Saloon, Rajkumar to Badar din Jeho House T.C Madeji (Ward-2)	568036	2%	1000	06 Months
15.	Construction Of Drains Type-II & I/C RCC Slabs, From Shop of Sunil Kumar To Shah Nawaz Junejo House Dakhan-Madeji Road TC Madeji (Ward-3)	986491	2%	1000	06 Months
16.	Construction Of Drains Type-II & I/C RCC Slabs, From Shop of Mashook Ujan to Qadir Bux Dayo Main road TC Madeji (Ward-3)	994876	2%	1000	06 Months
17.	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Mirani Mohalla from House of Rehmatullah to Usman Mirani House T/C Madeji (Ward-3)	997800	2%	1000	06 Months
18.	Construction of Paver Block Shahi Bazar Raj Kumar Shop to Anwar Panhwar shop TC Madeji (Ward-3)	989362	2%	1000	06 Months
19.	Construction of Paver Block Shahi Bazar Sanjay Shop to Moti Masjid Chowk TC Madeji (Ward-3)	837666	2%	1000	06 Months
20.	Construction of Paver Block Shahi Bazar Ghumro Shop to Sanjay Shop TC Madeji (Ward-3)	973886	2%	1000	06 Months
21.	Construction of Paver Block Shahi Bazar Jahangir Shop to Raj Kumar Shop TC Madeji (Ward-3)	956507	2%	1000	06 Months
22.	Construction/Repair Of Drains Type-I & I/C RCC Slabs, Shahi Bazar Jhangir Shop to Anwar Ali Panhwar Shop, Ghumro Shop to Moti Masjid Chowk T/C Madeji (Ward-3)	906331	2%	1000	06 Months
23.	Construction of Paver Block Old post office Soomra Mohalla Masjid Chowk to Abdul Majeed House TC Madeji (Ward-4)	974599	2%	1000	06 Months
24.	Construction of Paver Block Old post office Soomra Mohalla from Abdul Rehman House Haji Lutufullah House TC Madeji (Ward-4)	994164	2%	1000	06 Months
25.	Construction Of Drains Type-I & I/C RCC Slabs, From House of Taqi Shah to Station Road T/C Madeji (Ward 5)	975756	2%	1000	06 Months
26.	Brick Pavement from Sunil kumar Shop to Shah Nawaz Junejo TC Madeji Ward-4	947371	2%	1000	06 Months
27.	Construction Of Retaining wall & Brick Pavement at main road to Servant Quarter TC Madeji (Ward 4)	645415	2%	1000	06 Months



28.	Construction Of Retaining wall at Ali Hyder Shah to Juneja Mohalla TC Madeji (Ward 5)	293479	2%	1000	06 Months
29.	Construction of Paver Block Ali Hyder Shah to Juneja Mohalla TC Madeji (Ward 5)	995245	2%	1000	06 Months
30.	Construction Of Drains Type-II & I/C RCC Slabs, From Civil Hospital to Sardar Himath Ali Khan Kamario Gate Main road TC Madeji (Ward 5)	955797	2%	1000	06 Months
31.	Construction Of Drains Type-I & I/C RCC Slabs, and Paver Block at Juneja Mohalla from House of Abdul Rasheed Junejo to Abdul Latif Junejo T/C Madeji (Ward 5)	994520	2%	1000	06 Months
32.	Construction of Paver Block & Earth filling Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to Rasool Bux Mirbahar TC Madeji (Ward 5)	786295	2%	1000	06 Months
33.	Construction of Paver Block Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to House of Shahnawaz Jeho to Saifal Kumbhar House TC Madeji (Ward 5)	973806	2%	1000	06 Months
34.	Construction of Paver Block Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to Rasool Bux Mirani House TC Madeji (Ward 5)	983615	2%	1000	06 Months
35.	Construction of Paver Block from Noral Mirani to House of Hazoor Bux Junejo to Kadan Junejo TC Madeji (Ward 5)	985887	2%	1000	06 Months
36.	Repair Of Drains Type-I & I/C RCC Slabs, and Repair of T-II Drain at Baab Himath Ali Khan Gate to Baab Saein Bodlo Shah T/C Madeji (Ward 5)	838706	2%	1000	06 Months
37.	Construction Of Drains Type-I & I/C RCC Slabs, Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine Saifal Kumbhar Ajeeb Jeho House T/C Madeji (Ward 5)	986680	2%	1000	06 Months

### TERMS & CONDITIONS:

1. Tenders schedule shall be as follows:-

SCHEDULE	DATE & TIME	VENUE
Receiving of Applications and Issuance of Tenders	Tender Documents will be issued from <b>28-05-2018 TO 12-06-2018</b> During the Office Hours	i). Office of the of Chairman Town committee Madeji ii). Bidding document can be downloaded from the SPPRA Website ( <a href="http://www.pprasinidh.gov.pk">www.pprasinidh.gov.pk</a> ).
Dropping of Tenders	<b>13-06-2018</b> at 12:00 pm	Office of the of Chairman Town committee Madeji.
Opening of Tenders	<b>13-06-2018</b> at 2:30 pm	Office of the of Chairman Town committee Madeji

- In case of any reasons, if the tenders are not responded on the above date, the next date of submission and opening of bids will be **28-06-2018** at 11:30 am and the tender documents will also be available from **28-05-2018** to **28.06.2018 at 2:00 pm**.
- The bidding documents will be issued to the interested Firms/Contractors on submission of written request on letter head and on payment of non-refundable cost of tender price mentioned against each work, through pay order from any scheduled Bank in favor of **Chairman Town Committee Madeji**, and bidding document can also be downloaded from the SPPRA Website ([www.pprasinidh.gov.pk](http://www.pprasinidh.gov.pk)) with tender fee mentioned as above by mail or by hand.
- The Earnest Money equal 2% of offered rates/amount of Open Rate items and Earnest Money of schedule items mentioned against each work in shape of pay order from any scheduled Bank in favour of **Chairman Town Committee Madeji** must be enclosed with tender documents, otherwise the tender will be rejected.
- The Contractors must mention their complete and correct present/postal address in tender documents and quote the rates both in-words and in-figures. Incomplete / Conditional tenders will be not accepted. In addition, the bidders must furnish the documentary evidence against each eligibility as well as minimum qualification criteria. Otherwise their tenders will be summarily rejected.
- If any fake documents are found then the tender is liable to be rejected/cancelled without any compensation with penalty as per rules.
- Canvassing in connection of tenders is strictly prohibited and tenders submitted by the contractors who are reported to be involved in canvassing will be liable for rejection.

*[Handwritten signature]*



8. All the tenders will be dropped on as per above Schedule upto 02:00 pm and will be opened by the Procurement Committee, TC Madeji, in the Office of the Chairman Town Committee Madeji at 02:30 pm in presence of the such Contractors/Parties/Firms/Bidders who wish to be present.
9. In case, the date of opening declared as a Public Holiday by the Government, or non-working day due to any reason, the next official working day shall be deemed to be the date for submission and opening of tenders at the same time.
10. The Authority of Town Committee Madeji may reject all or any bids/tenders at any time prior to the acceptance of a bid or proposal, subject to the relevant provision of SPPRA Rules-2010.
11. Tenders will not be received after the schedule time.
12. Eligibility Criteria:-
  - NTN
  - Registration with Sindh Revenue Board (SRB).
  - Minimum Three years' Experience of relevant field.
  - Turnover last three years



*(Signature)*  
**(NAJAF ALI KHAN KAMARIO)**  
**CHAIRMAN**  
**TOWN COMMITTEE**  
**MADEJI**

Copy to:-

The Managing Director, SPPRA, Government of Sindh, with the request for hoisting above mentioned NIT on the SPPRA Website.  
The Deputy Commissioner Shikarpur  
The Director Local Government Larkano Division  
The P.S to Secretary LGD Karachi  
The Assistant Director Local Fund Audit Shikarpur  
The Town Officer Town Committee Madeji  
The Assistant Executive Engineer Town Committee Madeji  
The Sub Engineer Town Committee Madeji  
The Accountant Town Committee Madeji  
Copy affixed/pasted on Office Notice Board.

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.01**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Detailed Estimate For Construction of Paver Block New Shaikh Mohalla Madeji Alam Chowk to Haji Eiden House TC Madeji (Ward 1)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 671993(+) O/R
(e).	Amount of Bid Security:	Rs: 13440 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR.**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.02**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Detailed Estimate For Construction of Paver Block New Shaikh Mohalla Madeji From Aijaz Ali Shaikh House to Otaq Chowk TC Madeji (Ward 1)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 996371 (+) O/R
(e).	Amount of Bid Security:	Rs: 19927 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount (ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.03**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block New Shaikh Mohalla Madeji Masjid to Arbab Shaikh House & Haji Bashir Shaikh House to Sikandar House TC Madeji (Ward 1)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 991686 (+) O/R
(e).	Amount of Bid Security:	Rs: 19834 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*Mubpr*  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.04**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block New Shaikh Mohalla Madeji From House of Sikandar Shaikh to House of Lal Bux & Miskeen Shaikh TC Madeji (Ward 1)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 999276 (+) O/R
(e).	Amount of Bid Security:	Rs: 19986 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**



**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115

Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)

Fax# 0726575115

**BIDDING DATA  
WORK NO.05**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block New Shaikh Mohalla Madeji From Otaq Chowk to Masjid TC Madeji (Ward 1)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 988295 (+) O/R
(e).	Amount of Bid Security:	Rs: 19766 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: tcmadeji@gmail.com  
Fax# 0726575115

**BIDDING DATA  
WORK NO.06**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Abbasi Mohalla Amanullah Channa House to Shaman Abbasi House T/C Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 993654 (+) O/R
(e).	Amount of Bid Security:	Rs: 19873 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount (ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*M. H. P. S.*  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115

Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)

Fax# 0726575115

**BIDDING DATA  
WORK NO 07**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block from Ali Murad Brohi Shop to Geo Hussani House & Gul Hassan House TC Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 998550 (+) O/R
(e).	Amount of Bid Security:	Rs: 19971 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months. <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 12:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*M. J. J.*  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.08**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block from Atif Panhwar Shop to Lashari House TC Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 986449 (+) O/R
(e).	Amount of Bid Security:	Rs: 19729 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*Muhyo*  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.09**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Gareebabad Mohalla Sadaruddin shop to Manzoor Marfani T/C Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 983204 (+) O/R
(e).	Amount of Bid Security:	Rs: 19664 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount (ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*M. M. M. M.*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**



**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: tcmadeji@gmail.com  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO 10**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block from Ghulam Rasool House to Loung Shop TC Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 669863 (+) O/R
(e).	Amount of Bid Security:	Rs: 13397 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO 11**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Drains Type-I & I/C RCC Slabs, Ghulam Shabir Otaq to Mohammad Hashim Dayo House T/C Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 867857 (+) O/R
(e).	Amount of Bid Security:	Rs: 17357 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 12:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI

# OFFICE OF THE CHAIRMAN, TOWN COMMITTEE

## MADEJI DISTRICT SHIKARPUR

Phone No. 0726575115

Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)

Fax# 0726575115

### BIDDING DATA

### WORK NO 12

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block from Shaman Abbasi House to Shakoor Mangi House TC Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 989002 (+) O/R
(e).	Amount of Bid Security:	Rs: 19780 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount (ii). 8% Retention Money of bill amount will be deducted from Running Bill.	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO. 13**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Shaikh Mohalla to Ali Bux Mast from Khalid Soomro House to Gul Mir Otaq T/C Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 992577 (+) O/R
(e).	Amount of Bid Security:	Rs: 19852 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: N/S:	

CONTRACTOR

*M. M. M. M.*  
ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI



**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115

Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)

Fax# 0726575115

**BIDDING DATA  
WORK NO 14**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Qamar Din Vegetable Shop to Riaz Qazi Saloon, Rajkumar to Badar din Jeho House T.C Madeji (Ward-2)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 568036 (+) O/R
(e).	Amount of Bid Security:	Rs: 11361 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> <b>90 Days</b>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**



# OFFICE OF THE CHAIRMAN, TOWN COMMITTEE

## MADEJI DISTRICT SHIKARPUR

Phone No. 0726575115

Email: tcmadeji@gmail.com

Fax# 0726575115

**BIDDING DATA**  
**WORK NO 15**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Drains Type-II & I/C RCC Slabs, From Shop of Sunil Kumar To Shah Nawaz Junejo House Dakhan-Madeji Road TC Madeji (Ward-3)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 986491 (+) O/R
(e).	Amount of Bid Security:	Rs: 19730 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount (ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 12:30 pm
(k).	Time for Completion from written order of commencement:	180 Days
(l).	Liquidity Damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay; but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S: _____	

CONTRACTOR:

*[Signature]*  
ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI

# OFFICE OF THE CHAIRMAN, TOWN COMMITTEE

## MADEJI DISTRICT SHIKARPUR

Phone No. 0726575115

Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)

Fax# 0726575115

### BIDDING DATA WORK NO 16

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Drains Type-II & I/C RCC Slabs, From Shop of Mashook Ujan to Qadir Bux Dayo Main road TC Madeji (Ward-3)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 994876 (+) O/R
(e).	Amount of Bid Security:	Rs: 19898 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security):	02.00% of Contract/ Sanction Amount
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commencement:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI

CONTRACTOR

ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.17**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Mirani Mohalla from House of Rehmatullah to Usman Mirani House T/C Madeji (Ward-3)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 997800 (+) O/R
(e).	Amount of Bid Security:	Rs: 19956 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.18**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Shahi Bazar Raj Kumar Shop to Anwar Panhwar shop TC Madeji (Ward-3)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 989362 (+) O/R
(e).	Amount of Bid Security:	Rs: 19787 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**



**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.19**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Shahi Bazar Sanjay Shop to Moti Masjid Chowk TC Madeji (Ward-3)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 837666 (+) O/R
(e).	Amount of Bid Security:	Rs: 16753 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**



**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.20**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Shahi Bazar Ghumro Shop to Sanjay Shop TC Madeji (Ward-3)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 973886 (+) O/R
(e).	Amount of Bid Security:	Rs: 19478 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.21**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Shahi Bazar Jahangir Shop to Raj Kumar Shop TC Madeji (Ward-3)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 956507 (+) O/R
(e).	Amount of Bid Security:	Rs: 19130 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 12:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.22**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction/Repair Of Drains Type-I & I/C RCC Slabs, Shahi Bazar Jhangir Shop to Anwar Ali Panhwar Shop, Ghumro Shop to Moti Masjid Chowk T/C Madeji (Ward-3)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 906331 (+) O/R
(e).	Amount of Bid Security:	Rs: 18127 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.23**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Old post office Soomra Mohalla Masjid Chowk to Abdul Majeed House TC Madeji (Ward-4)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 974599 (+) O/R
(e).	Amount of Bid Security:	Rs: 19492 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06-Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.24**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Old post office Soomra Mohalla from Abdul Rehman House Haji Lutufullah House TC Madeji (Ward-4)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 994164 (+) O/R
(e).	Amount of Bid Security:	Rs: 19883 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**



**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.25**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Drains Type-I & I/C RCC Slabs, From House of Taqi Shah to Station Road T/C Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 976601 (+) O/R
(e).	Amount of Bid Security:	Rs: 19532 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06-Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.26**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Brick Pavement from Sunil kumar Shop to Shah Nawaz Junejo TC Madeji Ward-4
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 947371 (+) O/R
(e).	Amount of Bid Security:	Rs: 18947 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**


**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: tcmadeji@gmail.com  
Fax# 0726575115

**BIDDING DATA  
WORK NO.27**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Retaining wall & Brick Pavement at main road to Servant Quarter TC Madeji (Ward 4)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 645415 (+) O/R
(e).	Amount of Bid Security:	Rs: 12908 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.28**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Retaining wall at Ali Hyder Shah to Juneja Mohalla TC Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 293479 (+) O/R
(e).	Amount of Bid Security:	Rs: 5870 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.29**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Ali Hyder Shah to Juneja Mohalla TC Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 995245 (+) O/R
(e).	Amount of Bid Security:	Rs: 19905 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**



**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.30**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Drains Type-II & I/C RCC Slabs, From Civil Hospital to Sardar Himath Ali Khan Kamario Gate Main road TC Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 955797 (+) O/R
(e).	Amount of Bid Security:	Rs: 19116 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.31**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Drains Type-I & I/C RCC Slabs, and Paver Block at Juneja Mohalla from House of Abdul Rasheed Junejo to Abdul Latif Junejo T/C Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 994520 (+) O/R
(e).	Amount of Bid Security:	Rs: 19890 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 12:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.32**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block & Earth filling Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to Rasool Bux Mirbahar TC Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 786295 (+) O/R
(e).	Amount of Bid Security:	Rs: 15726 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount (ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*Mahy*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.33**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to House of Shahnawaz Jeho to Saifal Kumbhar House TC Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 973806 (+) O/R
(e).	Amount of Bid Security:	Rs: 19476 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE  
MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA  
WORK NO.34**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to Rasool Bux Mirani House TC Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 983615 (+) O/R
(e).	Amount of Bid Security:	Rs: 19672 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 12:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER  
TOWN COMMITTEE MADEJI**



**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.35**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction of Paver Block from Noral Mirani to House of Hazoor Bux Junejo to Kadan Junejo TC Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 985887 (+) O/R
(e).	Amount of Bid Security:	Rs: 19718 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*[Signature]*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115

Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)

Fax# 0726575115

**BIDDING DATA**  
**WORK NO.36**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Repair Of Drains Type-I & I/C RCC Slabs, and Repair of T-II Drain at Baab Himath Ali Khan Gate to Baab Saein Bodlo Shah T/C Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 838706 (+) O/R
(e).	Amount of Bid Security:	Rs: 16774 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	06 Months <i>90 Days</i>
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At/2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

*M. M. M. M.*  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**OFFICE OF THE CHAIRMAN, TOWN COMMITTEE**  
**MADEJI DISTRICT SHIKARPUR**

Phone No. 0726575115  
Email: [tcmadeji@gmail.com](mailto:tcmadeji@gmail.com)  
Fax# 0726575115

**BIDDING DATA**  
**WORK NO.37**

(a).	Name of Procuring Agency:-	TOWN COMMITTEE MADEJI
(b).	Brief Description of Works:-	Construction Of Drains Type-I & I/C RCC Slabs, Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine Saifal Kumbhar Ajeeb Jeho House T/C Madeji (Ward 5)
(c).	Procuring Agency's address:	TOWN COMMITTEE MADEJI
(d).	Estimated Cost:	Rs: 986680 (+) O/R
(e).	Amount of Bid Security:	Rs: 19734 (+) 2% of O/R
(f).	Period of Bid Validity (Months):	<del>06 Months</del> 90 Days
(g).	(i). Security Deposit:- (i/c bid security): 02.00% of Contract/ Sanction Amount	
	(ii). 8% Retention Money of bill amount will be deducted from Running Bill	
(h).	Percentage, if any, to be deducted from bills :	8% Income Tax
(i).	Deadline for Submission of Bids along with time :	13.06.2018 at 12:00 pm
(j).	Venue, Time and Date of Bid Opening:	Office of the Town Committee Madeji At 2:30 pm
(k).	Time for Completion from written order of commence:	180 Days
(l).	Liquidity damages: Rs: 1,000/- Per Day (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).	
(m).	Tender Cost Vide Pay Order No: _____ Dated: _____ Amount _____ Rs: 1000/- (One Thousand)	
(n).	Bidding Document issued to: M/S:	

CONTRACTOR

  
**ASSISTANT EXECUTIVE ENGINEER**  
**TOWN COMMITTEE MADEJI**

**ANNUAL PROCUREMENT PLAN ( YEAR 2017-18 )  
FOR PROCUREMENT WORKS IN TOWN COMMITTEE MADEJI DISTRICT SHIKARPUR**

S.N	Description of procurement	Quantity (where applicable)	Estimated unit cost (where applicable)	Estimated total cost	Funds allocated	Sources of ADP/NON ADP	Proposed procurement Method	Anticipated/ Actual date of Advertisement	Anticipated/ Actual date of Start	Anticipated/ Actual Date of Completion
1.	Construction of Paver Block New Shaikh Mohalla Madeji Alam Chowk to Haji Eiden House TC Madeji (Ward 1)	-	-	671993	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
2.	Construction of Paver Block New Shaikh Mohalla Madeji From Aijaz Ali Shaikh House to Otaq Chowk TC Madeji (Ward 1)	-	-	996371	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
3.	Construction of Paver Block New Shaikh Mohalla Madeji Masjid to Arbab Shaikh House & Haji Bashir Shaikh House to Sikandar House TC Madeji (Ward 1)	-	-	991686	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
4.	Construction of Paver Block New Shaikh Mohalla Madeji From House of Sikandar Shaikh to House of Lal Bux & Miskeen Shaikh TC Madeji (Ward 1)	-	-	999276	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
5.	Construction of Paver Block New Shaikh Mohalla Madeji From Otaq Chowk to Masjid TC Madeji (Ward 1)	-	-	988295	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
6.	Construction/Repair Of Drains Type-1 & I/C RCC Slabs, and Paver Block Abbasi Mohalla Amanullah Channa House to Shaman Abbasi House T/C Madeji (Ward-2)	-	-	993654	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
7.	Construction of Paver Block from Ali Murad Brohi Shop to Geo Hussani House & Gul Hassan House TC Madeji (Ward-2)	-	-	998550	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
8.	Construction of Paver Block from Atif Panhwar Shop to Lashari House TC Madeji (Ward-2)	-	-	986449	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
9.	Construction/Repair Of Drains Type-1 & I/C RCC Slabs, and Paver Block Gareebabad Mohalla Sadaruddin shop to Manzoor Marfani T/C Madeji (Ward-2)	-	-	983204	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
10.	Construction of Paver Block from Ghulam Rasool House to Loung Shop TC Madeji (Ward-2)	-	-	669863	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
11.	Construction Of Drains Type-1 & I/C RCC Slabs, Ghulam Shabir Otaq to Mohammad Hashim Dayo House T/C Madeji (Ward-2)	-	-	867857	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
12.	Construction of Paver Block from Shaman Abbasi House to Shakoor Mangi House TC Madeji (Ward-2)	-	-	989002	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
13.	Construction/Repair Of Drains Type-1 & I/C RCC Slabs, and Paver Block Shaikha Mohalla to Ali Bux Mast from Khalid Soomro House to Gul Mir Otaq T/C Madeji (Ward-2)	-	-	992577	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE



**ANNUAL PROCUREMENT PLAN ( YEAR 2017-18 )**  
**FOR PROCUREMENT WORKS IN TOWN COMMITTEE MADEJI DISTRICT SHIKARPUR**

14.	Construction of Paver Block Qamar Din Vegetable Shop to Riaz Qazi Saloon, Rajkumar to Badar din Jeho House T.C Madeji (Ward-2)	-	-	568036	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
15.	Construction Of Drains Type-II & I/C RCC Slabs, From Shop of Sunil Kumar To Shah Nawaz Junejo House Dakhan-Madeji Road TC Madeji (Ward-3)	-	-	986491	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
16.	Construction Of Drains Type-II & I/C RCC Slabs, From Shop of Mashook Ujan to Qadir Bux Dayo Main road TC Madeji (Ward-3)	-	-	994876	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
17.	Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Mirani Mohalla from House of Rehmatullah to Usman Mirani House T/C Madeji (Ward-3)	-	-	997800	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
18.	Construction of Paver Block Shahi Bazar Raj Kumar Shop to Anwar Panhwar shop TC Madeji (Ward-3)	-	-	989362	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
19.	Construction of Paver Block Shahi Bazar Sanjay Shop to Moti Masjid Chowk TC Madeji (Ward-3)	-	-	837666	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
20.	Construction of Paver Block Shahi Bazar Ghumro Shop to Sanjay Shop TC Madeji (Ward-3)	-	-	973886	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
21.	Construction of Paver Block Shahi Bazar Jahangir Shop to Raj Kumar Shop TC Madeji (Ward-3)	-	-	956507	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
22.	Construction/Repair Of Drains Type-I & I/C RCC Slabs, Shahi Bazar Jhangir Shop to Anwar Ali Panhwar Shop, Ghumro Shop to Moti Masjid Chowk T/C Madeji (Ward-3)	-	-	906331	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
23.	Construction of Paver Block Old post office Soomra Mohalla Masjid Chowk to Abdul Majeed House TC Madeji (Ward-4)	-	-	974599	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
24.	Construction of Paver Block Old post office Soomra Mohalla from Abdul Rehman House Haji Lutfulah House TC Madeji (Ward-4)	-	-	994164	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
25.	Construction Of Drains Type-I & I/C RCC Slabs, From House of Taqi Shah to Station Road T/C Madeji (Ward 5)	-	-	975756	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
26.	Brick Pavement from Sunil kumar Shop to Shah Nawaz Junejo TC Madeji Ward-4	-	-	947371	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
27.	Construction Of Retaining wall & Brick Pavement at main road to Seyvant Quarter TC Madeji (Ward 4)	-	-	645415	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE



**ANNUAL PROCUREMENT PLAN ( YEAR 2017-18 )  
FOR PROCUREMENT WORKS IN TOWN COMMITTEE MADEJI DISTRICT SHIKARPUR**

28.	Construction Of Retaining wall at Ali Hyder Shah to Juneja Mohalla TC Madeji (Ward 5)	-	-	293479	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
29.	Construction of Paver Block Ali Hyder Shah to Juneja Mohalla TC Madeji (Ward 5)	-	-	995245	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
30.	Construction Of Drains Type-II & I/C RCC Slabs, From Civil Hospital to Sardar Himath Ali Khan Kamario Gate Main road TC Madeji (Ward 5)	-	-	955797	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
31.	Construction Of Drains Type-I & I/C RCC Slabs, and Paver Block at Juneja Mohalla from House of Abdul Rasheed Junejo to Abdul Latif Junejo T/C Madeji (Ward 5)	-	-	994520	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
32.	Construction of Paver Block & Earth filling Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to Rasool Bux Mirbahar TC Madeji (Ward 5)	-	-	786295	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
33.	Construction of Paver Block Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to House of Shahnawaz Jeho to Saifal Kumbhar House TC Madeji (Ward 5)	-	-	973806	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
34.	Construction of Paver Block Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to Rasool Bux Mirani House TC Madeji (Ward 5)	-	-	983615	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
35.	Construction of Paver Block from Norral Mirani to House of Hazoor Bux Junejo to Kadan Junejo TC Madeji (Ward 5)	-	-	985887	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
36.	Repair Of Drains Type-I & I/C RCC Slabs, and Repair of T-II Drain at Baab Himath Ali Khan Gate to Baab Saain Bodlo Shah T/C Madeji (Ward 5)	-	-	838706	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE
37.	Construction Of Drains Type-I & I/C RCC Slabs, Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine Saifal Kumbhar Ajeeb Jeho House T/C Madeji (Ward 5)	-	-	986680	OZT SHARE 2017-18	Non ADP	Single Stage - One Envelope Procedure	IN-DUE COURSE	IN-DUE COURSE	IN-DUE COURSE

**ASSISTANT EXECUTIVE ENGINEER**

**TOWN COMMITTEE**

**MADEJI**

**TOWN OFFICER**

**TOWN COMMITTEE**

**MADEJI**



**CHAIRMAN**

**TOWN COMMITTEE**

**MADEJI**

## SCHEDULE B

**Sub-Work No. 1 Paver Block**

Construction of Paver Block New Shaikh Mohalla Madeji Alam  
Chowk to Haji Eiden House TC Madeji (Ward 1)

**Head Of Account:-**

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	821.70 cft	@Rs 11288.75	P%Cft	Rs: 92760
	Ratio 1:2:4	65.00 cft	@Rs 14429.25	P%Cft	Rs: 9379
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	591.60 cft	@Rs 1800.00	P%Cft	Rs: 10649
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	2230.00 Sft	@Rs 199.77	P-Sft	Rs: 445487

**Total Rs: 558275**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 558275	---	Rs: 558275
	<b>Total</b>	<b>Rs: 558275</b>	<b>---</b>	<b>Rs: 558275</b>

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block New Shaikh Mohalla Madeji from  
Aijaz Ali Shaikh House to Otaq Chowk TC Madeji (Ward 1)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1192.95 cft	@Rs 11288.75	P%Cft	Rs: 134669
2.	Ratio 1:2:4 Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	110.09 cft 614.55 cft	@Rs 14429.25 @Rs 1800.00	P%Cft P%Cft	Rs: 15885 Rs: 11062
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3281.40 Sft	@Rs 199.77	P-Sft	Rs: 655525

**Total Rs: 817141**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 817141	---	Rs: 817141
<b>Total</b>		<b>Rs: 817141</b>	<b>---</b>	<b>Rs: 817141</b>

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block New Shaikh Mohalla Madeji Masjid to Arbab Shaikh House & Haji Bashir Shaikh House to Sikandar House TC Madeji (Ward 1)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1269.02 cft	@Rs 11288.75	P%Cft	Rs: 143256
	Ratio 1:2:4	174.57 cft	@Rs 14429.25	P%Cft	Rs: 25189
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	653.74 cft	@Rs 1800.00	P%Cft	Rs: 11767
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3316.50 Sft	@Rs 199.77	P-Sft	Rs: 662537

**Total Rs: 842750**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 842750	---	Rs: 842750
	<b>Total</b>	<b>Rs: 842750</b>	<b>---</b>	<b>Rs: 842750</b>

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block New Shaikh Mohalla Madeji from House of Sikandar Shaikh to House of Lal Bux & Miskeen Shaikh TC Madeji (Ward 1)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1179.75 cft	@Rs 11288.75	P%Cft	Rs: 133179
	Ratio 1:2:4	141.57 cft	@Rs 14429.25	P%Cft	Rs: 20427
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	607.75 cft	@Rs 1800.00	P%Cft	Rs: 10940
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3146.00 Sft	@Rs 199.77	P-Sft	Rs: 628476

**Total Rs: 793022**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 793022	---	Rs: 793022
	<b>Total</b>	<b>Rs: 793022</b>	<b>---</b>	<b>Rs: 793022</b>


**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji



## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block New Shaikh Mohalla Madeji from Otaq Chowk to Masjid TC Madeji (Ward 1)

### Head Of Account:-

OZT Share/Own Sources 2017-18


Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1109.79 cft	@Rs 11288.75	P%Cft	Rs: 125281
	Ratio 1:2:4	38.94 cft	@Rs 14429.25	P%Cft	Rs: 5619
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	571.71 cft	@Rs 1800.00	P%Cft	Rs: 10291
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3245.00 Sft	@Rs 199.77	P-Sft	Rs: 648254

**Total Rs: 789445**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	<b>Rs: 789445</b>	---	<b>Rs: 789445</b>
	<b>Total</b>	<b>Rs: 789445</b>	---	<b>Rs: 789445</b>


**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction/Repair Of Drains Type-I & I/C RCC Slabs, and  
Paver Block Abbasi Mohalla Amanullah Channa House to  
Shaman Abbasi House T/C Madeji (Ward-2)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	1125.00 cft	@Rs 11948.36	P%Cft	Rs: 134419
2.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51). R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16). Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	3000.00 Sft	@Rs 2283.93	P%Sft	Rs: 68518
3.		235.95 Cft	@Rs 337	P.Cft	Rs: 79515
4.		9.48 Cwt	@Rs 5001.7	P.Cwt	Rs: 47417

**Total Rs:329869**

### Sub-Work No. 2

### Paver Block

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	1925.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 4076
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	1925.0 Cft	@Rs 263.0	P%0 Cft	Rs: 506
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1). Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8.	1925.0 Cft	@Rs 5039.0	P%0 Cft	Rs: 9700
4.		709.50 Cft	@Rs 11288.75	P% Cft	Rs: 80094
	<b>Ratio 1:2:4</b> Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	80.85 Cft	@Rs 14429.25	P% Cft	Rs: 11666
5.		1905.00 Sft	@Rs 199.77	P.Sft	Rs: 380562
6.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	365.50 Cft	@Rs 1800.0	P% Cft	Rs: 6579

**Total Rs: 493183**

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs:329869	---	Rs: 329869
2	Sub-Work 2 Paver Block	Rs: 493183	---	Rs: 493183
	<b>Total</b>	<b>Rs: 823052</b>	---	<b>Rs: 823052</b>

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block from Ali Murad Brohi Shop to  
Geo Hussani House & Gul Hassan House TC Madeji (Ward-2)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	3541.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 7498
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	3541.00 Cft	@Rs 263.0	P%0 Cft	Rs: 931
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	3541.00 Cft	@Rs 5039.0	P%0 Cft	Rs: 17843
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8 <b>Ratio 1:2:4</b>	1168.53 Cft	@Rs 11288.75	P% Cft	Rs: 131912
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	115.17 Cft	@Rs 14429.25	P% Cft	Rs: 16618
6.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	601.97 Cft	@Rs 1800.0	P% Cft	Rs: 10835
		3192.00 Sft	@Rs 199.77	P.Sft	Rs: 637666
<b>Total</b>					<b>Rs:823304</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	<b>Rs:823304</b>	---	<b>Rs:823304</b>
<b>Total</b>		<b>Rs:823304</b>	---	<b>Rs:823304</b>

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block from Atif Panhwar Shop to Lashari House TC Madeji (Ward-2)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	3522.50 Cft	@Rs 2117.50	P%0 Cft	Rs: 7459
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	3522.50 Cft	@Rs 263.0	P%0 Cft	Rs: 926
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	3522.50 Cft	@Rs 5039.0	P%0 Cft	Rs: <u>17750</u>
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8 <b>Ratio 1:2:4</b>	1162.43 Cft	@Rs 11288.75	P% Cft	Rs: 131223
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	113.85 Cft	@Rs 14429.25	P% Cft	Rs: 16428
6.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	598.83 Cft	@Rs 1800.0	P% Cft	Rs: 10779
		3177.50 Sft	@Rs 199.77	P.Sft	Rs: 634769
<b>Total</b>					<b>Rs:819334</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	<b>Rs:819334</b>	---	<b>Rs:819334</b>
<b>Total</b>		<b>Rs:819334</b>	---	<b>Rs:819334</b>

**Contractor**

  
**Assistant Executive Engineer**  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer**  
Town Committee  
Madeji



## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction/Repair Of Drains Type-I & I/C RCC Slabs, and  
Paver Block Gareebabad Mohalla Sadaruddin shop to  
Manzoor Marfani T/C Madeji (Ward-2)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	1350.00 cft	@Rs 11948.36	P%Cft	Rs: 161303
2.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51). R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or prrecast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16).	2700.00 Sft	@Rs 2283.93	P%Sft	Rs: 61666
3.	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	67.76 Cft	@Rs 337	P.Cft	Rs: 22835
4.		2.72 Cwt	@Rs 5001.7	P.Cwt	Rs: 13617

**Total Rs:259421**

### Sub-Work No. 2

### Paver Block

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	2231.25 Cft	@Rs 2117.50	P%0 Cft	Rs: 4725
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	2231.25 Cft	@Rs 263.0	P%0 Cft	Rs: 587
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	2231.25 Cft	@Rs 5039.0	P%0 Cft	Rs: 11243
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8.	779.63 Cft	@Rs 11288.75	P% Cft	Rs: 88010
	<b>Ratio 1:2:4</b>	74.25 Cft	@Rs 14429.25	P% Cft	Rs: 10714
5.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	2137.50 Sft	@Rs 199.77	P.Sft	Rs: 427008
6.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	401.63 Cft	@Rs 1800.0	P% Cft	Rs:7229

**Total Rs: 549516**

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs:259421	---	Rs: 259421
2	Sub-Work 2 Paver Block	Rs: 549516	---	Rs: 549516
	<b>Total</b>	<b>Rs: 808937</b>	<b>---</b>	<b>Rs: 808937</b>

**Contractor**

  
**Assistant Executive Engineer  
Town Committee  
Madeji**

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer  
Town Committee  
Madeji**

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block from Ghulam Rasool House to Loung Shop TC Madeji (Ward-2)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	2450.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 5188
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	2450.00 Cft	@Rs 263.0	P%0 Cft	Rs: 644
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	2450.00 Cft	@Rs 5039.0	P%0 Cft	Rs: <u>12346</u>
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8	808.50 Cft	@Rs 11288.75	P% Cft	Rs: 91270
	<b>Ratio 1:2:4</b>	57.75 Cft	@Rs 14429.25	P% Cft	Rs: 8333
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	416.50 Cft	@Rs 1800.0	P% Cft	Rs: 7497
6.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	2275.00 Sft	@Rs 199.77	P.Sft	Rs: 454477
<b>Total</b>					<b>Rs:579754</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs:579754	---	Rs:579754
<b>Total</b>		Rs:579754	---	Rs:579754

**Contractor**

*(Signature)*  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

*(Signature)*  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction Of Drains Type-I & I/C RCC Slabs, Ghulam Shabir Otaq to Mohammad Hashim Dayo House T/C Madeji (Ward-2)  
OZT Share/Own Sources 2017-18

#### Head Of Account:-

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	1290.47	@Rs 3176.25	P%0Cft	Rs:4099
2.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	567.80 cft	@Rs 11288.75	P%Cft	Rs: 64098
3.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	3680.10 cft	@Rs 11948.36	P%Cft	Rs: 439712
4.	Construction of standard open type drains connuttee block of C.C 1:2:4 cost of situ to the design profiles i/c cost of mould as per drawing i/c supplying floating cost of cement 1/32" thick to expose surface faces finished smooth curing complete as per drawing design. (P.H.S.I No.D, P/58) .Type (A).	680.0 Rft	@Rs 94.0	P.Rft	Rs: 63920
5.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51).	1777.50 Sft	@Rs 2283.93	P%Sft	Rs: 40597
6.	R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or pprcast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16).	79.28 Cft	@Rs 337	P.Cft	Rs: 26717
7.	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	3.19 Cwt	@Rs 5001.7	P.Cwt	Rs: 15932

**Total Rs:655074**

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs:655074	---	Rs: 655074
	<b>Total</b>	<b>Rs:655074</b>	<b>---</b>	<b>Rs:655074</b>

**Contractor**

  
**Assistant Executive Engineer  
Town Committee  
Madeji**

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer  
Town Committee  
Madeji**



## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block from Shaman Abbasi House to Shakoor Mangi House TC Madeji (Ward-2)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	3585.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 7591
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	3585.00 Cft	@Rs 263.0	P%0 Cft	Rs: 943
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	3585.00 Cft	@Rs 5039.0	P%0 Cft	Rs: 18065
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8	1183.05 Cft	@Rs 11288.75	P% Cft	Rs: 133552
	<b>Ratio 1:2:4</b>	112.20 Cft	@Rs 14429.25	P% Cft	Rs: 16190
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	609.45 Cft	@Rs 1800.0	P% Cft	Rs:10970
6.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	3245.00 Sft	@Rs 199.77	P.Sft	Rs: 648254
<b>Total</b>					<b>Rs:835564</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Paver Block	<b>Rs:835564</b>	---	<b>Rs:835564</b>
<b>Total</b>		<b>Rs:835564</b>	---	<b>Rs:835564</b>

**Contractor**

*(Signature)*  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

*(Signature)*  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Shaikh Mohalla to Ali Bux Mast from Khalid Soomro House to Gul Mir Otaq T/C Madeji (Ward-2)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	345.00 cft	@Rs 11948.36	P%Cft	Rs: 41222
2.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51). R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface	690.00 Sft	@Rs 2283.93	P%Sft	Rs: 15759
3.	i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or prrecast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16). Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	193.08 Cft	@Rs 337	P.Cft	Rs: 65068
4.		7.76 Cwt	@Rs 5001.7	P.Cwt	Rs: 38802
<b>Total</b>					<b>Rs:160850</b>

### Sub-Work No. 2

### Paver Block

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	2770.0 Cft	@Rs 2117.50	P%0 Cft	Rs: 5865
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	2770.0 Cft	@Rs 263.0	P%0 Cft	Rs:729
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1). Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8.	2770.0 Cft	@Rs 5039.0	P%0 Cft	Rs: <u>13958</u>
4.		914.10 Cft	@Rs 11288.75	P% Cft	Rs: 103190
	<b>Ratio 1:2:4</b>	54.45 Cft	@Rs 14429.25	P% Cft	Rs: 7857
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5). Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	470.90 Cft	@Rs 1800.0	P% Cft	Rs: 8476
6.		2605.00 Sft	@Rs 199.77	P.Sft	Rs: 520401
<b>Total</b>					<b>Rs: 660476</b>

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs:160850	---	Rs:160850
2	Sub-Work 2 Paver Block	Rs: 660476	---	Rs: 660476
	<b>Total</b>	<b>Rs: 821326</b>	---	<b>Rs: 821326</b>

**Contractor**

  
**Assistant Executive Engineer  
Town Committee  
Madeji**

### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer  
Town Committee  
Madeji**

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block Qamar Din Vegetable Shop to Riaz Qazi Saloon, Rajkumar to Badar din Jeho House T.C Madeji (Ward-2)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	710.33 cft	@Rs 11288.75	P%Cft	Rs: 80187
	Ratio 1:2:4	51.25 cft	@Rs 14429.25	P%Cft	Rs: 7395
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	365.93 cft	@Rs 1800.00	P%Cft	Rs: 6587
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	1947.50 Sft	@Rs 199.77	P-Sft	Rs: 389052

**Total Rs: 483221**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 483221	---	Rs: 483221
	<b>Total</b>	<b>Rs: 483221</b>	<b>---</b>	<b>Rs: 483221</b>

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction of Drains Type-II & I/C RCC Slabs, From Shop of  
Sunil Kumar To Shah Nawaz Junejo House Dakhan-Madeji  
Road TC Madeji (Ward-3)  
OZT Share/Own Sources 2017-18

#### Head Of Account:-

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Dismatling and removing Road mantling (C.S.I.No. 51- P. No:13).	90.00 cft	@Rs 605.00	P%Cft	Rs:545
2.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	3105.0 cft	@Rs 3176.25	P%0Cft	Rs: 9862
3.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	882.0 cft	@Rs 11288.75	P%Cft	Rs: 99567
4.	Pacca brick work in foundation and plinth in cement sand mortar(1:6). Construction of standard open type drains connuttee block of C.C 1:2:4 cost of situ to the design profiles i/c cost of mould as per drawing	1575.00 cft	@Rs 11948.36	P%Cft	Rs: 188187
5.	i/c supplying floating cost of cement 1/32" thick to expose surface faces finished smooth curing complete as per drawing design. (P.H.S.I No.D, P/58) .Type (B).	670.0 Rft	@Rs 174.00	P.Rft	Rs: 116580
6.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51). R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing	2100.00 Sft	@Rs 2283.93	P%Sft	Rs: 47963
7.	rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or pprecast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16). Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in	540.00 Cft	@Rs 337	P.Cft	Rs: 181980
8.	position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	21.70 Cwt	@Rs 5001.7	P.Cwt	Rs: 108519

**Total Rs:752657**



## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs:752657	---	Rs: 752657
	Total	Rs:752657	---	Rs:752657

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction Of Drains Type-II & I/C RCC Slabs, From Shop of Mashook Ujan to Qadir Bux Dayo Main road TC Madeji (Ward-3)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	2700.00 cft	@Rs 3176.25	P%0Cft	Rs: 8576
2.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	756.00 cft	@Rs 11288.75	P%Cft	Rs: 85343
3.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	1350.00 cft	@Rs 11948.36	P%Cft	Rs: 161303
4.	Construction of standard open type drains connuttee block of C.C 1:2:4 cost of situ to the design profiles i/c cost of mould as per drawing i/c supplying floating cost of cement 1/32" thick to expose surface faces finished smooth curing complete as per drawing design. (P.H.S.I No.D, P/58) .Type (B).	600.0 Rft	@Rs 174.00	P.Rft	Rs: 104400
5.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51).	1800.00 Sft	@Rs 2283.93	P%Sft	Rs: 41111
6.	R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16).	681.00 Cft	@Rs 337	P.Cft	Rs: 229497
7.	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	27.36 Cwt	@Rs 5001.7	P.Cwt	Rs: 136855

**Total Rs:767084**

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs:767084	---	Rs:767084
	Total	Rs:767084	---	Rs:767084

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction/Repair Of Drains Type-I & I/C RCC Slabs, and Paver Block Mirani Mohalla from House of Rehmatullah to Usman Mirani House T/C Madeji (Ward-3)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	300.00 cft	@Rs 11948.36	P%Cft	Rs: 35845
2.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51). R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16). Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	500.00 Sft	@Rs 2283.93	P%Sft	Rs: 11420
3.		67.76 Cft	@Rs 337	P.Cft	Rs: 22835
4.		2.72 Cwt	@Rs 5001.7	P.Cwt	Rs: 13617

**Total Rs:83717**

### Sub-Work No. 2

### Paver Block

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	3842.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 8135
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	3842.00 Cft	@Rs 263.0	P%0 Cft	Rs: 1010
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	3842.00 Cft	@Rs 5039.0	P%0 Cft	Rs: <u>19360</u>
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8. <b>Ratio 1:2:4</b>	873.25 Cft	@Rs 11288.75	P% Cft	Rs: 98579
	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	91.50 Cft	@Rs 14429.25	P% Cft	Rs: 13203
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	3127.00 Sft	@Rs 199.77	P.Sft	Rs: 624681
6.		593.81 Cft	@Rs 1800.0	P% Cft	Rs:10689

**Total Rs: 775657**

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs: 83717	---	Rs: 83717
2	Sub-Work 2 Paver Block	Rs: 775657	---	Rs: 775657
	<b>Total</b>	<b>Rs: 859374</b>	<b>---</b>	<b>Rs: 859374</b>

**Contractor**

  
**Assistant Executive Engineer**  
Town Committee  
**Madeji**

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer**  
Town Committee  
**Madeji**



## SCHEDULE B

**Sub-Work No. 1 Paver Block**

Construction of Paver Block Shahi Bazar Raj Kumar Shop to Anwar  
Panhwar shop TC Madeji (Ward-3)

**Head Of Account:-**

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	940.00 cft	@Rs 11288.75	P%Cft	Rs: 106114
	Ratio 1:2:4	117.50 cft	@Rs 14429.25	P%Cft	Rs: 16954
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	639.20 cft	@Rs 1800.00	P%Cft	Rs: 11506
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3290.00 Sft	@Rs 199.77	P-Sft	Rs: 657243

**Total Rs: 791818**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 791818	---	Rs: 791818
	<b>Total</b>	<b>Rs: 791818</b>	<b>---</b>	<b>Rs: 791818</b>


**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

**Sub-Work No. 1 Paver Block**

Construction of Paver Block Shahi Bazar Sanjay Shop to Moti Masjid Chowk TC Madeji (Ward-3)

**Head Of Account:-**

OZT Share/Own Sources 2017-18


Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	953.70 cft	@Rs 11288.75	P%Cft	Rs: 107661
	Ratio 1:2:4	56.10 cft	@Rs 14429.25	P%Cft	Rs: 8095
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	491.30 cft	@Rs 1800.00	P%Cft	Rs: 8843
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	2720.00 Sft	@Rs 199.77	P-Sft	Rs: 543374

**Total Rs: 667973**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 667973	---	Rs: 667973
	<b>Total</b>	<b>Rs: 667973</b>	<b>---</b>	<b>Rs: 667973</b>

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

**Sub-Work No. 1 Paver Block**

Construction of Paver Block Shahi Bazar Ghumro Shop to Sanjay Shop TC Madeji (Ward-3)

**Head Of Account:-**

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1113.75 cft	@Rs 11288.75	P%Cft	Rs: 125728
	Ratio 1:2:4	74.25 cft	@Rs 14429.25	P%Cft	Rs: 10714
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	573.75 cft	@Rs 1800.00	P%Cft	Rs: 10328
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3150.00 Sft	@Rs 199.77	P-Sft	Rs: 629276

**Total Rs: 776045**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 776045	---	Rs: 776045
	<b>Total</b>	<b>Rs: 776045</b>	<b>---</b>	<b>Rs: 776045</b>


**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

**Sub-Work No. 1 Paver Block**

Construction of Paver Block Shahi Bazar Jahangir Shop to Raj  
Kumar Shop TC Madeji (Ward-3)

**Head Of Account:-**

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	900.00 cft	@Rs 11288.75	P%Cft	Rs: 101599
	Ratio 1:2:4	100.00 cft	@Rs 14429.25	P%Cft	Rs: 14429
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	612.00 cft	@Rs 1800.00	P%Cft	Rs: 11016
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3200.00 Sft	@Rs 199.77	P-Sft	Rs: 639264

**Total Rs: 766308**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs: 766308	---	Rs: 766308
	<b>Total</b>	Rs: 766308	---	Rs: 766308

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction/Repair Of Drains Type-I & I/C RCC Slabs, Shahi Bazar Jhangir Shop to Anwar Ali Panhwar Shop, Ghumro Shop to Moti Masjid Chowk T/C Madeji (Ward-3)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Dismantling cement concrete reinforced seperatingrein for cement from concrete cleaning and straightening the same (G.S.I.NO.20 P.NO 10)	798.60cft	@Rs 5445.00	P%Cft	Rs: 43484
2.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	1453.50 cft	@Rs 11948.36	P%Cft	Rs: 173669
3.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51).	3876.00 Sft	@Rs 2283.93	P%Sft	Rs: 88525
4.	R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or prrecast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16).	798.60 Cft	@Rs 337	P.Cft	Rs: 269128
5.	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	32.09 Cwt	@Rs 5001.7	P.Cwt	Rs: 160488

**Total Rs:735294**



## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Drains	Rs:735294	---	Rs:735294
	Total	Rs: 735294	---	Rs:735294

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block Old post office Soomra Mohalla  
Masjid Chowk to Abdul Majeed House TC Madeji (Ward-4)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	3585.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 7591
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	3585.00 Cft	@Rs 263.0	P%0 Cft	Rs: 943
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	3585.00 Cft	@Rs 5039.0	P%0 Cft	Rs: 18065
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8 <b>Ratio 1:2:4</b>	1183.05 Cft	@Rs 11288.75	P% Cft	Rs: 133552
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	120.45 Cft	@Rs 14429.25	P% Cft	Rs: 17380
6.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	609.45 Cft	@Rs 1800.0	P% Cft	Rs:10970
		3220.00 Sft	@Rs 199.77	P.Sft	Rs: 643259
<b>Total</b>					<b>Rs:831760</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Paver Block	Rs:831760	---	Rs:831760
<b>Total</b>		Rs:831760	---	Rs:831760

**Contractor**

*(Signature)*  
**Assistant Executive Engineer  
Town Committee  
Madeji**

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

*(Signature)*  
**Assistant Executive Engineer  
Town Committee  
Madeji**

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block Old post office Soomra Mohalla from Abdul Rehman House Haji Lutufullah House TC Madeji (Ward-4)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	3640.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 7708
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	3640.00 Cft	@Rs 263.0	P%0 Cft	Rs: 957
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	3640.00 Cft	@Rs 5039.0	P%0 Cft	Rs: 18342
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8 <b>Ratio 1:2:4</b>	1201.20 Cft	@Rs 11288.75	P% Cft	Rs: 135600
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	118.80 Cft	@Rs 14429.25	P% Cft	Rs: 17142
6.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	618.80 Cft	@Rs 1800.0	P% Cft	Rs:11138
		3280.00 Sft	@Rs 199.77	P.Sft	Rs: 655246
<b>Total</b>					<b>Rs:846133</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Paver Block	Rs:846133	---	Rs:846133
<b>Total</b>		<b>Rs:846133</b>	<b>---</b>	<b>Rs:846133</b>

**Contractor**

*(Signature)*  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

*(Signature)*  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

**Sub-Work No. 1 Drain**

Construction Of Drains Type-I & I/C RCC Slabs, From House of Taqi Shah to Station Road T/C Madeji (Ward 5)

**Head Of Account:-**

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	3750.00 cft	@Rs 3176.25	P%0Cft	Rs: 11911
2.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1237.50 cft	@Rs 11288.75	P%Cft	Rs: 139698
3.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	2250.00 cft	@Rs 11948.36	P%Cft	Rs: 268838
4.	Construction of standard open type drains connuttee block of C.C 1:2:4 cost of situ to the design profiles i/c cost of mould as per drawing i/c supplying floating cost of cement 1/32" thick to expose surface faces finished smooth curing complete as per drawing design. (P.H.S.I No.D, P/58) .Type (B).	1500.0 Rft	@Rs 174.00	P.Rft	Rs: 141000
5.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51).	3750.00 Sft	@Rs 2283.93	P%Sft	Rs: 85647
6.	R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or pprecast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16).	147.50 Cft	@Rs 337	P.Cft	Rs: 49708
7.	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	5.93 Cwt	@Rs 5001.7	P.Cwt	Rs: 29642

**Total Rs:726444**

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Drain	Rs:726444	---	Rs:726444
<b>Total</b>		<b>Rs:726444</b>	<b>---</b>	<b>Rs:726444</b>

**Contractor**

  
**Assistant Executive Engineer  
Town Committee  
Madeji**

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer  
Town Committee  
Madeji**



## SCHEDULE B

### Sub-Work No. 1 Brick Pavement

Brick Pavement from Sunil Kumar Shop to Shah Nawaz Junejo  
TC Madeji Ward-4

#### Head Of Account:-

OZT Share/Own Sources 2017-18

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	37800 Cft	@Rs 2117.50	P%0 Cft	Rs: 80042
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	37800 Cft	@Rs 263.0	P%0 Cft	Rs: 9941
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	37800 Cft	@Rs 5039.0	P%0 Cft	Rs: 190474
4.	Dry Brick on edge paving sand grouted including preparation of bed by watering, ramming and bringing the same to proper camber by 1/2" thick mud plaster. (CSI No.5,	12000.0 Sft	@Rs 3823.57	P% Sft	Rs: 458828
<b>Total</b>					<b>Rs:739287</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Paver Block	Rs:739287	---	Rs:739287
<b>Total</b>		Rs:739287	---	Rs:739287

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 Retaining Wall

Construction of Retaining wall & Brick Pavement at main road  
to Servant Quarter TC Madeji (Ward 4)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	540.00 cft	@Rs 3176.25	P%0Cft	Rs: 1715
2.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	178.20 cft	@Rs 11288.75	P%Cft	Rs: 20117
3.	Pacca brick work in foundation and plinth in cement sand mortar (1:6).	946.80 cft	@Rs 11948.36	P%Cft	Rs: 113127
4.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51).	1260.00 Sft	@Rs 2283.93	P%Sft	Rs: 28778
<b>Total</b>					<b>Rs:163736</b>

### Sub-Work No. 2 Brick Pavement

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	17865 Cft	@Rs 2117.50	P%0 Cft	Rs: 37829
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	17865 Cft	@Rs 263.0	P%0 Cft	Rs: 4698
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	6525 Cft	@Rs 5039.0	P%0 Cft	Rs: 32879
4.	Dry Brick on edge paving sand grouted including preparation of bed by watering, ramming and bringing the same to proper camber by 1/2" thick mud plaster. (CSI No.5,	6525.0 Sft	@Rs 3823.57	P% Sft	Rs: 249488
<b>Total</b>					<b>Rs:324896</b>

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Retaining Wall	Rs:163736	---	Rs:163736
	Sub-Work 2 Brick Pavement	Rs:324896	---	Rs:324896
	<b>Total</b>	Rs:488632	---	Rs:488632

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

**Sub-Work No. 1 Retaining Wall**

Construction Of Retaining wall at Ali Hyder Shah to Juneja  
Mohalla TC Madeji (Ward 5)

**Head Of Account:-**

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	3000.0 cft	@Rs 3176.25	P%0Cft	Rs: 9529
2.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	660.00 cft	@Rs 11288.75	P%Cft	Rs: 74506
3.	Pacca brick work in foundation and plinth in cement sand mortar (1:6).	3331.42 cft	@Rs 11948.36	P%Cft	Rs: 398050
4.	Cement plaster 1:6 ½" thick upto 12' height (CSI No: 13, P-52)	6000.0 Sft	@Rs 2206.6	P%Sft	Rs:132396
5.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51).	6000.0 Sft	@Rs 2283.93	P%Sft	Rs: 137036
<b>Total</b>					<b>Rs:751516</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Retaining Wall	<b>Rs:751516</b>	---	<b>Rs:751516</b>
<b>Total</b>		<b>Rs:751516</b>	---	<b>Rs:751516</b>


**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
**Assistant Executive Engineer**  
**Town Committee**  
**Madeji**

## SCHEDULE B

**Sub-Work No. 1 Paver Block**

Construction of Paver Block Ali Hyder Shah to Juneja Mohalla TC  
Madeji (Ward 5)

**Head Of Account:-**

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1158.30 cft	@Rs 11288.75	P%Cft	Rs: 130758
	Ratio 1:2:4	33.75 cft	@Rs 14429.25	P%Cft	Rs: 4870
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	596.70 cft	@Rs 1800.00	P%Cft	Rs: 10741
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3240.00 Sft	@Rs 199.77	P-Sft	Rs: 647255

**Total Rs: 793623**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	<b>Rs: 793623</b>	---	<b>Rs: 793623</b>
	<b>Total</b>	<b>Rs: 793623</b>	---	<b>Rs: 793623</b>

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji



## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Construction Of Drains Type-II & I/C RCC Slabs, From Civil Hospital to Sardar Himath Ali Khan Kamario Gate Main road TC Madeji (Ward 5)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Dismantling and removing Road mantling (C.S.I.No. 51- P. No:13).	2250.0 cft	@Rs 605	P%Cft	Rs: 13613
2.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	1125.00 cft	@Rs 3176.25	P%0Cft	Rs: 3573
3.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	742.50 cft	@Rs 11288.75	P%Cft	Rs: 83819
4.	Pacca brick work in foundation and plinth in cement sand mortar(1:6). Construction of standard open type drains connuttee block of C.C 1:2:4 cost of situ to the design profiles i/c cost of mould as per drawing	1687.50 cft	@Rs 11948.36	P%Cft	Rs: 201629
5.	i/c supplying floating cost of cement 1/32" thick to expose surface faces finished smooth curing complete as per drawing design. (P.H.S.I No.D, P/58) .Type (B).	750.0 Rft	@Rs 174.00	P.Rft	Rs: 130500
6.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51). R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing	2250.0 Sft	@Rs 2283.93	P%Sft	Rs: 51388
7.	rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or prrecast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16).	480.0 Cft	@Rs 337	P.Cft	Rs: 161760
8.	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	19.29 Cwt	@Rs 5001.7	P.Cwt	Rs: 96461

**Total Rs:729131**

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs:729131	---	Rs:729131
	Total	Rs:729131	---	Rs:729131

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 Drain

Construction of Drains Type-I & I/C RCC Slabs, and Paver Block at Juneja Mohalla from House of Abdul Rasheed Junejo to Abdul Latif Junejo T/C Madeji (Ward 5)

• Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	856.68 cft	@Rs 3176.25	P%0Cft	Rs: 2721
2.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	285.56 cft	@Rs 11288.75	P%Cft	Rs: 32236
3.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	708.00 cft	@Rs 11948.36	P%Cft	Rs: 84594
4.	Construction of standard open type drains connuttee block of C.C 1:2:4 cost of situ to the design profiles i/c cost of mould as per drawing i/c supplying floating cost of cement 1/32" thick to expose surface faces finished smooth curing complete as per drawing design. (P.H.S.I No.D, P/58) .Type (B).	472.0 Rft	@Rs 174.00	P.Rft	Rs: 44368
5.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51).	1180.00 Sft	@Rs 2283.93	P%Sft	Rs: 26950
6.	R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16).	138.67 Cft	@Rs 337	P.Cft	Rs: 46730
7.	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	5.57 Cwt	@Rs 5001.7	P.Cwt	Rs: 27866

**Total Rs:265467**

**Sub-Work No. 2 Paver Block**

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	9500.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 20116
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	9500.00 Cft	@Rs 263.0	P%0 Cft	Rs: 2499
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	9500.00 Cft	@Rs 5039.0	P%0 Cft	Rs: <u>47871</u>
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8	627.00 Cft	@Rs 11288.75	P% Cft	Rs: 70780
	<b>Ratio 1:2:4</b>	62.70 Cft	@Rs 14429.25	P% Cft	Rs: 9047
5.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	1710.00 Sft	@Rs 199.77	P.Sft	Rs: 341607
6.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	323.00 Cft	@Rs 1800.0	P% Cft	Rs:5814
				<b>Total</b>	<b>Rs:497734</b>

**GENERAL ABSTRACT OF COST**

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Drain	Rs:265467	---	Rs:265467
2	Sub-Work 2 Paver Block	Rs:497734	---	Rs:497734
	<b>Total</b>	<b>Rs:763201</b>	<b>---</b>	<b>Rs:763201</b>

**Contractor**

  
 Assistant Executive Engineer  
 Town Committee  
 Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
 Assistant Executive Engineer  
 Town Committee  
 Madeji

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block & Earth filling Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine to Rasool Bux Mirbahar TC Madeji (Ward 5)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	32200.00 Cft	@Rs 2117.50	P%0 Cft	Rs: 68184
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	32200.00 Cft	@Rs 263.0	P%0 Cft	Rs: 8469
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	32200.00 Cft	@Rs 5039.0	P%0 Cft	Rs: <u>162256</u>
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8	379.50 Cft	@Rs 11288.75	P% Cft	Rs: 42841
	<b>Ratio 1:2:4</b>	231.00 Cft	@Rs 14429.25	P% Cft	Rs: 33332
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	1368.50 Cft	@Rs 1800.0	P% Cft	Rs:24633
6.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	1050.00 Sft	@Rs 199.77	P.Sft	Rs: 209759
<b>Total</b>					<b>Rs:549472</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Paver Block	Rs:549472	---	Rs:549472
<b>Total</b>		<b>Rs:549472</b>	<b>---</b>	<b>Rs:549472</b>

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block Main Station Road to Kachi Abadi  
Mirani Mohalla Hakim Junejo Machine to House of Shah Nawaz  
Jeho to Saifal Kumbhar House TC Madeji (Ward 5)

Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1127.12 cft	@Rs 11288.75	P%Cft	Rs: 127237
	Ratio 1:2:4	98.01 cft	@Rs 14429.25	P%Cft	Rs: 14142
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	580.64 cft	@Rs 1800.00	P%Cft	Rs: 10451
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3118.50 Sft	@Rs 199.77	P-Sft	Rs: 622983

**Total Rs:774813**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs:774813	---	Rs:774813
	<b>Total</b>	Rs:774813	---	Rs:774813

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji



## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block Main Station Road to Kachi Abadi  
Mirani Mohalla Hakim Junejo Machine to Rasool Bux Mirani  
House TC Madeji (Ward 5)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	1138.50 cft	@Rs 11288.75	P%Cft	Rs: 128522
	Ratio 1:2:4	99.00 cft	@Rs 14429.25	P%Cft	Rs: 14285
2.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5)	586.50 cft	@Rs 1800.00	P%Cft	Rs: 10557
3.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49)	3150.00 Sft	@Rs 199.77	P-Sft	Rs: 629276

**Total Rs:782640**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
3	Sub-Work 1 Paver Block	Rs:782640	---	Rs:782640
	<b>Total</b>	Rs:782640	---	Rs:782640

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 Paver Block

Construction of Paver Block from Noral Mirani to House of Hazoor Bux Junejo to Kadan Junejo TC Madeji (Ward 5)

#### Head Of Account:-

OZT Share/Own Sources 2017-18

1.	Barrow pit excavation undressed lead upto 100 ft ordinary soil (C.S.I. No. 3 P/ 1).	12187.50 Cft	@Rs 2117.50	P%0 Cft	Rs: 25807
2.	Earth work compaction (Soft ordinary or hard soil lying earth in 6" layers leveling complete.(C.S.I.No. 13 P/3).	12187.50 Cft	@Rs 263.0	P%0 Cft	Rs: 3205
3.	Add Every 50' additional lead or part there of soft ordinary or hard soil (G.S.I- 1, P-1).	12187.50 Cft	@Rs 5039.0	P%0 Cft	Rs: <u>61413</u>
4.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15) 1:4:8 <b>Ratio 1:2:4</b>	1447.50 Cft	@Rs 11288.75	P% Cft	Rs: 163405
5.	Hard Murrum or fine powdery murrum (SMI No.71 P.No 5).	186.00 Cft	@Rs 14429.25	P% Cft	Rs: 26838
6.	Providing and Fixing cement paving blocks flooring having size 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 i/c filling the joints with hill sand laying in specified manner / patter and design etc complete. (C.S.I No: 73, P-49).	492.15 Cft	@Rs 1800.0	P% Cft	Rs:8859
		2523.00 Sft	@Rs 199.77	P.Sft	Rs: 504020
<b>Total</b>					<b>Rs:793547</b>

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Paver Block	<b>Rs:793547</b>	---	<b>Rs:793547</b>
<b>Total</b>		<b>Rs:793547</b>	---	<b>Rs:793547</b>

#### Contractor

  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

#### Contractor

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 (SURFACE DRAINS)

Repair Of Drains Type-I & I/C RCC Slabs, and Repair of T-II  
Drain at Baab Himath Ali Khan Gate to Baab Saein Bodlo Shah  
T/C Madeji (Ward 5)  
OZT Share/Own Sources 2017-18

#### Head Of Account:-

Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	2475.00 cft	@Rs 11948.36	P%Cft	Rs: 295722
2.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51). R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing	4950.00 Sft	@Rs 2283.93	P%Sft	Rs: 113055
3.	rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or p/precast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16). Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in	480.00 Cft	@Rs 337	P.Cft	Rs: 161760
4.	position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	19.29 Cwt	@Rs 5001.7	P.Cwt	Rs: 96461

**Total Rs:666998**

### GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 CC Drains	Rs:666998	---	Rs:666998
	<b>Total</b>	<b>Rs:666998</b>	<b>---</b>	<b>Rs:666998</b>

#### Contractor

  
Assistant Executive Engineer  
Town Committee  
Madeji

#### Conditions.

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

#### Contractor

  
Assistant Executive Engineer  
Town Committee  
Madeji

## SCHEDULE B

### Sub-Work No. 1 Drain

Construction Of Drains Type-I & I/C RCC Slabs, Main Station Road to Kachi Abadi Mirani Mohalla Hakim Junejo Machine Saifal Kumbhar Ajeeb Jeho House T/C Madeji (Ward 5)

Head Of Account:-

OZT Share/Own Sources 2017-18


Sr No	Item of work	Qty:	Rate	Unit	Amount
1.	Excavation in foundation of building bridges and other structures i/c dig billing dressing refilling around the structures with excavated Earth watering ramming up to 5ft (b) in ordinary soil (C.S.I-18/ P/4)	1270.50 cft	@Rs 3176.25	P%OCft	Rs: 4035
2.	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (C.S.I-5 P/15)	423.50 cft	@Rs 11288.75	P%Cft	Rs: 47808
3.	Pacca brick work in foundation and plinth in cement sand mortar(1:6).	4861.50 cft	@Rs 11948.36	P%Cft	Rs: 580870
4.	Construction of standard open type drains connuttee block of C.C 1:2:4 cost of situ to the design profiles i/c cost of mould as per drawing i/c supplying floating cost of cement 1/32" thick to expose surface faces finished smooth curing complete as per drawing design. (P.H.S.I No.D, P/58) .Type (B).	700.0 Rft	@Rs 174.00	P.Rft	Rs: 65800
5.	Cement plaster (1:4) up to 20'height ½"thick (C.S.I-11/ P/51).	1750.00 Sft	@Rs 2283.93	P%Sft	Rs: 39969
6.	R.C.C work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c screening and washing of shingle (a) R.C work in roof slab members laid in situ or pprcast laid in position complete in a respect. (i) Ratio 1;2;4 90 lbs cement 2 cft sand 4 cft shingle 1/8" to ¼" gauge. (C.S.I-6 P/16).	15.97 Cft	@Rs 337	P.Cft	Rs: 5383
7.	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also includes removal of rust from bars. (C.S.I-8, P/16).	0.64 Cwt	@Rs 5001.7	P.Cwt	Rs: 3210

**Total Rs:747074**

## GENERAL ABSTRACT OF COST

Sr No	Item of work	Schedule Item	Non Schedule Item	Total
1	Sub-Work 1 Drain	Rs:747074	---	Rs:747074
	<b>Total</b>	<b>Rs:747074</b>	<b>---</b>	<b>Rs:747074</b>

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji

**Conditions.**

1. The work shall have to be executed according to specification.
2. No premium on non-schedule item shall be paid to the contractor.
3. Any error and omission in the description of items of work and the rate shall be governed with relevant schedule of rates and estimate.
4. The contractor shall have to bring the material to use in work from the quarries mentioned in the estimate.

**Contractor**

  
Assistant Executive Engineer  
Town Committee  
Madeji



No. SOIV/(LG)/8-10/2017/LAR  
**GOVERNMENT OF SINDH  
LOCAL GOVERNMENT DEPARTMENT**

Karachi dated the 31<sup>st</sup> July, 2017

To,


✓  
The Chairman,  
Town Committee, Madeji,  
**DISTRICT SHIKARPUR.**

**SUBJECT:- SUBMISSION OF PROPOSED BUDGET BOOK OF TOWN COMMITTEE MADEJI, DISTRICT SHIKARPUR.**

I am directed to refer to your letter No. TC/309/2017, Madeji dated 13-07-2017, on the subject noted above and to convey approval for Budget 2017-18 in respect of Town Committee Madeji subject to following conditions:-

- i) No official Vehicle will be purchased without prior approval of this Department
- ii) No creation / up-gradation and re-designation of the posts will be carried out without approval of the Government.
- iii) Maximum efforts should be made to achieve the revenue target and enhancement of the recoveries exaggerated budgeting must be avoided.
- iv) The expenditure may be incurred in accordance with the policy guidelines issued by the Local Government Department from time to time Rules applicable & functions assigned to the Council under SLG, Act 2013.
- v) Non-development expenditure including POL/Fuel must be controlled minimized.
- vi) Budget must be on the format of Budget Rules 1985 & all Components should be classified properly & subject to allocation of budgetary policy issued by Finance Department, Government of Sindh.
- vii) No liabilities of previous year will be claimed from early Budget without approval of Competent Authority.

2. Further necessary action may be taken, accordingly as per rules / policy.

  
**(LIAQUAT ALI MANGI)**  
SECTION OFFICER-IV

Copy is forwarded for information to:-

- The Director, Local Government, Larkana.
- The Assistant Director, Local Fund Audit, Shikarpur.
- The Town Officer, Town Committee Madeji, District Shikarpur.
- P.S to Secretary, Local Government & Housing Town Planning Department, Govt. of Sindh, Karachi.

SECTION OFFICER-IV





No. SO-IV/(LG)/8-21/2016/LAR  
GOVERNMENT OF SINDH  
LOCAL GOVERNMENT DEPARTMENT

Karachi dated the 4<sup>th</sup> January 2017

To,


✓ The Chairman / Town Officer  
Town Committee, Madeji,  
Taluka Garhiyaseen,  
DISTRICT SHIKARPUR.



**SUBJECT: RESOULATION NO.5 (III) DATED 23-11-2016 UNANI-MOUSLY  
PASSED BY THE HOUSE OF THE HOUSE OF THE TOWN  
COMMITTEE MADEJI.**

I am directed to refer to your letter No. TC/18/2016 dated 23-11-2016, on the subject noted above and to convey the approval/Permission for execution of (31) development Schemes through NIT during the year 2016-17 as per the list of schemes and resolution passed by Town Committee, Madeji District Shikarpur according to the SPPRA Rules 2010 subject to condition that no liability shall be occurred in any way.


Further necessary action may please be taken accordingly.

  
(AFTAB AHMED ABBASI)  
DEPUTY SECRETARY (ADMN)

A Copy is forwarded for information to:-

1. The Commissioner, Larkano.
2. The Director Local Government, Larkano.
3. The Deputy Commissioner, Shikarpur.
4. The Assistant Director Local Fund Audit, District Shikarpur.
5. P.S to Secretary Local Government Department, Karachi.

DEPUTY SECRETARY (ADMN)



GOVERNMENT OF SINDH  
LOCAL GOVERNMENT DEPARTMENT

Karachi dated the 08<sup>th</sup> August, 2017

NOTIFICATION

NO.SOIV (LG)/8-21/2016/LAR: With the approval of Competent Authority, a Procurement committee consisting on following for under taking Development Schemes in Town Committee Madeji is hereby constituted under Section-7 of SPPRA Rules, 2010:-

- |  |          |
|--|----------|
| 1. Town Officer, TC, Madeji  | Chairman |
| 2. Assistant Executive Engineer, TC, Madeji                            | Member   |
| 3. Assistant Executive Engineer,<br>High way Sub Division Garhi Yaseen | Member   |

The Function and responsibilities of Procurement Committee shall be as under Section-7&8 of SPPRA Rule 2010):-

1. Preparing bidding documents.
2. Carrying out technical as well as financial evaluation of the bids.
3. Preparing evaluation report as provided in Rule 45.
4. Making recommendations for the award of contract to the competent authority, and
5. Perform any other function ancillary and incidental to the above.

-: SECRETARY TO GOVT. OF SINDH:-

NO.SOIV (LG)/8-21/2016/LAR


Karachi, dated the 08<sup>th</sup> August, 2017

A copy is forwarded for information and necessary action to:-

1. The Director, Sindh Public Procurement Regularity Authority, Karachi.
2. The Director, Local Government, Larkana.
3. The Assistant Director, Local Fund Audit, Shikarpur.
4. The Chairman / Town Officer, Town Committee Madeji, District Shikarpur.
5. Officers Concerned (Chairman/Members), Complaint Redressal Committee.
6. Office order file.

(LIAQUAT ALI MANGI)  
SECTION OFFICER-IV





GOVERNMENT OF SINDH  
LOCAL GOVERNMENT DEPARTMENT

Karachi dated the 08<sup>th</sup> August, 2017

NOTIFICATION

NO.SOIV (LG)/8-21/2016/LAR: With the approval of Competent Authority, a Complaint Redressal Committee, is hereby constituted under Rule-31(1)(2) of SPPRA, Rules-2010, of Town Committee Madeji, District Shikarpur during the year 2017-18:-

- |  |          |
|--|----------|
| 1. Chairman, TC, Madeji  | Chairman |
| 2. Assistant Executive Engineer, TC, Madeji                            | Member   |
| 3. Assistant Executive Engineer,<br>High way Sub Division Garhi Yaseen | Member   |

The Function and responsibilities of Complaint Redressal Committee shall be under Rule-31(1) (2) of SPPRA Rule-2010:-

: SECRETARY TO GOVT. OF SINDH.-

NO.SOIV (LG)/8-21/2016/LAR

Karachi, dated the 08<sup>th</sup> August, 2017

A copy is forwarded for information and necessary action to:-

1. The Director, Sindh Public Procurement Regularity Authority, Karachi.
2. The Director, Local Government, Larkana.
3. The Assistant Director, Local Fund Audit, Shikarpur.
- ✓ 4. The Chairman / Town Officer, Town Committee Madeji, District Shikarpur.
5. Officers Concerned (Chairman/Members), Complaint Redressal Committee.
6. Office order file.

(LIAQUAT ALI MANGI)  
SECTION OFFICER-IV

# SPPRA BIDDING DOCUMENT

STANDARD BIDDING DOCUMENT

PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 2.5 MILLION)

OFFICE OF THE CHAIRMAN  
TOWN COMMITTEE MADEJI  
District Shikarpur

*Standard Bidding Document* is intended as a model for admeasurements (Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.

## **Instructions to Bidders/ Procuring Agencies.**

### **General Rules and Directions for the Guidance of Contractors.**

This section of the bidding documents should provide the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring Agency. It should also give information on bid submission, opening and evaluation, and on the award of contract.

Matters governing the performance of the Contract or payments under the Contract, or matters affecting the risks, rights, and obligations of the parties under the Contract are included as Conditions of Contract and *Contract Data*.

The *Instructions to Bidders* will not be part of the Contract and will cease to have effect once the contract is signed.

1. All work proposed to be executed by contract shall be notified in a form of Notice Inviting Tender (NIT)/Invitation for Bid (IFB) hoisted on website of Authority and Procuring Agency and also in printed media where ever required as per rules.

NIT must state the description of the work, dates, time and place of issuing, submission, opening of bids, completion time, cost of bidding document and bid security either in lump sum or percentage of Estimated Cost/Bid Cost. The interested bidder must have valid NTN also.

2. Content of Bidding Documents must include but not limited to: Conditions of contract, Contract Data, specifications or its reference, Bill of Quantities containing description of items with scheduled/item rates with premium to be filled in form of percentage above/ below or on item rates to be quoted, Form of Agreement and drawings.

3. **Fixed Price Contracts:** The Bid prices and rates are fixed during currency of contract and under no circumstance shall any contractor be entitled to claim enhanced rates for any item in this contract.

4. The Procuring Agency shall have right of rejecting all or any of the tenders as per provisions of SPP Rules 2010.

5. **Conditional Offer:** Any person who submits a tender shall fill up the usual printed form stating at what percentage above or below on the rates specified in Bill of Quantities for items of work to be carried out: he is willing to undertake the work and also quote the rates for those items which are based on market rates. Only one rate of such percentage, on all the Scheduled Rates shall be framed. Tenders, which propose any alternative in the works specified in the said form of invitation to tender or in the time



allowed for carrying out the work, or which contain any other conditions, will be liable to rejection. No printed form of tender shall include a tender for more than one work, but if contractor wish to tender for two or more works, they shall submit a separate tender for each.

The envelope containing the tender documents shall refer the name and number of the work.

6. All works shall be measured by standard instruments according to the rules.
7. Bidders shall provide evidence of their eligibility as and when requested by the Procuring Agency.
8. Any bid received by the Agency after the deadline for submission of bids shall be rejected and returned unopened to the bidder.
9. Prior to the detailed evaluation of bids, the Procuring Agency will determine whether the bidder fulfills all codal requirements of eligibility criteria given in the tender notice such as registration with tax authorities, registration with PEC (where applicable), turnover statement, experience statement, and any other condition mentioned in the NIT and bidding document. If the bidder does not fulfill any of these conditions, it shall not be evaluated further.
10. Bid without bid security of required amount and prescribed form shall be rejected.
11. Bids determined to be substantially responsive shall be checked for any arithmetic errors. Arithmetical errors shall be rectified on the following basis;
  - (A) **In case of schedule rates**, the amount of percentage quoted above or below will be checked and added or subtracted from amount of bill of quantities to arrive the final bid cost.
  - (B) **In case of item rates**, .If there is a discrepancy between the unit rate and the total cost that is obtained by multiplying the unit rate and quantity, the unit rate shall prevail and the total cost will be corrected unless in the opinion of the Agency there is an obvious misplacement of the decimal point in the unit rate, in which case the total cost as quoted will govern and the unit rate corrected. If there is a discrepancy between the total bid amount and the sum of total costs, the sum of the total costs shall prevail and the total bid amount shall be corrected.
  - (C) Where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.



### **Conditions of Contract**

**Clause – 1: Commencement & Completion Dates of work.** The contractor shall not enter upon or commence any portion or work except with the written authority and instructions of the Engineer-in-charge or of in subordinate-in-charge of the work. Failing such authority the contractor shall have no claim to ask for measurements of or payment for work.

The contractor shall proceed with the works with due expedition and without delay and complete the works in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckoned from the date on which the order to commence work is given to the contractor. And further to ensure good progress during the execution of the work, contractor shall be bound, in all in which the time allowed for completion of any work exceeds one month, to achieve progress on the prorate basis.

**Clause – 2: Liquidated Damages.** The contractor shall pay liquidated damages to the Agency at the rate per day stated in the bidding data for each day that the completion date is later than the Intended completion date; the amount of liquidated damage paid by the contractor to the Agency shall not exceed 10 per cent of the contract price. Agency may deduct liquidated damages from payments due to the contractor. Payment of liquidated damages does not affect the contractor's liabilities.

### **Clause – 3: Termination of the Contract.**

**(A)** Procuring Agency/Executive Engineer may terminate the contract if either of the following conditions exists:-

- (i) contractor causes a breach of any clause of the Contract;
- (ii) the progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired;
- (iii) in the case of abandonment of the work owing to the serious illness or death of the contractor or any other cause.
- (iv) contractor can also request for termination of contract if a payment certified by the Engineer is not paid to the contractor within 60 days of the date of the submission of the bill;

**(B)** The Executive Engineer/Procuring Agency has power to adopt any of the following courses as may deem fit:-

- (i) to forfeit the security deposit available except conditions mentioned at A (iii) and (iv) above;
- (ii) to finalize the work by measuring the work done by the contractor.

(C) In the event of any of the above courses being adopted by the Executive Engineer/Procuring Agency, the contractor shall have:-

- (i) no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work or the performance of the contract,
- (ii) however, the contractor can claim for the work done at site duly certified by the executive engineer in writing regarding the performance of such work and has not been paid.

Procuring Agency/Engineer may invite fresh bids for remaining work.

**Clause 4: Possession of the site and claims for compensation for delay.** The Engineer shall give possession of all parts of the site to the contractor. If possession of site is not given by the date stated in the contract data, no compensation shall be allowed for any delay caused in starting of the work on account of any acquisition of land, water standing in borrow pits/ compartments or in according sanction to estimates. In such case, either date of commencement will be changed or period of completion is to be extended accordingly.

**Clause –5: Extension of Intended Completion Date.** The Procuring Agency either at its own initiatives before the date of completion or on desire of the contractor may extend the intended completion date, if an event (which hinders the execution of contract) occurs or a variation order is issued which makes it impossible to complete the work by the intended completion date for such period as he may think necessary or proper. The decision of the Executive Engineer in this matter shall be final; where time has been extended under this or any other clause of this agreement, the date for completion of the work shall be the date fixed by the order giving the extension or by the aggregate of all such orders, made under this agreement.

When time has been extended as aforesaid, it shall continue to be the essence of the contract and all clauses of the contract shall continue to be operative during the extended period.

**Clause –6: Specifications.** The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards materials and all other matters in strict accordance with the specifications lodged in the office of the Executive Engineer and initialed by the parties, the said specification being a part of the contract. The contractor shall also confirm exactly, fully and faithfully to the designs, drawing, and instructions in writing relating to the work signed by the Engineer-in-charge and lodge in his office and to which the contractor shall be entitled to have access at such office or on the site of work for the purpose of inspection during office hours and the contractor shall, if he so requires, be entitled at his own expense to make or cause to be made copies of the specifications, and of all such designs, drawings, and instructions as aforesaid.

**Clause – 7: Payments.**

- (A) **Interim/Running Bill.** A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill at least once in a month and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as far as admissible, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose countersignature to the measurement list will be sufficient to warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

The Engineer /Procuring Agency shall pass/certify the amount to be paid to the contractor, which he considers due and payable in respect thereof, subject to deduction of security deposit, advance payment if any made to him and taxes.

All such intermediate payment shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the Engineer-in-charge from recoveries from final bill and rectification of defects and unsatisfactory items of works pointed out to him during defect liability period.

- (B) **The Final Bill.** A bill shall be submitted by the contractor within one month of the date fixed for the completion of the work otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

**Clause – 8: Reduced Rates.** In cases where the items of work are not accepted as so completed, the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

**Clause – 9: Issuance of Variation and Repeat Orders.**

- (A) Agency may issue a Variation Order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plans, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.
- (B) Contractor shall not perform a variation until the Procuring Agency has authorized the variation in writing subject to the limit not exceeding the contract cost by of 15% on the same conditions in all respects on which he agreed to do them in the

work, and at the same rates, as are specified in the tender for the main work. The contractor has no right to claim for compensation by reason of alterations or curtailment of the work.

- (C) In case the nature of the work in the variation does not correspond with items in the Bill of Quantities, the quotation by the contractor is to be in the form of new rates for the relevant items of work, and if the Engineer-in-charge is satisfied that the rate quoted is within the rate worked out by him on detailed rate analysis, and then only he shall allow him that rate after approval from higher authority.
- (D) The time for the completion of the work shall be extended in the proportion that the additional work bear to the original contact work.
- (E) In case of quantities of work executed result the Initial Contract Price to be xceeded by more than 15%, and then Engineer can adjust the rates for those quantities causing excess the cost of contract beyond 15% after approval of Superintending Engineer.
- (F) **Repeat Order:** Any cumulative variation, beyond the 15% of initial contract amount, shall be subject of another contract to be tendered out if the works are separable from the original contract.

**Clause-10: Quality Control.**

- (A) **Identifying Defects:** If at any time before the security deposit is refunded to the contractor/during defect liability period mentioned in bid data, the Engineer-in-charge or his subordinate-in-charge of the work may instruct the contractor to uncover and test any part of the works which he considers may have a defect due to use of unsound materials or unskillful workmanship and the contractor has to carry out a test at his own cost irrespective of work already approved or paid.
- (B) **Correction of Defects:** The contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require. The contractor shall correct the notified defect within the Defects Correction Period mentioned in notice.
- (C) **Uncorrected Defects:**
  - (i) In the case of any such failure, the Engineer-in-charge shall give the contractor at least 14 days notice of his intention to use a third party to correct a defect. He may rectify or remove, and re-execute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor.

- (ii) If the Engineer considers that rectification/correction of a defect is not essential and it may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fix therefore.

**Clause – 11:**

- (A) **Inspection of Operations.** The Engineer and his subordinates, shall at all reasonable times have access to the site for supervision and inspection of works under or in course of execution in pursuance of the contract and the contractor shall afford every facility for and every assistance in obtaining the right to such access.
- (B) **Dates for Inspection and Testing.** The Engineer shall give the contractor reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, then he either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, orders given to the contractor's duly authorized agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

**Clause – 12: Examination of work before covering up.**

- (A) No part of the works shall be covered up or put out of view/beyond the reach without giving notice of not less than five days to the Engineer whenever any such part of the works or foundations is or are ready or about to be ready for examination and the Engineer shall, without delay, unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations;
- (B) If any work is covered up or placed beyond the reach of measurement without such notice having been given, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed.

**Clause – 13: Risks.** The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or related services at the premises and of personal injury and death which arise during and in consequence of its performance of the contract. if any damage is caused while the work is in progress or become apparent within three months of the grant of the certificate of completion, final or otherwise, the contractor shall make good the same at his own expense, or in default the Engineer may cause the same to be made good by other workmen, and deduct the expenses from retention money lying with the Engineer.



**Clause-14: Measures for prevention of fire and safety measures.** The contractor shall not set fire to any standing jungle, trees, bush-wood or grass without a written permit from the Executive Engineer. When such permit is given, and also in all cases when destroying, cutting or uprooting trees, bush-wood, grass, etc by fire, the contractor shall take necessary measures to prevent such fire spreading to or otherwise damaging surrounding property. The contractor is responsible for the safety of all its activities including protection of the environment on and off the site. Compensation of all damage done intentionally or unintentionally on or off the site by the contractor's labour shall be paid by him.

**Clause-15:Sub-contracting.** The contractor shall not subcontract the whole of the works, except where otherwise provided by the contract. The contractor shall not subcontract any part of the works without the prior consent of the Engineer. Any such consent shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts, defaults and neglects of any subcontractor, his agents, servants or workmen as if these acts, defaults or neglects were those of the contractor, his agents' servants or workmen. The provisions of this contract shall apply to such subcontractor or his employees as if he or it were employees of the contractor.

**Clause – 16: Disputes.** All disputes arising in connection with the present contract, and which cannot be amicably settled between the parties, , the decision of the Superintending Engineer of the circle/officer/one grade higher to awarding authority shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions, hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other questions, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, of failure to execute the same, whether arising, during the progress of the work, or after the completion or abandonment thereof.

**Clause –17: Site Clearance.** On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (hereinafter called the Engineer in-charge) of such completion, but neither such certificate shall be given nor shall the work be considered to be complete until the contractor shall have removed all temporary structures and materials brought at site either for use or for operation facilities including cleaning debris and dirt at the site. If the contractor fails to comply with the requirements of this clause then Engineer-in-charge, may at the expense of the contractor remove and dispose of the same as he thinks fit and shall deduct the amount of all expenses so incurred from the contractor's retention money. The contractor shall have no claim in respect of any surplus materials as aforesaid except for any sum actually realized by the sale thereof.



**Clause –18: Financial Assistance /Advance Payment.**

- (A) **Mobilization advance** is not allowed.
- (B) **Secured Advance against materials brought at site.**
- (i) Secured Advance may be permitted only against imperishable materials/quantities anticipated to be consumed/utilized on the work within a period of three months from the date of issue of secured advance and definitely not for full quantities of materials for the entire work/contract. The sum payable for such materials on site shall not exceed 75% of the market price of materials;
  - (ii) Recovery of Secured Advance paid to the contractor under the above provisions shall be affected from the monthly payments on actual consumption basis, but not later than period more than three months (even if unutilized).

**Clause –19: Recovery as arrears of Land Revenue.** Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

**Clause –20: Refund of Security Deposit/Retention Money.** On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurements are checked by a competent authority, if such check is necessary otherwise from the last date of recording the final measurements), the defects notice period has also passed and the Engineer has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor (in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

**Divisional Accountant**

**Contractor**

**Executive Engineer/Procuring Agency**

### BILL OF QUANTITIES

#### (A) Description and rate of Items based on Composite Schedule of Rates.

Item No	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1	2	3	4	5	6

Amount TOTAL (a)

----- % above/below on the rates of CSR.

Amount to be added/deducted on the basis  
Of premium quoted. TOTAL (b)

Total (A) = a+b in words & figures:

Contractor

Executive Engineer/Procuring Agency

**(B) Description and rate of Items based on Market (Offered rates)**

Item No	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees

**Total (B) in words & figures:**

Contractor

Executive Engineer/Procuring Agency

Summary of Bill of Quantities.

Cost of Bid

Amount

1. (A) Cost based on Composite Schedule of Rates.

2. (B) Cost based on Non/Offered Schedule of Rates.

TOTAL COST OF BID (C) = Total (A) + Total (B)

Contractor

Executive Engineer/Procuring Agency