



# SUKKUR MUNICIPAL CORPORATION

## SCHEDULE OF QUANTITIES

### WORK NO. 9

Estimated Cost: 0.352 (M) Penalty Per Day: 0.05 of Estimated Cost

Time Limit 6 Months Earnest Money: 17600.00 or 5%

Name of Work:

**PROVIDING AND INSTALLATION OF TUBE WELL BORING  
NEAR POLICE HEADQUARTER DISPOSAL STATION SMC**

S. No.	Item / Description	Qty	Rate	Unit	Amount
<b>Part-A Schedule Item</b>					
1	Boring for tube well in all water bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c sinking and with drawing of casing pipe. for 1st 100 Rft	100.0	535.00	P.Rft	53,500.00
	for Remaining 90 Rft	90.0	620.00	P.Rft	55,800.00
2	Supplying and installing PVC strainers 'B' class of approved design quality and make i/c necessary sockets etc. complete.	100.00	363.35	P.Rft	36,335.00
3	Supplying and installing M.S blind pipe 3/16" (5 mm) thick of best and approved quality and make i/c necessary sockets etc. complete.	90.00	762.50	P.Rft	68,625.00
4	G.I Pipe 1" dia	120.00	128.55	P.Rft	15,426.00
5	Shrouding with graded bajri (3/8" to 1/8") or (9 to 3 mm) in between bore and blind pipe for the following diameters of strainers.	60.00	82.00	P.Rft	4,920.00
<b>Total</b>					<b>234,606.00</b>

**Part-B Non Schedule Item**

6	Supplying and Fixing Motor Pump with i/c Connections with all accessroies and labour charges etc complete (MR)				
7	Making Electrification and Panel Board Switches etc i/c Electric Connections with all accessroies and labour charges etc complete (MR)				
8	Misc. Expenses required during execution of work (MR)				
<b>Total Part-B</b>					

  
**Executive Engineer**  
Sukkur Municipal Corporation

I / We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R  
(+) Open Rate Rs. \_\_\_\_\_ for complete work / job

The total amount is Rs.

(In figure)

Rupees:

(In Words)

Contractor's Signature \_\_\_\_\_

Name of Firm \_\_\_\_\_

Adress: \_\_\_\_\_