

**OFFICE OF THE EXECUTIVE ENGINEER (B&R)  
ORANGI ZONE DMC (WEST) KARACHI**

**Tel: 36697869 & 36660102**

NO.XEN/B&R/O.Z/DMC/W/08/2018

DATED. 21/02/2018

**TENDER NOTICE**

(Through Website of SPPRA & Orangi Zone DMC (West))

Tender in sealed covers are invited for the following work (s) under SPP Rules 2010 from the firms having adequate experience in the relevant field. The tentative cost of work is under Rs. 1.0 Million.

S. No	Name of Work	E/Cost Rs.	Bids Security 2%	Cost of Tender
1	Repairing of Sewerage Line in Sector 8/A, gali NO. 6, 9, 10, & 13 in Data Nagar in Orangi Zone, DMC (West).	Rs. 8,17,540/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
2	Repairing of Sewerage line & C.C street in Nasimabad & Al-Muslimabad Gali # 01,02, & 04 in Data Nagar in Orangi Zone, DMC (West).	Rs.8,54,960/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
3	Improvement of c.c street at ward # 4, and other work U.C-21, in Orangi Zone, DMC (West).	Rs.9,99,305/-	Rs. 20,000/-	Rs. 1000/-
4	Rehabilitation of c.c Flooring gali # 06, Agror Mollaha in U.C # 23,Orangi Zone DMC (West).	Rs.8,33,128/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
5	Improvement of R.c.c pipe & Main Hole Near Iqra State Agency Ward-1 Noorani Mollaha in U.C # 22 Orangi Zone D.M.C (West).	Rs.9,99,116/-	Rs. 20,000/-	Rs. 1000/-
6	Improvement of c.c Flooring at gali # 04 & 05, Agror Mollaha in U.C # 23 Orangi Zone, DMC (West).	Rs.8,39,210/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
7	Rehabilitation of c.c street near Madina Masjid and Eid Gah, Shah Mollaha # 2 and other area in U.C # 21Orangi Zone, D.M.C (West).	Rs.9,95,745/-	Rs. 20,000/-	Rs. 1000/-
8	Rehabilitation of c.c street near Shakir Ahmed House, Shah Mollaha and other area in U.C # 21, Orangi Zone, D.M.C (west)	Rs.9,94,725/-	Rs. 20,000/-	Rs. 1000/-

9	Rehabilitation of c.c street near Saeed Ahmed house, Shah Mollaha and other Area in U.C # 21, Orangi Zone , D.M.C (West).	Rs.9,97,325/-	Rs. 20,000/-	Rs. 1000/-
10	Rehabilitation of c.c street near Ali Shah House, Shah Mollaha and Other Area in U.C # 21, Orangi Zone, DMC (West).	Rs.9,95,825/-	Rs. 20,000/-	Rs. 1000/-
11	Rehabilitation of c.c street near Shahi Masjid (Mosque), Shah Mollaha # 1 and other Area in U.C # 21, Orangi Zone (west).	Rs.9,95,745/-	Rs. 20,000/-	Rs. 1000/-
12	Rehabilitation of c.c street near Faisal Masjid (Mosque), Shah Mollaha # 1 and other Area in U.C # 21, Orangi Zone (west).	Rs.9,94,785/-	Rs. 20,000/-	Rs. 1000/-
13	Rehabilitation & Improvement of Sewerage System & other work in Sector 11 ½ in Orangi Zone, DMC (West).	Rs. 7,18,630/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
14	Repairing / Improvement of Pot Holes & tranches and Other works in Orangi Zone, DMC (West).	Rs. 7,12,580/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
15	Repairing / Maintenance of Pot Holes near Gate # 04 & 06, of Ejtima Gah, in Orangi Zone, DMC (West).	Rs. 7,40,250/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
16	Repairing / Maintenance of Pot Holes near Gate # 07 of Ejtima Gah, in Orangi Zone, DMC (West).	Rs. 7,45,450/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
17	Repairing of Nallaha from Soni Cowk to Fatima-u-Zohar in U.C # 11, Orangi Zone, DMC (West).	Rs. 8,89,340/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
18	Rehabilitation of Sewerage Line in Gali # 12, Sector 7-F Shah Faisal Mollaha, Baloch Goth, Orangi Zone, DMC (West).	Rs. 8,75,755/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
19	Repairing of c.c Flooring gali No. 11, Shaheed Chacha Abdul Ghani Sector 7-F Shah Faisal Mollaha Baloch Goth U.C # 11 Orangi Zone, DMC (West).	Rs. 7,74,802/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
20	Replacement of Broken Sewerage pipe line Different Masjid in U.C # 38 & 39, Surjani, Orangi Zone, D.M.C (West).	Rs. 9,98,220/-	Rs. 20,000/-	Rs. 1000/-
21	Repair & Maintenance of Sewerage System Back Side Deyar-e-Habib Masjid & Back Side of Qatar Hospital and varies places in Orangi, Zone, DMC (West).	Rs. 7,59,241/- + Open Rate	Rs. 20,000/-	Rs. 1000/-

22	Rehabilitation and Improvement of Sewerage System Different Areas Orangi Zone, DMC (West).	Rs. 7,59,241/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
23	Hiring of Machinery for cleaning of Nallaha in U.C # 11, 12, 13, Orangi Zone, DMC (West).	Rs. 6,70,000/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
24	Hiring of Private Labour in Cleaning of Nallaha Thorani Goth Rehmat Chowk & Other Work & other Places in Orangi Zone, DMC (West).	Rs. 7,30,000/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
25	Hiring of Machinery for cleaning of Nallaha in Block L & Other Work in Ali Garah Colony Culvert Orangi Zone, DMC (West).	Rs. 6,90,770/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
26	Hiring of Private Labour & Machinery for Cleaning of Nallaha and Other Places in U.C # 38, Surjani Town Orangi Zone, DMC (West).	Rs. 7,50,143/- + Open Rate	Rs. 20,000/-	Rs. 1000/-
27	Improvement / Repairing of Pot Holes & Tranches near Karimi Chowrangi and other places in U.C # 39, Surjani Town, Orangi Zone, D.M.C. (West).	Rs. 7,50,143/- + Open Rate	Rs. 20,000/-	Rs. 1000/-

**Terms & Conditions: -**

1. Tender Schedule Shall be as follows.

SCHEDULE	DATE & TIME	VENUE
Receiving of Application & Issuance of Tenders	22/02/2018 to 11/03/2018 During Office Hours	DMC (West) ORANGI Zone Office Sector 11-E Shahrah-e-Orangi Karachi
Dropping of Tenders	12/03/2018 11:30 A.M	Executive Engineer Orangi Zone DMC (West) Office
Opening of Tenders	12/03/2018 12:00 Noon	Executive Engineer Orangi Zone DMC (West) Office

2. The tender documents will be issued to contractor on submission of written request on letter head and on payment of non-refundable cost of tender price through pay order from Sindh Bank in favour of Orangi Zone DMC (West).
3. The Bid Security as mentioned above in shape of pay order in favour of Orangi Zone DMC (West) shall must be enclosed with tender documents without which the tender will be treated as cancelled.
4. In case the date of opening is declared as a public holiday by the Government, the next official working day shall be deemed to be the date for submission and opening of tenders at the same time as mentioned.
5. The total bid amount as well as the rates of items must be filled both in figures and words and in case any correction is made by the contractor himself then each correction must be initialed by the contractor; otherwise the tenders are liable to be summarily rejected.

6. The bidder are required to submit the above information along with their bid.
7. If any fake documents are found then the tender is liable to be rejected / cancelled without any compensation but with penalty as per rules.
8. Canvassing in connection with tenders is strictly prohibited and tenders submitted by the contractors who are reported to be involved in canvassing will be liable for rejection.
9. Bid Security of the unsuccessful bidder shall be released once the contractor has been signed with the successful bidder or the validity period has expired.
10. The Procuring agency may reject all or any bid subject to the relevant provisions of SPPRA Rules 2010.
11. Eligibility
  - i. NTN Certificate
  - ii. Valid Professional Tax
  - iii. S.R.B Certificate
  - iv. Bank Statement
  - v. Relevant Experience
  - vi. Turn Over of at least three years



**EXECUTIVE ENGINEER (B&R)**  
**ORANGI ZONE DMC (WEST)**  
EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)

**Not to be published**

**Director (CB) SPPRA**

With a request to upload on SPPRA (Authority) website and issue ID Number

**Incharge (I.T), Orangi Zone DMC (West)**

With a request to upload on Orangi Zone DMC (West) Website


**Copy to: -**

1. Administrator DMC (West)
2. P.S to Managing Director SPPRA
3. Office File



**ANNUAL PROCUREMENT PLAN  
(DISTRICT MUNICIPAL CORPORATION WEST)  
FINANCIAL YEAR 2017-2018**

S.No	Name of Scheme	Allocated Funds	Cost of ongoing works (Expenditure already incurred)	Funds earmarked for ongoing works	Cost of New Work (components)	Funds for new works (c-e)	Nature of Procurement	Method of Procurement	Anticipated/ Actual Date of Advertisement	Anticipated/ Actual Date of Start
a	b	c	d	e	f	g	h	i	j	k
1	Repairing of Sewerage Line in Sector 8/A, gali NO. 6, 9, 10, & 13 in Data Nagar in Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	8,17,540/- + Open Rate	8,17,540/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
2	Repairing of Sewerage line & C.C street in Nasimabad & Al-Muslimabad Gali # 01,02, & 04 in Data Nagar in Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	8,54,960/- + Open Rate	8,54,960/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
3	Improvement of c.c street at ward # 4, and other work U.C-21, in Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	9,99,305/-	9,99,305/-	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
4	Rehabilitation of c.c Flooring gali # 06, Agror Mollaha in U.C # 23, Orangi Zone DMC (West).	10,00,000	10,00,000	-----	8,33,128/- + Open Rate	8,33,128/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
5	Improvement of R.c.c pipe & Main Hole Near Iqra State Agency Ward-1 Noorani Mollaha in U.C # 22 Orangi Zone D.M.C (West).	10,00,000	10,00,000	-----	9,99,116/- + Open Rate	9,99,116/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
6	Improvement of c.c Flooring at gali # 04 & 05, Agror Mollaha in U.C # 23 Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	8,39,210/- + Open Rate	8,39,210/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
7	Rehabilitation of c.c street near Madina Masjid and Eid Gah, Shah Mollaha # 2 and other area in U.C # 21 Orangi Zone, D.M.C (West).	10,00,000	10,00,000	-----	9,95,745/-	9,95,745/-	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course

  
**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

8	Rehabilitation of c.c street near Shakir Ahmed House, Shah Mollaha and other area in U.C # 21, Orangi Zone, D.M.C (west)	10,00,000	10,00,000	-----	9,94,725/-	9,94,725/-	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
9	Rehabilitation of c.c street near Saeed Ahmed house, Shah Mollaha and other Area in U.C # 21, Orangi Zone , D.M.C (West).	10,00,000	10,00,000	-----	9,97,325/-	9,97,325/-	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
10	Rehabilitation of c.c street near Ali Shah House, Shah Mollaha and Other Area in U.C # 21, Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	9,95,825/-	9,95,825/-	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
11	Rehabilitation of c.c street near Shahi Masjid (Mosque), Shah Mollaha # 1 and other Area in U.C # 21, Orangi Zone (west).	10,00,000	10,00,000	-----	9,95,745/-	9,95,745/-	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
12	Rehabilitation of c.c street near Faisal Masjid (Mosque), Shah Mollaha # 1 and other Area in U.C # 21, Orangi Zone (west).	10,00,000	10,00,000	-----	9,94,785/-	9,94,785/-	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
13	Rehabilitation & Improvement of Sewerage System & other work in Sector 11 ½ in Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	7,18,630/- + Open Rate	7,18,630/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
14	Repairing / Improvement of Pot Holes & tranches and Other works in Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	7,12,580/- + Open Rate	7,12,580/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
15	Repairing / Maintenance of Pot Holes near Gate # 04 & 06, of Ejtima Gah, in Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	7,40,250/- + Open Rate	7,40,250/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
16	Repairing / Maintenance of Pot Holes near Gate # 07 of Ejtima Gah, in Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	7,45,450/- + Open Rate	7,45,450/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
17	Repairing of Nallaha from Soni Cowk to Fatima-u-Zohar in U.C # 11, Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	8,89,340/- + Open Rate	8,89,340/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
18	Rehabilitation of Sewerage Line in Gali # 12, Sector 7-F Shah Faisal Mollaha, Baloch Goth, Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	8,75,755/- + Open Rate	8,75,755/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course

  
**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

19	Repairing of c.c Flooring gali No. 11, Shaheed Chacha Abdul Ghani Sector	10,00,000	10,00,000	-----	7,74,802/- + Open Rate	7,74,802/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
20	Replacement of Broken Sewerage pipe line Different Masjid in U.C # 38 & 39, Surjani, Orangi Zone, D.M.C (West).	10,00,000	10,00,000	-----	9,98,220/- +	9,98,220/- +	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
21	Repair & Maintenance of Sewerage System Back Side Deyar-e-Habib Masjid & Back Side of Qatar Hospital and varies places in Orangi,	10,00,000	10,00,000	-----	7,59,241/- + Open Rate	7,59,241/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
22	Rehabilitation and Improvement of Sewerage System Different Areas Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	7,59,241/- + Open Rate	7,59,241/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
23	Hiring of Machinery for cleaning of Nallaha in U.C # 11, 12, 13, Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	6,70,000/- + Open Rate	6,70,000/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
24	Hiring of Private Labour in Cleaning of Nallaha Thorani Goth Rehmat Chowk & Other Work & other Places in Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	7,30,000/- + Open Rate	7,30,000/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
25	Hiring of Machinery for cleaning of Nallaha in Block L & Other Work in Ali Garah Colony Culvert Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	6,90,770/- + Open Rate	6,90,770/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
26	Hiring of Private Labour & Machinery for Cleaning of Nallaha and Other Places in U.C # 38, Surjani Town Orangi Zone, DMC (West).	10,00,000	10,00,000	-----	7,50,143/- + Open Rate	7,50,143/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course
27	Improvement / Repairing of Pot Holes & Tranches near Karimi Chowrangi and other places in U.C # 39, Surjani Town, Orangi Zone,	10,00,000	10,00,000	-----	7,50,143/- + Open Rate	7,50,143/- + Open Rate	Works and Services	SPPRA Rule 15(b) & 16	21.02.2018	In due course

  
**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)



**DISTRICT MUNICIPAL CORPORATION KARACHI WEST**  
**SECTOR 11-E SHAHRAH-E-ORANGI**  
TEL: 36697869 & 36660102  
FAX: 36762519

No: M.C/DMC/W/P.S/ 55 /2017

Dated: 09/03/2017

To,

The Secretary,  
Local Government Department,  
Government of Sindh,  
KARACHI.

**PROCUREMENT COMMITTEE**

In accordance with Rule-7 of Sindh Public Procurement Rules 2010 a procurement committee comprising following officers is hereby constitute.

**DISTRICT MUNICIPAL CORPORATION SITE ZONE**

- |    |  |           |
|----|--|-----------|
| 1. | Superintending Engineer DMC (West) BS-19                   | Chairman  |
| 2. | Executive Engineer / Director (Concerned) DMC (West) BS-18 | Secretary |
| 3. | Executive Engineer (Sewerage) KW&SB BS-18                  | Member    |

**DISTRICT MUNICIPAL CORPORATION ORANGI ZONE**

- |    |  |           |
|----|--|-----------|
| 1. | Superintending Engineer DMC (West) BS-19                   | Chairman  |
| 2. | Executive Engineer / Director (Concerned) DMC (West) BS-18 | Secretary |
| 3. | Assistant Director S.B.C.A BS-18                           | Member    |

**DISTRICT MUNICIPAL CORPORATION KEAMARI ZONE**

- |    |  |           |
|----|--|-----------|
| 1. | Superintending Engineer DMC (West) BS-19                   | Chairman  |
| 2. | Executive Engineer / Director (Concerned) DMC (West) BS-18 | Secretary |
| 3. | Executive Engineer (Sewerage) KW&SB BS-18                  | Member    |


**DISTRICT MUNICIPAL CORPORATION BALDIA ZONE**

- |    |  |           |
|----|--|-----------|
| 1. | Superintending Engineer DMC (West) BS-19                   | Chairman  |
| 2. | Executive Engineer / Director (Concerned) DMC (West) BS-18 | Secretary |
| 3. | Executive Engineer (Sewerage) KW&SB BS-18                  | Member    |

Function and responsibilities of procurement committee is as under.

1. Preparing bidding documents
2. Carrying out technical as well as financial evaluation of the bids
3. Preparing evaluation report as provided in Rule-45
4. Making recommendation for the award of contract to the competent authority
5. Perform any other function ancillary and incidental to the above.

The committee so constituted will be responsible to act strictly in accordance with Sindh  
Public Procurement Rules.



MUNICIPAL COMMISSIONER  
DISTRICT MUNICIPAL CORPORATION  
(WEST) KARACHI

Copy to: -

1. Superintending Engineer DMC (West)
2. XEN (B&R) Concerned Zone
3. XEN (Sewerage) KW&SB (West)
4. Assistant Director S.B.C.A
5. R.A.O (L.F.A) SITE Zone DMC (West)



**OFFICE OF THE MUNICIPAL COMMISSIONER**  
**DISTRICT MUNICIPAL CORPORATION KARACHI WEST**

No: M.C/DMC/W/P.S/ 54 /20

Dated: 9/3/17

To,

The Secretary,  
Local Government Department,  
Government of Sindh,  
KARACHI.

**REDRESSAL COMMITTEE 2017**

A Complaint redressal committee is hereby constituted with following composition to resolve the greivences & Settlement of disputes and adress the complaints of bidders as per Rule-31 of SPPRA Rules 2010 amended 2013 regarding NIT's of D.M.C (West) Karachi.

- |  |          |
|--|----------|
| 1. Administrator DMC (West) Karachi            | Chairman |
| 2. Additional Account Officer AG Sindh Karachi | Member   |
| 3. Superintending Engineer DMC (West) Karachi  | Member   |

The terms & Condition of committee are same as mentioned vide rule-31 of SPPRA rule 2010 amended 2013.

Municipal Commissioner  
DISTRICT MUNICIPAL CORPORATION  
(WEST) KARACHI

Copy to: -

1. Deputy Director (Enf-I) SPPRA Govt. Karachi
2. Superintending Engineer DMC (West)
3. Additional Account Officer AG Sindh Karachi



# SPPRA BIDDING DOCUMENT

STANDARD BIDDING DOCUMENT

PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

*Standard Bidding Document* is intended as a model for admeasurements (Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.



## Instructions to Bidders/ Procuring Agencies.

### General Rules and Directions for the Guidance of Contractors.

This section of the bidding documents should provide the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring Agency. It should also give information on bid submission, opening and evaluation, and on the award of contract.

Matters governing the performance of the Contract or payments under the Contract, or matters affecting the risks, rights, and obligations of the parties under the Contract are included as Conditions of Contract and *Contract Data*.

The *Instructions to Bidders* will not be part of the Contract and will cease to have effect once the contract is signed.

1. All work proposed to be executed by contract shall be notified in a form of Notice Inviting Tender (NIT)/Invitation for Bid (IFB) hoisted on website of Authority and Procuring Agency and also in printed media where ever required as per rules.

NIT must state the description of the work, dates, time and place of issuing, submission, opening of bids, completion time, cost of bidding document and bid security either in lump sum or percentage of Estimated Cost/Bid Cost. The interested bidder must have valid NTN also.

2. Content of Bidding Documents must include but not limited to: Conditions of contract, Contract Data, specifications or its reference, Bill of Quantities containing description of items with scheduled/item rates with premium to be filled in form of percentage above/ below or on item rates to be quoted, Form of Agreement and drawings.

3. **Fixed Price Contracts:** The Bid prices and rates are fixed during currency of contract and under no circumstance shall any contractor be entitled to claim enhanced rates for any item in this contract.

4. The Procuring Agency shall have right of rejecting all or any of the tenders as per provisions of SPP Rules 2010.

5. **Conditional Offer:** Any person who submits a tender shall fill up the usual printed form stating at what percentage above or below on the rates specified in Bill of Quantities for items of work to be carried out: he is willing to undertake the work and also quote the rates for those items which are based on market rates. Only one rate of such percentage, on all the Scheduled Rates shall be framed. Tenders, which propose any alternative in the works specified in the said form of invitation to tender or in the time

allowed for carrying out the work, or which contain any other conditions, will be liable to rejection. No printed form of tender shall include a tender for more than one work, but if contractor wish to tender for two or more works, they shall submit a separate tender for each.

The envelope containing the tender documents shall refer the name and number of the work.

6. All works shall be measured by standard instruments according to the rules.
7. Bidders shall provide evidence of their eligibility as and when requested by the Procuring Agency.
8. Any bid received by the Agency after the deadline for submission of bids shall be rejected and returned unopened to the bidder.
9. Prior to the detailed evaluation of bids, the Procuring Agency will determine whether the bidder fulfills all codal requirements of eligibility criteria given in the tender notice such as registration with tax authorities, registration with PEC (where applicable), turnover statement, experience statement, and any other condition mentioned in the NIT and bidding document. If the bidder does not fulfill any of these conditions, it shall not be evaluated further.
10. Bid without bid security of required amount and prescribed form shall be rejected.
11. Bids determined to be substantially responsive shall be checked for any arithmetic errors. Arithmetical errors shall be rectified on the following basis;
  - (A) **In case of schedule rates**, the amount of percentage quoted above or below will be checked and added or subtracted from amount of bill of quantities to arrive the final bid cost.
  - (B) **In case of item rates**, .If there is a discrepancy between the unit rate and the total cost that is obtained by multiplying the unit rate and quantity, the unit rate shall prevail and the total cost will be corrected unless in the opinion of the Agency there is an obvious misplacement of the decimal point in the unit rate, in which case the total cost as quoted will govern and the unit rate corrected. If there is a discrepancy between the total bid amount and the sum of total costs, the sum of the total costs shall prevail and the total bid amount shall be corrected.
  - (C) Where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.



## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency \_\_\_\_\_
- (b). Brief Description of Works \_\_\_\_\_
- (c). Procuring Agency's address:- \_\_\_\_\_
- (d). Estimated Cost:- \_\_\_\_\_
- (e). Amount of Bid Security:- \_\_\_\_\_ (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):- \_\_\_\_\_ (Not more than sixty days).
- (g). Security Deposit:-(including bid security):- \_\_\_\_\_  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :- \_\_\_\_\_
- (i). Deadline for Submission of Bids along with time :- \_\_\_\_\_
- (j). Venue, Time, and Date of Bid Opening:- \_\_\_\_\_
- (k). Time for Completion from written order of commence: - \_\_\_\_\_
- (L). Liquidity damages:- \_\_\_\_\_ (0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:(in words and figures)

(Executive Engineer/Authority issuing bidding document)

### Conditions of Contract

**Clause – 1: Commencement & Completion Dates of work.** The contractor shall not enter upon or commence any portion or work except with the written authority and instructions of the Engineer-in-charge or of in subordinate-in-charge of the work. Failing such authority the contractor shall have no claim to ask for measurements of or payment for work.

The contractor shall proceed with the works with due expedition and without delay and complete the works in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckoned from the date on which the order to commence work is given to the contractor. And further to ensure good progress during the execution of the work, contractor shall be bound, in all in which the time allowed for completion of any work exceeds one month, to achieve progress on the prorate basis.

**Clause – 2: Liquidated Damages.** The contractor shall pay liquidated damages to the Agency at the rate per day stated in the bidding data for each day that the completion date is later than the Intended completion date; the amount of liquidated damage paid by the contractor to the Agency shall not exceed 10 per cent of the contract price. Agency may deduct liquidated damages from payments due to the contractor. Payment of liquidated damages does not affect the contractor's liabilities.

#### **Clause – 3: Termination of the Contract.**

- (A) Procuring Agency/Executive Engineer may terminate the contract if either of the following conditions exists:-
- (i) contractor causes a breach of any clause of the Contract;
  - (ii) the progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired;
  - (iii) in the case of abandonment of the work owing to the serious illness or death of the contractor or any other cause.
  - (iv) contractor can also request for termination of contract if a payment certified by the Engineer is not paid to the contractor within 60 days of the date of the submission of the bill;
- (B) The Executive Engineer/Procuring Agency has power to adopt any of the following courses as may deem fit:-
- (i) to forfeit the security deposit available except conditions mentioned at A (iii) and (iv) above;
  - (ii) to finalize the work by measuring the work done by the contractor.



- (C) In the event of any of the above courses being adopted by the Executive Engineer/Procuring Agency, the contractor shall have:-
- (i) no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work or the performance of the contract,
  - (ii) however, the contractor can claim for the work done at site duly certified by the executive engineer in writing regarding the performance of such work and has not been paid.
- Procuring Agency/Engineer may invite fresh bids for remaining work.

**Clause 4: Possession of the site and claims for compensation for delay.** The Engineer shall give possession of all parts of the site to the contractor. If possession of site is not given by the date stated in the contract data, no compensation shall be allowed for any delay caused in starting of the work on account of any acquisition of land, water-standing in borrow pits/ compartments or in according sanction to estimates. In such case, either date of commencement will be changed or period of completion is to be extended accordingly.

**Clause -5: Extension of Intended Completion Date.** The Procuring Agency either at its own initiatives before the date of completion or on desire of the contractor may extend the intended completion date, if an event (which hinders the execution of contract) occurs or a variation order is issued which makes it impossible to complete the work by the intended completion date for such period as he may think necessary or proper. The decision of the Executive Engineer in this matter shall be final; where time has been extended under this or any other clause of this agreement, the date for completion of the work shall be the date fixed by the order giving the extension or by the aggregate of all such orders, made under this agreement.

When time has been extended as aforesaid, it shall continue to be the essence of the contract and all clauses of the contract shall continue to be operative during the extended period.

**Clause -6: Specifications.** The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards materials and all other matters in strict accordance with the specifications lodged in the office of the Executive Engineer and initialed by the parties, the said specification being a part of the contract. The contractor shall also confirm exactly, fully and faithfully to the designs, drawing, and instructions in writing relating to the work signed by the Engineer-in-charge and lodge in his office and to which the contractor shall be entitled to have access at such office or on the site of work for the purpose of inspection during office hours and the contractor shall, if he so requires, be entitled at his own expense to make or cause to be made copies of the specifications, and of all such designs, drawings, and instructions as aforesaid.

**Clause – 7: Payments.**

- (A) **Interim/Running Bill.** A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill at least once in a month and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as far as admissible, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose countersignature to the measurement list will be sufficient to warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

The Engineer /Procuring Agency shall pass/certify the amount to be paid to the contractor, which he considers due and payable in respect thereof, subject to deduction of security deposit, advance payment if any made to him and taxes.

All such intermediate payment shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the Engineer-in-charge from recoveries from final bill and rectification of defects and unsatisfactory items of works pointed out to him during defect liability period.

- (B) **The Final Bill.** A bill shall be submitted by the contractor within one month of the date fixed for the completion of the work otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

**Clause – 8: Reduced Rates.** In cases where the items of work are not accepted as so completed, the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

**Clause – 9: Issuance of Variation and Repeat Orders.**

- (A) Agency may issue a Variation Order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plans, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.
- (B) Contractor shall not perform a variation until the Procuring Agency has authorized the variation in writing subject to the limit not exceeding the contract cost by of 15% on the same conditions in all respects on which he agreed to do them in the



work, and at the same rates, as are specified in the tender for the main work. The contractor has no right to claim for compensation by reason of alterations or curtailment of the work.

- (C) In case the nature of the work in the variation does not correspond with items in the Bill of Quantities, the quotation by the contractor is to be in the form of new rates for the relevant items of work, and if the Engineer-in-charge is satisfied that the rate quoted is within the rate worked out by him on detailed rate analysis, and then only he shall allow him that rate after approval from higher authority.
- (D) The time for the completion of the work shall be extended in the proportion that the additional work bear to the original contract work.
- (E) In case of quantities of work executed result the Initial Contract Price to be exceeded by more than 15%, and then Engineer can adjust the rates for those quantities causing excess the cost of contract beyond 15% after approval of Superintending Engineer.
- (F) **Repeat Order:** Any cumulative variation, beyond the 15% of initial contract amount, shall be subject of another contract to be tendered out if the works are separable from the original contract.

**Clause-10: Quality Control.**

- (A) **Identifying Defects:** If at any time before the security deposit is refunded to the contractor/during defect liability period mentioned in bid data, the Engineer-in-charge or his subordinate-in-charge of the work may instruct the contractor to uncover and test any part of the works which he considers may have a defect due to use of unsound materials or unskillful workmanship and the contractor has to carry out a test at his own cost irrespective of work already approved or paid.
- (B) **Correction of Defects:** The contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require. The contractor shall correct the notified defect within the Defects Correction Period mentioned in notice.
- (C) **Uncorrected Defects:**
  - (i) In the case of any such failure, the Engineer-in-charge shall give the contractor at least 14 days notice of his intention to use a third party to correct a defect. He may rectify or remove, and re-execute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor.



- (ii) If the Engineer considers that rectification/correction of a defect is not essential and it may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fix therefore.

**Clause – 11:**

- (A) **Inspection of Operations.** The Engineer and his subordinates, shall at all reasonable times have access to the site for supervision and inspection of works under or in course of execution in pursuance of the contract and the contractor shall afford every facility for and every assistance in obtaining the right to such access.
- (B) **Dates for Inspection and Testing.** The Engineer shall give the contractor reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, then he either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, orders given to the contractor's duly authorized agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

**Clause – 12: Examination of work before covering up.**

- (A) No part of the works shall be covered up or put out of view/beyond the reach without giving notice of not less than five days to the Engineer whenever any such part of the works or foundations is or are ready or about to be ready for examination and the Engineer shall, without delay, unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations;
- (B) If any work is covered up or placed beyond the reach of measurement without such notice having been given, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed.

**Clause – 13: Risks.** The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or related services at the premises and of personal injury and death which arise during and in consequence of its performance of the contract. if any damage is caused while the work is in progress or become apparent within three months of the grant of the certificate of completion, final or otherwise, the contractor shall make good the same at his own expense, or in default the Engineer may cause the same to be made good by other workmen, and deduct the expenses from retention money lying with the Engineer.

**Clause-14: Measures for prevention of fire and safety measures.** The contractor shall not set fire to any standing jungle, trees, bush-wood or grass without a written permit from the Executive Engineer. When such permit is given, and also in all cases when destroying, cutting or uprooting trees, bush-wood, grass, etc by fire, the contractor shall take necessary measures to prevent such fire spreading to or otherwise damaging surrounding property. The contractor is responsible for the safety of all its activities including protection of the environment on and off the site. Compensation of all damage done intentionally or unintentionally on or off the site by the contractor's labour shall be paid by him.

**Clause-15:Sub-contracting.** The contractor shall not subcontract the whole of the works, except where otherwise provided by the contract. The contractor shall not subcontract any part of the works without the prior consent of the Engineer. Any such consent shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts, defaults and neglects of any subcontractor, his agents, servants or workmen as if these acts, defaults or neglects were those of the contractor, his agents' servants or workmen. The provisions of this contract shall apply to such subcontractor or his employees as if he or it were employees of the contractor.

**Clause - 16: Disputes.** All disputes arising in connection with the present contract, and which cannot be amicably settled between the parties, , the decision of the Superintending Engineer of the circle/officer/one grade higher to awarding authority shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions, hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other questions, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, of failure to execute the same, whether arising, during the progress of the work, or after the completion or abandonment thereof.


**Clause -17: Site Clearance.** On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (hereinafter called the Engineer in-charge) of such completion, but neither such certificate shall be given nor shall the work be considered to be complete until the contractor shall have removed all temporary structures and materials brought at site either for use or for operation facilities including cleaning debris and dirt at the site. If the contractor fails to comply with the requirements of this clause then Engineer-in-charge, may at the expense of the contractor remove and dispose of the same as he thinks fit and shall deduct the amount of all expenses so incurred from the contractor's retention money. The contractor shall have no claim in respect of any surplus materials as aforesaid except for any sum actually realized by the sale thereof.

**Clause -18: Financial Assistance /Advance Payment.**

- (A) **Mobilization advance** is not allowed.
- (B) **Secured Advance against materials brought at site.**
- (i) Secured Advance may be permitted only against imperishable materials/quantities anticipated to be consumed/utilized on the work within a period of three months from the date of issue of secured advance and definitely not for full quantities of materials for the entire work/contract. The sum payable for such materials on site shall not exceed 75% of the market price of materials;
- (ii) Recovery of Secured Advance paid to the contractor under the above provisions shall be affected from the monthly payments on actual consumption basis, but not later than period more than three months (even if unutilized).

**Clause -19: Recovery as arrears of Land Revenue.** Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

**Clause -20: Refund of Security Deposit/Retention Money.** On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurements are checked by a competent authority, if such check is necessary otherwise from the last date of recording the final measurements), the defects notice period has also passed and the Engineer has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor (in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

  
Divisional Accountant Accountant  
(B&R) Orangi Zone  
D.M.C. (WEST)

Contractor

  
Executive Engineer/Procuring Agency

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



**SCHEDULE OF QUANTITIES**

**WORK NO: 01**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 8,17,540 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Repairing of Sewerage Line in Sector 8/A, gali NO. 6, 9, 10, & 13  
in Data Nagar in Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	1706 Cft	3327.50	%Cft	56,767.00
2.	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape traveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guard light flags and temporary crossing for non vehicular traffic wherever required left upto 05' and lead upto 01 chain.	3938 Cft	4650.00	1000 Cft	18,312.00
3.	P/L R.C.C. rubber ring pipe of class "A" and fixing in trenches i/c cutting, fitting and jointing with rubber ring etc complete. .....15" Dia.....	750 Rft	367.00	P/Rft	2,75,250.00
4.	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 CC in 9" thick wall and beding cast in situ with fair face steel shuttering i/c excavation, back filling and disposal of surplus stuff etc.	35 Nos.	13064.0 0	Each	4,57,240.00
5.	Add for extra depth beyond 5' depth, less than 5' depth deduct at the same rate.	(-) 52.4972 Rft	1540.00	P/Rft	(-) 80,846.00
6.	Refilling of excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	3018 Cft	2760.00	1000 Cft	8,330.00

(2)

7.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	2598 Cft	1065.00	%Cft	27,669.00
8.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	60 Nos.	913.63	Each	54,818.00
9.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	50 Nos.	O/R	Each	O/R
<b>Total Estimated Cost</b>					<b>8,17,540 (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
ORANGI ZONE

**EXECUTIVE ENGINEER**  
Building and Roads  
Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

3)

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 02**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 8,54,960 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Repairing of Sewerage line & C.C street in Nasimabad & Al-Muslimabad Gali # 01,02, & 04 in Data Nagar in Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	1031 Cft	3327.50	%Cft	34,307.00
2.	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape traveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guard light flags and temporary crossing for non vehicular traffic wherever required left upto 05' and lead upto 01 chain.	789 Cft	4650.00	1000 Cft	3,669.00
3.	Excavation for pipe line in trenches and pits in soft rock by hammering and chiesling i/c alignment and shape level and grade cutting joint holes and disposal of surplus earth within one chain as directed by Engineer Incharge.	875 Cft	10770.00	1000 Cft	9,424.00
4.	P/L R.C.C. rubber ring pipe of class "A" and fixing in trenches i/c cutting, fitting and jointing with rubber ring etc complete. .....15" Dia.....	350 Rft	367.00	P/Rft	1,28,450.00
5.	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 CC in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation, back filling and disposal of surplus stuff etc.	20 Nos.	13064.00	Each	2,61,280.00
6.	Add for extra depth beyond 5' depth, less than 5' depth deduct at the same rate.	(-) 29,998 Rft	1540.00	P/Rft	(-) 46,197.00



7.	Refilling of excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	1234 Cft	2760.00	1000 Cft	3,406.00
8.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	1566 Cft	1065.00	%Cft	16,678.00
9.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	60 Nos.	913.63	Each	54,818.00
10.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	7000 Sft	526.28	%Sft	36,840.00
11.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	7000 Sft	3275.50	% Sft	2,29,285.00
12.	P/L Granular sub-base course material over prepared sub-grade in grade, thickness and typical cross sections for new grade / widening existing pavement using well graded granular stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	750 Cft	O/R	P/Cft	O/R
13.	P/L Aggregate base course material over prepared sub-grade in grade, thickness and typical cross sections grade / widening existing pavement using well graded crushed stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	1350 Cft	O/R	P/Cft	O/R
14.	Extra for using (S.R Cement sulphate resistant cement in place of ordinary Portland cement.	202 CWT	O/R	% Cwt	O/R
15.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.( Markeet Rate)	41 Nos.	3000.00	Each	1,23,000.00
<b>Total Estimated Cost</b>					<b>8,54,960 (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
 ORANGI ZONE  
 EXECUTIVE ENGINEER  
 Building and Roads  
 Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R

**SCHEDULE OF QUANTITIES**  
**WORK NO: 03**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 9,99,305/-

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Improvement of c.c street at ward # 4, in U.C-21, in Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2250 Cft	3327.50	%Cft	74,869.00
2.	Dismantling of cement concrete 1:3:6 plain flooring.	1200 Cft	1306.80	%Cft	15,682.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	7950 Cft	1065.00	%Cft	84,668.00
4.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	8500 Sft	526.28	%Sft	44,734.00
5.	P/L 1:4:8 CC using GSB 2" to 3" and i/c leveling compacting, curing etc complete without shuttering.	2125 Cft	11288.75	% Cft	2,39,886.00
6.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	8500 Sft	3275.50	% Sft	2,78,418.00
7.	Extra for using (S.R Cement sulphate resistant cement in place of ordinary Portland cement.	437 CWT	75.00	% Cwt	32,775.00
8.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	20 Nos.	913.63	Each	18,273.00
9.	S/F Imported Earth with in the a radius of 5 miles i/c digging, lodging, un-lodging all lead and lift leveling and water compaction etc complete.	4800 Cft	25.00	P/Cft	1,20,000.00
10.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	30 Nos.	3000.00	Each	90,000.00

	<b>Total Estimated Cost</b>	<b>9,99,305/-</b>
--	-----------------------------	-------------------

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
 ORANGI ZONE

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES****WORK NO: 04****DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**Estimated Cost Rs: 8,33,128/- + O/REarnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Rehabilitation of c.c Flooring gali # 06, Agror Mollaha in U.C #  
23,Orangi Zone DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2000 Cft	3327.50	%Cft	66,550.00
2.	Dismantling of cement concrete 1:3:6 plain flooring.	1800 Cft	1306.80	%Cft	23,522.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	5000 Cft	1065.00	%Cft	53,250.00
4.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	10000 Sft	526.28	%Sft	52,628.00
5.	P/L 1:4:8 CC using GSB 2" to 3" and i/c leveling compacting, curing etc complete without shuttering.	2500 Cft	11288.75	% Cft	2,82,219.00
6.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	10000 Sft	3275.50	% Sft	3,27,550.00
7.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	30 Nos.	913.63	Each	27,409.00
8.	P/L Granular sub-base course material over prepared sub-grade in grade, thickness and typical cross sections for new grade / widening existing pavement using well graded granular stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	1600 Cft	O/R	P/Cft	O/R
9.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	05 Nos.	O/R	Each	O/R

10.	Extra for using (S.R Cement sulphate resistant cement in place of ordinary Portland cement.	289 CWT	O/R	% Cwt	O/R
<b>Total Estimated Cost</b>					<b>8,33,128/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
**ORANGI ZONE**

**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES****WORK NO: 05****DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**Estimated Cost Rs: 9,99,116/-Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Improvement of R.c.c pipe & Main Hole Near Iqra State Agency Ward-1 Noorani Mollaha in U.C # 22 Orangi Zone D.M.C (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2134 Cft	3327.50	%Cft	71,009.00
2.	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape traveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guard light flags and temporary crossing for non vehicular traffic wherever required left upto 05' and lead upto 01 chain.	3625 Cft	4650.00	1000 Cft	16,865.00
3.	Excavation for pipe line in trenches and pits in soft rock by hammering and chiesling i/c alignment and shape level and grade cutting joint holes and disposal of surplus earth within one chain as directed by Engineer Incharge.	1000 Cft	10770.00	1000 Cft	10,770.00
4.	Excavation for pipe line in trenches and pits in soft rock by hammering and chiesling i/c alignment and shape level and grade cutting joint holes and disposal of surplus earth within one chain as directed by Engineer Incharge.	1200 Cft	24150.00	1000 Cft	28,980.00
5.	P/L R.C.C. rubber ring pipe of class "A" and fixing in trenches i/c cutting, fitting and jointing with rubber ring etc complete. .....15" Dia.....	750 Rft	367.00	P/Rft	2,75,250.00
6.	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 CC in 9" thick wall and beding cast in situ with fair face steel shuttering i/c excavation, back filling and disposal of surplus stuff etc.	35 Nos.	13064.00	Each	4,57,240.00
7.	Add for extra depth beyond 5' depth, less than 5' depth deduct at the same rate.	61.25 Rft (-)	1540.00	P/Rft	(-) 94,325.00

8.	Refilling of excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	3832 Cft	2760.00	1000 Cft	10,576.00
9.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	5334 Cft	1065.00	%Cft	56,807.00
10.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	45 Nos.	913.63	Each	41,113.00
11.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	2000 Cft	2420.00	%Cft	4,840.00
12.	P/F Per Coasted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	40 Nos.	3000.00	Each	1,20,000.00
<b>Total Estimated Cost</b>					<b>9,99,116/-</b>

Nomenclature, Quantities and Rates etc checked and found correct.



**EXECUTIVE ENGINEER(B&R)  
ORANGI ZONE**

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_



**SCHEDULE OF QUANTITIES****WORK NO: 06****DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**Estimated Cost Rs: 8,39,210 + O/REarnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Improvement of c.c Flooring at gali # 04 & 05, Agror Mollaha  
in U.C # 23 Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2000 Cft	3327.50	%Cft	66,550.00
2.	Dismantling of cement concrete 1:3:6 plain flooring.	1800 Cft	1306.80	%Cft	23,522.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	6000 Cft	1065.00	%Cft	63,900.00
4.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	10000 Sft	526.28	%Sft	52,628.00
5.	P/L 1:4:8 CC using GSB 2" to 3" and i/c leveling compacting, curing etc complete without shuttering.	2500 Cft	11288.75	% Cft	2,82,219.00
6.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	10000 Sft	3275.50	% Sft	3,27,550.00
7.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	25 Nos.	913.63	Each	22,841.00
8.	P/L Granular sub-base course material over prepared sub-grade in grade, thickness and typical cross sections for new grade / widening existing pavement using well graded granular stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	1500 Cft	O/R	P/Cft	O/R

(2)

9.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	05 Nos.	O/R	Each	O/R
<b>Total Estimated Cost</b>					<b>8,39,210 (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
**ORANGI ZONE**

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 07**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 9,95,745/-

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Rehabilitation of c.c street near Madina Masjid and Eid Gah, Shah Mollaha # 2 and other area in U.C # 21Orangi Zone, D.M.C (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2600 Cft	3327.50	%Cft	86,515.00
2.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	3542 Cft	1437.00	% Cft	5,090.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	5400 Cft	1065.00	%Cft	57,510.00
4.	S/F Imported Earth with in the a radius of 5 miles i/c digging, lodging, un-lodging all lead and lift leveling and water compaction etc complete.	3200 Cft	25.00	P/Cft	80,000.00
5.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	10500 Sft	526.28	%Sft	55,259.00
6.	P/L 1:4:8 CC using GSB 2" to 3" and i/c leveling compacting, curing etc complete without shuttering.	2625 Cft	11288.75	% Cft	2,96,330.00
7.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	10500 Sft	3275.50	% Sft	3,43,928.00
8.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	45 Nos.	913.63	Each	41,113.00
9.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	10 Nos.	3000.00	Each	30,000.00

(2)

<b>Total Estimated Cost</b>	<b>9,95,745/-</b>
-----------------------------	-------------------

Nomenclature, Quantities and Rates etc checked and found correct.



**EXECUTIVE ENGINEER(B&R)  
ORANGI ZONE**

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES****WORK NO: 08****DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**Estimated Cost Rs: 9,94,725/-Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Rehabilitation of c.c street near Shakir Ahmed House, Shah Mollaha and other area in U.C # 21, Orangi Zone, D.M.C (west).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2600 Cft	3327.50	%Cft	86,515.00
2.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	2832 Cft	1437.00	%Cft	4,070.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	5400 Cft	1065.00	%Cft	57,510.00
4.	S/F Imported Earth with in the a radius of 5 miles i/c digging, lodging, un-lodging all lead and lift leveling and water compaction etc complete.	3200 Cft	25.00	P/Cft	80,000.00
5.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	10500 Sft	526.28	%Sft	55,259.00
6.	P/L 1:4:8 CC using GSB 2" to 3" and i/c leveling compacting, curing etc complete without shuttering.	2625 Cft	11288.75	% Cft	2,96,330.00
7.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	10500 Sft	3275.50	% Sft	3,43,928.00
8.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	45 Nos.	913.63	Each	41,113.00
9.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	10 Nos.	3000.00	Each	30,000.00

(2)

	<b>Total Estimated Cost</b>	<b>9,94,725/-</b>
--	-----------------------------	-------------------

Nomenclature, Quantities and Rates etc checked and found correct.



**EXECUTIVE ENGINEER(B&R)  
ORANGI ZONE**

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_





(2)

	<b>Total Estimated Cost</b>	<b>9,97,325/-</b>
--	-----------------------------	-------------------



Nomenclature, Quantities and Rates etc checked and found correct.

**EXECUTIVE ENGINEER(B&R)  
ORANGI ZONE**

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_



21

	<b>Total Estimated Cost</b>
	<b>9,95,825/-</b>

Nomenclature, Quantities and Rates etc checked and found correct.

**EXECUTIVE ENGINEER(B&R)  
ORANGI ZONE**

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 11**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 9,95,745/-

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Rehabilitation of c.c street near Shahi Masjid (Mosque), Shah Mollaha # 1 and other Area in U.C # 21, Orangi Zone (west).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2600 Cft	3327.50	%Cft	86,515.00
2.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	3542 Cft	1437.00	%Cft	5,090.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	5400 Cft	1065.00	%Cft	57,510.00
4.	S/F Imported Earth with in the a radius of 5 miles i/c digging, lodging, un-lodging all lead and lift leveling and water compaction etc complete.	3200 Cft	25.00	P/Cft	80,000.00
5.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	10500 Sft	526.28	%Sft	55,259.00
6.	P/L 1:4:8 CC using GSB 2" to 3" and i/c leveling compacting, curing etc complete without shuttering.	2625 Cft	11288.75	% Cft	2,96,330.00
7.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	10500 Sft	3275.50	% Sft	3,43,928.00
8.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	45 Nos.	913.63	Each	41,113.00
9.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	10 Nos.	3000.00	Each	30,000.00

27

	<b>Total Estimated Cost</b>	<b>9,95,745/-</b>
--	-----------------------------	-------------------



Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
**ORANGI ZONE**

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER**  
**Building and Roads**  
**Orangi Zone DMC (West)**

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_



**SCHEDULE OF QUANTITIES****WORK NO: 12****DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**Estimated Cost Rs: 9,94,785/-Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Rehabilitation of c.c street near Faisal Masjid (Mosque), Shah Mollaha # 1 and other Area in U.C # 21, Orangi Zone (west).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2600 Cft	3327.50	%Cft	86,515.00
2.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	2874 Cft	1437.00	%Cft	4,130.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	5400 Cft	1065.00	%Cft	57,510.00
4.	S/F Imported Earth with in the a radius of 5 miles i/c digging, lodging, un-lodging all lead and lift leveling and water compaction etc complete.	3200 Cft	25.00	P/Cft	80,000.00
5.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	10500 Sft	526.28	%Sft	55,259.00
6.	P/L 1:4:8 CC using GSB 2" to 3" and i/c leveling compacting, curing etc complete without shuttering.	2625 Cft	11288.75	% Cft	2,96,330.00
7.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	10500 Sft	3275.50	% Sft	3,43,928.00
8.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	45 Nos.	913.63	Each	41,113.00
9.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	10 Nos.	3000.00	Each	30,000.00

(2)

	<b>Total Estimated Cost</b>	<b>9,94,785/-</b>
--	-----------------------------	-------------------

Nomenclature, Quantities and Rates etc checked and found correct.

**EXECUTIVE ENGINEER(B&R)  
ORANGI ZONE**

M/S \_\_\_\_\_

**EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES****WORK NO: 13****DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**Estimated Cost Rs: 7,18,630 (+) O/REarnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Rehabilitation & Improvement of Sewerage System & other work  
in Sector 11 ½ in Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTI TY	RATE	PER	AMOUNT
1.	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape traveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guard light flags and temporary crossing for non vehicular traffic wherever required left upto 05' and lead upto 01 chain.	720 Cft	4650.00	1000 Cft	3,348.00
2.	P/L R.C.C. rubber ring pipe of class "A" and fixing in trenches i/c cutting, fitting and jointing with rubber ring etc complete. .....15" Dia.....	96 Rft	367.00	P/Rft	35,232.00
3.	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 CC in 9" thick wall and beding cast in situ with fair face steel shuttering i/c excavation, back filling and disposal of surplus stuff etc.	08 Nos.	13064.00	Each	1,04,512.00
4.	Add for extra depth beyond 5' depth, less than 5' depth deduct at the same rate.	(-) 12.896 Rft	1540.00	P/Rft	(-) 19,860.00
5.	Refilling of excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	619 Cft	2760.00	1000 Cft	1,708.00
6.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	165 Nos.	913.63	Each	1,50,749.00
7.	Hiring of Excavator for desalting and cleaning of Nallah Long Boom i/c POL (for 08 Hours Per Day).	16 Hours	O/R	P/Hour	O/R
8.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	05 Days	O/R	P/Day	O/R
9.	Hiring of Tractor Trolley Heavy Duty for cleaning of Garbage, Street of Road side earth i/c Loading, Unloading etc complete with POL (for 08 Hours Per Day).	20 Trips	O/R	P/Trip	O/R

10.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	35 Nos.	O/R	Each P. Day	O/R
11.	Dismantling and removing of medaling carpeting etc.	6000 cft	605.00	% cft	36,300.00
12.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	5000 cft	1437.00	% cft	7,185.00
13.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	11000	1065.00	% cft	1,17,150.00
14.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	3000 Sft	526.28	% Sft	15,788.00
15.	P/L Granular sub-base course material over prepared sub-grade in grade, thickness and typical cross sections for new grade / widening existing pavement using well graded granular stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	3000 Cft	3341.71	% Cft	1,00,251.00
16.	P/L Aggregate base course material over prepared sub-grade in grade, thickness and typical cross sections grade / widening existing pavement using well graded crushed stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	3000 Cft	5542.24	P/Cft	1,66,267.00
17.	P/F Per Casted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	30 Nos.	O/R	Each	O/R
<b>Total Estimated Cost</b>					<b>7,18,630/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.



**EXECUTIVE ENGINEER(B&R  
ORANGI ZONE**

M/S \_\_\_\_\_

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES****WORK NO: 14****DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**Estimated Cost Rs: 7,12,580 (+) O/REarnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Repairing / Improvement of Pot Holes & tranches and Other works in Orangi Zone, DMC (West)

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling and removing of medaling carpeting etc.	8000 cft	605.00	% cft	48,400.00
2.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	7500 cft	1437.00	% <sup>0</sup> cft	10,778.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	19259	1065.00	% cft	2,05,108.00
4.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	4000 Sft	526.28	%Sft	21,051.00
5.	P/L Granular sub-base course material over prepared sub-grade in grade, thickness and typical cross sections for new grade / widening existing pavement using well graded granular stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	3000 Cft	3341.71	% Cft	1,00,251.00
6.	P/L Aggregate base course material over prepared sub-grade in grade, thickness and typical cross sections grade / widening existing pavement using well graded crushed stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	5900 Cft	5542.24	P/Cft	3,26,992.00
7.	P/F Per Casted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	25 Nos.	O/R	Each	O/R
8.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	08 Days	O/R	P/Day	O/R
9.	Hiring of Tractor Trolly Heavy Duty for cleaning of Garbage, Street of Road side earth i/c Loading, Unloading etc complete with POL (for 08 Hours Per Day).	30 Trips	O/R	P/Trip	O/R

10.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	55 Nos.	O/R	Each P. Day	O/R
<b>Total Estimated Cost</b>					<b>7,12,580/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.



**EXECUTIVE ENGINEER(B&R  
ORANGI ZONE  
EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_



**SCHEDULE OF QUANTITIES**

**WORK NO: 15**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 7,40,250 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Repairing / Maintenance of Pot Holes near Gate # 04 & 06, of Ejtima Gah, in Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTIT Y	RATE	PER	AMOUNT
1.	Preparing sub base by supplying and spreading well graded pit or bed run gravel having aliquot limit not greater than 25 & plasticity index not greater than 6 in proper camber & grade i/c watering rolling & compacting in layer, thickness of each compacted layer not exceeding 6" compacted upto 98-100 % density as per modified AASHTO density (Rate i/c all cost of materials T&P and carriage upto 3 chains.	8440 cft	3341.71	% cft	2,82,040.00
2.	P/L Aggregate base course material in proper grade and camber having CBR 80 % as per AASHO standard specification i/c spreading & compacting by approved mech means (motor grader, Vibratory roller, & smooth wheel roller etc). watering to maintain the moisture content the compaction of each layer shall 100 % to the max dry density. (Rate i/c all cost of materials T &P and carriage up to 3 chains.	6674.38 cft	5542.24	% cft	3,69,910.00
3.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	07 Nos	8500.00	P/Day	59,500
4.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	24 Nos.	1200.00	Each P. Day	28,800
5.	S/F Imported Earth with in the a radius of 5 miles i/c digging, loading, un-lodging all lead and lift leveling and water compaction etc complete.	2948 Cft	O/R	P/Cft	O/R
6.	P/F Per Casted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	25 Nos.	O/R	Each	O/R
<b>Total Estimated Cost</b>					<b>7,40,250/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.



**EXECUTIVE ENGINEER**  
Building and Roads  
Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES****WORK NO: 16****DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**Estimated Cost Rs: 7,45,450 (+) O/REarnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Repairing / Maintenance of Pot Holes near Gate # 07 of Ejtima Gah, in Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTIT Y	RATE	PER	AMOUNT
1.	Preparing sub base by supplying and spreading well graded pit or bed run gravel having aliquot limit not greater than 25 & plasticity index not greater than 6 in proper camber & grade i/c watering rolling & compacting in layer, thickness of each compacted layer not exceeding 6" compacted upto 98-100 % density as per modified AASHTO density (Rate i/c all cost of materials T&P and carriage upto 3 chains.	7996.03 cft	3341.71	% cft	2,67,204.00
2.	P/L Aggregate base course material in proper grade and camber having CBR 80 % as per AASHO standard specification i/c spreading & compacting by approved mech means (motor grader, Vibratory roller, & smooth wheel roller etc). watering to maintain the moisture content the compaction of each layer shall 100 % to the max dry density. (Rate i/c all cost of materials T &P and carriage up to 3 chains.	6500 cft	5542.24	% cft	3,60,246.00
3.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	07 Nos	8500.00	P/Day	59,500
4.	Hiring of Tractor Trolly Heavy Duty for cleaning of Garbage, Street of Road side earth i/c Loading, Unloading etc complete with POL (for 08 Hours Per Day).	18 Nos	1650.00	P/Trip	29,700
5.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	24 Nos.	1200.00	Each P. Day	28,800
6.	S/F Imported Earth with in the a radius of 5 miles i/c digging, loading, un-lodging all lead and lift leveling and water compaction etc complete.	2829 Cft	O/R	P/Cft	O/R
7.	P/F Per Casted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	24 Nos.	O/R	Each	O/R
<b>Total Estimated Cost</b>					<b>7,45,450/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked  
and found correct.

  
**EXECUTIVE ENGINEER(B&R  
ORANGI ZONE**  
**EXECUTIVE ENGINEER**  
Building and Roads  
Orangi Zone DMC (West)  
**T-C / ACCOUNTANT**

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 17**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 8,89,340 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Repairing of Nallaha from Soni Cowk to Fatima-u Zohar in U.C # 11, Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of R.C.C. separating reinforcement from concrete, cleaning and straightening same.	1200 Cft	5445.00	%Cft	65,340.00
2.	Dismantling of cement concrete 1:2:4 plain flooring.	2500 Cft	3327.50	%Cft	83,188.00
3.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	15000 Cft	2420.00	% 0 Cft	36,300.00
4.	Fabrication of mild steel reinforcement for cement concrete i/c cutting, bending, layer in position making joints and fastening i/c cost of binding works and removal of rust from bars.	6.0 Cwt	5001.70	P/Cwt	30,010.00
5.	RCC work i/c all labor and material except the cost of reinforcement and its labor for bending which will be paid separately. This rate also i/c all kinds of forms, molds, lifting, shuttering, cutting, rendering and finishing the expose surface i/c screening and washing of shingles ratio 1:2:4.	1056 Cft	337.00	P/Cft	3,55,872.00
6.	Extra for using (S.R Cement sulphate resistant cement in place of ordinary Portland cement.	364.04 CWT	75.00	P.cwt	27,528
7.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	12430 Cft	1065.00	%Cft	1,32,380.00
8.	Cement concrete plain including placing compacting, finishing and curing, Complete, (Including screening and washing at stone aggregate without shuttering Ratio 1:2:4.	1100 Cft	14429.25	% Cft	1,58,722.00

9.	P/F pre-cast R.C.C Ring slab 39" dia with R.C.C Man Hole Cover of 21" dia fixing as per direction of Engineer Incharge.	07 Nos	O/R	P/Sft	O/R ✓
<b>Total Estimated Cost</b>					<b>8,89,340/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
 ORANGI ZONE  
**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_



**SCHEDULE OF QUANTITIES**

**WORK NO: 18**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 8,75,755 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Rehabilitation of Sewerage Line in Gali # 12, Sector 7-F Shah Faisal Mollaha, Baloch Goth, Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2255 Cft	3327.50	%Cft	75,035.00
2.	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape traveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guard light flags and temporary crossing for non vehicular traffic wherever required left upto 05' and lead upto 01 chain.	5250 Cft	4650.00	1000 Cft	24,413.00
3.	P/L R.C.C. rubber ring pipe of class "A" and fixing in trenches i/c cutting, fitting and jointing with rubber ring etc complete. .....15" Dia.....	700 Rft	367.00	P/Rft	2,56,900.00
4.	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 CC in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation, back filling and disposal of surplus stuff etc.	30 Nos.	13064.00	Each	3,91,920.00
5.	Add for extra depth beyond 5' depth, less than 5' depth deduct at the same rate.	(-) 15.003 Rft	1540.00	P/Rft	(-) 23,105.00
6.	Refilling of excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	4391 Cft	2760.00	1000 Cft	12,119.00
7.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	51 Nos.	913.63	Each	46,595.00
8.	P/F Per Casted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	40 Nos.	O/R	Each	O/R

9.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	8627	1065.00	% cft	91,878.00
<b>Total Estimated Cost</b>					<b>8,75,755/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R  
ORANGI ZONE  
EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 19**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 7,74,802/- + O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Repairing of c.c Flooring gali No. 11, Shaheed Chacha Abdul Ghani Sector 7-F Shah Faisal Mollaha Baloch Goth U.C # 11 Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2250 Cft	3327.50	%Cft	74,869.00
2.	Dismantling of cement concrete 1:3:6 plain flooring.	1200 Cft	1306.80	%Cft	15,682.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	7950 Cft	1065.00	%Cft	84,668.00
4.	S/F Imported Earth with in the a radius of 5 miles i/c digging, lodging, un-lodging all lead and lift leveling and water compaction etc complete.	2500 Cft	O/R	P/Cft	O/R
5.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	8500 Sft	526.28	%Sft	44,734.00
6.	P/L 1:4:8 CC using GSB 2" to 3" and i/c leveling compacting, curing etc complete without shuttering.	2125 Cft	11288.75	% Cft	2,39,886.00
7.	P/L 2" thick topping C.C (1:2:4) i/c surface finishing & dividing in to panels.	8500 Sft	3275.50	% Sft	2,78,418.00
8.	Extra for using (S.R Cement sulphate resistant cement in place of ordinary Portland cement.	437 CWT	O/R	% Cwt	O/R
9.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	40 Nos.	913.63	Each	36,545.00
10.	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	30 Nos.	O/R	Each	O/R

	<b>Total Estimated Cost</b>	<b>7,74,802/- + Open Rate</b>
--	-----------------------------	-----------------------------------

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
**ORANGI ZONE**  
**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES****WORK NO: 20****DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**Estimated Cost Rs: 9,98,220/-Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Replacement of Broken Sewerage pipe line Different Masjid in  
U.C # 38 & 39, Surjani, Orangi Zone, D.M.C (West).

S.No:	DESCRIPTION OF WORK	QUANTIT Y	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	2200 Cft	3327.50	%Cft	73,205.00
2.	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape traveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guard light flags and temporary crossing for non vehicular traffic wherever required left upto 05' and lead upto 01 chain.	3003 Cft	4650.00	1000 Cft	13,964.00
3.	P/L R.C.C. rubber ring pipe of class "A" and fixing in trenches i/c cutting, fitting and jointing with rubber ring etc complete. .....15" Dia.....	600 Rft	367.00	P/Rft	2,20,200.00
4.	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 CC in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation, back filling and disposal of surplus stuff etc.	50 Nos.	13064.00	Each	6,53,200.00
5.	Add for extra depth beyond 5' depth, less than 5' depth deduct at the same rate.	(-) 50 Rft	1540.00	P/Rft	(-) 77,000.00
6.	Refilling of excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	2264 Cft	2760.00	1000 Cft	6,249.00
7.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	25 Nos. 25 Nos	913.63 1051.25	Each	22,841.00 26,281.00
8.	P/F RCC Per Casted ring slab or i/c linter of required size and shape and racking out Joint with CM curing etc complete as per direction of Engineer Incharge.	494 Cft	120.00	P.Cft	59,280.00

Total Estimated Cost 9,98,220/-

Nomenclature, Quantities and Rates etc checked and found correct.

  
EXECUTIVE ENGINEER(B&R)  
ORANGI ZONE  
EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

T-C / ACCOUNTANT

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 21**

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KARACHI, ORANGI ZONE**

Estimated Cost Rs: 7,59,241 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Repair & Maintenance of Sewerage System Back Side Deyar-e-Habib Masjid & Back Side of Qatar Hospital and varies places in Orangi, Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	1612 Cft	3327.50	%Cft	53,639.00
2.	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape traveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guard light flags and temporary crossing for non vehicular traffic wherever required left upto 05' and lead upto 01 chain.	4400 Cft	4650.00	1000 Cft	20,640.00
3.	Excavation for pipe line in trenches and pits in soft rock by hammering and chieslling i/c alignment and shape level and grade cutting joint holes and disposal of surplus earth within one chain as directed by Engineer Incharge.	1000 Cft	10770.00	1000 Cft	10,770.00
4.	P/L R.C.C. rubber ring pipe of class "A" and fixing in trenches i/c cutting, fitting and jointing with rubber ring etc complete. .....15" Dia.....	750 Rft	367.00	P/Rft	2,75,250.00
5.	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 CC in 9" thick wall and beding cast in situ with fair face steel shuttering i/c excavation, back filling and disposal of surplus stuff etc.	31 Nos.	13064.00	Each	4,04,984.00
6.	Add for extra depth beyond 5' depth, less than 5' depth deduct at the same rate.	(-) 54.25 Rft	1540.00	P/Rft	(-) 83,545.00



7.	Refilling of excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	3479 Cft	2760.00	1000 Cft	9,602.00
8.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	4231 Cft	1065.00	%Cft	45,060.00
9.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	25 Nos.	913.63	Each	22,841.00
10.	S/F Imported Earth with in the a radius of 5 miles i/c digging, lodging, un-lodging all lead and lift leveling and water compaction etc complete.	1000 Cft	O/R	P/Cft	O/R
11.	P/F Per coasted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.( Markeet Rate)	20 Nos.	O/R	Each	O/R
<b>Total Estimated Cost</b>					<b>7,59,241 (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
 ORANGI ZONE  
**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES****WORK NO: 22****DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**Estimated Cost Rs: 7,59,241 (+) O/REarnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-**SUBJECT:** Rehabilitation and Improvement of Sewerage System Different Areas Orangi Zone, DMC (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling of cement concrete 1:2:4 plain flooring.	1612 Cft	3327.50	%Cft	53,639.00
2.	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape traveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guard light flags and temporary crossing for non vehicular traffic wherever required left upto 05' and lead upto 01 chain.	4400 Cft	4650.00	1000 Cft	20,640.00
3.	Excavation for pipe line in trenches and pits in soft rock by hammering and chiesling i/c alignment and shape level and grade cutting joint holes and disposal of surplus earth within one chain as directed by Engineer Incharge.	1000 Cft	10770.00	1000 Cft	10,770.00
4.	P/L R.C.C. rubber ring pipe of class "A" and fixing in trenches i/c cutting, fitting and jointing with rubber ring etc complete. .....15" Dia.....	750 Rft	367.00	P/Rft	2,75,250.00
5.	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 CC in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation, back filling and disposal of surplus stuff etc.	31 Nos.	13064.00	Each	4,04,984.00
6.	Add for extra depth beyond 5' depth, less than 5' depth deduct at the same rate.	(-) 54.25 Rft	1540.00	P/Rft	(-) 83,545.00

7.	Refilling of excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	3479 Cft	2760.00	1000 Cft	9,602.00
8.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	4231 Cft	1065.00	%Cft	45,060.00
9.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	25 Nos.	913.63	Each	22,841.00
10.	S/F Imported Earth with in the a radius of 5 miles i/c digging, lodging, un-lodging all lead and lift leveling and water compaction etc complete.	1000 Cft	O/R	P/Cft	O/R
11.	P/F Per coasted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.( Markeet Rate)	20 Nos.	O/R	Each	O/R
<b>Total Estimated Cost</b>					<b>7,59,241 (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
 ORANGI ZONE  
**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 23**

**DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**

Estimated Cost Rs: 6,70,000 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-


**SUBJECT:** Hiring of Machinery for cleaning of Nallaha in U.C # 11, 12, 13,  
Orangi Zone, DMC (West).

S. No :	DESCRIPTION OF WORK	QUANTIT Y	RATE	PER	AMOUNT
1.	Hiring of Excavator for desalting and cleaning of Nallah Long Boom i/c POL (for 08 Hours Per Day).	5x8 40 Hours	3088.13	P/Hour	1,23,525
2.	Hiring Seal Dumpers Hino for lifting of Garbage & Silt Nallaha i/c Loading unloading in all respect with pol (for 08 Hours Per Day).	7x3x8 168 46 214	2006.90	P/Hour	4,29,477
3.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	1 x 6 6 days	8500.00	P/Day	51,000
4.	Hiring of Tractor Trolley Heavy Duty for cleaning of Garbage, Street of Road side earth i/c Loading, Unloading etc complete with POL (for 08 Hours Per Day).	7 x 4 28	1600.00	P/Trip	44,800
5.	Hiring of Loader for lifting of Garbage & silt etc with POL (for 08 Hours Per Day).	1 day	22000.00	P.day	22,000
6.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	220 Nos.	O/R	Each P. Day	O/R
<b>Total Estimated Cost</b>					<b>6,70,000/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

  
**EXECUTIVE ENGINEER(B&R  
ORANGI ZONE  
EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)**

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 24**

**DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**

Estimated Cost Rs: 7,30,000 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Hiring of Private Labour in Cleaning of Nallaha Thorani Goth  
Rehmat Chowk & Other Work & other Places in Orangi Zone,  
DMC (West).

S. No	DESCRIPTION OF WORK	QUANTIT Y	RATE	PER	AMOUNT
1.	Hiring of Excavator for desalting and cleaning of Nallah Long Boom i/c POL (for 08 Hours Per Day).	5x8 40 Hours	3088.13	P/Hour	1,23,525
2.	Hiring Seal Dumpers Hino for lifting of Garbage & Silt Nallaha i/c Loading unloading in all respect with pol (for 08 Hours Per Day).	7x3x8 168 46 214	2006.90	P/Hour	4,29,477
3.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	10 x 1 10 days	8500.00	P/Day	85,000
4.	Hiring of Tractor Trolly Heavy Duty for cleaning of Garbage, Street of Road side earth i/c Loading, Unloading etc complete with POL (for 08 Hours Per Day).	5 x 6 30	1600.00	P/Trip	48,000
5.	Hiring of Loader for lifting of Garbage & silt etc with POL (for 08 Hours Per Day).	2 x 1 2 day	22000.00	P.day	44,000
6.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	164 Nos.	O/R	Each P. Day	O/R
<b>Total Estimated Cost</b>					<b>7,30,000 (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R  
ORANGI ZONE**

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)  
T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 25**

**DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**

Estimated Cost Rs: 6,90,770 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Hiring of Machinery for cleaning of Nallaha in Block L & Other  
Work in Ali Garah Colony Culvert Orangi Zone, DMC (West).

S. No :	DESCRIPTION OF WORK	QUANTIT Y	RATE	PER	AMOUNT
1.	Hiring of Excavator for desalting and cleaning of Nallah Long Boom i/c POL (for 08 Hours Per Day).	1x6x8 48 Hours	3088.13	P/Hour	1,48,230
2.	Hiring Seal Dumpers Hino for lifting of Garbage & Silt Nallaha i/c Loading unloading in all respect with pol (for 08 Hours Per Day).	7x4x8 224	2006.90	P/Hour	4,49,540
3.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	1 x 6 6 days	8500.00	P/Day	51,000
4.	Hiring of Tractor Trolley Heavy Duty for cleaning of Garbage, Street of Road side earth i/c Loading, Unloading etc complete with POL (for 08 Hours Per Day).	3 x 4 12	1600.00	P/Trip	20,000
5.	Hiring of Loader for lifting of Garbage & silt etc with POL (for 08 Hours Per Day).	1 x 1 1 day	22000.00	P.day	22,000
6.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	200 Nos.	O/R	Each P. Day	O/R
<b>Total Estimated Cost</b>					<b>6,90,770 (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

  
**EXECUTIVE ENGINEER(B&R)  
ORANGI ZONE  
EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)  
T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_

**SCHEDULE OF QUANTITIES**

**WORK NO: 26**

**DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**

Estimated Cost Rs: 7,50,143 (+) O/R

Earnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Hiring of Private Labour & Machinery for Cleaning of Nallaha and Other Places in U.C # 38, Surjani Town Orangi Zone, DMC (West).

S. No :	DESCRIPTION OF WORK	QUANTIT Y	RATE	PER	AMOUNT
1.	Hiring of Excavator for desalting and cleaning of Nallah Long Boom i/c POL (for 08 Hours Per Day).	5 x 8 40 days	3088.13	P/Hour	1,23,525
2.	Hiring Seal Dumpers Hino for lifting of Garbage & Silt Nallaha i/c Loading unloading in all respect with pol (for 08 Hours Per Day).	7x4x8 224	2006.90	P/Hour	4,49,546
3.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	10 x 1 10 Nos	8500.00	P/Day	85,000
4.	Hiring of Tractor Trolley Heavy Duty for cleaning of Garbage, Street of Road side earth i/c Loading, Unloading etc complete with POL (for 08 Hours Per Day).	5 x 6 30	1600.00	P/Trip	48,000
5.	Hiring of Loader for lifting of Garbage & silt etc with POL (for 08 Hours Per Day).	2 x 1 2 Nos	22000.00	P.day	44,000
6.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	146 Nos.	O/R	Each P. Day	O/R
<b>Total Estimated Cost</b>					<b>7,50,143 (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

  
**EXECUTIVE ENGINEER(B&R)**  
ORANGI ZONE  
**EXECUTIVE ENGINEER**  
Building and Roads  
Orangi Zone DMC (West)  
**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_



**SCHEDULE OF QUANTITIES****WORK NO: 27****DISTRICT MUNICIPAL CORPORATION (WEST)  
KARACHI, ORANGI ZONE**Estimated Cost Rs: 7,50,143 (+) O/REarnest Money Rs: 20,000/-

Time Limit: \_\_\_\_\_

Penalty Per Day Rs: 1,000/-

**SUBJECT:** Improvement / Repairing of Pot Holes & Tranches near Karimi Chowrangi and other places in U.C # 39, Surjani Town, Orangi Zone, D.M.C. (West).

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling and removing of medaling carpeting etc.	4250 cft	605.00	% cft	25,713.00
2.	Earth work excavation of road side nails forming its banks or putting the same on embankment as directed breaking clods dressing etc complete in ordinary soil.	12402 cft	1437.00	% 0 cft	17,822.00
3.	Cartage of sand, bajri, lime, surkhi, murrum, building rubbish i/c loading unloading stacking at site all lide and lift.	18650	1065.00	% cft	1,98,623.00
4.	Preparing of sub-grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller.	8200 Sft	526.28	%Sft	43,155.00
5.	P/L Granular sub-base course material over prepared sub-grade in grade, thickness and typical cross sections for new grade / widening existing pavement using well graded granular stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	3000 Cft	3341.71	% Cft	1,00,251.00
6.	P/L Aggregate base course material over prepared sub-grade in grade, thickness and typical cross sections grade / widening existing pavement using well graded crushed stone with sand and silt having a smooth gradation as per AASHTO-M watering with all lead and lift as per directed by Engineer Incharge.	4600 Cft	5542.24	P/Cft	2,54,943.00
7.	P/L 1:2:4 RCC manhole cover i/c tor bars frame using GSB ¾" and down gauge etc complete.	120 Nos.	913.63 1051.25	Each	1,09,636.00
8.	P/F Per Casted RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of Engineer Incharge.	11 Nos.	O/R	Each	O/R
9.	Hiring of Tractor Blade Heavy Duty for cleaning of Garbage, Street of Road side earth with POL (for 08 Hours Per Day).	08 Days	O/R	P/Day	O/R

10.	Hiring of Private Labour for cleaning of Nallah (by Afghani or Bajorri for 08 Hours).	28 Nos.	O/R	Each P. Day	O/R
<b>Total Estimated Cost</b>					<b>7,50,143/- (+) Open Rate</b>

Nomenclature, Quantities and Rates etc checked and found correct.

  
**EXECUTIVE ENGINEER(B&R)**  
 ORANGI ZONE  
**EXECUTIVE ENGINEER**  
 Building and Roads  
 Orangi Zone DMC (West)

M/S \_\_\_\_\_

Pay Order NO: \_\_\_\_\_ Dated: \_\_\_\_\_ Rs: \_\_\_\_\_

**T-C / ACCOUNTANT**

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below the S/R \_\_\_\_\_

(+) Open Rate Rs: \_\_\_\_\_ for complete work/job.

The total amount is Rs: \_\_\_\_\_ (Rupees: \_\_\_\_\_)

Contractor's Signature: \_\_\_\_\_

Address: \_\_\_\_\_

CELL #: \_\_\_\_\_



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**

**NIT No: 08/2017-18, Work No: 01**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Repairing of Sewerage Line in Sector 8/A, gali NO. 6, 9, 10, & 13 in Data Nagar in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 8,17,540/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On:12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi

Phone. 36697869 & 36660102

**BIDDING DATA**

**NIT No: 08/2017-18, Work No: 02**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Repairing of Sewerage line & C.C street in Nasimabad & Al-Muslimabad Gali # 01,02, & 04 in Data Nagar in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 8,54,960/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),


Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 03**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Improvement of c.c street at ward # 4, and other work U.C-21, in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,99,305/-
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 04**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Rehabilitation of c.c Flooring gali # 06, Agror Mollaha in U.C # 23, Orangi Zone DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 8,33,128/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION (WEST),

ORANGI ZONE, KARACHI

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 05**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Improvement of R.c.c pipe & Main Hole Near Iqra State Agency Ward-I Noorani Mollaha in U.C # 22 Orangi Zone D.M.C (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,99,116/-
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)





DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi


Phone: 36697869 & 36660102

**BIDDING DATA**

**NIT No: 08/2017-18, Work No: 06**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Improvement of c.c Flooring at gali # 04 & 05, Agror Mollaha in U.C # 23 Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 8,39,210/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)




DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI

Sector 11/E Shahrah-e-Orangi, Karachi  
Phone. 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 07**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Rehabilitation of c.c street near Madina Masjid and Eid Gah, Shah Mollaha # 2 and other area in U.C # 21Orangi Zone, D.M.C (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,95,745/-
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi  
Phone: 36697869 & 36660102

**BIDDING DATA**

**NIT No: 08/2017-18, Work No: 08**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Rehabilitation of c.c street near Shakir Ahmed House, Shah Mollaha and other area in U.C # 21, Orangi Zone, D.M.C (west).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,94,725/-
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)  
EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),


Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 09**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Rehabilitation of c.c street near Saeed Ahmed house, Shah Mollaha and other Area in U.C # 21, Orangi Zone , D.M.C (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,97,325/-
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),


Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 10**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Rehabilitation of c.c street near Ali Shah House, Shah Mollaha and Other Area in U.C # 21, Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,95,825/-
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No:11**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Rehabilitation of c.c street near Shahi Masjid (Mosque), Shah Mollaha # 1 and other Area in U.C # 21, Orangi Zone (west).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,95,745/-
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)





DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI

Sector 11/E Shahrah-e-Orangi, Karachi  
Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 12**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Rehabilitation of c.c street near Faisal Masjid (Mosque), Shah Mollaha # 1 and other Area in U.C # 21, Orangi Zone (west).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,94,785/-
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)





DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**

**NIT No: 08/2017-18, Work No: 13**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Rehabilitation & Improvement of Sewerage System & other work in Sector 11 ½ in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,18,630/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 14**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Repairing / Improvement of Pot Holes & trenches and Other works in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,12,580/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 15**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Repairing / Maintenance of Pot Holes near Gate # 04 & 06, of Ejtima Gah, in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,40,250/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 16**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Repairing / Maintenance of Pot Holes near Gate # 07 of Ejtima Gah, in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,45,450/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)  
EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 17**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Repairing of Nallaha from Soni Cowk to Fatima-u-Zohar in U.C # 11, Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 8,89,340/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),


Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 18**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Rehabilitation of Sewerage Line in Gali # 12, Sector 7-F Shah Faisal Mollaha, Baloch Goth, Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 8,75,755/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)





DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI

Sector 11/E Shahrah-e-Orangi, Karachi  
Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 19**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Repairing of c.c Flooring gali No. 11, Shaheed Chacha Abdul Ghani Sector 7-F Shah Faisal Mollaha Baloch Goth U.C # 11 Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,74,802/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)





DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi

Phone. 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 20**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Replacement of Broken Sewerage pipe line Different Masjid in U.C # 38 & 39, Surjani, Orangi Zone, D.M.C (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 9,98,220/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On: 12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 21**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Repair & Maintenance of Sewerage System Back Side Deyar-e-Habib Masjid & Back Side of Qatar Hospital and varies places in Orangi, Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,59,241/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On:12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI

(WEST),


Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**  
**NIT No: 08/2017-18, Work No: 22**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Repairing of Sewerage Line in Sector 8/A, gali NO. 6, 9, 10, & 13 in Data Nagar in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,59,241/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On:12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



**DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI**

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA  
NIT No: 08/2017-18, Work No: 23**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Hiring of Machinery for cleaning of Nallaha in U.C # 11, 12, 13, Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 6,70,000/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On:12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



**DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI**

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA  
NIT No: 08/2017-18, Work No: 24**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Hiring of Private Labour in Cleaning of Nallaha Thorani Goth Rehmat Chowk & Other Work & other Places in Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,30,000/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On:12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S:

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)



**DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI**

Sector 11/E Shahrah-e-Orangi, Karachi


Phone: 36697869 & 36660102

**BIDDING DATA**

**NIT No: 08/2017-18, Work No: 25**

- (a). Name of Procuring Agency District Municipal Corporation (West), Karachi
- (b). Brief Description of Works Hiring of Machinery for cleaning of Nallaha in Block L & Other Work in Ali Garah Colony Culvert Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 6,90,770/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On:12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)





**DISTRICT MUNICIPAL CORPORATION (WEST),  
ORANGI ZONE, KARACHI**

Sector 11/E Shahrah-e-Orangi, Karachi

Phone: 36697869 & 36660102

**BIDDING DATA**

**NIT No: 08/2017-18, Work No: 26**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Hiring of Private Labour & Machinery for Cleaning of Nallaha and Other Places in U.C # 38, Surjani Town Orangi Zone, DMC (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,50,143/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On:12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)





**DISTRICT MUNICIPAL CORPORATION  
ORANGI ZONE, KARACHI**

**(WEST),**

Sector 11/E Shahrah-e-Orangi, Karachi


Phone. 36697869 & 36660102

**BIDDING DATA**

**NIT No: 08/2017-18, Work No: 27**

- (a). Name of Procuring Agency: District Municipal Corporation (West), Karachi
- (b). Brief Description of Works: Improvement / Repairing of Pot Holes & Tranches near Karimi Chowrangi and other places in U.C # 39, Surjani Town, Orangi Zone, D.M.C. (West).
- (c). Procuring Agency's address: Sector 11-E Shahrah-e-Orangi Karachi
- (d). Estimated Cost: 7,50,143/- + O/R
- (e). Amount of Bid Security: 20,000/-
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 02.00% of Contract/Sanction Amount  
(ii). 8% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 7.5 % Income Tax
- (i). Deadline for Submission of Bids along with time : 12.03.2018 at 11:30 AM
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer (B&R), Orangi Zone, DMC(West), Karachi, at Sector 11-E Shahrah-e-Orangi, Karachi at 12:00 Noon On:12.03.2018.
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 500/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1000/- (Rupees: One Thousand Only).
- (n). Earnest Money Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: \_\_\_\_\_
- (o). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

  
EXECUTIVE ENGINEER(B&R)  
ORANGI Zone, DMC(West)

EXECUTIVE ENGINEER  
Building and Roads  
Orangi Zone DMC (West)