

**OFFICE OF THE EXECUTIVE ENGINEER (BUILDINGS ) KASHMORE@ KANDHKOT**

Phone No:0722/573773

No: XEN:(B)/TC/ 1933 /2018

Kash:@ K.kot Dated: 16 /02 /2018

**NOTICE INVITING TENDERS:**

01. Executive Engineer Buildings Division Kashmore @ Kandhkot invites sealed tenders from interested parties / firms meeting the eligibility criteria to participate as per SPPRA Rules (2010):-.

Sr No:	Name of Schemes	Estimate Cost	Completion Period	Cost of Tender	Bid Security
AS PER STATEMENT ATTACHED					

02. **Eligibility:** Registration with Pakistan Engineering Council for the year 2018 in respect above category (Relevant with Building Department)

03. **Qualification**

- List of two similar assignments under-taken over the past 7 years.
- Detail of equipments and transport owned by firm / contractor.
- Financial Statement (summary) and income tax return for the last 3 years.
- List of litigation (if any) and nature of litigation.
- Affidavit that firm has never been black listed.
- Names, Qualification and Experience of Technical Staff working with firm.
- The SRB Certificate for the year 2018 is required
- The license for Electric Work is necessary.

04. **Method of Procurement** Single Stage Single Envelope.

05. **Terms & Conditions**

Under following condition bid will be rejected:-

- Conditional and telegraphic bids / tenders.
- Bids not accompanied by bid security of required amount and form.
- Bids received after specified date and time.
- Black listed firms.
- The undersigned reserves the Right of accepting / rejecting any or all tenders as per relevant clause of SPPRA – 2010.

	Last date of receipt of application and issuance of tender documents	Last date of submission of tenders	The date of opening of tenders
<b>1<sup>st</sup> Date</b>	From the date of publication upto <b>15/03/2018</b> till 11.00 a.m	<b>15/03/2018</b> till 12.00 Noon	<b>15/03/2018</b> at 01.00 P.M
<b>2<sup>nd</sup> Date</b>	From the date of publication upto <b>03/04/2018</b> till 11.00 a.m	<b>03/04/2018</b> till 12.00 Noon	<b>03/04/2018</b> at 01.00 P.M

EXECUTIVE ENGINEER  
BUILDINGS DIVISION,  
KASHMORE @ KANDHKOT

SPPRA INWARD DIARY

No: 6449

DATED: 28/2/2018

Copy fwc's for favour of information to:-

01. The P.S to Deputy Commissioner Kashmore @ Kandhkot.
02. The Director of Information 96 Sindh Secretariat Karachi, along with seven (7) copies of the list for publication in three leading News paper i.e One in English, One in Urdu and One in Sindhi, specially local news paper daily as per latest rules regulations framed by the Government of Sindh. If publication is made in more than three news paper , no payment for extra publication will be made.
03. The Director SPPRA Sindh Karachi for information and hosting the advertisement on the site of SPPRA.
04. The Secretary Information (Technology) Government of Sindh Karachi for information and insertion on Government Web Site.
05. The Superintending Engineer Works & Services Department Kashmore @ Kandhkot.
06. The Executive Engineer (All) Kashmore @ Kandhkot.
07. The Assistant Engineer Buildings (All) working under Executive Engineer Buildings Kashmore @ Kandhkot.
08. Copy to Notice Board / Head Clerk / Drafts man ( Local).

  
EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT

# LIST OF WORK

S.#	NAME OF SCHEME	COST IN MILLION	EARNST MONEY	TENDER FFF	TIME ALLOWED
<b>Community Development Sustainable Goals Programme 2017-2018</b>					
1	Installation of Solar Street Light Poles from House of Syed Bashir Ahmed Shah Ghouspur Taluka Kandhkot	2.000	0.100	3,000	12 Months
2	Installation of Solar Street Light Poles from Syed Yaqoob Shah House upto Dargah Jeelani Badha Ghouspur Taluka Kandhkot	2.000	0.100	3,000	12 Months
3	Installation of Solar Street Light Poles in Village Asadullah Khan Khoso Taluka Tangwani	1.000	0.050	1,500	12 Months
4	Construction of Tough Tile / Paver Road in Village Lahri Khan Malik Taluka Kashmore	1.000	0.050	1,500	12 Months
5	Construction of Tough Tile / Paver Road in Village Atthar Khan Domki Taluka Kashmore	1.000	0.050	1,500	12 Months
6	Construction of Tough Tile / Paver Road from Union Council Office Ground U/C R.B Chachar Taluka Kashmore	2.000	0.100	3,000	12 Months
7	Construction of Tough Tile / Paver Road in Village Mohammad Nawaz Golo U/C Elsi Taluka Kashmore	1.000	0.050	1,500	12 Months
8	Construction of Guard Room for Security in Revenue Colony Dera More Kashmore	1.000	0.050	1,500	12 Months
9	Construction of Compound Wall Eid Gah at Village Sain Rakhio Mirani Taluka Kandhko	2.000	0.100	3,000	12 Months
10	Constrution of Musafir Khana at Village Dargah Bharchondi Sharif Taluka Kashmore	3.000	0.150	3,000	12 Months
11	Construction of Government Dispensary at Village Rais Noor Ahmed Bhayo Taluka Kandhkot				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
12	Construction of Government Dispensary at Village Abdul Rasheed Ogahi Taluka Kandhkot				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
13	Construction of Government Dispensary at Village Riaz Bahlkani Taluk Tangwani				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
14	Construction of Government Dispensary at Village Wadero Saif Din Khan Jakhrani U/C Mahar Taluka Kashmore				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
15	Construction of Government Dispensary at Village Kathgarh Taluka kashmore				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
16	Construction of Government Dispensary at Village Abdullah Domki Taluka Kashmore				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
17	Construction of Government Dispensary at Village Malik Larho Taluka Kashmore				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
18	Construction of Government Dispensary at Village Arbelo Khan Bangwar Taluka Kashmore				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
19	Construction of Government Dispensary at Village Mohammad Nawaz Bangwar Taluka Kashmore				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
20	Construction of Government Dispensary at Village Haji Sawan Jakhrani Taluka Kashmore				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
21	Construction of Government Dispensary at Village Mushtaque Ali Bangwar U/C Kumb Taluka Kashmore				
	a) Civil Work	1.850	0.093	3,000	12 Months
	b) Electric Work	0.150	0.008	1,000	12 Months
22	Construction of Jamia Masjid Murad Wah Kashmore "Remaining Work"	14.000	0.700	3,000	12 Months

S.#	NAME OF SCHEME	COST IN MILLION	EARNEST MONEY	TENDER	TIME ALLOWED
23	Construction of Eid Gah Dari Taluka Kandhkot	5.000	0.250	3,000	12 Months
24	Construction of Eid Gah in Village Haibat Taluka Kandhkot	2.000	0.100	3,000	12 Months
25	Construction of Tough Tile / Paver Road and Drainage in 16 Wards M.C Kandhkot	16.000	0.800	3,000	12 Months
26	Construction of Tough Tile / Paver Road from Village Qaloo Khan Bhayo Taluka Kandhkot	4.000	0.200	3,000	12 Months
27	Construction of Tough Tile / Paver Road from Baxio Lolai to Sindh Dhoro Taluka Kandhkot	0.900	0.045	1,500	12 Months
28	Construction of Tough Tile / Paver Road in Village Rano Mirani U/C Naseer Taluka Kandhkot	0.900	0.045	1,500	12 Months
29	Construction of Tough Tile / Paver Road Out Side House of Agha Arsalan Pathan & Other Streets Ward No. 11 Taluka Kandhkot	1.600	0.080	3,000	12 Months
30	Construction of Tough Tile / Paver Road in Village Rais Yaqoob Bhutto Badani Taluka Kashmore	2.000	0.100	3,000	12 Months
31	Construction of Tough Tile / Paver Road in Village Rais Munwar Bhutto Badani Taluka Kashmore	2.000	0.100	3,000	12 Months
32	Construction of Tough Tile / Paver Road in Village Jam Jumo Samejo Badani Taluka Kandhkot	2.000	0.100	3,000	12 Months
33	Construction of Tough Tile / Paver Road in Village Ali Hassan Khokhar Badani Taluka Kashmore	1.000	0.050	1,500	12 Months
34	Installation of Solar Street Light Poles in Village Rais Mohammad Hayat Ogahi Taluka Kandhkot	1.500	0.075	2,000	12 Months
35	Installation of Solar Street Light Poles in Village Dari Taluka Kandhkot	5.700	0.285	3,000	12 Months
36	Installation of Solar Street Light Poles in Ghouspur Town	10.000	0.500	3,000	12 Months
37	M&R to Old Mukhtiarkar Bungalow at Kandhkot (Occupied by Civil Judge)	0.150	0.008	1,000	12 Months
38	Renovation and Rehabilitation of Sain Mana Ram Mandar Mirzapur Mohalla Kandhkot	20.000	1.000	1,000	12 Months
39	M&R to Cat IIIrd Bungalow No.03 Occupied by I.S.I Sub-Division Complex Kashmore	0.150	0.008	1,000	12 Months
40	M&R to Cat IIIrd Bungalow No. (Occupied Mukhtiarkar Kashmore)	0.150	0.008	1,000	12 Months
41	M&R to office of Executive Engineer & Assistant Engineer (Buildings) Kandhkot	0.135	0.007	1,000	12 Months
42	M&R to Investigation Office in Sub-Divisional Complex at Kashmore	0.150	0.008	1,000	12 Months
43	M&R to Day to Day Emergent Work in District Kashmore @ Kandhkot	0.150	0.008	1,000	12 Months
44	M&R to M.C.H Centre at Kandhkot	0.200	0.010	1,000	12 Months
45	M&R to R.H.C Tangwani i/c Electric Work	0.300	0.015	1,000	12 Months
46	M&R to Staff Quarter in Works & Services Colony at Kandhkot (Occupied by Office Superintendent).	0.100	0.005	1,000	12 Months

EXECUTIVE ENGINEER  
(BUILDINGS) ENGINEER  
KASHMORE @ KANDHKOT





**GOVERNMENT OF SINDH  
WORKS & SERVICES DEPARTMENT**

Karachi dated the 29<sup>th</sup> November, 2016.

**NOTIFICATION**

**No.E&A(W&S)3-9/2016 (KK)** : With the approval of Competent Authority, Procurement Committee, in terms of Rule-7 of Sindh Public Procurement Rules-2010 (Amended 2013), is hereby constituted for procurement of "Goods - Works" in the "Office : Executive Engineer, Buildings Division, Kashmore @ Kandhkot" excluding, procurement involving foreign exchange, with the following composition:-

1.	Executive Engineer, Buildings Division, Kashmore @ Kandhkot	Chairman
2.	Executive Engineer, Highways Division, Kashmore @ Kandhkot	Member
3.	Executive Engineer, Public Health Engineering Division, Kashmore @ Kandhkot	Member

2. The Functions & Responsibilities of the Committee will be same as specified in Rule-7 & 8 of Sindh Public Procurement Rules-2010.

**SECRETARY TO GOVT. OF SINDH**

**No.E&A(W&S)3-9/2016 (KK)**

Karachi, dated the 29<sup>th</sup> November, 2016.

A copy is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Managing Director, SPPRA, Karachi.
3. The Chief Engineer (Buildings), Sukkur
4. The Chairman / Members of the Committee.
5. The Deputy Director (Monitoring), PM&E Cell, W&SD.
6. PS to Minister, Works & Services Sindh
7. PS to Secretary, W&S Department.
8. Notification file

**SECTION OFFICER (GENERAL)  
FOR SECRETARY TO GOVT. OF SINDH**



**GOVERNMENT OF SINDH  
WORKS & SERVICES DEPARTMENT**

Karachi, dated the 29<sup>th</sup> November, 2016

**NOTIFICATION**

**No.E&A(W&S)3-9/2016 (KK):** With the approval of Competent Authority a Committee with the following composition, in terms of Rule-31 of Sindh Public Procurement Rules-2010 is hereby constituted a complaint redressal Committee for redressal of grievances and settlement of disputes, if any, arises between procuring agency and bidders in the Office of Executive Engineer, Buildings Division, Kashmore @ Kandhkot:-

- |      |  |          |
|------|--|----------|
| i)   | Superintending Engineer (W&S)<br>Kashmore @ Kandhkot   | Chairman |
| ii)  | Divisional Accounts Officer, Kashmore @ Kandhkot   | Member   |
| iii) | An independent professional from the relevant field<br>(Technical Expert) from Market privately, who is<br>Well versed with procurement process under SPPRA<br>Rules 2010. | Member   |

2. The Functions & Responsibilities of the Committee will be same as specified in Rules-31(4) and (5) of Sindh Public Procurement Rules-2010

**AIJAZ AHMED MEMON  
SECRETARY TO GOVT. OF SINDH**

**No.E&A(W&S)3-9/2016 (KK)**

Karachi dated the 29<sup>th</sup> November, 2016

A copy is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Managing Director, SPPRA, Karachi.
3. The Chief Engineer (Highways), Sukkur.
4. The Deputy Secretary (Staff) to Chief Secretary, Sindh, Karachi.
5. The Chairman / Members of the Committee
6. The Deputy Director (Monitoring), PM&E Cell, W&SD.
7. P S to Secretary, W&S Department, Govt. of Sindh, Karachi.
8. The District Accounts Officer, Hyderabad
9. Notification file.

**SECTION OFFICER (GENERAL)  
FOR SECRETARY TO GOVT. OF SINDH**

**REVISED ANNUAL PROCUREMENT PLAN  
WORKS & SERVICES DEPARTMENT  
(FINANCIAL YEAR 2017-2018)**

**OFFICE OF THE EXECUTIVE ENGINEER BUILDINGS DIVISION KASHMORE @ KANDHKOT**

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
1		Construction of Mosque at Village Mehboob Dhall Jakhrani U/C Mulguzar Taluka Kandhkot (Phase-I).						National Competitive Bidding Method					
		a) Civil Work			0.950	0.238	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.050	0.013	District ADP	--do--	--	Yes	--	--	--
2		Construction of Mosque alongwith Solar in Village Bahadur Khan Mirani Taluka Kandhkot.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--
3		Renovation & Rehabilitation of Masjid at Village Ismail Essani Taluka Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
4		Renovation & Rehabilitation of Masjid at Village Nazar Ali Dahani Taluka Tangwani.			0.400	0.100	District ADP	--do--	--	Yes	--	--	--
5		Renovation & Rehabilitation of Masjid at Village Ghulam Ali Dahani Taluka Tangwani.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
6		Renovation & Rehabilitation of Masjid Haji Khan at Village Dari Taluka Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
7		Renovation & Rehabilitation of Masjid in Civil Hospital at Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
8		Renovation & Rehabilitation of D.C Office Masjid at Kandhkot.			3.000	0.750	District ADP	--do--	--	Yes	--	--	--
9		Renovation & Rehabilitation of Dargah Dado Jeo Faqeer Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
10		Construction of Madarsa Faizane Hasnain Opposite B-Section Police Station at Kandhkot.			3.000	0.750	District ADP	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
11		Construction of Compound Wall Suhryani Graveyard Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
12		Construction of Compound Wall Graveyard at Abdul Rasool Dahani Taluka Tangwani.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
13		Construction of Compound Wall I/C Earth filling in Graveyard in Village Dari Taluka Kandhkot.			6.000	1.500	District ADP	National Competitive Bidding Method	--	Yes	--	--	--
14		Construction of Boundary Wall in Graveyard at Village Nobat Khan Bangwar U/C R.B Chachar Taluka Kashmore.			1.500	0.375	District ADP	--do--	--	Yes	--	--	--
15		Construction of Entrance Gate of D.C Office / Residence at Kandhkot.			5.000	1.250	District ADP	--do--	--	Yes	--	--	--
16		Construction of Entrance Gate 02 Nos. at Kandhkot.			7.500	1.875	District ADP	--do--	--	Yes	--	--	--
17		Construction of Census Office / Canteen and Anti Encroachment Office at D.C Office I/C 02 Nos. Wash Rooms at Kandhkot.			7.000	1.750	District ADP	--do--	--	Yes	--	--	--
18		Construction of Citizen Club at Kandhkot (Remaining Work).			10.000	2.500	District ADP	--do--	--	Yes	--	--	--
19		Construction of Sweet House at Kandhkot.			5.000	1.250	District ADP	--do--	--	Yes	--	--	--
20		Construction of Additional Rooms in 1/5 Madadgar at Kandhkot.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			0.950	0.238	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.050	0.013	District ADP	--do--	--	Yes	--	--	--
21		Construction of Assistant Commissioner Residence at Kandhkot.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			4.750	1.188	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.250	0.063	District ADP	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
22		Construction of Public Toilets at Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
23		Construction of Boundary Wall at Revenue Quarter Flats at Kandhkot.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
24		Remaining Work of Beautification in Kandhkot City Taluka Kandhkot. (Fountains).			3.000	0.750	District ADP	--do--	--	Yes	--	--	--
25		Remaining Work of Dialysis Centre at Kandhkot.			10.000	2.500	District ADP	--do--	--	Yes	--	--	--
26		Tree Plantation at Karampur Town Taluka Tangwani.			1.000	0.250	District ADP	National Competitive Bidding Method	--	Yes	--	--	--
27		Up-Gradation of Basic Health Unit at Village Aijaz Ali Dahani Taluka Tangwani (remaining work).			5.000	1.250	District ADP	--do--	--	Yes	--	--	--
28		Renovation & Rehabilitation of D.C Office / Furniture, Equipments, Electric Work and A.C Offices / Mukhtiarkar Offices Tangwani / Kandhkot / Kashmore.			15.000	3.750	District ADP	--do--	--	Yes	--	--	--
29		Renovation & Rehabilitation of D.C House I/C Furniture & Electric Work at Kandhkot.			9.000	2.250	District ADP	--do--	--	Yes	--	--	--
30		Renovation & Rehabilitation of Peoples Party Office at Kandhkot.			3.000	0.750	District ADP	--do--	--	Yes	--	--	--
31		Renovation & Rehabilitation of Judicial Lock-up at Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
32		Renovation & Rehabilitation of Operation Theater in T.H.Q Hospital at Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
33		Renovation & Rehabilitation of Assistant Commissioner / Mukhtiarkar / Judicial Lock-up at Kashmore.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
34		Renovation & Rehabilitation of Revenue Rest House Dera More at Kashmore.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--



Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
35		Renovation & Rehabilitation of R.H.C Karampur Taluka Tangwani.			3.000	0.750	District ADP	--do--	--	Yes	--	--	--
36		Renovation & Rehabilitation of BHU at Mir Bijar Khan Bijarani Taluka Tangwani.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			1.500	0.375	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
37		Construction of Government Dispensary at Village Mohammad Khan Khoso U/C Sodhi Taluka Kashmore.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--
38		Construction of Government Dispensary at Village Zeeshan Golo U/C Zore Garh Taluka Kashmore.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--
39		Construction of Government Dispensary at Village Muheem Khan Bajkani U/C Gulwali Taluka Tangwani.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--
40		Construction of Government Dispensary at Village Qurban Ali Bangwar U/C Kumbri Taluka Kashmore.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--
41		Construction of Government Dispensary at Village Motio Khan Lashari U/C Lashari Taluka Tangwani.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimted unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
42		Construction of Government Dispensary at Village Mast Ali Mazari Taluka Kashmore.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--
43		Construction of Government Dispensary at Village Abdul Bari Khoso U/C Doulatpur Taluka Kandhkot.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--
44		Construction of Government Dispensary at Village Hamid Khan Bahlkani Taluka Tangwani.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--
45		Construction of Government Dispensry at Village Muqdam Mohammad Murad Nindwani U/C Jamal Taluka Tangwani.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			3.800	0.950	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.200	0.050	District ADP	--do--	--	Yes	--	--	--
46		Construction of Government Dispensary at Village Kathoor Khan Bangwar U/C Doulatpur Taluka Kandhkot.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			1.850	0.463	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.150	0.038	District ADP	--do--	--	Yes	--	--	--
47		Construction of Government Dispensary at Village Ameer Hussain Golato U/C Toj Taluka Kashmore.				-	District ADP	--do--	--	Yes	--	--	--
		a) Civil Work			1.850	0.463	District ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.150	0.038	District ADP	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timining of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
48		Construction of Tough Tile / Paver Road from House of Jameel Kakal & Various Streets of U/C-4 Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
49		Construction of Tough Tile / Paver Road / Park in Session Court New Building Kandhkot.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
50		Construction of Tough Tile / Paver Road in Village Kundo Khan Bakhrani to Primary School Taj Mohammad Bakhrani U/C Lashari Taluka Tangwani.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
51		Construction of Tough Tile / Paver Road in Village Farhad Ali Golato U/C Malguzar Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
52		Construction of Tough Tile / Paver Road in Village Muqdam Wajib Khan Golato U/C Cheel Taluka Tangwani.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
53		Construction of Tough Tile / Paver Road in Village Ghulam Fareed Suhryani U/C Bahkani Taluka Tangwani.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
54		Construction of Tough Tile / Paver Road in Village Master Sodho Khan Chachar U/C Haibat Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
55		Construction of Tough Tile / Paver Road from Kashmore Road to Jamia Darul Fiuz to Liaqat Khoso House Station Road Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
56		Construction of Tough Tile / Paver Road Khair Shah Link Road to Village Haji Faiz Mohammad Bangwar Deh Suhryani pur U/C Doulatpur Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimted unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timining of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
57		Construction of Tough Tile / Paver Road in Village Wakif Khan Bajkani U/C Manjhee Taluka Tangwani.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
58		Construction of Tough Tile / Paver Road Doli Chowk to House of Bashir Ahmed Shah Ghouspur Taluka Kandhkot.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--
59		Construction of Tough Tile / Paver Road in Village Riyasat Ali Dahani Taluka Tangwani.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
60		Construction of Tough Tile / Paver Road in Village Mir Irshad Ali Bajkani Taluka Tangwani.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
61		Construction of Tough Tile / Paver Road in Village Arbab Ali Ogahi Taluka Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
62		Construction of Tough Tile / Paver Road in Village Nazar Ali Dahani Taluka Tangwani.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
63		Construction of Tough Tile / Paver Road in Village Wasoo Khan Laghani U/C R.B Chachar Taluka Kashmore.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
64		Construction of Tough Tile / Paver Road Imam Bargah Syed Ghulam Muhibullah Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
65		Construction of Tough Tile / Paver Road in Village Nawab Khan Dahani Taluka Tangwani.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
66		Construction of Tough Tile / Paver Road Madina Masjid Main Railway Station Road to Shop of Ghous Bux Soomro Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimted unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timining of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
67		Construction of Tough Tile / Paver Road in Town Committee to Dargah / Shaikh House and various streets of Ghouspur Town Taluka Kandhkot.			1.500	0.375	District ADP	--do--	--	Yes	--	--	--
68		Construction of Tough Tile / Paver Road in Village Abdul Qadir Bhayo Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
69		Construction of Tough Tile / Paver Road in Village Haibat Bajkani to Shaman Bajkani Taluka Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
70		Construction of Tough Tile / Paver Road in Shaheed Benazir Colony Ward No.05 Taluka Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
71		Construction of Tough Tile / Paver Road in Village Mir Bagan Khan Domki Buxapur City Taluka Kashmore.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
72		Construction of Tough Tile / Paver Road from House of Agha Zulfiqar Pathan Nanik Mohalla U/C-04 Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
73		Construction of Tough Tile / Paver Road from house of Agha Waqas & various streets of U/C-04 Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
74		Construction of Tough Tile / Paver Road in Village Aftab Dhall Jakhrani Taluka Tangwani.			4.500	1.125	District ADP	--do--	--	Yes	--	--	--
75		Construction of Tough Tile / Paver Road in Village Mohammad Amin Bangwar U/C Akhero Taluka Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
76		Construction of Tough Tile / Paver Road Ghulam Mustafa Mirani House to Ali Hassan Malik House Eid Gah Mohalla Kandhkot.			0.500	0.125	District ADP	--do--	--	Yes	--	--	--



Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
77		Construction of Tough Tile / Paver Road Eid Gah Mohalla Ali Sher Khan Malik House Kandhkot			0.500	0.125	District ADP	--do--	--	Yes	--	--	--
78		Construction of Tough Tile / Paver Road from Station Road via Masood Soomro House Railway Station Kandhkot.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--
79		Construction of Tough Tile / Paver Road from House Ashique Ali Chajjan Gulsher Mohalla Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
80		Construction of Tough Tile / Paver Road in Village Zeeshan Ahmed Golo U/C Zore Garh Taluka Kashmore.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
81		Construction of Tough Tile / Paver Road in Ward No.02 Kashmore.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
82		Construction of Tough Tile / Paver Road in Village Haji Noor Khoso Taluka Tangwani.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--
83		Construction of Tough Tile / Paver Road in Village Mohammad Khan Khoso Taluka Tangwani.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--
84		Construction of Tough Tile / Paver Road in Village Mohammad Hayat Ogahi Taluka Kandhkot.			1.500	0.375	District ADP	--do--	--	Yes	--	--	--
85		Construction of Tough Tile / Paver Road in Village Bhannar Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
86		Construction of Tough Tile / Paver Road in Village Jehan Khan Bangwar & Various streets Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
87		Construction of Tough Tile / Paver Road in Village Shahmore Khan Bangwar U/C Akhero Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
88		Construction of Tough Tile / Paver Road in Village Qadir Bux Khoso U/C Doulatpur Taluka Kandhkot.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
89		Construction of Tough Tile / Paver Road from Mehboob Ali Bangwar Link Road to Village Faqeer Mohammad Hassan Bangwar U/C R.B Chachar Taluka Kashmore.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--
90		Construction of Tough Tile / Paver Road from House of Qurban Ali Bangwar Workshop Mohalla Kandhkot.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
91		Construction of Tough Tile / Paver Road from House of Ghulam Sarwar Golo & various streets ward No.02 Kandhkot.			1.500	0.375	District ADP	--do--	--	Yes	--	--	--
92		Construction of Tough Tile / Paver Road from House of Abdul Razzaque Mazari Eid Gah Moahlla Kashmore-02 Taluka Kashmore.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
93		Construction of Tough Tile / Paver Road in Village Fatehuddin Bajkani U/C Gulwali Taluka Tangwani.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
94		Construction of Tough Tile / Paver Road in Village Rasool Bux Menik U/C Doulatpur Taluka Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
95		Construction of Tough Tile / Paver Road Rasaldar Raod to Amir Hussain Golato to Mohammad Khan Gabol Taluka Kandhkot.			2.000	0.500	District ADP	--do--	--	Yes	--	--	--
96		Construction of Tough Tile / Paver Road from House of Haji Mohammad Ramzan Panhyar & various streets of Golimar Mohalla Kandhkot.			1.000	0.250	District ADP	--do--	--	Yes	--	--	--
97		Construction of Tough Tile / Paver Road in Village Malguzar Khan Suhryani U/C Zore Garh Taluka Kashmore.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--
98		Installation of Solar Lights Poles in Village Mari Sher Mohammad U/C Saifal Taluka Tangwani.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--
99		Installation of Solar Lights Poles in Village Dodaiko U/C Karampur Taluka Tangwan.			2.500	0.625	District ADP	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
100		Installation of Solar Lights Poles in Village Sam Bus Dahani U/C Naseer Taluka Tangwani.			2.500	0.625	District ADP	---do--	--	Yes	--	--	--
101		Construction of Tough Tile / Paver Road from Haibat Road to House of Shahzade Khoso Taluka Kandhkot.			4.000	1.000	District ADP	---do--	--	Yes	--	--	--
102		Installation of Solar Lights Poles in Village Rais Ghulam Hyder Awan U/C Wakro Taluka Kandhkot.			2.500	0.625	District ADP	---do--	--	Yes	--	--	--
103		Installation of Solar Lights Poles in Village Hyder Ali Dahani U/C Tangwani Taluka Tangwani.			2.500	0.625	District ADP	---do--	--	Yes	--	--	--
104		Renovation & Rehabilitation of BHU Hafeezullah Khoso Taluka Tangwani (Electric Work).			0.700	0.175	District ADP	---do--	--	Yes	--	--	--
105		Construction of Government Dispensary at Village Shahdad Khan Malik Taluka Tangwani (Electric Work).			0.500	0.125	District ADP	---do--	--	Yes	--	--	--
106		Construction Residential Flats for Lower Staff Quarters in T.H.Q Hospital at Kandhkot "Remaining Work"			4.000	1.000	District ADP	---do--	--	Yes	--	--	--
107		Const. of Government Dispensary at Village Malhoo Khan Bhayo Taluka Kandhkot											
		a) Civil Work			2.150	2.150	OGDCL	---do--	--	Yes	--	--	--
		b) Electric Work			0.150	0.150	OGDCL	---do--	--	Yes	--	--	--
108		Const. of Government Dispensary at Village Sardar Taj Mohammad Khan Muhammadani Taluka Kandhkot											
		a) Civil Work			2.050	2.050	OGDCL	---do--	--	Yes	--	--	--
		b) Electric Work			2.050	2.050	OGDCL	---do--	--	Yes	--	--	--
109		Const. of Government Dispensary at Village Sardar Taj Mohammad Khan Muhammadani Taluka Kandhkot			1.500	1.500	OGDCL	---do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
110		Renovation & Rehabilitation of Press Club Kandhkot "Remaining Work"											
		a) Civil Work			4.579	1.145	DISTRICT ADP	--do--	--	Yes	--	--	--
		b) Electric Work			0.500	0.125	DISTRICT ADP	--do--	--	Yes	--	--	--
111		Construction of Government Dispensary at Village Ahmdan Khan Bangwar Taluka Kandhkot.	5.000		5.000	5.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
112		Construction of Eid Gah at Village Ghous Bux Bangwar Taluka Kandhkot.	5.000		5.000	5.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
113		Construction of Eid Gah at Village Jahan Khan Bangwar Taluka Kandhkot.	5.000		5.000	5.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
114		Construction of Compound Wall Graveyard at Village Haibat Shaheed Taluka Tangwani.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
115		Construction of Compound Wall Graveyard at Village Mitho Arab Khan Bhayo Taluka Kandhkot.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
116		Construction of CC Drain Kandhkot Shikarpur Road Near Jeelani Service Station Kandhkot.	1.500		1.500	1.500	C.D.P 2017-18	--do--	--	Yes	--	--	--
117		Construction of Shelter Hut at Karpur Hindu Shamshanghat Taluka Tangwani.	1.000		1.000	1.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
118		Renovation / Re-Construction of Eid Gah at Village Mir Bijar Khan Bijarani Taluka Tangwani.	5.000		5.000	5.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
119		Construction of Eid Gah at Village Khalid Brohi Taluka Tangwani.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
120		Construction of Eid Gah at Village Saeed Khan Rind Taluka Tangwani.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
121		Construction of Eid Gah at Village Shabirabad Taluka Tangwani.	5.000		5.000	5.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
122		Construction of Eid Gah at Village Khio Khan Balhkani Taluka Tangwani.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
123		Construction of Eid Gah at Village Kundo Bakhrani Taluka Tangwani.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
124		Construction of Eid Gah at Village Mansorabad Taluka Tangwani.	5.000		5.000	5.000	C.D.P 2017-18	--do--	--	Yes	--	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimted unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timining of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
125		Construction of Eid Gah at Village Haji Aitbar Brohi Taluka Tangwani.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
126		Construction of Eid Gah at Village Rahmatabad Taluka Kandhkot.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
127		Construction of Eid Gah at Village Raza Mohammad Khoso Taluka Kandhkot.	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
128		Installation of Solar Lights Poles in Village Mir Altaf Khan Khoso Taluka Tangwani.	3.000		3.000	3.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
129		Construction of Tough Tile / Paver Road in Karampur City Taluka Tangwani.	2.500		2.500	2.500	C.D.P 2017-18	--do--	--	Yes	--	--	--
130		Installation of Solar Lights Poles in Village Mohammad Murad Nindwani Taluka Tangwani.	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
131		Installation of Solar Lights Poles in Village Mir Taj Mohammad Bijarani Taluka Tangwani.	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
132		Installation of Solar Lights Poles in Village Mansoorabad Taluka Tangwani.	3.000		3.000	3.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
133		Installation of Solar Lights Poles in Village new Alif Khan Bijarani Taluka Tangwani.	5.000		5.000	5.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
134		Installation of Solar Lights Poles in Village Gotho Abdul Rahim Nindwani Taluka Tangwani.	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
135		Installation of Solar Lights Poles in Village Ata Mohammad Mehon Nindwani Taluka Tangwani.	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	Yes	--	--	--
136		Installation of Solar Lights Poles in Village Azad Nindwani Taluka Tangwani.	1.500		1.500	1.500	C.D.P 2017-18	--do--	--	Yes	--	--	--
137		Construction of Makbara (Late) Syed Mehmood Shah Tyar Ghazi at Village Jahan Khan Bangwar Deh Akhero Taluka Kandhkot.	1.300		1.300	1.300	C.D.P 2017-18	--do--	--	Yes	--	--	--
138		Construction of Tough Tile / Paver Road in Village Nazar Ali Dahani Taluka Kandhkot.	1.400		1.400	1.400	C.D.P 2017-18	--do--	--	Yes	--	--	--
139		Construction of Tough Tile / Paver Road in Village Sher Mohammad Golo U/C Rasaldar Taluka Kandhkot.	1.300		1.300	1.300	C.D.P 2017-18	--do--	--	Yes	--	--	--
140		Installation of Solar Street Light Poles from House of Syed Bashir Ahmed Shah Ghouspur Taluka Kandhkot	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	--	Yes	--	--



Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
141		Installation of Solar Street Light Poles from Syed Yaqoob Shah House upto Dargah Jeelani Badha Ghouspur Taluka Kandhkot	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
142		Installation of Solar Street Light Poles in Village Asadullah Khan Khoso Taluka Tangwani	1.000		1.000	1.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
143		Construction of Tough Tile / Paver Road in Village Lahri Khan Malik Taluka Kashmore	1.000		1.000	1.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
144		Construction of Tough Tile / Paver Road in Village Atthar Khan Domki Taluka Kashmore	1.000		1.000	1.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
145		Construction of Tough Tile / Paver Road from Union Council Office Ground U/C R.B Chachar Taluka Kashmore	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
146		Construction of Tough Tile / Paver Road in Village Mohammad Nawaz Golo U/C Elsi Taluka Kashmore	1.000		1.000	1.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
147		Construction of Guard Room for Security in Revenue Colony Dera More Kashmore	1.000		1.000	1.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
148		Construction of Compound Wall Eid Gah at Village Sain Rakhio Mirani Taluka Kandhko	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
149		Construction of Musafir Khana at Village Dargah Bharchondi Sharif Taluka Kashmore	3.000		3.000	3.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
150		Construction of Government Dispensary at Village Rais Noor Ahmed Bhayo Taluka Kandhkot					C.D.P 2017-18	--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	--do--	--	--	Yes	--	--
151		Construction of Government Dispensary at Village Abdul Rasheed Ogahi Taluka Kandhkot					C.D.P 2017-18	--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	--do--	--	--	Yes	--	--
152		Construction of Government Dispensary at Village Riaz Bahlkani Taluk Tangwani					C.D.P 2017-18	--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	--do--	--	--	Yes	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimated unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
153		Construction of Government Dispensary at Village Wadero Saif Din Khan Jakhrani U/C Mahar Taluka Kashmore					C.D.P 2017-18	.--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	.--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	.--do--	--	--	Yes	--	--
154		Construction of Government Dispensary at Village Kathgarh Taluka kashmore					C.D.P 2017-18	.--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	.--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	.--do--	--	--	Yes	--	--
155		Construction of Government Dispensary at Village Abdullah Domki Taluka Kashmore					C.D.P 2017-18	.--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	.--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	.--do--	--	--	Yes	--	--
156		Construction of Government Dispensary at Village Malik Larho Taluka Kashmore					C.D.P 2017-18	.--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	.--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	.--do--	--	--	Yes	--	--
157		Construction of Government Dispensary at Village Arbelo Khan Bangwar Taluka Kashmore					C.D.P 2017-18	.--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	.--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	.--do--	--	--	Yes	--	--
158		Construction of Government Dispensary at Village Mohammad Nawaz Bangwar Taluka Kashmore					C.D.P 2017-18	.--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	.--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	.--do--	--	--	Yes	--	--
159		Construction of Government Dispensary at Village Haji Sawan Jakhrani Taluka Kashmore					C.D.P 2017-18	.--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	.--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	.--do--	--	--	Yes	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimted unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timining of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
160		Construction of Government Dispensary at Village Mushtaque Ali Bangwar U/C Kumb Taluka Kashmore					C.D.P 2017-18	--do--	--	--	Yes	--	--
		a) Civil Work	1.850		1.850	1.850	C.D.P 2017-18	--do--	--	--	Yes	--	--
		b) Electric Work	0.150		0.150	0.150	C.D.P 2017-18	--do--	--	--	Yes	--	--
161		Construction of Jamia Masjid Murad Wah Kashmore "Remaining Work"	14.000		14.000	14.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
162		Construction of Eid Gah Dari Taluka Kandhkot	5.000		5.000	5.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
163		Construction of Eid Gah in Village Haibat Taluka Kandhkot	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
164		Construction of Tough Tile / Paver Road and Drainage in 16 Wards M.C Kandhkot	16.000		16.000	16.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
165		Construction of Tough Tile / Paver Road from Village Qaloo Khan Bhayo Taluka Kandhkot	4.000		4.000	4.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
166		Construction of Tough Tile / Paver Road from Baxio Lolai to Sindh Dhoro Taluka Kandhkot	0.900		0.900	0.900	C.D.P 2017-18	--do--	--	--	Yes	--	--
167		Construction of Tough Tile / Paver Road in Village Rano Mirani U/C Naseer Taluka Kandhkot	0.900		0.900	0.900	C.D.P 2017-18	--do--	--	--	Yes	--	--
168		Construction of Tough Tile / Paver Road Out Side House of Agha Arsalan Pathan & Other Streets Ward No. 11 Taluka Kandhkot	1.600		1.600	1.600	C.D.P 2017-18	--do--	--	--	Yes	--	--
169		Construction of Tough Tile / Paver Road in Village Rais Yaqoob Bhutto Badani Taluka Kashmore	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
170		Construction of Tough Tile / Paver Road in Village Rais Munwar Bhutto Badani Taluka Kashmore	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
171		Construction of Tough Tile / Paver Road in Village Jam Jumo Samejo Badani Taluka Kandhkot	2.000		2.000	2.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
172		Construction of Tough Tile / Paver Road in Village Ali Hassan Khokhar Badani Taluka Kashmore	1.000		1.000	1.000	C.D.P 2017-18	--do--	--	--	Yes	--	--

Sr No	ADP No:	Description of Procurement	Quality (Where Applicable)	Estimted unit cost (Where Applicable)	Estimated Total Cost	Fund Allocated	Source of Funds ADP/ Non ADP	Proposed Procurement Method	Timining of Procurement				Remarks
									1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
173		Installation of Solar Street Light Poles in Village Rais Mohammad Hayat Ogahi Taluka Kandhkot	1.500		1.500	1.500	C.D.P 2017-18	--do--	--	--	Yes	--	--
174		Installation of Solar Street Light Poles in Village Dari Taluka Kandhkot	5.700		5.700	5.700	C.D.P 2017-18	--do--	--	--	Yes	--	--
175		Installation of Solar Street Light Poles in Ghouspur Town	10.000		10.000	10.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
176		M&R to Old Mukhtiarkar Bungalow at Kandhkot (Occupied by Civil Judge)	0.150		0.150	0.150	M&R Programme	--do--	--	--	Yes	--	--
177		Renovation and Rehabilitation of Sain Mana Ram Mandar Mirzapur Mohalla Kandhkot	20.000		20.000	20.000	C.D.P 2017-18	--do--	--	--	Yes	--	--
178		M&R to Cat Illrd Bungalow No.03 Occupied by I.S.I Sub-Division Complex Kashmore	0.150		0.150	0.150	M&R Programme	--do--	--	--	Yes	--	--
179		M&R to Cat Illrd Bungalow No. (Occupied Mukhtiarkar Kashmore)	0.150		0.150	0.150	M&R Programme	--do--	--	--	Yes	--	--
180		M&R to office of Executive Engineer & Assistant Engineer (Buildings) Kandhkot	0.135		0.135	0.135	M&R Programme	--do--	--	--	Yes	--	--
181		M&R to Investigation Office in Sub-Divisional Complex at Kashmore	0.150		0.150	0.150	M&R Programme	--do--	--	--	Yes	--	--
182		M&R to Day to Day Emergent Work in District Kashmore @ Kandhkot	0.150		0.150	0.150	M&R Programme	--do--	--	--	Yes	--	--
183		M&R to M.C.H Centre at Kandhkot	0.200		0.200	0.200	M&R Programme	--do--	--	--	Yes	--	--
184		M&R to R.H.C Tangwani	0.300		0.300	0.300	M&R Programme	--do--	--	--	Yes	--	--
185		M&R to Staff Quarter in Works & Services Colony at Kandhkot (Occupied by Office Superintendent).	0.100		0.100	0.100	M&R Programme	--do--	--	--	Yes	--	--

  
**EXECUTIVE ENGINEER**  
**(BUILDINGS) DIVISION**  
**KASHMORE @ KANDHKOT**

# SPPRA BIDDING DOCUMENT

Sr No: 01



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Installation of Solar Street Light Poles from House of Syed Bashir  
Ahmed Shah Ghouspur Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**



**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Installation of Solar Street Light Poles from House of Syed Bashir Ahmed Shah Ghouspur Taluka Kandhkot*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *2.000 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHDULE-(B)**  
**INSTALLATION OF SOLAR LIGHTS POLES FROM HOUSE OF SYED BASHIR**  
**AHMED SHAH GHOSPUR TALUKA KANDHKOT (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S.No.	Name of Item	Qty:	Rate	Unit	Amount
1.	Providing superior imported quality of M.S Hexagonal Pole of 25 ft. height with proper warping secured having the following specification and designed for may wind velocity with paint final coat.  Specification are as under:-  10'-4" 10'-3" 5'-2 1/2" and with base plate 1' 1/2" x 1' 1/2" complete with all accuracies. (Quoted by Market Value)	10 Nos.		Each	
	<b>TOTAL</b>	10 Nos.		Each	
2	<b><u>SOLAR POWERED LED STREET LIGHT</u></b>	10 Nos.		Each	
		<b>Total 01 &amp; 02</b>			

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 02



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Installation of Solar Street Light Poles from Syed Yaqoob Shah House  
upto Dargah Jeelani Badha Ghouspur Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Installation of Solar Street Light Poles from Syed Yaqoob Shah House upto Dargah Jeelani Badha Ghouspur Taluka Kandhkot*
- (c).Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*

(d). Estimated Cost:-      *2.000 Million*

(e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)

(f).Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).

(g).Security Deposit:-(including bid security):-      *10%*

(in % age of bid amount /estimated cost equal to 10%)

(h). Percentage, if any, to be deducted from bills :-      *5%*

(i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*

(j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*

(k). Time for Completion from written order of commence: -      *12 Months*

(L).Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).

(m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHDULE-(B)**  
**INSTALLATION OF SOLAR LIGHTS POLES FROM SYED YAQOOB SHAH HOUSE**  
**UPTO DARGAH JEELANI BADHA GHOSHPUR TALUKA KANDHKOT**  
**(CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S.No.	Name of Item	Qty:	Rate	Unit	Amount
1.	Providing superior imported quality of M.S Hexagonal Pole of 25 ft. height with proper warping secured having the following specification and designed for may wind velocity with paint final coat.  <b>Specification are as under:-</b>  10'-4" 10'-3" 5'-2 1/2" and with base plate 1' 1/2" x 1' 1/2" complete with all accuracies. (Quoted by Market Value)	10 Nos.		Each	
	<b>TOTAL</b>	10 Nos.		Each	
2	<b><u>SOLAR POWERED LED STREET LIGHT</u></b>	10 Nos.		Each	
		<b>Total 01 &amp; 02</b>			

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* *Rs:*

*Diff: cost of Bitumen (B)* *Rs:*

*G.Total (A+B)* *Rs.*

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**



# **SPPRA BIDDING DOCUMENT**

Sr No: 03



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Installation of Solar Street Light Poles in Village Asadullah Khan  
Khoso Taluka Tangwani*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Installation of Solar Street Light Poles in Village Asadullah Khan Khoso Taluka Tangwani*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *1.000 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHDULE-(B)**  
**INSTALLATION OF SOLAR LIGHTS POLES IN VILLAGE ASADULLAH KHAN**  
**KHOSO TALUKA TANGWANI (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S.No.	Name of Item	Qty:	Rate	Unit	Amount
1.	Providing superior imported quality of M.S Hexagonal Pole of 25 ft. height with proper warping secured having the following specification and designed for may wind velocity with paint final coat.  <b>Specification are as under:-</b>  10'-4" 10'-3" 5'-2 ½" and with base plate 1' ½" x 1' ½" complete with all accuracies. (Quoted by Market Value)	05 Nos.		Each	
	<b>TOTAL</b>	05 Nos.		Each	
2	<b><u>SOLAR POWERED LED STREET LIGHT</u></b>	10 Nos.		Each	
		<b>Total 01 &amp; 02</b>			

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# **SPPRA BIDDING DOCUMENT**

Sr No: 04



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road in Village Lahri Khan  
Malik Taluka Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Tough Tile / Paver Road in Village Lahri Khan  
Malik Taluka Kashmore*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *1.000 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)



**SCHDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE LAHRI KHAN MALIK**  
**TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	150 Cft	8694/95	%Cft	13042/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	790 Cft	11948/36	%Cft	94392/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	975 Cft	9424/10	%0Cft	9188/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/60	%Cft	4198/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	244 Cft	8694/95	%Cft	21216/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	800 Sft	3015/76	%Cft	24126/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 197 x 80 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	975 Sft	199/77	P.Sft	194776/-
				<b>Total</b>	<b>348849/-</b>
				<b>Therefore 348849 x 286=</b>	<b>997708/-</b>
				<b>100</b>	

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 05



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road in Village Atthar  
Khan Domki Taluka Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Tough Tile / Paver Road in Village Atthar  
Khan Domki Taluka Kashmore*
- (c).Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.000 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g).Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L).Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE ATTHAR KHAN DOMKI**  
**TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	150 Cft	8694/95	%Cft	13042/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	790 Cft	11948/36	%Cft	94392/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	975 Cft	9424/10	%0Cft	9188/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/60	%Cft	4198/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	244 Cft	8694/95	%Cft	21216/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	800 Sft	3015/76	%Cft	24126/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 197 x 80 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	975 Sft	199/77	P.Sft	194776/-
				<b>Total</b>	<b>348849/-</b>
				<b>Therefore 348849 x 286=</b>	<b>997708/-</b>
				<b>100</b>	

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 06



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road from Union Council Office  
Ground U/C R.B Chachar Taluka Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***



**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Tough Tile / Paver Road from Union Council Office Ground U/C R.B Chachar Taluka Kashmore*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *2.000 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD FROM UNOIN COUNCIL OFFICE**  
**GROUND U/C R.B CHACHAR TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	3500 Cft	8694/95	%Cft	304323/-
02.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	7000 Cft	9024/10	%0Cft	63169/-
03.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	3500 Cft	1720/66	%Cft	60223/-
04.	Providing & fixing cement paving blocks flooring having size of 197 x 197 x 80 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	7000 Sft	199/77	P.Sft Total	<u>1398390/-</u> <b>1826105/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 07



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road in Village Mohammad  
Nawaz Golo U/C Elsi Taluka Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Tough Tile / Paver Road in Village Mohammad Nawaz Golo U/C Elsi Taluka Kashmore*
- (c).Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.000 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g).Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L).Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE MOHAMMAD NAWAZ**  
**GOLO U/C ELSI TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	150 Cft	8694/95	%Cft	13042/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	790 Cft	11948/36	%Cft	94392/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	975 Cft	9424/10	%0Cft	9188/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/60	%Cft	4198/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	244 Cft	8694/95	%Cft	21216/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	800 Sft	3015/76	%Cft	24126/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 197 x 80 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	975 Sft	199/77	P.Sft	194776/-
				<b>Total</b>	<b>348849/-</b>
					<b>Therefore 348849 x 286 = 997708/-</b>
					<b>100</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**



# SPPRA BIDDING DOCUMENT

Sr No: 08



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Guard Room for Security in Revenue  
Colony Dera More Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Guard Room for Security in Revenue Colony Dera More Kashmore*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.000 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GUARD ROOM FOR SECURITY IN REVENUE COLONY DERA**  
**MORE KASHMORE**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
<b>Part "A" MAIN BUILDING</b>					
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	511 Cft	3176/25	%0Cft	1623/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	153 Cft	8694/95	%Cft	13303/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	438 Cft	11948/36	%Cft	52334/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	358 Cft	337/-	P.Cft	120646/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	19.17 Cwt	5001/70	P.Cwt	95883/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	141 Cft	12674/36	%Cft	86439/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	265 Cft	1512/50	%0Cft	2497/-
08.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	133 Cft	1141/25	%Cft	1518/-
09.	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screening and washing of stone aggregate without shuttering 1:2:4 (S.I.No. 05 (i) P-18)	88 Cft	14429/25	%Cft	12698/-
10.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	1296 Sft	2206/60	%Sft	28598/-
11.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	1296 Sft	2197/52	%Sft	28480/-
12.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	894 Sft	1287/44	%Sft	11510/-
13.	First Class Deodar Wood	60 Sft	1273/76	P.Sft	76426/-
14.	P/L White Marble 3/4" thick	265 Sft	567/48	P.Sft	150382/-
15.	Dedo Marble	168 Sft	186/04	P.Sft	31255/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Supplying & fixing in position iron / steel grill of ¾" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	17 Sft	180/50	P.Sft	3069/-
17.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	120 Sft	2116/41	%Sft	3740/-
18.	S/F Matt Finish	1216 Sft	2717/-	%Sft	33039/-
19.	White Washing 03 Coats	265 Sft	829/95	%Sft	2199/-
20.	Wire Gauze	265 Sft	190/72	P.Sft	<u>3242/-</u>
				<b>Total</b>	<b>776297/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	01. Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	01 Nos.	5044/60	Each	5045/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary coat of red lead paint & pair of ½" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	01 Nos.	6237/-	Each	6237/-
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	01 No.	2533/47	Each	2533/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	01 No.	2042/43	Each	2042/-
05.	05. Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	01 Nos.	447/15	Each	477/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	01 No.	877/80	Each	878/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	02Nos.	1384/24	Each	2768/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	02 Nos.	478/28	Each	957/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	03 Nos.	704/20	Each	2113/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	15 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	05 Nos.	270/60	Each	1353/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	40 Rft	8/45	P.Rft	338/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	05 Nos.	264/-	Each	1320/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	01 No.	1142/24	Each	1142/24
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 ½" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	10 Rft	116/20	P.Rft	1162/-
		05 Rft	155/27	P.Rft	776/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	20 Rft	250/60	P.Rft	5012/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-
20.	20. Fiber Glass Tank 250 Gallon	01 No.	21989/61	P.Rft	21990/-
				<b>Total</b>	<b>151484/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot



# SPPRA BIDDING DOCUMENT

Sr No: 09



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Compound Wall Eid Gah at Village Sain Rakhio  
Mirani Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Compound Wall Eid Gah at Village Sain Rakhio  
Mirani Taluka Kandhkot*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*

(d). **Estimated Cost:-**      *2.000 Million*

(e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).

(g). **Security Deposit:-(including bid security):-**      *10%*

(in % age of bid amount /estimated cost equal to 10%)

(h). **Percentage, if any, to be deducted from bills :-**      *5%*

(i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*

(j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*

(k). **Time for Completion from written order of commence: -**      *12 Months*

(L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).

(m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF COMPOUND WALL EID GAH AT VILLAGE SAIN RAKHIO MIRANI**  
**TALUKA KANDHKOT.**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	322 Cft	3176/25	%0Cft	1023/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	109 Cft	8694/95	%Cft	9477/-
03.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	354 Cft	337/-	P.Cft	119298/-
04.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	21.24 Cwt	5001/70	P.Cwt	106236/-
05.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	418 Cft	11948/36	%Cft	49944/-
11.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	347 Cft	12346/65	%Cft	42843/-
12.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	925 Sft	1213/58	%Sft	11226/-
13.	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster of paris and then painting with weather coat of approved make (new surface) (S.I.No. 38 (a) P-61)	1400 Sft	1948/10	%Sft	27273/-
				Total	367320/-

Therefore  $\frac{397623 \times 471}{100} = 1872804/-$

**PART "A" (II) STEEL GATE I/C PILLARS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges And other structures including dabbling Dressing refilling ground structure with Excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-05)	31 Cft	3176/25	%0Cft	99/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	06 Cft	8694/95	%Cft	522/-
03.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	55 Cft	337/-	P.Cft	18535/-
04.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	2.4 5Cwt	5001/70	P.Cwt	18535/-
05.	P/L HALLA TILE	114 Sft	47651/56	%Sft	54323/-
06.	Making & fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre with locking arrangement (S.I.No. 24 P-97)	60 Sft	594/57	P.Sft	35674/-
07.	Preparing new surface painting of doors Corrugated (S.I.No. 5 (c) P-76	120 Sft	2116/41	%Sft	2540/-
				<b>Total</b>	<b>123947/-</b>

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# **SPPRA BIDDING DOCUMENT**

Sr No: 10



## **STANDARD FORM OF BIDDING DOCUMENT**

**FOR**

**PROCUREMENT OF WORKS**

*(For Contracts (Small) amounting between Rs.2.50 million to Rs.50.00 million)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

**Name of Scheme:-**

*Constrution of Musafir Khana at Village Dargah Bharchondi  
Sharif Taluka Kashmore*

**Name of Contractor:-**

**Dr No: & Date of Issue**

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of Bidding Documents. The following specific data for the works to be tendered shall complete, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

#### **1.1 Name of Procuring Agency**

Executive Engineer Buildings Division Kashmore @ Kandhkot  
(Insert name of the Procuring Agency)

#### **Brief Description of Works**

Construction of Musafir Khana at Village Dargah Bharchondi  
Sharif Taluka Kashmore

5.1 Estimated Cost

**3.00 Million**

5.1 (a) Procuring Agency's address:

Executive Engineer Buildings Division Kashmore @ Kandhkot  
(Insert address of the Procuring Agency with telex/fax)

(b) Engineer's address:

Executive Engineer Buildings Division Near D.C Office Kashmore @ Kandhkot  
(Insert name and address of the Engineer, if any, with telex/fax.)

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows: (Insert required capabilities and documents)

- i. Financial capacity: (must have turnover of Rs-----Million);
- ii. Technical capacity: (mention the appropriate category of registration with PEC and qualification and experience of the staff);
- iii. Construction Capacity: (mention the names and number of equipments required for the work).



12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

(b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

**13.1 Amount of Bid Security**

5%

( Fill in lump sum amount or in % age of bid amount /estimated cost, but not below 1% and not exceeding 5%)

**14.1 Period of Bid Validity**

90 Days

(Fill in "number of days" not exceeding 90)

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (0) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

Executive Engineer Buildings Division Kashmore @ Kandhkot

(insert postal address or location of bid box for delivery by hand)

**15.1 Deadline for Submission of Bids**

Time: 12.00 Noon on 15/03/2018

**16.1 Venue, Time, and Date of Bid Opening**

Venue: Kandhkot

Time: 1.00 P.M Date: 15/03/2018

**16.4 Responsiveness of Bids**

(i) Bid is valid till required period,

- \*(ii) Bid prices are firm during currency of contract/Price adjustment;
- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

\*Procuring agency can adopt either of two options . ( *Select either of them*)

- (a) **Fixed Price contract:** In these contracts no escalation will be provided during currency of the contract and normally period of completion of these works is upto 12 months.
- (b) **Price adjustment contract:** In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh, after bid opening during currency of the contract.

**SCHEDULE-(B)**  
**CONSTRUCTION OF MUSAFIR KHANA AT VILLAGE DARGAH BHARCHONDI SHARIF**  
**TALUKA KASHMORE.**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1628 Cft	3176/25	%0Cft	5171/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	488 Cft	8694/95	%Cft	42431/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1439 Cft	11948/36	%Cft	171937/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	1108 Cft	337/-	P.Cft	373396/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	59.35 Cwt	5001/70	P.Cwt	296851/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1945 Cft	12674/36	%Cft	246516/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1293 Cft	1512/50	%0Cft	12185/-
08.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	517 Cft	1141/25	%Cft	8896/-
09.	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screening and washing of stone aggregate without shuttering 1:2:4 (S.I.No. 05 (i) P-18)	176 Cft	14429/25	%Cft	25395/-
10.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	5100 Sft	2206/60	%Sft	112537/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	5100 Sft	2197/52	%Sft	112074/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	1296 Sft	2197/52	%Sft	28480/-
13.	First Class Deodar Wood	230 Sft	1273/76	P.Sft	292965/-
14.	P/L White Marble 3/4" thick	1034 Sft	567/48	P.Sft	586774/-
15.	Dedo Marble	346 Sft	186/04	P.Sft	64370/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	S/F Matt Finish	5100 Sft	2717/-	%Sft	138567/-
17.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	460 Sft	2116/41	%Sft	9735/-
18.	White Washing 03 Coats	682 Sft	829/95	%Sft	5660/-
19.	Weather coat 03 coats	1152 Sft	1948/10	%Sft	22441/-
				Total	2547732/-

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	01. Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	01 Nos.	5044/60	Each	5045/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary cost of red lead paint & pair of ½" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	01 Nos.	6237/-	Each	6237/-
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	01 No.	2533/47	Each	2533/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	01 No.	2042/43	Each	2042/-
05.	05. Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	01 Nos.	447/15	Each	477/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	01 No.	877/80	Each	878/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	02Nos.	1384/24	Each	2768/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	02 Nos.	478/28	Each	957/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	03 Nos.	704/20	Each	2113/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	15 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	05 Nos.	270/60	Each	1353/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	40 Rft	8/45	P.Rft	338/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	05 Nos.	264/-	Each	1320/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	01 No.	1142/24	Each	1142/24
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 ½" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	10 Rft	116/20	P.Rft	1162/-
		05 Rft	155/27	P.Rft	776/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	20 Rft	250/60	P.Rft	5012/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-
20.	20. Fiber Glass Tank 250 Gallon	01 No.	21989/61	P.Rft	21990/-
				<b>Total</b>	<b>3338229/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**



# **SPPRA BIDDING DOCUMENT**

Sr No: 11(a)



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

***Name of Scheme:-***

*Construction of Government Dispensary at Village Rais Noor  
Ahmed Bhayo Taluka Kandhkot ( Civil Work)*

***Name of Contractor:-***

***Dr No: & Date of Issue***

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Rais Noor Ahmed Bhayo Taluka Kandhkot ( Civil Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.850 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE RAIS NOOR AHMED**  
**BHAYO TALUKA KANDHKOT (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2' 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P -)	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary cost of red lead paint & pair of 1/2" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 ½" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-



S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft		P.Rft	
02.	Check Valve 1-1/2" dia	01 No.		Each	
03.	S/F Hand Pump	01 No.		Each	
04.	Electric Motor 1 H.P	01 Nos.		Each	_____
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

	Amount to be added /deducted on the	
<b>Total (A)</b>		<b>Rs:</b>
<b>Diff: cost of Bitumen (B)</b>		<b>Rs:</b>
<b>G.Total (A+B)</b>		<b>Rs.</b>

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# SPPRA BIDDING DOCUMENT

Sr No: 11(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Construction of Government Dispensary at Village Rais Noor  
Ahmed Bhayo Taluka Kandhkot ( Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Rais Noor  
Ahmed Bhayo Taluka Kandhkot ( Electric Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.150 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE RAIS NOOR AHMED**  
**BHAYO TALUKA KANDHKOT (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm2) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm2) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm2) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

**PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 12(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Abdul Rasheed  
Ogahi Taluka Kandhkot (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency

Executive Engineer Buildings Division Kashmore @ Kandhkot
- (b). Brief Description of Works

Construction of Government Dispensary at Village Abdul Rasheed Ogahi Taluka Kandhkot (Civil Work)
- (c).Procuring Agency's address:-

Executive Engineer Buildings Division Kashmore @ Kandhkot
- (d). Estimated Cost:-

1.850 Million
- (e). Amount of Bid Security:-

5%

(Fill in lump sum amount

or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-

90 Days

(Not more than sixty days).
- (g).Security Deposit:-(including bid security):-

10%

(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-

5%
- (i). Deadline for Submission of Bids along with time :-

15/03/2018 (12.00 Noon)
- (j). Venue, Time, and Date of Bid Opening:-

15/03/2018 (1.00 P.M)
- (k). Time for Completion from written order of commence: -

12 Months
- (L).Liquidity damages:-

0.05 Per Day

0.05 of Estimated Cost or Bid cost

per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:

(in words and figures)



**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE ABDUL RASHEED**  
**OGAHI TALUKA KANDHKOT (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P -)	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary coat of red lead paint & pair of 1/2" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 ½" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and paining 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<b>Total</b>
					21990/-
					221535/-

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	
			<b>Total</b>	_____

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** Rs:

**Diff: cost of Bitumen (B)** Rs:

**G.Total (A+B)** Rs.

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# **SPPRA BIDDING DOCUMENT**

Sr No: 12(b)



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Abdul Rasheed  
Ogahi Taluka Kandhkot (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Abdul Rasheed  
Ogahi Taluka Kandhkot (Electric Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.150 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)



**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE ABDUL RASHEED**  
**OGAHI TALUKA KANDHKOT (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

**PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	_____

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** \_\_\_\_\_ **Rs:**

**Diff: cost of Bitumen (B)** \_\_\_\_\_ **Rs:**

**G.Total (A+B)** \_\_\_\_\_ **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 13(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Riaz Bahlkani  
Taluk Tangwani (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Riaz Bahlkani Taluk Tangwani (Civil Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.850 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE RIAZ BAHLKANI**  
**TALUKA TANGWANI (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

***Part "A" Main Building***

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P -)	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary cost of red lead paint & pair of 1/2" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-



S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/1 of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	_____
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

	Amount to be added /deducted on the	
<b>Total (A)</b>		<b>Rs:</b>
<b>Diff: cost of Bitumen (B)</b>		<b>Rs:</b>
<b>G.Total (A+B)</b>		<b>Rs.</b>

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 13(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Riaz Bahlkani  
Taluk Tangwani (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Riaz Bahlkani Taluk Tangwani (Electric Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.150 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE RIAZ BAHLKANI**  
**TALUKA TANGWANI (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm2) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm2) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm2) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

## **PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 14(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Construction of Government Dispensary at Village Wadero Saif Din  
Khan Jakhrani U/C Mahar Taluka Kashmore (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**



**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Wadero Saif Din Khan Jakhrani U/C Mahar Taluka Kashmore (Civil Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *1.850 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE WADER SAIF DIN KHAN**  
**JAKHRANI U/C MAHAR TALUKA KASHMORE (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P - )	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary cost of red lead paint & pair of 1/2" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft		P.Rft	
02.	Check Valve 1-1/2" dia	01 No.		Each	
03.	S/F Hand Pump	01 No.		Each	
04.	Electric Motor 1 H.P	01 Nos.		Each	_____
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* Rs:

*Diff: cost of Bitumen (B)* Rs:

*G.Total (A+B)* Rs.

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 14(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Construction of Government Dispensary at Village Wadero Saif Din  
Khan Jakhrani U/C Mahar Taluka Kashmore (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**



## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Wadero Saif Din Khan Jakhrani U/C Mahar Taluka Kashmore (Electric Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.150 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE WADER SAIF DIN KHAN**  
**JAKHRANI U/C MAHAR TALUKA KASHMORE (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

## **PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 15(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Kathgarh  
Taluka kashmore (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Kathgarh Taluka kashmore (Civil Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *1.850 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE KATHGARH TALUKA**  
**KASHMORE (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2' 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 ½" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 ½" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P - )	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of ¾" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary cost of red lead paint & pair of ½" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-



S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 ½" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	_____
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** Rs:

**Diff: cost of Bitumen (B)** Rs:

**G.Total (A+B)** Rs.

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 15(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Kathgarh  
Taluka kashmore (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Kathgarh  
Taluka kashmore (Electric Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.150 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE KATHGARH TALUKA**  
**KASHMORE (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

**PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**



# SPPRA BIDDING DOCUMENT

Sr No: 16(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Construction of Government Dispensary at Village Abdullah  
Domki Taluka Kashmore (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Abdullah Domki Taluka Kashmore (Civil Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *1.850 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE ABDULLAH DOMKI**  
**TALUKA KASHMORE (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 ½" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 ½" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P -)	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of ¾" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary coat of red lead paint & pair of ½" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 ½" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft <u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	_____
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot



# SPPRA BIDDING DOCUMENT

Sr No: 16(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Abdullah  
Domki Taluka Kashmore (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Abdullah Domki Taluka Kashmore (Electric Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *0.150 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE ABDULLAH DOMKI**  
**TALUKA KASHMORE (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

**PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 17(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Construction of Government Dispensary at Village Malik Larho  
Taluka Kashmore (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Malik Larho Taluka Kashmore (Civil Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.850 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE MALIK LARHO TALUKA**  
**KASHMORE (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-



S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P -)	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary coat of red lead paint & pair of 1/2" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	_____
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 17(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Malik Larho  
Taluka Kashmore (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency

Executive Engineer Buildings Division Kashmore @ Kandhkot
- (b). Brief Description of Works

Construction of Government Dispensary at Village Malik Larho Taluka Kashmore (Electric Work)
- (c).Procuring Agency's address:-

Executive Engineer Buildings Division Kashmore @ Kandhkot
- (d). Estimated Cost:-

0.150 Million
- (e). Amount of Bid Security:-

5%

(Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-

90 Days

(Not more than sixty days).
- (g).Security Deposit:-(including bid security):-

10%

(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-

5%
- (i). Deadline for Submission of Bids along with time :-

15/03/2018 (12.00 Noon)
- (j). Venue, Time, and Date of Bid Opening:-

15/03/2018 (1.00 P.M)
- (k). Time for Completion from written order of commence: -

12 Months
- (L).Liquidity damages:-

0.05 Per Day

0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:

(in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE MALIK LARHO TALUKA**  
**KASHMORE (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>



## **PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	_____

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 18(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Arbelo Khan  
Bangwar Taluka Kashmore (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency *Executive Engineer Buildings Division Kashmir @ Kandhkot*
- (b). Brief Description of Works *Construction of Government Dispensary at Village Arbelo Khan Bangwar Taluka Kashmir (Civil Work)*
- (c). Procuring Agency's address:- *Executive Engineer Buildings Division Kashmir @ Kandhkot*
- (d). Estimated Cost:- *1.850 Million*
- (e). Amount of Bid Security:- *5%* (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):- *90 Days* (Not more than sixty days).
- (g). Security Deposit:-(including bid security):- *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :- *5%*
- (i). Deadline for Submission of Bids along with time :- *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:- *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: - *12 Months*
- (L). Liquidity damages:- *0.05 Per Day* *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount: (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE ARBELO KHAN**  
**BANGWAR TALUKA KASHMORE (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P - )	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary cost of red lead paint & pair of 1/2" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 ½" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and paining 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-



S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft <u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	_____
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* Rs:

*Diff: cost of Bitumen (B)* Rs:

*G.Total (A+B)* Rs.

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 18(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Arbelo Khan  
Bangwar Taluka Kashmore (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmir @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Arbelo Khan  
Bangwar Taluka Kashmir (Electric Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmir @ Kandhkot*
- (d). Estimated Cost:-      *0.150 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE ARBELO KHAN**  
**BANGWAR TALUKA KASHMORE (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

**PART "B" NON-SCHEDUEL ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit bakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 19(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Mohammad  
Nawaz Bangwar Taluka Kashmore (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Government Dispensary at Village Mohammad Nawaz Bangwar Taluka Kashmore (Civil Work)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *1.850 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)



**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE MOHAMMAD NAWAZ**  
**BANGWAR TALUKA KASHMORE (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage, tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage, tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P -)	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary coat of red lead paint & pair of 1/2" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	_____
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 19(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

***Name of Scheme:-***

*Construction of Government Dispensary at Village Mohammad  
Nawaz Bangwar Taluka Kashmore (Electric Work)*

***Name of Contractor:-***

***Dr No: & Date of Issue***

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Mohammad Nawaz Bangwar Taluka Kashmore (Electric Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *0.150 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)



**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE MOHAMMAD NAWAZ**  
**BANGWAR TALUKA KASHMORE (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

**PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 20(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Haji Sawan  
Jakhrani Taluka Kashmore (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Haji Sawan Jakhrahi Taluka Kashmore (Civil Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.850 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE HAJI SAWAN**  
**JAKHRANI TALUKA KASHMORE (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 1/2" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P -)	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of 3/4" x 1/4" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary cost of red lead paint & pair of 1/2" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-



S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/1 of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-



S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft		P.Rft	
02.	Check Valve 1-1/2" dia	01 No.		Each	
03.	S/F Hand Pump	01 No.		Each	
04.	Electric Motor 1 H.P	01 Nos.		Each	_____
				<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# SPPRA BIDDING DOCUMENT

Sr No: 20(b)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Haji Sawan  
Jakhrani Taluka Kashmore (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Haji Sawan Jakhrahi Taluka Kashmore (Electric Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *0.150 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE HAJI SAWAN**  
**JAKHRANI TALUKA KASHMORE (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

**PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	_____

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 21(a)



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Mushtaque Ali  
Bangwar U/C Kumb Taluka Kashmore (Civil Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Mushtaque Ali  
Bangwar U/C Kumb Taluka Kashmore (Civil Work)*
- (c).Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.850 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g).Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L).Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE MUSHTAQUE ALI**  
**BANGWAR U/C KUMB TALUKA KASHMORE (A) "CIVIL WORK" (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

**Part "A" Main Building**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	1213 Cft	3176/05	%0Cft	3853/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	364 Cft	8694/95	%Cft	31650/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	1074 Cft	11948/36	%Cft	128325/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	792 Cft	337/-	P.Cft	266904/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	35.350 Cwt	5001/70	P.Cwt	176810/-
06.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	1354 Cft	12674/36	%Cft	171611/-
07.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	1213 Cft	1512/50	%0Cft	1224/-
08.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 22 P-05)	699 Cft	3630/-	%0Cft	2537/-
09.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	350 Cft	1141/25	%Cft	3994/-
10.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	231 Cft	8122/95	%Cft	18764/-
11.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	3684 Sft	2206/60	%Sft	81291/-
12.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	3684 Sft	2197/25	%Sft	80957/-
13.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	1044 Sft	1287/44	%Sft	13441/-



S. No.	Item of work	Qty:	Rate	Unit	Amount
14.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 ½" x 3" for Doors using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	84 Sft	228/90	P.Sft	19228/-
15.	Providing and fixing G.I frames / Chowkats of Size 7" x 2" or 4 ½" x 3" for Windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ration 1:6 and repairing of the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.I.No. 29 P-99)	80 Sft	240/50	P.Sft	19240/-
16.	First Class Commercial Ply Wood (S.I.No. P -)	112 Sft	903/-	P.Sft	101136/-
17.	S/F Colour Tiles Flooring (S.I.No. P- )	1097 Sft	27747/06	%Sft	304385/-
18.	Supplying & fixing in position iron / steel grill of ¾" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	35 Sft	180/50	P.Sft	6318/-
19.	Distempering 03 Coats (S.I.No. P- )	3684 Sft	1079/65	%Sft	39774/-
20.	White Washing 03 Coats (S.I.No.24 (c) P-60 )	699 Sft	829/95	%Sft	5801/-
21.	Coloring Washing 02 Coats (S.I.No. P- )	1044 Sft	159/90	%Sft	1669/-
22.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	112 Sft	2116/41	%Sft	2370/-
				<b>Total</b>	<b>1481282/-</b>

**"PART "B" INTERNAL WATER SUPPLY AND EXTERNAL DRAINAGE"**

**Part "A" Schedule Items**

01.	Providing & fixing squatting type while of flushing eastern with internal fitting & flush pipe with bend and making requisite numbers of holders in wall plinth & floor for pipe connections & making good in cement concrete 1:2:4 w.c pan of less than 23" clear opening between flashing rims and 03 gallon flushing tank with 4" dia C.I trap (S.I.No. 01 (a) P-01)	02 Nos.	5044/60	Each	10089/-
02.	P/F 22" x 16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.C or C.I cantilever brackets 6 inches built into wall painted white in two coats after a primary cost of red lead paint & pair of ½" dia chrome bars waste of approved pattern 1-1/4" dia malleable iron or cp brass traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for pie connection and making good in c.c. 1:2:4 (foreign equivalent) (S.I.No. 13 P-04).	02 Nos.	6237/-	Each	12474/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
03.	Add: Extra work for providing and fixing earthen ware pedestal white or colored glazed (standard pattern) (S.I.No. 11 P-03)	02 Nos.	2533/47	Each	5067/-
04.	Providing & fixing 6" x 2" or 6" x 3" C.I trap of the approved self scheme cleaning design with a C.I screwed down grating with or without a vent arm complete with and i/c making requisite number of holes in walls plinth and floor for pipe connections & making good in C.C 1:2:4 (S.I.No. 20 P-06)	04 Nos.	2042/43	Each	8170/-
05.	Providing & fixing in position nyloon Connections complete with ½" dia bars nuts and lining joints to nyloon connection (S.I.No. 23 P-06)	02 Nos.	447/15	Each	894/-
06.	S&F swan type pillar cock of superior quality with c.p head ½" dia (S.I.No. 16 (b) P-19)	02 Nos.	877/80	Each	1756/-
07.	P&F long bib cock superior crystal head with c.p head ½" dia (S.I.No. 13 (b) P-19)	06 Nos.	1384/24	Each	8305/-
08.	S&F C.P concealed stop cock of superior quality with crystal head ½" dia (S.I.No. 11 (b) P-18)	06 Nos.	478/28	Each	2870/-
09.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree including extra painting to match the color of the building plain tee (S.I.No. 07 P-09)	06 Nos.	704/20	Each	4225/-
10.	P&F 4" dia C.I soil and vent pipes i/c cutting and fitting and extra painting match the colour of building (S.I.No. 02 P-09)	30 Rft	333/29	P.Rft	9999/-
11.	Providing and fixing 4" x 4" x 4" dia C.I branchen of the required degree with access doors, rubber washer 1/8" thick and bolts and nuts and extra painting to match colour of the building (S.I.No.07 P-09)	10 Nos.	270/60	Each	2706/-
12.	Providing G.I pipes specials & clamps etc including fixing cutting and fitting complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling (S.I.No. 01 (ii) P-12). (a) ¾" dia	100 Rft	95/79	P.Rft	9579/-
13.	Add: Extra labour for concealed G.I pipe and fittings i/c making recess in the wall for pipe and making good in cement mortar etc complete (S.I.No. 02 (ii) P-12)	100 Rft	8/45	P.Rft	845/-
14.	P&F M.S clamps of the approved design to 4" dia C.I pipe sockets i/c the cost of cutting and making good to wall or M.S bolts & nuts 4" dia into wall i/c pipe distance pieces extra painting to match the colour of the building (S.I.No. 14 P-00)	15 Nos.	264/-	Each	3960/-
15.	S&F jet shower with rod of superior quality With c.p head ½" (S.I.No. 15 P-19)	02 Nos.	1142/24	Each	2284/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
16.	Constructing manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement motor 1:3 cement plastered 1:3 ½" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2" x 1-1/2" (457x457mm) of 1.75 Cwt (88.9 Kg) embedded in plain C.C. 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) side projecting 4" (102 mm) from the face of all at 12" (305 mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health (Southern Zone) (S.I.No. 07 P-04).	05 Nos.	14748/-	Each	73740/-
17.	Providing G.I Pipes and Specials etc. including cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposal of surplus earth within one chain and painting 2 coats of bitumen pain to pipes & specials after cleaning & hassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handling (S.I.No. 01 (iv) P-14)	50 Rft	116/20	P.Rft	810/-
		25 Rft	155/27	P.Rft	3882/-
18.	Providing R.C.C pipe with callars class "B" and digginhg the tenches to required depth and fixing in position including cutting fitting and jointing with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe and refilling with excavated staff (S.I.No. 02 (e) P-21) 9" dia	150 Rft	250/60	P.Rft	37590/-
19.	Boring for tube well in all water Bearing soils from ground level upto 100 ft. or 30.5 meter depth i/c skinning and with drawing of casing pipe (S.I.No. 1 (a) P-41)	80 Rft	160/-	P.Rft	12800/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
20.	Fiber Glass Tank	250 Gallon	01 No.	21989/61	P.Rft
					<u>21990/-</u>
				<b>Total</b>	<b>221535/-</b>

**Part "B" Non-Schedule Items**

01.	Stainer Filter	10 Rft	P.Rft	
02.	Check Valve 1-1/2" dia	01 No.	Each	
03.	S/F Hand Pump	01 No.	Each	
04.	Electric Motor 1 H.P	01 Nos.	Each	_____
			<b>Total</b>	

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** Rs:

**Diff: cost of Bitumen (B)** Rs:

**G.Total (A+B)** Rs.

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# **SPPRA BIDDING DOCUMENT**

Sr No: 21(b)



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Government Dispensary at Village Mushtaque Ali  
Bangwar U/C Kumb Taluka Kashmore (Electric Work)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmir @ Kandhkot*
- (b). Brief Description of Works      *Construction of Government Dispensary at Village Mushtaque Ali Bangwar U/C Kumb Taluka Kashmir (Electric Work)*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmir @ Kandhkot*
- (d). Estimated Cost:-      *0.150 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE MUSHTAQUE ALI**  
**BANGWAR U/C KUMB TALUKA KASHMORE (B) "ELECTRIC WORK" (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

**PART "A" SCHEDULE ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	35 Points	910/-	P.P	31850/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	01 Points	1590/-	P.P	1590/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm <sup>2</sup> ) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	100 Meter	200/-	P.Meter	20000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm <sup>2</sup> ) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	52 Meter	428/-	P.Meter	22256/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	35 Nos.	67/-	Each	2345/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	21 Nos.	203/-	Each	4263/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>126627/-</b>

**PART "B" NON-SCHEDULED ITEMS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	06 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	20 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watt Bulb (S.I.No. P- )	07 Nos.		Each	
				<b>Total</b>	_____

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot**



# **SPPRA BIDDING DOCUMENT**

Sr No: 22



**STANDARD FORM OF BIDDING DOCUMENT**

**FOR**

**PROCUREMENT OF WORKS**

*(For Contracts (Small) amounting between Rs.2.50 million to Rs.50.00 million)*

**BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Construction of Jamia Masjid Murad Wah Kashmore  
"Remaining Work"*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuing Bidding Documents. The following specific data for the works to be tendered shall complete, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

#### **1.1 Name of Procuring Agency**

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert name of the Procuring Agency)*

#### **Brief Description of Works**

**Construction of Jamia Masjid Murad Wah Kashmore**

**"Remaining Work"**

5.1 Estimated Cost

**14.00 Million**

5.1 (a) Procuring Agency's address:

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert address of the Procuring Agency with telex/fax)*

(b) Engineer's address:

**Executive Engineer Buildings Division Near D.C Office Kashmore @ Kandhkot**

*( Insert name and address of the Engineer, if any, with telex/fax.)*

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows: *(Insert required capabilities and documents)*

- i. Financial capacity: *( must have turnover of Rs-----Million);*
- ii. Technical capacity :*(mention the appropriate category of registration with PEC and qualification and experience of the staff);*
- iii. Construction Capacity: *( mention the names and number of equipments required for the work).*

12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

(b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

**13.1 Amount of Bid Security**

5%

( Fill in lump sum amount or in % age of bid amount /estimated cost, but not below 1% and not exceeding 5%)

**14.1 Period of Bid Validity**

90 Days

(Fill in "number of days" not exceeding 90)

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (0) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

Executive Engineer Buildings Division Kashmore @ Kandhkot

(insert postal address or location of bid box for delivery by hand)

**15.1 Deadline for Submission of Bids**

Time: 12.00 Noon on 15/03/2018

**16.1 Venue, Time, and Date of Bid Opening**

Venue: Kandhkot

Time: 1.00 P.M Date: 15/03/2018

**16.4 Responsiveness of Bids**

(i) Bid is valid till required period,

- \*(ii) Bid prices are firm during currency of contract/Price adjustment;
- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

\*Procuring agency can adopt either of two options . ( *Select either of them*)

- (a) **Fixed Price contract:** In these contracts no escalation will be provided during currency of the contract and normally period of completion of these works is upto 12 months.
- (b) **Price adjustment contract:** In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh, after bid opening during currency of the contract.

**SCHEDULE-(B)**  
**CONSTRUCTION OF JAMIA MASJID MURAD WAH KASHMORE "REMAINING WORK".**  
**(CDP 2017-2018).**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges And other structures including dabbling Dressing refilling ground structure with Excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-05)	6300 Cft	3176/25	%0Cft	20010/-
02.	Stone Pitching hand packed	900 Sft	7708/47	%Sft	69376/-
03.	C.C 1:4:8	450 Cft	9416/28	%Cft	42373/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	7292 Cft	337/-	P.Cft	2457404/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	325.53 Cwt	5001/70	P.Cwt	1628232/-
06.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	10304 Cft	9424/10	%0Cft	
07.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	2576 Cft	1720/66	%Cft	
08.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	5141 Cft	12674/36	%Cft	651589/-
09.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	2576 Cft	8694/95	%Cft	223982/-
10.	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screening and washing of stone aggregate without shuttering 1:2:4 (S.I.No. 05 (i) P-18)	876 Cft	14429/25	%Cft	126400/-
01.	P/L White Marble ¾" thick	9843 Sft	567/48	P.Sft	5585706/-
07.	Marble Dedo	9466 Sft	186/04	P.Sft	1761055/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
08.	Providing & laying tiles glazed 6"x6"x 1/4" on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles to proper profile (S.I.No. 60 P-53)	2220 Sft	30509/77	%Sft Total	<u>677317/-</u> 13295512/-

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* *Rs:*

*Diff: cost of Bitumen (B)* *Rs:*

*G.Total (A+B)* *Rs.*

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# **SPPRA BIDDING DOCUMENT**

Sr No: 23



## ***STANDARD FORM OF BIDDING DOCUMENT***

***FOR***

### ***PROCUREMENT OF WORKS***

***(For Contracts (Small) amounting between Rs.2.50 million to Rs.50.00 million)***

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

***Name of Scheme:-***

***Construction of Eid Gah Dari Taluka Kandhkot***

***Name of Contractor:-***

***Dr No: & Date of Issue***

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuing Bidding Documents. The following specific data for the works to be tendered shall complete, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

#### **1.1 Name of Procuring Agency**

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert name of the Procuring Agency)*

#### **Brief Description of Works**

**Construction of Eid Gah Dari Taluka Kandhkot**

5.1 Estimated Cost

**5.00 Million**

5.1 (a) Procuring Agency's address:

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert address of the Procuring Agency with telex/fax)*

(b) Engineer's address:

**Executive Engineer Buildings Division Near D.C Office Kashmore @ Kandhkot**

*( Insert name and address of the Engineer, if any, with telex/fax.)*

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows: *(Insert required capabilities and documents)*

i. Financial capacity: *( must have turnover of Rs-----Million);*

ii. Technical capacity :*(mention the appropriate category of registration with PEC and qualification and experience of the staff);*

iii. Construction Capacity: *( mention the names and number of equipments required for the work).*



12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

(b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

**13.1 Amount of Bid Security**

5%

( Fill in lump sum amount or in % age of bid amount /estimated cost, but not below 1% and not exceeding 5%)

**14.1 Period of Bid Validity**

90 Days

(Fill in "number of days" not exceeding 90)

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (0) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

Executive Engineer Buildings Division Kashmore @ Kandhkot

(insert postal address or location of bid box for delivery by hand)

**15.1 Deadline for Submission of Bids**

Time: 12.00 Noon on 15/03/2018

**16.1 Venue, Time, and Date of Bid Opening**

Venue: Kandhkot

Time: 1.00 P.M Date: 15/03/2018

**16.4 Responsiveness of Bids**

(i) Bid is valid till required period,

- \*(ii) Bid prices are firm during currency of contract/Price adjustment;
- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

\*Procuring agency can adopt either of two options . ( *Select either of them*)

- (a) **Fixed Price contract:** In these contracts no escalation will be provided during currency of the contract and normally period of completion of these works is upto 12 months.
- (b) **Price adjustment contract:** In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh, after bid opening during currency of the contract.

**SCHEDULE-(B)**  
**CONSTRUCTION OF EID GAH DARI TALUKA KANDHKOT (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

<i>S. No.</i>	<i>Item of work</i>	<i>Qty:</i>	<i>Rate</i>	<i>Unit</i>	<i>Amount</i>
<b><u>PART "A" (I)</u></b>					
01.	Excavation in foundation of building bridges And other structures including dabbling Dressing refilling ground structure with Excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-05)	156 Cft	3176/25	%0Cft	495/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	31 Cft	8694/95	%Cft	2695/-
01.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	283 Cft	11948/36	%Cft	33814/-
02.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	110 Cft	337/-	P.Cft	37070/-
03.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	5.50 Cwt	5001/70	P.Cwt	27509/-
04.	Pacca brick work other than building including sticking of joints upto 20 feet height in 1:6 (S.I.No. 07 (e) P-26).	375 Cft	12365/48	%Cft	46371/-
05.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	1100 Sft	2206/60	%Sft	24273/-
06.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	1100 Sft	2197/52	%Sft	24173/-
07.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	500 Sft	1287/44	%Sft	6437/-
08.	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screening and washing of stone aggregate without shuttering 1:2:4 (S.I.No. 05 (i) P-18)	19 Cft	14429/25	%Cft	2742/-
09.	Primary Coat of Chalk under Distemper (S.I.No. P- )	1600 Sft	442/75	%Sft	7084/-
10.	Distempering 03 Coats (S.I.No P- )	1600 Sft	1079/65	%Sft Total	17274/- 226747/-
<b>Therefore 226747 x 503 =</b>					<b>1140537/-</b>
100					

**PART "A" (II) STEEL GATE I/C PILLARS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges And other structures including dabbling Dressing refilling ground structure with Excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-05)	31 Cft	3176/25	%0Cft	99/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	06 Cft	8694/95	%Cft	522/-
03.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	55 Cft	337/-	P.Cft	18535/-
04.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	2.4 5Cwt	5001/70	P.Cwt	18535/-
05.	P/L HALLA TILE	114 Sft	47651/56	%Sft	54323/-
06.	Making & fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre with locking arrangement (S.I.No. 24 P-97)	60 Sft	594/57	P.Sft	35674/-
07.	Preparing new surface painting of doors Corrugated (S.I.No. 5 (c) P-76	120 Sft	2116/41	%Sft	2540/-
				<b>Total</b>	<b>123947/-</b>

**PART "B"**

01.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	32500 Cft	3630/-	%0Cft	117975/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	3250 Cft	8694/95	%Cft	282586/-
03.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	6500 Cft	1141/25	%Cft	74181/-
04.	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	13000 Sft	199/77	P.Sft	2856711/-



# **SPPRA BIDDING DOCUMENT**

Sr No: 24



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

***BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Eid Gah in Village Haibat Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Eid Gah in Village Haibat Taluka Kandhkot*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *2.000 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF EID GAH IN VILLAGE HAIBAT TALUKA KANDHKOT**  
**(CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
<b><u>PART "A" (I)</u></b>					
01.	Excavation in foundation of building bridges And other structures including dabbling Dressing refilling ground structure with Excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-05)	156 Cft	3176/25	%0Cft	495/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	31 Cft	8694/95	%Cft	2695/-
01.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	283 Cft	11948/36	%Cft	33814/-
02.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	110 Cft	337/-	P.Cft	37070/-
03.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	5.50 Cwt	5001/70	P.Cwt	27509/-
04.	Pacca brick work other than building including sticking of joints upto 20 feet height in 1:6 (S.I.No. 07 (e) P-26).	375 Cft	12365/48	%Cft	46371/-
05.	Cement Plaster 1:6 upto 2" height ½" thick (S.I.No. 13 (b) P-58)	1100 Sft	2206/60	%Sft	24273/-
06.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	1100 Sft	2197/52	%Sft	24173/-
07.	Cement pointing struck joints on Wall 1:2 (S.I.No. 19 P-59)	500 Sft	1287/44	%Sft	6437/-
08.	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screening and washing of stone aggregate without shuttering 1:2:4 (S.I.No. 05 (i) P-18)	19 Cft	14429/25	%Cft	2742/-
09.	Primary Coat of Chalk under Distemper (S.I.No. P- )	1600 Sft	442/75	%Sft	7084/-
10.	Distemping 03 Coats (S.I.No P- )	1600 Sft	1079/65	%Sft	17274/-
				Total	226747/-
<b>Therefore 226747 x 502 =</b>					<b>1140537/-</b>
<b>100</b>					



**PART "A" (II) STEEL GATE I/C PILLARS**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges And other structures including dabbling Dressing refilling ground structure with Excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-05)	31 Cft	3176/25	%0Cft	99/-
02.	Cement concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	06 Cft	8694/95	%Cft	522/-
03.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	55 Cft	337/-	P.Cft	18535/-
04.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	2.4 5Cwt	5001/70	P.Cwt	18535/-
05.	P/L HALLA TILE	114 Sft	47651/56	%Sft	54323/-
06.	Making & fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre with locking arrangement (S.I.No. 24 P-97)	60 Sft	594/57	P.Sft	35674/-
07.	Preparing new surface painting of doors Corrugated (S.I.No. 5 (c) P-76	120 Sft	2116/41	%Sft	2540/-
				<b>Total</b>	<b>123947/-</b>

**PART "B"**

01.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	25000 Cft	3630/-	%0Cft	90750/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	625 Cft	8694/95	%Cft	54343/-
03.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	1250 Cft	1141/25	%Cft	14266/-
04.	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	2500 Sft	199/77	P.Sft	499425/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
05.	Extra Lead for 3.0 Miles	26250 Cft	579/41	%Cft	<u>152095/-</u>
				<b>Total</b>	<b>818879/-</b>

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* *Rs:*

*Diff: cost of Bitumen (B)* *Rs:*

*G.Total (A+B)* *Rs.*

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# **SPPRA BIDDING DOCUMENT**

Sr No: 25



**STANDARD FORM OF BIDDING DOCUMENT**

**FOR**

**PROCUREMENT OF WORKS**

**(For Contracts (Small) amounting between Rs.2.50 million to Rs.50.00 million)**

**BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

**Name of Scheme:-**

**Construction of Tough Tile / Paver Road and Drainage  
in 16 Wards M.C Kandhkot**

**Name of Contractor:-**

**Dr No: & Date of Issue**

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuing Bidding Documents. The following specific data for the works to be tendered shall complete, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

#### **1.1 Name of Procuring Agency**

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert name of the Procuring Agency)*

#### **Brief Description of Works**

**Construction of Tough Tile / Paver Road and Drainage  
in 16 Wards M.C Kandhkot**

5.1 Estimated Cost

**16.00 Million**

5.1 (a) Procuring Agency's address:

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert address of the Procuring Agency with telex/fax)*

(b) Engineer's address:

**Executive Engineer Buildings Division Near D.C Office Kashmore @ Kandhkot**

*( Insert name and address of the Engineer, if any, with telex/fax.)*

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows: *(Insert required capabilities and documents)*

- i. Financial capacity: *( must have turnover of Rs-----Million);*
- ii. Technical capacity :*(mention the appropriate category of registration with PEC and qualification and experience of the staff);*
- iii. Construction Capacity: *( mention the names and number of equipments required for the work).*

12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

(b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

**13.1 Amount of Bid Security**

5%

( Fill in lump sum amount or in % age of bid amount /estimated cost, but not below 1% and not exceeding 5%)

**14.1 Period of Bid Validity**

90 Days

(Fill in "number of days" not exceeding 90)

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (0) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

Executive Engineer Buildings Division Kashmore @ Kandhkot

(insert postal address or location of bid box for delivery by hand)

**15.1 Deadline for Submission of Bids**

Time: 12.00 Noon on 15/03/2018

**16.1 Venue, Time, and Date of Bid Opening**

Venue: Kandhkot

Time: 1.00 P.M Date: 15/03/2018

**16.4 Responsiveness of Bids**

(i) Bid is valid till required period,

- \*(ii) Bid prices are firm during currency of contract/Price adjustment;
- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

\*Procuring agency can adopt either of two options . ( *Select either of them*)

- (a) **Fixed Price contract:** In these contracts no escalation will be provided during currency of the contract and normally period of completion of these works is upto 12 months.
- (b) **Price adjustment contract:** In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh, after bid opening during currency of the contract.

**SCHEDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD AND DRAINAGE IN 16 WARD M.C**  
**KANDHKOT (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S. No.	Item of work	Qty:	Rate	Unit	Amount
<b><u>PART "A" TOUGH TILE / PAVER ROAD</u></b>					
01.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 3.0 miles (S.I.No. 22 P-05)	1000 Cft	3630/-	%Cft	3630/-
02.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	250 Cft	1141/25	%Cft	2853/-
03.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	500 Cft	8694/95	%Cft	43475/-
04.	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern pigment and design etc. complete (S.I.No.54 P-56)	1000 Sft	223/97	P.Sft	223970/-
05.	Extra Lead for 3.0 Miles	1250 Cft	579/41	%Cft	7243/-
				<b>Total</b>	<b>281171/-</b>

**PART "B" OPEN DRAIN**

01.	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screening and washing of stone aggregate without shuttering 1:2:4 (S.I.No. 05 (i) P-18)	63 Cft	14429/25	%Cft	9090/-
02.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	150 Cft	11948/36	%Cft	17923/-
03.	Const. of Standard Open Drain concrete Block of C.C 1:2:4 with situ to the design Profile (S.I.No. D-1 P-58 P.H.E)	100 Rft	94/-	P.Rft	9400/-
04.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	1000 Sft	3015/76	%Sft	30157/-
05.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	15 Cft	337/-	P.Cft	5055/-

<i>S. No.</i>	<i>Item of work</i>	<i>Qty:</i>	<i>Rate</i>	<i>Unit</i>	<i>Amount</i>
06.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	0.669 Cwt	5001/70	P.Cwt	<u>3346/-</u>
				<b>Total</b>	<b>74971/-</b>

### **ABSTRACT**

Part "A" Tough Tile / Paver Road Rs.281171/-

Part "B" Open Drain

Rs.74971/-

Total Rs.356142/-

Therefore  $\frac{356142 \times 4446}{100} =$  Rs.15834073/-

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

Total (A) Rs:

Diff: cost of Bitumen (B) Rs:

G.Total (A+B) Rs.

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot



# **SPPRA BIDDING DOCUMENT**

Sr No: 26



## **STANDARD FORM OF BIDDING DOCUMENT**

**FOR**

### **PROCUREMENT OF WORKS**

*(For Contracts (Small) amounting between Rs.2.50 million to Rs.50.00 million)*

#### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

**Name of Scheme:-**

**Construction of Tough Tile / Paver Road from Village Qaloo  
Khan Bhayo Taluka Kandhkot**

**Name of Contractor:-**

**Dr No: & Date of Issue**

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuing Bidding Documents. The following specific data for the works to be tendered shall complete, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

#### **1.1 Name of Procuring Agency**

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert name of the Procuring Agency)*

#### **Brief Description of Works**

**Construction of Tough Tile / Paver Road from Village Qaloo**

**Khan Bhayo Taluka Kandhkot**

5.1 Estimated Cost

**4.00 Million**

5.1 (a) Procuring Agency's address:

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert address of the Procuring Agency with telex/fax)*

(b) Engineer's address:

**Executive Engineer Buildings Division Near D.C Office Kashmore @ Kandhkot**

*( Insert name and address of the Engineer, if any, with telex/fax.)*

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows: *(Insert required capabilities and documents)*

i. Financial capacity: *( must have turnover of Rs-----Million);*

ii. Technical capacity :*(mention the appropriate category of registration with PEC and qualification and experience of the staff);*

iii. Construction Capacity: *( mention the names and number of equipments required for the work).*

12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

(b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

**13.1 Amount of Bid Security**

5%

( Fill in lump sum amount or in % age of bid amount /estimated cost, but not below 1% and not exceeding 5%)

**14.1 Period of Bid Validity**

90 Days

(Fill in "number of days" not exceeding 90)

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (0) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

Executive Engineer Buildings Division Kashmore @ Kandhkot

(insert postal address or location of bid box for delivery by hand)

**15.1 Deadline for Submission of Bids**

Time: 12.00 Noon on 15/03/2018

**16.1 Venue, Time, and Date of Bid Opening**

Venue: Kandhkot

Time: 1.00 P.M Date: 15/03/2018

**16.4 Responsiveness of Bids**

(i) Bid is valid till required period,

- \* (ii) Bid prices are firm during currency of contract/Price adjustment;
- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

\*Procuring agency can adopt either of two options . ( *Select either of them*)

- (a) **Fixed Price contract:** In these contracts no escalation will be provided during currency of the contract and normally period of completion of these works is upto 12 months.
- (b) **Price adjustment contract:** In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh, after bid opening during currency of the contract.

**SCHEDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE QALOO KHAN BHAYO**  
**TALUKA KANDHKOT (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

<i>S. No.</i>	<i>Item of work</i>	<i>Qty:</i>	<i>Rate</i>	<i>Unit</i>	<i>Amount</i>
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04)	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	638 Cft	8694/95	%Cft	55474/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	451 Cft	11948/36	%Cft	53887/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 3.0 miles (S.I.No. 22 P-05)	1200 Cft	9424/10	%0Cft	4356/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/66	%Cft	4198/-
06.	Extra Lead for 3.0 Miles	1444 Cft	579/41	%Cft	8367/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	500 Sft	3015/76	%Sft	15079/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern pigment and design etc. complete (S.I.No.54 P-56)	97 5Sft	223/97	P.Sft	218371/-
09.	Borrowpit excavation undressed lead upto 100 Cft Ordinary Soil (S.I.No. 03 (a) P-17)	520 Cft	1150/-	%0Cft	575/-
10.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	15 Cft	337/-	P.Cft	5055/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
11.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	0.669 Cwt	5001/70	P.Cwt Total	<u>3346/-</u> 368248/-

Therefore  $\frac{368248 \times 1075}{100} = 3958666/-$

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

Total (A) Rs:

Diff: cost of Bitumen (B) Rs:

G.Total (A+B) Rs.

Total Amount in words (A+B) \_\_\_\_\_

Contractor

Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot

# **SPPRA BIDDING DOCUMENT**

Sr No: 27



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road from Baxio Lolai  
to Sindh Dhoru Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency

Executive Engineer Buildings Division Kashmore @ Kandhkot
- (b). Brief Description of Works

Construction of Tough Tile / Paver Road from Baxio Lolai to Sindh Dhoru Taluka Kandhkot
- (c).Procuring Agency's address:-

Executive Engineer Buildings Division Kashmore @ Kandhkot
- (d). Estimated Cost:-

0.900 Million
- (e). Amount of Bid Security:-

5%

(Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-

90 Days

(Not more than sixty days).
- (g).Security Deposit:-(including bid security):-

10%

(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-

5%
- (i). Deadline for Submission of Bids along with time :-

15/03/2018 (12.00 Noon)
- (j). Venue, Time, and Date of Bid Opening:-

15/03/2018 (1.00 P.M)
- (k). Time for Completion from written order of commence: -

12 Months
- (L).Liquidity damages:-

0.05 Per Day

0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:

(in words and figures)



**SCHEDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE BAXIO LOLAI TO SINDH**  
**DHORO TALUKA KANDHKOT (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

<i>S. No.</i>	<i>Item of work</i>	<i>Qty:</i>	<i>Rate</i>	<i>Unit</i>	<i>Amount</i>
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04)	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	638 Cft	8694/95	%Cft	55474/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	451 Cft	11948/36	%Cft	53887/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 3.0 miles (S.I.No. 22 P-05)	1200 Cft	9424/10	%0Cft	4356/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/66	%Cft	4198/-
06.	Extra Lead for 3.0 Miles	1444 Cft	579/41	%Cft	8367/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	500 Sft	3015/76	%Sft	15079/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern pigment and design etc. complete (S.I.No.54 P-56)	97 5Sft	223/97	P.Sft	218371/-
09.	Borrowpit excavation undressed lead upto 100 Cft Ordinary Soil (S.I.No. 03 (a) P-17)	520 Cft	1150/-	%0Cft	575/-
10.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	15 Cft	337/-	P.Cft	5055/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
11.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	0.669 Cwt	5001/70	P.Cwt Total	<u>3346/-</u> 368248/-

Therefore  $\frac{368248 \times 244}{100} = 998525/-$

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* Rs:

*Diff: cost of Bitumen (B)* Rs:

*G.Total (A+B)* Rs.

*Total Amount in words (A+B)* \_\_\_\_\_

Contractor

Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot

# SPPRA BIDDING DOCUMENT

Sr No: 28



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road in Village Rano Mirani  
U/C Naseer Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Tough Tile / Paver Road in Village Rano Mirani  
U/C Naseer Taluka Kandhkot*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.900 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHEDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE RANO MIRANI U/C**  
**NASEER TALUKA KANDHKOT (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

<i>S. No.</i>	<i>Item of work</i>	<i>Qty:</i>	<i>Rate</i>	<i>Unit</i>	<i>Amount</i>
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04)	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	638 Cft	8694/95	%Cft	55474/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	451 Cft	11948/36	%Cft	53887/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 3.0 miles (S.I.No. 22 P-05)	1200 Cft	9424/10	%0Cft	4356/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/66	%Cft	4198/-
06.	Extra Lead for 3.0 Miles	1444 Cft	579/41	%Cft	8367/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	500 Sft	3015/76	%Sft	15079/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern pigment and design etc. complete (S.I.No.54 P-56)	97 5Sft	223/97	P.Sft	218371/-
09.	Borrowpit excavation undressed lead upto 100 Cft Ordinary Soil (S.I.No. 03 (a) P-17)	520 Cft	1150/-	%0Cft	575/-
10.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	15 Cft	337/-	P.Cft	5055/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
11.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	0.669 Cwt	5001/70	P.Cwt Total	<u>3346/-</u> 368248/-

Therefore  $\frac{368248 \times 244}{100} = 998525/-$

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* Rs:

*Diff: cost of Bitumen (B)* Rs:

*G.Total (A+B)* Rs.

*Total Amount in words (A+B)* \_\_\_\_\_

Contractor

Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot

# SPPRA BIDDING DOCUMENT

Sr No: 29



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road Out Side House of Agha  
Arsalan Pathan & Other Streets Ward No. 11 Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Construction of Tough Tile / Paver Road Out Side House of Agha Arsalan Pathan & Other Streets Ward No. 11 Taluka Kandhkot*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.600 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)



**SCHEDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD OUT SIDE HOUSE OF AGHA ARSLAN**  
**PATHAN & OTHER STREETS WARD NO.11 TALUKA KANDHKOT (CDP 2017-2018)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S. No.	Item of work	Qty:	Rate	Unit	Amount
<b><u>PART "A" TOUGH TILE / PAVER ROAD</u></b>					
01.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 3.0 miles (S.I.No. 22 P-05)	1000 Cft	3630/-	%0Cft	3630/-
02.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	250 Cft	1141/25	%Cft	2853/-
03.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	500 Cft	8694/95	%Cft	43475/-
04.	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern pigment and design etc. complete (S.I.No.54 P-56)	1000 Sft	223/97	P.Sft	223970/-
05.	Extra Lead for 3.0 Miles	1250 Cft	579/41	%Cft	7243/-
				<b>Total</b>	<b>281171/-</b>

**PART "B" OPEN DRAIN**

01.	Cement concrete plain i/c placing compacting finishing and curing complete (i/c screening and washing of stone aggregate without shuttering 1:2:4 (S.I.No. 05 (i) P-18)	63 Cft	14429/25	%Cft	9090/-
02.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	150 Cft	11948/36	%Cft	17923/-
03.	Const. of Standard Open Drain concrete Block of C.C 1:2:4 with situ to the design Profile (S.I.No. D-1 P-58 P.H.E)	100 Rft	94/-	P.Rft	9400/-
04.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	1000 Sft	3015/76	%Sft	30157/-
05.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	15 Cft	337/-	P.Cft	5055/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
06.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	0.669 Cwt	5001/70	P.Cwt	3346/-
				Total	74971/-

## ABSTRACT

Part "A" Tough Tile / Paver Road Rs.281171/-

Part "B" Open Drain

Rs.74971/-  
Total Rs.356142/-

Therefore  $\frac{356142 \times 449}{100} =$  Rs.1599077/-

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

Total (A) Rs:

Diff: cost of Bitumen (B) Rs:

G.Total (A+B) Rs.

Total Amount in words (A+B) \_\_\_\_\_

Contractor

Executive Engineer,  
Buildings Division  
Kashmore @ Kandhkot

# SPPRA BIDDING DOCUMENT

Sr No: 30



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road in Village Rais Yaqoob  
Bhutto Badani Taluka Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works *Construction of Tough Tile / Paver Road in Village Rais Yaqoob Bhutto Badani Taluka Kashmore*
- (c). Procuring Agency's address:- *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:- *2.000 Million*
- (e). Amount of Bid Security:- *5%* (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):- *90 Days* (Not more than sixty days).
- (g). Security Deposit:- (including bid security):- *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :- *5%*
- (i). Deadline for Submission of Bids along with time :- *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:- *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: - *12 Months*
- (L). Liquidity damages:- *0.05 Per Day* *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount: (in words and figures)

**SCHDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE RAIS YAQOOB BHUTTO**  
**BADANI TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	150 Cft	8694/95	%Cft	13042/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	790 Cft	11948/36	%Cft	94392/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	975 Cft	9424/10	%0Cft	9188/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/60	%Cft	4198/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	244 Cft	8694/95	%Cft	21216/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	800 Sft	3015/76	%Cft	24126/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 197 x 80 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	975 Sft	199/77	P.Sft	194776/-
				<b>Total</b>	<b>348849/-</b>
				<b>Therefore 348849 x 573=</b>	<b>1999926/-</b>
				<b>100</b>	

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 31



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Constrcution of Tough Tile / Paver Road in Village Rais Munwar  
Bhutto Badani Taluka Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Constrcution of Tough Tile / Paver Road in Village Rais Munwar Bhutto Badani Taluka Kashmore*
- (c).Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *2.000 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g).Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L).Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE RAIS MUNWAR BHUTTO**  
**BADANI TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	150 Cft	8694/95	%Cft	13042/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	790 Cft	11948/36	%Cft	94392/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	975 Cft	9424/10	%0Cft	9188/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/60	%Cft	4198/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	244 Cft	8694/95	%Cft	21216/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	800 Sft	3015/76	%Cft	24126/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 197 x 80 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	975 Sft	199/77	P.Sft	194776/-
				<b>Total</b>	<b>348849/-</b>
				<b>Therefore 348849 x 573=</b>	<b>1999926/-</b>
				<b>100</b>	

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**



# SPPRA BIDDING DOCUMENT

Sr No: 32



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*Constrcution of Tough Tile / Paver Road in Village Jam Jumo  
Samejo Badani Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *Construction of Tough Tile / Paver Road in Village Jam Jumo Samejo Badani Taluka Kandhkot*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *2.000 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE JAM JUMO KHAN**  
**SAMEJO BADANI TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	150 Cft	8694/95	%Cft	13042/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	790 Cft	11948/36	%Cft	94392/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	975 Cft	9424/10	%0Cft	9188/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/60	%Cft	4198/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	244 Cft	8694/95	%Cft	21216/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	800 Sft	3015/76	%Cft	24126/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 197 x 80 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	975 Sft	199/77	P.Sft	194776/-
				<b>Total</b>	<b>348849/-</b>
				<b>Therefore 348849 x 573=</b>	<b>1999926/-</b>
				<b>100</b>	

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# **SPPRA BIDDING DOCUMENT**

Sr No: 33



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Construction of Tough Tile / Paver Road in Village Ali Hassan  
Khokhar Badani Taluka Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency *Executive Engineer Buildings Division Kashmore @ Kandhkot*

(b). Brief Description of Works *Construction of Tough Tile / Paver Road in Village Ali Hassan Khokhar Badani Taluka Kashmore*

(c). Procuring Agency's address:- *Executive Engineer Buildings Division Kashmore @ Kandhkot*

(d). Estimated Cost:- *1.000 Million*

(e). Amount of Bid Security:- *5%* (Fill in lump sum amount

or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). Period of Bid Validity (days):- *90 Days* (Not more than sixty days).

(g). Security Deposit:-(including bid security):- *10%*

(in % age of bid amount /estimated cost equal to 10%)

(h). Percentage, if any, to be deducted from bills :- *5%*

(i). Deadline for Submission of Bids along with time :- *15/03/2018 (12.00 Noon)*

(j). Venue, Time, and Date of Bid Opening:- *15/03/2018 (1.00 P.M)*

(k). Time for Completion from written order of commence: - *12 Months*

(L). Liquidity damages:- *0.05 Per Day* *0.05 of Estimated Cost or Bid cost*

per day of delay, but total not exceeding 10%).

(m). Deposit Receipt No: Date: Amount: (in words and figures)

**SCHDULE-(B)**  
**CONSTRUCTION OF TOUGH TILE / PAVER ROAD IN VILLAGE ALI HASSAN KHOKHAR**  
**BADANI TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	300 Cft	3176/25	%0Cft	953/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	150 Cft	8694/95	%Cft	13042/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	790 Cft	11948/36	%Cft	94392/-
04.	Filling Watering and ramming earth under floor with new earth excavated from foundation lead upto one chain and lift upto 5 ft. Extra 6.0 miles (S.I.No. 22 P-05)	975 Cft	9424/10	%0Cft	9188/-
05.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	244 Cft	1720/60	%Cft	4198/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	244 Cft	8694/95	%Cft	21216/-
07.	Cement Plaster 1:4 upto 2" height 3/4" thick (S.I.No. 11 (a) P-58)	800 Sft	3015/76	%Cft	24126/-
08.	Providing & fixing cement paving blocks flooring having size of 197 x 197 x 80 (mm) of catty / quddra/coble b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and lying in specified manner / pattern and design etc. complete (S.I.No.54 P-56)	975 Sft	199/77	P.Sft	194776/-
				<b>Total</b>	<b>348849/-</b>
					<b>Therefore 348849 x 286=</b>
					<b>100</b>
					<b>997708/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

**SCHDULE-(B)**

# SPPRA BIDDING DOCUMENT

Sr No: 34



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*Installation of Solar Street Light Poles in Village Rais Mohammad  
Hayat Ogahi Taluka Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *Installation of Solar Street Light Poles in Village Rais Mohammad Hayat Ogahi Taluka Kandhkot*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *1.500 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)



**INSTALLATION OF SOLAR LIGHTS POLES IN VILLAGE RAIS MOHAMMAD**  
**HAYAT OGHI TALUKA KASHMORE (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S.No.	Name of Item	Qty:	Rate	Unit	Amount
1.	Providing superior imported quality of M.S Hexagonal Pole of 25 ft. height with proper warping secured having the following specification and designed for may wind velocity with paint final coat.  <b>Specification are as under:-</b>  10'-4" 10'-3" 5'-2 1/2" and with base plate 1' 1/2" x 1' 1/2" complete with all accuracies. (Quoted by Market Value)	07 Nos.		Each	
	<b>TOTAL</b>	07 Nos.		Each	
2	<b><u>SOLAR POWERED LED STREET LIGHT</u></b>	07 Nos.		Each	
		<b>Total 01 &amp; 02</b>			

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* *Rs:*

*Diff: cost of Bitumen (B)* *Rs:*

*G.Total (A+B)* *Rs.*

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# **SPPRA BIDDING DOCUMENT**

Sr No: 35



**STANDARD FORM OF BIDDING DOCUMENT**

**FOR**

**PROCUREMENT OF WORKS**

**(For Contracts (Small) amounting between Rs.2.50 million to Rs.50.00 million)**

**BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

**Name of Scheme:-**

**Installation of Solar Street Light Poles in Village Dari  
Taluka Kandhkot**

**Name of Contractor:-**

**Dr No: & Date of Issue**

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuing Bidding Documents. The following specific data for the works to be tendered shall complete, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

#### **1.1 Name of Procuring Agency**

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert name of the Procuring Agency)*

#### **Brief Description of Works**

**Installation of Solar Street Light Poles in Village Dari**

**Taluka Kandhkot**

5.1 Estimated Cost

**5.70 Million**

5.1 (a) Procuring Agency's address:

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert address of the Procuring Agency with telex/fax)*

(b) Engineer's address:

**Executive Engineer Buildings Division Near D.C Office Kashmore @ Kandhkot**

*( Insert name and address of the Engineer, if any, with telex/fax.)*

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows: *(Insert required capabilities and documents)*

- i. Financial capacity: *( must have turnover of Rs-----Million);*
- ii. Technical capacity :*(mention the appropriate category of registration with PEC and qualification and experience of the staff);*
- iii. Construction Capacity: *( mention the names and number of equipments required for the work).*

12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

(b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

**13.1 Amount of Bid Security**

5%

( Fill in lump sum amount or in % age of bid amount /estimated cost, but not below 1% and not exceeding 5%)

**14.1 Period of Bid Validity**

90 Days

(Fill in "number of days" not exceeding 90)

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (0) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

Executive Engineer Buildings Division Kashmore @ Kandhkot

(insert postal address or location of bid box for delivery by hand)

**15.1 Deadline for Submission of Bids**

Time: 12.00 Noon on 15/03/2018

**16.1 Venue, Time, and Date of Bid Opening**

Venue: Kandhkot

Time: 1.00 P.M Date: 15/03/2018

**16.4 Responsiveness of Bids**

(i) Bid is valid till required period,

- \*(ii) Bid prices are firm during currency of contract/Price adjustment;
- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

\*Procuring agency can adopt either of two options . ( *Select either of them*)

- (a) **Fixed Price contract:** In these contracts no escalation will be provided during currency of the contract and normally period of completion of these works is upto 12 months.
- (b) **Price adjustment contract:** In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh, after bid opening during currency of the contract.

**SCHDULE-(B)**  
**INSTALLATION OF SOLAR LIGHTS POLES IN VILLAGE DARI TALUKA**  
**KANDHKOT (CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S.No.	Name of Item	Qty:	Rate	Unit	Amount
1.	Providing superior imported quality of M.S Hexagonal Pole of 25 ft. height with proper warping secured having the following specification and designed for may wind velocity with paint final coat.  Specification are as under:-  10'-4" 10'-3" 5'-2 1/2" and with base plate 1' 1/2" x 1' 1/2" complete with all accuracies. (Quoted by Market Value)	28 Nos.		Each	
	<b>TOTAL</b>	28 Nos.		Each	
2	<b><u>SOLAR POWERED LED STREET LIGHT</u></b>	28 Nos.		Each	
		<b>Total 01 &amp; 02</b>			

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

**Total Amount in words (A+B)** \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# **SPPRA BIDDING DOCUMENT**

Sr No: 36



**STANDARD FORM OF BIDDING DOCUMENT**

**FOR**

**PROCUREMENT OF WORKS**

*(For Contracts (Small) amounting between Rs.2.50 million to Rs.50.00 million)*

**BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

**Name of Scheme:-**

**Installation of Solar Street Light Poles in Ghouspur Town**

**Name of Contractor:-**

**Dr No: & Date of Issue**

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuing Bidding Documents. The following specific data for the works to be tendered shall complete, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

#### **1.1 Name of Procuring Agency**

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert name of the Procuring Agency)*

#### **Brief Description of Works**

**Installation of Solar Street Light Poles in Ghouspur Town**

5.1 Estimated Cost

**10.00 Million**

5.1 (a) Procuring Agency's address:

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert address of the Procuring Agency with telex/fax)*

(b) Engineer's address:

**Executive Engineer Buildings Division Near D.C Office Kashmore @ Kandhkot**

*( Insert name and address of the Engineer, if any, with telex/fax.)*

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows: *(Insert required capabilities and documents)*

- i. Financial capacity: *( must have turnover of Rs-----Million);*
- ii. Technical capacity :*(mention the appropriate category of registration with PEC and qualification and experience of the staff);*
- iii. Construction Capacity: *( mention the names and number of equipments required for the work).*



12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

(b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

**13.1 Amount of Bid Security**

5%

( Fill in lump sum amount or in % age of bid amount /estimated cost, but not below 1% and not exceeding 5%)

**14.1 Period of Bid Validity**

90 Days

(Fill in "number of days" not exceeding 90)

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (0) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

Executive Engineer Buildings Division Kashmore @ Kandhkot

(insert postal address or location of bid box for delivery by hand)

**15.1 Deadline for Submission of Bids**

Time: 12.00 Noon on 15/03/2018

**16.1 Venue, Time, and Date of Bid Opening**

Venue: Kandhkot

Time: 1.00 P.M Date: 15/03/2018

**16.4 Responsiveness of Bids**

(i) Bid is valid till required period,

- \*(ii) Bid prices are firm during currency of contract/Price adjustment;
- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

\*Procuring agency can adopt either of two options . ( *Select either of them*)

- (a) **Fixed Price contract:** In these contracts no escalation will be provided during currency of the contract and normally period of completion of these works is upto 12 months.
- (b) **Price adjustment contract:** In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh, after bid opening during currency of the contract.

**SCHDULE-(B)**  
**INSTALLATION OF SOLAR LIGHTS POLES IN GHOSHPUR TOWN**  
**(CDP 2017-2018)**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S.No.	Name of Item	Qty:	Rate	Unit	Amount
1.	Providing superior imported quality of M.S Hexagonal Pole of 25 ft. height with proper warping secured having the following specification and designed for may wind velocity with paint final coat.  <b>Specification are as under:-</b>  10'-4" 10'-3" 5'-2 1/2" and with base plate 1' 1/2" x 1' 1/2" complete with all accuracies. (Quoted by Market Value)	50 Nos.		Each	
	<b>TOTAL</b>	50 Nos.		<b>Each</b>	
2	<b><u>SOLAR POWERED LED STREET LIGHT</u></b>	50 Nos.		<b>Each</b>	
		<b>Total 01 &amp; 02</b>			

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

\_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 37



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*M&R to Old Mukhtiarkar Bungalow at Kandhkot  
(Occupied by Civil Judge)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *M&R to Old Mukhtiarkar Bungalow at Kandhkot  
(Occupied by Civil Judge)*
- (c).Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *0.150 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g).Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L).Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHDULE-(B)**  
**M&R TO OLD MUKHTIARKAR BUNGALOW AT KANDHKOT (OCCUPIED BY CIVIL JUDGE)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Removing Cement Plaster	737 Sft	121/-	%Sft	892/-
02.	Applying floating of cement	737 Sft	660/-	%Sft	4864/-
03.	Cement Plaster 1:6 upto 2" height ½" thick (S.I.No. 13 (b) P-58)	737 Sft	2206/60	%Sft	16263/-
04.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	737 Sft	2197/52	%Sft	16194/-
05.	Providing & laying tiles glazed 6"x6"x ¼" on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar ¾" thick i/c washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles to proper profile (S.I.No. 60 P-53)	48 Sft	30509/77	%Sft	14645/-
06.	Marble Dedo	112 Sft	28299/30	%Sft	31695/-
07.	Supplying & fixing in position iron / steel grill of ¾" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	16 Sft	180/50	P.Sft	2888/-
08.	Wire Gauze	16 Sft	190/72	P.Sft	3052/-
09.	Preparing Old surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	162 Sft	1160/06	%Sft	1879/-
10.	White Washing 02 Coats	1160 Sft	425/84	%Sft	4940/-
11.	Distemping 03 Cotas	4116 Sft	1079/65	%Sft	44438/-
12.	Color washing 03 coats	504 Sft	859/90	%Sft	4334/-
				<b>Total</b>	<b>146084/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# **SPPRA BIDDING DOCUMENT**

Sr No: 38



## ***STANDARD FORM OF BIDDING DOCUMENT***

***FOR***

### ***PROCUREMENT OF WORKS***

***(For Contracts (Small) amounting between Rs.2.50 million to Rs.50.00 million)***

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

***Name of Scheme:-***

***Renovation and Rehabilitation of Sain Mana Ram Mandar  
Mirzapur Mohalla Kandhkot***

***Name of Contractor:-***

***Dr No: & Date of Issue***

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## **BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuing Bidding Documents. The following specific data for the works to be tendered shall complete, amend, or supplement the provisions in the Instructions to Bidders. Wherever there is a conflict, the provisions herein shall prevail over those in the Instructions to Bidders.)

### **Instructions to Bidders**

#### **Clause Reference**

#### **1.1 Name of Procuring Agency**

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert name of the Procuring Agency)*

#### **Brief Description of Works**

**Renovation and Rehabilitation of Sain Mana Ram Mandar**

**Mirzapur Mohalla Kandhkot**

5.1 Estimated Cost

**20.00 Million**

5.1 (a) Procuring Agency's address:

**Executive Engineer Buildings Division Kashmore @ Kandhkot**

*( Insert address of the Procuring Agency with telex/fax)*

(b) Engineer's address:

**Executive Engineer Buildings Division Near D.C Office Kashmore @ Kandhkot**

*( Insert name and address of the Engineer, if any, with telex/fax.)*

10.3 Bid shall be quoted entirely in Pak. Rupees. The payment shall be made in Pak. Rupees.

11.2 The bidder has the financial, technical and constructional capability necessary to perform the Contract as follows: *(Insert required capabilities and documents)*

- i. Financial capacity: *( must have turnover of Rs-----Million);*
- ii. Technical capacity : *(mention the appropriate category of registration with PEC and qualification and experience of the staff);*
- iii. Construction Capacity: *( mention the names and number of equipments required for the work).*



12.1 (a) A detailed description of the Works, essential technical and performance characteristics.

(b) Complete set of technical information, description data, literature and drawings as required in accordance with Schedule B to Bid, Specific Works Data. This will include but not be limited to a sufficient number of drawings, photographs, catalogues, illustrations and such other information as is necessary to illustrate clearly the significant characteristics such as general construction dimensions and other relevant information about the works to be performed.

**13.1 Amount of Bid Security**

5%

( Fill in lump sum amount or in % age of bid amount /estimated cost, but not below 1% and not exceeding 5%)

**14.1 Period of Bid Validity**

90 Days

(Fill in "number of days" not exceeding 90)

**14.4 Number of Copies of the Bid to be submitted:**

One original plus (0) copies.

**14.6 (a) Procuring Agency's Address for the Purpose of Bid Submission**

Executive Engineer Buildings Division Kashmore @ Kandhkot

(insert postal address or location of bid box for delivery by hand)

**15.1 Deadline for Submission of Bids**

Time: 12.00 Noon on 15/03/2018

**16.1 Venue, Time, and Date of Bid Opening**

Venue: Kandhkot

Time: 1.00 P.M Date: 15/03/2018

**16.4 Responsiveness of Bids**

(i) Bid is valid till required period,

- \*(ii) Bid prices are firm during currency of contract/Price adjustment;
- (iii) Completion period offered is within specified limits,
- (iv) Bidder is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) Bid does not deviate from basic technical requirements and
- (vi) Bids are generally in order, etc.

\*Procuring agency can adopt either of two options . ( *Select either of them*)

- (a) **Fixed Price contract:** In these contracts no escalation will be provided during currency of the contract and normally period of completion of these works is upto 12 months.
- (b) **Price adjustment contract:** In these contracts escalation will be paid only on those items and in the manner as notified by Finance Department, Government of Sindh, after bid opening during currency of the contract.

**SCHDULE-(B)**  
**RENOVATION AND REHABILITATION OF SAIN MANA RAM MANDAR MIRZAPUR**  
**MOHALLA AT KANDHKOT**

**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	1205 Cft	337/-	P.Cft	406085/-
02.	Fabrication of TOR Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	57.41 Cwt	5001/70	P.Cwt	287148/-
03.	White Marble ¾" thick (S.I.No. P- )	7169 Sft	567/48	P.Sft	4068264/-
04.	P/F Steel Grill	236 Sft	194/16	P.Sft	45822/-
05.	P/F Steel Grill Doors	87 Sft	231/60	P.Sft	20149/-
06.	P/L Glazed Tile 6 x 6x ¼"	10378 Sft	30509/77	%Sft	3166304/-
07.	Glazed Tile Dedo	972 Sft	28299/30	%Sft	275069/-
08.	P/F False Ceiling Plster of Paris	7268 Sft	346/50	P.Sft	2518362/-
09.	Aluminum Doors	96 Sft	1507/66	%Sft	144735/-
10.	Aluminum Windows	464 Sft	1647/69	%Sft	764528/-
11.	First Class deodar wood wrought, joinery in doors and windows etc. fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats handles and cords with hooks etc 1-3/4" thick (Without Chowkats) (S.I.No.07 (b) P-65)	299 Sft	1273/76	P.Sft	380854/-
12.	Matt Finish	420 Sft	34448/38	%Sft	14466/-
13.	Preparing Surface Rock Wall	7105 Sft	4504/50	%Sft	320045/-
				<b>Total</b>	<b>19736325/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 39



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*M&R to Cat IIIrd Bungalow No.03 Occupied by I.S.I  
Sub-Division Complex Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *M&R to Cat IIIrd Bungalow No.03 Occupied by I.S.I  
Sub-Division Complex Kashmore*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.150 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHDULE-(B)**  
**M&R TO CAT IIIRD BUNGALOW NO.03 OCCUPIED BY I.S.I SUB-DIVISION COMPLEX**  
**KASHMORE**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Removing Cement Plaster	737 Sft	121/-	%Sft	892/-
02.	Applying floating of cement	737 Sft	660/-	%Sft	4864/-
03.	Cement Plaster 1:6 upto 2" height ½" thick (S.I.No. 13 (b) P-58)	737 Sft	2206/60	%Sft	16263/-
04.	Cement Plaster 1:4 upto 2" height ¾" thick (S.I.No. 11 (a) P-58)	737 Sft	2197/52	%Sft	16194/-
05.	Providing & laying tiles glazed 6"x6"x ¼" on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar ¾" thick i/c washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles to proper profile (S.I.No. 60 P-53)	48 Sft	30509/77	%Sft	14645/-
06.	Marble Dedo	112 Sft	28299/30	%Sft	31695/-
07.	Supplying & fixing in position iron / steel grill of ¾" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	16 Sft	180/50	P.Sft	2888/-
08.	Wire Gauze	16 Sft	190/72	P.Sft	3052/-
09.	Preparing Old surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	162 Sft	1160/06	%Sft	1879/-
10.	White Washing 02 Coats	1160 Sft	425/84	%Sft	4940/-
11.	Distemping 03 Cotas	4116 Sft	1079/65	%Sft	44438/-
12.	Color washing 03 coats	504 Sft	859/90	%Sft	4334/-
				<b>Total</b>	<b>146084/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# **SPPRA BIDDING DOCUMENT**

Sr No: 40



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*M&R to Cat IIIrd Bungalow No. (Occupied Mukhtiarkar Kashmore)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *M&R to Cat IIIrd Bungalow No. (Occupied Mukhtiarkar Kashmore)*
- (c).Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *0.150 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f).Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g).Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L).Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)



**SCHDULE-(B)**  
**M&R TO CAT IIIRD BUNGALOW NO. (OCCUPIED MUKHTIARKAR KASHMORE)**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Removing Cement Plaster	737 Sft	121/-	%Sft	892/-
02.	Applying floating of cement	737 Sft	660/-	%Sft	4864/-
03.	Cement Plaster 1:6 upto 2" height ½" thick (S.I.No. 13 (b) P-58)	737 Sft	2206/60	%Sft	16263/-
04.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	737 Sft	2197/52	%Sft	16194/-
05.	Providing & laying tiles glazed 6"x6"x ¼" on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar ¾" thick i/c washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles to proper profile (S.I.No. 60 P-53)	48 Sft	30509/77	%Sft	14645/-
06.	Marble Dedo	112 Sft	28299/30	%Sft	31695/-
07.	Supplying & fixing in position iron / steel grill of ¾" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	16 Sft	180/50	P.Sft	2888/-
08.	Wire Gauze	16 Sft	190/72	P.Sft	3052/-
09.	Preparing Old surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	162 Sft	1160/06	%Sft	1879/-
10.	White Washing 02 Coats	1160 Sft	425/84	%Sft	4940/-
11.	Distemrping 03 Cotas	4116 Sft	1079/65	%Sft	44438/-
12.	Color washing 03 coats	504 Sft	859/90	%Sft	4334/-
				<b>Total</b>	<b>146084/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# SPPRA BIDDING DOCUMENT

Sr No: 41



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### **BUILDINGS DIVISION KASHMORE @ KANDHKOT**

*Name of Scheme:-*

*M&R to office of Executive Engineer & Assistant Engineer  
(Buildings) Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

**EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT**

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *M&R to office of Executive Engineer & Assistant Engineer (Buildings) Kandhkot*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *0.135 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:- (including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHDULE-(B)**  
**M&R TO OFFICE OF EXECUTIVE ENGINEER & ASSISTANT ENGINEER (BUILDINGS)**  
**KANDHKOT**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Excavation in foundation of building bridges and other structures including dagbelling dressing refilling ground structure with excavated earth watering and ramming lead upto 5ft in ordinary soil (S.I.No. 18 (b) P-04).	163 Cft	3176/25	%0Cft	518/-
02.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:5:10 (S.I.No. 4 (c) P-17).	33 Cft	8694/95	%Cft	2870/-
03.	Pacca brick work in foundation and plinth in 1:6 cement sand mortar (S.I.No. 04 (e) P-24).	153 Cft	11948/36	%Cft	18281/-
04.	Reinforced cement concrete work including all labour and material except the cost of steel reinforced and its labour for bending and binding which will be paid separately. This rate also includes all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle 1:2:4 (S.I.No. 06 (i) P-19)	37 Cft	337/-	P.Cft	12469/-
05.	Fabrication of Mild Steel reinforced for cement concrete including cutting bending laying in position, making joints and fastenings including cost of binding wire (also including removal of rust from bars (S.I.No. 07 (ii) P-20)	1.85 Cwt	5001/70	P.Cwt	9253/-
06.	Filling Watering and ramming earth under floor with surplus earth from foundation lead upto one chain and lift upto 5 ft. (S.I.No. 21 P-05)	34 Cft	3630/-	%0Cft	123/-
07.	Supplying and filling sand under floor and plugging in walls (S.I.No. 29 P-31)	11 Cft	1141/25	%Cft	126/-
08.	Cement Concrete brick or stone ballast 1-1/2" to 2" 1:6:12 (S.I.No. 04 (d) P-17)	08 Cft	8122/95	%Cft	6498/-
09.	Pacca brick work in ground floor in 1:6 (S.I.No. 5 (i) P-25)	160 Cft	12674/36	%Cft	20279/-
10.	Cement Plaster 1:6 upto 2" height 1/2" thick (S.I.No. 13 (b) P-58)	462 Sft	2206/60	%Sft	10194/-
11.	Cement Plaster 1:4 upto 2" height 3/8" thick (S.I.No. 11 (a) P-58)	462 Sft	2197/25	%Sft	10153/-
12.	S/F T-Iron	0.29 Cwt	3750/-	P.Cwt	1088/-
13.	Second Class tile	42 Sft	7607/25	%Sft	3195/-
14.	First Class Dedar Wood	18 Sft	1273/76	P.Sft	22928/-
15.	C.C topping	25 Sft	4411/88	%Sft	1103/-
16.	P/L Glazed Tile	25 Sft	27675/66	%Sft	6919/-
17.	P/L White Glazed Tile	100 Sft	28253/61	%Sft	28254/-
18.	Preparing new surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	35 Sft	2116/41	%Sft	741/-

S. No.	Item of work	Qty:	Rate	Unit	Amount
19.	Primary coat of chalk	462 Sft	442/75	%Sft	2046/-
20.	Distemping 03 Coats	462 Sft	1079/65	%Sft	4988/-
21.	Extra Lead for 3.0 Mile	45 Sft	579/41	%Sft	261/-
				<b>Total</b>	<b>127114/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

<i>Total (A)</i>	<i>Rs:</i>
<i>Diff: cost of Bitumen (B)</i>	<i>Rs:</i>
<i>G.Total (A+B)</i>	<i>Rs.</i>
<i>Total Amount in words (A+B)</i> _____	

---

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# **SPPRA BIDDING DOCUMENT**

Sr No: 42



## **STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS**

*(For Contracts Costing up to Rs 2.5 MILLION)*

***BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*M&R to Investigation Office in Sub-Divisional Complex at Kashmore*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *M&R to Investigation Office in Sub-Divisional Complex at Kashmore*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.150 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHDULE-(B)**  
**M&R TO INVESTIGATION OFFICE IN SUB-DIVISIONAL COMPLEX AT KASHMORE**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Removing Cement Plaster	737 Sft	121/-	%Sft	892/-
02.	Applying floating of cement	737 Sft	660/-	%Sft	4864/-
03.	Cement Plaster 1:6 upto 2" height ½" thick (S.I.No. 13 (b) P-58)	737 Sft	2206/60	%Sft	16263/-
04.	Cement Plaster 1:4 upto 2" height ¾" thick (S.I.No. 11 (a) P-58)	737 Sft	2197/52	%Sft	16194/-
05.	Providing & laying tiles glazed 6"x6"x ¼" on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar ¾" thick i/c washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles to proper profile (S.I.No. 60 P-53)	48 Sft	30509/77	%Sft	14645/-
06.	Marble Dedo	112 Sft	28299/30	%Sft	31695/-
07.	Supplying & fixing in position iron / steel grill of ¾" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	16 Sft	180/50	P.Sft	2888/-
08.	Wire Gauze	16 Sft	190/72	P.Sft	3052/-
09.	Preparing Old surface painting of doors and windows any type (including edges) (S.I.No. 5 (c) P-76)	162 Sft	1160/06	%Sft	1879/-
10.	White Washing 02 Coats	1160 Sft	425/84	%Sft	4940/-
11.	Distempring 03 Cotas	4116 Sft	1079/65	%Sft	44438/-
12.	Color washing 03 coats	504 Sft	859/90	%Sft	4334/-
				<b>Total</b>	<b>146084/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**



# SPPRA BIDDING DOCUMENT

Sr No: 43



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

***BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*M&R to Day to Day Emergent Work in District Kashmore @ Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *M&R to Day to Day Emergent Work in District Kashmore @ Kandhkot*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.150 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHDULE-(B)**  
**M&R TO DAY TO DAY EMERGENT WORK IN DISTRICT KASHMORE @ KANDHKOT**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	Electric Motor	05 Nos.		Each	
02.	Fiber Glass Tank	01 No.		Each	
03.	Energy Sever	100 Nos.		Each	
04.	Office Chair	09 Nos.		Each	
				<b>Total</b>	_____

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

*Total (A)* *Rs:*

*Diff: cost of Bitumen (B)* *Rs:*

*G.Total (A+B)* *Rs.*

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 44



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

***BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*M&R to M.C.H Centre at Kandhkot*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *M&R to M.C.H Centre at Kandhkot*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *0.200 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)

**SCHDULE-(B)**  
**M&R TO M.C.H CENTRE AT KANDHKOT**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	C. C Topping	881 Sft	3275/50	%Sft	28857/-
02.	P/L HALLA TILE	224 Sft	47651/62	%Sft	106740/-
03.	S/F Iron Steel	26 Sft	180/50	P.Sft	4693/-
				<b>Total</b>	<b>182682/-</b>

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

*Total Amount in words (A+B)* \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**

# SPPRA BIDDING DOCUMENT

Sr No: 45



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*M&R to R.H.C Tangwani i/c Electric Work*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). Brief Description of Works      *M&R to R.H.C Tangwani i/c Electric Work*
- (c). Procuring Agency's address:-      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). Estimated Cost:-      *0.300 Million*
- (e). Amount of Bid Security:-      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity (days):-      *90 Days*      (Not more than sixty days).
- (g). Security Deposit:-(including bid security):-      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). Percentage, if any, to be deducted from bills :-      *5%*
- (i). Deadline for Submission of Bids along with time :-      *15/03/2018 (12.00 Noon)*
- (j). Venue, Time, and Date of Bid Opening:-      *15/03/2018 (1.00 P.M)*
- (k). Time for Completion from written order of commence: -      *12 Months*
- (L). Liquidity damages:-      *0.05 Per Day*      *0.05 of Estimated Cost or Bid cost*  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:      (in words and figures)



**SCHDULE-(B)**  
**M&R to R.H.C Tangwani "electric work"**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

**(A) Description and rate of Items bases on composite schedule of Rates.**

S. No.	Item of work	Qty:	Rate	Unit	Amount
<b><u>PART "A" SCHEDULE ITEMS</u></b>					
01.	Wiring for light or fan points with 1/1 13 (3-029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 129 P-15).	40 Points	910/-	P.P	36400/-
02.	Wiring for plug points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 130 P-15).	10 Points	742/-	P.P	7420/-
03.	Wiring for Call Bell points with (3/.029) PVC insulated wire in 20 mm / (3/4") channel patti or surface as required (New) (S.I.No. 131 P-15).	02 Points	1590/-	P.P	3180/-
04.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.036 (4mm2) copper conductor in 3/4" dia PVC conduct un-surface (New) (S.I.No.04 P-01).	470 Meter	200/-	P.Meter	94000/-
06.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.044 (6mm2) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.05 P-01).	10 Meter	305/-	P.Meter	3050/-
07.	Providing & Lying (MAIN or SUB MAIN) with size 2-7/.052 (10mm2) copper conductor in 1" dia PVC conduct un-surface (New) (S.I.No.06 P-01).	100 Meter	428/-	P.Meter	42800/-
08.	P/F two way S.P 15 Amps. switch flush type (New) (S.I.No. 221 P-33)	20 Nos.	67/-	Each	1340/-
09.	P&F two pin 5 Amp plug & socket (New) (S.I.No. 222 P-33)	10 Nos.	80/-	Each	800/-
10.	P&F three pin 10 / 15 Amp. Plug & Sockets (New) (S.I.No. 227 P-33)	04 Nos.	162/-	Each	648/-
11.	P&F Holder for 125 watts Light @ as per Site requirement & instruction of Engineer In charge (New) (S.I.No. 189 P-29)	10 Nos.	203/-	Each	2030/-
12.	P&F Circuit breaker 6,10,15,20,30,40,50 and 63 Amp. S.P (TB-58) on prepared board as required (New) (S.I.No. 203 P-31)	04 Nos.	916/-	Each	3664/-
13.	P&F Circuit breaker 15,20,30,40,50 60,75 and 100 Amp. TP (XS-100NS) on prepared board as required (New) (S.I.No. 207 P-31)	01 No.	9261/-	Each	9261/-
14.	P&F Brass Ceiling Fan 56" (good quality) (New) (S.I.No.235 P-34)	06 Nos.	3185/-	Each	19110/-
				<b>Total</b>	<b>273395/-</b>

## PART "B" NON-SCHEDULE ITEMS

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	P&F panel board double shutter to accommodate circuit breakers i/c painting with enameled paint and for other similar job on surface (L.Q.R)	01 Sft		P.Sft	
02.	P&F wall bracket light fancy type superior quality i/c necessary electric connection and fixing on wall or ceiling etc complete (L.Q.R)	04 Nos.		Each	
03.	P/F Energy sever superior quality i/c fixing on wall (L.Q.R)	26 Nos.		Each	
04.	P&F double S.W board to accommodate mains or sub-mains control switches and for sub-mains control switch and for other smaller jobs on surface (L.Q.R)	06.0 Sft		P.Sft	
05.	P/F 12" Exhaust fan capacitor type i/c shutter metallic body 60 watts 20 volts S.P complete in all respect (L.Q.R)	01 No.		Each	
06.	S/F Wall bracket fan 18" size A.C Single Phase Superior Quality complete i/c Fixing on wall as required (Royal make) (L.Q.R)	01 No.		Each	
07.	Providing and Fixing 100 Watts Bulb (S.I.No. P- )	09 Nos.		Each	
				<b>Total</b>	_____

\_\_\_\_\_ % on the rates of CSR.

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
Buildings Division  
Kashmore @ Kandhkot

# SPPRA BIDDING DOCUMENT

Sr No: 46



## STANDARD BIDDING DOCUMENT PROCUREMENT OF WORKS

*(For Contracts Costing up to Rs 2.5 MILLION)*

### ***BUILDINGS DIVISION KASHMORE @ KANDHKOT***

*Name of Scheme:-*

*M&R to Staff Quarter in Works & Services Colony at Kandhkot  
(Occupied by Office Superintendent)*

*Name of Contractor:-*

*Dr No: & Date of Issue*

***EXECUTIVE ENGINEER  
BUILDINGS DIVISION  
KASHMORE @ KANDHKOT***

## BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). **Name of Procuring Agency**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (b). **Brief Description of Works**      *M&R to Staff Quarter in Works & Services Colony at Kandhkot  
(Occupied by Office Superintendent)*
- (c). **Procuring Agency's address:-**      *Executive Engineer Buildings Division Kashmore @ Kandhkot*
- (d). **Estimated Cost:-**      *0.100 Million*
- (e). **Amount of Bid Security:-**      *5%*      (Fill in lump sum amount  
or in % age of bid amount /estimated cost, but not exceeding 5%)
- (f). **Period of Bid Validity (days):-**      *90 Days*      (Not more than sixty days).
- (g). **Security Deposit:-(including bid security):-**      *10%*  
(in % age of bid amount /estimated cost equal to 10%)
- (h). **Percentage, if any, to be deducted from bills :-**      *5%*
- (i). **Deadline for Submission of Bids along with time :-**      *15/03/2018 (12.00 Noon)*
- (j). **Venue, Time, and Date of Bid Opening:-**      *15/03/2018 (1.00 P.M)*
- (k). **Time for Completion from written order of commence: -**      *12 Months*
- (L). **Liquidity damages:-**      *0.05 Per Day*      0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). **Deposit Receipt No: Date: Amount:**      (in words and figures)

**SCHDULE-(B)**  
**M&R TO STAFF QUARTER IN WORKS & SERVICES COLONY AT KANDHKOT (OCCUPIED BY**  
**OFFICE SUPERINTENDENT).**  
**DRAFT BIDDING DOCUMENT FOR WORKS**  
**BILLS OF QUANTITIES**

(A) Description and rate of Items bases on composite schedule of Rates.

S. No.	Item of work	Qty:	Rate	Unit	Amount
01.	First Class Deodar Wood	41 Sft	902/93	P.Sft	37020/-
02.	Supplying & fixing in position iron / steel grill of ¼" x ¼" size iron of approved design including painting 3 coats etc. complete (weight not to be than 3.7 lbs / sq. foot of finished grill (S.I.No.26 P-97)	48 Sft	180/50	P.Sft	8664/-
03.	Wire Gauze fixed to channel	60 Sft	192/41	P.Sft	9236/-
04.	Providing & laying tiles glazed 6"x6"x ¼" on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar ¾" thick i/c washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles to proper profile (S.I.No. 60 P-53)	117 Sft	30509/77	%Sft Total	35696/- 90616/-

\_\_\_\_\_ % on the rates of CSR.

Amount to be added /deducted on the

**Total (A)** **Rs:**

**Diff: cost of Bitumen (B)** **Rs:**

**G.Total (A+B)** **Rs.**

Total Amount in words (A+B) \_\_\_\_\_

**Contractor**

**Executive Engineer,**  
**Buildings Division**  
**Kashmore @ Kandhkot**